

ACC LEVEL 3  
OR EXPANSION REMODEL

University of Utah

Job Number# 70403

Salt Lake City, Utah 84104

Construction Set

Sept 19, 2022

**FFKR** ARCHITECTS

## TABLE OF CONTENTS

### DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

|                  |                                                                                                            |
|------------------|------------------------------------------------------------------------------------------------------------|
| DOCUMENT 00 7200 | THE UNIVERSITY OF UTAH FACILITIES MANAGEMENT<br>GENERAL CONDITIONS                                         |
| DOCUMENT 00 7300 | THE UNIVERSITY OF UTAH FACILITIES MANAGEMENT<br>SUPPLEMENTAL CONDITIONS FOR UNIVERSITY OF UTAH<br>PROJECTS |
| DOCUMENT 00 7319 | SUPPLEMENTAL GENERAL CONDITIONS FOR HEALTH<br>INSURANCE                                                    |
| DOCUMENT 00 7384 | SUPPLEMENTAL GENERAL CONDITIONS REGARDING ILLEGAL<br>IMMIGRATION                                           |
| DOCUMENT 00 7385 | SUPPLEMENTAL GENERAL CONDITIONS FOR CONSTRUCTION<br>AGREEMENTS                                             |
| DOCUMENT 00 7386 | SUPPLEMENTAL GENERAL CONDITIONS FOR DRUG AND<br>ALCOHOL TESTING DESIGN AND/OR CONSTRUCTION<br>CONTRACTS    |

### DIVISION 01 - GENERAL REQUIREMENTS

|                 |                                            |
|-----------------|--------------------------------------------|
| SECTION 01 1000 | SUMMARY                                    |
| SECTION 01 2500 | SUBSTITUTION PROCEDURES                    |
| SECTION 01 2510 | SUBSTITUTION REQUEST FORM                  |
| SECTION 01 2600 | CONTRACT MODIFICATION PROCEDURES           |
| SECTION 01 2900 | PAYMENT PROCEDURES                         |
| SECTION 01 3100 | PROJECT MANAGEMENT AND COORDINATION        |
| SECTION 01 3200 | CONSTRUCTION PROGRESS DOCUMENTATION        |
| SECTION 01 3300 | SUBMITTAL PROCEDURES                       |
| SECTION 01 4000 | QUALITY REQUIREMENTS                       |
| SECTION 01 5000 | TEMPORARY FACILITIES AND CONTROLS          |
| SECTION 01 6000 | PRODUCT REQUIREMENTS                       |
| SECTION 01 7300 | EXECUTION                                  |
| SECTION 01 7419 | CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL |
| SECTION 01 7700 | CLOSEOUT PROCEDURES                        |
| SECTION 01 7823 | OPERATION AND MAINTENANCE DATA             |
| SECTION 01 7839 | PROJECT RECORD DOCUMENTS                   |
| SECTION 01 7900 | DEMONSTRATION AND TRAINING                 |
| SECTION 01 9113 | GENERAL COMMISSIONING REQUIREMENTS         |

### DIVISION 02 – EXISTING CONDITIONS

|                 |                      |
|-----------------|----------------------|
| SECTION 02 4119 | SELECTIVE DEMOLITION |
|-----------------|----------------------|

### DIVISION 05 – METALS

|                 |                    |
|-----------------|--------------------|
| SECTION 05 5000 | METAL FABRICATIONS |
|-----------------|--------------------|

DIVISION 06 – WOOD, PLASTICS, AND COMPOSITES

|                 |                                               |
|-----------------|-----------------------------------------------|
| SECTION 06 1053 | MISCELLANEOUS ROUGH CARPENTRY                 |
| SECTION 06 4116 | PLASTIC-LAMINATE-FACED ARCHITECTURAL CABINETS |
| SECTION 06 4219 | PLASTIC-LAMINATE-FACED WOOD PANELING          |

DIVISION 07 – THERMAL AND MOISTURE PROTECTION

|                 |                                             |
|-----------------|---------------------------------------------|
| SECTION 07 8100 | APPLIED FIREPROOFING                        |
| SECTION 07 8413 | PENETRATION FIRESTOPPING                    |
| SECTION 07 8443 | JOINT FIRESTOPPING                          |
| SECTION 07 9100 | PREFORMED JOINT SEALS AND MULLION TRIM CAPS |
| SECTION 07 9200 | JOINT SEALANTS                              |

DIVISION 08 – OPENINGS

|                 |                                                            |
|-----------------|------------------------------------------------------------|
| SECTION 08 1113 | HOLLOW METAL FRAMES                                        |
| SECTION 08 1416 | FLUSH WOOD DOORS                                           |
| SECTION 08 3113 | ACCESS DOORS AND FRAMES                                    |
| SECTION 08 3323 | OVERHEAD COILING DOORS                                     |
| SECTION 08 4243 | INTENSIVE CARE UNIT/CRITICAL CARE UNIT (ICU/CCU) ENTRANCES |
| SECTION 08 7100 | DOOR HARDWARE                                              |
| SECTION 08 8000 | INTERIOR GLAZING                                           |
| SECTION 08 8813 | FIRE-RESISTANT GLAZING                                     |

DIVISION 09 – FINISHES

|                 |                                    |
|-----------------|------------------------------------|
| SECTION 09 2116 | GYPSUM BOARD SHAFT WALL ASSEMBLIES |
| SECTION 09 2216 | NON-STRUCTURAL METAL FRAMING       |
| SECTION 09 2900 | GYPSUM BOARD                       |
| SECTION 09 3013 | CERAMIC TILING                     |
| SECTION 09 3023 | GLASS TILING                       |
| SECTION 09 5113 | ACOUSTICAL PANEL CEILINGS          |
| SECTION 09 6513 | RESILIENT BASE AND ACCESSORIES     |
| SECTION 09 6516 | RESILIENT SHEET FLOORING           |
| SECTION 09 6543 | LINOLEUM FLOORING                  |
| SECTION 09 6813 | TILE CARPETING                     |
| SECTION 09 9123 | INTERIOR PAINTING                  |

DIVISION 10 – SPECIALTIES

|                 |                               |
|-----------------|-------------------------------|
| SECTION 10 2123 | CUBICLES                      |
| SECTION 10 2239 | FOLDING PANEL PARTITIONS      |
| SECTION 10 2600 | WALL AND DOOR PROTECTION      |
| SECTION 10 2800 | TOILET AND BATH ACCESSORIES   |
| SECTION 10 4413 | FIRE PROTECTION CABINETS      |
| SECTION 10 4416 | FIRE EXTINGUISHERS            |
| SECTION 10 5123 | PLASTIC-LAMINATE-CLAD LOCKERS |

DIVISION 12 – FURNISHINGS

|                 |                              |
|-----------------|------------------------------|
| SECTION 12 2413 | ROLLER WINDOW SHADES         |
| SECTION 12 3661 | SOLID SURFACING COUNTERTOPS  |
| SECTION 12 3662 | QUARTZ AGGLOMERATE WALL TOPS |

DIVISION 21 – FIRE SUPPRESSION

|                 |                                                  |
|-----------------|--------------------------------------------------|
| SECTION 21 1000 | WATER-BASED FIRE-SUPPRESSION SYSTEMS - HOSPITALS |
|-----------------|--------------------------------------------------|

DIVISION 22 – PLUMBING

|                 |                                                                  |
|-----------------|------------------------------------------------------------------|
| SECTION 22 0500 | COMMON WORK RESULTS FOR PLUMBING                                 |
| SECTION 22 0517 | SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING                     |
| SECTION 22 0518 | ESCUTCHEONS FOR PLUMBING PIPING                                  |
| SECTION 22 0519 | METERS AND GAGES FOR PLUMBING PIPING                             |
| SECTION 22 0523 | GENERAL-DUTY VALVES FOR PLUMBING PIPING                          |
| SECTION 22 0529 | HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT           |
| SECTION 22 0548 | VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT |
| SECTION 22 0553 | IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT                 |
| SECTION 22 0719 | PLUMBING PIPING INSULATION                                       |
| SECTION 22 1116 | DOMESTIC WATER PIPING                                            |
| SECTION 22 1119 | DOMESTIC WATER PIPING SPECIALTIES                                |
| SECTION 22 1316 | SANITARY WASTE AND VENT PIPING                                   |
| SECTION 22 1319 | SANITARY WASTE PIPING SPECIALTIES                                |
| SECTION 22 1423 | STORM DRAINAGE PIPING SPECIALTIES                                |
| SECTION 22 4000 | PLUMBING FIXTURES                                                |
| SECTION 22 4500 | EMERGENCY PLUMBING FIXTURES                                      |
| SECTION 22 6113 | COMPRESSED-AIR PIPING FOR LABORATORY AND HEALTHCARE FACILITIES   |
| SECTION 22 6213 | VACUUM PIPING FOR LABORATORY AND HEALTHCARE FACILITIES           |
| SECTION 22 6313 | GAS PIPING FOR LABORATORY AND HEALTHCARE FACILITIES              |
| SECTION 22 6600 | CHEMICAL WASTE SYSTEM FOR LABORATORY AND HEALTHCARE FACILITIES   |
| SECTION 22 6710 | PURE WATER PIPING                                                |

DIVISION 23 – HEATING VENTILATING AND AIR CONDITIONING

|                 |                                              |
|-----------------|----------------------------------------------|
| SECTION 23 0100 | MECHANICAL REQUIREMENTS                      |
| SECTION 23 0150 | TEMPORARY USE OF EQUIPMENT AND SYSTEMS       |
| SECTION 23 0500 | COMMON WORK RESULTS FOR HVAC                 |
| SECTION 23 0513 | COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT |
| SECTION 23 0517 | SLEEVES AND SLEEVE SEALS FOR HVAC PIPING     |
| SECTION 23 0518 | ESCUTCHEONS FOR HVAC PIPING                  |
| SECTION 23 0523 | GENERAL-DUTY VALVES FOR HVAC PIPING          |



|                 |                                                    |
|-----------------|----------------------------------------------------|
| SECTION 23 0529 | HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT |
| SECTION 23 0548 | VIBRATION AND SEISMIC CONTROLS FOR HVAC            |
| SECTION 23 0550 | OPERATION AND MAINTENANCE OF HVAC SYSTEMS          |
| SECTION 23 0553 | IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT       |
| SECTION 23 0593 | TESTING, ADJUSTING, AND BALANCING FOR HVAC         |
| SECTION 23 0713 | DUCT INSULATION                                    |
| SECTION 23 0719 | HVAC PIPING INSULATION                             |
| SECTION 23 0800 | MECHANICAL SYSTEMS COMMISSIONING                   |
| SECTION 23 0900 | INSTRUMENTATION AND CONTROL FOR HVAC               |
| SECTION 23 2113 | HYDRONIC PIPING                                    |
| SECTION 23 2116 | HYDRONIC PIPING SPECIALTIES                        |
| SECTION 23 3001 | COMMON DUCT REQUIREMENTS                           |
| SECTION 23 3113 | METAL DUCTS                                        |
| SECTION 23 3300 | AIR DUCT ACCESSORIES                               |
| SECTION 23 3423 | HVAC POWER VENTILATORS                             |
| SECTION 23 3600 | AIR TERMINAL UNITS                                 |
| SECTION 23 3713 | DIFFUSERS, REGISTERS, AND GRILLES                  |
| SECTION 23 7313 | CUSTOM FANWELL RETRO FIT                           |
| SECTION 23 7600 | HOSPITAL OPERATING ROOM MODULAR DIFFUSER SYSTEM    |
| SECTION 23 8216 | HYDRONIC AIR COILS                                 |

#### DIVISION 26 – ELECTRICAL

|                 |                                                              |
|-----------------|--------------------------------------------------------------|
| SECTION 26 0519 | LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES           |
| SECTION 26 0529 | HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS                  |
| SECTION 26 0533 | RACEWAY AND BOXES FOR ELECTRICAL SYSTEMS                     |
| SECTION 26 0536 | CABLE TRAY FOR ELECTRICAL SYSTEMS                            |
| SECTION 26 0544 | SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING |
| SECTION 26 0548 | VIBRATION AND SEISMIC CONTROLS FOR ELECTRICAL SYSTEMS        |
| SECTION 26 0553 | IDENTIFICATION FOR ELECTRICAL SYSTEMS                        |
| SECTION 26 0923 | LIGHTING CONTROL DEVICES                                     |
| SECTION 26 2416 | PANELBOARDS                                                  |
| SECTION 26 2726 | WIRING DEVICES                                               |
| SECTION 26 2813 | FUSES                                                        |
| SECTION 26 2816 | ENCLOSED SWITCHES AND CIRCUIT BREAKERS                       |
| SECTION 26 5119 | LED INTERIOR LIGHTING                                        |

#### DIVISION 27 – COMMUNICATIONS

|                 |                                            |
|-----------------|--------------------------------------------|
| SECTION 27 1100 | TELECOMMUNICATION PATHWAYS & SPACES        |
| SECTION 27 1300 | COMMUNICATIONS BACKBONE CABLING            |
| SECTION 27 1500 | COMMUNICATIONS HORIZONTAL CABLING          |
| SECTION 27 4133 | MASTER ANTENNA TELEVISION SYSTEM           |
| SECTION 27 5117 | NETWORKED PUBLIC ADDRESS AND PAGING SYSTEM |
| SECTION 27 5223 | NURSE CALL                                 |

#### DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84104

Code Review

|                 |                                        |
|-----------------|----------------------------------------|
| SECTION 28 1300 | ACCESS CONTROL SECURITY SYSTEM         |
| SECTION 28 2300 | VIDEO SURVEILLANCE                     |
| SECTION 28 3111 | DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEM |

B L A N K P A G E

**The University of Utah  
U FACILITIES**

**GENERAL CONDITIONS**

**September 1, 2020**

**Table of Contents**

**ARTICLE 1. GENERAL PROVISIONS**

- 1.1 Definitions

**ARTICLE 2. UNIVERSITY**

- 2.1 Information and Services Required of University  
2.1.1 University's Representative  
2.1.2 Specialists and Inspectors  
2.1.3 Surveys and Legal Description  
2.1.4 Prompt Information and Services  
2.1.5 Copies of Contract Documents  
2.2 Construction By University or By Separate Contractors  
2.2.1 University's Right To Perform Construction and to Award Separate Contracts  
2.2.2 Coordination of the Work  
2.2.3 Coordination of Schedules  
2.2.4 Reporting Problems to University  
2.2.5 Contractor Remedial Work

**ARTICLE 3. A/E**

- 3.1 A/E's Administration of the Contract  
3.1.1 In General  
3.1.2 Site Visits  
3.1.3 Communications Facilitating Contract Administration  
3.1.4 A/E May Reject Work, Order Inspection, Tests  
3.1.5 A/E Review Contractor's Submittals  
3.2 Ownership and Use of A/E's Drawings, Specifications, and Other Documents

**ARTICLE 4. CONTRACTOR**

- 4.1 Review of Contract Documents and Field Conditions By Contractor  
4.1.1 Reviewing Contract Documents, Information, Reporting Errors, Inconsistencies or Omissions  
4.1.2 Review of Field Conditions

- 4.1.3 Subsurface Investigations  
4.1.4 Perform in Accordance with Contract Documents and Submittals  
4.1.5 Performance to Produce the Complete System and Intended Results  
4.1.6 Intent and Hierarchy  
4.1.7 Dividing Work and Contractor Representation  
4.1.8 Planning and Priority  
4.2 Supervision and Representatives  
4.2.1 Supervision and Control  
4.2.2 Persons Performing Work  
4.2.3 Designated Representatives  
4.2.4 Discipline and Competence  
4.2.5 Responsibility  
4.2.6 Not Relieved of Obligations  
4.2.7 Inspections and Approvals  
4.3 Payment by Contractor  
4.4 Taxes and Other Payments to Government  
4.5 Permits, Fees, Notices, Labor and Materials  
4.5.1 Permits and Fees  
4.5.2 Compliance, Notices  
4.5.3 Correlation of Contract Documents and Laws  
4.5.4 Failure to Give Notice  
4.6 Time and Contractor's Construction Schedules  
4.6.1 Progress and Completion  
4.6.2 Schedule Preparation  
4.6.3 Schedule Submittal  
4.6.4 Schedule Content Requirements  
4.6.5 Interim Completion Dates and Milestones  
4.6.6 Float Time  
4.6.7 Updates  
4.6.8 Schedule of Submittals  
4.6.9 Schedule Recovery  
4.6.10 Schedule Changes and Modifications  
4.6.11 Excusable Delay  
4.6.12 Compensable Delay, Suspension or Interruption.  
4.6.13 Time Extension Requests  
4.6.14 Liquidated Damages  
4.7 Documents and Samples at the Site, Certifying "As-Built"

- 4.8 Shop Drawings, Product Data and Samples
  - 4.8.1 Not Contract Documents
  - 4.8.2 Promptness
  - 4.8.3 Not Perform Until A/E Approves
  - 4.8.4 Representations by Contractor
  - 4.8.5 Contractor's Liability
  - 4.8.6 Direct Specific Attention to Revisions
  - 4.8.7 Informational Submittals
  - 4.8.8 Professional Services
- 4.9 Use of Site
  - 4.9.1 In General
  - 4.9.2 Access to Neighboring Properties
- 4.10 Access to Work
- 4.11 Intellectual Property Licenses
- 4.12 Indemnification
  - 4.12.1 Not Exclusive
  - 4.12.2 Not Limited

## **ARTICLE 5. SUBCONTRACTORS**

- 5.1 Award of Subcontracts and Other Contracts For Portions of the Work
  - 5.1.1 Subcontracting Work Permitted; Conditions
  - 5.1.2 Subsequent Changes
  - 5.1.3 Business and Licensing Requirements
  - 5.1.4 Bonding of Subcontractors
  - 5.1.5 Subcontractor Default Insurance
- 5.2 Subcontractor Relations
  - 5.2.1 Contractor Fully Responsible
  - 5.2.2 Comply with Contract Documents
  - 5.2.3 Rights
  - 5.2.4 Sub-Subcontractors
  - 5.2.5 Document Copies
- 5.3 Contingent Assignment of Subcontracts

## **ARTICLE 6. PROTECTION OF PERSONS AND PROPERTY**

- 6.1 Safety of Persons and Property
  - 6.1.1 Contractor Responsibility
  - 6.1.2 Safety Program, Precautions
  - 6.1.3 Compliance with Laws
  - 6.1.4 Erect and Maintain Safeguards
  - 6.1.5 Utmost Care
  - 6.1.6 Prompt Remedy
  - 6.1.7 Safety Designee
  - 6.1.8 Load Safety
  - 6.1.9 Off-Site Responsibility
  - 6.1.10 Emergencies
- 6.2 Hazardous Materials
- 6.3 Historical and Archeological Considerations
- 6.4 Contractor Liability

## **ARTICLE 7. MODIFICATIONS, PRs & PCOs, PRE AND CLAIMS PROCESS**

- 7.1 Modifications: In General

- 7.1.1 Types of Modifications and Limitations
- 7.1.2 By Whom Issued
- 7.1.3 Contractor to Proceed Unless Otherwise Stated
- 7.1.4 Adjusting Unit Prices
- 7.1.5 Concealed or Unknown Conditions
- 7.1.6 Increase in Contract Time
- 7.1.7 Allowances
- 7.2 Contractor Initiated Requests
  - 7.2.1 The Request for Information, RFI, Process and Time to File
  - 7.2.2 Proposed Change Order ("PCO")
  - 7.2.3 Substitutions
- 7.3 Proposal Request Initiated by University
  - 7.3.1 If Agreement, Change Order Issued
  - 7.3.2 If Disagreement
- 7.4 Change Orders
  - 7.4.1 Adjusting Price Based Upon Agreement
  - 7.4.2 University Resolution of Price in the Absence of an Agreement Under Paragraph 7.4.1
  - 7.4.3 Credits
  - 7.4.4 Effect of a Change Order
- 7.5 Construction Change Directives
  - 7.5.1 When Used and Contractor's Right to Challenge
  - 7.5.2 Proceed with Work
  - 7.5.3 Interim Payments by University
- 7.6 ASI
- 7.7 Procedure for Preliminary Resolution Efforts
  - 7.7.1 Request for Preliminary Resolution Effort (PRE)
  - 7.7.2 Time for Filing
  - 7.7.3 Content Requirement
  - 7.7.4 Supplementation
  - 7.7.5 Subcontractors
  - 7.7.6 Information and Meetings
  - 7.7.7 Contractor Required to Continue Performance
  - 7.7.8 Decision
  - 7.7.9 Decision Final Unless Claim Submitted
  - 7.7.10 Extension Requires Mutual Agreement
  - 7.7.11 If Decision Not Issued
  - 7.7.12 Payment for Performance
- 7.8 Resolution of Claim
  - 7.8.1 Claim
  - 7.8.2 Subcontractors
  - 7.8.3 Time for Filing
  - 7.8.4 Content Requirement
  - 7.8.5 Extension of Time to Submit Documentation
  - 7.8.6 Contractor Required to Continue Performance
  - 7.8.7 Agreement of Claimant on Method and Person(s) Evaluating the Claim
  - 7.8.8 The Evaluation Process, Timeframes of Evaluator(s), Director's Determination, Administrative Appeal to

- the Executive Director and Judicial Review
- 7.8.9 Appeal Process Prerequisite for Further Consideration or Judicial Review
- 7.8.10 Payment of Claim
- 7.8.11 Allocation of Costs of Claim Resolution Process.
- 7.8.12 Alternative Procedures
- 7.8.13 Impact on Future Selections
- 7.8.14 Report to Building Board
- 7.8.15 University's Right to Have Issues, Disputes or Claims Considered

#### **ARTICLE 8. PAYMENTS AND COMPLETION**

- 8.1 Schedule of Values
- 8.2 Applications for Payment
  - 8.2.1 In General
  - 8.2.2 Payment for Material and Equipment
  - 8.2.3 Warranty of Title
  - 8.2.4 Holdback by University
- 8.3 Certificates for Payment
  - 8.3.1 Issued by A/E
  - 8.3.2 A/E's Representations
- 8.4 Decisions to Withhold Certification
  - 8.4.1 When Withheld
  - 8.4.2 Certification Issued When Reasons For Withholding Removed
  - 8.4.3 Continue Work Even if Contractor Disputes A/E's Determination
  - 8.4.4 University Not in Breach
- 8.5 Progress Payments
  - 8.5.1 In General, Interest on Late Payments
  - 8.5.2 Contractor and Subcontractor Responsibility
  - 8.5.3 Information Furnished by A/E or University to Subcontractor
  - 8.5.4 University and A/E Not Liable
  - 8.5.5 Certificate, Payment or Use Not Acceptance of Improper Work
- 8.6 Payment Upon Substantial Completion
- 8.7 Partial Occupancy or Use
  - 8.7.1 In General
  - 8.7.2 Inspection
  - 8.7.3 Not Constitute Acceptance
  - 8.7.4 Insurance
- 8.8 Final Payment
  - 8.8.1 Certificate for Payment
  - 8.8.2 Conditions for Final Payment
  - 8.8.3 Waiver of Claims: Final Payment
  - 8.8.4 Delays Not Contractor's Fault
  - 8.8.5 Waiver by Accepting Final Payment

#### **ARTICLE 9. TESTS AND INSPECTIONS, SUBSTANTIAL AND FINAL COMPLETION, UNCOVERING, CORRECTION OF WORK AND GUARANTY PERIOD**

- 9.1 Tests and Inspections
  - 9.1.1 In General
  - 9.1.2 Failure of an Inspector to Appear
  - 9.1.3 Nonconforming Work
  - 9.1.4 Certificates
  - 9.1.5 A/E Observing
  - 9.1.6 Promptness
- 9.2 Uncovering of Work
  - 9.2.1 Uncover Uninspected Work
  - 9.2.2 Observation Prior to Covering
  - 9.2.3 When an Inspector Fails to Appear or A/E or University Did Not Make Prior Request
- 9.3 Inspections: Substantial and Final
  - 9.3.1 Substantial Completion Inspection
  - 9.3.2 Final Completion Inspection
  - 9.3.3 Punchlist Completion
- 9.4 Correction of Work and Guaranty Period
  - 9.4.1 Contractor Correct the Work
  - 9.4.2 Guaranty and Correction After Substantial Completion
  - 9.4.3 Removal of Work
  - 9.4.4 Not Limit Other Obligations
- 9.5 Additional Warranties
  - 9.5.1 In General
  - 9.5.2 Exclusion
  - 9.5.3 Furnish Evidence on Request
- 9.6 Acceptance of Nonconforming Work

#### **ARTICLE 10. INSURANCE AND BONDS**

- 10.1 Contractor's Liability Insurance
  - 10.1.1 In General
  - 10.1.2 Coverage
  - 10.1.3 Endorsements
  - 10.1.4 Terms
  - 10.1.5 Failure to Provide
  - 10.1.6 Certificates
  - 10.1.7 No Limitation
- 10.2 "Builder's Risk" Insurance
  - 10.2.1 In General
  - 10.2.2 Deductible
  - 10.2.3 Waiver of Subrogation
  - 10.2.4 Special Hazards
  - 10.2.5 Non-Eligible Projects
- 10.3 Performance Bond and Payment Bond

## **ARTICLE 11. MISCELLANEOUS PROVISIONS**

- 11.1 A/E's Responsibilities
- 11.2 Successors and Assigns
- 11.3 Written Notice
  - 11.3.1 Personal Delivery and Registered or Certified Mail
  - 11.3.2 E-mail
- 11.4 Rights and Remedies
  - 11.4.1 Not Limit
  - 11.4.2 No Waiver
- 11.5 No Discrimination, No Sexual Harassment
- 11.6 Applicable Laws and Enforcement
- 11.7 Interpretation
- 11.8 Venue
- 11.9 Severability
- 11.10 Construction of Words
- 11.11 No Third-Party Rights

- 12.3.7 Partial Termination
- 12.3.8 Partial Payments
- 12.3.9 Preserve and Make Available Records
- 12.3.10 Suspension, Delay or Interruption of Work by University for Convenience
- 12.4 University's Right to Stop the Work

## **ARTICLE 12. TERMINATION OR SUSPENSION OF THE CONTRACT**

- 12.1 Termination by Contractor for Cause
  - 12.1.1 In General
  - 12.1.2 Notice
- 12.2 Termination by University for Cause
  - 12.2.1 In General
  - 12.2.2 University's Right to Carry Out the Work Upon Termination for Cause
  - 12.2.3 Items Required to Be Transferred or Delivered
  - 12.2.4 Payment
  - 12.2.5 University Protection if Lienable
  - 12.2.6 Credits and Deficits
  - 12.2.7 If Contractor Found Not in Default or Excusable
  - 12.2.8 Rights and Remedies Not Exclusive
  - 12.2.9 Time Period for Claims
- 12.3 Termination for Convenience of University
  - 12.3.1 In General
  - 12.3.2 Contractor Obligations
  - 12.3.3 Termination Claim
  - 12.3.4 Agreed Upon Payment
  - 12.3.5 Payment Not Agreed Upon
  - 12.3.6 Deductions

**The University of Utah  
U FACILITIES**

---

**GENERAL CONDITIONS**

**September 1, 2020**

THESE GENERAL CONDITIONS (“General Conditions”) are part of and subject to the Contractor’s Agreement (defined below) between University of Utah (defined below) and Contractor (defined below).

**ARTICLE 1. GENERAL PROVISIONS.**

**1.1 DEFINITIONS.**

**ARCHITECT/ENGINEER OR A/E.** “Architect / Engineer” or “A/E” means the person or entity practicing as a design professional, including architect, engineer, interior designer, and/or landscape architect, retained under separate agreement with University to act on behalf of University according to the Contract Documents (defined below) and the A/E’s employees, representatives and consultants. For Work (defined below) where there is no A/E hired by University, references in these General Conditions to A/E shall be deemed to refer to University’s Representative.

**ADDENDA.** “Addenda” means the written or graphic instruments issued prior to the execution of the Contractor’s Agreement (defined below) that clarify, correct, or change the bidding documents or the Contract Documents.

**A/E’s SUPPLEMENTAL INSTRUCTION OR ASI.** “A/E’s Supplemental Instruction” or “ASI” means a supplemental instruction issued by the A/E to Contractor that results in a clarification, correction, or minor change in the Work and does not affect the Contract Time (defined below) or the Contract Price (defined below).

**AMENDMENT.** “Amendment” means any document or communication that changes (or purports to change) the terms of Contractor’s Agreement and/or the General Conditions, except as to: (1) scope of the Work; (2) Contract Price; and/or (3) Contract Time. With the exception of Supplemental General Conditions (defined below), no Amendment shall be valid and/or binding on University unless: (1) the Amendment is set forth in a separate document, clearly titled “Amendment”; and (2) the Amendment is specifically and expressly accepted in writing by the Executive Director (defined below).

**BID.** “Bid” means the offer or proposal of the bidder submitted on the prescribed form setting forth the prices for the Work to be performed.

**BONDS.** “Bonds” means collectively the bid bond, performance bond, payment bond, and any other instruments of security.



**CHANGE ORDER.** “Change Order” means a written instrument signed by both University and Contractor, issued after the execution of the Contractor’s Agreement on University’s form, authorizing: (1) a change in the Work; (2) an adjustment of the Contract Price; and/or (3) an adjustment of the Contract Time.

**CLAIM.** “Claim” means a dispute, demand, assertion or other matter submitted by Contractor, including a subcontractor at any tier, subject to the provisions of these General Conditions. The claimant may seek, as a matter of right, modification, adjustment or interpretation of Contract terms, payment of money, extension of time or other relief with respect to the terms of the Contract. A request for Preliminary Resolution Effort (“PRE”) (defined below) shall not be considered a “Claim”. A request for an amendment of the Contract Documents, requested Change Order or a Construction Change Directive (“CCD”) (defined below) is not a PRE or Claim unless agreement cannot be reached, and the procedures of these General Conditions are followed.

**CONSTRUCTION CHANGE DIRECTIVE.** “Construction Change Directive” means a written order signed by University, issued after execution of the Contractor’s Agreement, directing Contractor to perform a change in the Work and stating a proposed basis for adjustment, if any, in the Contract Price and/or Contract Time.

**CONTRACT DOCUMENTS.** “Contract Documents” means collectively Contractor’s Agreement, these General Conditions of Contractor’s Agreement, applicable Supplemental General Conditions, Drawings (defined below), Specifications (defined below), Addenda, other documents listed in the Contractor’s Agreement, authorized Amendments and Supplementary Conditions and Modifications (defined below) issued after execution of the Contractor’s Agreement. The Contract Documents shall also include the bidding/proposal documents, including the Instructions to Bidders/Proposers, Notice to Contractors and the Bid/Proposal Form, to the extent not in conflict with the other above-stated Contract Documents and other documents and oral representations which are memorialized in writing and documented as an attachment to the Contractor’s Agreement.

**CONTRACT PRICE.** “Contract Price” means the total amount payable by University to Contractor for performance of the Work, including any authorized changes in the Work.

**CONTRACT TIME.** “Contract Time” means the time within which Contractor shall complete the Work, including any authorized changes in the Work

**CONTRACTOR.** “Contractor” means the person or entity identified as such in the Contractor’s Agreement. As used in the Contract Documents, “Contractor” includes Contractor’s employees, agents, representatives, subcontractors at any tier, and any other third party hired by Contractor to perform a portion of the Work and is referred to throughout the Contract Documents as if singular in number.

**CONTRACTOR’S AGREEMENT.** “Contractor’s Agreement” means, unless the context requires otherwise, the agreement executed by the Contractor and University for the Work.

**DAY.** “Day” or “days” means calendar day unless otherwise specifically defined.

**DEFECTIVE.** “Defective” is an adjective which when modifying the word “Work” refers to Work that does not conform to the Contract Documents, or does not meet the requirements of any inspection, referenced standard, code, test or approval referred to in the Contract Documents, or which fails to meet generally accepted craft standards, or which has been damaged.

**DIRECTOR.** “Director” means the Director of Design and Construction Support of the U Facilities department of the University of Utah, unless the context requires otherwise. Director may include a designee selected by the Director for a particular function described in the Contract Documents.

**DRAWINGS.** “Drawings” means the graphic and pictorial portions of the Contract Documents, wherever located and whenever issued, showing the design, location, and dimensions of the Work and generally includes drawings, elevations, sections, details, schedules, and diagrams, including electronic copies.

**EXECUTIVE DIRECTOR.** “Executive Director” means the Chief Facilities Officer of the University of Utah including unless otherwise stated, the Executive Director’s duly authorized designee.

**FINAL COMPLETION.** “Final Completion” means the date when all Work to be performed by Contractor has been completed and accepted in writing by University.

**INSPECTION.** “Inspection” or its derivatives means a review of the Work, including but not limited to a visual review of the Work completed to date to ascertain if the Work is in accordance with the Contract Documents, including all applicable building codes and construction standards.

**MODIFICATION.** “Modification” means: (1) a Change Order; (2) a Construction Change Directive; or (3) an ASI. Contractor’s Agreement may be amended or modified only by: (1) an authorized Amendment; or (2) a Modification.

**NOTICE TO PROCEED.** “Notice to Proceed” means a document prepared by University that authorizes Contractor to commence Work. It shall be deemed issued upon being sent by University to Contractor’s address specified in Contractor’s Bid.

**PRELIMINARY RESOLUTION EFFORT OR PRE.** “Preliminary Resolution Effort” or “PRE” means the processing of a request for preliminary resolution or any similar notice about an issue that could potentially lead to a Claim and is prior to reaching the status of a Claim.

**PRODUCT DATA.** “Product Data” means illustrations, standard schedules, performance charts, instructions, brochures, diagrams, and other information furnished by Contractor to illustrate materials or equipment for some portion of the Work.

**PROPOSAL REQUEST OR PR.** “Proposal Request” or “PR” means a request made by University to Contractor requesting a proposal to resolve an issue as part of the Change Order process.

**PROPOSED CHANGE ORDER OR PCO.** “Proposed Change Order” or “PCO” means a request by Contractor submitted to the University Representative to commence the Change Order process. It shall not be considered a “PRE” or a “Claim”. The PCO may be related to any potential or actual delay, disruption, unforeseen condition or any other matter for which Contractor intends to seek an increase in the Contract Price and/or extension of the Contract Time.

**REQUEST FOR INFORMATION OR RFI.** “Request for Information” or “RFI” means a written request from Contractor to the A/E seeking information, direction, or clarification related to the Contract Documents, including Drawings and/or Specifications.

**RULE.** “Rule”, unless the context requires otherwise, means a rule of the Utah Administrative Code.

**SALES TAX AND/OR USE TAX.** “Sales Tax” and/or “Use Tax”, unless the context requires otherwise, means the sales tax and/or use tax collected or to be collected by the Utah State Tax Commission and shall include any sales and/or use tax that the Utah State Tax Commission collects on behalf of any special district, local government, or political subdivision.

**SAMPLES.** “Samples” mean physical examples that illustrate materials, equipment or workmanship and establish standards by which the Work shall be judged.

**SHOP DRAWINGS.** “Shop Drawings” means drawings, diagrams, schedules and other data specially prepared for the Work by Contractor, or a subcontractor at any tier, manufacturer, supplier or distributor to illustrate some portion of the Work.

**SPECIFICATIONS.** “Specifications” means that portion of the Contract Documents consisting of the written requirements for materials, equipment, construction systems, standards, installation and workmanship for the Work and performance of related systems and services.

**SUBCONTRACTOR.** “Subcontractor” means any person or entity under contract with Contractor to provide services or labor for the Work. “Subcontractor” includes a trade contractor or specialty contractor. “Subcontractor” does not include suppliers who provide only materials, equipment or supplies to Contractor or a Subcontractor. The term “Subcontractor” is referred to throughout the Contract Documents as if singular in number and means a Subcontractor or authorized representative of the Subcontractor. The term “Sub-subcontractor” means a person or entity that has a contract with a Subcontractor to provide services or labor for the Work and also includes all lower tier sub-subcontractors. The terms “Subcontractor” and “Sub-subcontractor” do not include a separate contractor retained by University or subcontractors or sub-subcontractors of a separate contractor retained by University.

**SUBSTANTIAL COMPLETION.** “Substantial Completion” and its derivatives means the date certified in accordance with Section 9.2 when the Work, or a designated portion thereof, is sufficiently complete, and any lack of completion or performance does not materially interfere with University’s intended use of the Work, in accordance with the Contract Documents, so that University can occupy and use the Work for its intended use. University’s “intended use” or “occupy” as used in this definition, shall include any intended use or occupation by any agency or entity that University intends to use or occupy the Work.

**SUPPLEMENTAL GENERAL CONDITIONS.** “Supplemental General Conditions” means the Supplemental General Conditions identified on DFCM’s website, [dfcm.utah.gov](http://dfcm.utah.gov), applicable to the Work, if any, that supplements these General Conditions. Supplemental General Conditions are authorized Amendments.

**SUPPLEMENTARY CONDITIONS.** “Supplementary Conditions” means the part of the Contract Documents, if any, that amends or supplements these General Conditions and/or applicable Supplemental General Conditions. Supplementary Conditions, if authorized, are an Amendment.

**UNIVERISTY.** “University” means the University of Utah, Unless the context requires otherwise, University is the “Owner” as that term is commonly understood in the construction industry.

**WORK.** “Work” means the construction, services, supervision, labor, tools, equipment, materials, products and transportation, to be furnished by Contractor, so as to fulfill the Contractor’s obligations as required by the Contract Documents.

## **ARTICLE 2. University.**

### **2.1 INFORMATION AND SERVICES REQUIRED OF UNIVERSITY.**

**2.1.1 UNIVERSITY’S REPRESENTATIVE.** University shall designate a representative authorized to act on behalf of University with respect to the Work (“University’s Representative”). Unless the context requires otherwise, “University’s Representative” is the “Owner’s representative” as that term is commonly understood in the construction industry. University’s Representative shall have authority to review and approve the Work, including the time schedule for completion, and the authority (but not a duty) to stop the Work for any reason, including, without limitation, unsafe conditions, or to direct Contractor to remedy, repair, or replace

any Work, if necessary, to ensure its proper execution. University and University's Representative shall endeavor to render decisions pertaining to documents submitted by the A/E and/or Contractor to avoid a delay in the orderly and sequential progress of the Work. Contractor shall be responsible for time lost and the cost of correcting Work that in University's judgment was executed improperly. University shall be the final interpreter of the Contract Documents; the decision of University in the absence of arbitrary or capricious conduct shall be conclusive. Notwithstanding anything to the contrary in the Contract Documents, University's approval shall not relieve Contractor of Contractor's sole responsibility for the Work.

**2.1.2 SPECIALISTS AND INSPECTORS.** University shall provide building inspection services in accordance with the applicable building codes, including routine and special inspections unless otherwise noted in the Contract Documents. University may assign an inspector or specialist to note deviations from, or necessary adjustments to, the Contract Documents or to report deficiencies or defects in the Work. The inspector's or specialist's activities in no way relieve Contractor from the responsibilities set forth in the Contract Documents.

**2.1.3 SURVEYS AND LEGAL DESCRIPTION.** Except to the extent not applicable to the type of Work to be performed pursuant to Contractor's Agreement, University shall furnish surveys describing physical characteristics, legal limitations and utility locations for the Work site, and a legal description of the Work site. The Contractor shall be entitled to rely on the accuracy of such survey information furnished by University but shall exercise proper precautions relating to the safe performance of the Work. The Contractor recognizes that the exact location of underground or hidden utilities, plumbing and electrical runs may be somewhat different from the location indicated on such surveys furnished by University or in the Contract Documents. The Contractor shall exercise reasonable skill and care to locate underground or hidden utilities, plumbing and electrical runs that are to remain to prevent damage thereto. The Contractor shall review the survey information provided by University and shall promptly provide written notice to University of any survey information that Contractor knows or discovers to be inaccurate.

**2.1.4 PROMPT INFORMATION AND SERVICES.** Upon receipt of a written request from Contractor, University shall endeavor to furnish information or services under University's control with reasonable promptness to avoid delay in the orderly progress of the Work.

**2.1.5 COPIES OF CONTRACT DOCUMENTS.** Unless otherwise provided in the Contract Documents, University shall provide or make available to Contractor, free of charge, paper or electronic copies of Contract Documents, as determined by University, as are reasonably necessary for execution of the Work. University's website may also provide Contract Documents for the Work.

## **2.2 CONSTRUCTION BY UNIVERSITY OR BY SEPARATE CONTRACTORS.**

**2.2.1 UNIVERSITY'S RIGHT TO PERFORM CONSTRUCTION AND TO AWARD SEPARATE CONTRACTS.** University reserves the right to enter into contracts with third parties in connection with the Work and to perform construction or other activities itself on or about the Work site.

**2.2.2 COORDINATION OF WORK.** Contractor shall afford University and the separate contractors or subcontractors retained by University adequate opportunity for the introduction and storage of their materials and equipment and the execution of their work. Contractor shall properly connect and coordinate the Work with the work of University and separate contractors or subcontractors.

**2.2.3 COORDINATION OF SCHEDULES.** Contractor shall cooperate with University and any separate contractors and subcontractors hired by University in performing the Work so that all portions of the Work may be completed in the shortest possible time within normal working hours. Contractor shall furnish separate contractors and subcontractors full information regarding time schedules for Contractor's Work.

Contractor shall coordinate the Work with the workers who may be retained by University, all separate contractors and subcontractors, and their activities in the vicinity of the Work site.

**2.2.4 REPORTING PROBLEMS TO UNIVERSITY.** If part of Contractor's Work depends on work by University or a separate contractor, Contractor shall, prior to proceeding with that portion of the Work, promptly report in writing to University any apparent defects in workmanship of the work of University and/or such separate contractor that would render it unsuitable for proper execution of the Work. Failure of Contractor to report defects shall constitute an acknowledgment that University's or the separate contractor's completed or partially completed work is fit and proper to receive Contractor's Work, except as to defects in workmanship not then reasonably discoverable.

**2.2.5 CONTRACTOR REMEDIAL WORK.** If Contractor causes damage to the work of University or any separate contractors or subcontractors, Contractor shall promptly remedy such damage and shall use all reasonable efforts to promptly negotiate a settlement with University and such separate contractors and subcontractors.

### **ARTICLE 3. A/E.**

#### **3.1 A/E'S ADMINISTRATION OF THE CONTRACT.**

**3.1.1 IN GENERAL.** The A/E shall assist University in administering the Contract in accordance with the Contract Documents. The A/E shall have authority to act on behalf of University, but only to the extent provided in the Contract Documents and/or A/E's agreement with University.

#### **3.1.2 SITE VISITS.**

**3.1.2.1** Site visits or inspections by the A/E or University shall in no way limit or affect Contractor's responsibility to comply with all the requirements and the overall design concept of the Contract Documents as well as all federal, state, and local laws, rules, regulations, ordinances and orders of public authorities applicable to the Work.

**3.1.2.2** The A/E shall promptly submit to University a written report subsequent to each site visit detailing the visit.

**3.1.3 COMMUNICATIONS FACILITATING CONTRACT ADMINISTRATION.** Except as authorized by University or as otherwise provided in the Contract Documents, including these General Conditions, the A/E and Contractor shall communicate through University on issues regarding the timing of the Work, cost of the Work, and scope of the Work. Communications by and with the A/E's consultants shall be through the A/E. Communications by and with Subcontractors shall ordinarily be through Contractor. Communications by and with separate contractors shall be through University.

**3.1.4 A/E MAY REJECT WORK, ORDER INSPECTIONS, TESTS.** The A/E shall have the authority to reject Work which, based upon the A/E's knowledge or what may be reasonably inferred from the A/E's site observations and review of data, does not conform to the Contract Documents. Whenever the A/E considers it necessary or advisable for implementation of the intent of the Contract Documents, the A/E shall have the authority to require additional inspections or testing of the Work in accordance with the provisions of the Contract Documents, whether or not such Work is fabricated, installed, or completed; however, the A/E must obtain University's prior written approval of any such additional inspections or testing. Neither this authority of the A/E nor a decision made in good faith either to exercise or not to exercise such authority shall give rise to a duty or responsibility of the A/E to Contractor, Subcontractors, their agents or employees or other persons performing portions of the Work, including separate contractors. If Contractor disputes the rejection of

any Work and the correction thereof shall involve additional cost or time, it shall be University's option to accept such Work whether it shall be conforming or nonconforming.

### **3.1.5 A/E REVIEW OF CONTRACTOR'S SUBMITTALS.**

**3.1.5.1** Contractor shall submit Shop Drawings, Product Data, and Samples and other submittals required by the Contract Documents to the A/E as required by the approved submittal schedule.

**3.1.5.2** The A/E shall review and take appropriate action upon Contractor's submittals such as Shop Drawings, Product Data, and Samples, but only for the purpose of checking for conformance with the information and design concepts expressed in the Contract Documents. A/E action taken on a submittal shall not constitute a Modification.

**3.1.5.3** The A/E's action shall be taken no later than fourteen (14) days following A/E's receipt of the submittal, unless agreed to otherwise by Contractor and University, in order to avoid a delay in the Work of Contractor or of separate contractors while allowing sufficient time in the A/E's professional judgment to permit adequate review.

**3.1.5.4** Review of such submittals shall not be conducted for the purpose of determining the accuracy and completeness of other details such as dimensions and quantities or for substantiating instructions for installation or performance of equipment or systems, all of which remain the responsibility of Contractor as required by the Contract Documents.

**3.1.5.5** The A/E's review of Contractor's submittals shall not relieve Contractor of Contractor's obligations under the Contract Documents.

**3.1.5.6** The A/E's review shall not constitute approval of safety precautions or, unless otherwise specifically stated by the A/E, of any construction means, methods, techniques, sequences, or procedures.

**3.1.5.7** The A/E's approval of a specific item shall not indicate approval of an assembly of which the item is a component.

**3.1.5.8** When professional certification of performance characteristics of materials, systems, or equipment is the responsibility of the Contractor under the Contract Documents, the A/E shall be entitled to rely upon such certifications to establish that the materials, systems or equipment shall meet the performance criteria required by the Contract Documents.

**3.2 OWNERSHIP AND USE OF A/E'S DRAWINGS, SPECIFICATIONS AND OTHER DOCUMENTS.** All Drawings, Specifications, and other documents prepared by the A/E for the Work are and shall remain the property of University, and University shall retain all common law, statutory, and other reserved rights with respect thereto. Said documents are intended for use as an integrated set for the Work. Neither Contractor nor A/E shall modify or use Contract Documents on any other project without the prior written consent of University. Any such non-permissive use or modification by Contractor, Contractor's Subcontractors at any tier, or anyone else for whose acts Contractor is liable, shall be at Contractor's sole risk. To the fullest extent permitted by law, Contractor shall release, indemnify, hold harmless, and defend University, and require all Subcontractors to release, indemnify, hold harmless, and defend University, from and against any and all liabilities, claims, demands, actions, damages, losses, and expenses, including but not limited to attorney fees and costs of litigation, arising out of such non-permissive use or modification by Contractor or its Subcontractors. Contractor, including its Subcontractors, are granted a limited license to use and reproduce applicable portions of the Drawings, Specifications, and other documents prepared by the A/E appropriate to and for use in the execution of the Work. Contractor shall preserve the copyright notice, if any, shown on the Drawings, Specifications and other documents prepared by the A/E for the Work, on all copies.

Submittals or distributions necessary to meet official regulatory requirements or for other purposes relating to the Work shall not be construed as a publication in derogation of University's copyright or other reserved rights.

#### **ARTICLE 4. CONTRACTOR.**

##### **4.1 REVIEW OF CONTRACT DOCUMENTS AND FIELD CONDITIONS BY CONTRACTOR.**

**4.1.1 REVIEW OF DOCUMENTS.** Contractor shall carefully study and compare the Contract Documents with each other and with information furnished by University and shall at once report to University and A/E all errors, omissions, inconsistencies and/or ambiguities discovered. Contractor shall not be liable to University or A/E for damage resulting from errors, omissions, inconsistencies and/or ambiguities in the Contract Documents unless Contractor recognized such error, omission, inconsistency and/or ambiguity or a contractor of ordinary skill and expertise for the type of Work involved would have readily so recognized such error, omission, inconsistency and/or ambiguity, and Contractor failed to report such to University and A/E. If Contractor performs any Work without such notice to University and A/E and prior to resolution of the error, omission, inconsistency and/or ambiguity, Contractor shall be responsible for such performance and shall bear the costs for correction.

**4.1.2 REVIEW OF FIELD CONDITIONS.** Contractor shall take field measurements, verify field conditions and carefully compare such field measurements and conditions and other information known to Contractor, or information that a contractor of ordinary skill and expertise for the type of Work involved would have known, before commencing Work. Contractor shall immediately report to University and A/E all errors, omissions, inconsistencies and/or ambiguities discovered. If Contractor performs any Work without such notice to University and A/E and prior to resolution of the error, omission, inconsistency and/or ambiguity, Contractor shall be responsible for such performance and shall bear the costs for correction.

**4.1.3 SUBSURFACE INVESTIGATIONS.** If University has provided the Contractor with reports of subsurface investigations and/or tests of soils at the Work site ("Geotechnical Report") as part of the Contract Documents, the Contractor may rely upon the accuracy of the technical data contained in such Geotechnical Report at the locations where the data was obtained and to the depth indicated. However, Contractor acknowledges that the conditions indicated in any Geotechnical Report of any subsurface investigations and/or tests of soils at the Work site may not be representative of conditions existing at locations and/or at depths other than where data was obtained or that conditions different than those indicated by such Geotechnical Report may exist at the Work site. Contractor shall not be entitled to any increase in the Contract Price and/or increase in the Contract Time based on any data, opinion and/or recommendation in any Geotechnical Report and/or any inaccuracy, incompleteness, mistake and/or error in any Geotechnical Report except to the extent that Contractor is entitled to an increase in the Contract Price and/or extension of the Contract Time for a concealed or unknown condition as provided in Section 7.1.5.

**4.1.4 PERFORM IN ACCORDANCE WITH CONTRACT DOCUMENTS AND SUBMITTALS.** Contractor shall perform the Work in accordance with the Contract Documents and submittals to which no exception has been taken in accordance with the Contract Documents.

**4.1.5 PERFORMANCE TO PRODUCE THE COMPLETE SYSTEM AND INTENDED RESULTS.** The Contract Documents shall be read as a whole and wherever possible, the provisions shall be construed in order that all provisions are operable. The intent of the Contract Documents is to include all items necessary for the proper execution and completion of the Work by Contractor, whether or not specifically set forth in the Contract Documents, for the Contract Price and within the Contract Time. Performance by Contractor shall be required to the extent consistent with and reasonably inferable from the Contract Documents as being necessary to allow the Work to function for its intended use.

**4.1.6 INTENT AND HIERARCHY.** The Contract Documents are complimentary, and what is required by one Contract Document or provisions thereof, shall be as binding as if required by all the Contract

Documents or provisions thereof. In case of an irreconcilable conflict between provisions within a Contract Document or between Contract Documents, the following priorities shall govern as listed below:

**4.1.6.1** A Modification or authorized Amendment (including authorized Supplementary Conditions) shall govern over all Contract Documents listed in Sections 4.1.6.2 – 4.1.6.6 or previous Modifications or authorized Amendments (including authorized Supplementary Conditions).

**4.1.6.2** The Contractor's Agreement shall govern over all Contract Documents listed in Sections 4.1.6.3 - 4.1.6.6.

**4.1.6.3** Supplemental General Conditions shall govern over all Contract Documents listed in Sections 4.1.6.4 – 4.6.1.6.

**4.1.6.4** These General Conditions shall govern over the Contract Documents listed in Sections 4.1.6.5 – 4.1.6.6.

**4.1.6.5** The Drawings and Specifications shall govern over the Contract Documents listed in Section 4.1.6.6.

**4.1.6.6** Attachments to the Contractor's Agreement, Contractor's management plan, bidding/proposal documents, including the Instructions to Bidders/Proposers, Notice to Contractors and the Bid/Proposal Form and/or documented interview information, if any, are Contract Documents, binding on Contractor, but are subordinate to the Contract Documents listed in Sections 4.1.6.1 – 4.1.6.5.

**4.1.6.7** An Addendum shall govern over all other Contract Documents and any previously issued Addendum.

**4.1.6.8** In case of a conflict or ambiguity within the same level of hierarchy of described documents, University reserves the right to revise the documents to select the most stringent requirement unless the preponderance of the Contract Documents indicate a less stringent requirement.

**4.1.7 DIVIDING WORK AND CONTRACTOR REPRESENTATION.** Organization of the Specifications into divisions, sections and articles, and arrangement of Drawings, shall not control Contractor in dividing the Work among Subcontractors or in establishing the extent of Work to be performed by any trade. Contractor shall ensure that the Subcontractors at any tier, manufacturers and suppliers engaged or to be engaged by Contractor, are and shall be familiar with the requirements for performance by them of their obligations.

**4.1.8 PLANNING AND PRIORITY.** Contractor shall plan and schedule the Work and shall maintain the schedule to Substantially Complete the Work within the Contract Time.

## **4.2 SUPERVISION AND REPRESENTATIVES.**

**4.2.1 SUPERVISION AND CONTROL.** Contractor shall supervise and direct the Work using Contractor's best skill and attention to complete the Work within the Contract Time. Contractor shall be solely responsible for and have control over the construction means, methods, techniques, sequences, and procedures and for coordinating all portions of the Work, except to the extent that the Contract Documents specifically and expressly state otherwise.

**4.2.2 PERSONS PERFORMING WORK.** Contractor shall perform the Work using qualified employees, consultants, and Subcontractors selected and paid for by Contractor, adequately trained in the requirements of their particular jobs, and skilled in the Work assigned to them. Contractor shall use all



reasonable efforts to maintain a stable project team and minimize changes in key members of the team where loss of key members could have an adverse impact on the Contract Time. Any change in key personnel assigned to the Work must be approved by University in writing.

**4.2.3 DESIGNATED REPRESENTATIVES.** Contractor shall employ a competent superintendent and necessary assistants, fluent in spoken and written English, who shall be at the Work site during performance of the Work. Contractor's superintendent shall maintain communication between University, the A/E, and Contractor and be responsible for the management of Contractor's activities and deliverables described in the Contract Documents, as well as management of any third-party resources hired by Contractor to provide services or products under the Contract Documents. Contractor's superintendent shall represent Contractor, and communications given to the superintendent shall be as binding as if given to Contractor. Important communications shall be confirmed in writing. Other communications shall be similarly confirmed in writing on written request in each case.

**4.2.4 DISCIPLINE AND COMPETENCE.** Contractor shall enforce safety procedures, strict discipline, and good order among Contractor's employees, Contractor's Subcontractors, agents, representatives and other persons performing the Work under the Contract Documents. If University reasonably determines that a particular person does not follow safety procedures, is unfit or unskilled for the assigned Work, disregards instructions, ignores the environmental restraints of the Work, or jeopardizes the goodwill between University and the public, Contractor shall immediately replace the person upon receipt of University's request to do so and shall not employ the person again on the Work.

**4.2.5 RESPONSIBILITY.** Contractor shall be responsible to the State of Utah and University for the acts and omissions of Contractor's employees, Subcontractors and their agents and employees and other persons performing portions of the Work under a contract with Contractor or on behalf of Contractor.

**4.2.6 NOT RELIEVED OF OBLIGATIONS.** Contractor shall not be relieved of obligations to perform the Work in accordance with the Contract Documents either by activities or duties of University or University's agents in University's administration of the Contractor's Agreement, or by tests, inspections, or approvals required or performed by persons other than Contractor or for those that Contractor is liable.

**4.2.7 INSPECTIONS AND APPROVALS.**

**4.2.7.1** All Work performed by Contractor shall be subject to the inspection and approval of University to determine whether the Work is in accordance with the Contract Documents. Contractor shall permit and facilitate inspection of the Work at all times by University, University's representatives and governmental authorities having jurisdiction.

**4.2.7.2** Contractor shall be responsible for requesting inspections for various stages and portions of the Work required under the Contract Documents in a timely manner in accordance with the process and document requirements of the applicable inspection authority. In the event Work is not in a condition to be inspected at the time scheduled for the inspection of such Work for causes for which the Contractor is responsible, Contractor shall bear all associated costs and expenses without reimbursement by University.

**4.2.7.3** If any of the Work is required to be inspected or approved by the terms of the Contract Documents, Contractor shall timely request such inspection or approval to be performed in accordance with Article 9. Except as provided in Article 9, Work shall not proceed without any required inspection and the associated authorization to proceed. Contractor shall promptly notify University if the inspector fails to appear at the site.

**4.2.7.4** Contractor shall work with the inspector to maintain an Open Issues Log and Contractor shall proceed diligently to resolve all open issues.

**4.3 PAYMENT BY CONTRACTOR.** Except to the extent it is otherwise stated in the Contract Documents, Contractor shall provide and pay for all supervision, labor, tools, equipment, materials and transportation, including, without limitation: construction equipment and machinery; water; heat; utilities; and other facilities, supplies, consumables and services necessary for the proper execution and completion of the Work, whether temporary or permanent and whether or not incorporated or to be incorporated in the Work.

**4.4 TAXES AND OTHER PAYMENTS TO GOVERNMENT.** Contractor shall pay Sales Tax and/or Use Tax, consumer, employment-related and similar taxes related to the Work or portions thereof provided by Contractor which are legally enacted when bids are received or negotiations concluded, whether or not yet effective or merely scheduled to go into effect. Contractor shall comply with the laws and regulations regarding the payment of Sales Tax and/or Use Tax and any exemptions. The procurement documents may have a provision regarding specific items which are exempt from State of Utah Sales Tax and/or Use Tax. Any such exemption shall be used only for the items and the project specified in the procurement documents. Any such exemption does not apply to taxes levied by the federal government or any taxing entity outside of the State of Utah. If Contractor properly relies upon a provision(s) of the bidding or proposal documents indicating exemption from State of Utah Sales Tax and/or Use Tax, and if State of Utah Sales Tax and/or Use Tax subsequently becomes due, then Contractor shall be paid such tax amount not included in the bid/proposal amount due to the reliance upon such provision.

**4.5 PERMITS, FEES, NOTICES, LABOR AND MATERIALS.**

**4.5.1 PERMITS AND FEES.** Unless otherwise required in the Contract Documents, it shall not be necessary for Contractor to obtain or pay for local building permits, plan check fees, electrical permits, plumbing permits, connection fees, or impact fees, nor shall it be necessary to pay fees for inspections pertaining thereto.

**4.5.2 COMPLIANCE, NOTICES.** Contractor shall comply with and give notices required by all federal, state, and local laws, rules, regulations, ordinances, and orders of public authorities applicable to the Work.

**4.5.3 CORRELATION OF CONTRACT DOCUMENTS AND LAW.** It is not Contractor's responsibility to ascertain that the Contract Documents are in accordance with applicable federal, state and/or local laws, rules, regulations, ordinances, and/or orders of public authorities having jurisdiction. However, if Contractor observes, or if such would be readily observable to a contractor of ordinary skill and expertise for the type of Work involved, that a portion of the Contract Documents is at variance therewith, Contractor shall promptly notify the A/E and University in writing, and necessary changes shall be accomplished by appropriate Modification and/or Amendment.

**4.5.4 FAILURE TO GIVE NOTICE.** If Contractor, or any Subcontractor, performs Work without complying with the requirements of this Section 4.5, Contractor shall assume responsibility for such Work and shall bear the appropriate amount of the applicable costs of correction.

## **4.6 TIME AND CONTRACTOR'S CONSTRUCTION SCHEDULES.**

### **4.6.1 PROGRESS AND COMPLETION.**

**4.6.1.1** Time is of the essence in this Contract. By executing the Contractor's Agreement, Contractor confirms that the Contract Time is adequate to perform the Work. The Contractor shall proceed expeditiously with adequate forces to achieve Substantial Completion within the Contract Time.

**4.6.1.2** Contractor shall commence and complete the Work within the Contract Time and pursuant to the schedule, an initial version of which shall be prepared and provided by Contractor to University and the A/E for approval, as it may be modified with University's consent. Unless and except to the extent that preliminary Work at the Work site is authorized in writing by University, Contractor shall not prematurely commence the Work at the Work site or elsewhere until University issues a Notice to Proceed or prior to the effective date of insurance required by Article 10 to be furnished by Contractor, whichever is later. Contractor shall proceed expeditiously with adequate forces to achieve Substantial Completion within the Contract Time. All other Work shall be completed no later than the date established for Final Completion. Contractor shall notify University when Contractor considers the entire Work to be completed. University shall be entitled to a final inspection to determine whether the Work has been completed in accordance with the Contract Documents. The date of Substantial Completion shall be established by a certificate of Substantial Completion issued by the A/E or a written acknowledgement of Substantial Completion signed by University.

**4.6.1.3 INITIAL CONTRACT TIME.** Unless otherwise specified in the bidding documents, the initial Contract Time shall be the time identified in the Contractor's Agreement.

### **4.6.2 SCHEDULE PREPARATION.**

**4.6.2.1** Promptly after being awarded the Work, Contractor shall prepare and submit for University's and the A/E's approval, a planned progress schedule for the Work. Contractor shall plan and schedule the Work to facilitate the Work and shall maintain a schedule to place proper priority to sequence the Work to complete the Work within the Contract Time. Contractor shall commence and complete the Work by the dates set forth in the agreed upon schedule and Contractor's Agreement.

**4.6.2.2** The schedule shall include a time-line for procurement, fabrication, construction, and testing activities, including interdependence of items necessary to complete the Work, duration of activities, interim completion dates, milestones, closeout and commissioning, submittals, and critical path.

**4.6.2.3** Contractor shall advise and consult with University during progress of the Work and keep University fully informed as to the status of the Work at intervals as required by University. Contractor shall provide University with a daily listing of personnel and equipment used on the Work. If the Work is not on schedule, Contractor shall immediately advise University in writing of Contractor's proposed action to bring it on schedule.

**4.6.2.4** University may take reasonable exception to activity duration, activity placement, construction logic, and time frame for any element of the Work to be scheduled and may recommend revisions.

### **4.6.3 SCHEDULE SUBMITTAL.**

**4.6.3.** Contractor shall develop the CPM schedule using Primavera, MS Project or Phoenix unless otherwise authorized by University. The critical path shall be identified, including the critical paths for interim completion dates and milestones.

**4.6.3.2** Contractor shall update the schedule at least once a month and submit the updated schedule with each Application for Payment.

**4.6.3.3** No progress payments shall be approved until Contractor has submitted a detailed CPM schedule covering the first ninety (90) days of the Work with a general CPM schedule for the entire Work. The detailed schedule for the entire Work shall be completed prior to the second Application for Payment, unless otherwise authorized in writing by University.

#### **4.6.4 SCHEDULE CONTENT REQUIREMENTS.**

**4.6.4.1** The schedule shall indicate the duration of activities and order, sequence and interdependence of all items known to be necessary to complete the Work, including construction, procurement, fabrication and delivery of materials and equipment, commissioning, submittals and approvals of submittals or other documents. Work items of University, other contractors, utilities, and other third parties that may affect or be affected by Contractor shall be included.

**4.6.4.2** If University is required by the Contract Documents to furnish any materials, equipment, or other items to be incorporated into the Work by Contractor, Contractor shall submit, with the first schedule submittal, a letter clearly indicating the dates that such items are required at the Work site.

**4.6.4.3** The schedule shall indicate an early Substantial Completion date for the Work that is no later than the Work's required Substantial Completion date.

**4.6.4.4** The schedule, including duration of all activities, shall be given in calendar days and indicate all of the following:

**4.6.4.4.1** Interfaces with the Work of outside contractors (e.g., utilities, power, and any separate contractors retained by University);

**4.6.4.4.2** Description of activity including activity number/numbers;

**4.6.4.4.3** Estimated duration time for each activity and remaining duration;

**4.6.4.4.4** Early start, late start, early finish, late finish date, and predecessor/successors including stop-start relationships with lead and lag time for each activity – all activities shall have a predecessor and a successor, except for the start milestone and finish milestone;

**4.6.4.4.5** Total Float and Free Float available to each path of activities;

**4.6.4.4.6** Actual start date for each activity begun;

**4.6.4.4.7** Actual finish date for each activity completed;

**4.6.4.4.8** The percentage complete of each activity in progress or completed;

**4.6.4.4.9** Identification of all critical path activities;

**4.6.4.4.10** The critical path for the Work, with the path of activities being clearly and easily recognizable on the time-scaled network diagram. The path(s) with the least amount of float must be identified. Except as may otherwise be explicitly and specifically provided in the Contract Documents, no more than forty-percent (40%) of all activities may be identified as critical path items. The relationship between non-critical activities and

activities on the critical path shall be clearly shown on the network diagram. Near critical path activities shall also be identified;

**4.6.4.4.11** Unless otherwise authorized by University, all activities on the schedule representing construction on the site may not have a duration longer than fourteen (14) days. Construction items that require more than fourteen (14) days to complete must be broken into identifiable activities on the schedule with durations less than fourteen (14) days. The sum of these activities represents the total length required to complete that construction item; and

**4.6.4.4.12** Additional requirements, if any, as specified in the Supplemental General Conditions and/or authorized Supplementary Conditions.

**4.6.5 INTERIM COMPLETION DATES AND MILESTONES.** The schedule must include contractually specified interim completion dates and milestones (which completion milestones must have a “finish on or before” soft constraint added). The milestones and completion dates indicated are considered essential to the satisfactory performance of the Contractor’s Agreement and to the coordination of all Work. The milestone dates listed are not intended to be a complete listing of all Work or of interfaces with other contractors.

**4.6.6 FLOAT TIME.** “Total Float” is defined as the amount of time that an activity can be delayed from its early without delaying Substantial Completion. “Free Float” is the amount of time that an activity can be delayed without delaying the early start date of any successor activity. Total Float time and Free Float time shall belong to the project and University and Contractor have the right to use the Total Float time and/or Free Float Time for non-critical path activities until Contractor has reallocated such time on a newly submitted schedule.

**4.6.7 UPDATES.** Prior to any approval of an Application for Payment, University, A/E, and Contractor shall review Contractor’s schedule compared to the Work completed. The amount of Work completed shall be approved by University as supported by the schedule of values and as verified by the determination of Work completed. If necessary, Contractor shall then update and submit to University the schedule with the Application for Payment; all of which shall be in accordance with University’s approval. All updates shall be provided in electronic and hard copy formats. At each scheduled meeting with University, Contractor shall provide a four week look ahead, with long lead items identified. If the Work is not on schedule, Contractor shall immediately advise University in writing of Contractor’s proposed action to bring it on schedule.

**4.6.8 SCHEDULE OF SUBMITTALS.** Contractor shall prepare and keep current, for the A/E’s and University’s review and approval, a schedule of submittals required by the Contract Documents, which shall be coordinated with Contractor’s construction schedule and allow the A/E a reasonable time to review the submittals. The submittal schedule shall be included as part of the construction schedule. Submittals requiring expedited review must be clearly identified as such in the schedule of submittals. Contractor shall coordinate and agree upon a submittal schedule with A/E. If a submittal does not pass a second review, then a meeting will be held to determine a path to proceed and expedite approval. Contractor shall notify A/E in writing if expedited review of a submittal is critical.

**4.6.9 SCHEDULE RECOVERY.** If the Work represented on the critical path falls behind more than seven (7) days, Contractor shall redo the schedule within seven (7) days, showing how the Contractor shall recover the time. Contractor’s schedule must have an approved baseline schedule before the schedule may be updated. A narrative that addresses the changes in the schedule from the previously submitted schedule shall be submitted along with the updated schedule in electronic .pdf format and on the written request of University in native electronic copy format of the scheduling software utilized by Contractor. Contractor shall comply with the most recent schedules.

#### **4.6.10 SCHEDULE CHANGES.**

**4.6.10.1** The Contract Time may only be shortened or extended by a Change Order or Construction Change Directive.

**4.6.10.2** Should Contractor, after approval of the complete detailed construction schedule, desire to change Contractor's plan of construction, Contractor shall submit its requested revisions to University and the A/E, along with a written statement of the revisions including a description of the sequence and duration changes for rescheduling the Work, methods of maintaining adherence to intermediate milestones and the completion dates, and the reasons for the revisions. Requested changes to the approved baseline schedule shall include a narrative that addresses the requested changes. If the requested changes are acceptable to University, which acceptance shall not be unreasonably withheld, they shall be incorporated into the schedule in the next reporting period by Contractor. If after Contractor submits a request for change in the schedule, University does not agree with the request, University shall schedule a meeting with Contractor to discuss the differences.

**4.6.10.3** The critical path schedule, as the term is used in these General Conditions, shall be based on the current version of Contractor's schedule for the Work and accepted by University just prior to the an asserted change in the Work, asserted delay, suspension, or interruption. If Contractor believes it is entitled to an extension of Contract Time under the Contract Documents, Contractor shall submit a PCO in accordance with Section 7.2 to the A/E and University accompanied by an analysis ("Requested Time Adjustment Schedule") in accordance with the Contract Documents for time extensions. The "Requested Time Adjustment Schedule" shall include "fragnets" that represent the added or changed Work to the schedule. The impact on unchanged activities caused by the changes and/or delays being analyzed shall be included in these fragnets. A "fragnet" as used in these General Conditions and when used in the context of project scheduling is a subset of project activities that are inter-related by predecessor and successor relationships that are tied into the main schedule with identified start and completion points. Each fragnet may or may not be on the critical path. An entire schedule consists of a series of inter-related fragnets.

#### **4.6.11 EXCUSABLE DELAY.**

**4.6.11.1** If Contractor is unreasonably delayed in the progress of the Work on the critical path schedule by an act or neglect of University; or separate contractors retained by University; or by a Force Majeure Delay (defined below) that University reasonably determines may justify delay beyond the date for Substantial Completion, then the Contract Time shall be extended by Change Order for the period of time caused by such delay. The Contract Price shall not be increased, and the Contract Time shall not be extended for any delays that are concurrent with Contractor delays.

**4.6.11.1.1** For purposes of the Contractor's Agreement, a Force Majeure Delay shall mean a delay to the commencement or the progress of the Work by reason of events or causes beyond the control of University, the Contractor, and the Contractor's Subcontractors and Sub-subcontractors of any tier, or anyone directly or indirectly employed by them or anyone for whose acts they may be liable. Notwithstanding anything to the contrary set forth herein, Force Majeure Delays shall not include: (1) labor disputes confined to the Work site or relating solely to the Work that are due to a breach of a collective bargaining agreement by the Contractor or its Subcontractors or Sub-subcontractors of any tier, or anyone directly or indirectly employed by them or anyone for whose acts they may be liable; (2) adverse weather conditions, except as provided in Section 4.6.11.2; (3) a failure of the Contractor or its Subcontractors or Sub-subcontractors of any tier, or anyone directly or indirectly employed by them or anyone for whose acts they may be liable, to comply with any laws, codes or orders of governmental authorities with jurisdiction of the Work; or (4) any financial inability of the Contractor or its Subcontractors or Sub-subcontractors of any tier, or anyone directly or indirectly employed by them, to perform their obligations under the Contract Documents.

**4.6.11.1.2** Delays which according to the schedule do not affect any critical path milestone dates or the completion dates shown on the schedule at the time of the delay shall not be the basis for a change in the Contract Time.

**4.6.11.1.3** Contractor shall immediately take all steps reasonably possible to lessen the adverse impact of delay. Notwithstanding the foregoing, to the extent any of the causes for delay were caused by Contractor, reasonably foreseeable by Contractor, or avoidable by Contractor, then to such extent the delay shall not be cause for a change in the Contract Price and/or Contract Time. For purposes of this Section, “Contractor” shall include all Subcontractors and others under the responsibility of the Contractor.

**4.6.11.1.4** The determination of the total amount of time extension, if any, shall be based upon the current schedule in effect at the inception of the change and/or delay and upon all data relevant to the extension as supported by appropriate substantiating relative data in the project record. Once approved, such data shall be incorporated in the next monthly update of the schedule by Contractor.

**4.6.11.2** The Contract Price shall not be increased and the Contract Time shall not be extended for normal bad weather or any weather that is reasonably foreseeable at the time of entering into the Contractor’s Agreement. The Contract Time as stated in the Contract Documents includes due allowance for days on which Work cannot be performed out of doors. Contractor acknowledges that Contractor may lose days due to weather conditions. The Contract Time may be extended at no cost to University if all of the following are met, which must be established by Contractor:

**4.6.11.2.1** That the weather prevented Work from occurring that is on the critical path for the Work based upon a critical path schedule previously submitted to University and to the extent accepted by University;

**4.6.11.2.2** There are no concurrent delays for which Contractor is responsible;

**4.6.11.2.3** Contractor took all reasonable steps to alleviate the impact of the weather and made reasonable attempts to prevent the delay and despite such reasonable actions of Contractor, the weather impacted the critical path as described above; and

**4.6.11.2.4** In connection with the weather event for which delay is claimed by Contractor, the weather was either exceptionally adverse, such as a tornado, severe wind storm, or severe hail storm, or one of the following occurred:

**4.6.11.2.4.1** for any day between November 1 and March 31 for which delay is claimed by Contractor, the recorded minimum temperature at the Work site, as verifiably documented by Contractor, fell below the mean minimum temperature for the station closest to the Work site (“Proximate Station”) for the applicable month according to the Western Regional Climate Center Website, <http://www.wrcc.dri.edu/summary> (“WRCCW”), as shown on the *Average of Minimum Temperature* chart on the WRCCW for the Proximate Station, less the mean extreme minimum temperature for the Proximate Station for the applicable month, as shown on the *Minimum of Minimum Temperature Chart* on the WRCCW for the Proximate Station, divided by Two (2);

**4.6.11.2.4.2** for any day between November 1 and March 31 for which delay is claimed by Contractor, the recorded maximum temperature at the Work site, as verifiably documented by Contractor, fell below the mean minimum temperature as shown on the *Average of Minimum Temperature* chart on the WRCCW for the Proximate Station;

**4.6.11.2.4.3** for any day for which delay is claimed by Contractor, the recorded precipitation at the Work site, as verifiably documented by Contractor, exceeded seventy-five percent (75%) of the daily extreme for the applicable month as shown on the *POR – Daily Precipitation Average and Extreme* chart on the WRCCW for the Proximate Station;

**4.6.11.2.4.4** for any day for which delay is claimed by Contractor, the recorded snowfall at the Work site, as verifiably documented by Contractor, exceeded seventy-five percent (75%) of the daily extreme for the applicable month as shown on the *POR – Daily Snowfall Average and Extreme* chart on the WRCCW for the Proximate Station.

#### **4.6.12 COMPENSABLE DELAY, SUSPENSION OR INTERRUPTION.**

**4.6.12.1** In addition to the other requirements of the Contract Documents, a compensable delay, suspension, or interruption of the Work occurs only when the following conditions are met:

**4.6.12.1.1** The delay is caused by University for a reason not permitted by the Contract Documents; and

**4.6.12.1.2** Contractor delivers a written notice to the A/E and University within seven (7) days that Contractor knows or should have known of the condition giving rise to the purported compensable delay, suspension, or interruption, and the condition affects the Contract Time as indicated by the last agreed upon critical path schedule.

**4.6.12.2** To the extent of the compensable delay, Contractor's total entitlement for all compensable delay damages is the computed result of the following formula: Contract Price divided by Contract Time (in calendar days); the result of which is then multiplied by 0.05; and the result of which is multiplied by the number of calendar days of compensable days allowed under these General Conditions that are beyond the Contract Time. Notwithstanding any other provision of these General Conditions or the Contract Documents, to the extent Contractor is entitled to receive a markup under Sections 7.4.2.5.1 or 7.4.2.5.2 this provision shall be inapplicable, and the markup shall be deemed to include all the compensable delay damages provided by this Section.

**4.6.12.3** The length and extent of compensable delay shall be determined, with the use of the Work's critical path schedule by ascertaining the number of additional days added to the Contract Time are needed in order to perform the Work in accordance with the Contract Documents as a result of the delay, suspension, or interruption after receipt of the written notice received by the A/E and University under Section 4.6.12.1.2.

**4.6.12.4** Notwithstanding any other provision of these General Conditions, to the extent a non-compensable delay occurs at the same time as a compensable delay, University shall not be responsible for any compensation to Contractor and the Contract Price shall not be increased for the period of the non-compensable delay.

**4.6.13 TIME EXTENSION REQUESTS.** Contractor shall notify University within seven (7) days of a potential delay and Contractor shall request any and all Contract Time extensions within twenty-one (21) days after Contractor knew or should have known about the delay. Contractor must support any request for a Contract Time extension with a critical path schedule analysis.

#### **4.6.14 LIQUIDATED DAMAGES.**

**4.6.14.1** Time is of the essence in the Contract Documents. University will suffer damages that are difficult to ascertain for each calendar day the date for Substantial Completion is delayed. Therefore, as agreed damages and not as a penalty, University may offset from any payments due Contractor the sum stated in the Contractor's Agreement, as augmented in Section 4.6.14.2 in the case of continuing delay, for each day Substantial Completion is delayed beyond the date established for Substantial Completion of the Work by the Contract Documents.

**4.6.14.2** For each day subsequent to the fourteenth (14<sup>th</sup>) day after the date established for Substantial Completion of the Work by the Contract Documents, the liquidated damages amount stated in the Contractor's



Agreement shall be increased by ½ percent (0.5%) of the amount stated in the Contractor's Agreement for each day Substantial Completion is delayed beyond the date established for Substantial Completion of the Work by the Contract Documents.

**4.6.14.3** The sum for liquidated damages due University by Contractor has been agreed upon by reason of the inconvenience and added costs of administration, engineering, supervision, and other expenses resulting from Contractor's default.

**4.6.14.4** To the extent liquidated damages exceed any amounts that would otherwise be due Contractor, Contractor shall be liable for such excess to University.

**4.6.14.5** Notwithstanding any other provision of these General Conditions, the availability of liquidated damages to University shall not limit University's right to seek damages or other remedies available under law or equity to the extent such damages or remedies are not based upon delay.

**4.6.15 NO WAIVER OF UNIVERSITY'S RIGHTS.** Permitting Contractor to continue any part of the Work after the time fixed for completion or beyond any authorized extension thereof shall in no way operate as a waiver or estoppel on the part of University of any of its rights under the Contract Documents, including the right to liquidated damages or any other remedies or compensation.

**4.7 DOCUMENTS AND SAMPLES AT THE SITE, CERTIFYING "AS-BUILTS".** Contractor shall maintain at the Work site one record copy of the Drawings, Specifications, Addenda, authorized Amendments and Modifications, in good order and marked weekly to record changes and selections made during construction, as well as approved Shop Drawings, Product Data, Samples and similar submittals. These items shall be available to the A/E and shall be delivered to the A/E for submittal to University upon completion of the Work, signed by Contractor, certifying that they show complete and exact "as-built" conditions, stating sizes, kind of materials, piping, conduit locations, and similar matters. All notes of encountered or changed conditions shall be included.

#### **4.8 SHOP DRAWINGS, PRODUCT DATA AND SAMPLES.**

**4.8.1 NOT CONTRACT DOCUMENTS.** Shop Drawings, Product Data, Samples and other submittals are not Contract Documents. The submittal shall demonstrate, for those portions of the Work for which the submittal is required, the way Contractor proposes to conform to the information given and the design concept expressed in the Contract Documents.

**4.8.2 PROMPTNESS.** Contractor shall coordinate submittals prepared by Subcontractors and Sub-subcontractors, review, approve, and submit to the A/E, Shop Drawings, Product Data, Samples and other submittals required by the Contract Documents with reasonable promptness and according to an agreed submittal schedule in such sequence as to cause no delay in the Work, or the activities of University, or separate contractors.

**4.8.3 NOT PERFORM UNTIL A/E APPROVES.** Contractor shall not perform any portion of the Work requiring submittal and review of Shop Drawings, Product Data, Samples, mock-ups where required or other submittals (including deferred submittals) until the applicable submittal has been approved in writing by the A/E. Contractor shall perform the Work in accordance with the approved submittals. Submittals marked "No-exceptions taken" or its equivalent by the A/E are considered approved for purposes of this Section 4.8.3.

**4.8.4 REPRESENTATIONS BY CONTRACTOR.** By approving and submitting Shop Drawings, Product Data, Samples, and other submittals, Contractor represents that Contractor has determined and verified materials, field measurements, field construction criteria, manufacturer installation instructions and

procurement and delivery dates related thereto and has checked and coordinated the information contained within such submittals with the requirements of the Work and of the Contract Documents.

**4.8.5 CONTRACTOR'S LIABILITY.** Contractor shall not be relieved of responsibility for deviations from the requirements of the Contract Documents by the A/E's approval of Shop Drawings, Product Data, Samples, or similar submittals unless Contractor has specifically informed the A/E in writing of such deviation at the time of the submittal and the A/E has given written approval to the specific deviation. Contractor shall not be relieved of responsibility for errors or omissions in Shop Drawings, Product Data, Samples, or other submittals by the A/E's review and approval.

**4.8.6 DIRECT SPECIFIC ATTENTION TO REVISIONS.** Contractor shall direct specific attention in writing to all revisions on resubmitted Shop Drawings, Product Data, Samples, or other submittals, except those requested by the A/E and indicated on previous submittals.

**4.8.7 INFORMATIONAL SUBMITTALS.** Informational submittals upon which the A/E is not expected to take responsive action may be so identified in the Contract Documents.

**4.8.8 PROFESSIONAL SERVICES.** The Contractor shall not be required to provide professional services that constitute the practice of architecture or engineering unless such services are specifically required by the Contract Documents for a portion of the Work or unless the Contractor needs to provide such services in order to carry out the Contractor's responsibilities for construction means, methods, techniques, sequences and procedures. The Contractor shall not be required to provide professional services in violation of applicable law. If professional design services or certifications by a design professional related to systems, materials or equipment are specifically required of the Contractor by the Contract Documents, University and the A/E will specify performance and design criteria that such services must satisfy. The Contractor shall cause such services or certifications to be provided by a properly licensed Design Professional (as that term is defined in Section 4.8.8.1 of these General Conditions), whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings and other submittals prepared by such professional. Each Design Professional providing such services shall carry professional errors and omissions insurance in an amount of at least Two Million Dollars (\$2,000,000.00) per claim/annual aggregate with a deductible or self-insured retention of not greater than One Hundred Thousand Dollars (\$100,000.00), unless different amounts are authorized by University in writing. Shop Drawings and other submittals related to the Work designed or certified by such Design Professional, if prepared by others, shall bear such Design Professional's written approval when submitted to the A/E. University and the A/E shall be entitled to rely upon the adequacy, accuracy and completeness of the services, certifications and approvals performed or provided by such Design Professional, provided University and A/E have specified to the Contractor performance and design criteria that such services must satisfy. Pursuant to this Section 4.8, the A/E will review, approve or take other appropriate action on submittals only for the limited purpose of checking for conformance with information given and the design concept expressed in the Contract Documents. The Contractor shall not be responsible for the adequacy of the performance and design criteria specified in the Contract Documents.

**4.8.8.1** A "Design Professional" is any and all employees or independent contractors directly or indirectly employed by the Contractor, a Subcontractor or a Sub-subcontractor of any tier to perform any professional design services required by the Contract Documents. The Contractor or its Subcontractors or Sub-subcontractors of any tier employing the Design Professional shall require the Design Professional to agree in writing to be bound by the terms of the Contract Documents insofar as they apply to the design services of the Design Professional in the performance of the Work.

**4.8.8.2** The Contractor hereby assigns to University all common law, statutory and other rights that the Contractor may have in the drawings, specifications and other documents prepared by the Design Professional for the Work (the "Design Documents"), including all copyrights. The Contractor shall endeavor to obtain a similar assignment to University by the Design Professional and by the Subcontractors or Sub-subcontractors

of any tier employing the Design Professional of their common law, statutory and other rights (including copyrights) in the Design Documents. At the date of final payment or upon the earlier termination of the Contractor's Agreement, the Contractor shall promptly deliver to University hardcopy originals of all Design Documents and all Design Documents in reproducible (not read only) electronic media.

**4.8.8.3** The Contractor shall require and hereby represents and warrants to University that the Design Professional is appropriately registered with and licensed by the State of Utah to perform the services required by the Contract Documents to be performed by the Design Professional.

**4.8.8.4** All services provided by the Design Professional shall be performed consistent with the professional skill and care ordinarily provided by other design professionals: (1) with the same or similar license; and (2) providing the same or similar design professional service (A) in the same or similar locality, (B) at the same or similar time and (C) under the same or similar circumstances, provided that, if the nature of the project reasonably requires specialized design expertise, the Design Professional shall perform design professional services consistent with such specialized design expertise.

**4.8.8.5** Notwithstanding any approval of University or A/E of any Design Documents, the Contractor shall be responsible for assuring that all Design Documents (whether prepared by a Design Professional employed by the Contractor, a Subcontractor or a Sub-subcontractor of any tier) are technically adequate and accurate and are in accordance with all laws, ordinances, codes, regulations or other requirements of governmental authorities having jurisdiction of the Work applicable to the Work on the day of the issuance of such documents and on the day of the use of such documents on the Work.

**4.8.8.6** The Contractor shall be responsible and liable to University for any and all losses, costs, and/or expenses incurred by University arising out of, related to and/or connected with errors or omissions in the services provided hereunder by the Design Professional, to the extent that such errors or omissions were caused by the failure of the Design Professional to perform services consistent with the requirements of Section 4.8.8.4 or by other fault of the Design Professional, whether or not such losses, costs and/or expenses were caused by any negligence or other fault of the Contractor. This responsibility and liability shall survive completion of the Work or termination of the Contractor's Agreement.

**4.8.8.7** The Contractor shall indemnify and hold harmless University and the other Indemnified Parties (as defined in Section 4.12) from and against any and all third-party claims, demands, losses, liabilities, judgments, costs, expenses and/or attorney fees arising of, related to and/or connected with errors or omissions in the services provided hereunder by the Design Professional, to the extent that such errors or omissions were caused by the failure of the Design Professional to perform services consistent with the requirements of Section 4.8.8.4 or by other fault of the Design Professional, whether or not such third-party claims, demands, losses, liabilities, judgments, costs, expenses and/or attorney fees were caused by any negligence or other fault of the Contractor. This indemnity is in addition to the indemnity provided in Section 4.12 and shall survive completion of the Work or termination of the Contractor's Agreement.

**4.8.8.8** The Contractor's or its Subcontractor's or Sub-subcontractor of any tier's agreement with the Design Professional for design services in the performance of the Work shall state that University and its successors and assigns are intended third-party beneficiaries of such agreement and such agreement with the Design Professional shall require the Design Professional to deliver to University a separate agreement wherein the Design Professional shall expressly contract with University to provide the Design Professional's professional services consistent with the standard of care established by Section 4.8.8.4.

**4.8.8.9** The Contractor shall indemnify, defend and hold harmless University and the other Indemnified Parties (as defined in Section 4.12 of these General Conditions) from and against any and all claims, demands, losses, liabilities, judgments, costs, expenses and/or attorney fees caused by any suits or claims of infringement of any patent rights or copyrights for materials, methods or systems depicted upon or required by Design

Documents prepared by the Design Professional. This indemnity is in addition to the indemnity provided in Sections 4.11 and 4.12 of these General Conditions and shall survive completion of the Work or termination of the Contractor's Agreement.

#### **4.9 USE OF SITE.**

**4.9.1 IN GENERAL.** Contractor shall confine its equipment, the storage of materials, and the operations of its workers at the Work site to areas permitted by the Contract Documents, laws, rules, regulations, ordinances, orders, and permits and shall not unreasonably encumber the Work site with materials or equipment. Contractor shall take all reasonable steps to secure the Work site and protect the Work from any damage. Upon completion of the Work, Contractor shall leave the Work site free and clear of all waste materials, rubbish, tools, equipment, and surplus materials. Contractor shall at all times keep the Work site free from spilled liquids and chemicals, toxic or otherwise. If such a spill occurs while Contractor has control of the Work site, Contractor shall be responsible to clean the affected areas on or about the Work site and pay all associated costs, fines, and penalties. Notwithstanding the foregoing, Contractor shall not be responsible for any damage to the Work site or the Work to the extent caused by University or University's agents.

#### **4.9.2 ACCESS TO NEIGHBORING PROPERTIES.**

**4.9.2.1** Contractor shall not, except as provided in the Contract Documents or with University's advance written consent when necessary to perform the Work, interfere with access to properties neighboring the Work site by the owners of such properties and their respective tenants, agents, invitees and guests.

**4.9.2.2** Various federal, state, and local agencies and private landowners may own or control lands and facilities either crossed by or adjacent to the Work site. University shall secure and pay for all necessary rights of access to the Work site. Contractor shall comply with all stipulations provided by University and shall maintain a cooperative relationship with all agencies and landowners. Contractor shall not retain on the Work site any person who in the judgment of University prejudices or tends to endanger this cooperation. Contractor shall not enter into any agreement with such agencies or landowners related to the Work without prior approval by University.

**4.10 ACCESS TO WORK.** Contractor shall provide University and the A/E access to the Work in preparation and progress, at all times and wherever located.

**4.11 INTELLECTUAL PROPERTY LICENSES.** Contractor shall obtain and pay for all royalties and other license fees for all equipment, property, or processes of Contractor used or purchased in connection with performance of the Work. Contractor shall defend suits or claims for infringement of intellectual property rights and shall hold University and the A/E harmless from loss on account thereof but shall not be responsible for such defense or loss when a particular design, process, or product of a particular manufacturer or manufacturers is required by the Contract Documents. However, if Contractor has reason to believe that the required design, process or product is an infringement of any third party's intellectual property right, Contractor shall be responsible for such defense or loss unless such information is promptly furnished to University in writing.

**4.12 INDEMNIFICATION.** To the fullest extent permitted by law, Contractor shall release, indemnify, hold harmless, and defend the State of Utah, the State of Utah's institutions, agencies (including, but not limited to, University), departments, divisions, authorities, and instrumentalities, boards, commissions, elected or appointed officers, employees, agents and authorized volunteers (collectively "Indemnified Parties") from and against any and all claims, liabilities, demands, actions, damages, losses and expenses of any nature whatsoever, including, but not limited to, attorneys' fees and defense costs (collectively "Liabilities"), and including those events covered under the blanket Contractual Liability Coverage required under the Contract Documents, arising out of, related to, or connected with any act or omission in the performance of the Work, including the

Work of all Subcontractors and their employees, provided that any Liabilities are caused in whole or in part by the negligent, intentional, or other wrongful act or omission of Contractor, any Subcontractor, their employees, or anyone directly or indirectly employed or the agent of any of them or anyone for whose acts any of them may be liable, regardless of whether or not it is caused in part by an Indemnified Party. Without relieving Contractor of any obligation under the Contract, the Indemnified Parties shall have the right, at their option, to fully participate in the investigation, defense and settlement of any Liabilities.

**4.12.1 NOT EXCLUSIVE.** The foregoing obligations in this Section 4.12 shall not be construed to negate, abridge, or otherwise reduce any other right or obligation of indemnity which would otherwise exist as to any party or person under the Contract Documents.

**4.12.2 NOT LIMITED.** The foregoing obligations in this Section 4.12 shall not be limited by a limitation on amount or type of damages, compensation or benefits payable by or for the Contractor or Subcontractor under workers' or workmen's compensation acts, disability benefit acts or other employee benefit acts.

## **ARTICLE 5. SUBCONTRACTORS.**

### **5.1 AWARD OF SUBCONTRACTS AND OTHER CONTRACTS FOR PORTIONS OF THE WORK.**

#### **5.1.1 SUBCONTRACTING WORK PERMITTED; CONDITIONS.**

**5.1.1.1** Contractor may subcontract portions of the Work.

**5.1.1.2** University reserves the right to reject on reasonable ground any Subcontractor. Contractor shall not contract with any person or entity to whom University has made reasonable objection. Contractor shall not be required to contract with anyone to whom Contractor has made reasonable and timely objection, provided that any additional costs associated with Contractor replacing a Subcontractor objected to by Contractor with a replacement Subcontractor not objectionable to Contractor shall be at no cost to University.

**5.1.2 SUBSEQUENT CHANGES.** After execution of Contractor's Agreement Subcontractors listed by Contractor in accordance with Utah Code § 63A-5b-605 and Rule R23-1-615 may be changed by Contractor only in accordance with the requirements of Utah Code § 63A-5b-605 and R23-1-615.

**5.1.2.1** University shall pay the additional costs for a University-requested change in Subcontractor if all of the following conditions are met:

**5.1.2.1.1** If University in writing requests the change of a Subcontractor;

**5.1.2.1.2** The original Subcontractor is a responsible subcontractor that meets the requirements of the Contract Documents; and

**5.1.2.1.3** The original Subcontractor did not withdraw as a Subcontractor on the Work.

**5.1.2.2** In all other circumstances, Contractor shall pay the additional cost for a change in a Subcontractor.

**5.1.3 BUSINESS AND LICENSING REQUIREMENTS.** All Subcontractors used by Contractor shall have secured, at their own expense, all necessary professional accreditations, registrations, and licenses in the state of Utah.

**5.1.4 BONDING OF SUBCONTRACTORS.** Subcontractors, as identified by University in the procurement documents, may be required to submit performance and payment bonds to cover the full extent of

their portion of the Work. This provision does not in any way limit the right of Contractor to have Subcontractors at any tier be required to have a performance and/or payment bond at Contractor's expense.

**5.1.5 SUBCONTRACTOR DEFAULT INSURANCE.** If the Contract Price includes any amount to compensate the Contractor for Subcontractor Default Insurance ("SDI"), then, notwithstanding anything in the Contract Documents to the contrary:

**5.1.5.1** University shall be added to the SDI by a financial interest endorsement reasonably acceptable to University at no cost to University;

**5.1.5.2** If the Contract Documents provide for Contractor contingency, no Contractor contingency may be expended for any Subcontractor default or for any expenses and/or losses arising out of, connected with and/or related to any Subcontractor default;

**5.1.5.3** Contractor shall in no event be entitled to an increase in the Contract Price and/or extension of the Contract Time for a Subcontractor default or for expense, losses and/or delays arising out of, connected with and/or related in any way to a Subcontractor default; and

**5.1.5.4** The cost of SDI is included in Contractor's overhead and profit for purposes of Article 7.

## **5.2 SUBCONTRACTUAL RELATIONS.**

**5.2.1 CONTRACTOR FULLY RESPONSIBLE.** Subcontracting any portion of the Work shall not relieve Contractor of Contractor's obligations or duties under the Contract Documents, Contractor shall be fully responsible and liable to University for the acts and omissions of all Subcontractors at any tier and their employees and agents and Contractor shall maintain complete control over all Subcontractors. Neither the consent of University to a Subcontractor proposed by Contractor, nor anything contained in the Contract Documents shall be deemed to create a contractual relationship between a Subcontractor at any tier and University.

**5.2.2 COMPLY WITH CONTRACT DOCUMENTS.** By appropriate enforceable agreement Contractor shall require each Subcontractor to be bound to Contractor by the terms of the Contract Documents, and to assume toward Contractor all the obligations and responsibilities that Contractor, by the Contract Documents, assumes towards University and the A/E.

**5.2.3 RIGHTS.** Each Subcontractor agreement shall preserve and protect the rights of University under the Contract Documents with respect to that portion of the Work to be performed by the Subcontractor so that subcontracting any portion of the Work shall not prejudice any rights of University under the Contract Documents, and shall allow to the Subcontractor, unless specifically provided otherwise in the Subcontractor agreement, the benefit of all rights and remedies against Contractor that Contractor, by the Contract Documents, has against University.

**5.2.4 SUB-SUBCONTRACTORS.** Contractor shall require each Subcontractor to enter into similar agreements with Sub-subcontractors and to require such Sub-subcontractors to enter into similar agreements with lower tier Sub-subcontractors that comply with the requirements of Sections 5.2.2 and 5.2.3.

**5.2.5 DOCUMENT COPIES.** Contractor shall make available to each proposed Subcontractor, prior to execution of the Subcontractor agreement, copies of the Contract Documents to which the Subcontractor shall be bound. Contractor shall require Subcontractors to make copies of applicable portions of the Contract Documents available to their respective proposed Sub-subcontractors.

**5.3 CONTINGENT ASSIGNMENT OF SUBCONTRACTS TO UNIVERSITY.** Contractor contingently assigns each Subcontractor agreement with a Subcontractor for a portion of the Work to University, provided that the assignment is effective only after termination of the Contractor's Agreement by University for cause pursuant to Section 12.2 or stoppage of the Work by University pursuant to Section 12.5, and only for those Subcontractor agreements that University accepts by notifying the Subcontractor in writing. Contractor shall remain liable for all obligations incurred under assigned Subcontractor agreements prior to University's acceptance of such assignment.

## **ARTICLE 6. PROTECTION OF PERSONS AND PROPERTY.**

### **6.1 SAFETY OF PERSONS AND PROPERTY.**

**6.1.1 CONTRACTOR RESPONSIBILITY.** Contractor shall be solely responsible for initiating, maintaining, and supervising all safety precautions and programs in connection with the performance of the Work. Contractor shall seek to minimize the risk of bodily injury, property damage, and environmental harm by taking all reasonable precautions to protect:

**6.1.1.1** All persons at and/or in proximity to the Work site;

**6.1.1.2** Materials and equipment to be incorporated in the Work, whether in storage on or off the Work site, under the care, custody, or control of Contractor or a Subcontractor;

**6.1.1.3** Property and structures located at the Work site and adjacent to the Work site, whether or not such property and structures are part of the Work, such as trees, shrubs, lawns, walks, pavements, roadways, structures and utilities not designated for removal, relocation or replacement in the course of construction; and

**6.1.1.4** The environment.

**6.1.2 SAFETY PROGRAM, PRECAUTIONS.** Contractor shall institute and provide to University a project specific safety program at the start of the Work to minimize accidents. The program shall continue to the final completion of the Work and conform to applicable laws, rules, and regulations. including without limitation. the Utah Occupational Safety and Health Rules as published by the Utah Labor Commission - UOSH Division at Utah Administrative Code, R614. Contractor shall post signs, erect barriers, and provide those items necessary to implement the safety program. As soon as Contractor proceeds with the Work, Contractor shall have all workers and all visitors on the Work site wear safety hard hats, as well as all other appropriate safety apparel such as safety glasses and shoes, and obey all safety laws, rules, and regulations. Contractor shall post a sign in a conspicuous location indicating the necessity of wearing hard hats, and Contractor shall loan such hard hats to visitors. Contractor shall maintain a clean and orderly Work site.

**6.1.3 COMPLIANCE WITH LAWS.** Contractor shall give notices and comply with applicable laws, rules, regulations, ordinances, and orders of public authorities applicable to the safety of persons and property and their protection from damage, injury and loss. In particular, Contractor shall comply with all applicable provisions of federal, state and municipal safety laws, rules and regulations, specifically including, without limitation, building codes, to prevent accidents and injury to persons on, about or adjacent to the Work site.

**6.1.4 ERECT AND MAINTAIN SAFEGUARDS.** As required by existing conditions at the Work site and proper and safe performance of the Work, Contractor shall erect and maintain safeguards for safety and protection, including effective fences, danger signs, barricades and other warnings against hazards. Contractor shall also promulgate safety regulations and notify owners and users of adjacent sites and/or utilities before performing Work that may impact such adjacent sites and/or utilities.

**6.1.5 UTMOST CARE.** When use or storage of explosives or other dangerous materials or equipment or unusual methods are necessary for execution of the Work, Contractor shall exercise utmost care and carry on such activities under the supervision of properly qualified personnel.

**6.1.6 PROMPT REMEDY.** Contractor shall promptly remedy any damage and loss (other than damage or loss insured under property insurance required by Section 10.2) to persons, property and/or the environment arising in conjunction with the Work caused in whole or in part by Contractor, Subcontractors, or any person or entity for whose acts Contractor is responsible, without cost or expense to University.

**6.1.7 SAFETY DESIGNEE.** Contractor shall designate a responsible member of Contractor's organization at the Work site whose duty shall be the prevention of accidents, damage, injury and loss. This person shall be Contractor's superintendent, unless otherwise designated by Contractor in writing to University and the A/E.

**6.1.8 LOAD SAFETY.** Contractor shall not load or permit any part of the construction or Work site to be loaded so as to endanger its safety and/or the safety of persons at or in the vicinity of the Work site.

**6.1.9 OFF-SITE RESPONSIBILITY.** In addition to its other obligations under this Article 6, the Contractor shall, at Contractor's sole cost and expense, promptly repair any damage or disturbance to walls, utilities, streets, ways, sidewalks, curbs and the property of the State, University and third parties (including municipalities and other governmental agencies) resulting from the performance of the Work, whether by Contractor or by Contractor's Subcontractors at any tier. The Contractor shall not cause materials, including soil and debris, to be placed or left on streets or ways.

**6.1.10 EMERGENCIES.** In an emergency affecting safety of persons or property, Contractor shall act, at Contractor's discretion, to prevent threatened damage, injury or loss. Contractor shall promptly notify University of the action taken.

**6.2 HAZARDOUS MATERIALS.** In the event Contractor encounters at the Work site material reasonably believed to be asbestos, polychlorinated biphenyl (PCB), or any other hazardous waste or substance that may endanger the health of persons performing Work or being at the Work site that is not part of the Work and/or disclosed by the Contract Documents, Contractor shall immediately stop Work in the area affected and immediately report the condition to University and the A/E by phone with a follow-up email. Contractor shall resume the Work in the affected area upon written direction provided by University. Except to the extent provided otherwise in the Contract Documents, or if the presence of hazardous materials is due to the fault of Contractor, Contractor shall not be required to perform, without Contractor's consent, any Work relating to asbestos, polychlorinated biphenyl (PCB), or any other hazardous waste or substance.

**6.3 HISTORICAL AND ARCHEOLOGICAL CONSIDERATIONS.** In the event Contractor discovers any cultural, historical, or archeological material that is either recognized as an item to be protected under federal, state, or local law or regulation, or is an item of obvious value to the State of Utah, Contractor shall cease any Work that would interfere with such discovery and immediately report the condition to University and the A/E by phone with a follow-up email. Contractor shall resume the Work upon the direction of University. Contractor shall ensure cooperation with any University-recognized archaeologist or other cultural/historical expert.

**6.4 CONTRACTOR LIABILITY.** If Contractor fails in any of its obligations in Sections 6.2 through 6.3, Contractor shall be liable for any damages to University, the State of Utah, or any third party resulting from such noncompliance. Contractor shall also be liable for any mitigation or restoration effort resulting from such noncompliance. To the extent all the following is met, the presence of hazardous material or cultural, historical, or archeological material at the Work site shall qualify as a concealed or unforeseen condition under Section 7.1.5:



**6.4.1** The presence of such material is not reasonably foreseeable given the site conditions that Contractor is or should have been aware of;

**6.4.2** The presence of such material is not identified in any part of the Contract Documents;

**6.4.3** Contractor has undertaken all proper action to mitigate any impact of the discovery of such material on the Contract Time and/or Contract Price;

**6.4.4** The discovery of such material increases the Contract Time and/or Contract Price from what is stated in the Contract Documents; and

**6.4.5** The requirements of Section 7.1.5 and the Contract Documents are met.

## **ARTICLE 7. MODIFICATIONS, PRs & PCOs, PRE AND CLAIM PROCESS.**

### **7.1 MODIFICATIONS: IN GENERAL.**

**7.1.1 TYPES OF MODIFICATIONS AND LIMITATIONS.** Changes in the Work may be accomplished after execution of the Contractor's Agreement, and without invalidating the Contract Documents, by ASI, Change Order or Construction Change Directive, subject to the limitations stated in this Article 7 and elsewhere in the Contract Documents. Contractor must have a written Change Order or Construction Change Directive executed by University under this Article 7 prior to proceeding with any Work for which Contractor intends to request an increase in the Contract Price and/or an extension of the Contract Time.

**7.1.2 BY WHOM ISSUED.** The A/E or University may issue ASIs not involving an adjustment in the Contract Price or an extension of the Contract Time which are not inconsistent with the intent of the Contract Documents. A Change Order or Construction Change Directive shall be issued by University. The A/E shall prepare Change Orders and Construction Change Directives with specific documentation and data for University's approval and execution in accordance with the Contract Documents.

**7.1.3 CONTRACTOR TO PROCEED UNLESS OTHERWISE STATED.** Changes in the Work shall be performed under applicable provisions of the Contract Documents, and Contractor shall proceed promptly, unless otherwise provided in the ASI, Change Order or Construction Change Directive.

**7.1.4 ADJUSTING UNIT PRICES.** If unit prices are stated in the Contract Documents or subsequently agreed upon, and if quantities originally contemplated are so changed in a proposed Change Order or Construction Change Directive that application of such unit prices to quantities of Work proposed shall cause a substantial inequity to University or Contractor, the applicable unit prices may be equitably adjusted.

**7.1.5 CONCEALED OR UNKNOWN CONDITIONS.** Contractor must file a written notice with University within seven (7) calendar days of the date that Contractor knew or should have known of a site condition described below or Contractor shall be deemed to waive any right to file any PCO, PRE, or Claim for an increase in the Contract Price and/or extension of the Contract Time related to such condition:

**7.1.5.1** If Contractor encounters unknown and reasonably unforeseeable subsurface or otherwise concealed physical conditions, including hazardous or historical/cultural/archeological materials under Article 6, which differ materially from those indicated by the Contract Documents or which would have been revealed by a reasonably thorough site inspection; or

**7.1.5.2** If Contractor encounters unknown physical conditions of an unusual nature which differ materially from those ordinarily found to exist and generally recognized as inherent in construction activities of the character provided for in the Contract Documents.

**7.1.6 INCREASE IN CONTRACT TIME.** To the extent University and/or the State of Utah is damaged by the failure of Contractor to provide the notice required by Section 7.1.5 after the Contractor knows or should have known of such site condition, Contractor shall be liable for liquidated damages attributable thereto, as well as any damages to the State of Utah and/or University that are allowable in addition to liquidated damages.

**7.1.7 ALLOWANCES.**

**7.1.7.1** The Contractor has included in the Contract Price all allowances stated in the Contract Documents. Items covered by allowances shall be supplied for such amounts and by such persons or entities as University may direct, but the Contractor shall not be required to employ persons or entities to whom the Contractor has reasonable objection.

**7.1.7.2** Unless otherwise provided in the Contract Documents:

**7.1.7.2.1** Allowances shall cover the cost to the Contractor of materials and equipment delivered at the Work site and all required taxes, less applicable trade discounts;

**7.1.7.2.2** Allowances shall cover the Contractor's costs of unloading and handling at the Work site, labor, installation costs and other expenses contemplated for allowance items of the Work, including the Contractor's overhead and profit.

**7.1.7.2.3** Whenever costs are more than or less than allowances, the Contract Price for the Work shall be adjusted accordingly by Change Order. The amount of the Change Order shall reflect (1) the difference between actual costs and the allowances under Section 7.1.7.2.1 and (2) changes in Contractor's costs under Section 7.1.7.2.2.

**7.1.7.3** Materials and equipment under an allowance shall be selected by University with reasonable promptness.

**7.2 CONTRACTOR INITIATED REQUESTS.**

**7.2.1 THE REQUEST FOR INFORMATION ("RFI") PROCESS AND TIME TO FILE.** Contractor may file an RFI with the A/E regarding any question the answer to which will assist Contractor in the proper completion of the Work, including, but not limited to, issues related to the Contract Documents, Drawings, and Specifications. The RFI shall be filed with the A/E in a timely manner so as not to prejudice University as to the quality, time, or cost related to the Work.

**7.2.2 PROPOSED CHANGE ORDER ("PCO").** Within seven (7) days after Contractor knows or should know of a situation or condition for which Contractor anticipates requesting an increase in the Contract Price and/or extension of the Contract Time, Contractor must file a Proposed Change Order ("PCO") with University, or Contractor shall be deemed to waive any right to claim an increase in the Contract Price and/or extension of the Contract Time related to such situation or condition. The PCO shall include all documentation supporting the PCO available to Contractor at the time of filing and Contractor shall thereafter diligently pursue the supplementation(s) of such documentation and promptly deliver such supplementation(s) to University.

**7.2.2.1** One of the following may occur after a PCO is filed with University:

**7.2.2.1.1** University, after considering any input by the A/E, may reach an agreement with Contractor and issue a Change Order.

**7.2.2.1.2** University, after considering any input by the A/E, may issue a Construction Change Directive.

**7.2.2.1.3** If University, after considering any input by the A/E, disagrees with Contractor's PCO, University may seek additional information or verification from Contractor, the A/E, or other sources, and may negotiate with Contractor, may issue a Change Order upon such later agreement, may issue or retract an issued PR, or may issue a Construction Change Directive.

**7.2.2.2** If a Construction Change Directive is issued which identifies University's position in regard to a Contract Price and/or Contract Time adjustment or if a PCO is denied by University, Contractor must file a PRE no later than twenty-one (21) days after Contractor's receipt of the Construction Change Directive or such denial of the PCO. Failure to timely file a PRE shall be deemed to waive any right to an increase in the Contract Price and/or extension of the Contract Time related to a Construction Change Directive beyond that identified by University in the Construction Change Directive, if any, or denial of the PCO. Such waiver shall entitle University to convert a Construction Change Directive into a Change Order, whether or not executed by Contractor.

**7.2.2.3** If a Construction Change Directive leaves open the determination of an increase in the Contract Price and/or extension of the Contract Time related to a change in the Work, then the time period for commencement of filing the PRE shall not accrue until such time as University has conveyed to Contractor University's position as to increase, if any, in the Contract Price and/or extension, if any, of the Contract Time as a result of the change in the Work.

**7.2.2.4** The Contractor must continually cooperate with University in providing data, documentation and efforts to resolve any issues related to a PCO.

**7.2.3 SUBSTITUTIONS.** The Contractor may make substitutions only with the consent of University, after evaluation by the A/E and in accordance with a Change Order. Substitutions will be considered after the award of the Contractor's Agreement only when a PCO is submitted by the Contractor to substitute a non-specified product for a product specified in the Contract Documents, under the following conditions:

**7.2.3.1** The PCO is accompanied by complete data on the proposed substitution substantiating compliance with the design intent and performance requirements of the Contract Documents, including product identification and description, performance and test data, references and samples where applicable, comparison of the proposed substitution with the products specified or named in the Contract Documents, and the impact of the substitution upon the Contract Time.

**7.2.3.2.** The PCO is accompanied by accurate cost data on the proposed substitution and comparison with the products specified, whether or not modification of the Contract Price is to be a consideration.

**7.2.3.3** The Contractor is responsible for any additional costs for the A/E's additional services caused by the evaluation of the proposed substitution and/or the substitution of products.

**7.2.3.4** The PCO for substitution by the Contractor shall constitute a certification by the Contractor that the Contractor has investigated the proposed substitute product and determined that it is equal or superior in all respects to that specified; the cost data presented by the Contractor is complete and includes all related costs under the Contract Documents, including the A/E's additional services; the Contractor waives all claims for additional costs related to the substitution which subsequently become apparent; the Contractor will provide the same guarantee or warranty for the substituted product that the Contractor would have provided for the

product specified in the Contract Documents; and the Contractor will coordinate the installation of the accepted substitute, making such changes as may be required for the Work to be properly completed in all respects.

**7.2.3.5** Substitutions will not be considered by the A/E or University if they are intended or implied by submittals of Shop Drawings, Product Data or Samples without a PCO for substitution or when for their implementation they require a substantial revision of the Contract Documents in order to accommodate their use.

**7.3 PROPOSAL REQUEST INITIATED BY UNIVERSITY.** University may submit a Proposal Request to Contractor seeking information, data, impact on the Contract Price and/or impact on the Contract Time for a change in the Work or other modification to the Contract Documents. The PR shall provide a time limit for Contractor to file a response with the A/E and University. If a proposal is not timely provided by Contractor, University may calculate a Change Order under Section 7.4.2. Upon timely receipt of a proposal, one of the following shall occur:

**7.3.1 IF AGREEMENT, CHANGE ORDER ISSUED.** University, after considering any input by the A/E, may reach an agreement with the Contractor and issue a Change Order.

**7.3.2 IF DISAGREEMENT.** If University disagrees with Contractor's proposal, after considering any input from the A/E, University may seek additional information or verification from Contractor or other sources, may negotiate with Contractor, may issue a Change Order upon such later agreement, may retract the PR, or may issue a Construction Change Directive. If a Construction Change Directive is issued that identifies University's position in regard to the increase, if any in the Contract Price and/or extension, if any, of the Contract Time, Contractor must file a PRE within twenty-one (21) days of Contractor's receipt of the Construction Change Directive, or Contractor shall be deemed to waive any right for an increase in the Contract Price and/or extension of the Contract Time as a result of the issuance of the Construction Change Directive beyond that identified by University in the Construction Change Directive, if any. Such waiver shall entitle University to convert the Construction Change Directive into a Change Order, whether or not executed by Contractor. If the Construction Change Directive leaves open the determination of an increase, if any, in the Contract Price and/or extension, if any, of the Contract Time related to the change in the Work, then the time period for commencement of filing the PRE shall not accrue until such time as University has conveyed to Contractor University's position as to the increase, if any, in the Contract Price and/or extension, if any, of the Contract Time resulting from the change in the Work.

## **7.4 CHANGE ORDERS.**

**7.4.1 ADJUSTING PRICE BASED UPON AGREEMENT.** If a Change Order provides for an adjustment to the Contract Price, the adjustment shall be based on the mutual agreement of Contractor and University, including any terms mandated by unit price agreements or other terms of the Contract Documents.

**7.4.2 UNIVERSITY RESOLUTION OF PRICE IN THE ABSENCE OF AN AGREEMENT UNDER SECTION 7.4.1.** In the absence of an agreement under Section 7.4.1, the adjustment in Contract Price shall be based on an itemized accounting of costs and savings supported by appropriate data. Unless otherwise provided in the Contract Documents, costs for the purposes of this Section shall be limited to the following:

**7.4.2.1** All direct and indirect costs of labor; including workers' compensation insurance, social security, and other federal and state payroll-based taxes, and payroll-based fringe benefits paid by Contractor so long as they are reasonable and no higher than that charged to other clients;

**7.4.2.2** Costs of materials, on-site temporary facilities, supplies, and equipment (except hand tools) required for or incorporated into the Work;

**7.4.2.3** Rental costs of machinery, equipment, tools (except hand tools), and on-site temporary facilities, whether rented from Contractor or others;

**7.4.2.4** Costs of permits and other fees, sales, use or similar taxes related to the Work; and

**7.4.2.5** Overhead and profit. The markups stated herein for overhead and profit are intended to cover the Contractor's profit and all indirect costs associated with a change in the Work. Items covered by such markups include, but are not limited to: home office expenses, branch office and field office overhead expense of any kind; project management; estimating, engineering; coordinating; expediting; purchasing; billing and invoicing; detailing; legal, accounting, data processing or other administrative expenses; computer and telephone costs (including computer and phone allowances); shop drawings; liability insurance premium, auto insurance premium, performance and payment bond premium and SDI; vehicle costs (including vehicle allowances); ESOP related costs; and warranty expense costs. The cost for the use of small tools is also to be considered covered by such markups. Small tools shall be defined as tools and equipment (power or non-power) with an individual purchase cost of less than Seven Hundred Fifty Dollars (\$750).

**7.4.2.5.1** The maximum markup percentage to be paid to any contractor (regardless of tier) including Contractor, a Subcontractor and/or Sub-subcontractor on self-performed work shall be a single markup percentage not-to-exceed fifteen percent (15%) of the net increased direct cost of: (A) direct labor and allowable labor burden costs applicable to the change in the Work; (B) the net cost of material and installed equipment incorporated into the change in the Work, and (C) net rental cost of major equipment and related fuel costs necessary to complete the change in the Work;

**7.4.2.5.2** With respect to pricing the portion of Change Orders involving work performed by lower tier contractors, including Subcontractors and Sub-subcontractors, the maximum markup percentage allowable to the Contractor, Subcontractor or Sub-subcontractor supervising the lower tier contractor's work shall not exceed seven percent (7%) of the net increase of all approved changes in the Work performed by all contractors combined for any particular Change Order.

**7.4.2.5.3** Contractor agrees to include these limitations on Change Order pricing in Contractor's subcontracts with Subcontractors and shall likewise require all of Contractor's Subcontractors to include the same provisions in all sub-subcontracts with their respective Sub-subcontractors of any tier.

**7.4.3 CREDITS.** The amount of credit to be allowed by Contractor to University for a deletion or change in the Work which results in a net decrease in the Contract Price shall be actual net cost as confirmed to University based upon corroboration by an appropriate source, provided, however, the application of the markup percentages referenced in Section 7.4.2.5 for overhead and profit will apply only to additive change orders. In those instances where a change in the Work involves both additive and deductive work, the additions and deductions will be netted and the markup percentage adjustments will be applied to the net additive amount, if any.

**7.4.4 EFFECT OF A CHANGE ORDER.** A Change Order signed by the Contractor constitutes the Contractor's agreement that, when implemented by University, the adjustment in the Contract Price, if any, and/or the adjustment in the Contract Time, if any, for the change in the Work shall fully and finally compensate the Contractor and its Subcontractors and Sub-subcontractors of any tier for any and all additional costs, damages or expenses arising directly or indirectly out of the change in the Work described in the Change Order.

**7.4.4.1** All Change Orders shall be conclusively presumed to constitute settlement of all Claims for direct or indirect damages of the Contractor, its Subcontractors and their respective Sub-subcontractors of any tier arising out of the change in the Work. This shall include, but is not limited to, any and all so-called "delay," "equitable adjustment," "impact," "cumulative impact," "acceleration," "constructive acceleration," "inefficiency," "interference," "indirect," "ripple" or "consequential" claims, costs or damages and all direct or

indirect costs pertaining to the Contractor's home office, branch offices, or field site office and all other costs and effects whatsoever relating to the change in the Work.

**7.4.4.2** Any statement unilaterally added by the Contractor to a Change Order or contained in any transmittal or separate correspondence wherein the Contractor unilaterally attempts to reserve rights to seek any further increases in the Contract Price and/or further extensions of the Contract Time for a change in the Work that is the subject of the Change Order and/or arising out of, related to and/or connected with the change in the Work described in the Change Order shall be null and void.

## **7.5 CONSTRUCTION CHANGE DIRECTIVES.**

**7.5.1 WHEN USED AND CONTRACTOR'S RIGHT TO CHALLENGE.** Without invalidating the Contractor's Agreement, University reserves the right to unilaterally issue, in University's sole discretion, a Construction Change Directive that requires Contractor to proceed with a change in the Work. University may order minor changes within the scope of Work without granting an adjustment in the Contract Price or an extension of the Contract Time if such minor changes within the scope of Work are consistent with the intent of the Contract Documents. In order to expedite the Work and avoid or minimize delays in the Work that may affect the Contract Price or Contract Time, the Contract Documents shall be amended as described below. If the Construction Change Directive leaves open the determination of an increase, if any, in the Contract Price and/or extension, if any, of the Contract Time related to the change in the Work, then the Construction Change Directive shall indicate the timeframe(s) in which Contractor shall provide further information to resolve such open issue(s). When University and Contractor agree upon an increase, if any, in the Contract Price and/or extension, if any, in the Contract Time related to a Construction Change Directive, the parties shall execute a Change Order. Additionally, the Construction Change Directive may be converted to a Change Order under Section 7.2.2.2 or Section 7.3.2.

**7.5.2 PROCEED WITH WORK.** Upon receipt of a Construction Change Directive, Contractor shall promptly proceed with the change in the Work involved.

**7.5.3 INTERIM PAYMENTS BY UNIVERSITY.** Pending the final determination of the increase in the Contract Price, if any, associated with a Construction Change Directive, University shall pay any undisputed amount to Contractor.

**7.6 ASI.** The A/E may at any time that is consistent with maintaining the quality, safety, time, budget, and function of the Work, issue to Contractor an ASI after approval from University is obtained.

## **7.7 PROCEDURE FOR PRELIMINARY RESOLUTION EFFORTS.**

**7.7.1 REQUEST FOR PRELIMINARY RESOLUTION EFFORT (PRE).** If Contractor wishes to raise an issue related to an alleged breach of contract by University or an issue concerning time or money, Contractor shall file a PRE as a prerequisite for any consideration of the issue by University. The labeling of the notice or request shall not preclude the consideration of the issue by University.

**7.7.2 TIME FOR FILING.** The PRE must be filed in writing with University within twenty-one (21) days of any of the following:

**7.7.2.1** Issuance of a Construction Change Directive that states the adjustment in Contract Price and/or Contract Time, if any, if Contractor disagrees with such adjustment;

**7.7.2.2** Issuance of a statement of University's position with respect to the adjustment in Contract Price and/or Contract Time, if any, in a previously issued Construction Change Directive that left open the adjustment in Contract Price and/or Contract Time, if Contractor disagrees with such statement;

**7.7.2.3** Issuance of a denial of a PCO by University;

**7.7.2.4** In the case of a Subcontractor, after the expiration of the time period for the Contractor/Subcontractor PRE process under Section 7.7.5; or

**7.7.2.5** Except as provided in Section 7.2.2, when Contractor knows or should have known about any other issue where Contractor seeks an adjustment in the Contract Price, Contract Time and/or other relief from University.

**7.7.3** **CONTENT REQUIREMENT.** The PRE shall be required to include in writing to the extent information is reasonably available at the time of filing of the PRE:

**7.7.3.1** A description of the issue;

**7.7.3.2** The potential impact on the Work, Contract Price and/or Contract Time; and

**7.7.3.3** An indication of the relief sought.

**7.7.4** **SUPPLEMENTATION.** Additional detail of the content requirement under Section 7.7.3 shall be provided later if the detail is not yet available at the initial filing as follows:

**7.7.4.1** While the issue is continuing or the impact is being determined, Contractor shall provide a written updated status report every thirty (30) days or as otherwise reasonably requested by University; and

**7.7.4.2** After the issue is concluded and/or the impact is determinable, complete information, including any impacts on Contract Price, Contract Time and/or other relief requested, if any, must be provided to University within twenty-one (21) days of the earlier of the date the issue is concluded or the impact is determinable.

**7.7.5** **SUBCONTRACTORS.** Contractor must include the provisions of this Section 7.7.5 in Contractor's subcontract with each Subcontractor and require each Subcontractor to do likewise in each Subcontractor's sub-subcontracts with Sub-subcontractors. At Contractor's discretion, Contractor may allow a Sub-subcontractor at the second tier and beyond to submit a PRE directly to Contractor.

**7.7.5.1** In order for a Subcontractor at any tier to be involved with the PRE of University, the following conditions and process shall apply:

**7.7.5.1.1** The Subcontractor must have attempted to resolve the issue with Contractor, including the submission of a PRE with Contractor.

**7.7.5.1.2** The Subcontractor must file a copy of the PRE with University;

**7.7.5.1.3** The PRE to Contractor must meet the time, content, and supplementation requirements of Sections 7.7.2, 7.7.3 and 7.7.4. The triggering event for a Subcontractor to file a PRE shall be the time at which the issue cannot be resolved through negotiation;

**7.7.5.1.4** The PRE submitted to Contractor shall only be eligible for consideration in University's PRE process to the extent the issue is reasonably related to the performance of University or an entity for which University is liable;

**7.7.5.1.5** Contractor shall resolve the PRE with the Subcontractor within sixty (60) days of its submittal to Contractor or such other time period as subsequently agreed to by the Subcontractor in writing. If Contractor

fails to resolve the PRE with the Subcontractor within such required time period, the Subcontractor may submit in writing the PRE with Contractor and University. In order to be eligible for University's consideration of the PRE, the Subcontractor must submit the PRE within twenty-one (21) days of the expiration of the time period for the Contractor/Subcontractor PRE process. University shall consider the PRE as being submitted by Contractor on behalf of the Subcontractor;

**7.7.5.1.6** Upon such PRE being submitted, Contractor shall cooperate with University in reviewing the issue;

**7.7.5.1.7** University shall not be obligated to consider any submission which is not in accordance with any provision of this Section 7.7;

**7.7.5.1.8** The Subcontractor may accompany Contractor in participating with University regarding the PRE raised by the Subcontractor. University shall not be precluded from meeting with Contractor separately, and it shall be the responsibility of Contractor to keep the Subcontractor informed of any such meetings; and

**7.7.5.1.9** Notwithstanding any provision of this Section 7.7.5, a Subcontractor shall be entitled to pursue a payment bond claim.

**7.7.6 INFORMATION AND MEETINGS.** University may request additional information and may meet with the parties involved with the issue.

**7.7.7 CONTRACTOR REQUIRED TO CONTINUE PERFORMANCE.** Pending the final resolution of the issue, unless otherwise agreed upon in writing by University, Contractor shall proceed diligently with performance of the Work and University shall continue to make payments of undisputed amounts in accordance with the Contract Documents.

**7.7.8 DECISION.** University shall issue to Contractor, and any other third party brought into the process by University as being potentially liable to University, a written decision providing the basis for the decision on the issues presented by all of the parties within thirty (30) days of receipt of all the information required under Sections 7.7.3 and 7.7.4.

**7.7.9 DECISION FINAL UNLESS CLAIM SUBMITTED.** The decision by University shall be final, and not subject to any further administrative or judicial review (not including judicial enforcement) unless a Claim is submitted in accordance with these General Conditions.

**7.7.10 EXTENSION REQUIRES MUTUAL AGREEMENT.** Any time period specified in Section 7.7 may be extended by mutual agreement of Contractor and University.

**7.7.11 IF DECISION NOT ISSUED.** If the decision is not issued within the thirty (30) day period, stated in Section 7.7.8 including any agreed to extensions, the issue may be pursued as a Claim.



## **7.7.12 PAYMENT FOR PERFORMANCE.**

**7.7.12.1** Except as otherwise provided in the Contract Documents, any final decision where University is to pay additional monies to Contractor, shall not be delayed by any PRE, Claim, or appeal by another party.

**7.7.12.2** Payment to Contractor in accordance with any final decision shall be made by University consistent with the Contract Documents.

**7.7.12.3** Notwithstanding any other provision of the Contract Documents, payment to Contractor shall be subject to any set-off, claims, or counterclaims of University.

**7.7.12.4** Payment to Contractor for a Subcontractor issue submitted by the Contractor shall be paid by Contractor to Subcontractor in accordance with the subcontract between Contractor and Subcontractor.

**7.7.12.5** Any payment or performance determined owing by Contractor to University shall be made in accordance with the Contract Documents.

## **7.8. RESOLUTION OF CLAIM.**

**7.8.1 CLAIM.** If the decision on the PRE is not issued within the required timeframe or if Contractor is not satisfied with the decision, Contractor, or other party brought into the process by University, may submit a Claim in accordance with this Section 7.8 as a prerequisite for any further consideration by University or the right to any judicial review of the issue giving rise to the Claim.

**7.8.2 SUBCONTRACTORS.** In order for a Subcontractor to have its issue considered in the Claim process by University, the Subcontractor that had its issue considered under Section 7.7.5 may submit the issue as a Claim by filing it with Contractor and University within the same timeframe and with the same content requirements as required of a Claim submitted by Contractor under this Section 7.8.2. University shall consider the Claim as being submitted by Contractor on behalf of the Subcontractor. Under no circumstances shall any provision of these General Conditions or the Contract Documents be construed so as to create any contractual relationship between University and any Subcontractor.

**7.8.2.1** Upon such Claim being submitted, the Contractor shall fully cooperate with the Director, the person(s) evaluating the claim and any subsequent reviewing authority.

**7.8.2.2** The Director shall not be obligated to consider any submission which is not in accordance with this Section 7.8.2.

**7.8.2.3** The Subcontractor may accompany Contractor in participating with the Director, the person(s) evaluating the Claim and any subsequent reviewing authority regarding the Claim. The Director, the person(s) evaluating the Claim, and any subsequent reviewing authority is not precluded from meeting with Contractor separately, and it shall be the responsibility of Contractor to keep the Subcontractor informed of any such meetings and matters discussed.

**7.8.2.4** Notwithstanding any provision of this Section 7.8, a Subcontractor shall be entitled to pursue a payment bond claim.

**7.8.3 TIME FOR FILING.** The Claim must be filed in writing promptly with the Director, but in no case more than twenty-one (21) days after the decision is issued on the PRE under Section 7.7.8 or no more than twenty-one (21) days after the thirty (30) day period under Section 7.7.11 has expired with a decision not issued.

**7.8.4 CONTENT REQUIREMENT.** The written Claim shall include:

**7.8.4.1** A description of the issues in dispute;

**7.8.4.2** The basis for the Claim, including documentation and analysis required by the Contract Documents and applicable law and rules that allow for the proper determination of the Claim;

**7.8.4.3** A detailed cost estimate for any amount sought, including copies of any related invoices; and

**7.8.4.4** A specific identification of the relief sought.

**7.8.5 EXTENSION OF TIME TO SUBMIT DOCUMENTATION.** The time period for submitting documentation and any analysis to support a Claim may be extended by the Director upon written request of the claimant showing just cause for such extension, which request must be included in the initial Claim submittal.

**7.8.6 CONTRACTOR REQUIRED TO CONTINUE PERFORMANCE.** Pending the final determination of the Claim, including any judicial review or appeal process, and unless otherwise agreed upon in writing by the Director, Contractor shall proceed diligently with performance of the Contract and University shall continue to make payments of undisputed amounts in accordance with the Contract Documents.

**7.8.7 AGREEMENT OF CLAIMANT ON METHOD AND PERSON(S) EVALUATING THE CLAIM.** The Director shall first attempt to reach agreement with the claimant on the method and person(s) to evaluate the Claim. If such agreement cannot be made within fourteen (14) days of filing of the Claim, the Director shall select the method and person(s), considering the purposes described in Rule R23-26-1. Unless agreed to by the Director and the claimant, any selected person shall not have a conflict of interest or appearance of impropriety. Any party and the person(s) evaluating the Claim has a duty to promptly raise any circumstances regarding a conflict of interest or appearance of impropriety. If such a reasonable objection is raised, and unless otherwise agreed to by the Director and the claimant, the Director shall take appropriate action to eliminate the conflict of interest or appearance of impropriety. The dispute resolution methods and person(s) may include any of the following:

**7.8.7.1** A single expert and/or hearing officer qualified in the field that is the subject of the Claim;

**7.8.7.2** An expert panel, consisting of members that are qualified in a field that is the subject of the Claim;

**7.8.7.3** An arbitration process which may be binding if agreed to by the parties to the Claim;

**7.8.7.4** A mediator; or

**7.8.7.5** Any other method that best accomplishes the purposes set forth in Rule R23-26-1.

**7.8.8 THE EVALUATION PROCESS, TIMEFRAMES OF EVALUATOR(S), DIRECTOR'S DETERMINATION, ADMINISTRATIVE APPEAL TO THE EXECUTIVE DIRECTOR AND JUDICIAL REVIEW.** The Claim shall be evaluated, the timeframe for specific events related to the person(s) evaluating the Claim, the Director's determination, any appeal to the Executive Director and any judicial review shall be subject to the provisions of Rule R23-26-5(8), R23-26-5(9), R23-26-6 and R23-26-8. A copy of these Administrative Rules is available at <https://rules.utah.gov>.

**7.8.9 APPEAL PROCESS PREREQUISITE FOR FURTHER CONSIDERATION OR JUDICIAL REVIEW.** The administrative appeal to the Executive Director is a prerequisite for any further consideration by the State of Utah, or to judicial review of the issue giving rise to the Claim. It shall be

considered that the Contractor, or another party brought into the process by University, has not exhausted its administrative remedies if such an administrative appeal is not undertaken.

#### **7.8.10 PAYMENT OF CLAIM.**

**7.8.10.1** When a stand-alone component of a Claim has received a final determination, and is no longer subject to review or appeal, that amount shall be paid in accordance with the payment provisions of the Contract Documents or judicial order.

**7.8.10.2** When the entire Claim has received a final determination, and is no longer subject to review or appeal, the full amount shall be paid within fourteen (14) days of the date of the final determination unless the Work or services have not been completed, in which case the amount shall be paid in accordance with the payment provisions of the Contract Documents to the point that the Work is completed.

**7.8.10.3** The final determination date is the earlier of the date upon which the claimant accepted the settlement in writing with an executed customary release document and waived its rights of appeal, or the expiration of the appeal period, with no appeal filed, or the determination made resulting from the final appeal.

**7.8.10.4** Any final determination where University is to pay additional monies to Contractor shall not be delayed by any appeal or request for judicial review by another party brought into the process by University as being liable to University.

**7.8.10.5** Notwithstanding any other provision of the Contract Documents, payment of all or part of a Claim shall be subject to any set-off, claims, or counterclaims of University.

**7.8.10.6** Payment to Contractor for a Subcontractor issue (Claim) deemed filed by Contractor, shall be paid by Contractor to the Subcontractor in accordance with the subcontract between Contractor and the Subcontractor.

**7.8.10.7** The execution of a customary release document by the claimant related to any payment may be required as a condition of making the payment. Unless expressly and specifically released in writing by University, settlement of a Claim by University shall not be deemed a waiver of Claims reserved under Section 8.8.3.

#### **7.8.11 ALLOCATION OF COSTS OF CLAIM RESOLUTION PROCESS.**

**7.8.11.1** In order to file a Claim, a claimant must pay a Fifteen Hundred Dollar (\$1,500.00) filing fee to University. When the Claim is a pass-through from a Subcontractor in accordance with Section 7.7.5, the payment of the fee shall be made by the Subcontractor.

**7.8.11.2** Unless otherwise agreed to by the parties to the Claim, the costs of resolving the Claim shall be allocated among the parties on the same proportionate basis as the determination of financial responsibility for the Claim.

**7.8.11.3** The costs of resolving the Claim that are subject to allocation include the claimant's filing fee, the costs of any person(s) evaluating the Claim, the costs of making any required record of the process, and any additional testing or inspection procured to investigate and/or evaluate the Claim.

**7.8.11.4** Each party shall be responsible for its own attorney fees.

**7.8.12 ALTERNATIVE PROCEDURES.** To the extent otherwise permitted by law, if all parties to a Claim agree in writing, a protocol for resolving a Claim may be used that differs from the process described in this Section 7.8.

**7.8.13 IMPACT ON FUTURE SELECTIONS.**

**7.8.13.1** The presentation of a good faith and non-frivolous issue or Claim shall not be considered by University in University's selection process for a future award of contract; and

**7.8.13.2** The submission of a bad faith and frivolous issue or Claim, or the failure by a Contractor to facilitate resolution of a Claim, may be considered in University's evaluation of performance.

**7.8.14 REPORT TO BUILDING BOARD.** University may report on the Claim to the Utah State Building Board.

**7.8.15 UNIVERSITY'S RIGHT TO HAVE ISSUES, DISPUTES OR CLAIMS CONSIDERED.** As stated in Rule R23-26-1(6), Sections 7.7 and 7.8 do not limit the right of University to have any of University's issues, disputes or claims considered. University reserves all rights to pursue University's issues, disputes or claims in law or equity including, but not limited to, any or all of the following: damages, delay damages and impacts, losses, liability, patent or latent defects, or failure to perform under the Contract Documents. If the Director appoints an expert or a panel to consider any such issue(s), dispute(s) or claim(s) of University, Contractor shall cooperate with such expert or panel process.

**ARTICLE 8. PAYMENTS AND COMPLETION.**

**8.1 SCHEDULE OF VALUES.** With the first Application for Payment, Contractor shall submit to the A/E and University a schedule of values allocated to all the various portions of the Work. The schedule of values shall be submitted on the form approved and provided by University. The schedule of values must consist of a detailed and specific breakdown of values actually associated with the various items of Work and shall in no event be "frontloaded". The A/E shall make recommendations to University regarding the schedule of values including any suggested modifications. When approved, including any approved modifications, by University, it shall be the basis for future Contractor Applications for Payment. Contractor shall be entitled to reasonably reallocate values in the schedule of values with prior written notice to University. Contractor shall not be entitled to payment until receipt and acceptance of the schedule of values.

**8.2 APPLICATIONS FOR PAYMENT.**

**8.2.1 IN GENERAL.** The following general requirements shall be met:

**8.2.1.1** Contractor shall submit to the A/E an itemized Application for Payment for Work completed in accordance with the schedule of values and that reflects retainage as provided for in the Contractor's Agreement. The Application for Payment shall be on a form approved and provided by University.

**8.2.1.2** The Application for Payment shall be supported by such data substantiating Contractor's right to payment as University or the A/E may require.

**8.2.1.3** The Application for Payment may include requests for payment pursuant to approved Change Orders or Construction Change Directives.

**8.2.1.4** The Application for Payment shall not include requests for payment for portions of the Work performed by a Subcontractor when Contractor does not intend to pay that Subcontractor because of a dispute or other reason.

**8.2.1.5** In executing the Application for Payment, Contractor shall attest that Subcontractors involved with prior Applications for Payment have been paid, unless Contractor provides a detailed explanation why such payment has not occurred. University reserves the right to require Contractor to submit a Utah Conditional Waiver and Release Upon Progress Payment form from one or more Subcontractors.

**8.2.2 PAYMENT FOR MATERIAL AND EQUIPMENT.** Unless otherwise provided in the Contract Documents, payments shall be made on account of materials and equipment delivered and suitably stored at the Work site for subsequent incorporation into the Work. If approved in advance by University and A/E, payment may similarly be made for materials and equipment suitably stored off-site at a location agreed upon in writing. Payment for materials and equipment stored on or off-site shall be conditioned upon compliance by Contractor with procedures satisfactory to University to establish University's title to such materials and equipment or otherwise protect University's interest, and shall include applicable insurance, storage, and transportation to the Work site for such materials and equipment stored off-site. University may require copies of invoices or other suitable documentation.

**8.2.3 WARRANTY OF TITLE.** Contractor warrants that title to all Work covered by an Application for Payment shall pass to University no later than the time for payment. Contractor further warrants that upon submittal of an Application for Payment, all Work for which Certificates for Payment have been previously issued and payments received from University shall, to the best of Contractor's knowledge, information, and belief, be free and clear of liens, claims, security interests, or encumbrances in favor of the Contractor, Subcontractors, or other persons or entities making a claim by reason of having provided labor, materials, and/or equipment relating to the Work.

**8.2.4 HOLDBACK BY UNIVERSITY.** Notwithstanding anything to the contrary contained in the Contract Documents, University may, as a result of the claims resolution process, withhold any payment to Contractor if and for so long as Contractor fails to perform any of its obligations under the Contract Documents or otherwise is in default under any of the Contract Documents.

### **8.3 CERTIFICATES FOR PAYMENT.**

**8.3.1 ISSUED BY A/E.** The A/E shall within seven (7) days after receipt of Contractor's Application for Payment, either issue to University a Certificate for Payment, with a copy to the Contractor, for such amount as the A/E determines due or notify Contractor and University in writing of the A/E's reasons for withholding certification in whole or in part as provided in Section 8.4.1. If the A/E fails to act within said seven (7) day period, Contractor may file the Application for Payment directly with University and University shall thereafter have twenty-one (21) days from the date of University's receipt to resolve the amount to be paid and to pay the undisputed amount. The accuracy of Contractor's Applications for Payment shall be Contractor's responsibility, not A/E's.

**8.3.2 A/E'S REPRESENTATIONS.** The A/E's issuance of a Certificate for Payment shall constitute a representation to University that to the best of the A/E's knowledge, information and belief, based upon the A/E's observations at the site, the data comprising the Application for Payment, and what is reasonably inferable from the observations and data, that the Work has progressed to the point indicated in the Application for Payment and that the quality of the Work is in accordance with the Contract Documents. The foregoing representations are subject to minor deviations from the Contract Documents correctable prior to completion and to specific qualifications expressed by the A/E. The issuance of a Certificate for Payment shall further constitute a representation that Contractor is entitled to payment in the amount certified. However, the issuance of a Certificate for Payment shall not be a representation that the A/E has: (1) made exhaustive or continuous on-site inspections to check the quality or quantity of the Work; (2) reviewed construction means, methods, techniques, sequences or procedures; (3) reviewed copies of requisitions received from Subcontractors and material suppliers and other data requested by University to substantiate Contractor's right to payment; (4)

ascertained how or for what purpose Contractor used money previously paid on account of Contract Price; or  
(5) any duty to make such inquiries.

#### **8.4 DECISIONS TO WITHHOLD CERTIFICATION.**

**8.4.1 WHEN WITHHELD.** The A/E may decide not to certify payment and may withhold a Certificate for Payment in whole or in part, to the extent reasonably necessary to protect University, if in the A/E's judgment the representations to University required in Section 8.3.2 cannot be made. If the A/E is unable to certify payment in the amount of the Application for Payment, the A/E shall notify Contractor and University as provided in Section 8.3.1. If Contractor and the A/E cannot agree on a revised amount, the A/E shall promptly issue a Certificate for Payment for the amount to which the A/E makes such representations to University. The A/E may also decide not to certify payment or, because of subsequently discovered evidence or observations, may nullify the whole or part of a Certificate for Payment previously issued, to such extent as may be necessary in the A/E's opinion to protect University from loss because of:

**8.4.1.1** Defective Work not remedied;

**8.4.1.2** Third party claims filed or reasonable evidence indicating probable filing of such claims;

**8.4.1.3** Failure of Contractor to make payments properly to Subcontractors or for labor, materials, or equipment;

**8.4.1.4** Reasonable evidence that the Work cannot be completed for the unpaid balance of the Contract Price;

**8.4.1.5** Damage to University or another contractor;

**8.4.1.6** Reasonable evidence that the Work will not be completed within the Contract Time, and that the unpaid balance of the Contract Price would not be adequate to cover actual or liquidated damages for the anticipated delay; or

**8.4.1.7** Failure to carry out the Work in accordance with the Contract Documents.

**8.4.2 CERTIFICATION ISSUED WHEN REASONS FOR WITHHOLDING REMOVED.** When the reasons stated in Section 8.4.1 for withholding certification are removed, certification shall be made for such related amounts.

**8.4.3 CONTINUE WORK EVEN IF CONTRACTOR DISPUTES A/E'S DETERMINATION.** If Contractor disputes any determination by the A/E or the result of the claims resolution process with regard to any Certification of Payment, Contractor nevertheless shall expeditiously continue to prosecute the Work.

**8.4.4 UNIVERSITY NOT IN BREACH.** University shall not be deemed to be in breach of Contractor's Agreement by reason of the withholding of any payment pursuant to any provision of the Contract Documents provided University's action or such withholding is consistent with the results of the dispute resolution process.

#### **8.5 PROGRESS PAYMENTS.**

##### **8.5.1 IN GENERAL, INTEREST OR LATE PAYMENTS.**

**8.5.1.1** Except as provided in Section 8.3.1, University shall pay any undisputed amount within twenty-eight (28) days of the date that the Application for Payment was submitted to the A/E. In no event shall University be required to pay any disputed amount.

**8.5.1.2** Except as otherwise provided by law, if any payment is late based upon the provisions of the Contract Documents, Contractor shall be paid interest at the rate stated in Utah Code § 15-6-3.

**8.5.2 CONTRACTOR AND SUBCONTRACTOR RESPONSIBILITY.** Contractor shall promptly and no later than the date established in Utah Code § 15-6-5 pay each Subcontractor, upon receipt of payment from University, out of the amount paid to Contractor on account of such Subcontractor's portion of the Work, the amount to which said Subcontractor is entitled. Contractor shall, by appropriate agreement with each Subcontractor, require each Subcontractor to make payment to its Sub-subcontractors in a similar manner.

**8.5.3 INFORMATION FURNISHED BY A/E OR UNIVERSITY TO SUBCONTRACTOR.** The A/E or University shall, on request, furnish to a Subcontractor, if practicable, information regarding percentages of completion or amounts applied for by Contractor and action taken thereon by the A/E and University on account of portions of the Work done by such Subcontractor.

**8.5.4 UNIVERSITY AND A/E NOT LIABLE.** Neither University or A/E shall have an obligation to pay, monitor, or enforce the payment of money to a Subcontractor, except to the extent as may otherwise be required by law.

**8.5.5 CERTIFICATE, PAYMENT OR USE NOT ACCEPTANCE OF DEFECTIVE WORK.** A Certificate for Payment, a progress payment, or partial or entire use or occupancy of the Work by University shall not constitute acceptance of Work that is not in accordance with the Contract Documents.

**8.6 PAYMENT UPON SUBSTANTIAL COMPLETION.** Upon Substantial Completion of the Work or designated portion thereof and upon application by Contractor and certification by the A/E, University shall make payment, reflecting adjustment in retainage, if any, for such Work or portion thereof as provided in the Contract Documents. To the extent allowed by law, University may retain until final completion up to twice the fair market value of the Work that has not been completed in accordance with the Contract Documents, or, in the absence of applicable Contract Documents, generally accepted craft standards.

**8.7 PARTIAL OCCUPANCY OR USE.**

**8.7.1 IN GENERAL.** University may occupy or use any completed or partially completed portion of the Work at any stage when such portion is designated by separate agreement with Contractor and authorized by public authorities having jurisdiction over the Work. Such partial occupancy or use may commence whether or not the portion is Substantially Complete, provided University and Contractor have accepted in writing the responsibilities assigned to each of them for payments, retainage if any, security, maintenance, heat, utilities, damage to the Work and insurance, and have agreed in writing concerning the period for correction of the Work and commencement of the warranties required by the Contract Documents. When Contractor considers a portion to be Substantially Complete, Contractor shall prepare and submit a list to the A/E as previously provided for herein. Consent of Contractor to partial occupancy or use shall not be unreasonably withheld. Contractor shall have continuing responsibility to protect the Work site and the Work during such partial occupancy or use and shall be responsible for damage except to the extent caused solely by University during such partial occupancy or use. The stage of progress of the Work shall be determined by written agreement between University and Contractor.

**8.7.2 INSPECTION.** Immediately prior to such partial occupancy or use, University, Contractor and A/E shall jointly inspect the area to be occupied or portion of the Work to be used in order to determine and record the condition of the Work.

**8.7.3 NOT CONSTITUTE ACCEPTANCE.** Except to the extent it is agreed upon in writing by University, partial occupancy or use of a portion of the Work shall not constitute acceptance of Work not complying with the requirements of the Contract Documents.

**8.7.4 INSURANCE.** Partial occupancy or use shall not commence until the insurance company or companies providing property insurance under Section 10.2 have provided any required consent to such partial occupancy or use by endorsement or otherwise. University shall take reasonable steps to obtain any required consent of the insurance company or companies and shall, without mutual written consent, take no action with respect to partial occupancy or use that would cause cancellation, lapse or reduction of insurance.

## **8.8 FINAL PAYMENT.**

**8.8.1 CERTIFICATE FOR PAYMENT.** The A/E's final Certificate for Payment shall constitute a further representation that the conditions listed in Section 8.8.2 as precedent to Contractor's being entitled to final payment have been fulfilled.

**8.8.2 CONDITIONS FOR FINAL PAYMENT.** Neither final payment nor any remaining retained percentage shall become due until Contractor submits to the A/E the following to the extent required by University:

**8.8.2.1** An affidavit that payrolls, bills for material and equipment, and other indebtedness connected with the Work (less amounts withheld by University) have been paid or otherwise satisfied;

**8.8.2.2** A current or additional certificate evidencing that insurance required by the Contract Documents to remain in force after final payment is currently in effect and shall not be canceled or allowed to expire until at least twenty-eight (28) days prior written notice, by certified mail, return receipt requested, has been given to University;

**8.8.2.3** A written statement that Contractor knows of no reason that the insurance shall not be renewable to cover the period required by the Contract Documents;

**8.8.2.4** If requested by the surety in a timely manner or by University, consent of surety, to final payment;

**8.8.2.5** Receipt of Record Drawings, Specifications, Addenda, Change Orders and other Modifications maintained at the site; the warranties, instructions, operation and maintenance manuals, and training videos required to be furnished by the Contract Documents;

**8.8.2.6** Other data establishing payment or satisfaction of obligations, such as a Utah Waiver and Release Upon Final Payment form from Contractor, Subcontractors and Sub-subcontractors, receipts, other releases and waivers of liens, claims, security interests, or encumbrances arising out of Contractor's Agreement, to the extent and in such form as may be designated by University. If a Subcontractor or Sub-subcontractor refuses to furnish a release or waiver required by University, University may require consent of surety to the final payment. If liens, claims, security interests, or encumbrances remain unsatisfied after payments are made, Contractor shall refund to University all money that University may be compelled to pay in discharging such liens, claims, security interests or encumbrances including all costs and reasonable attorney fees; and

**8.8.2.7** A written statement demonstrating how Contractor shall distribute interest earned on retention to Subcontractors as required by Utah Code § 13-8-5.

**8.8.3 WAIVER OF CLAIMS: FINAL PAYMENT.** The making of final payment shall constitute a waiver of Claims by University, except those arising from:



**8.8.3.1** Liens, Claims, security interests, or encumbrances arising out of the Contract Documents and unsettled;

**8.8.3.2** Failure of the Work to comply with the requirements of the Contract Documents;

**8.8.3.3** Terms of warranties required by the Contract Documents; or

**8.8.3.4** Claims arising within the one-year period for correction of the Work and Claims to the extent not barred by Utah Code § 78B-2-225 and/or Utah Code § 78B-4-513.

**8.8.4 DELAYS NOT CONTRACTOR'S FAULT.** If, after Substantial Completion of the Work, Final Completion is materially delayed through no fault of Contractor or by issuance of Change Orders affecting final completion, University shall, upon application by Contractor and certification by the A/E, and without terminating Contractor's Agreement, make payment of the balance due for that portion of the Work fully completed and accepted. Such payment shall be made under terms and conditions governing final payment. Unless otherwise stated by University in writing, the making of final payment shall constitute a waiver of claims by University as provided in Section 8.8.3 for that portion of that Work fully completed and accepted by University.

**8.8.5 WAIVER BY ACCEPTING FINAL PAYMENT.** Acceptance of final payment by Contractor or a Subcontractor shall constitute a waiver of Claims by that payee except those Claims previously made in writing and identified by that payee as unsettled at the time of final Application for Payment.

## **ARTICLE 9. TESTS AND INSPECTIONS, SUBSTANTIAL AND FINAL COMPLETION, UNCOVERING, CORRECTION OF WORK AND GUARANTY PERIOD.**

### **9.1 TESTS AND INSPECTIONS.**

**9.1.1 IN GENERAL.** Tests, inspections, and approvals of portions of the Work required by the Contract Documents or by laws, rules, regulations, or orders of public authorities having jurisdiction shall be made at an appropriate time. Unless otherwise specifically set forth in the Contract Documents or agreed to by University in writing, University shall contract for such tests, inspections, and approvals with an independent entity, or with the appropriate public authority, and University shall bear all related costs of tests, inspections, and approvals, except as provided below. If any of the Work is required to be inspected or approved by the terms of the Contract Documents or by any public authority, Contractor shall, at least two (2) working days prior to the time of the desired inspection, and following the procedures established by University, request such inspection or approval to be performed. Contractor shall give the A/E timely notice of when and where tests and inspections are to be made so that the A/E may observe such procedures.

**9.1.2 FAILURE OF AN INSPECTOR TO APPEAR.** Work shall not proceed without any required inspection and the associated authorization by University to proceed unless the following procedures and requirements have been met:

**9.1.2.1** The inspection or approval was requested in a timely manner as provided in Section 9.1.1;

**9.1.2.2** Contractor received written confirmation from the inspection entity that the inspection was scheduled;

**9.1.2.3** Contractor has contacted or attempted to contact the inspector to confirm whether the inspector is able to perform the inspection as scheduled;

**9.1.2.4** If the inspector informs Contractor that the inspector is unable to perform the inspection as scheduled or if Contractor is unable to contact the inspector, Contractor shall attempt to contact the A/E or University for instruction; and

**9.1.2.5** Contractor has documented the condition of the Work prior to being covered through photos or other means.

**9.1.3 NONCONFORMING WORK.** If procedures for testing, inspection, or approval under Section 9.1.1 reveal failure of portions of the Work to comply with the requirements established by the Contract Documents, Contractor shall bear all costs made necessary by such failure including those of repeated procedures and compensation for University's expenses, including the cost of retesting for verification of compliance if necessary, until University accepts the Work in question as complying with the requirements of the Contract Documents.

**9.1.4 CERTIFICATES.** Required certificates of testing, inspection, or approval shall, unless otherwise required by the Contract Documents, be secured by Contractor and promptly delivered to the A/E.

**9.1.5 A/E OBSERVING.** If the A/E is to observe tests, inspections, or approvals required by the Contract Documents, the A/E shall do so with reasonable promptness and, where practicable, at the normal place of testing.

**9.1.6 PROMPTNESS.** Tests, inspections, and arrangements for approvals conducted pursuant to the Contract Documents shall be made promptly to avoid delay in the Work.

## **9.2 UNCOVERING OF WORK.**

**9.2.1 UNCOVER UNINSPECTED WORK.** Except as provided in Section 9.2.3, if a portion of the Work is covered prior to an inspector's approval to proceed, it must be uncovered for the inspector's inspection and be replaced at Contractor's expense without change in the Contract Price and/or Contract Time.

**9.2.2 OBSERVATION PRIOR TO COVERING.** Except as provided in Section 9.2.3, if University or the A/E has requested in writing to observe conditions prior to any Work being covered or if such observation is required by the Contract Documents, and the Work is covered without such observation, Contractor shall be required to uncover and appropriately replace the Work at Contractor's expense without change in the Contract Price and/or Contract Time. If Contractor requests an inspection and University or the A/E, including any inspector of each, does not appear, Contractor shall immediately notify University of such failure to appear, but shall not cover the Work without such inspection.

**9.2.3 WHEN AN INSPECTOR FAILS TO APPEAR OR A/E OR UNIVERSITY DID NOT MAKE PRIOR REQUEST.** If Work is performed by Contractor without an inspection as provided in Section 9.1.2 or if a portion of the Work has been covered which the A/E or University has not specifically requested to observe prior to its being covered or such observation is not required by the Contract Documents, the A/E or University may request to see such Work and it shall be uncovered by Contractor. If such Work is in accordance with the Contract Documents, costs of uncovering and replacement, shall, by appropriate Change Order, be charged to University. If such Work is not in accordance with the Contract Documents, Contractor shall pay such costs unless the condition was caused by University or a separate contractor in which event University shall be responsible for payment of such costs.

### **9.3 INSPECTIONS: SUBSTANTIAL AND FINAL.**

**9.3.1 SUBSTANTIAL COMPLETION INSPECTION.** Prior to requesting a Substantial Completion inspection, Contractor shall prepare a comprehensive initial punchlist, including unresolved items from prior inspections, for review by University and the A/E to determine if the Work is ready for a Substantial Completion inspection. If University and A/E determine that the initial punchlist indicates that the Work is not Substantially Complete, the initial punchlist shall be returned to Contractor with written comments. If University and A/E determines that the initial punchlist indicates that the Work may be Substantially Complete, the A/E shall promptly organize and perform a Substantial Completion inspection in the presence of University and all appropriate authorities.

**9.3.1.1** If the A/E reasonably determines that the initial punchlist prepared by Contractor substantially understates the amount of the Work remaining to be completed and the Work is not Substantially Complete, the A/E shall report this promptly to University, and upon concurrence of University, Contractor shall be assessed the costs of the inspection and punchlist review incurred by the A/E and University.

**9.3.1.2** When the Work or designated portion thereof is Substantially Complete, the A/E shall prepare a Certificate of Substantial Completion which shall establish the date of Substantial Completion; shall establish responsibilities of University and Contractor for security, maintenance, heat, utilities, damage to the Work, and insurance; and shall fix the time within which Contractor shall finish all items on the punchlist accompanying the Certificate ("Punchlist Completion Date"). The Certificate of Substantial Completion shall require approval by University. If there is a punchlist, Contractor shall proceed promptly to complete and correct items on the punchlist. Failure to include an item on the punchlist does not alter the responsibility of Contractor to complete all Work in accordance with the Contract Documents.

**9.3.1.3** Warranties required by the Contract Documents shall commence on the date of Substantial Completion of the Work or designated portion thereof except to the extent as provided otherwise in the Contract Documents or if such warranty is related to an item where the Work is not complete. Written warranties shall state the length of the warranty, which must comply with the Contract Documents.

**9.3.1.4** The Certificate of Substantial Completion shall be submitted by the A/E to University and Contractor for their written acceptance of responsibilities assigned to them in such Certificate.

**9.3.1.5** Except to the extent University otherwise approves in advance and in writing, Contractor shall submit the following documents in order to achieve Substantial Completion: written warranties, guarantees, operation and maintenance manuals, and all complete as-built drawings. Contractor shall also provide or obtain any required approvals for occupancy. Contractor shall be responsible for the guaranty of all Work, whether performed by it or by its Subcontractors and Sub-subcontractors at any tier.

**9.3.2 FINAL COMPLETION INSPECTION.** Prior to requesting a final inspection, Contractor shall verify all punchlist items are corrected and completed. Once all punchlist items are corrected and completed, Contractor shall notify University and request a final inspection. University shall notify the A/E and perform a final inspection. When all punchlist items are completed, a final Application for Payment shall be provided by Contractor, certified by the A/E, and processed by University.

**9.3.3 PUNCHLIST COMPLETION.** As compensation to University for administrative costs incurred by University as a result of delay in final project close-out, for each day subsequent to the Punchlist Completion Date that Contractor fails to complete the punchlist and subject to Section 8.8.4, Contractor shall pay to University five percent (5%) of the liquidated damages amount stated in the Contractor's Agreement.

## **9.4 CORRECTION OF WORK AND GUARANTY PERIOD.**

**9.4.1 CONTRACTOR CORRECT THE WORK.** Contractor shall correct Work rejected by the A/E, an inspector or University, or failing to conform to the requirements of the Contract Documents, whether observed before or after Substantial Completion and whether or not fabricated, installed or completed. Contractor shall bear the costs of correcting such rejected Work, including additional testing and inspections and compensation for the A/E's and inspector's services and expenses made necessary thereby.

**9.4.2 GUARANTY AND CORRECTION AFTER SUBSTANTIAL COMPLETION.** If within one year after the date of Substantial Completion of the Work or designated portion thereof, or after the date for commencement of warranties established under Section 9.2.1 or by terms of an applicable special warranty or guaranty required by the Contract Documents, any of the Work is found not to be in accordance with the requirements of the Contract Documents, including failure to perform for its intended purpose, Contractor shall correct it promptly after receipt of written notice from University to do so, unless University has previously given Contractor a written acceptance of such condition. The period of one year shall be extended with respect to portions of the Work first performed after Substantial Completion by the period of time between Substantial Completion and the actual performance of the Work. This obligation of Contractor under this Section 9.4.2 shall be operative notwithstanding the acceptance of the Work under the Contract Documents, the issuance of a final certificate of payment, partial or total occupancy and/or termination of Contractor's Agreement. University shall give notice of observed defects with reasonable promptness; however, failure to give such notice shall not relieve Contractor of its obligation to correct the Work. All corrected Work shall be subject to a one-year guaranty period the same in all respects as the original Work, except that such guaranty period shall commence from the time of Substantial Completion of the corrected Work. This guaranty period does not affect University's right to pursue any available remedies against Contractor, including, but not limited to, University's right to pursue a cause of action for defective construction against Contractor within the time period established by Utah Code § 78B-2-225.

## **9.4.3 REMOVAL OF WORK.**

**9.4.3.1** Contractor shall promptly remove from the Work site all Work that University and/or the A/E determines as being in nonconformance with the Contract Documents, whether incorporated or not.

**9.4.3.2** Contractor shall promptly replace and re-execute any Work not in accordance with the Contract Documents without change in the Contract Price and/or Contract Time.

**9.4.3.3** Contractor shall bear the expense of correcting destroyed or damaged construction, whether completed or partially completed, by University or separate contractors destroyed or damaged by such removal or replacement.

**9.4.3.4** If Contractor does not remove such rejected Work within a reasonable time, fixed by written notice, University may have the Work removed and stored at the expense of Contractor.

**9.4.3.5** If Contractor does not correct the nonconforming Work within a reasonable time, fixed by written notice, University may correct it in accordance with Section 2.2.2 of these General Conditions.

**9.4.4 NOT LIMIT OTHER OBLIGATIONS.** Nothing contained in this Section 9.4 shall be construed to establish a period of limitation with respect to other obligations that Contractor may have under the Contract Documents. Establishment of the time period of one year as described in Section 9.4.2 relates only to the specific obligation of Contractor to correct the Work, and has no relationship to the time within which the obligation to comply with the Contract Documents may be sought to be enforced, nor to the time within which proceedings may be commenced to establish Contractor's liability with respect to Contractor's obligations other than specifically to correct the Work.

## **9.5 ADDITIONAL WARRANTIES.**

**9.5.1 IN GENERAL.** In addition to any other provisions of this Article 9, the following warranties shall apply:

**9.5.1.1** Contractor warrants to University that materials and equipment furnished under the Contract Documents shall be of good quality and new, except to the extent otherwise required or expressly permitted by the Contract Documents.

**9.5.1.2** Contractor also warrants to University that the Work shall be free from defects not inherent in the quality required or expressly permitted and that the Work shall conform with the requirements of the Contract Documents. Work not conforming to said requirements, including substitutions not implemented by Change Order, Construction Change Directive, or ASI as provided in Article 7, may be considered defective at University's option.

**9.5.2 EXCLUSION.** Unless due to the negligent or intentional act or omission of Contractor or those under the Contractor's control, or as otherwise stated in the Contract Documents, Contractor's guaranty excludes remedy for damage or defect caused by abuse, modifications not executed by Contractor, improper or insufficient maintenance, improper operation, or normal wear and tear under normal usage.

**9.5.3 FURNISH EVIDENCE ON REQUEST.** If requested by the A/E or University, Contractor shall furnish satisfactory evidence as to the type and quality of materials and equipment.

**9.6 ACCEPTANCE OF NONCONFORMING WORK.** If University prefers to accept Work that is not in accordance with the requirements of the Contract Documents, University may do so in writing instead of requiring its removal and correction, in which case the Contract Price shall be reduced as appropriate. Such adjustment shall be effectuated whether or not final payment has been made.

## **ARTICLE 10. INSURANCE AND BONDS.**

### **10.1 CONTRACTOR'S LIABILITY INSURANCE.**

**10.1.1 IN GENERAL.** The Contractor shall purchase and maintain in a company or companies lawfully authorized to do business in the State of Utah such insurance as will protect the Contractor from claims set forth below which may arise out of or result from the Contractor's operations and completed operations under the Contract and for which Contractor may be legally liable, whether such operations be by the Contractor or by a Subcontractor or by a Sub-subcontractor or anyone directly employed by them, or by anyone for whose acts they may be liable:

**10.1.1.1** Claims under workers' compensation, disability benefit and other similar employee benefit acts that are applicable to the Work to be performed;

**10.1.1.2** Claims for damages because of bodily injury, occupational sickness or disease, or death of the Contractor's employees;

**10.1.1.3** Claims for damages because of bodily injury, sickness or disease, or death of any person other than the Contractor's employees;

**10.1.1.4** Claims for damages insured by usual personal injury liability coverage;

**10.1.1.5** Claims for damages, other than to the Work itself, because of injury to or destruction of tangible property, including loss of use resulting therefrom;

**10.1.1.6** Claims for damages because of bodily injury, death of a person or property damage arising out of ownership, maintenance or use of a motor vehicle;

**10.1.1.7** Claims for bodily injury or property damage arising out of completed operations;

**10.1.1.8** Claims involving contractual liability insurance applicable to the Contractor's obligations under Section 4.12; and

**10.1.1.9** If the Contract Documents require the Contractor to provide and/or the Contractor provides professional services, claims for damages because of negligent errors or omissions in the performance of professional services.

**10.1.2 COVERAGE.** Without limiting Contractor's obligations or liabilities hereunder, the Contractor shall, at its sole expense, purchase and maintain the following insurance coverages required by Section 10.1.1 of these General Conditions from insurers authorized to do business in the state of Utah and rated "A-" or better with a financial size category of class VII or larger by the A.M. Best Company. The following insurance coverages required by Section 10.1.1 of these General Conditions shall be procured with the following terms and insurance limits unless otherwise agreed in writing by University and the Contractor:

**10.1.2.1** Commercial General Liability Insurance covering all liabilities for personal injury and property damage arising in connection with the Work, with limits of liability of Five Million Dollars (\$5,000,000.00) per each occurrence and in the aggregate.

**10.1.2.2** Workers Compensation Insurance in compliance with all applicable laws of each jurisdiction in which the Work will be performed.

**10.1.2.3** Employers Liability Insurance covering all liabilities for personal injuries of the Contractor's employees, with limits of liability of Five Million Dollars (\$5,000,000.00) for each occurrence and in the aggregate.

**10.1.2.4** If the Contract Documents require the Contractor to provide and/or the Contractor provides professional services, Professional Liability Insurance with limits of liability of Two Million Dollars (\$2,000,000.00) for each claim and in the aggregate with a retroactive or effective date not later than the effective date of the Contractor's Agreement and with a deductible or self-insured retention of not greater than One Hundred Thousand Dollars (\$100,000.00) per claim.

**10.1.2.5** Automobile Liability Insurance, including coverages of owned, non-owned and hired vehicles covering all liabilities for personal injury and property damage arising from the use of motor vehicles, with combined single limits of liability of Two Million Dollars (\$2,000,000.00) for each occurrence and in the aggregate.

**10.1.2.6** If the Contractor is unable to obtain the insurance required by this Section 10.1, Contractor may carry excess liability insurance and/or umbrella insurance that, when combined with Contractor's primary coverage in a given category of insurance, brings the total coverage in such category to be not less than the amount required by this Section 10.1 for that category of insurance.

**10.1.3 ENDORSEMENTS.** The Contractor shall provide the following coverage endorsements for each category of insurance required by this Section 10.1, except in the case of Workers' Compensation Insurance, Employers' Liability Insurance and Professional Liability Insurance:

**10.1.3.1** An endorsement including University as an additional insured;

**10.1.3.2** An endorsement including a cross liability clause, noting that each of the parties comprising the insured shall be considered as a separate entity, the insurance applies as if a separate policy has been issued to each party, and no “insured-versus-insured” exclusion exists in the policy.

**10.1.3.3** An endorsement waiving all expressed or implied rights of subrogation against University and the State of Utah.

**10.1.4 TERMS.** Except as otherwise expressly provided in Section 10.1.2, the insurance of the Contractor required to be maintained pursuant to this Section 10.1 shall be on the following terms:

**10.1.4.1** All insurance shall begin no later than the effective date of the Contractor’s Agreement and shall continue until the final completion of the Work and for a period of two (2) years following the final completion of the Work, provided, however, if the Contractor’s Agreement is terminated prior to the final completion of the Work, such insurance shall continue for a period of two (2) years following the termination of the Contractor’s Agreement.

**10.1.4.2** Before performing any of the Work and after each time the policies are renewed or varied, the Contractor shall provide to University certificates of insurance and endorsements consistent with this Section 10.1.4 and Sections 10.1.1, 10.1.2 and 10.1.3 of these General Conditions. If required by University the Contractor shall deliver copies of the insurance policies providing the insurance coverages required by this Section 10.1, and all endorsements thereto.

**10.1.4.3** All insurance shall not be varied to the detriment of University, cancelled or allowed to lapse until thirty (30) days’ prior written notice has been given to University.

**10.1.5 FAILURE TO PROVIDE.** Should the Contractor at any time neglect or refuse to provide the insurance required by this Section 10.1, or should such insurance be canceled, University shall have the right, but not the obligation, to procure the same at the cost and expense of the Contractor, and the cost thereof may be deducted by University from any monies then due or thereafter to become due to the Contractor. If University or the other Indemnified Parties are damaged by the failure of the Contractor to purchase or maintain insurance as required by this Section 10.1, the Contractor shall bear all reasonable costs, expenses and damages incurred by University and/or the other Indemnified Parties arising from such failure to purchase or maintain the insurance required by this Section 10.1.

**10.1.6 CERTIFICATES.** The acceptance of delivery of any Certificates of Insurance or copies of insurance policies required to be purchased and maintained pursuant to the Contract Documents does not constitute approval or agreement by the recipient that the insurance requirements have been met or that those Certificates of Insurance or insurance policies comply with the Contract Documents.

**10.1.7 NO LIMITATION.** The Contractor shall procure such insurance coverages and such insurance limits for its insurance coverages that the Contractor, in its sole discretion, after consultation with its insurance and risk advisors, determines to be sufficient for Contractor’s purposes given the risks of the project. This Section 10.1 sets forth University’s minimum insurance requirements; the Contractor may procure additional or broader insurance coverages or greater insurance limits than required by Section 10.1 at Contractor’s expense. Nothing in Section 10.1 or elsewhere in the Contract Documents is intended to limit the Contractor’s liability to University or the Indemnified Parties to liabilities covered by the insurance coverages required by Section 10.1 or to the minimum insurance limits required of such insurance coverages by Section 10.1.

## **10.2 “BUILDER’S RISK” INSURANCE.**

**10.2.1 IN GENERAL.** Provided that the Contractor’s Agreement is for new buildings, structures, or construction projects, or for the alteration or repair of, or addition to existing buildings, structures, or improvements (an “Eligible Project”), University shall maintain insurance to protect the interest of the Contractor, Subcontractors, or Sub-subcontractors subject to all of the terms, conditions, limitations, exclusions, waivers and/or endorsements stated in the Commercial Property Policy Declarations and Scheduled Forms available on DFCM’s website, [dfcm.utah.gov](http://dfcm.utah.gov) (“Builder’s Risk Insurance”).

**10.2.2 DEDUCTIBLE.** To the extent that the Builder’s Risk Insurance provides for a deductible (including, without limitation, a specific loss deductible, cumulative loss deductible and/or sub-deductible), with respect to any damages or losses to property covered by the Builder’s Risk Insurance caused in whole or in part by the negligence, breach of contractual duty or other fault of University (or those for whom University is responsible, including the A/E and the A/E’s consultants) or the Contractor (or those for whom the Contractor is responsible, including the Contractor’s Subcontractors and Sub-subcontractors of any tier), any deductible applicable to such covered damages or losses to property shall be paid by the party, whether University or the Contractor, legally responsible for the negligence, breach of contractual duty or other fault that caused the losses or damages. If both University and the Contractor are legally responsible in part for the negligence, breach of contractual duty or other fault that caused such losses or damages to property, University and the Contractor shall pay any deductible applicable to such covered damages or losses to property in proportion to their comparative fault. With respect to any damages or losses to property covered by the Builder’s Risk Insurance caused by an act of nature, such as the weather or other natural disasters, and not caused in whole or in part by the negligence, breach of contractual duty or other fault of University (or those for whom University is responsible, including the A/E and the A/E’s consultants) or the Contractor (or those for whom the Contractor is responsible, including the Contractor’s Subcontractors and Sub-subcontractors of any tier), University and Contractor shall each pay half of the amount of any deductible to such covered damages or losses to property.

**10.2.3 WAIVER OF SUBROGATION.** University and Contractor waive all rights against: (1) each other and the other Indemnified Parties and any of their subcontractors, sub-subcontractors, agents and employees, each of the other; and (2) the A/E, A/E’s consultants, separate contractors described in Section 2.2, if any, and any of their subcontractors, sub-subcontractors, agents and employees, for damages caused by fire or other causes of loss to the extent covered by Builder’s Risk Insurance obtained pursuant to Section 10.2.1 and maintained during the course of construction, but only to the extent of the actual recovery of insurance proceeds by the injured party, except such rights as they have to proceeds of such insurance held by University as fiduciary. University or Contractor, as appropriate, shall require of the A/E, A/E’s consultants, separate contractors described in Section 2.2, if any, and the subcontractors, sub-subcontractors, agents and employees of any of them, by appropriate agreements, written where legally required for validity, similar waivers each in favor of other parties enumerated herein. The policies shall provide such waivers of subrogation by endorsement or otherwise. A waiver of subrogation shall be effective as to a person or entity even though that person or entity would otherwise have a duty of indemnification, contractual or otherwise, did not pay the insurance premium directly or indirectly, and whether or not the person or entity had an insurable interest in the property damaged. The waiver of rights under this Section 10.2.3 shall not include: (1) subject to Section 10.2.2, the right to recover amounts deducted or excluded from the insurance proceeds in the form of deductibles paid by the injured party; and (2) claims arising out of design errors or omissions.

**10.2.4 SPECIAL HAZARDS.** If the Contractor’s Agreement is for an Eligible Project, but Contractor desires insurance coverage for risks other than those covered by the Builder’s Risk Insurance, the Contractor may obtain such insurance, however, the cost thereof shall be borne by the Contractor and shall not be included in the Contract Price.

**10.2.5 NON-ELIGIBLE PROJECTS.** If the Contractor’s Agreement is not for an Eligible Project, Contractor shall bear the risk of damage and/or loss to Contractor’s materials, equipment and other property,



until acceptance of the Work by University in writing, and no protection from damage and/or loss of the Work (including, without limitation, so called “builders risk”, “course of construction”, “inland marine” and/or similar property insurance) will be provided by University for the protection of Contractor. Contractor may obtain insurance to cover such risks, however, the cost thereof shall be borne by the Contractor and shall not be included in the Contract Price. Section 10.2.3 shall not apply to Non-Eligible Projects.

**10.3 PERFORMANCE BOND AND PAYMENT BOND.** The Contractor shall furnish a Performance and Payment Bond naming the Contractor as Principal and University and University’s designees as Obligees written on AIA Document A312 (2010) Performance Bond and Labor and Material Payment Bond forms in a penal sum of not less than the Contract Price for the Work as the Contract Price may be modified by Change Order (the “Bonds”). The cost of the Bonds, without mark-up, may be included in the Contract Price. The Contractor shall deliver the Bonds to University at least three (3) days before the commencement of any Work at the Work site. Delivery of the Bonds may be accomplished *via* email. The Bonds shall be procured from a surety authorized to do business in the State of Utah and rated A- or better by the A.M. Best Company at the time of issuance of the Bonds and holding Certificates of Authority as an acceptable surety on federal bonds as listed by the United States Department of Treasury (Circular 570, as amended) in its most recent list at the time of issuance of the Bonds. The penal sum of the Bonds shall be within the maximum specified for such surety in Circular 570, as amended. The attorney-in-fact who executes the Bonds on behalf of the surety shall affix to the Bonds a certified and current copy of his or her power of attorney. If the surety on any of the Bonds furnished by the Contractor is declared a bankrupt or becomes insolvent or its rights to do business are terminated in the State of Utah or it ceases to meet the requirements of this Section 10.3, the Contractor shall within ten (10) calendar days thereafter substitute another bond and surety, both of which must be acceptable to University. Upon the request of any person or entity appearing to be a potential beneficiary of bonds covering payment of obligations arising under the Contract, the Contractor shall promptly furnish a copy of the bonds or shall authorize a copy to be furnished.

## **ARTICLE 11. MISCELLANEOUS PROVISIONS.**

**11.1 A/E’S RESPONSIBILITIES.** These General Conditions are not intended to provide an exhaustive or complete list of the A/E’s responsibilities. A separate agreement between University and the A/E incorporates these General Conditions by reference and includes additional design and contract administration responsibilities.

**11.2 SUCCESSORS AND ASSIGNS.** University and Contractor respectively bind themselves, their partners, successors, assigns and legal representatives to the other party hereto and to partners, successors, assigns and legal representatives of such other party in respect to covenants, agreements and obligations contained in the Contract Documents. Contractor shall not assign Contractor’s Agreement without the prior written consent of University, nor shall Contractor assign any amount due or to become due or any of Contractor’s rights under the Contract Documents, without prior written consent of University.

### **11.3 WRITTEN NOTICE.**

**11.3.1 PERSONAL DELIVERY AND REGISTERED OR CERTIFIED MAIL.** Written notice shall be deemed to have been duly served if delivered in person to the individual or a member of the firm or entity or to an officer of the corporation for which it was intended, or if delivered at or sent by registered or certified mail, return receipt requested, to the last business address known to the party giving notice.

**11.3.2 E-MAIL.** Notwithstanding any other provision of these General Conditions, written notice shall also be deemed to have been duly served by verified use of an e-mail system by using the known and operative e-mail address of the intended recipient. Service by use of the e-mail system is encouraged when timely notice shall benefit University, the A/E, or Contractor. Notice shall be considered complete and verified upon the sending and confirmation of delivery using the e-mail system, if on the same day notice is also sent by registered

or certified mail, return receipt requested, to the last business address known to the party giving notice, confirming the e-mail delivery.

#### **11.4 RIGHTS AND REMEDIES.**

**11.4.1 NOT LIMIT.** Duties and obligations imposed by the Contract Documents and rights and remedies available thereunder shall be in addition to and not a limitation of duties, obligations, rights, and remedies otherwise imposed or available by law.

**11.4.2 NO WAIVER.** Except as expressly provided elsewhere in the Contract Documents, no action or failure to act by University, the A/E, or Contractor shall constitute a waiver of a right or duty afforded them under the Contract Documents, nor shall such action or failure to act constitute approval or acquiescence in a breach thereunder, except as any of the above may be specifically agreed to in writing. In no case shall Contractor or any Subcontractors be entitled to rely upon any waiver of any of these General Conditions, unless agreed to in writing by University.

**11.5 NO DISCRIMINATION, NO SEXUAL HARASSMENT.** Pursuant to the laws of the United States and the State of Utah, Contractor, Subcontractors, or anyone for whose act any of them may be liable, shall take affirmative action to not discriminate against any employee or applicant for employment because of race, creed, color, sex, religion, ancestry or national origin. To the extent applicable, said persons shall comply with all provisions of Executive Order No. 11246 dated September 24, 1965 and rules, regulations, orders, instructions, designations and other directives promulgated pursuant thereto. Contractor, Subcontractors, or anyone for whose act any of them may be liable, shall not act in any manner as would violate the laws, regulations, and policies of the United States or the State of Utah prohibiting sexual harassment.

**11.6 APPLICABLE LAWS AND ENFORCEMENT.** The Contract Documents shall be governed by and construed in accordance with the laws of the State of Utah, excluding any choice of law provisions that would otherwise require application of laws of any other jurisdiction.

**11.7 INTERPRETATION.** In the interest of brevity, the Contract Documents frequently omit modifying words such as “all” and “any” and articles such as “the” and “an”, but the fact that a modification or an article is absent from one statement and appears in another is not intended to affect the interpretation of either statement.

**11.8 VENUE.** In case of any dispute that may arise under the Contract Documents, the place of venue shall be in the County of Salt Lake, State of Utah, unless otherwise agreed to by all of the parties in writing.

**11.9 SEVERABILITY.** The invalidity of any provision or part of a provision of the Contract Documents shall not impair or affect in any manner the validity, enforceability, or effect of the remainder of the Contract Documents.

**11.10 CONSTRUCTION OF WORDS.** Unless otherwise stated in the Contract Documents, words which have well-known technical or construction industry meanings shall be construed as having such recognized meanings. Unless the context requires otherwise, all other technical words shall be construed in accordance with the meaning normally established by the particular, applicable profession or industry. All other words, unless the context requires otherwise, shall be construed with an ordinary, plain meaning.

**11.11 NO THIRD-PARTY RIGHTS.** These General Conditions create rights and duties only as between University and Contractor, and University and A/E. Nothing contained herein shall be deemed as creating third party beneficiary contract rights or other actionable rights or duties as between Contractor and A/E, or as between University, Contractor, or A/E on the one hand, and any other person or entity.

## **ARTICLE 12. TERMINATION OR SUSPENSION OF THE CONTRACT.**

### **12.1 TERMINATION BY CONTRACTOR FOR CAUSE.**

**12.1.1 IN GENERAL.** If the Work is stopped for a period of sixty (60) days through no act or fault of the Contractor or a Subcontractor, or their agents or employees or any other persons performing portions of the Work under contract with any of the above, the Contractor may terminate the Contractor's Agreement in accordance with Section 12.1.2 for any of the following reasons:

**12.1.1.1** Because University has persistently failed to fulfill material obligations of University under the Contract Documents with respect to matters important to the progress of the Work;

**12.1.1.2** Issuance of an order of a court or other public authority having jurisdiction which necessitates such termination, except that where the Contractor has standing, the Contractor must cooperate in efforts to stay and/or appeal such order;

**12.1.1.3** An act of government, such as a declaration of national emergency, making material unavailable; or

**12.1.1.4** Unavoidable casualties or other similar causes.

**12.1.2 NOTICE.** If one of the reasons for termination in Section 12.1.1 exists, the Contractor may, upon fourteen (14) additional days' written notice to University and A/E, and such condition giving cause for termination still not cured, terminate Contractor's Agreement and recover from University payment for Work properly executed as of the date of termination, including profit and overhead on Work properly completed as of the date of termination, on a percentage completion basis, along with Contractor's reasonable demobilization expenses incurred within seven (7) days of termination, but Contractor shall in no event be entitled to recover consequential damages as a result of such termination or profit and/or overhead on the Work not executed.

### **12.2 TERMINATION BY UNIVERSITY FOR CAUSE.**

**12.2.1 IN GENERAL.** University may terminate the Contractor's Agreement if Contractor fails to cure any of the following within a period of seven (7) days (or longer if University so approves in writing) after receipt of notice from University specifying the breach or failure:

**12.2.1.1** Contractor refuses or fails to supply enough properly skilled workers or proper materials;

**12.2.1.2** Contractor fails to make payment to Subcontractors for materials, equipment, or labor;

**12.2.1.3** Contractor disregards laws, ordinances, rules, regulations, or orders of a public authority having jurisdiction;

**12.2.1.4** Contractor fails to perform the Work such that the Work will be Substantially Completed within the Contract Time or Contractor fails to make progress with the Work as required by the Contract Documents;

**12.2.1.5** Contractor fails to perform the Work in accordance with the Contract Documents or is otherwise in breach of a material provision of the Contract Documents;

**12.2.1.6** As permissible by law for a reason to terminate, Contractor is adjudged bankrupt;

**12.2.1.7** As permissible by law for a reason to terminate, Contractor should make a general assignment for the benefit of creditors;

**12.2.1.8** As permissible by law for a reason to terminate, Contractor should have a receiver appointed on account of Contractor's insolvency; or

**12.2.1.9** Contractor fails to follow safety requirements and precautions either as expressly provided in the Contract Documents or as consistent with the customary practices in the industry.

**12.2.2 UNIVERSITY'S RIGHT TO CARRY OUT THE WORK UPON TERMINATION FOR CAUSE.** If Contractor fails to remedy the breach or failure within seven (7) days or other mutually agreed period after notice from University, University may, without prejudice to other remedies available to University and in addition to enforcement of any other of University's rights, terminate the Contractor's Agreement, take possession of the Work site and all materials, finish the Work by whatever reasonable method University may deem expedient, and charge Contractor, or file a claim against Contractor's bankruptcy estate, for any additional costs incurred by University to complete the Work. Contractor shall not be entitled to receive any further payment until the Work is completed, nor shall Contractor be relieved from its obligations and liabilities assumed under the Contractor's Agreement. If University's costs exceed the amount of any payment(s) owed by University to Contractor subject to offset by University, University may bill Contractor for the difference, which Contractor shall pay within twenty-eight (28) days of receipt of University's invoice.

**12.2.3 ITEMS REQUIRED TO BE TRANSFERRED OR DELIVERED.** University may require Contractor to transfer title and deliver to University, in the manner and to the extent directed by University:

**12.2.3.1** Any completed portion of the Work; and

**12.2.3.2** Any partially completed portion of the Work and any parts, tools, dies, jigs, fixtures, drawings, information, and contract rights as Contractor has specifically produced or specifically acquired for the performance of such part of the Work as has been terminated; and Contractor shall, upon direction of University, protect and preserve property in the possession of Contractor in which University has an interest.

**12.2.4 PAYMENT.** When University terminates Contractor's Agreement for one or more of the reasons stated in Section 12.2.1, University may withhold payment and/or pursue all available remedies.

**12.2.5 UNIVERSITY PROTECTION IF LIENABLE.** When the Work is lienable, University may withhold from amounts otherwise due Contractor for such Work such amount as University determines to be necessary to protect the State against loss because of liens.

**12.2.6 CREDITS AND DEFICITS.** If the unpaid balance of the Contract Price exceeds the full cost of finishing the Work, including compensation for the A/E's services and expenses made necessary thereby, such excess shall be paid to Contractor. If such cost exceeds the unpaid balance of the Contract Price, Contractor shall pay the difference to University and this obligation for payment shall survive the termination of Contractor's Agreement.

**12.2.7 IF CONTRACTOR FOUND NOT IN DEFAULT OR EXCUSABLE.** If, after notice of termination of Contractor's Agreement under the provisions of Section 12.2, it is determined for any reason that Contractor was not in default under the provisions of Section 12.2, or that the default was excusable under the provisions of Section 12.2, the rights and obligations of the parties shall be the same as if the notice of termination had been issued pursuant to the termination for convenience provisions of Section 12.3.

**12.2.8 RIGHTS AND REMEDIES NOT EXCLUSIVE.** The rights and remedies of University provided in this Section 12.2 shall not be exclusive and are in addition to any other rights and remedies provided by law or under the Contract Documents.

**12.2.9 TIME PERIOD FOR CLAIMS.** Any PRE by Contractor for adjustment under this Section 12.2 must be asserted by Contractor, in writing, within twenty-one (21) days from the date of termination; provided that University may, in its sole discretion, receive and act upon any such PRE asserted at any time prior to final payment under Contractor's Agreement.

### **12.3 TERMINATION FOR CONVENIENCE OF UNIVERSITY.**

**12.3.1 IN GENERAL.** The performance of Work under Contractor's Agreement may be terminated by University in accordance with this Section 12.3 in whole or in part, or from time to time, whenever University shall determine that such termination is in the best interest of University or any person or entity for whom University is acting under Contractor's Agreement. Any such termination shall be effectuated by delivery to Contractor of a notice of termination specifying the extent to which performance of Work is terminated and the date upon which such termination becomes effective.

**12.3.2 CONTRACTOR OBLIGATIONS.** After receipt of a notice of termination, and except as otherwise directed by University in writing, the Contractor shall:

**12.3.2.1** Stop Work under Contractor's Agreement on the date and to the extent specified in the notice of termination;

**12.3.2.2** Place no further orders or subcontracts for materials, services or facilities, except as may be necessary for completion of such portion of the Work that is not terminated;

**12.3.2.3** Terminate all orders and subcontracts to the extent that they relate to performance of Work terminated by the notice of termination;

**12.3.2.4** Assign to University in the manner, at the times, and to the extent directed by University, all of the right, title, and interest of Contractor under the orders and subcontracts so terminated, in which case University shall have the right, in its discretion, to settle or pay any or all claims arising out of the termination of such orders and subcontracts;

**12.3.2.5** Settle all outstanding liabilities and all claims arising out of such termination of orders and subcontracts, with the approval or ratification of University, which approval or ratification shall be final for all the purposes of this Section 12.3;

**12.3.2.6** Transfer title and deliver to University in the manner, at the times, and to the extent, if any, directed by University:

**12.3.2.6.1** The fabricated or unfabricated parts, Work in process, completed Work, supplies, and other material produced as a part of, or acquired in connection with the performance of the Work terminated by the notice of termination; and

**12.3.2.6.2** The completed or partially completed drawings, information, and other property which, if Contractor's Agreement had been completed, would have been required to be furnished to University;

**12.3.2.7** Use best efforts to sell, in the manner, at the times, to the extent, and at the price or prices directed or authorized by University, any property of the types referred to in Section 12.3.2.6; provided, however, that Contractor:

**12.3.2.7.1** Shall not be required to extend credit to any purchaser; and

**12.3.2.7.2** Shall dispose of any such property under the conditions prescribed by and at a price or prices approved by University; and provided further that the proceeds of any such transfer of or disposition shall be applied in reduction of any payments to be made by University to Contractor under Contractor's Agreement or shall otherwise be credited against the Contract Price or paid in such other manner as University may direct;

**12.3.2.8** Complete performance of such part of the Work as shall not have been terminated by the notice of termination; and

**12.3.2.9** Take such action as may be necessary, or as University may direct, for the protection and preservation of the property related to Contractor's Agreement which is in the possession of Contractor in which the State of Utah has or may acquire an interest.

**12.3.3 TERMINATION CLAIM.** After receipt of a notice of termination, Contractor may submit to University a PRE, in the form and with certification prescribed by University. Such PRE shall be submitted promptly but in no event not later than twenty-one (21) days from the effective date of termination.

**12.3.4 AGREED UPON PAYMENT.** Subject to the provisions of Section 12.3.3 above, Contractor and University may agree upon the amount to be paid to Contractor by reason of the total or partial termination of Work pursuant to this Section 12.3.

**12.3.5 PAYMENT NOT AGREED UPON.** In the event Contractor and University fail to agree as provided in Section 12.3.4 upon the whole amount to be paid to Contractor by reason of the termination of Work pursuant to this Section 12.3, University shall pay to the Contractor the amounts determined by University as follows, but without duplication of any amounts agreed upon in accordance with Section 12.3.4:

**12.3.5.1** With respect to all Work performed prior to effective date of termination, the total (without duplication of any items) of:

**12.3.5.1.1** The cost of such Work including undisputed Claim amounts;

**12.3.5.1.2** The cost of terminating, settling and paying claims arising out of the termination of Work under subcontracts or orders as provided in Section 12.3.2.5, exclusive of the amounts paid or payable on account of supplies or materials delivered or services furnished by Subcontractors prior to the effective date of termination under Contractor's Agreement, which amounts shall be included in the cost on account of which payment is made under Section 12.3.5.1.1;

**12.3.5.1.3** An amount, as overhead and profit on Section 12.3.5.1.1 above, determined by University to be fair and reasonable;

**12.3.5.1.4** The reasonable cost of the preservation and protection of property incurred pursuant to Section 12.3.2.9; and any other reasonable cost incidental to termination of Work, including expenses incidental to the determination of the amount due to Contractor as the result of the termination of Work.

**12.3.5.1.5** The total amount to be paid to Contractor under Section 12.3.5.1 above shall not exceed the Contract Price as reduced by the amount of payments otherwise made and as further reduced by the Contract Price of Work not terminated. Except for normal spoilage, and except to the extent that University shall have otherwise expressly assumed the risk of loss in writing, there shall be excluded from the amounts payable to Contractor under Section 12.3.5.1 above, the fair value of property which is destroyed, lost, stolen, or damaged so as to become undeliverable to University, or to a buyer pursuant to Section 12.3.2.7.

**12.3.6 DEDUCTIONS.** In arriving at the amount due Contractor under this Section 12.3, there shall be deducted:

**12.3.6.1** All unliquidated advance or other payments on account theretofore made to the Contractor, applicable to the terminated portion of Contractor's Agreement;

**12.3.6.2** Any Claim which University and/or the State of Utah may have against Contractor in connection with Contractor's Agreement; and

**12.3.6.3** The agreed price for, or the proceeds of sale of, any materials, supplies, or other things acquired by Contractor or sold, pursuant to the provisions of this Section 12.3, and not otherwise recovered by or credited to University.

**12.3.7 PARTIAL TERMINATION.** If the termination is partial, Contractor may file with University a PRE for the amounts specified in Contractor's Agreement relating to the continued portion of Contractor's Agreement and such equitable adjustment as may be agreed upon shall be made in such amounts. Any PRE under this Section 12.3.7 must be filed within twenty-one (21) days from the effective date of the partial termination.

**12.3.8 PARTIAL PAYMENTS.** University may, from time to time, under such terms and conditions as it may prescribe, make partial payments and payments on account against costs incurred by Contractor in connection with the terminated portion of Contractor's Agreement whenever, in the opinion of University, the aggregate of such payments shall be within the amount to which Contractor shall be entitled hereunder. If the total of such payments is in excess of the amount finally agreed or determined to be due under this Section 12.3, such excess shall be payable by Contractor to University upon demand, together with interest at a rate stated in Utah Code § 15-1-1, for the period until the date such excess is repaid to University; provided, however, that no interest shall be charged with respect to any such excess payment attributable to a reduction in Contractor's claim by reason of retention or other disposition of termination inventory until fourteen (14) days after the date of such retention or disposition, or such later date as determined by University by reason of the circumstances.

**12.3.9 PRESERVE AND MAKE AVAILABLE RECORDS.** Unless otherwise provided for in Contractor's Agreement, or by applicable law, Contractor shall, from the effective date of termination until the expiration of three years after final settlement under Contractor's Agreement, preserve and make available to University at all reasonable times at the office of Contractor, but without charge to University, all books, records, documents, and other evidence bearing on the costs and expenses of Contractor under Contractor's Agreement and relating to the Work terminated hereunder, or, to the extent approved by University, photographs, or other authentic reproductions thereof.

**12.3.10 SUSPENSION, DELAY OR INTERRUPTION OF WORK BY UNIVERSITY FOR CONVENIENCE.** University may in writing and without cause, order Contractor to suspend, delay, or interrupt the Work, in whole or in part, for such period of time as University may determine to be appropriate for the convenience of University.

**12.4 UNIVERSITY'S RIGHT TO STOP THE WORK.** If Contractor fails to correct Work or fails to carry out Work as required by the Contract Documents or fails to comply with all required and customary safety precautions; University, in writing, may order Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, the right of University to stop the Work shall not give rise to a duty on the part of University to exercise this right for the benefit of Contractor or any other person or entity.

The University of Utah  
FACILITIES MANAGEMENT

**SUPPLEMENTAL  
GENERAL CONDITIONS  
FOR UNIVERSITY OF UTAH PROJECTS**

September 30, 2011

**TABLE OF CONTENTS**

| <b><u>ARTICLES</u></b>                                             | <b><u>Page Number</u></b> |
|--------------------------------------------------------------------|---------------------------|
| 1. Basic Definitions.....                                          | 2                         |
| 2. Affirmative Action .....                                        | 2                         |
| 3. Access to Communications Manholes .....                         | 2                         |
| 4. Digging Permits .....                                           | 2                         |
| 5. Request for Utility Shutdown.....                               | 3                         |
| 6. Drug Free Workplace .....                                       | 4                         |
| 7. Hazardous Chemicals.....                                        | 4                         |
| 8. Interim Life Safety Measures .....                              | 4                         |
| 9. Keys.....                                                       | 4                         |
| 10. No Smoking Area.....                                           | 5                         |
| 11. Operating & Maintenance Manuals / Warranties & Guarantees..... | 5                         |
| 12. Parking Permits .....                                          | 7                         |
| 13. Parking on University Sidewalks .....                          | 7                         |
| 14. Sexual Harassment .....                                        | 7                         |
| 15. Site Lighting.....                                             | 7                         |
| 16. Tax Exemption .....                                            | 7                         |
| <i>Tax Exemption Certificate</i> .....                             | 8                         |
| 17. Water Use on Campus.....                                       | 9                         |
| 18. Storm Water Pollution Prevention (SWPPP) .....                 | 9                         |
| 19. Vehicle Idling Policy.....                                     | 10                        |
| 20. Environmentally Preferable Products.....                       | 10                        |
| 21. Integrity of Fire Rated Partitions.....                        | 10                        |
| 22. Roof Access .....                                              | 11                        |
| 23. Utility Connections .....                                      | 11                        |
| 24. Additional OSHA Requirements.....                              | 18                        |

Revision Note: This document replaces the *Supplemental General Conditions for University of Utah Projects* dated May 2, 2011. The only change is a new paragraph 5.1 added to Article 5 “Request for Utility Shutdown.”



## **Article 1 Basic Definitions**

Except as otherwise described herein, definitions provided in the General Conditions apply to this document. The following definition is added to the General Conditions:

**UNIVERSITY PROJECT MANAGER.** “University Project Manager” means the University of Utah Facilities Management person directly assigned to coordinate the University’s interests and involvement in the Work. If the contractor’s agreement is issued by the University of Utah, the “University Project Manager” is the “University’s Representative” as defined in the General Conditions.

## **Article 2 Affirmative Action**

The Contractor is encouraged to utilize the services of Small Business Enterprises, Disabled Veteran-Owned Business Enterprises, Minority-Owned Business Enterprises, Woman-Owned Business Enterprises, and Small Disadvantage Business Enterprises as subcontractors and/or suppliers for University projects. The Contractor may be required to survey and provide information on contracts and utilization of these services.

## **Article 3 Access to Communication Manholes**

The University of Utah requires communications manholes on campus to be fitted with a secure access system. Authorization will be required before the Contractor may enter any communication manhole, whether secured or not. Authorization will be requested through the University Project Manager and permission will be given by University Information Technology - Network and Communication Services.

- 3.1 The Contractor must not proceed with any work in the manhole without first fully understanding the systems and equipment currently in place. Assistance in identifying communications systems and their functions in the manhole may be obtained from University Information Technology - Network and Communication Services at 801-581-8999.
- 3.2 Note that campus communication systems provide support to several critical functions at the University, including, but not limited to major research activities. An unintended shutdown may adversely affect several critical functions, including highly expensive research. Unintended shutdown of any communication service caused by the Contractor which results in any damage(s) will be assessed to and paid by the Contractor.

## **Article 4 Digging Permits**

A Digging Permit shall be required for all underground digging on campus. The University and other non-University entities support an extensive network of underground utilities.

- 4.1 Contractors shall request digging permits through the University Project Manager.
- 4.2 Requests for a Digging Permit are available on-line or from the University Project Manager. Requests must be submitted at least five full University working days prior to the commencement of digging. The request should include a description of the intended work, and drawing(s) showing the intended work area and the contract limit lines.

- 4.3 This permit process does not automatically request Blue Stakes assistance. The Contractor must also contact Blue Stakes and other utility companies as applicable for assistance in locating non-University underground utilities.
- 4.4 The issued Digging Permit will identify University utilities known to exist within the affected area. After issuance of the permit, Facilities Management (“FM”) will mark the location of existing University utilities at the site. Note that there is a risk that some underground utilities may not be documented in University records. All excavation should proceed with caution.
- 4.5 During excavation, the equipment operator shall have copies of the Digging Permit and Blue Stakes documentation in his/her immediate possession to guide the operator in utility avoidance and to document the University’s approval of the work.
- 4.6 Additional assistance in locating existing University utilities is available from the University Surveyor at 801-585-5070.
- 4.7 Contractor shall provide the University Project Manager notice of not less than two working days prior to backfilling over utilities or other underground improvements. While the intent of this requirement is to allow the University to collect survey data, this does not relieve the Contractor of its obligation to maintain As-Built documentation required by Article 4.8 of the General Conditions.

## **Article 5 Request for Utility Shutdown**

A Request for Utility Shutdown shall be submitted to the University Project Manager for each anticipated interruption of any existing utility service on campus. This includes, but is not limited to, any interruption to electric systems, communications; control systems, security, gas (natural, laboratory gasses, etc.), water (potable, non-potable, purified, etc.), steam systems, high-temperature water systems; sanitary sewer, storm sewer, etc. The Contractor is to discuss anticipated shut-down requirements with University Project Manager well in advance of the proposed shut-down.

- 5.1 Prior to beginning any work on a Utility Shutdown, the Contractor must meet with the University Project Manager and Plant Operations staff to define a hazard control plan that can include Lock Out Tag Out, Confined Space Entry, and NFPA 70 compliance. Refer to Article 24 in these Supplemental General Conditions for additional information. The Contractor must verify that all sources of hazardous energy for the affected system have been identified, properly controlled and/or isolated, and locked out prior to beginning any work. The Contractor and its subcontractors shall place their own locks on the shut down system as an added measure of protection for their employees.
- 5.2 Utility Shutdown Request forms are available on-line or they can be obtained from the University Project Manager.
- 5.3 Submit the request to the University Project Manager at least three (3) full University working days prior to the day of shut-down.

- 5.4 A longer lead time is required for interruptions affecting several campus departments, scientific experiment disruption, and similar complications. Shutdowns of this nature must be identified early and reviewed with the University Project Manager in order to determine notice requirements.
- 5.5 Each utility shut-down request is subject to approval by Campus Design & Construction, Plant Operations, and University departments which will be affected by the proposed loss of service.
- 5.6 If immediate shutdown is required to prevent damage to personnel or property, contact Plant Operations Dispatch at 801-581-7221.

#### **Article 6 Drug Free Workplace**

It is the policy of the University of Utah that "...the unlawful manufacture, distribution, dispensation, possession, or use of a controlled substance on University property is prohibited." All contractors, subcontractors, and their employees, while under contract with the University must abide by the terms of the above policy. Violation may result in termination of the contract. The University will prosecute violators of this policy to the fullest extent possible.

#### **Article 7 Hazardous Chemicals**

The University of Utah shall inform contractors of hazardous chemicals their employees may be exposed to while working on University projects. Conversely, the Contractor shall inform the University of Utah of all hazardous chemicals the Contractor will bring on campus that University of Utah employees may be exposed to. This exchange of information shall occur through the University Project Manager.

#### **Article 8 Interim Life Safety Measures**

The Contractor must observe the following interim life safety measures during construction of the project. The University must approve any variance or exception in writing.

- 8.1 All exits will provide free and unobstructed egress.
- 8.2 Free and unobstructed access to emergency departments and for emergency forces will be maintained.
- 8.3 Fire alarm, detection, and suppression systems will not be impaired. In the event of disruption, alternative systems shall be provided which are satisfactory to the authority having jurisdiction.
- 8.4 Temporary construction partitions will be smoke tight and built of non-combustible or limited combustible materials that will not contribute to the development or spread of a fire.
- 8.5 The Contractor will provide appropriate additional fire fighting equipment (such as charged, current fire extinguishers) on the construction site.
- 8.6 Smoking is prohibited in or adjacent to construction areas.

- 8.7 The Contractor will develop and enforce storage, housekeeping, and egress removal practices that reduce the flammable and combustible fire load of the building to the lowest level necessary for daily operation.
- 8.8 When structural or compartmentation features of fire safety are compromised, the Contractor will notify the A/E and University Project Manager so that the University can develop alternate fire safety procedures.

#### **Article 9 Keys**

Should the Contractor require key(s), (as determined by the University Project Manager) for access to the Project Site, the University Project Manager shall arrange to obtain such key(s) for the Contractor.

- 9.1 At the completion of the Project and before final payment is approved, the Contractor shall return University key(s) to the University Project Manager. Should he/she be unable to do so because of loss, theft, or for any reason, the cost of replacement key(s) and/or re-keying of any locks deemed necessary shall be deducted from the Contractor's final payment. Loss or theft of keys is to be reported to the University Project Manager immediately.

#### **Article 10 No Smoking Area**

In order to comply with the Utah State Clean Air Act which prohibits smoking in public buildings, a strict no smoking policy shall be enforced at any job site located within the confines of any University of Utah building or within 25 feet of any building opening or entrance. This policy will apply to all contractors, their employees and subcontractors.

#### **Article 11 Operating and Maintenance Manuals / Warranties and Guarantees**

- 11.1 All information is to be organized by discipline (architectural, mechanical, electrical, etc.).
- 11.2 Security Systems O&M Manuals and Warranties/Guarantees
  - a. The Security Contractor shall submit security systems O&M and warranty/guaranty documents separately.
  - b. These documents must be delivered directly to the UCard main office by the installing Security Contractor. No other entity will receive a copy of security system documentation.
- 11.3 Warranties and Guarantees
  - a. Submit two sets of paper originals bound in a binder for the University (plus sets required by DFCM for their projects)
  - b. Submit two CDs of the same information prepared electronically in a self executable searchable PDF format for the University (plus sets required by DFCM for their projects).

- c. Hard copies and electronic submittals are to be clearly identified on the front cover and label with the title “Warranties and Guarantees”, University building number, the project name, University project number, and the Contractor’s business name.

#### 11.4 Operating and Maintenance Manuals

- a. Submit O&M manuals as a separate bound document in the same formats described above for warranties and guarantees (2 paper sets and 2 electronic copies of a self executable searchable PDF).
- b. The following information shall appear on the front cover (both CD and hard copy):

|                                           |
|-------------------------------------------|
| <u>"Operation and Maintenance Manual"</u> |
| Building Number:                          |
| Project Name:                             |
| Volume Number:                            |
| University Project Number:                |
| <br>A/E Firm:                             |
| A/E Subconsultant(s):                     |
| Commissioning Agent:                      |
| <br>Contractor:                           |
| Major Subcontractor(s):                   |

- c. Special equipment must include a material list, and special architectural items must include paint color identification (source and catalog number).
- d. Include complete set(s) of building control diagrams, drawn as installed at the site with all sequences of operations included for all equipment. Equipment, devices and wiring shall be clearly identified with model, size, etc. These drawings are to be included in O&Ms as well as being framed behind glass and hung in the mechanical room along with a valve matrix showing valve type, service and location.
- e. For each item of equipment, include approved submittals and provide data and instruction sheets marked to indicate the equipment/device serial number, the plan symbol found on the construction drawings, the model number, and all options ordered.
- f. Additionally, the following information is to be included:
  - (1) A table of contents.
  - (2) A complete parts list(s) and source of supply for each piece of equipment, including contact information (addresses and phone numbers).

- (3) The balance report, where applicable.
- (4) Performance curves and capacity data.
- (5) Wiring diagrams.

#### **Article 12 Parking Permits**

Every vehicle will require a permit to park on the University of Utah campus. The Contractor is responsible for all costs of required parking permits. Contractor permits are available at 1901 E. South Campus Drive, Room #101 (the north-west corner of the Annex Building just east of the Jon M. Huntsman Center). The sale of parking permits to Contractors is subject to any limitations or other constraints identified in the bidding documents and by University of Utah Commuter Services.

#### **Article 13 Parking on University Sidewalks**

Parking or driving on campus sidewalks is not allowed unless prior authorization is received and a hang-tag permit is clearly visible in the vehicle. Authorization must be obtained through the University Project Manager. The hang-tag shall be placed on the vehicle's dashboard or interior mirror, fully visible through the windshield at all times. Not all sidewalks are vehicle accessible. For more information see <http://www.facilities.utah.edu/sidewalkpermits/>.

#### **Article 14 Sexual Harassment**

Sexual harassment of any kind is taken very seriously at the University. Contractors will be held responsible for the actions of their employees and subcontractors while working on University projects. Any contractor, subcontractor, or employee thereof participating in verbal or other sexual intimidation of any kind toward any other individual or group (e.g., making "catcalls") shall be held in violation of Federal Law, Title VII, Section 703 (sexual harassment) and will be prosecuted to the fullest extent possible. University sanctions of convicted violators may include, but not be limited to, termination of Contract.

#### **Article 15 Site Lighting**


New and existing site lighting along walkways and around the perimeter of the construction site shall be operational for all hours of darkness during extent of construction. Upon notification of lighting failure, the Contractor shall respond and initiate repair of the failed system within four hours of notification. If the response time exceeds four hours, the University reserves the right to repair the system and the Contractor will then be responsible for the repair costs.

#### **Article 16 Tax Exemption**

Do not include Utah State Sales and Use Tax on materials purchased for the Work, and do not include this tax on materials for proposed changes or invoices. The University of Utah is exempt from Federal Excise Taxes and Utah Sales and Use Taxes. The Contractor is responsible for complying with all Utah State Sales and Use Tax exemption requirements. The Contractor is responsible for payment of all Utah State Sales and Use Tax obligations that arise from the Contractor's failure to comply with exemption requirements.

***The Utah State Tax Commission Exemption Certificate (Number N21318)  
is provided on the following page.***

## TAX EXEMPTION CERTIFICATE

|                                                                                                           |  |                                                                                                                 |  |                                                           |                          |
|-----------------------------------------------------------------------------------------------------------|--|-----------------------------------------------------------------------------------------------------------------|--|-----------------------------------------------------------|--------------------------|
|                          |  | Utah State Tax Commission<br><b>Exemption Certificate</b><br>(Sales, Use, Tourism and Motor Vehicle Rental Tax) |  | <b>TC-721</b><br>Rev. 1/09                                |                          |
| Name of business or institution claiming exemption (purchaser)<br><b>University of Utah</b>               |  |                                                                                                                 |  | Telephone Number<br><b>801-581-7241</b>                   |                          |
| Street Address<br><b>1901 E South Campus Dr Rm 151</b>                                                    |  | City<br><b>Salt Lake City</b>                                                                                   |  | State<br><b>UT</b>                                        | ZIP Code<br><b>84112</b> |
| Authorized Signature<br> |  | Name (please print)<br><b>James T. Parker</b>                                                                   |  | Title<br><b>Director of Procurement &amp; Supply Mgt.</b> |                          |
| Name of Seller or Supplier:                                                                               |  |                                                                                                                 |  | Date                                                      |                          |

The person signing this certificate **MUST** check the applicable box showing the basis for which the exemption is being claimed. Questions should be directed (preferably in writing) to Taxpayer Services, Utah State Tax Commission, 210 N 1950 W, Salt Lake City, UT 84134. Telephone (801) 297-2200, or toll free 1-800-662-4335.

**DO NOT SEND THIS CERTIFICATE TO THE TAX COMMISSION**  
Keep it with your records in case of an audit.



### CONSTRUCTION MATERIALS PURCHASED FOR RELIGIOUS AND CHARITABLE ORGANIZATIONS

I certify the construction materials purchased are on behalf of a religious or charitable organization. I further certify the purchased construction materials will be installed or converted into real property owned by the religious or charitable organization.

Name of religious or charitable organization:

UNIVERSITY OF UTAH

Sales Tax Exemption No. N21318

Name of project: \_\_\_\_\_

To be valid this certificate must be filled in completely, including a check mark in the proper box.

**A sales tax license number is required only where indicated.**

Please sign, date and, if applicable, include your license or exemption number.

**NOTE TO SELLER:** Keep this certificate on file since it must be available for audit review.

**NOTE TO PURCHASER:** Keep a copy of this certificate for your records. You must notify the seller of cancellation, modification, or limitation of the exemption you have claimed.

If you need an accommodation under the Americans with Disabilities Act, contact the Tax Commission at (801) 297-3811 or TDD (801) 297-2020. Please allow three working days for a response.

**DO NOT SEND THIS CERTIFICATE TO THE TAX COMMISSION**  
Keep it with your records in case of an audit.

## **Article 17 Water Use on Campus**

Fire hydrants on campus may only be used with permission. If water trucks or tanks must be filled outside the construction area, the water station between Buildings 306 and 309 may be used.

## **Article 18 Storm Water Pollution Prevention (SWPPP)**

In addition to complying with the SWPPP requirements provided for in the Instruction to Bidders, the Contractor shall comply with the following. The University must approve any variance or exception in writing.

- 18.1 The Contractor must employ the following storm water pollution prevention measures during construction of the project.
  - a. Perimeter control, a system of sediments control best management practices (BMPs) that act as barriers to retain sediment on the construction site.
  - b. Construction entrance/exit stabilization for all entrances/exits used by the project, no matter how short the duration. Sediment tracking onto University roads, parking lots, sidewalks, and other paved surfaces is prohibited. If tracking occurs, the Contractor must clean the affected area before the end of the workday.
  - c. Temporary earth stabilization until final stabilization has been achieved.
  - d. Protect all storm drain inlets/catch basins that could receive storm water from the project until final stabilization of the site has been achieved.
  - e. If concrete work is part of the project, a concrete washout area must be provided. The area must be lined or a sealed container may be used.
- 18.2 The Contractor's SWPPP must be reviewed and approved by the University's Department of Environmental Health and Safety (EHS) prior to submitting the application (NOI) online, and the Contractor must have the permit before beginning construction. The University Project Manager will assist in submitting the Contractor's SWPPP to EHS.
- 18.3 The Contractor shall assume full responsibility for any SWPPP drafted by others and adopted by the Contractor for use at the construction site. The Contractor shall finalize and file the SWPPP grading, sediment and erosion control plan and pay permit fees. The Contractor shall make any needed modifications to the SWPPP to fit the existing site conditions prior to beginning construction.
- 18.4 In addition to other requirements, the Contractor shall:
  - a. Inspect the construction site to verify the SWPPP plan every two weeks and after significant rainfall, and keep a record of each inspection at the construction site,
  - b. Remedy deficient management practices, controls and control structures; and,



- c. Modify the SWPPP as site conditions change (i.e., as demolition and construction phases progress).

#### **Article 19 Vehicle Idling Policy**

In an effort to reduce vehicle emissions and fuel use at the University of Utah, the Contractor shall adhere to this idling policy for all vehicles and equipment operating on campus.

- 19.1 For the purposes of this policy, idling means an engine is running while the vehicle it serves is stationary, or the equipment it operates is not performing work.
- 19.2 Contractor vehicles and equipment are prohibited from idling for periods longer than 60 seconds except under the following conditions:
  - a. Where idling is necessary to power auxiliary equipment such as lifts, hoists, computers or safety lighting (auxiliary equipment does not include the vehicle's air conditioner, heater or defrost for wintertime vehicle warm up),
  - b. Where idling is necessary for testing, maintenance, repair or diagnostic purposes,
  - c. Where idling is necessary to maintain factory installed emissions equipment on diesel equipment,
  - d. Where a vehicle is stopped at a traffic control signal; in heavy traffic at a TRAX line or railroad crossing; traveling through a construction zone; and / or,
  - e. Where turning off the motor could jeopardize the health and safety of the driver or passenger.

#### **Article 20 Environmentally Preferable Products**

Subject to limitations and the review and approval requirements stated in the General Conditions and other Contract Documents regarding substitutions, substitution requests and the use of specified materials or products, the Contractor, where allowed, is encouraged to offer Energy Star certified products, EPEAT (Electronic Product Environmental Assessment Tool) recommended products, or products that meet FEMP (Federal Energy Management Program) standards for energy consumption. The University of Utah also encourages contractors to offer products or services, when allowed by Contract Documents, that have a lesser or reduced effect on human health and the environment when compared with competing products or services. Items considered may include raw materials acquisition, production, manufacturing, packaging, distribution, reuse, operation, maintenance, disposal, etc.

#### **Article 21 Integrity of Fire Rated Partitions**

For all construction work performed in patient care facilities, unless specifically shown on the drawings, neither the Contractor nor any Subcontractor shall allow holes, cuts, or any other type of penetration in any floor slab, partition above the ceiling, or any otherwise concealed partition, without first notifying the University or the University's representative of every such occurrence. The purpose of this notification is to enable the University to verify that each such penetration is properly sealed according to the requirements of current UBC and NFPA codes ( as part of the Work of the Contractor) if required by the

University. Prior to covering concealed locations, and prior to Substantial Completion, the Contractor shall be responsible to arrange an inspection with the University or University's representative where personal inspection will verify that each such penetration is properly sealed.

## **Article 22 Roof Access**

Access to University roofs is limited to authorized personnel only. Roof safety is the responsibility of the Contractor and includes any individual working for or contracting with the Contractor. Safety issues include potential falling hazards and roof integrity protection. Any individual intending to access a University roof must first obtain permission follow the procedures described at the Plant Operations web site under "Roof Access."

## **Article 23 Utility Connections**

Connections to certain campus utilities require specific tasks. The following utilities have specific connection task requirements:

- 23.1 Trace Wire. For all underground piping, a #10 THW copper wire must be installed alongside of the pipe to serve as a trace wire. The trace wire must be brought to the interior of valve boxes and manholes when applicable. At building penetrations, trace wire must be brought to the surface outside of the building and secured inside a single valve irrigation box with cover. Any terminations of trace wire not described above shall be secured inside a single valve irrigation box with cover. Terminations of the trace wire shall be noted on As-Built drawings.
- 23.2 Electrical Power-Up. The following requirements must be met prior to activating electrical power at new or remodeled buildings on campus. The Contractor's Work will be subject to inspection by the University's Electric Shop and power-up will not be allowed until the following requirements are met.
  - a. Manholes
    - (1) Switchgear in manholes shall be labeled to identify the building being served.
    - (2) Each new and existing high voltage cable shall be fire-taped and racked on manhole walls.
    - (3) Each new and existing high voltage cable shall be marked to indicate feeder number and feeder voltage.
    - (4) Each conduit leaving the manhole shall be marked to show the next manhole or building.
    - (5) Each manhole shall be labeled with a manhole number.
    - (6) All ground wires in the manhole and all terminations shall be properly grounded.
    - (7) Prior to power-up, each manhole shall be cleaned of all trash.

b. Above Ground High Voltage Switches and Transformers

- (1) Switches and transformers shall be labeled to identify the voltage and building served.
- (2) Properly ground all gear and terminations.
- (3) Color code each feeder leaving the transformer per the voltage feeding the building. Colored tape shall be applied at all terminations, junction boxes and pull boxes. Conductors in sizes #6 and below shall be color coded with colored insulation. Power conductors shall be color coded as follows:

| Conductor | 208v  | 480v   |
|-----------|-------|--------|
| phase A   | black | brown  |
| phase B   | red   | orange |
| phase C   | blue  | yellow |
| neutral   | white | grey   |
| ground    | green | green  |

c. Main Distribution Panels

- (1) Each distribution panel shall be grounded.
- (2) Each feeder entering the panel from a transformer shall be color coded (as described in paragraph “b” above) to identify the voltage.
- (3) Each distribution panel shall be labeled to identify the voltage.

d. Equipment Labeling

- (1) Compliance with NFPA 70E 2009 130.3 C Equipment Labeling (including current updates) is required. All labels must be in place prior to connection to the University Electrical System.

23.3 High Temperature Water Connections. The following requirements must be met prior to activating high temperature water piping at new or remodeled buildings on campus. The Contractor will assist the University during system start-up.

- a. Prior to requesting start-up assistance, the Contractor shall check all parts of the system for leaks, and repack valve stem glands that indicate a need for additional packing.

- b No valve between existing and new HTW piping shall be opened until after all tests are approved, and internal cleaning operations are complete; then, system valves may be opened only with authorization and on-site-assistance from Campus Utility Services, the High Temperature Water Plant, and the University Project Manager.
- c The HTW Plant personnel will provide on site management of the start-up process and direct the Contractor in valve positioning. The Contractor shall not activate any valve during start-up until directed to do so by the University.
- d Additional requirements include:
  - (1) Shut-down and start-up will be accomplished by University personnel only. The Contractor shall follow "Request for Utility Shutdown" procedures, but allow additional lead time to allow adequate preparation time for University services.
  - (2) The Contractor shall boil out each HTW pipe system before connecting to a live HTW system. Water quality for start up must be 0 PPH and shall be verified by a University authorized water treatment specialist.
  - (3) Pressure test each pipeline at 800 lbs for 24 hours. If hydrostatic testing is not feasible, provide certification of a leak proof system through x-ray analysis.
  - (4) Before opening or cutting into any HTW pipe, the Contractor must verify 0 PSI in the line and receive approval from the HTW plant.
  - (5) All connections shall be welded and tested before start up. Threaded pipe connections will not be allowed.
  - (6) All pressure gauges, thermometers, valves, etc. shall be furnished and installed in the piping system prior to start-up.
  - (7) Pipe insulation will be installed in confined areas such as manhole vaults and any location where space limitations pose a risk of burn injury.
  - (8) Ladders shall be installed inside manhole vaults.

23.4 Natural Gas Main Connections. Natural gas piping shall be installed in accordance with State adopted code, DOT standards, Questar standards, and University of Utah standards.

- a. Exterior buried gas lines shall follow Questar approved specifications for plastic pipe and shall be bedded in sand the entire length of the line. Exterior above ground gas lines 2-1/2" and larger shall be schedule 40 forged black steel butt welded fittings; or, for 2" and smaller shall be 150 lb malleable iron with screwed fittings. Steel pipe must have an approved protective coating.

- (1) For buried plastic pipe, yellow warning tape shall be installed 2 feet above the gas line, in addition to an 18 gage copper wire along the entire length of the pipe.
  - (2) When a gas pipe is run through a wall, the pipe shall be run through protective sleeve and sealed to prevent water from entering the building.
  - (3) All outside above ground gas piping shall be painted with a protective gray paint.
- b. All gas piping shall be tested at 3 PSI for 10 minutes with no drop. A half-pound increment gauge shall be used. Where the supply is over 2 pounds, the test shall be at 1 ½ times the maximum working pressure. All tests shall be witnessed by the University of Utah Plumbing Shop or its' designee.
- 23.5 Sanitary Sewer Connections. Sewer mains shall be installed in accordance with State adopted code, using procedures to keep dirt out of the sewer main. All installed piping shall be inspected by the University Plumbing Shop prior to backfill.
- a. Buried sewer mains shall be bedded in sand and supported throughout its entire length. Under no circumstances will a pipe be supported with rocks.
  - b. Warning tape will be installed at 2 feet above the pipe when PVC pipe is installed.
  - c. Each new sewer main shall be air tested between manholes by a certified testing company. If the air test fails, a camera shall be sent down the sewer main to inspect the line, and the damaged part of the main will be dug up and repaired.
  - d. All building laterals shall be tied in with a manhole, not a WYE.
- 23.6 Steam System Connections. An extension to any campus steam piping system will not be allowed until a stamped professionally engineered plan, including drawings and specifications, is approved by the University. Isolation shut-off valves and steam trap design is required.
- a. Welded or threaded pipe connections are allowed on steam / condensate systems using only black steel pipe and fittings.
  - b. Verify the steam demand for each building system before adding any steam appliance.
  - c. Do not pipe condensate directly to sanitary sewer.
  - d. Verify proper steam connection points and condensate return connection points before completing the installation and connecting to the existing system.

23.7 Piping Tie-In to Existing Building Systems. All piping shall be insulated and labeled. Specific requirements for connections to existing building systems are:

a. Pressure Testing

- (1) The Contractor shall apply a hydrostatic test to each piping system. Each system shall hold a minimum of 100 PSI of water or 1 ½ times the operating pressure, whichever is greater, for 30 minutes without any pressure drop on the gage.

b. Pipe Cleaning

- (1) Piping (black iron, PVC, copper) shall be cleaned with West B802 Alkaline Clean, 25 gallons in every 1000 gallons of water. Circulate the mix 24 to 48 hours, flush with potable city water, then final fill the system with chemicals described hereinafter. The Contractor shall provide documentation and certify that the required procedure was followed.

c. Chemical Fill

- (1) Each piping system to be connected to existing shall be filled with appropriate chemicals or antifreeze equal to the existing system before isolation valves are opened to the building system.
- (2) Close loop systems shall have West C-404, 50 to 100 PPM, MO+6.
- (3) Glycol systems shall have 30% minimum of either Jeffcool P150 or Dowfost.
- (4) Open loop systems shall have West C-313-U at 200 PPM; and shall include sodium hypochlorite at 0.5 to 1.5 PPM.

d. Black iron piping shall be American made schedule 40 seamless (only).

e. Copper Piping

- (1) Copper piping shall be type L with dielectric unions and sweat fittings.
- (2) Gas welded piping shall be nitrogen purged while welding. All fittings will be wiped clean.

23.8 Storm Drainage Connections. Storm drainage piping shall be installed in accordance with State adopted code, and in a manner as to keep dirt out of the piping. All installed piping shall be inspected by the University Plumbing Shop and the University's inspector (Office of the Building Official) prior to backfill or concealment.

a. Exterior Piping

- (1) Storm water from roofs, paved areas, yards, courtyards, etc. shall drain into a dedicated storm drainage system. Under no circumstance shall storm water be tied to a sanitary sewer line.
- (2) Storm drainage piping shall be installed with a bedding material in the bottom of the trench. If PVC is used, 1 foot of sand on the bottom of the pipe, and 2 feet of sand over the top of the pipe will be required. Under no circumstance shall the pipe be resting on rocks.
  - (a) All storm drain laterals shall tie into a manhole or a collection box.
  - (b) A storm drain shall not reduce in size in the direction of flow.
  - (c) Buried storm drain piping 12 inches and smaller shall be tested by a certified testing company between manholes. If the test fails, a camera shall be sent down the line to determine the location of the bad section, it shall be dug up and repaired.
  - (d) Buried storm drain piping larger than 12 inches shall be inspected using a camera sent down the line to check joints for tightness. If a joint is not secure, it shall be dug up and repaired.

b. Interior piping:

- (1) Storm drain piping inside buildings shall be tested using either water or air.
  - (a) If water is used, all openings shall be tightly sealed, except at the highest point, and then filled with water to the point of overflow. No part of the system shall be tested with less than 10 feet of head of water. The static pressure shall be held for 15 minutes.
  - (b) If air is used, 5 PSI shall be maintained for a minimum of 15 minutes with no loss on the gage.

23.9 Water Main Connections. Installation and disinfection of water mains shall be in accordance with State adopted code. Before connecting new water mains to an existing water main; the following must be done:

- a. All water mains shall be kept clean during construction.
- b. All fittings shall be installed with restraining glands and thrust blocks.
- c. All water mains shall be swabbed and cleaned with a 1% hypochlorite disinfecting solution if dirt or trench water enters the pipe per State adopted code.

- d. All water lines shall be capped at the end of the work day to protect piping from animal entry and dirt inside the pipe.
- e. When C900 is used, it shall be bedded with sand one foot below the pipe and 2 feet above the pipe. Caution tape shall be installed at 2 feet above and all along the pipe.
- f. All building supply lines shall be installed with shut off valves on all three sides of the tee.
- g. To fill the water main with water, the Contractor must use an approved cross-connection control device. A hydrostatic pressure test will be required (200 PSI for 2 hours).
- h. All new water lines shall be chlorinated with a 50 PPM or higher and remain in the pipe for a 24 hour period. After the retention period, the heavily chlorinated water shall be flushed into a sanitary sewer only. Salt Lake City Sewer Department must be contacted to let them know that high chlorinated water is coming to them. Upon refilling the system with clean potable water, two bacteriological samples 24 hours apart shall be taken. After the second sample comes back satisfactory, the system can be connected to the University's water system. All work shall be inspected by the University of Utah's Plumbing Shop before being buried or concealed and prior to start-up.

23.10 Water Line Connections Inside Buildings. Water lines entering each building shall have parallel pressure reducing valves and parallel backflow prevention devices with appropriate isolation valves on each parallel path.

- a. Backflow prevention devices shall be installed to separate potable water from industrial and/or non-potable water.
- b. Installation shall be in accordance with State adopted code and will be inspected by the University Plumbing Shop and Building Inspector.
- c. Each floor of the building shall have an isolation valve(s), accessible at the floor it serves.
- d. Each laboratory room shall have an isolation valve(s), accessible in the lab it serves, in addition to shut-off valves at each fixture in the lab.
- e. The Contractor shall test water piping at 2 times the operating pressure for 30 minutes. The test shall be in accordance with State adopted code.
- f. The Contractor shall clean the water piping system by first flushing with clean potable water until dirty water is no longer observed at outlet points. The system shall be filled with clean water including 50 PPM chlorine and held in the system for 24 hours (or 200 PPM for 3 hours). The system shall then be flushed with clean potable water until chlorine is no longer present. The heavily chlorinated



water shall be flushed into a sanitary sewer only. Salt Lake City Sewer Department must be contacted to let them know that high chlorinated water is coming to them.

#### **Article 24 Additional OSHA Requirements**

In addition to any safety regulations or practices which may otherwise be required or prudent, the Contractor shall establish and implement safety programs that comply with the following OSHA General Industry regulations when working inside University buildings or on or around University utility systems:

- 24.1 CFR 1910.146, Permit Required Confined Space
- 24.2 CFR 1910.147; Control of Hazardous Energy (Lock Out Tag Out)
- 24.3 CFR 1910.335; Electrical Safeguards for Personal Protection

*End of Supplemental General Conditions*

# **SUPPLEMENTAL GENERAL CONDITIONS FOR HEALTH INSURANCE**

**Effective March 17, 2016**

## **Article 1. Intent and Purpose.**

Current law: House Bill 282, 2016 Utah Legislative Session. Legislative History: The 2009 Utah Legislature passed House Bill 331 entitled "Health Reform – Health Insurance Coverage in State Contracts" which law became effective July 1, 2009. This bill has been amended by HB20 of the 2010 Utah Legislative Session, HB 128 of the 2011 Utah Legislative Session as well as HB 282 of the 2016 Utah.

These laws require certain state entities, including DFCM, to require a contractor who contracts with the state entity to offer the contractor's employees qualified health insurance coverage as defined in Utah Code Annotated (UCA) 26-40-115, and in accordance with the commercially equivalent benchmark provided by the Department of Health, the CHIP commercial benchmark for FY 2016 and posted on the following URL: <http://www.health.utah.gov/chip/PDF/2016Benchmark.pdf>, in accordance with UCA 26-40-115(2), during the duration of the contract if the contract is over a certain amount, and if the contract is a construction and/or or design contract. The intent of the Articles of these Supplemental General Conditions is to provide the necessary provisions to the General Conditions as a result of such Bills. The purpose of this Supplemental General Conditions for Health Insurance is to comply with UCA 63A-5-205 as well as Utah Code Administrative Rule R23-23 which are both hereby incorporated by reference herein. In case of conflict between UCA 63A-5-205 and Rule R23-23, UCA 63A-5-205 shall control.

## **Article 2. Applicability of these Supplemental General Conditions.**

This Supplemental General Conditions for Health Insurance only applies to those contracts as required by UCA 63A-5-205.

As stated in UCA 63A- 5-205:

- (1) Except as provided in UCA 63A-5-205(4) below, UCA 63A-5- 205(3) applies to all design or construction contracts entered into by the Division or the Board on or after July 1, 2009, and
  - (a) applies to a prime contractor if the prime contract is in the amount of 2,000,000 or greater at the original execution of the contract; and
  - (b) applies to a subcontractor if the subcontract is in the amount of \$1,000,000 or greater at the original execution of the contract.
- (2) UCA 63A-5-205(3) does not apply if:
  - (a) the application of UCA 63A-5-205(3) jeopardizes the receipt of federal funds;
  - (b) the contract is a sole source contract;
  - (c) the contract is an emergency procurement;
  - (d) to a change order as defined in Section 63G-6a-103, or a modification to a contract, when the contract does not meet the threshold required by UCA 63A-5-205(3).

(3) A person who intentionally uses change order or contract modifications to circumvent the requirements of UCA 63A-5-205(3) is guilty of an infraction.

### **Article 3. Definitions.**

The following definitions apply to this Supplemental General Conditions for Health Insurance:

3.1 "Contractor" means the person/entity under direct contract with the Division herein. If the direct contract includes a Design Professional, then the Design Professional is a "Contractor" for purposes of this Supplemental General Conditions for Health Insurance.

3.2 "Design Professional" means the Architect or Engineer, its Subconsultants or Subcontractors at any tier, or any of their agents, employees, including those employed directly or indirectly, or other persons or entities for whose acts the Design Professional or its Subconsultants/Subcontractors at any tier may be liable.

3.3 "Employee(s)" means an "employee," "worker" or "operative" as defined in UCA 34A-2-104 who:

- (i) works at least 30 hours per calendar week; and
- (ii) meets employer eligibility waiting requirements for health care insurance which may not exceed the first day of the calendar month following 60 days from the date of hire.

3.4 "Health benefit plan" means the same as that term is defined in UCA 31A-1-301.

3.5 "Qualified health insurance coverage" means the same as that term is defined in UCA 26-40-115.

3.6 "Subcontractor" means the same as that term is defined in Section 63A-5-208.

3.7 "State" means the State of Utah.

3.8 "Director" includes an authorized designee of the Director.

### **Article 4. Health Insurance Certification.**

4.1 A Contractor (including Design Professional) shall demonstrate compliance with UCA 63A-5-205 (6)(a) or (b) at the time of execution of each initial contract described in UCA 63A-5-205(3). The compliance is subject to an audit by DAS, DFCM or the Office of the Legislative Auditor General. A Contractor (including Design Professional) subject to UCA Section 63A-5-205(3) shall demonstrate to the director that the Contractor has and will maintain an offer of qualified health insurance coverage for the Contractor's employees and employees' dependents. Such Certification shall be on the form provided by DFCM.

4.2 If a subcontractor of the contractor is subject to Subsection (3) of UCA 63A-5-205, the contractor shall:

(a) place a requirement in the subcontract that the subcontractor shall obtain and maintain an offer of qualified health insurance coverage for the subcontractor's employees and the employees' dependents during the duration of the subcontract; and

(b) certify to the director that the subcontractor has and will maintain an offer of qualified health insurance coverage for the subcontractor's employees and the employees' dependents during the duration of the prime contract.

4.3 The actuarially equivalent determination required for the qualified health insurance coverage is met by the Contractor if the Contractor provides the department or division with a written statement of actuarial equivalency, which is no more than one year old, regarding the contractor's offer of qualified health coverage from an actuary selected by the contractor or the contractor's insurer, or an underwriter who is responsible for developing the employer group's premium rates;



# **SUPPLEMENTAL** **GENERAL CONDITIONS** **REGARDING ILLEGAL IMMIGRATION**

May 10, 2011

**Article 1. Intent and Purpose. Senate Bill 81 modified by Senate Bill 39 – 2009.** The 2009 Utah Legislature passed Senate Bills 81 and 39 regarding “**Illegal Immigration**” which laws became effective July 1, 2009 (hereinafter “SB81/39”). The 2011 Utah Legislature made further amendments that relate to this document in HB 116. These bills deal with provisions related to the immigration status of individuals within the state. The intent of Articles 1 through 3 of these Supplemental General Conditions is to provide the necessary provisions to the General Conditions as a result of such bills.

**Article 2. Applicability.** These “Supplemental General Conditions for Illegal Immigration” under SB 39 of the 2009 Utah General Legislative Session and HB 116 of the 2011 Utah General Legislative Session, only applies to Request for Proposals and includes sole sources that are part of Requests for Proposals. However, all entities under contract with DFCM as well as all others that are subject to applicable immigration laws, including their subcontractors/subconsultants, at any tier, shall comply with all applicable immigration laws. This document does not apply to procurements that are done by the Competitive Sealed Bidding process (often referred to as “low-bid”), the Multi-Step Process, direct awards, sole sources awards that are not part of Requests for Proposals, and emergency procurements. This document also does not apply to good faith contract modifications to contracts that existed prior to July 1, 2009.

There is a Program Start Date defined in said HB 116 of the 2011 Utah General Legislative Session. At such time that knowledge is obtained about when that Program Start Date is, DFCM will post an amendment to this “Supplemental General Conditions Regarding Illegal Immigration.”

**Article 3. E-Verify Clause.** Certify registration and use of employment “Status Verification System”.

- 3.1 Each offeror and each person signing on behalf of any offeror certifies as to its own entity, under penalty of perjury, that the named Contractor has registered and is participating in the Status Verification System to verify the work eligibility status of the Contractor’s new employees that are employed in the State of Utah in accordance with 63G-12-302 as described in HB 116 of the 2011 Utah General Legislative Session. *(A copy of 63G-12-302 is provided at the end of this document for your convenience.)*
- 3.2 The Contractor shall require that the following provision be placed in each subcontract at every tier: “The subcontractor shall certify to the main (prime or general) contractor by affidavit that the subcontractor has verified through the Status Verification System the employment status of each

## **SUPPLEMENTAL GENERAL CONDITIONS FOR ILLEGAL IMMIGRATION**

**May 10, 2011**

**PAGE NO. 2**

new employee of the respective subcontractor, all in accordance with Section 63G-11-103 and to comply with all applicable employee status verification laws. Such affidavit must be provided prior to the notice to proceed for the subcontractor to perform the work.”

- 3.3 The State of Utah or DFCM will not consider a proposal for award, nor will it make any award where there has not been compliance with this Article.
- 3.4 Manually or electronically signing the Proposal is deemed the Contractor’s certification of compliance with all provisions of this employment status verification certification required by all applicable status verification laws including UCA Section 63G-12-302 as described in HB 116 of the 2011 Utah General Legislative Session. *(A copy of 63G-12-302 is provided at the end of this document for your convenience.)*

### **Article 4. Indemnity**

- 4.1 Contractor (includes, but is not limited to any Contractor, Design Professional, Designer or Consultant) shall protect, indemnify and hold harmless, the State of Utah, the DFCM and its officers, employees, agents, representatives and anyone that the State of Utah or the DFCM may be liable for, against any claim, damages or liability arising out of or resulting from violations of these Supplemental General Conditions Regarding Illegal Immigration whether violated by employees, agents, or contractors of the following:
  - 4.1.1 Contractor;
  - 4.1.2. Subcontractor at any tier; and/or
  - 4.1.3 any entity or person for whom the Contractor or Subcontractor may be liable.
- 4.2 Notwithstanding 4.1 above, Design Professionals or Designers under direct contract with the DFCM shall only be required to indemnify the State of Utah or the DFCM for a liability claim that arises out of the design professional's services, unless the liability claim arises from the Design Professional's negligent act, wrongful act, error or omission, or other liability imposed by law except that the Design Professional shall be required to indemnify the State of Utah or the DFCM in regard to subcontractors or subconsultants at any tier that are under the direct or indirect control or responsibility of the Design Professional, and includes all independent contractors, agents, employees or anyone else for whom the Design Professional may be liable at any tier.

**SUPPLEMENTAL GENERAL CONDITIONS FOR ILLEGAL IMMIGRATION**

**May 10, 2011**

**PAGE NO. 3**

**\* The following is provided for your convenience: Note: The definitions of "Public Employer," "Status Verification System," "Unauthorized Alien," and "Program Start Date" as well as other relevant definitions are located in Section 63G-12-102. Other provisions of Utah Code Title 63G, Chapter 12, should be read as well as all applicable immigration laws.)**

**63G-12-302. Status verification system -- Registration and use -- Performance of services -- Unlawful practice.**

(1) As used in this section:

(a) "Contract" means an agreement for the procurement of goods or services that is awarded through a request for proposals process with a public employer and includes a sole source contract.

(b) "Contractor" means a subcontractor, contract employee, staffing agency, or any contractor regardless of its tier.

(2) (a) Subject to Subsection (5), a public employer shall register with and use a Status Verification System to verify the federal employment authorization status of a new employee.

(b) This section shall be enforced without regard to race, religion, gender, ethnicity, or national origin.

(3) (a) Subject to Subsection (5), beginning July 1, 2009:

(i) a public employer may not enter into a contract for the physical performance of services within the state with a contractor unless the contractor registers and participates in the Status Verification System to verify the work eligibility status of the contractor's new employees that are employed in the state; and

(ii) a contractor shall register and participate in the Status Verification System in order to enter into a contract with a public employer.

(b) (i) For purposes of compliance with Subsection (3)(a), a contractor is individually responsible for verifying the employment status of only new employees who work under the contractor's supervision or direction and not those who work for another contractor or subcontractor, except as otherwise provided in Subsection (3)(b)(ii).

(ii) Each contractor or subcontractor who works under or for another contractor shall certify to the main contractor by affidavit that the contractor or subcontractor has verified through the Status Verification System the employment status of each new employee of the respective contractor or subcontractor.

(c) Subsection (3)(a) does not apply to a contract:

(i) entered into by the entities referred to in Subsection (3)(a) prior to July 1, 2009, even though the contract may involve the physical performance of services within the state on or after July 1, 2009; or

(ii) that involves underwriting, remarketing, broker-dealer activities, securities placement, investment advisory, financial advisory, or other financial or investment banking services.

(4) (a) It is unlawful for an employing entity in the state to discharge an employee working in Utah who is a United States citizen or permanent resident alien and replace the employee with, or have the employee's duties assumed by, an employee who:

(i) the employing entity knows, or reasonably should have known, is an unauthorized alien hired on or after July 1, 2009; and

(ii) is working in the state in a job category:

(A) that requires equal skill, effort, and responsibility; and

(B) which is performed under similar working conditions, as defined in 29 U.S.C., Sec. 206 (d)(1), as the job category held by the discharged employee.

(b) An employing entity, which on the date of a discharge in question referred to in Subsection (4)(a) is enrolled in and using the Status Verification System to verify the employment eligibility of its employees in Utah who are hired on or after July 1, 2009, is exempt from liability, investigation, or lawsuit arising from an action under this section.

(c) A cause of action for a violation of this Subsection (4) arises exclusively from the provisions of this Subsection (4).

(5) On and after the program start date:

(a) a public employer, after hiring an employee, shall verify the employment eligibility of the new employee:

(i) through the status verification system if the individual does not hold a permit; and

(ii) through the u-verify program if the individual holds a permit; and

(b) a contractor is considered to be in compliance with this section if, after hiring an employee, the contractor verifies the employment eligibility of the new employee:

(i) through the status verification system if the individual does not hold a permit; and

(ii) through the u-verify program if the individual holds a permit.

Renumbered and Amended by Chapter 18, 2011 General Session



# **SUPPLEMENTAL GENERAL CONDITIONS FOR CONSTRUCTION AGREEMENTS**

July 15, 2008

**Article 1. Intent and Purpose: Senate Bill 220 – 2008.**

The 2008 Utah Legislature passed Senate Bill 220 entitled “Cause of Action for Defective Construction” which law became effective May 5, 2008 (hereinafter “SB220”). The intent purpose of Article 1 through 3 of these Supplement General Conditions is to provide the necessary provisions to the General Conditions as a result of such Bill.

**Article 2. “Entities under the Contractor”** shall mean any and all agents, independent contractors, subcontractors, suppliers, manufacturers and providers at every tier under the General Contractor.

**Article 3. General Provisions**

**3.1 Conditions.** The General Conditions impose duties and performance obligations on the parties. This includes, but is not limited to, the provisions of Article 5.2.1 (regarding subcontractor’s compliance with Contract Documents), Article 4.13 (indemnification which discusses acts, omissions, and negligence responsibility) and other provisions of the General Conditions which list many performance obligations of the General Contractor and those under the General Contractor.

**3.2 Third Party Beneficiary.** The State of Utah and DFCM shall be an intended third party beneficiary to all contracts entered into with Entities under the Contractor. Upon written request by DFCM, DFCM shall be entitled to obtain copies of all such contracts. The General Contractor shall be responsible for assuring that all such third party beneficiary agreements are in place and shall bear the responsibility for any lack of required language in any contracts with an Entity under the Contractor which does not contain this required provision.

**3.3 “Economic Loss Rule.”** The “Economic Loss Rule” as it has been referred to in Utah law shall be deemed to be interpreted in accordance with prevailing Utah law.



- 3.4 Toxic Torts.** “Defective Construction” for purposes of any limitation of any cause of action or right as contemplated by SB220 does not, under these Supplemental General Conditions and for purposes of any Entities under the Contractor, include the use or installing of a defective or inherently dangerous, hazardous or toxic product, substance, or material. The State has third party beneficiary rights and other rights allowed by law to pursue a direct cause of action against the manufacturer and/or distributor of such defective or inherently dangerous, hazardous or toxic product, substance or material, except that the General Contractor and other subcontractors, exclusive of manufacturers and distributors, under the General Contractor shall not be responsible to the State of Utah for said “product, substance or material” unless the General Contractor or such subcontractor knew or should reasonably have known that the product, substance or material was defective or inherently dangerous, hazardous or toxic at the time it was provided or installed on the Project.
- 3.5 Subsection 3 of SB 220.** For purposes of Subsection (3) of SB 220, the phrase “property damage” shall be deemed to refer to damage to “other property” meaning property that is other than the exact specific construction defect itself.
- 3.6 “Failure of the Construction to Function as Designed.”** The language “failure to function as designed” as used in SB 220 shall not be deemed to refer to the failure of the construction to be constructed in accordance with the Contract Documents.
- 3.7 Independent Duty.** The State of Utah and DFCM maintain the right to pursue a cause of action against the General Contractor and directly against any Entities under the Contractor, for violation of any independent duty owed to the State of Utah or DFCM.
- 3.8 Not create Contract Right by Entity under the Contractor with State of Utah or DFCM.** These Supplemental General Conditions shall not be construed in any manner which would create a contract between the State of Utah/DFCM and any Entity under the Contractor, except for the Third Party Beneficiary rights of the State of Utah/DFCM provided herein. Any pursuit of a claim by an Entity under the Contractor, including payment claims, shall be maintained either against the payment bond or the upper tier Contractor in accordance with Utah law.

#### **Article 4. Warranties and Obligations**

Every Entity under the Contractor has an obligation to comply with the requirements of this Contract, including the indemnification of the Owner for negligent or intentional construction defects and to provide materials and construction that meets all express or implied warranties under the Uniform Commercial Code, including fitness for a particular purpose, merchantability, workmanlike construction (work completed in a skillful manner and is non-defective) and habitability, and is performed with the reasonable care to protect persons and property. In regard to toxic, hazardous materials and other matters of construction where applicable statutory and case law allows, strict liability shall apply.



# **SUPPLEMENTAL GENERAL CONDITIONS FOR DESIGN AGREEMENTS**

July 15, 2008

**Article 1. Intent and Purpose: Senate Bill 220 – 2008.**

The 2008 Utah Legislature passed Senate Bill 220 entitled “Cause of Action for Defective Construction” which law became effective May 5, 2008 (hereinafter “SB220”). The intent purpose of these Supplement General Conditions is to provide the necessary provisions to the General Conditions as a result of such Bill.

**Article 2. “Entities under the Designer”** shall mean any and all agents, independent contractors, consultants, subconsultants, subcontractors, suppliers, manufacturers and providers at every tier under the Designer.

**Article 3. General Provisions**

- 3.1 Design Agreement.** The Design Agreement for the subject Project imposes duties and performance obligations on the parties. This includes, but is not limited to, the standard of care provisions provided in said Design Agreement.
- 3.2 Third Party Beneficiary.** The State of Utah and DFCM shall be a third party beneficiary to all contracts entered into with Entities under the Designer. Upon written request by DFCM, DFCM shall be entitled to obtain copies of all such contracts. The Designer shall be responsible for assuring that all such third party beneficiary agreements are in place and shall bear the responsibility for any lack of required language in any contracts with an Entity under the Designer which does not contain this required provision.
- 3.3. “Economic Loss Rule.”** The “Economic Loss Rule” as it has been referred to in Utah law shall be deemed to be interpreted in accordance with prevailing Utah law.
- 3.4 Toxic Torts.** “Defective Construction” for purposes of any limitation of any cause of action or right as contemplated by SB220 does not, under these Supplemental General Conditions and for purposes of any Entities under the Designer, include the use or installing of a defective or inherently dangerous,

hazardous or toxic product, substance, or material. The State has third party beneficiary rights and other rights allowed by law to pursue a direct cause of action against the manufacturer and/or distributor of such defective or inherently dangerous, hazardous or toxic product, substance or material, except that the Designer and other consultants/subconsultants under the Designer, exclusive of manufacturers and distributors, shall not be responsible to the State of Utah for said “product, substance or material” unless the Designer or such consultants/subconsultants knew or should reasonably have known that the product, substance or material was defective or inherently dangerous, hazardous or toxic at the time it was made a part of the Contract Documents by the Designer.

- 3.5 Subsection 3 of SB 220.** For purposes of Subsection (3) of SB 220, the phrase “property damage” shall be deemed to refer to damage to “other property” meaning property that is other than the exact specific construction defect itself.
- 3.6 “Failure of the Construction to Function as Designed.”** The language “failure to function as designed” as used in SB 220 shall not be deemed to refer to the failure of the construction to be constructed in accordance with the Contract Documents.
- 3.7 Independent Duty.** The State of Utah and DFCM maintain the right to pursue a cause of action against the Designer and directly against any Entities under the Designer, for violation of any independent duty owed to the State of Utah or DFCM.
- 3.8 Not create Contract Right by Entity under the Designer with State of Utah or DFCM.** These Supplemental General Conditions shall not be construed in any manner which would create a contract between the State of Utah/DFCM and any Entity under the Designer, except for the Third Party Beneficiary rights of the State of Utah/DFCM provided herein. Any pursuit of a claim by an Entity under the Designer, including payment claims, shall be maintained against the upper tier entity in accordance with Utah law



**SUPPLEMENTAL GENERAL CONDITIONS**  
**FOR DRUG AND ALCOHOL TESTING**  
**DESIGN AND/OR CONSTRUCTION CONTRACTS**

July 1, 2010

1. These Supplemental General Conditions shall only apply to design or construction contracts in compliance with UCA Section 63G-6-604 and Utah Administrative Code Rule R23-7. (Note: the Administrative Rule is anticipated to have an effective date in early July, 2010 and will upon its being effective apply to those design and construction contracts issued on or after July 1, 2010, and the Statute itself is effective on July 1, 2010.) All applicable provisions of UCA Section 63G-6-604 and Utah Administrative Code Rule R23-7 are incorporated herein by reference as if fully set forth herein. The provisions below provide some, but not all of the provisions of said statute and administrative rule. The absence of the recitation of a provision of UCA Section 63G-6-604 or Utah Administrative Code Rule R23-7 below, shall not lessen its importance. Contractors and Designers are encouraged to read the complete UCA Section 63G-6-604 and Utah Administrative Code Rule R23-7 in order to assure compliance with all the applicable provisions.

2. Definitions. For the purpose of these Supplemental General Conditions, the definitions in UCA Section 63G-6-604 and Utah Administrative Code Rule R23-7 shall apply. For convenience, the following definitions are provided below:

a. **“Contractor” for purposes of these Supplemental General Conditions includes the Prime Contractor, a Designer (Architect/Engineer), and any of their subcontractors, consultants or subconsultants at any tier involved in design and/or construction. “Contractor” for purposes of these Supplemental General Conditions does not include a supplier who provide only materials, equipment or supplies to a Contractor, Designer or any of their subcontractors, consultants or subconsultants at any tier.**

b. "Covered Individual" means an individual who: (i) on behalf of the Contractor provides services directly related to design or construction under the contract; and (ii) is in a safety sensitive position, including a design position that has responsibilities that directly affect the safety of an improvement to real property that is the subject of a state construction contract

3. Contractor shall have a drug and alcohol testing policy in accordance with UCA Section 63G-6-604 and Utah Administrative Code Rule R23-7 during the period of the contract that applies to the “Covered Individuals” hired by the Contractor. Contractor shall post in one or more conspicuous places notice

**SUPPLEMENTAL GENERAL CONDITIONS FOR DRUG AND ALCOHOL TESTING**  
**JULY 1, 2010**  
**PAGE NO. 2**

to “Covered Individuals” hired by the Contractor that the Contractor has the drug and alcohol testing policy described in UCA Section 63G-6-604 and Utah Administrative Code Rule R23-7-4(1)(a)(i). Said “Covered Individuals” shall be subject to random drug and alcohol testing under said policy if at any time during the period of the contract there are ten (10) or more “Covered Individuals” hired by the Contractor.

4. Contractor hereby certifies the following:

a. By executing this Contract, that the Contractor, including all entities included in the definition of Contractor in paragraph 2.a. above, shall comply with all provisions of Utah Administrative Code Rule R23-7 as well as UCA 63G-6-604, including having and maintaining a drug and alcohol testing policy, the posting and random testing requirements during the period of the contract that applies to Covered Individuals hired by the Contractor, including all entities included in the definition of Contractor in paragraph 2.a. above;

b. That the Contractor, including all entities included in the definition of Contractor in paragraph 2.a. above, shall have these requirements placed in all subcontracts for design or construction at any tier, in order that all such subcontractors, consultants and subconsultants at any tier have notice of these requirements and understand the need for compliance with these requirements;

c. That the subcontractors, consultants and subconsultants at any tier referred to in paragraph 4.b. above shall comply with the same requirements as the Contractor for having and maintaining a drug and alcohol testing policy, the posting and random testing requirements during the period of their contract;

d. That the Contractor, or any entity included in the definition of Contractor in paragraph 2.a. above may be suspended or debarred in accordance with the Utah Procurement Code for failure to comply as provided in UCA Section 63G-6-604(3)(a) and Utah Administrative Code Rule R23-7-4(3)(b); and

e. That the prime contractor or prime designer shall on a semi-annual basis throughout the term of this Contract, report to the Division in writing, information that indicates compliance with the provisions of UCA Section 63G-6-604 and Utah Administrative Code Rule R23-7.

5. Reasonable notice and an opportunity to cure any violation of UCA 63G-6-604 shall be provided to the Contractor before any suspension or debarment may be undertaken by the Division against the Contractor in light of the circumstances of the Contract or the violation. The greater the risk to person(s) or property as a result of noncompliance, the shorter this notice and opportunity to cure shall be, including the possibility that the notice may provide for immediate compliance if necessary to protect person(s) or property.

6. If a Contractor meets the requirements of UCA Section 63G-6-604 and Utah Administrative Code Rule R23-7, said statute and rule may not be construed to restrict the Contractor’s ability to impose or implement an otherwise lawful provision as part of a drug and alcohol testing policy.

## SECTION 01 1000 - SUMMARY

### PART 1 - GENERAL

#### 1.1 SUMMARY

##### A. Section Includes:

1. Project information.
2. Work covered by Contract Documents.
3. Work under separate contracts.
4. Owner-furnished products.
5. Access to site.
6. Coordination with occupants.
7. Work restrictions.
8. Specification and drawing conventions.

##### B. Related Requirements:

1. Section 01 5000 "Temporary Facilities and Controls" for limitations and procedures governing temporary use of Owner's facilities.

#### 1.2 PROJECT INFORMATION

##### A. Project Identification: ACC Level 3 OR Expansion.

1. FFKR Project Number 22042.
2. Project Location: University of Utah Hospital, 50 North Medical Drive, Salt Lake City, UT 84112.

##### B. Owner: State of Utah; University of Utah.

1. Owner Project Number: 70403

##### C. Architect: FFKR Architects, 730 Pacific Avenue, Salt Lake City, Utah 84104, (801) 521-6186.

1. Contact: Michael Dolan / Rachel McKenzie Hansen

##### D. Construction Manager, general Contractor (CMGC): Gramoll Construction.

##### E. Project Web Site: Unifier, administered by University of Utah. Submittals, RFIs, Proposal Requests, ASIs, CCDs, and Change Orders received through Unifier.

1.3 WORK COVERED BY CONTRACT DOCUMENTS

- A. The Overall Work of Project: Remodel of the Existing OR Suite to include 2 New additional ORs.
- B. Type of Contract:
  - 1. Project will be constructed under a single prime contract.

1.4 WORK UNDER SEPARATE CONTRACTS

- A. General: Cooperate fully with separate contractors so work on those contracts may be carried out smoothly, without interfering with or delaying Work under this Contract or other contracts. Coordinate the Work of this Contract with work performed under separate contracts.

1.5 OWNER-FURNISHED PRODUCTS

- A. Owner will furnish products indicated. The Work includes receiving, unloading, handling, storing, protecting, and installing Owner-furnished products and making building services connections.
- B. Owner-Furnished Products:
  - 1. Furnishings, appliances, equipment, and other items as coordinated with Owner and as shown on the responsibility matrix.

1.6 ACCESS TO SITE

- A. General: Contractor shall have limited use of Project site for construction operations as indicated on Drawings by the Contract limits and as indicated by requirements of this Section.
- B. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.9 Use of Site; 4.9.1 in General.
- C. See University of Utah U Facilities; General Conditions; Article 2 The University; 2.2 Construction by the University or by Separate Contractors; 2.2.1 University's Right to Perform Construction and to Award Separate Contracts.
- D. Use of Site: Limit use of Project site to areas within the Contract limits indicated. Do not disturb portions of Project site beyond areas in which the Work is indicated.
  - 1. Driveways, Walkways and Entrances: Keep driveways and entrances serving premises beyond the construction fencing clear and available to Owner, Owner's employees, and emergency vehicles at all times. Do not use these areas for parking or storage of materials.

- a. Schedule deliveries to minimize use of driveways and entrances by construction operations.
- b. Schedule deliveries to minimize space and time requirements for storage of materials and equipment on-site.
- c. Coordinate construction activities outside the construction fence and within the contract limits with the Owner, Architect, and adjacent property users prior to commencing the Work.

## 1.7 WORK RESTRICTIONS

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.9 Use of Site; 4.9.2 Access to Neighboring Properties.
- B. Work Restrictions, General: Comply with restrictions on construction operations.
  1. Comply with limitations on use of public streets and with other requirements of authorities having jurisdiction.
  2. Project is located within a working Trauma Medical Center. Coordinate Work with Owner to assure that Work is performed with sensitivity to the needs of Trauma Center patients and employees.
    - a. To the extent possible, minimize duration of Work with high noise and vibration levels.
    - b. Advise Owner of times when Work will be performed that requires high noise or vibration levels.
    - c. Perform Work that requires high noise and vibration levels at times acceptable to Owner.
- C. Nonsmoking Building / Campus: Smoking is not permitted within the building or anywhere on the University of Utah Campus.
- D. Controlled Substances: Use of tobacco products and other controlled substances on Project site is not permitted.
- E. Employee Identification: All Contractor personnel will be required to obtain University of Utah identification badges. Provide identification tags for Contractor personnel working on Project site. Require personnel to use identification tags at all times.
- F. Employee Screening: Comply with Owner's requirements for drug and background screening of Contractor personnel working on Project site.
  1. Maintain list of approved screened personnel with Owner's representative.



## 1.8 SPECIFICATION AND DRAWING CONVENTIONS

- A. Specification Content: The Specifications use certain conventions for the style of language and the intended meaning of certain terms, words, and phrases when used in particular situations. These conventions are as follows:
  - 1. Imperative mood and streamlined language are generally used in the Specifications. The words "shall," "shall be," or "shall comply with," depending on the context, are implied where a colon (:) is used within a sentence or phrase.
  - 2. Specification requirements are to be performed by Contractor unless specifically stated otherwise.
- B. Division 01 General Requirements: Requirements of Sections in Division 01 apply to the Work of all Sections in the Specifications.
- C. Drawing Coordination: Requirements for materials and products identified on Drawings are described in detail in the Specifications. One or more of the following are used on Drawings to identify materials and products:
  - 1. Terminology: Materials and products are identified by the typical generic terms used in the individual Specifications Sections.
  - 2. Keynoting: Materials and products are identified by reference keynotes referencing Specification Section numbers found in this Project Manual.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 1000

## SECTION 01 2500 - SUBSTITUTION PROCEDURES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for substitutions.
- B. Related Requirements:
  - 1. Section 01 6000 "Product Requirements" for requirements for submitting comparable product submittals for products by listed manufacturers.

#### 1.3 DEFINITIONS

- A. Substitutions: Changes in products, materials, equipment, and methods of construction from those required by the Contract Documents and proposed by Contractor.
  - 1. Substitutions for Cause: Changes proposed by Contractor that are required due to changed Project conditions, such as unavailability of product, regulatory changes, or unavailability of required warranty terms.
  - 2. Substitutions for Convenience: Changes proposed by Contractor or Owner that are not required in order to meet other Project requirements but may offer advantage to Contractor or Owner.

#### 1.4 ACTION SUBMITTALS

- A. Proposed Products List and Substitution Requests:
  - 1. Intent:
    - a. To fully identify, prior to beginning the Work, the products Contractor intends to provide, and substitutions the Contractor requests.
    - b. To facilitate timely submittal processing by avoiding rejection of unacceptable products and unspecified products later during construction.
  - 2. Proposed Products List:

- a. Within 14 calendar days after date of receipt of notice to proceed and before submitting any Product Submittals, submit for approval the list of the products proposed for installation. Include the name of the manufacturer for each product and, where applicable, the name of Subcontractor.
- b. The list shall be tabulated by and be complete for each Specification Section.
- c. For each product listed, clearly indicate: a) As Specified, or b) Not As Specified. For each product designated Not As Specified, clearly indicate: c) Comparable Product, or d) Proposed Substitution.

B. Substitution Requests Accompanying the Proposed Products List:

1. A request for substitution will be considered, subject to the following requirements:
  - a. Include with the proposed products list a completed substitution request form for each proposed substitution anticipated for the Project. Check the box indicating the request is submitted with the proposed products list.
  - b. Submit each proposed substitution using a separate copy of the substitution request form. Use substitution request form included in the Project Manual, or request form from the Architect. See Section 01 2510 Substitution Request Form. Submit in number of copies specified for proposed product list.
  - c. The substitution request is submitted at the time the proposed products list is submitted. A request submitted after the time set for submittal of the proposed products list is subject to automatic rejection.
  - d. Include with the request complete data on the proposed substitution. Such data shall include:
    - 1) Product Data highlighted to show applicability to the proposed substitution and project conditions.
    - 2) Performance and test data.
    - 3) References, and samples, where applicable.
    - 4) An itemized comparison of the proposed substitution with the product features specified in the Contract Documents, including data relating to design and artistic effect, where applicable.
  - e. Include copies of the pertinent Contract Documents, clearly marked and highlighted to show changes necessary to accommodate the proposed substitution.
  - f. If the proposed substitution is due to unavailability of a specified product, a written statement shall accompany it, written by the supplier of the specified product, confirming lack of availability.
  - g. By submitting the substitution request, Contractor affirms that: 1) the proposed substitution conforms to the required dimensions and meets or exceeds the standards of required function, appearance, and quality set by the specified product: and 2) the burden of proof rests with the Contractor.
  - h. By submitting a substitution request, Contractor agrees to absorb all costs resulting from acceptance of the proposed substitution, including both known and subsequently discovered revisions to other construction needed to accommodate the substitution, and other expected and unforeseen costs, such as delays, code approval-related expenses, and additional architectural services.

C. Substitution Requests After Proposed Products List:

1. Use no product in the Work that is not named in the Contract Documents, or not listed in the Proposed Products List, or not approved as a substitute or comparable product. Products specified solely by reference standard or performance requirements do not require naming.
2. During construction of the Work, products not listed on the accepted Proposed Products List shall not be used without receipt of an approved substitution request for a listed product. A substitution request will be considered under one of the following conditions:
  - a. The product listed on the accepted Proposed Product List becomes unavailable. Include with the substitution request a letter from the listed manufacturer, on the manufacturer's letterhead, verifying that the product is no longer available.
  - b. Conditions uncovered at the Site render the listed product inappropriate, or an undesirable choice for the conditions uncovered. Include with the substitution request a full description of the uncovered conditions and why the requested substitution is preferable to the listed product.
3. Make each substitution request on the specified substitution request form. Fully execute form in accordance with the provisions of Article, Proposed Products List and Accompanying Substitution Requests, except for provisions requiring submittal concurrent with proposed products list. Check the box indicating the Contractor's request is being submitted separate from and after submittal of the proposed products list

D. A request for substitution forwarded by the Contractor means that Contractor:

1. Has investigated the proposed substitution.
2. Has determined that the substitution is equal to or superior in quality and serviceability (performance) to the product specified in the Contract Documents.
3. Will provide the same guarantee for the substitution that is required for the product specified in the Contract Documents.
4. Waives all claims for additional costs that subsequently become apparent as a result of the substitution.
5. Will coordinate the installation of the accepted substitution into the Work, and will make such changes in the Work of the various trades as may be required to provide a completed condition.

E. A request for a substitution will not be considered if:

1. The substitution is merely indicated or implied on the Shop Drawing or Product Data submittal without the specified formal request and documented proof of conformance. Submittal approvals for items not meeting specifications are not valid. Completed construction related to such items is subject to rejection.
2. Implementation requires a major revision of the Contract Documents in order to accommodate the substitution.
3. The substitution request is substantially incomplete.

F. Architect's Review of Proposed Products List and Substitution Requests:

1. The Architect will review properly submitted proposed products list and accompanying substitution requests.
2. The Architect will evaluate each substitution request and inform Contractor in writing whether the proposed substitution is accepted, accepted as noted, or not accepted.
  - a. Substitution requests that do not conform to requirements, including submittal timing, are subject to return without review.
  - b. A substitution will not be considered accepted by the Owner until it has been documented by Change Order.
3. The Architect's decision as to conformance and acceptability will be consistent with the intent of the Contract Documents.
4. In the absence of written acceptance of a substitution request, proposed substitutions shall be understood as not accepted.
5. The Architect will endeavor to evaluate the substitution request in a reasonable period of time. With the request, the Contractor shall inform the Architect of the deadline for final decision on the request. In the absence of Architect's decision within the critical time, the Contractor shall proceed with the specified product.

G. Product List and Substitution Request Format:

1. Product List: Provide PDF of the list.
2. Substitution Requests: Provide PDF of requests.

1.5 QUALITY ASSURANCE

- A. Compatibility of Substitutions: Investigate and document compatibility of proposed substitution with related products and materials. Engage a qualified testing agency to perform compatibility tests recommended by manufacturers.

1.6 PROCEDURES

- A. Coordination: Revise or adjust affected work as necessary to integrate work of the approved substitutions.

1.7 SUBSTITUTIONS

- A. Substitutions for Cause: Submit requests for substitution immediately on discovery of need for change, but not later than 15 days prior to time required for preparation and review of related submittals.
1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:

- a. Requested substitution is consistent with the Contract Documents and will produce indicated results.
  - b. Substitution request is fully documented and properly submitted.
  - c. Requested substitution will not adversely affect Contractor's construction schedule.
  - d. Requested substitution has received necessary approvals of authorities having jurisdiction.
  - e. Requested substitution is compatible with other portions of the Work.
  - f. Requested substitution has been coordinated with other portions of the Work.
  - g. Requested substitution provides specified warranty.
  - h. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.
- B. Substitutions for Convenience: Not allowed unless otherwise indicated.
- C. Substitutions for Convenience: Architect will consider requests for substitution if received within days after the Notice to Proceed. Requests received after that time may be considered or rejected at discretion of Architect.
  - 1. Conditions: Architect will consider Contractor's request for substitution when the following conditions are satisfied. If the following conditions are not satisfied, Architect will return requests without action, except to record noncompliance with these requirements:
    - a. Requested substitution offers Owner a substantial advantage in cost, time, energy conservation, or other considerations, after deducting additional responsibilities Owner must assume. Owner's additional responsibilities may include compensation to Architect for redesign and evaluation services, increased cost of other construction by Owner, and similar considerations.
    - b. Requested substitution does not require extensive revisions to the Contract Documents.
    - c. Requested substitution is consistent with the Contract Documents and will produce indicated results.
    - d. Substitution request is fully documented and properly submitted.
    - e. Requested substitution will not adversely affect Contractor's construction schedule.
    - f. Requested substitution has received necessary approvals of authorities having jurisdiction.
    - g. Requested substitution is compatible with other portions of the Work.
    - h. Requested substitution has been coordinated with other portions of the Work.
    - i. Requested substitution provides specified warranty.
    - j. If requested substitution involves more than one contractor, requested substitution has been coordinated with other portions of the Work, is uniform and consistent, is compatible with other products, and is acceptable to all contractors involved.

ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84132

Code Review

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 2500

SECTION 01 2510 - SUBSTITUTION REQUEST FORM

Project: Refer to page header above. Additional Package/Contract Info: \_\_\_\_\_

Date of Request:            CM/GC Tracking No.:        AE Tracking No.:

This substitution request is governed by the provisions of Section 01 2500.

☐ This Substitution Request is submitted during the bidding period.

☐ This Substitution Request is submitted with Proposed Products List dated: \_\_\_\_\_

☐ This Substitution Request is submitted separate from and after submittal of the Proposed Products List.

RE:

| Specifications Section Title | Section No. | Page | Paragraph |
|------------------------------|-------------|------|-----------|
|------------------------------|-------------|------|-----------|

PROPOSED SUBSTITUTION:

This substitution request is governed by, and complies with, the provisions of Section 01 2500 "Substitution Procedures."

Reason for Substitution:    ☐ For Cause                      ☐ For Convenience

General Description:

The accompanying attachments, per the provisions governing substitutions, provide a full description of the proposed substitution. The proposed substitution includes the following changes:

☐ To Contract Sum:    ☐ None    ☐ Add:    ☐ Deduct: \$

☐ To Contract Time:    ☐ None    ☐ Add:    ☐ Deduct: ☐ days

Assumption of Responsibility for Equal Performance

The Construction Manager/General Contractor that is submitting this request affirms that the proposed substitution conforms to required dimensions and meets or exceeds the standards of required function, appearance, and quality established by the specified product. Requester understands and affirms compliance with the provisions governing substitutions.

Requester's Name:                                              Date:

Requesting Firm: CM or CG only

Notes:

1. Transmit substitution request to Architect's Project Manager.
2. Do not transmit substitution request as part of product submittal.
3. Do not transmit product submittal for substitution item until substitution is accepted by Owner and Architect.
4. Owner's Acceptance of substitution request is not complete until documented through addendum or contract modification.

ARCHITECT'S REVIEW:

Proposed substitution is: ☐ Not Reviewed    ☐ Not Accepted    ☐ Accepted As Noted    ☐ Accepted

Remarks:



ACC LEVEL 3 OR EXPANSION REMODEL

Code Review

University of Utah

Salt Lake City, Utah 84132

Name Date

cc: Owner; CM/GC, project specifier

OWNER'S REVIEW:

Proposed substitution is: ☐ Not Reviewed ☐ Not Accepted ☐ Accepted As Noted ☐ Accepted

Remarks:

Name Date

cc: Architect; CM/GC, project specifier

END OF SECTION 01 2500

## SECTION 01 2600 - CONTRACT MODIFICATION PROCEDURES

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for handling and processing Contract modifications.
- B. Related Requirements:
  - 1. Section 01 2500 "Substitution Procedures" for administrative procedures for handling requests for substitutions made after the Contract award.

#### 1.2 MINOR CHANGES IN THE WORK

- A. Architect will issue supplemental instructions authorizing minor changes in the Work, not involving adjustment to the Contract Sum or the Contract Time, through Unifier.

#### 1.3 PROPOSAL REQUESTS

- A. Owner-Initiated Proposal Requests: Architect will issue a detailed description of proposed changes in the Work that may require adjustment to the Contract Sum or the Contract Time. If necessary, the description will include supplemental or revised Drawings and Specifications.
  - 1. Work Change Proposal Requests issued by Architect are not instructions either to stop work in progress or to execute the proposed change.
  - 2. Within time specified in Proposal Request or 20 days, when not otherwise specified, after receipt of Proposal Request, submit a quotation estimating cost adjustments to the Contract Sum and the Contract Time necessary to execute the change.
    - a. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
    - b. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
    - c. Include costs of labor and supervision directly attributable to the change.
    - d. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
    - e. Quotation Form: Submit through Unifier.

- B. Contractor-Initiated Proposals: If latent or changed conditions require modifications to the Contract, Contractor may initiate a claim by submitting a request for a change to Architect.
  - 1. Include a statement outlining reasons for the change and the effect of the change on the Work. Provide a complete description of the proposed change. Indicate the effect of the proposed change on the Contract Sum and the Contract Time.
  - 2. Include a list of quantities of products required or eliminated and unit costs, with total amount of purchases and credits to be made. If requested, furnish survey data to substantiate quantities.
  - 3. Indicate applicable taxes, delivery charges, equipment rental, and amounts of trade discounts.
  - 4. Include costs of labor and supervision directly attributable to the change.
  - 5. Include an updated Contractor's construction schedule that indicates the effect of the change, including, but not limited to, changes in activity duration, start and finish times, and activity relationship. Use available total float before requesting an extension of the Contract Time.
  - 6. Comply with requirements in Section 01 2500 "Substitution Procedures" if the proposed change requires substitution of one product or system for product or system specified.
  - 7. Proposal Request Form: Submit through Unifier.

#### 1.4 CHANGE ORDER PROCEDURES

- A. On Owner's approval of a Work Changes Proposal Request, Architect will issue a Change Order for signatures of Owner and Contractor through Unifier.

#### 1.5 CONSTRUCTION CHANGE DIRECTIVE

- A. Construction Change Directive: Architect may issue a Construction Change Directive through Unifier. Construction Change Directive instructs Contractor to proceed with a change in the Work, for subsequent inclusion in a Change Order.
  - 1. Construction Change Directive contains a complete description of change in the Work. It also designates method to be followed to determine change in the Contract Sum or the Contract Time.
- B. Documentation: Maintain detailed records on a time and material basis of work required by the Construction Change Directive.
  - 1. After completion of change, submit an itemized account and supporting data necessary to substantiate cost and time adjustments to the Contract.

ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84132

Code Review

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 2600

## SECTION 01 2900 - PAYMENT PROCEDURES

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements necessary to prepare and process Applications for Payment.
- B. Related Requirements:
  - 1. Section 01 2600 "Contract Modification Procedures" for administrative procedures for handling changes to the Contract.
  - 2. Section 01 3200 "Construction Progress Documentation" for administrative requirements governing the preparation and submittal of the Contractor's construction schedule.

#### 1.2 DEFINITIONS

- A. Schedule of Values: A statement furnished by Contractor allocating portions of the Contract Sum to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.

#### 1.3 SCHEDULE OF VALUES

- A. Coordination: Coordinate preparation of the schedule of values with preparation of Contractor's construction schedule.
  - 1. Coordinate line items in the schedule of values with other required administrative forms and schedules, including the following:
    - a. Application for Payment forms with continuation sheets.
    - b. Submittal schedule.
    - c. Items required to be indicated as separate activities in Contractor's construction schedule.
    - d. Schedule of Values to match with Schedule of values in Unifier.
  - 2. Submit the schedule of values to Architect at earliest possible date, but no later than 30 days before the date scheduled for submittal of initial Applications for Payment.
- B. Format and Content: Use Project Manual table of contents as a guide to establish line items for the schedule of values. Provide at least one line item for each Specification Section.
  - 1. Identification: Include the following Project identification on the schedule of values:

- a. Project name and location.
  - b. Name of Architect.
  - c. Architect's project number.
  - d. Contractor's name and address.
  - e. Date of submittal.
2. Arrange schedule of values consistent with format of AIA Document G703.
3. Arrange the schedule of values in tabular form with separate columns to indicate the following for each item listed:
  - a. Related Specification Section or Division.
  - b. Description of the Work.
  - c. Name of subcontractor.
  - d. Name of manufacturer or fabricator.
  - e. Name of supplier.
  - f. Change Orders (numbers) that affect value.
  - g. Dollar value of the following, as a percentage of the Contract Sum to nearest one-hundredth percent, adjusted to total 100 percent.
    - 1) Labor.
    - 2) Materials.
    - 3) Equipment.
4. Provide a breakdown of the Contract Sum in enough detail to facilitate continued evaluation of Applications for Payment and progress reports. Coordinate with Project Manual table of contents. Provide multiple line items for principal subcontract amounts in excess of five percent of the Contract Sum.
  - a. Include separate line items under Contractor and principal subcontracts for Project closeout requirements in an amount totaling five percent of the Contract Sum and subcontract amount.
5. Round amounts to nearest whole dollar; total shall equal the Contract Sum.
6. Provide a separate line item in the schedule of values for each part of the Work where Applications for Payment may include materials or equipment purchased or fabricated and stored, but not yet installed.
  - a. Differentiate between items stored on-site and items stored off-site. Include evidence of insurance.
7. Provide separate line items in the schedule of values for initial cost of materials, for each subsequent stage of completion, and for total installed value of that part of the Work.
8. Each item in the schedule of values and Applications for Payment shall be complete. Include total cost and proportionate share of general overhead and profit for each item.
  - a. Temporary facilities and other major cost items that are not direct cost of actual work-in-place may be shown either as separate line items in the schedule of values or distributed as general overhead expense, at Contractor's option.

9. Schedule Updating: Update and resubmit the schedule of values before the next Applications for Payment when Change Orders or Construction Change Directives result in a change in the Contract Sum.

#### 1.4 APPLICATIONS FOR PAYMENT

- A. Each Application for Payment following the initial Application for Payment shall be consistent with previous applications and payments as certified by Architect and paid for by Owner.
  1. Initial Application for Payment, Application for Payment at time of Substantial Completion, and final Application for Payment involve additional requirements.
- B. Payment Application Times: The period covered by each Application for Payment is one month, ending on the last day of the month.
  1. Submit draft copy of Application for Payment seven days prior to due date for review by Architect.
- C. Application for Payment Forms: Use University of Utah Application and Certificate of Payment as form for Applications for Payment.
- D. Application Preparation: Complete every entry on form. Notarize and execute by a person authorized to sign legal documents on behalf of Contractor. Architect will return incomplete applications without action.
  1. Entries shall match data on the schedule of values and Contractor's construction schedule. Use updated schedules if revisions were made.
  2. Include amounts for work completed following previous Application for Payment, whether or not payment has been received. Include only amounts for work completed at time of Application for Payment.
  3. Include amounts of Change Orders and Construction Change Directives issued before last day of construction period covered by application.
  4. Indicate separate amounts for work being carried out under Owner-requested project acceleration.
- E. Stored Materials: Include in Application for Payment amounts applied for materials or equipment purchased or fabricated and stored, but not yet installed. Differentiate between items stored on-site and items stored off-site.
  1. Provide certificate of insurance, evidence of transfer of title to Owner, and consent of surety to payment, for stored materials.
  2. Provide supporting documentation that verifies amount requested, such as paid invoices. Match amount requested with amounts indicated on documentation; do not include overhead and profit on stored materials.
  3. Provide summary documentation for stored materials indicating the following:
    - a. Value of materials previously stored and remaining stored as of date of previous Applications for Payment.

- b. Value of previously stored materials put in place after date of previous Application for Payment and on or before date of current Application for Payment.
  - c. Value of materials stored since date of previous Application for Payment and remaining stored as of date of current Application for Payment.
- F. Transmittal: Submit one signed and notarized copy of each Application for Payment to Architect by a method ensuring receipt within 24 hours. Include waivers of lien and similar attachments if required.
  - 1. Transmit each copy with a transmittal form listing attachments and recording appropriate information about application.
- G. Waivers of Mechanic's Lien: With each Application for Payment, submit waivers of mechanic's liens from subcontractors, sub-subcontractors, and suppliers for construction period covered by the previous application.
  - 1. Submit partial waivers on each item for amount requested in previous application, after deduction for retainage, on each item.
  - 2. When an application shows completion of an item, submit conditional final or full waivers.
  - 3. Owner reserves the right to designate which entities involved in the Work must submit waivers.
  - 4. Submit final Application for Payment with or preceded by conditional final waivers from every entity involved with performance of the Work covered by the application who is lawfully entitled to a lien.
  - 5. Waiver Forms: Submit executed waivers of lien on forms, acceptable to Owner.
- H. Initial Application for Payment: Administrative actions and submittals that must precede or coincide with submittal of first Application for Payment include the following:
  - 1. List of subcontractors.
  - 2. Schedule of values.
  - 3. Contractor's construction schedule (preliminary if not final).
  - 4. Combined Contractor's construction schedule (preliminary if not final) incorporating Work of multiple contracts, with indication of acceptance of schedule by each Contractor.
  - 5. Products list (preliminary if not final).
  - 6. Submittal schedule (preliminary if not final).
  - 7. List of Contractor's staff assignments.
  - 8. List of Contractor's principal consultants.
  - 9. Copies of building permits.
  - 10. Copies of authorizations and licenses from authorities having jurisdiction for performance of the Work.
  - 11. Initial progress report.
  - 12. Report of preconstruction conference.
  - 13. Certificates of insurance and insurance policies.
  - 14. Performance and payment bonds.
  - 15. Data needed to acquire Owner's insurance.



- I. Application for Payment at Substantial Completion: After Architect issues the Certificate of Substantial Completion, submit an Application for Payment showing 100 percent completion for portion of the Work claimed as substantially complete.
  - 1. Include documentation supporting claim that the Work is substantially complete and a statement showing an accounting of changes to the Contract Sum.
  - 2. This application shall reflect Certificate(s) of Substantial Completion issued previously for Owner occupancy of designated portions of the Work.
- J. Final Payment Application: After completing Project closeout requirements, submit final Application for Payment with releases and supporting documentation not previously submitted and accepted, including, but not limited, to the following:
  - 1. Evidence of completion of Project closeout requirements.
  - 2. Insurance certificates for products and completed operations where required and proof that taxes, fees, and similar obligations were paid.
  - 3. Updated final statement, accounting for final changes to the Contract Sum.
  - 4. AIA Document G706, "Contractor's Affidavit of Payment of Debts and Claims."
  - 5. AIA Document G706A, "Contractor's Affidavit of Release of Liens."
  - 6. AIA Document G707, "Consent of Surety to Final Payment."
  - 7. Evidence that claims have been settled.
  - 8. Final meter readings for utilities, a measured record of stored fuel, and similar data as of date of Substantial Completion or when Owner took possession of and assumed responsibility for corresponding elements of the Work.
  - 9. Final liquidated damages settlement statement.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 2900

## SECTION 01 3100 - PROJECT MANAGEMENT AND COORDINATION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative provisions for coordinating construction operations on Project including, but not limited to, the following:
  - 1. General coordination procedures.
  - 2. Coordination drawings.
  - 3. Requests for Information (RFIs).
  - 4. Project Document Transfer site.
  - 5. Project meetings.
- B. Each contractor shall participate in coordination requirements. Certain areas of responsibility are assigned to a specific contractor.
- C. Related Requirements:
  - 1. Section 01 3200 "Construction Progress Documentation" for preparing and submitting Contractor's construction schedule.
  - 2. Section 01 7300 "Execution" for procedures for coordinating general installation and field-engineering services, including establishment of benchmarks and control points.
  - 3. Section 01 7700 "Closeout Procedures" for coordinating closeout of the Contract.
  - 4. Section 01 9113 "General Commissioning Requirements" for coordinating the Work with Owner's Commissioning Authority.

#### 1.2 DEFINITIONS

- A. RFI: Request from Owner, Architect, or Contractor seeking information required by or clarifications of the Contract Documents.

#### 1.3 INFORMATIONAL SUBMITTALS

- A. See University of Utah U Facilities; General Conditions; Article 5 Subcontractors; 5.1 Award of Subcontracts and Other Contracts for Portions of the Work; 5.1.1.2.
- B. Subcontract List: Prepare a written summary identifying individuals or firms proposed for each portion of the Work, including those who are to furnish products or equipment fabricated to a special design. Use CSI Form 1.5A. Include the following information in tabular form:
  - 1. Name, address, and telephone number of entity performing subcontract or supplying products.

2. Number and title of related Specification Section(s) covered by subcontract.
3. Drawing number and detail references, as appropriate, covered by subcontract.

C. Key Personnel Names: Within 15 days of starting construction operations, submit a list of key personnel assignments, including superintendent and other personnel in attendance at Project site. Identify individuals and their duties and responsibilities; list addresses and telephone numbers, including home, office, and cellular telephone numbers and e-mail addresses. Provide names, addresses, and telephone numbers of individuals assigned as alternates in the absence of individuals assigned to Project.

1. Post copies of list in project meeting room, in temporary field office, and by each temporary telephone. Keep list current at all times.

#### 1.4 GENERAL COORDINATION PROCEDURES

A. Coordination: Coordinate construction operations included in different Sections of the Specifications to ensure efficient and orderly installation of each part of the Work. Coordinate construction operations, included in different Sections, that depend on each other for proper installation, connection, and operation.

1. Schedule construction operations in sequence required to obtain the best results where installation of one part of the Work depends on installation of other components, before or after its own installation.
2. Coordinate installation of different components to ensure maximum performance and accessibility for required maintenance, service, and repair.
3. Make adequate provisions to accommodate items scheduled for later installation.

B. Administrative Procedures: Coordinate scheduling and timing of required administrative procedures with other construction activities to avoid conflicts and to ensure orderly progress of the Work. Such administrative activities include, but are not limited to, the following:

1. Preparation of Contractor's construction schedule.
2. Preparation of the schedule of values.
3. Installation and removal of temporary facilities and controls.
4. Delivery and processing of submittals.
5. Progress meetings.
6. Preinstallation conferences.
7. Project closeout activities.
8. Startup and adjustment of systems.

C. Conservation: Coordinate construction activities to ensure that operations are carried out with consideration given to conservation of energy, water, and materials. Coordinate use of temporary utilities to minimize waste.

1. Salvage materials and equipment involved in performance of, but not actually incorporated into, the Work. See other Sections for disposition of salvaged materials that are designated as Owner's property.

## 1.5 COORDINATION DRAWINGS

- A. Coordination Drawings, General: Prepare coordination drawings according to requirements in individual Sections, and additionally where installation is not completely shown on Shop Drawings, where limited space availability necessitates coordination, or if coordination is required to facilitate integration of products and materials fabricated or installed by more than one entity.
1. Content: Project-specific information, drawn accurately to a scale large enough to indicate and resolve conflicts. Do not base coordination drawings on standard printed data. Include the following information, as applicable:
    - a. Use applicable Drawings as a basis for preparation of coordination drawings. Prepare sections, elevations, and details as needed to describe relationship of various systems and components.
    - b. Coordinate the addition of trade-specific information to the coordination drawings by multiple contractors in a sequence that best provides for coordination of the information and resolution of conflicts between installed components before submitting for review.
    - c. Indicate functional and spatial relationships of components of architectural, structural, civil, mechanical, and electrical systems.
    - d. Indicate space requirements for routine maintenance and for anticipated replacement of components during the life of the installation.
    - e. Show location and size of access doors required for access to concealed dampers, valves, and other controls.
    - f. Indicate required installation sequences.
    - g. Indicate dimensions shown on the Drawings. Specifically note dimensions that appear to be in conflict with submitted equipment and minimum clearance requirements. Provide alternate sketches to Architect indicating proposed resolution of such conflicts. Minor dimension changes and difficult installations will not be considered changes to the Contract.
- B. Coordination Drawing Organization: Organize coordination drawings as follows:
1. Floor Plans and Reflected Ceiling Plans: Show architectural and structural elements, and mechanical, plumbing, fire-protection, fire-alarm, and electrical Work. Show locations of visible ceiling-mounted devices relative to acoustical ceiling grid. Supplement plan drawings with section drawings where required to adequately represent the Work.
  2. Plenum Space: Indicate subframing for support of ceiling and wall systems, mechanical and electrical equipment, and related Work. Locate components within ceiling plenum to accommodate layout of light fixtures indicated on Drawings. Indicate areas of conflict between light fixtures and other components.
  3. Mechanical Rooms: Provide coordination drawings for mechanical rooms showing plans and elevations of mechanical, plumbing, fire-protection, fire-alarm, and electrical equipment.
  4. Structural Penetrations: Indicate penetrations and openings required for all disciplines.
  5. Slab Edge and Embedded Items: Indicate slab edge locations and sizes and locations of embedded items for metal fabrications, sleeves, anchor bolts, bearing plates, angles, slab depressions for floor finishes, and similar items.

6. Mechanical and Plumbing Work: Show the following:
    - a. Sizes and bottom elevations of ductwork, piping, and conduit runs, including insulation, bracing, flanges, and support systems.
    - b. Dimensions of major components, such as dampers, valves, diffusers, access doors, cleanouts and electrical distribution equipment.
    - c. Fire-rated enclosures around ductwork.
  7. Electrical Work: Show the following:
    - a. Runs of vertical and horizontal conduit 1-1/4 inches in diameter and larger.
    - b. Light fixture, exit light, emergency battery pack, smoke detector, and other fire-alarm locations.
    - c. Panel board, switch board, switchgear, transformer, busway, generator, and motor control center locations.
    - d. Location of pull boxes and junction boxes, dimensioned from column center lines.
  8. Fire-Protection System: Show the following:
    - a. Locations of standpipes, mains piping, branch lines, pipe drops, and sprinkler heads.
  9. Review: Architect will review coordination drawings to confirm that the Work is being coordinated, but not for the details of the coordination, which are Contractor's responsibility. If Architect determines that coordination drawings are not being prepared in sufficient scope or detail, or are otherwise deficient, Architect will so inform Contractor, who shall make changes as directed and resubmit.
  10. Coordination Drawing Prints: Prepare coordination drawing prints according to requirements in Section 01 3300 "Submittal Procedures."
- C. Coordination Digital Data Files: Prepare coordination digital data files according to the following requirements:
1. File Preparation Format: Same digital data software program, version, and operating system as original Drawings.
  2. File Submittal Format: Submit or post coordination drawing files using format same as file preparation format and Portable Data File (PDF) format.
  3. Architect will furnish Contractor one set of digital data files of Drawings for use in preparing coordination digital data files.
    - a. Architect makes no representations as to the accuracy or completeness of digital data files as they relate to Drawings.
    - b. Digital Data Software Program: Drawings are available in Revit.
    - c. Contractor shall execute a data licensing agreement in the form of Agreement form acceptable to Owner and Architect.

1.6 REQUESTS FOR INFORMATION (RFIs)

- A. See University of Utah U Facilities; General Conditions; Article 7 Modifications, PRs & PCOs, PRE and Claims Process; 7.2 Contractor Initiated Requests; 7.2.1 The Request for Information (RFI) Process and Time to File.
- B. General: Immediately on discovery of the need for additional information or interpretation of the Contract Documents, Contractor shall prepare and submit an RFI in the form specified.
  - 1. Architect will return RFIs submitted to Architect by other entities controlled by Contractor with no response.
  - 2. Coordinate and submit RFIs in a prompt manner so as to avoid delays in Contractor's work or work of subcontractors.
- C. Content of the RFI: Include a detailed, legible description of item needing information or interpretation and the following:
  - 1. Project name.
  - 2. Project number.
  - 3. Date.
  - 4. Name of Contractor.
  - 5. Name of Architect.
  - 6. RFI number, numbered sequentially.
  - 7. RFI subject.
  - 8. Specification Section number and title and related paragraphs, as appropriate.
  - 9. Drawing number and detail references, as appropriate.
  - 10. Field dimensions and conditions, as appropriate.
  - 11. Contractor's suggested resolution. If Contractor's suggested resolution impacts the Contract Time or the Contract Sum, Contractor shall state impact in the RFI.
  - 12. Contractor's signature.
  - 13. Attachments: Include sketches, descriptions, measurements, photos, Product Data, Shop Drawings, coordination drawings, and other information necessary to fully describe items needing interpretation.
    - a. Include dimensions, thicknesses, structural grid references, and details of affected materials, assemblies, and attachments on attached sketches.
- D. RFI Forms: Unifier Software-generated form with substantially the same content as indicated above.
  - 1. Attachments shall be electronic files in Adobe Acrobat PDF format.
- E. Architect's Action: Architect will review each RFI, determine action required, and respond. Allow 10 working days for Architect's response for each RFI. RFIs received by Architect after 1:00 p.m. will be considered as received the following working day.
  - 1. The following Contractor-generated RFIs will be returned without action:
    - a. Requests for approval of submittals.

- b. Requests for approval of substitutions.
    - c. Requests for approval of Contractor's means and methods.
    - d. Requests for coordination information already indicated in the Contract Documents.
    - e. Requests for adjustments in the Contract Time or the Contract Sum.
    - f. Requests for interpretation of Architect's actions on submittals.
    - g. Incomplete RFIs or inaccurately prepared RFIs.
  2. Architect's action may include a request for additional information, in which case Architect's time for response will date from time of receipt of additional information.
  3. Architect's action on RFIs that may result in a change to the Contract Time or the Contract Sum may be eligible for Contractor to submit Change Proposal according to Section 01 2600 "Contract Modification Procedures."
  - a. If Contractor believes the RFI response warrants change in the Contract Time or the Contract Sum, notify Architect in writing within 10 days of receipt of the RFI response.
- F. RFI Log: Prepare, maintain, and submit a tabular log of RFIs organized by the RFI number. Submit log weekly. Software log with not less than the following:
  1. Project name.
  2. Name and address of Contractor.
  3. Name and address of Architect.
  4. RFI number including RFIs that were returned without action or withdrawn.
  5. RFI description.
  6. Date the RFI was submitted.
  7. Date Architect's response was received.
- G. On receipt of Architect's action, update the RFI log and immediately distribute the RFI response to affected parties. Review response and notify Architect within seven days if Contractor disagrees with response.
  1. Identification of related Minor Change in the Work, Construction Change Directive, and Proposal Request, as appropriate.
  2. Identification of related Field Order, Work Change Directive, and Proposal Request, as appropriate.

#### 1.7 PROJECT INFORMATION MANAGEMENT

- A. Use University of Utah's Project Web site (Unifier System) for purposes of hosting and managing the following project communication and documentation until Final Completion. Architect's Project Web site includes the following functions:
  1. Project directory.
  2. RFI forms.
  3. Task and issue management.
  4. Submittals forms and logs.

5. Drawing and specification document hosting, viewing, and updating.
6. Online document collaboration.
7. Reminder and tracking functions.
8. Archiving functions.

B. Architect will issue Drawings and Specifications through the Information Management Site.

C. Architect will accept and return RFIs and submittal documents only through the Project Information Management Site, unless otherwise arranged.

## 1.8 PROJECT MEETINGS

A. General: Schedule and conduct meetings and conferences at Project site unless otherwise indicated.

1. Attendees: Inform participants and others involved, and individuals whose presence is required, of date and time of each meeting. Notify Owner and Architect of scheduled meeting dates and times.
2. Agenda: Prepare the meeting agenda. Distribute the agenda to all invited attendees.
3. Minutes: Entity responsible for conducting meeting will record significant discussions and agreements achieved. Distribute the meeting minutes to everyone concerned, including Owner, and Architect, within seven days of the meeting.

B. Preconstruction Conference: Schedule and conduct a preconstruction conference before starting construction, at a time convenient to Owner and Architect, but no later than 15 days after execution of the Agreement.

1. Conduct the conference to review responsibilities and personnel assignments.
2. Attendees: Authorized representatives of Owner, Owner's Commissioning Authority, Architect, and their consultants; Contractor and its superintendent; major subcontractors; suppliers; and other concerned parties shall attend the conference. Participants at the conference shall be familiar with Project and authorized to conclude matters relating to the Work.
3. Agenda: Discuss items of significance that could affect progress, including the following:
  - a. Tentative construction schedule.
  - b. Critical work sequencing and long-lead items.
  - c. Designation of key personnel and their duties.
  - d. Lines of communications.
  - e. Procedures for processing field decisions and Change Orders.
  - f. Procedures for RFIs.
  - g. Procedures for testing and inspecting.
  - h. Procedures for processing Applications for Payment.
  - i. Submittal procedures.
  - j. Use of the premises.
  - k. Work restrictions.
  - l. Working hours.
  - m. Owner's occupancy requirements.



- n. Responsibility for temporary facilities and controls.
  - o. Procedures for moisture and mold control.
  - p. Procedures for disruptions and shutdowns.
  - q. Construction waste management and recycling.
  - r. Parking availability.
  - s. Office, work, and storage areas.
  - t. Equipment deliveries and priorities.
  - u. First aid.
  - v. Security.
  - w. Progress cleaning.
4. Minutes: Entity responsible for conducting meeting will record and distribute meeting minutes.
- C. Preinstallation Conferences: Conduct a preinstallation conference at Project site before each construction activity that requires coordination with other construction.
- 1. Attendees: Installer and representatives of manufacturers and fabricators involved in or affected by the installation and its coordination or integration with other materials and installations that have preceded or will follow, shall attend the meeting. Advise Architect, Owner's Commissioning Authority of scheduled meeting dates.
  - 2. Agenda: Review progress of other construction activities and preparations for the particular activity under consideration, including requirements for the following:
    - a. Contract Documents.
    - b. Options.
    - c. Related RFIs.
    - d. Related Change Orders.
    - e. Purchases.
    - f. Deliveries.
    - g. Submittals.
    - h. Review of mockups.
    - i. Possible conflicts.
    - j. Compatibility requirements.
    - k. Time schedules.
    - l. Weather limitations.
    - m. Manufacturer's written instructions.
    - n. Warranty requirements.
    - o. Compatibility of materials.
    - p. Acceptability of substrates.
    - q. Temporary facilities and controls.
    - r. Space and access limitations.
    - s. Regulations of authorities having jurisdiction.
    - t. Testing and inspecting requirements.
    - u. Installation procedures.
    - v. Coordination with other work.
    - w. Required performance results.
    - x. Protection of adjacent work.
    - y. Protection of construction and personnel.

3. Record significant conference discussions, agreements, and disagreements, including required corrective measures and actions.
4. Reporting: Distribute minutes of the meeting to each party present and to other parties requiring information.
5. Do not proceed with installation if the conference cannot be successfully concluded. Initiate whatever actions are necessary to resolve impediments to performance of the Work and reconvene the conference at earliest feasible date.

D. Progress Meetings: Conduct progress meetings at weekly intervals.

1. Coordinate dates of meetings with preparation of payment requests.
2. Attendees: In addition to representatives of Owner, Owner's Commissioning Authority, and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meeting shall be familiar with Project and authorized to conclude matters relating to the Work.
3. Agenda: Review and correct or approve minutes of previous progress meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
  - a. Contractor's Construction Schedule: Review progress since the last meeting. Determine whether each activity is on time, ahead of schedule, or behind schedule, in relation to Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
    - 1) Review schedule for next period.
  - b. Review present and future needs of each entity present, including the following:
    - 1) Interface requirements.
    - 2) Sequence of operations.
    - 3) Status of submittals.
    - 4) Deliveries.
    - 5) Off-site fabrication.
    - 6) Access.
    - 7) Site utilization.
    - 8) Temporary facilities and controls.
    - 9) Progress cleaning.
    - 10) Quality and work standards.
    - 11) Status of correction of deficient items.
    - 12) Field observations.
    - 13) Status of RFIs.
    - 14) Status of proposal requests.
    - 15) Pending changes.
    - 16) Status of Change Orders.
    - 17) Pending claims and disputes.
    - 18) Documentation of information for payment requests.

4. Minutes: Entity responsible for conducting the meeting will record and distribute the meeting minutes to each party present and to parties requiring information.
  - a. Schedule Updating: Revise Contractor's construction schedule after each progress meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with the report of each meeting.
- E. Coordination Meetings: Conduct Project coordination meetings as required. Project coordination meetings are in addition to specific meetings held for other purposes, such as progress meetings and preinstallation conferences.
  1. Attendees: In addition to representatives of Owner, Owner's Commissioning Authority, and Architect, each contractor, subcontractor, supplier, and other entity concerned with current progress or involved in planning, coordination, or performance of future activities shall be represented at these meetings. All participants at the meetings shall be familiar with Project and authorized to conclude matters relating to the Work.
  2. Agenda: Review and correct or approve minutes of the previous coordination meeting. Review other items of significance that could affect progress. Include topics for discussion as appropriate to status of Project.
    - a. Combined Contractor's Construction Schedule: Review progress since the last coordination meeting. Determine whether each contract is on time, ahead of schedule, or behind schedule, in relation to combined Contractor's construction schedule. Determine how construction behind schedule will be expedited; secure commitments from parties involved to do so. Discuss whether schedule revisions are required to ensure that current and subsequent activities will be completed within the Contract Time.
    - b. Schedule Updating: Revise combined Contractor's construction schedule after each coordination meeting where revisions to the schedule have been made or recognized. Issue revised schedule concurrently with report of each meeting.
    - c. Review present and future needs of each contractor present, including the following:
      - 1) Interface requirements.
      - 2) Sequence of operations.
      - 3) Status of submittals.
      - 4) Deliveries.
      - 5) Off-site fabrication.
      - 6) Access.
      - 7) Site utilization.
      - 8) Temporary facilities and controls.
      - 9) Work hours.
      - 10) Hazards and risks.
      - 11) Progress cleaning.
      - 12) Quality and work standards.
      - 13) Change Orders.
  3. Reporting: Record meeting results and distribute copies to everyone in attendance and to others affected by decisions or actions resulting from each meeting.

ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84132

Code Review

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not Used)

END OF SECTION 01 3100

## SECTION 01 3200 - CONSTRUCTION PROGRESS DOCUMENTATION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for documenting the progress of construction during performance of the Work, including the following:
  - 1. Contractor's construction schedule.
  - 2. Construction schedule updating reports.
  - 3. Daily construction reports.
  - 4. Site condition reports.
  - 5. Special reports.
- B. Related Requirements:
  - 1. Section 01 3300 "Submittal Procedures" for submitting schedules and reports.
  - 2. Section 01 4000 "Quality Requirements" for submitting a schedule of tests and inspections.

#### 1.2 DEFINITIONS

- A. Activity: A discrete part of a project that can be identified for planning, scheduling, monitoring, and controlling the construction project. Activities included in a construction schedule consume time and resources.
  - 1. Critical Activity: An activity on the critical path that must start and finish on the planned early start and finish times.
  - 2. Predecessor Activity: An activity that precedes another activity in the network.
  - 3. Successor Activity: An activity that follows another activity in the network.
- B. CPM: Critical path method, which is a method of planning and scheduling a construction project where activities are arranged based on activity relationships. Network calculations determine when activities can be performed and the critical path of Project.
- C. Critical Path: The longest connected chain of interdependent activities through the network schedule that establishes the minimum overall Project duration and contains no float.
- D. Event: The starting or ending point of an activity.
- E. Float: The measure of leeway in starting and completing an activity.

1. See University of Utah Facilities Management; General Conditions; General Conditions; Article 4 Contractor; 4.6 Time and Contractor's Construction Schedules; 4.6.6 Float Time.
  2. Float time is not for the exclusive use or benefit of either Owner or Contractor, but is a jointly owned, expiring Project resource available to both parties as needed to meet schedule milestones and Contract completion date.
  3. Free float is the amount of time an activity can be delayed without adversely affecting the early start of the successor activity.
  4. Total float is the measure of leeway in starting or completing an activity without adversely affecting the planned Project completion date.
- F. Resource Loading: The allocation of manpower and equipment necessary for the completion of an activity as scheduled.

### 1.3 INFORMATIONAL SUBMITTALS

- A. Format for Submittals: Submit required submittals in the following format:
1. Working electronic copy of schedule file, where indicated.
  2. PDF electronic file.
- B. Contractor's Construction Schedule: Initial schedule, of size required to display entire schedule for entire construction period.
1. Submit a working electronic copy of schedule, using software indicated, and labeled to comply with requirements for submittals. Include type of schedule (initial or updated) and date on label.
- C. Construction Schedule Updating Reports: Submit with Applications for Payment.
- D. Daily Construction Reports: Submit at monthly intervals.
- E. Site Condition Reports: Submit at time of discovery of differing conditions.
- F. Special Reports: Submit at time of unusual event.

### 1.4 COORDINATION

- A. Coordinate Contractor's construction schedule with the schedule of values, submittal schedule, progress reports, payment requests, and other required schedules and reports.
1. Secure time commitments for performing critical elements of the Work from entities involved.
  2. Coordinate each construction activity in the network with other activities and schedule them in proper sequence.

## PART 2 - PRODUCTS

### 2.1 CONTRACTOR'S CONSTRUCTION SCHEDULE, GENERAL

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.6 Time and Contractor's Construction Schedules; 4.6.4 Schedule Content Requirements.
- B. Time Frame: Extend schedule from date established for the Notice to Proceed to date of final completion.
  - 1. Contract completion date shall not be changed by submission of a schedule that shows an early completion date, unless specifically authorized by Change Order.
- C. Activities: Treat each story or separate area as a separate numbered activity for each main element of the Work. Comply with the following:
  - 1. Activity Duration: Define activities so no activity is longer than 20 days, unless specifically allowed by Architect.
  - 2. Procurement Activities: Include procurement process activities for long lead items and major items, requiring a cycle of more than 60 days, as separate activities in schedule. Procurement cycle activities include, but are not limited to, submittals, approvals, purchasing, fabrication, and delivery.
  - 3. Submittal Review Time: Include review and resubmittal times indicated in Section 01 3300 "Submittal Procedures" in schedule. Coordinate submittal review times in Contractor's construction schedule with submittal schedule.
  - 4. Startup and Testing Time: Include no fewer than 30 days for startup and testing.
  - 5. Substantial Completion: Indicate completion in advance of date established for Substantial Completion, and allow time for Architect's administrative procedures necessary for certification of Substantial Completion.
  - 6. Punch List and Final Completion: Include not more than 30 days for completion of punch list items and final completion.
- D. Constraints: Include constraints and work restrictions indicated in the Contract Documents and as follows in schedule, and show how the sequence of the Work is affected.
  - 1. Work by Owner: Include a separate activity for each portion of the Work performed by Owner.
  - 2. Owner-Furnished Products: Include a separate activity for each product. Include delivery date. Delivery dates indicated stipulate the earliest possible delivery date.
  - 3. Work Restrictions: Show the effect of the following items on the schedule:
    - a. Coordination with existing construction.
    - b. Limitations of continued occupancies.
    - c. Uninterruptible services.
    - d. Partial occupancy before Substantial Completion.
    - e. Use of premises restrictions.
    - f. Provisions for future construction.
    - g. Seasonal variations.

- h. Environmental control.
- 4. Work Stages: Indicate important stages of construction for each major portion of the Work, including, but not limited to, the following:
  - a. Subcontract awards.
  - b. Submittals.
  - c. Purchases.
  - d. Mockups.
  - e. Fabrication.
  - f. Sample testing.
  - g. Deliveries.
  - h. Installation.
  - i. Tests and inspections.
  - j. Adjusting.
  - k. Curing.
  - l. Building flush-out.
  - m. Startup and placement into final use and operation.
- 5. Construction Areas: Identify each major area of construction for each major portion of the Work. Indicate where each construction activity within a major area must be sequenced or integrated with other construction activities to provide for the following:
  - a. Completion of mechanical installation.
  - b. Completion of electrical installation.
  - c. Substantial Completion.
- E. Milestones: Include milestones indicated in the Contract Documents in schedule, including, but not limited to, the Notice to Proceed, Substantial Completion, and final completion.
  - 1. See University of Utah Facilities Management; General Conditions; Article 4 Contractor; 4.6 Time and Contractor's Construction Schedules; 4.6.5 Interim Completion Dates and Milestones.
- F. Cost Correlation: Superimpose a cost correlation timeline, indicating planned and actual costs. On the line, show planned and actual dollar volume of the Work performed as of planned and actual dates used for preparation of payment requests.
  - 1. See Section 01 2900 "Payment Procedures" for cost reporting and payment procedures.
- G. Upcoming Work Summary: Prepare summary report indicating activities scheduled to occur or commence prior to submittal of next schedule update. Summarize the following issues:
  - 1. Unresolved issues.
  - 2. Unanswered Requests for Information.
  - 3. Rejected or unreturned submittals.
  - 4. Notations on returned submittals.
  - 5. Pending modifications affecting the Work and Contract Time.



- H. Recovery Schedule: When periodic update indicates the Work is 14 or more calendar days behind the current approved schedule, submit a separate recovery schedule indicating means by which Contractor intends to regain compliance with the schedule. Indicate changes to working hours, working days, crew sizes, and equipment required to achieve compliance, and date by which recovery will be accomplished.
- I. Computer Scheduling Software: Prepare schedules using current version of a program that has been developed specifically to manage construction schedules.

## 2.2 CONTRACTOR'S CONSTRUCTION SCHEDULE (CPM SCHEDULE)

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.6 Time and Contractor's Construction Schedules; 4.6.2 Schedule Preparation.
- B. CPM Schedule: Prepare Contractor's construction schedule using a cost- and resource-loaded, time-scaled CPM network analysis diagram for the Work.
  - 1. Develop network diagram in sufficient time to submit CPM schedule so it can be accepted for use no later than 60 days after date established for the Notice to Proceed.
    - a. Failure to include any work item required for performance of this Contract shall not excuse Contractor from completing all work within applicable completion dates, regardless of Architect's approval of the schedule.
  - 2. Conduct educational workshops to train and inform key Project personnel, including subcontractors' personnel, in proper methods of providing data and using CPM schedule information.
  - 3. Establish procedures for monitoring and updating CPM schedule and for reporting progress. Coordinate procedures with progress meeting and payment request dates.
  - 4. Use "one workday" as the unit of time for individual activities. Indicate nonworking days and holidays incorporated into the schedule in order to coordinate with the Contract Time.
- C. CPM Schedule Preparation: Prepare a list of all activities required to complete the Work. Using the startup network diagram, prepare a skeleton network to identify probable critical paths.
  - 1. Activities: Indicate the estimated time duration, sequence requirements, and relationship of each activity in relation to other activities. Include estimated time frames for the following activities:
    - a. Preparation and processing of submittals.
    - b. Mobilization and demobilization.
    - c. Purchase of materials.
    - d. Delivery.
    - e. Fabrication.
    - f. Utility interruptions.
    - g. Installation.
    - h. Work by Owner that may affect or be affected by Contractor's activities.

- i. Testing and commissioning.
  - j. Punch list and final completion.
  - k. Activities occurring following final completion.
2. Critical Path Activities: Identify critical path activities, including those for interim completion dates. Scheduled start and completion dates shall be consistent with Contract milestone dates.
3. Processing: Process data to produce output data on a computer-drawn, time-scaled network. Revise data, reorganize activity sequences, and reproduce as often as necessary to produce the CPM schedule within the limitations of the Contract Time.
4. Format: Mark the critical path. Locate the critical path near center of network; locate paths with most float near the edges.
  - a. Subnetworks on separate sheets are permissible for activities clearly off the critical path.
- D. Contract Modifications: For each proposed contract modification and concurrent with its submission, prepare a time-impact analysis using a network fragment to demonstrate the effect of the proposed change on the overall project schedule.
- E. Initial Issue of Schedule: Prepare initial network diagram from a sorted activity list indicating straight "early start-total float." Identify critical activities. Prepare tabulated reports showing the following:
  1. Contractor or subcontractor and the Work or activity.
  2. Description of activity.
  3. Main events of activity.
  4. Immediate preceding and succeeding activities.
  5. Early and late start dates.
  6. Early and late finish dates.
  7. Activity duration in workdays.
  8. Total float or slack time.
  9. Average size of workforce.
  10. Dollar value of activity (coordinated with the schedule of values).
- F. Schedule Updating: Concurrent with making revisions to schedule, prepare tabulated reports showing the following:
  1. Identification of activities that have changed.
  2. Changes in early and late start dates.
  3. Changes in early and late finish dates.
  4. Changes in activity durations in workdays.
  5. Changes in the critical path.
  6. Changes in total float or slack time.
  7. Changes in the Contract Time.

## 2.3 REPORTS

- A. Daily Construction Reports: Prepare a daily construction report recording the following information concerning events at Project site:
1. List of subcontractors at Project site.
  2. List of separate contractors at Project site.
  3. Approximate count of personnel at Project site.
  4. Equipment at Project site.
  5. Material deliveries.
  6. High and low temperatures and general weather conditions, including presence of rain or snow.
  7. Accidents.
  8. Meetings and significant decisions.
  9. Unusual events (see special reports).
  10. Stoppages, delays, shortages, and losses.
  11. Meter readings and similar recordings.
  12. Emergency procedures.
  13. Orders and requests of authorities having jurisdiction.
  14. Change Orders received and implemented.
  15. Construction Change Directives received and implemented.
  16. Services connected and disconnected.
  17. Equipment or system tests and startups.
  18. Partial completions and occupancies.
  19. Substantial Completions authorized.
- B. Site Condition Reports: Immediately on discovery of a difference between site conditions and the Contract Documents, prepare and submit a detailed report. Submit with a Request for Information. Include a detailed description of the differing conditions, together with recommendations for changing the Contract Documents.

## 2.4 SPECIAL REPORTS

- A. General: Submit special reports directly to Owner within one day of an occurrence. Distribute copies of report to parties affected by the occurrence.
- B. Reporting Unusual Events: When an event of an unusual and significant nature occurs at Project site, whether or not related directly to the Work, prepare and submit a special report. List chain of events, persons participating, response by Contractor's personnel, evaluation of results or effects, and similar pertinent information. Advise Owner in advance when these events are known or predictable.

### PART 3 - EXECUTION

#### 3.1 CONTRACTOR'S CONSTRUCTION SCHEDULE

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.6 Time and Contractor's Construction Schedules; 4.6.2 Schedule Preparation.
- B. Contractor's Construction Schedule Updating: At monthly intervals, update schedule to reflect actual construction progress and activities. Issue schedule one week before each regularly scheduled progress meeting.
  - 1. Revise schedule immediately after each meeting or other activity where revisions have been recognized or made. Issue updated schedule concurrently with the report of each such meeting.
  - 2. Include a report with updated schedule that indicates every change, including, but not limited to, changes in logic, durations, actual starts and finishes, and activity durations.
  - 3. As the Work progresses, indicate final completion percentage for each activity.
- C. Distribution: Distribute copies of approved schedule to Architect, Owner, separate contractors, testing and inspecting agencies, and other parties identified by Contractor with a need-to-know schedule responsibility.
  - 1. Post copies in Project meeting rooms and temporary field offices.
  - 2. When revisions are made, distribute updated schedules to the same parties and post in the same locations. Delete parties from distribution when they have completed their assigned portion of the Work and are no longer involved in performance of construction activities.

END OF SECTION 01 3200

## SECTION 01 3300 - SUBMITTAL PROCEDURES

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes requirements for the submittal schedule and administrative and procedural requirements for submitting Shop Drawings, Product Data, Samples, and other submittals.
- B. Related Requirements:
  - 1. Section 01 2900 "Payment Procedures" for submitting Applications for Payment and the schedule of values.
  - 2. Section 01 3200 "Construction Progress Documentation" for submitting schedules and reports, including Contractor's construction schedule.
  - 3. Section 01 7823 "Operation and Maintenance Data" for submitting operation and maintenance manuals.
  - 4. Section 01 7839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
  - 5. Section 01 7900 "Demonstration and Training" for submitting video recordings of demonstration of equipment and training of Owner's personnel.

#### 1.2 DEFINITIONS

- A. Action Submittals: Written and graphic information and physical samples that require Architect's responsive action. Action submittals are those submittals indicated in individual Specification Sections as "action submittals."
- B. Informational Submittals: Written and graphic information and physical samples that do not require Architect's responsive action. Submittals may be rejected for not complying with requirements. Informational submittals are those submittals indicated in individual Specification Sections as "informational submittals."
- C. Portable Document Format (PDF): An open standard file format licensed by Adobe Systems used for representing documents in a device-independent and display resolution-independent fixed-layout document format.

#### 1.3 ACTION SUBMITTALS

- A. Submittal Schedule: Submit a schedule of submittals, arranged in chronological order by dates required by construction schedule. Include time required for review, ordering, manufacturing, fabrication, and delivery when establishing dates. Include additional time required for making corrections or revisions to submittals noted by Architect and additional time for handling and reviewing submittals required by those corrections.

1. Coordinate submittal schedule with list of subcontracts, the schedule of values, and Contractor's construction schedule.
2. Initial Submittal: Submit concurrently with startup construction schedule. Include submittals required during the first 60 days of construction. List those submittals required to maintain orderly progress of the Work and those required early because of long lead time for manufacture or fabrication.
3. Final Submittal: Submit concurrently with the first complete submittal of Contractor's construction schedule.
  - a. Submit revised submittal schedule to reflect changes in current status and timing for submittals.
4. Format: Arrange the following information in a tabular format:
  - a. Scheduled date for first submittal.
  - b. Specification Section number and title.
  - c. Submittal category: Action; informational.
  - d. Name of subcontractor.
  - e. Description of the Work covered.
  - f. Scheduled date for Architect's final release or approval.
  - g. Scheduled date of fabrication.
  - h. Scheduled dates for purchasing.
  - i. Scheduled dates for installation.
  - j. Activity or event number.

#### 1.4 SUBMITTAL ADMINISTRATIVE REQUIREMENTS

- A. See University of Utah U Facilities; General Conditions; Article 3 A/E; 3.1 A/E's Administration of the Contract; 3.1.5 A/E Review of Contractor's Submittals
- B. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.6 Time and Contractor's Construction Schedule; 4.6.8 Schedule of Submittals.
- C. Architect's Digital Data Files: Electronic digital data files of the Contract Drawings will be provided by Architect for Contractor's use in preparing submittals.
  1. Architect will furnish Contractor one set of digital data drawing files of the Contract Drawings for use in preparing Shop Drawings and Project record drawings.
    - a. Architect makes no representations as to the accuracy or completeness of digital data drawing files as they relate to the Contract Drawings.
    - b. Digital Drawing Software Program: The Contract Drawings are available in Revit.
    - c. Contractor shall execute a data licensing agreement in the form of Agreement form acceptable to Owner and Architect.
- D. Coordination: Coordinate preparation and processing of submittals with performance of construction activities.

1. Coordinate each submittal with fabrication, purchasing, testing, delivery, other submittals, and related activities that require sequential activity.
  2. Submit all submittal items required for each Specification Section concurrently unless partial submittals for portions of the Work are indicated on approved submittal schedule.
  3. Submit action submittals and informational submittals required by the same Specification Section as separate packages under separate transmittals.
  4. Coordinate transmittal of different types of submittals for related parts of the Work so processing will not be delayed because of need to review submittals concurrently for coordination.
    - a. Architect reserves the right to withhold action on a submittal requiring coordination with other submittals until related submittals are received.
- E. Processing Time: Allow time for submittal review, including time for resubmittals, as follows. Time for review shall commence on Architect's receipt of submittal. No extension of the Contract Time will be authorized because of failure to transmit submittals enough in advance of the Work to permit processing, including resubmittals.
1. Initial Review: Allow 15 working days for initial review of each submittal. Allow additional time if coordination with subsequent submittals is required. Architect will advise Contractor when a submittal being processed must be delayed for coordination.
  2. Resubmittal Review: Allow 15 working days for review of each resubmittal.
  3. Sequential Review: Where sequential review of submittals by Architect's consultants, Owner, or other parties is indicated, allow 21 working days for initial review of each submittal.
- F. Electronic Submittals: Identify and incorporate information in each electronic submittal file as follows:
1. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
  2. Name file with submittal number or other unique identifier, including revision identifier.
    - a. File name shall use project identifier and Specification Section number followed by a decimal point and then a sequential number (e.g., LNHS-061000.01). Resubmittals shall include an alphabetic suffix after another decimal point (e.g., LNHS-061000.01.A).
  3. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by Architect.
  4. Transmittal Form for Electronic Submittals: Use software-generated form from electronic project management software acceptable to Owner, containing the following information:
    - a. Project name.
    - b. Date.
    - c. Name and address of Architect.
    - d. Name of Contractor.
    - e. Name of firm or entity that prepared submittal.

- f. Names of subcontractor, manufacturer, and supplier.
  - g. Category and type of submittal.
  - h. Submittal purpose and description.
  - i. Specification Section number and title.
  - j. Specification paragraph number or drawing designation and generic name for each of multiple items.
  - k. Drawing number and detail references, as appropriate.
  - l. Location(s) where product is to be installed, as appropriate.
  - m. Related physical samples submitted directly.
  - n. Indication of full or partial submittal.
  - o. Transmittal number, numbered consecutively.
  - p. Submittal and transmittal distribution record.
  - q. Other necessary identification.
  - r. Remarks.
- 5. Metadata: Include the following information as keywords in the electronic submittal file metadata:
  - a. Project name.
  - b. Number and title of appropriate Specification Section.
  - c. Manufacturer name.
  - d. Product name.
- G. Options: Identify options requiring selection by Architect.
- H. Deviations and Additional Information: On an attached separate sheet, prepared on Contractor's letterhead, record relevant information, requests for data, revisions other than those requested by Architect on previous submittals, and deviations from requirements in the Contract Documents, including minor variations and limitations. Include same identification information as related submittal.
- I. Resubmittals: Make resubmittals in same form and number of copies as initial submittal.
  - 1. Note date and content of previous submittal.
  - 2. Note date and content of revision in label or title block and clearly indicate extent of revision.
  - 3. Resubmit submittals until they are marked with approval notation from Architect's action stamp.
- J. Distribution: Furnish copies of final submittals to manufacturers, subcontractors, suppliers, fabricators, installers, authorities having jurisdiction, and others as necessary for performance of construction activities. Show distribution on transmittal forms.
- K. Use for Construction: Retain complete copies of submittals on Project site. Use only final action submittals that are marked with approval notation from Architect's action stamp.



## PART 2 - PRODUCTS

### 2.1 SUBMITTAL PROCEDURES

- A. General Submittal Procedure Requirements: Prepare and submit submittals required by individual Specification Sections. Types of submittals are indicated in individual Specification Sections.
  - 1. Post electronic submittals as PDF electronic files directly Document Transfer site for Project.
    - a. Architect will return annotated file. Annotate and retain one copy of file as an electronic Project record document file.
  - 2. Certificates and Certifications Submittals: Provide a statement that includes signature of entity responsible for preparing certification. Certificates and certifications shall be signed by an officer or other individual authorized to sign documents on behalf of that entity.
    - a. Provide a digital signature with digital certificate on electronically submitted certificates and certifications where indicated.
    - b. Provide a notarized statement on original paper copy certificates and certifications where indicated.
- B. Product Data: Collect information into a single submittal for each element of construction and type of product or equipment.
  - 1. If information must be specially prepared for submittal because standard published data are not suitable for use, submit as Shop Drawings, not as Product Data.
  - 2. Mark each copy of each submittal to show which products and options are applicable.
  - 3. Include the following information, as applicable:
    - a. Manufacturer's catalog cuts.
    - b. Manufacturer's product specifications.
    - c. Standard color charts.
    - d. Statement of compliance with specified referenced standards.
    - e. Testing by recognized testing agency.
    - f. Application of testing agency labels and seals.
    - g. Notation of coordination requirements.
    - h. Availability and delivery time information.
  - 4. For equipment, include the following in addition to the above, as applicable:
    - a. Wiring diagrams showing factory-installed wiring.
    - b. Printed performance curves.
    - c. Operational range diagrams.
    - d. Clearances required to other construction, if not indicated on accompanying Shop Drawings.

5. Submit Product Data before or concurrent with Samples.
  6. Submit Product Data in the following format:
    - a. PDF electronic file.
- C. Shop Drawings: Prepare Project-specific information, drawn accurately to scale. Do not base Shop Drawings on reproductions of the Contract Documents or standard printed data.
1. Preparation: Fully illustrate requirements in the Contract Documents. Include the following information, as applicable:
    - a. Identification of products.
    - b. Schedules.
    - c. Compliance with specified standards.
    - d. Notation of coordination requirements.
    - e. Notation of dimensions established by field measurement.
    - f. Relationship and attachment to adjoining construction clearly indicated.
    - g. Seal and signature of professional engineer if specified.
  2. Sheet Size: Except for templates, patterns, and similar full-size drawings, submit Shop Drawings on sheets at least 8-1/2 by 11 inches , but no larger than 30 by 42 inches.
  3. Submit Shop Drawings in the following format:
    - a. PDF electronic file.
- D. Samples: Submit Samples for review of kind, color, pattern, and texture for a check of these characteristics with other elements and for a comparison of these characteristics between submittal and actual component as delivered and installed.
1. Transmit Samples that contain multiple, related components such as accessories together in one submittal package.
  2. Identification: Attach label on unexposed side of Samples that includes the following:
    - a. Generic description of Sample.
    - b. Product name and name of manufacturer.
    - c. Sample source.
    - d. Number and title of applicable Specification Section.
    - e. Specification paragraph number and generic name of each item.
  3. For projects where electronic submittals are required, provide corresponding electronic submittal of Sample transmittal, digital image file illustrating Sample characteristics, and identification information for record.
  4. Disposition: Maintain sets of approved Samples at Project site, available for quality-control comparisons throughout the course of construction activity. Sample sets may be used to determine final acceptance of construction associated with each set.
    - a. Samples that may be incorporated into the Work are indicated in individual Specification Sections. Such Samples must be in an undamaged condition at time of use.

- b. Samples not incorporated into the Work, or otherwise designated as Owner's property, are the property of Contractor.
  - 5. Samples for Initial Selection: Submit manufacturer's color charts consisting of units or sections of units showing the full range of colors, textures, and patterns available.
    - a. Number of Samples: Submit one full set of available choices where color, pattern, texture, or similar characteristics are required to be selected from manufacturer's product line. Architect will return submittal with options selected.
  - 6. Samples for Verification: Submit full-size units or Samples of size indicated, prepared from same material to be used for the Work, cured and finished in manner specified, and physically identical with material or product proposed for use, and that show full range of color and texture variations expected. Samples include, but are not limited to, the following: partial sections of manufactured or fabricated components; small cuts or containers of materials; complete units of repetitively used materials; swatches showing color, texture, and pattern; color range sets; and components used for independent testing and inspection.
    - a. Number of Samples: Submit three sets of Samples. Architect will retain two Sample sets; remainder will be returned. Mark up and retain one returned Sample set as a project record sample.
      - 1) Submit a single Sample where assembly details, workmanship, fabrication techniques, connections, operation, and other similar characteristics are to be demonstrated.
      - 2) If variation in color, pattern, texture, or other characteristic is inherent in material or product represented by a Sample, submit at least three sets of paired units that show approximate limits of variations.
- E. Product Schedule: As required in individual Specification Sections, prepare a written summary indicating types of products required for the Work and their intended location. Include the following information in tabular form:
  - 1. Type of product. Include unique identifier for each product indicated in the Contract Documents or assigned by Contractor if none is indicated.
  - 2. Manufacturer and product name, and model number if applicable.
  - 3. Number and name of room or space.
  - 4. Location within room or space.
  - 5. Submit product schedule in the following format:
    - a. PDF electronic file.
- F. Coordination Drawing Submittals: Comply with requirements specified in Section 01 3100 "Project Management and Coordination."
- G. Contractor's Construction Schedule: Comply with requirements specified in Section 01 3200 "Construction Progress Documentation."

- H. Application for Payment and Schedule of Values: Comply with requirements specified in Section 01 2900 "Payment Procedures."
- I. Test and Inspection Reports and Schedule of Tests and Inspections Submittals: Comply with requirements specified in Section 01 4000 "Quality Requirements."
- J. Closeout Submittals and Maintenance Material Submittals: Comply with requirements specified in Section 01 7700 "Closeout Procedures."
- K. Maintenance Data: Comply with requirements specified in Section 01 7823 "Operation and Maintenance Data."
- L. Qualification Data: Prepare written information that demonstrates capabilities and experience of firm or person. Include lists of completed projects with project names and addresses, contact information of architects and owners, and other information specified.
- M. Welding Certificates: Prepare written certification that welding procedures and personnel comply with requirements in the Contract Documents. Submit record of Welding Procedure Specification and Procedure Qualification Record on AWS forms. Include names of firms and personnel certified.
- N. Installer Certificates: Submit written statements on manufacturer's letterhead certifying that Installer complies with requirements in the Contract Documents and, where required, is authorized by manufacturer for this specific Project.
- O. Manufacturer Certificates: Submit written statements on manufacturer's letterhead certifying that manufacturer complies with requirements in the Contract Documents. Include evidence of manufacturing experience where required.
- P. Product Certificates: Submit written statements on manufacturer's letterhead certifying that product complies with requirements in the Contract Documents.
- Q. Material Certificates: Submit written statements on manufacturer's letterhead certifying that material complies with requirements in the Contract Documents.
- R. Material Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting test results of material for compliance with requirements in the Contract Documents.
- S. Product Test Reports: Submit written reports indicating that current product produced by manufacturer complies with requirements in the Contract Documents. Base reports on evaluation of tests performed by manufacturer and witnessed by a qualified testing agency, or on comprehensive tests performed by a qualified testing agency.
- T. Research Reports: Submit written evidence, from a model code organization acceptable to authorities having jurisdiction, that product complies with building code in effect for Project. Include the following information:
  - 1. Name of evaluation organization.

2. Date of evaluation.
  3. Time period when report is in effect.
  4. Product and manufacturers' names.
  5. Description of product.
  6. Test procedures and results.
  7. Limitations of use.
- U. Preconstruction Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of tests performed before installation of product, for compliance with performance requirements in the Contract Documents.
- V. Compatibility Test Reports: Submit reports written by a qualified testing agency, on testing agency's standard form, indicating and interpreting results of compatibility tests performed before installation of product. Include written recommendations for primers and substrate preparation needed for adhesion.
- W. Field Test Reports: Submit written reports indicating and interpreting results of field tests performed either during installation of product or after product is installed in its final location, for compliance with requirements in the Contract Documents.
- X. Design Data: Prepare and submit written and graphic information, including, but not limited to, performance and design criteria, list of applicable codes and regulations, and calculations. Include list of assumptions and other performance and design criteria and a summary of loads. Include load diagrams if applicable. Provide name and version of software, if any, used for calculations. Include page numbers.

## 2.2 DELEGATED-DESIGN SERVICES

- A. Performance and Design Criteria: Where professional design services or certifications by a design professional are specifically required of Contractor by the Contract Documents, provide products and systems complying with specific performance and design criteria indicated.
1. If criteria indicated are not sufficient to perform services or certification required, submit a written request for additional information to Architect.
- B. Delegated-Design Services Certification: In addition to Shop Drawings, Product Data, and other required submittals, submit digitally signed PDF electronic file of certificate, signed and sealed by the responsible design professional, for each product and system specifically assigned to Contractor to be designed or certified by a design professional.
1. Indicate that products and systems comply with performance and design criteria in the Contract Documents. Include list of codes, loads, and other factors used in performing these services.

## PART 3 - EXECUTION

### 3.1 CONTRACTOR'S REVIEW

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.8 Shop Drawings, Product Data and Samples; 4.8.4 Representations by Contractor.
- B. Action and Informational Submittals: Review each submittal and check for coordination with other Work of the Contract and for compliance with the Contract Documents. Note corrections and field dimensions. Mark with approval stamp before submitting to Architect.
- C. Project Closeout and Maintenance Material Submittals: See requirements in Section 01 7700 "Closeout Procedures."
- D. Approval Stamp: Stamp each submittal with a uniform, approval stamp. Include Project name and location, submittal number, Specification Section title and number, name of reviewer, date of Contractor's approval, and statement certifying that submittal has been reviewed, checked, and approved for compliance with the Contract Documents.

### 3.2 ARCHITECT'S ACTION

- A. See University of Utah U Facilities; General Conditions; Article 3 A/E; 3.1 A/E's Administration of the Contract; 3.1.5 A/E Review of Contractor's Submittals.
- B. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.8 Shop Drawings, Product Data and Samples; 4.8.6 Direct Specific Attention to Revisions.
- C. Action Submittals: Architect will review each submittal, make marks to indicate corrections or revisions required, and return it. Architect will stamp each submittal with an action stamp and will mark stamp appropriately to indicate action.
- D. Informational Submittals: Architect will review each submittal and will not return it, or will return it if it does not comply with requirements. Architect will forward each submittal to appropriate party.
- E. Partial submittals prepared for a portion of the Work will be reviewed when use of partial submittals has received prior approval from Architect.
- F. Incomplete submittals are unacceptable, will be considered nonresponsive, and will be returned for resubmittal without review.
- G. Submittals not required by the Contract Documents may be returned by the Architect without action.

END OF SECTION 01 3300

## SECTION 01 4000 - QUALITY REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.
  - 1. See University of Utah U Facilities; General Conditions; Article 9 Tests and Inspections, Substantial and Final Completion, Uncovering, Correction of Work and Guaranty Period; 9.1 Tests and Inspection; 9.1.1 in General.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for quality assurance and quality control.
- B. Testing and inspecting services are required to verify compliance with requirements specified or indicated. These services do not relieve Contractor of responsibility for compliance with the Contract Document requirements.
  - 1. Specified tests, inspections, and related actions do not limit Contractor's other quality-assurance and -control procedures that facilitate compliance with the Contract Document requirements.
  - 2. Requirements for Contractor to provide quality-assurance and -control services required by Architect, Owner, Commissioning Authority, or authorities having jurisdiction are not limited by provisions of this Section.
- C. Related Requirements:
  - 1. Divisions 02 through 33 Sections for specific test and inspection requirements.

#### 1.3 DEFINITIONS

- A. See University of Utah U Facilities; General Conditions; Article 2 The University; 2.1 Information and Services Required of University; 2.1.2 Specialists and Inspectors.
- B. Quality-Assurance Services: Activities, actions, and procedures performed before and during execution of the Work to guard against defects and deficiencies and substantiate that proposed construction will comply with requirements.
- C. Quality-Control Services: Tests, inspections, procedures, and related actions during and after execution of the Work to evaluate that actual products incorporated into the Work and

completed construction comply with requirements. Services do not include contract enforcement activities performed by Architect.

- D. Mockups: Full-size physical assemblies that are constructed on-site. Mockups are constructed to verify selections made under Sample submittals; to demonstrate aesthetic effects and, where indicated, qualities of materials and execution; to review coordination, testing, or operation; to show interface between dissimilar materials; and to demonstrate compliance with specified installation tolerances. Mockups are not Samples. Unless otherwise indicated, approved mockups establish the standard by which the Work will be judged.
- E. Preconstruction Testing: Tests and inspections performed specifically for Project before products and materials are incorporated into the Work, to verify performance or compliance with specified criteria.
- F. Product Testing: Tests and inspections that are performed by an NRTL, an NVLAP, or a testing agency qualified to conduct product testing and acceptable to authorities having jurisdiction, to establish product performance and compliance with specified requirements.
- G. Source Quality-Control Testing: Tests and inspections that are performed at the source, e.g., plant, mill, factory, or shop.
- H. Field Quality-Control Testing: Tests and inspections that are performed on-site for installation of the Work and for completed Work.
- I. Testing Agency: An entity engaged to perform specific tests, inspections, or both. Testing laboratory shall mean the same as testing agency.
- J. Installer/Applicator/Erector: Contractor or another entity engaged by Contractor as an employee, Subcontractor, or Sub-subcontractor, to perform a particular construction operation, including installation, erection, application, and similar operations.
  - 1. Use of trade-specific terminology in referring to a trade or entity does not require that certain construction activities be performed by accredited or unionized individuals, or that requirements specified apply exclusively to specific trade(s).
- K. Experienced: When used with an entity or individual, "experienced" means having successfully completed a minimum of five previous projects similar in nature, size, and extent to this Project; being familiar with special requirements indicated; and having complied with requirements of authorities having jurisdiction.

#### 1.4 CONFLICTING REQUIREMENTS

- A. Referenced Standards: If compliance with two or more standards is specified and the standards establish different or conflicting requirements for minimum quantities or quality levels, comply with the most stringent requirement. Refer conflicting requirements that are different, but apparently equal, to Architect for a decision before proceeding.



- B. Minimum Quantity or Quality Levels: The quantity or quality level shown or specified shall be the minimum provided or performed. The actual installation may comply exactly with the minimum quantity or quality specified, or it may exceed the minimum within reasonable limits. To comply with these requirements, indicated numeric values are minimum or maximum, as appropriate, for the context of requirements. Refer uncertainties to Architect for a decision before proceeding.

## 1.5 INFORMATIONAL SUBMITTALS

- A. Contractor's Statement of Responsibility: When required by authorities having jurisdiction, submit copy of written statement of responsibility sent to authorities having jurisdiction before starting work on the following systems:
  - 1. Seismic-force-resisting system, designated seismic system, or component listed in the designated seismic system quality-assurance plan prepared by Architect.
  - 2. Main wind-force-resisting system or a wind-resisting component listed in the wind-force-resisting system quality-assurance plan prepared by Architect.
- B. Testing Agency Qualifications: For testing agencies specified in "Quality Assurance" Article to demonstrate their capabilities and experience. Include proof of qualifications in the form of a recent report on the inspection of the testing agency by a recognized authority.

## 1.6 REPORTS AND DOCUMENTS

- A. Test and Inspection Reports: Prepare and submit certified written reports specified in other Sections. Include the following:
  - 1. Date of issue.
  - 2. Project title and number.
  - 3. Name, address, and telephone number of testing agency.
  - 4. Dates and locations of samples and tests or inspections.
  - 5. Names of individuals making tests and inspections.
  - 6. Description of the Work and test and inspection method.
  - 7. Identification of product and Specification Section.
  - 8. Complete test or inspection data.
  - 9. Test and inspection results and an interpretation of test results.
  - 10. Record of temperature and weather conditions at time of sample taking and testing and inspecting.
  - 11. Comments or professional opinion on whether tested or inspected Work complies with the Contract Document requirements.
  - 12. Name and signature of laboratory inspector.
  - 13. Recommendations on retesting and reinspecting.
- B. Manufacturer's Field Reports: Prepare written information documenting tests and inspections specified in other Sections. Include the following:
  - 1. Name, address, and telephone number of representative making report.

2. Statement on condition of substrates and their acceptability for installation of product.
  3. Summary of installation procedures being followed, whether they comply with requirements and, if not, what corrective action was taken.
  4. Results of operational and other tests and a statement of whether observed performance complies with requirements.
  5. Other required items indicated in individual Specification Sections.
- C. Permits, Licenses, and Certificates: For Owner's records, submit copies of permits, licenses, certifications, inspection reports, releases, jurisdictional settlements, notices, receipts for fee payments, judgments, correspondence, records, and similar documents, established for compliance with standards and regulations bearing on performance of the Work.

## 1.7 QUALITY ASSURANCE

- A. General: Qualifications paragraphs in this article establish the minimum qualification levels required; individual Specification Sections specify additional requirements.
- B. Manufacturer Qualifications: A firm experienced in manufacturing products or systems similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- C. Fabricator Qualifications: A firm experienced in producing products similar to those indicated for this Project and with a record of successful in-service performance, as well as sufficient production capacity to produce required units.
- D. Installer Qualifications: A firm or individual experienced in installing, erecting, or assembling work similar in material, design, and extent to that indicated for this Project, whose work has resulted in construction with a record of successful in-service performance.
- E. Professional Engineer Qualifications: A professional engineer who is legally qualified to practice in jurisdiction where Project is located and who is experienced in providing engineering services of the kind indicated. Engineering services are defined as those performed for installations of the system, assembly, or product that are similar in material, design, and extent to those indicated for this Project.
- F. Specialists: Certain Specification Sections require that specific construction activities shall be performed by entities who are recognized experts in those operations. Specialists shall satisfy qualification requirements indicated and shall be engaged for the activities indicated.
1. Requirements of authorities having jurisdiction shall supersede requirements for specialists.
- G. Testing Agency Qualifications: An NRTL, an NVLAP, or an independent agency with the experience and capability to conduct testing and inspecting indicated, as documented according to ASTM E 329; and with additional qualifications specified in individual Sections; and, where required by authorities having jurisdiction, that is acceptable to authorities.
1. NRTL: A nationally recognized testing laboratory according to 29 CFR 1910.7.

2. NVLAP: A testing agency accredited according to NIST's National Voluntary Laboratory Accreditation Program.
- H. Manufacturer's Representative Qualifications: An authorized representative of manufacturer who is trained and approved by manufacturer to observe and inspect installation of manufacturer's products that are similar in material, design, and extent to those indicated for this Project.
- I. Mockups: Before installing portions of the Work requiring mockups, build mockups for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work:
  1. Build mockups in location and of size indicated.
  2. Notify Architect and testing agency seven days in advance of dates and times when mockups will be constructed.
  3. Demonstrate the proposed range of aesthetic effects and workmanship.
  4. Obtain Architect's approval of mockups before starting work, fabrication, or construction.
    - a. Allow seven days for initial review and each re-review of each mockup.

#### 1.8 QUALITY CONTROL

- A. See University of Utah U Facilities; General Conditions; Article 2 The University; 2.1 Information and Services Required of University; 2.1.2 Specialists and Inspectors
- B. Owner Responsibilities: Where quality-control services are indicated as Owner's responsibility, Owner will engage a qualified testing agency to perform these services.
  1. Owner will furnish Contractor with names, addresses, and telephone numbers of testing agencies engaged and a description of types of testing and inspecting they are engaged to perform.
  2. Costs for retesting and reinspecting construction that replaces or is necessitated by work that failed to comply with the Contract Documents will be charged to Contractor.
- C. Contractor Responsibilities: Tests and inspections not explicitly assigned to Owner are Contractor's responsibility. Perform additional quality-control activities required to verify that the Work complies with requirements, whether specified or not.
  1. Where services are indicated as Contractor's responsibility, engage a qualified testing agency to perform these quality-control services.
    - a. Contractor shall not employ same entity engaged by Owner, unless agreed to in writing by Owner.
  2. Notify testing agencies at least 24 hours in advance of time when Work that requires testing or inspecting will be performed.
  3. Where quality-control services are indicated as Contractor's responsibility, submit a certified written report, in duplicate, of each quality-control service.

4. Testing and inspecting requested by Contractor and not required by the Contract Documents are Contractor's responsibility.
  5. Submit additional copies of each written report directly to authorities having jurisdiction, when they so direct.
- D. Manufacturer's Field Services: Where indicated, engage a manufacturer's representative to observe and inspect the Work. Manufacturer's representative's services include examination of substrates and conditions, verification of materials, inspection of completed portions of the Work, and submittal of written reports.
- E. Retesting/Reinspecting: Regardless of whether original tests or inspections were Contractor's responsibility, provide quality-control services, including retesting and reinspecting, for construction that replaced Work that failed to comply with the Contract Documents.
- F. Testing Agency Responsibilities: Cooperate with Architect and Contractor in performance of duties. Provide qualified personnel to perform required tests and inspections.
1. Notify Architect and Contractor promptly of irregularities or deficiencies observed in the Work during performance of its services.
  2. Determine the location from which test samples will be taken and in which in-situ tests are conducted.
  3. Conduct and interpret tests and inspections and state in each report whether tested and inspected work complies with or deviates from requirements.
  4. Submit a certified written report, in duplicate, of each test, inspection, and similar quality-control service through Contractor.
  5. Do not release, revoke, alter, or increase the Contract Document requirements or approve or accept any portion of the Work.
  6. Do not perform any duties of Contractor.
- G. Associated Services: Cooperate with agencies performing required tests, inspections, and similar quality-control services, and provide reasonable auxiliary services as requested. Notify agency sufficiently in advance of operations to permit assignment of personnel. Provide the following:
1. Access to the Work.
  2. Incidental labor and facilities necessary to facilitate tests and inspections.
  3. Adequate quantities of representative samples of materials that require testing and inspecting. Assist agency in obtaining samples.
  4. Facilities for storage and field curing of test samples.
  5. Delivery of samples to testing agencies.
  6. Preliminary design mix proposed for use for material mixes that require control by testing agency.
  7. Security and protection for samples and for testing and inspecting equipment at Project site.
- H. Coordination: Coordinate sequence of activities to accommodate required quality-assurance and -control services with a minimum of delay and to avoid necessity of removing and replacing construction to accommodate testing and inspecting.

1. Schedule times for tests, inspections, obtaining samples, and similar activities.

#### 1.9 SPECIAL TESTS AND INSPECTIONS

- A. See University of Utah U Facilities; General Conditions; Article 2 The University; 2.1 Information and Services Required of University; 2.1.2 Specialists and Inspectors.
- B. Special Tests and Inspections: Owner will Engage a qualified testing agency or special inspector to conduct special tests and inspections required by authorities having jurisdiction as the responsibility of Owner, and as follows:
  1. Verifying that manufacturer maintains detailed fabrication and quality-control procedures and reviews the completeness and adequacy of those procedures to perform the Work.
  2. Notifying Architect, Commissioning Authority, and Contractor promptly of irregularities and deficiencies observed in the Work during performance of its services.
  3. Submitting a certified written report of each test, inspection, and similar quality-control service to Architect and Commissioning Authority with copy to Contractor and to authorities having jurisdiction.
  4. Submitting a final report of special tests and inspections at Substantial Completion, which includes a list of unresolved deficiencies.
  5. Interpreting tests and inspections and stating in each report whether tested and inspected work complies with or deviates from the Contract Documents.
  6. Retesting and reinspecting corrected work.

#### 1.10 MOCK-UP PROVISIONS

- A. Prepare mock-ups for Work specifically requested in specifications. Include work for Sections required to provide mock-ups.
- B. Construct in locations indicated.
- C. Prepare mock-ups for Architect, Commissioning Agent, and Testing Agency review in reasonable promptness and in orderly sequence, to not cause delays of Work.
- D. Failure to prepare mock-ups in ample time is not considered sufficient reason for extension of Contract time and no claim for extension by reason of such default will be allowed.

#### PART 2 - PRODUCTS (Not Used)

#### PART 3 - EXECUTION

##### 3.1 TEST AND INSPECTION LOG

- A. Test and Inspection Log: Prepare a record of tests and inspections. Include the following:

1. Date test or inspection was conducted.
  2. Description of the Work tested or inspected.
  3. Date test or inspection results were transmitted to Architect.
  4. Identification of testing agency or special inspector conducting test or inspection.
- B. Maintain log at Project site. Post changes and revisions as they occur. Provide access to test and inspection log for Architect's, Commissioning Authority's, reference during normal working hours.

### 3.2 REPAIR AND PROTECTION

- A. General: On completion of testing, inspecting, sample taking, and similar services, repair damaged construction and restore substrates and finishes.
1. Provide materials and comply with installation requirements specified in other Specification Sections or matching existing substrates and finishes. Restore patched areas and extend restoration into adjoining areas with durable seams that are as invisible as possible. Comply with the Contract Document requirements for cutting and patching in Section 01 7300 "Execution."
- B. Protect construction exposed by or for quality-control service activities.
- C. Repair and protection are Contractor's responsibility, regardless of the assignment of responsibility for quality-control services.

END OF SECTION 01 4000

## SECTION 01 5000 - TEMPORARY FACILITIES AND CONTROLS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes requirements for temporary utilities, support facilities, and security and protection facilities, to extent not already provided in previously issued bid packages.
- B. Related Requirements:
  - 1. Section 01 1000 "Summary" for work restrictions and limitations on utility interruptions.

#### 1.2 USE CHARGES

- A. Installation, removal, and use charges for temporary facilities shall be included in the Contract Sum unless otherwise indicated. Allow other entities engaged in the Project to use temporary services and facilities without cost, including, but not limited to, Owner's construction forces, Architect, occupants of Project, testing agencies, and authorities having jurisdiction.
- B. Water and Sewer Service from Existing System: Water from Owner's existing water system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.
- C. Electric Power Service from Existing System: Electric power from Owner's existing system is available for use without metering and without payment of use charges. Provide connections and extensions of services as required for construction operations.

#### 1.3 INFORMATIONAL SUBMITTALS

- A. Site Plan: Show temporary facilities, staging areas, and parking areas for construction personnel.
- B. Erosion- and Sedimentation-Control Plan: Show compliance with requirements of EPA Construction General Permit or authorities having jurisdiction, whichever is more stringent.
- C. Fire-Safety Program: Show compliance with requirements of NFPA 241 and authorities having jurisdiction. Indicate Contractor personnel responsible for management of fire-prevention program.
- D. Dust- and HVAC-Control Plan: Submit coordination drawing and narrative that indicates the dust- and HVAC-control measures proposed for use, proposed locations, and proposed time frame for their operation. Identify further options if proposed measures are later determined to be inadequate. Include the following:

1. Locations of dust-control and ICRA barrier partitions at each phase of work.
2. HVAC system isolation schematic drawing.
3. Location of proposed air-filtration system discharge.
4. Waste handling procedures.
5. Other dust-control measures.

#### 1.4 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.
- C. Accessible Temporary Egress: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines and ICC/ANSI A117.1.

#### 1.5 PROJECT CONDITIONS

- A. Temporary Use of Permanent Facilities: Engage Installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use as a construction facility before Owner's acceptance, regardless of previously assigned responsibilities.

### PART 2 - PRODUCTS

#### 2.1 MATERIALS

- A. Polyethylene Sheet: Reinforced, fire-resistive sheet, 10-mil minimum thickness, with flame-spread rating of 15 or less in accordance with ASTM E84 and passing NFPA 701 Test Method 2.
- B. Dust-Control Adhesive-Surface Walk-Off Mats: Provide mats, minimum 36 by 60 inches.
- C. ICRA Barriers:

#### 2.2 TEMPORARY FACILITIES

- A. Common-Use Field Office: Space of sufficient size to accommodate needs of Owner, Architect, and construction personnel office activities and to accommodate Project meetings specified in other Division 01 Sections. Keep office clean and orderly. Furnish and equip offices as follows:



1. Furniture required for Project-site documents including file cabinets, plan tables, plan racks, and bookcases.
2. Conference room of sufficient size to accommodate meetings of 20 individuals. Provide electrical power service and 120-V ac duplex receptacles, with no fewer than one receptacle on each wall. Furnish room with conference table, chairs, and 4-foot- square tack and marker boards.
3. Drinking water and private toilet.
4. Copy machine and supplies.
5. Heating and cooling equipment necessary to maintain a uniform indoor temperature of 68 to 72 deg F.
6. Lighting fixtures capable of maintaining average illumination of 20 fc at desk height.

B. Storage and Fabrication Sheds:

1. Store combustible materials apart from building.

## 2.3 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.
- B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters with individual space thermostatic control.
  1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
  2. Heating Units: Listed and labeled for type of fuel being consumed, by a qualified testing agency acceptable to authorities having jurisdiction, and marked for intended location and application.
  3. Permanent HVAC System: The permanent HVAC system shall not be used for Construction activity ventilation.
- C. Air-Filtration Units: Primary and secondary HEPA-filter-equipped portable units with four-stage filtration. Provide single switch for emergency shutoff. Configure to run continuously.

## PART 3 - EXECUTION

### 3.1 INSTALLATION, GENERAL

- A. Locate facilities where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify facilities as required by progress of the Work.
- B. Provide each facility ready for use when needed to avoid delay. Do not remove until facilities are no longer needed or are replaced by authorized use of completed permanent facilities.

### 3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
  - 1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
- B. Water Service: Connect to Owner's existing water service facilities. Clean and maintain water service facilities in a condition acceptable to Owner. At Substantial Completion, restore these facilities to condition existing before initial use.
- C. Sanitary Facilities: Provide temporary toilets, wash facilities, and drinking water for use of construction personnel. Comply with requirements of authorities having jurisdiction for type, number, location, operation, and maintenance of fixtures and facilities.
- D. Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.
- E. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.
  - 1. Provide dehumidification systems when required to reduce substrate moisture levels to level required to allow installation or application of finishes.
- F. Electric Power Service: Connect to Owner's existing electric power service. Maintain equipment in a condition acceptable to Owner.
- G. Lighting: Provide temporary lighting with local switching that provides adequate illumination for construction operations, observations, inspections, and traffic conditions.
  - 1. Install and operate temporary lighting that fulfills security and protection requirements without operating entire system.

### 3.3 SUPPORT FACILITIES INSTALLATION

- A. General: Comply with the following:
  - 1. Provide construction for temporary sheds located within construction area or within 30 feet of building lines that is noncombustible according to ASTM E 136. Comply with NFPA 241.
  - 2. Maintain support facilities until Architect schedules Substantial Completion inspection. Remove before Substantial Completion. Personnel remaining after Substantial

Completion will be permitted to use permanent facilities, under conditions acceptable to Owner.

- B. Parking: Use designated areas of Owner's existing parking areas for construction personnel.
- C. Project Signs: Provide Project signs as indicated. Unauthorized signs are not permitted.
  - 1. Temporary Signs: Provide other signs as indicated and as required to inform public and individuals seeking entrance to Project.
    - a. Provide temporary, directional signs for construction personnel and visitors.
  - 2. Maintain and touchup signs so they are legible at all times.
- D. Waste Disposal Facilities: Comply with requirements specified in Section 01 7419 "Construction Waste Management and Disposal."
- E. Lifts and Hoists: Provide facilities necessary for hoisting materials and personnel.
  - 1. Truck cranes and similar devices used for hoisting materials are considered "tools and equipment" and not temporary facilities.

### 3.4 SECURITY AND PROTECTION FACILITIES INSTALLATION

- A. Protection of Existing Facilities: Protect existing vegetation, equipment, structures, utilities, and other improvements at Project site and on adjacent properties, except those indicated to be removed or altered. Repair damage to existing facilities.
- B. Environmental Protection: Provide protection, operate temporary facilities, and conduct construction as required to comply with environmental regulations and that minimize possible air, waterway, and subsoil contamination or pollution or other undesirable effects.
- C. Stormwater Control: Comply with requirements of authorities having jurisdiction. Provide barriers in and around excavations and subgrade construction to prevent flooding by runoff of stormwater from heavy rains.
- D. Security Enclosure and Lockup: Install temporary enclosure around partially completed areas of construction. Provide lockable entrances to prevent unauthorized entrance, vandalism, theft, and similar violations of security. Lock entrances at end of each work day.
- E. Barricades, Warning Signs, and Lights: Comply with requirements of authorities having jurisdiction for erecting structurally adequate barricades, including warning signs and lighting.
- F. Temporary Egress: Maintain temporary egress from existing occupied facilities as indicated and as required by authorities having jurisdiction.

- G. Temporary Enclosures: Provide temporary enclosures for protection of construction, in progress and completed, from exposure, foul weather, other construction operations, and similar activities. Provide temporary weathertight enclosure for building exterior.
  - 1. Where heating or cooling is needed and permanent enclosure is incomplete, insulate temporary enclosures.
- H. Temporary ICRA Barriers: Provide floor-to-ceiling dustproof partitions that comply with Class III and Class IV Infection Control Risk Assessment (ICRA) standards, to stop spread of infection, contamination, dust, and dirt migration and to separate areas occupied by Owner and patients from fumes and noise.
  - 1. Construct ICRA barrier dustproof partitions with gypsum wallboard, with joints taped on occupied side, and fire-retardant-treated plywood on construction operations side.
  - 2. Construct ICRA barriers that are fully-sealed, impermeable, and able to withstand expected negative air pressure levels.
    - a. Construct dustproof partitions with two layers of 6-mil polyethylene sheet on each side. Cover floor with two layers of 6-mil polyethylene sheet, extending sheets 18 inches up the sidewalls. Overlap and tape full length of joints. Cover floor with fire-retardant-treated plywood.
    - b. Construct vestibule and airlock at each entrance through temporary partition with not less than 48 inches between doors. Maintain water-dampened foot mats in vestibule.
  - 3. Where fire-resistance-rated temporary partitions are indicated or are required by authorities having jurisdiction, construct partitions according to the rated assemblies.
  - 4. Insulate partitions to control noise transmission to occupied areas.
  - 5. Seal joints and perimeter. Equip partitions with gasketed dustproof doors and security locks where openings are required.
  - 6. Protect air-handling equipment.
  - 7. Provide walk-off mats at each entrance through temporary partition.
- I. Temporary Fire Protection: Install and maintain temporary fire-protection facilities of types needed to protect against reasonably predictable and controllable fire losses. Comply with NFPA 241; manage fire-prevention program.
  - 1. Prohibit smoking on site..
  - 2. Supervise welding operations, combustion-type temporary heating units, and similar sources of fire ignition according to requirements of authorities having jurisdiction.
  - 3. Develop and supervise an overall fire-prevention and -protection program for personnel at Project site. Review needs with local fire department and establish procedures to be followed. Instruct personnel in methods and procedures. Post warnings and information.
  - 4. Provide temporary standpipes and hoses for fire protection. Hang hoses with a warning sign stating that hoses are for fire-protection purposes only and are not to be removed. Match hose size with outlet size and equip with suitable nozzles.

### 3.5 OPERATION, TERMINATION, AND REMOVAL

- A. Supervision: Enforce strict discipline in use of temporary facilities. To minimize waste and abuse, limit availability of temporary facilities to essential and intended uses.
- B. Maintenance: Maintain facilities in good operating condition until removal.
  - 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar facilities on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
- C. Temporary Facility Changeover: Do not change over from using temporary security and protection facilities to permanent facilities until Substantial Completion.
- D. Termination and Removal: Remove each temporary facility when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
  - 1. Materials and facilities that constitute temporary facilities are property of Contractor. Owner reserves right to take possession of Project identification signs.
  - 2. Remove temporary roads and paved areas not intended for or acceptable for integration into permanent construction. Where area is intended for landscape development, remove soil and aggregate fill that do not comply with requirements for fill or subsoil. Remove materials contaminated with road oil, asphalt and other petrochemical compounds, and other substances that might impair growth of plant materials or lawns. Repair or replace street paving, curbs, and sidewalks at temporary entrances, as required by authorities having jurisdiction.
  - 3. At Substantial Completion, repair, renovate, and clean permanent facilities used during construction period. Comply with final cleaning requirements specified in Section 01 7700 "Closeout Procedures."

END OF SECTION 01 5000

## SECTION 01 6000 - PRODUCT REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes administrative and procedural requirements for selection of products for use in Project; product delivery, storage, and handling; manufacturers' standard warranties on products; special warranties; and comparable products.
- B. Related Requirements:
  - 1. Section 01 2300 "Alternates" for products selected under an alternate.
  - 2. Section 01 2500 "Substitution Procedures" for requests for substitutions.

#### 1.3 DEFINITIONS

- A. Products: Items obtained for incorporating into the Work, whether purchased for Project or taken from previously purchased stock. The term "product" includes the terms "material," "equipment," "system," and terms of similar intent.
  - 1. Named Products: Items identified by manufacturer's product name, including make or model number or other designation shown or listed in manufacturer's published product literature that is current as of date of the Contract Documents.
  - 2. New Products: Items that have not previously been incorporated into another project or facility. Products salvaged or recycled from other projects are not considered new products.
  - 3. Comparable Product: Product that is demonstrated and approved by Architect through submittal process to have the indicated qualities related to type, function, dimension, in-service performance, physical properties, appearance, and other characteristics that equal or exceed those of specified product.
- B. Basis-of-Design Product Specification: A specification in which a single manufacturer's product is named and accompanied by the words "basis-of-design product," including make or model number or other designation. In addition to the basis-of-design product description, product attributes and characteristics may be listed to establish the significant qualities related to type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other special features and requirements for purposes of evaluating comparable products of additional manufacturers named in the specification.

- C. Subject to Compliance with Requirements: Where the phrase "Subject to compliance with requirements" introduces a product selection procedure in an individual Specification Section, provide products qualified under the specified product procedure. In the event that a named product or product by a named manufacturer does not meet the other requirements of the specifications, select another named product or product from another named manufacturer that does meet the requirements of the specifications. Submit a comparable product request, if applicable.

#### 1.4 ACTION SUBMITTALS

- A. Comparable Product Request Submittal: Submit request for consideration of each comparable product. Identify basis-of-design product or fabrication or installation method to be replaced. Include Specification Section number and title and Drawing numbers and titles.
  - 1. Include data to indicate compliance with the requirements specified in "Comparable Products" Article.
  - 2. Architect's Action: If necessary, Architect will request additional information or documentation for evaluation within seven days of receipt of a comparable product request. Architect will notify Contractor of approval or rejection of proposed comparable product request within 15 days of receipt of request, or seven days of receipt of additional information or documentation, whichever is later.
    - a. Form of Architect's Approval of Submittal: As specified in Section 01 3300 "Submittal Procedures."
    - b. Use product specified if Architect does not issue a decision on use of a comparable product request within time allocated.
- B. Basis-of-Design Product Specification Submittal: Comply with requirements in Section 01 3300 "Submittal Procedures." Show compliance with requirements.

#### 1.5 QUALITY ASSURANCE

- A. Compatibility of Options: If Contractor is given option of selecting between two or more products for use on Project, select product compatible with products previously selected, even if previously selected products were also options.
  - 1. Each contractor is responsible for providing products and construction methods compatible with products and construction methods of other contractors.
  - 2. If a dispute arises between contractors over concurrently selectable but incompatible products, Architect will determine which products shall be used.
- B. Identification of Products: Except for required labels and operating data, do not attach or imprint manufacturer or product names or trademarks on exposed surfaces of products or equipment that will be exposed to view in occupied spaces or on the exterior.

1. Labels: Locate required product labels and stamps on a concealed surface, or, where required for observation following installation, on a visually accessible surface that is not conspicuous.
2. Equipment Nameplates: Provide a permanent nameplate on each item of service-connected or power-operated equipment. Locate on a visually accessible but inconspicuous surface. Include information essential for operation, including the following:
  - a. Name of product and manufacturer.
  - b. Model and serial number.
  - c. Capacity.
  - d. Speed.
  - e. Ratings.
3. See individual identification sections in Divisions 21, 22, 23, and 26 for additional identification requirements.

#### 1.6 PRODUCT DELIVERY, STORAGE, AND HANDLING

- A. Deliver, store, and handle products using means and methods that will prevent damage, deterioration, and loss, including theft and vandalism. Comply with manufacturer's written instructions.
- B. Delivery and Handling:
  1. Schedule delivery to minimize long-term storage at Project site and to prevent overcrowding of construction spaces.
  2. Coordinate delivery with installation time to ensure minimum holding time for items that are flammable, hazardous, easily damaged, or sensitive to deterioration, theft, and other losses.
  3. Deliver products to Project site in an undamaged condition in manufacturer's original sealed container or other packaging system, complete with labels and instructions for handling, storing, unpacking, protecting, and installing.
  4. Inspect products on delivery to determine compliance with the Contract Documents and to determine that products are undamaged and properly protected.
- C. Storage:
  1. Store products to allow for inspection and measurement of quantity or counting of units.
  2. Store materials in a manner that will not endanger Project structure.
  3. Store products that are subject to damage by the elements, under cover in a weather tight enclosure above ground, with ventilation adequate to prevent condensation.
  4. Protect foam plastic from exposure to sunlight, except to extent necessary for period of installation and concealment.
  5. Comply with product manufacturer's written instructions for temperature, humidity, ventilation, and weather-protection requirements for storage.
  6. Protect stored products from damage and liquids from freezing.



7. Provide a secure location and enclosure at Project site for storage of materials and equipment by Owner's construction forces. Coordinate location with Owner.

## 1.7 PRODUCT WARRANTIES

- A. Warranties specified in other Sections shall be in addition to, and run concurrent with, other warranties required by the Contract Documents. Manufacturer's disclaimers and limitations on product warranties do not relieve Contractor of obligations under requirements of the Contract Documents.
  1. Manufacturer's Warranty: Written warranty furnished by individual manufacturer for a particular product and specifically endorsed by manufacturer to Owner.
  2. Special Warranty: Written warranty required by the Contract Documents to provide specific rights for Owner.
- B. Special Warranties: Prepare a written document that contains appropriate terms and identification, ready for execution.
  1. Manufacturer's Standard Form: Modified to include Project-specific information and properly executed.
  2. Specified Form: When specified forms are included with the Specifications, prepare a written document using indicated form properly executed.
  3. See other Sections for specific content requirements and particular requirements for submitting special warranties.
- C. Submittal Time: Comply with requirements in Section 01 7700 "Closeout Procedures."

## PART 2 - PRODUCTS

### 2.1 PRODUCT SELECTION PROCEDURES

- A. General Product Requirements: Provide products that comply with the Contract Documents, are undamaged and, unless otherwise indicated, are new at time of installation.
  1. Provide products complete with accessories, trim, finish, fasteners, and other items needed for a complete installation and indicated use and effect.
  2. Standard Products: If available, and unless custom products or nonstandard options are specified, provide standard products of types that have been produced and used successfully in similar situations on other projects.
  3. Owner reserves the right to limit selection to products with warranties meeting requirements of the
  4. Contract Documents.
  5. Where products are accompanied by the term "as selected," Architect will make selection.
  6. Descriptive, performance, and reference standard requirements in the Specifications establish salient characteristics of products.

7. Or Equal: For products specified by name and accompanied by the term "or equal," or "or approved equal," or "or approved," comply with requirements in "Comparable Products" Article to obtain approval for use of an unnamed product.
  - a. Submit additional documentation required by Architect in order to establish equivalency of proposed products. Evaluation of "or equal" product status is by the Architect, whose determination is final.

B. Product Selection Procedures:

1. Sole Product: Where Specifications name a single manufacturer and product, provide the named product that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
  - a. Sole product may be indicated by the phrase: "Subject to compliance with requirements, provide the following: ..."
2. Sole Manufacturer/Source: Where Specifications name a single manufacturer or source, provide a product by the named manufacturer or source that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered.
  - a. Sole manufacturer/source may be indicated by the phrase: "Subject to compliance with requirements, provide products by the following: ..."
3. Limited List of Products: Where Specifications include a list of names of both manufacturers and products, provide one of the products listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated by the addition of "Or As Approved" or "Or Approved Comparable Product".
  - a. Limited list of products may be indicated by the phrase: "Subject to compliance with requirements, provide one of the following: ..."
4. Non-Limited List of Products: Where Specifications include a list of names of both available manufacturers and products, provide one of the products listed, or an unnamed product, which complies with requirements.
  - a. Non-limited list of products is indicated by the phrase: "Subject to compliance with requirements, available products that may be incorporated in the Work include, but are not limited to, the following: ..."
5. Limited List of Manufacturers: Where Specifications include a list of manufacturers' names, provide a product by one of the manufacturers listed that complies with requirements. Comparable products or substitutions for Contractor's convenience will not be considered unless otherwise indicated by the addition of "Or As Approved" or "Or Approved Comparable Product".

- a. Limited list of manufacturers is indicated by the phrase: "Subject to compliance with requirements, provide products by one of the following: ..."
- 6. Non-Limited List of Manufacturers: Where Specifications include a list of available manufacturers, provide a product by one of the manufacturers listed, or a product by an unnamed manufacturer, which complies with requirements.
  - a. Non-limited list of manufacturers is indicated by the phrase: "Subject to compliance with requirements, available manufacturers whose products may be incorporated in the Work include, but are not limited to, the following: ..."
- 7. Basis-of-Design Product: Where Specifications name a product, or refer to a product indicated on Drawings, and include a list of manufacturers, provide the specified or indicated product or a comparable product by one of the other named manufacturers. Drawings and Specifications indicate sizes, profiles, dimensions, and other characteristics that are based on the product named. Comply with requirements in "Comparable Products" Article for consideration of an unnamed product by one of the other named manufacturers.
  - a. For approval of products by unnamed manufacturers, comply with requirements in Section 01 2500 "Substitution Procedures" for substitutions for convenience.
- 8. Reference Standards: Where Specifications describe a product by referring to a reference standard without listing product/manufacturer, propose a product that meets the standard. Where additional product description modifies the reference standard, proposed product shall meet the standard as modified.
  - a. A product specified by reference standard shall comply with the requirements of the standard in effect on the date of the Bidding Documents, except:
    - 1) Where a date is specified with the standard; then the edition of the standard so dated shall govern.
    - 2) Where the governing code requires compliance to another edition of the standard.
- C. Product Uniformity: It is the intent of the Documents that the completed construction be uniform throughout the Project. For each type of product, the manufacturer and model shall not vary. After a particular product has been identified and approved for an application, that product shall be used for that application across all the subcontracts and other Work-related contracts held by the Contractor or Construction Manager. This provision applies equally to accepted substitutions.
- D. Visual Matching Specification: Where Specifications require "match Architect's sample," provide a product that complies with requirements and matches Architect's sample. Architect's decision will be final on whether a proposed product matches.
  - 1. If no product available within specified category matches and complies with other specified requirements, comply with requirements in Section 01 2500 "Substitution Procedures" for proposal of product.

- E. Visual Selection Specification: Where Specifications include the phrase "as selected by Architect from manufacturer's full range" or similar phrase, select a product that complies with requirements. Architect will select color, gloss, pattern, density, or texture from manufacturer's product line that includes both standard and premium items.

## 2.2 COMPARABLE PRODUCTS

- A. Conditions for Consideration of Comparable Products: Architect will consider Contractor's request for comparable product when the following conditions are satisfied. If the following conditions are not satisfied, Architect may return requests without action, except to record noncompliance with these requirements:
  - 1. The product option and selection procedure, as described in this Section, governing the specified product:
    - a. Allows the Contractor to make comparable product requests.
    - b. Does not require the use of the product substitution procedure.
  - 2. Evidence that proposed product does not require revisions to the Contract Documents, is consistent with the Contract Documents, will produce the indicated results, and is compatible with other portions of the Work. Detailed comparison of significant qualities of proposed product with those named in the Specifications. Significant product qualities include attributes such as type, function, in-service performance and physical properties, weight, dimension, durability, visual characteristics, and other specific features and requirements.
  - 3. Evidence that proposed product provides specified warranty.
  - 4. List of similar installations for completed projects with project names and addresses and names and addresses of architects and owners, if requested.
  - 5. Samples, if requested.
  - 6. By proposing a product that is not listed, for consideration as a comparable product, the Contractor affirms that it meets requirements, except where clearly indicated otherwise. Approval, if granted, will be contingent upon the product meeting requirements as comparable product. In the absence of clear indication of non-compliance in product submittal, approval of the comparable product by Architect, will be based on Contractor's affirmation, whether explicit or implicit.
- B. Submittal Requirements: Approval by the Architect of Contractor's request for use of comparable product is not intended to satisfy other submittal requirements. Comply with specified submittal requirements.

## PART 3 - EXECUTION (Not Used)

END OF SECTION 01 6000

## SECTION 01 7300 - EXECUTION

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes general administrative and procedural requirements governing execution of the Work including, but not limited to, the following:
  - 1. Construction layout.
  - 2. Installation of the Work.
  - 3. Cutting and patching.
  - 4. Progress cleaning.
  - 5. Starting and adjusting.
  - 6. Protection of installed construction.
- B. Related Requirements:
  - 1. Section 01 1000 "Summary" for limits on use of Project site.
  - 2. Section 01 3300 "Submittal Procedures" for submitting surveys.
  - 3. Section 01 7700 "Closeout Procedures" for recording of Owner-accepted deviations from indicated lines and levels, and final cleaning.

#### 1.2 DEFINITIONS

- A. Cutting: Removal of in-place construction necessary to permit installation or performance of other work.
- B. Patching: Fitting and repair work required to restore construction to original conditions after installation of other work.

#### 1.3 INFORMATIONAL SUBMITTALS

- A. Cutting and Patching Plan: Submit plan describing procedures at least 10 days prior to the time cutting and patching will be performed. Include the following information:
  - 1. Extent: Describe reason for and extent of each occurrence of cutting and patching.
  - 2. Changes to In-Place Construction: Describe anticipated results. Include changes to structural elements and operating components as well as changes in building appearance and other significant visual elements.
  - 3. Products: List products to be used for patching and firms or entities that will perform patching work.
  - 4. Dates: Indicate when cutting and patching will be performed.

5. Utilities and Mechanical and Electrical Systems: List services and systems that cutting and patching procedures will disturb or affect. List services and systems that will be relocated and those that will be temporarily out of service. Indicate length of time permanent services and systems will be disrupted.

- a. Include description of provisions for temporary services and systems during interruption of permanent services and systems.

- B. Landfill Receipts: Submit copy of receipts issued by a landfill facility, licensed to accept hazardous materials, for hazardous waste disposal.

## 1.4 QUALITY ASSURANCE

- A. Cutting and Patching: Comply with requirements for and limitations on cutting and patching of construction elements.

1. Structural Elements: When cutting and patching structural elements, notify Architect of locations and details of cutting and await directions from Architect before proceeding. Shore, brace, and support structural elements during cutting and patching. Do not cut and patch structural elements in a manner that could change their load-carrying capacity or increase deflection.
2. Operational Elements: Do not cut and patch operating elements and related components in a manner that results in reducing their capacity to perform as intended or that results in increased maintenance or decreased operational life or safety.
3. Other Construction Elements: Do not cut and patch other construction elements or components in a manner that could change their load-carrying capacity, that results in reducing their capacity to perform as intended, or that results in increased maintenance or decreased operational life or safety.
4. Visual Elements: Do not cut and patch construction in a manner that results in visual evidence of cutting and patching. Do not cut and patch exposed construction in a manner that would, in Architect's opinion, reduce the building's aesthetic qualities. Remove and replace construction that has been cut and patched in a visually unsatisfactory manner.

- B. Cutting and Patching Conference: Before proceeding, meet at Project site with parties involved in cutting and patching, including mechanical and electrical trades. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.

- C. Manufacturer's Installation Instructions: Obtain and maintain on-site manufacturer's written recommendations and instructions for installation of products and equipment.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. General: Comply with requirements specified in other Sections.

- B. In-Place Materials: Use materials for patching identical to in-place materials. For exposed surfaces, use materials that visually match in-place adjacent surfaces to the fullest extent possible.
  - 1. If identical materials are unavailable or cannot be used, use materials that, when installed, will provide a match acceptable to Architect for the visual and functional performance of in-place materials.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Existing Conditions: The existence and location of utilities and construction indicated as existing are not guaranteed. Before beginning sitework, investigate and verify the existence and location of mechanical and electrical systems, and other construction affecting the Work.
  - 1. Before construction, verify the location and invert elevation at points of connection of sanitary sewer, storm sewer, and water-service piping; underground electrical services, and other utilities.
- B. Examination and Acceptance of Conditions: Before proceeding with each component of the Work, examine substrates, areas, and conditions, with Installer or Applicator present where indicated, for compliance with requirements for installation tolerances and other conditions affecting performance. Record observations.
  - 1. Examine roughing-in for mechanical and electrical systems to verify actual locations of connections before equipment and fixture installation.
  - 2. Examine walls, floors, and roofs for suitable conditions where products and systems are to be installed.
  - 3. Verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Proceed with installation only after unsatisfactory conditions have been corrected. Proceeding with the Work indicates acceptance of surfaces and conditions.

### 3.2 PREPARATION

- A. Field Measurements: Take field measurements as required to fit the Work properly. Recheck measurements before installing each product. Where portions of the Work are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Space Requirements: Verify space requirements and dimensions of items shown diagrammatically on Drawings.

- C. Review of Contract Documents and Field Conditions: Immediately on discovery of the need for clarification of the Contract Documents caused by differing field conditions outside the control of Contractor, submit a request for information to Architect according to requirements in Section 01 3100 "Project Management and Coordination."

### 3.3 CONSTRUCTION LAYOUT

- A. Verification: Before proceeding to lay out the Work, verify layout information shown on Drawings, in relation to existing benchmarks. If discrepancies are discovered, notify Architect promptly.

### 3.4 INSTALLATION

- A. General: Locate the Work and components of the Work accurately, in correct alignment and elevation, as indicated.
  - 1. Make vertical work plumb and make horizontal work level.
  - 2. Where space is limited, install components to maximize space available for maintenance and ease of removal for replacement.
  - 3. Conceal pipes, ducts, and wiring in finished areas unless otherwise indicated.
  - 4. Maintain minimum headroom clearance of 96 inches in occupied spaces and 90 inches in unoccupied spaces.
- B. Comply with manufacturer's written instructions and recommendations for installing products in applications indicated.
- C. Install products at the time and under conditions that will ensure the best possible results. Maintain conditions required for product performance until Substantial Completion.
- D. Conduct construction operations so no part of the Work is subjected to damaging operations or loading in excess of that expected during normal conditions of occupancy.
- E. Sequence the Work and allow adequate clearances to accommodate movement of construction items on site and placement in permanent locations.
- F. Tools and Equipment: Do not use tools or equipment that produce harmful noise levels.
- G. Templates: Obtain and distribute to the parties involved templates for work specified to be factory prepared and field installed. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing products to comply with indicated requirements.
- H. Attachment: Provide blocking and attachment plates and anchors and fasteners of adequate size and number to securely anchor each component in place, accurately located and aligned with other portions of the Work. Where size and type of attachments are not indicated, verify size and type required for load conditions.



1. Mounting Heights: Where mounting heights are not indicated, mount components at heights directed by Architect.
  2. Allow for building movement, including thermal expansion and contraction.
  3. Coordinate installation of anchorages. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.
- I. Joints: Make joints of uniform width. Where joint locations in exposed work are not indicated, arrange joints for the best visual effect. Fit exposed connections together to form hairline joints.
- J. Hazardous Materials: Use products, cleaners, and installation materials that are not considered hazardous.

### 3.5 CUTTING AND PATCHING

- A. Cutting and Patching, General: Employ skilled workers to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time, and complete without delay.
1. Cut in-place construction to provide for installation of other components or performance of other construction, and subsequently patch as required to restore surfaces to their original condition.
- B. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during installation or cutting and patching operations, by methods and with materials so as not to void existing warranties.
- C. Temporary Support: Provide temporary support of work to be cut.
- D. Protection: Protect in-place construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of Project that might be exposed during cutting and patching operations.
- E. Adjacent Occupied Areas: Where interference with use of adjoining areas or interruption of free passage to adjoining areas is unavoidable, coordinate cutting and patching according to requirements in Section 01 1000 "Summary."
- F. Existing Utility Services and Mechanical/Electrical Systems: Where existing services/systems are required to be removed, relocated, or abandoned, bypass such services/systems before cutting to minimize interruption to occupied areas.
- G. Cutting: Cut in-place construction by sawing, drilling, breaking, chipping, grinding, and similar operations, including excavation, using methods least likely to damage elements retained or adjoining construction. If possible, review proposed procedures with original Installer; comply with original Installer's written recommendations.

1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots neatly to minimum size required, and with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
  2. Finished Surfaces: Cut or drill from the exposed or finished side into concealed surfaces.
  3. Concrete and Masonry: Cut using a cutting machine, such as an abrasive saw or a diamond-core drill.
  4. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
  5. Proceed with patching after construction operations requiring cutting are complete.
- H. Patching: Patch construction by filling, repairing, refinishing, closing up, and similar operations following performance of other work. Patch with durable seams that are as invisible as practicable. Provide materials and comply with installation requirements specified in other Sections, where applicable.
1. Inspection: Where feasible, test and inspect patched areas after completion to demonstrate physical integrity of installation.
  2. Exposed Finishes: Restore exposed finishes of patched areas and extend finish restoration into retained adjoining construction in a manner that will minimize evidence of patching and refinishing.
    - a. Clean piping, conduit, and similar features before applying paint or other finishing materials.
    - b. Restore damaged pipe covering to its original condition.
  3. Floors and Walls: Where walls or partitions that are removed extend one finished area into another, patch and repair floor and wall surfaces in the new space. Provide an even surface of uniform finish, color, texture, and appearance. Remove in-place floor and wall coverings and replace with new materials, if necessary, to achieve uniform color and appearance.
    - a. Where patching occurs in a painted surface, prepare substrate and apply primer and intermediate paint coats appropriate for substrate over the patch, and apply final paint coat over entire unbroken surface containing the patch. Provide additional coats until patch blends with adjacent surfaces.
  4. Ceilings: Patch, repair, or rehang in-place ceilings as necessary to provide an even-plane surface of uniform appearance.
  5. Exterior Building Enclosure: Patch components in a manner that restores enclosure to a weathertight condition and ensures thermal and moisture integrity of building enclosure.
- I. Cleaning: Clean areas and spaces where cutting and patching are performed. Remove paint, mortar, oils, putty, and similar materials from adjacent finished surfaces.

### 3.6 PROGRESS CLEANING

- A. See University of Utah Facilities Management; General Conditions; Article 4 Contractor; 4.9 Use of Site; 4.9.1 In General.
- B. General: Clean Project site and work areas daily, including common areas. Enforce requirements strictly. Dispose of materials lawfully.
  - 1. Comply with requirements in NFPA 241 for removal of combustible waste materials and debris.
  - 2. Do not hold waste materials more than seven days during normal weather or three days if the temperature is expected to rise above 80 deg F.
  - 3. Containerize hazardous and unsanitary waste materials separately from other waste. Mark containers appropriately and dispose of legally, according to regulations.
    - a. Use containers intended for holding waste materials of type to be stored.
  - 4. Coordinate progress cleaning for joint-use areas where Contractor and other contractors are working concurrently.
- C. Site: Maintain Project site free of waste materials and debris.
- D. Work Areas: Clean areas where work is in progress to the level of cleanliness necessary for proper execution of the Work.
  - 1. Remove liquid spills promptly.
  - 2. Where dust would impair proper execution of the Work, broom-clean or vacuum the entire work area, as appropriate.
- E. Installed Work: Keep installed work clean. Clean installed surfaces according to written instructions of manufacturer or fabricator of product installed, using only cleaning materials specifically recommended. If specific cleaning materials are not recommended, use cleaning materials that are not hazardous to health or property and that will not damage exposed surfaces.
- F. Concealed Spaces: Remove debris from concealed spaces before enclosing the space.
- G. Exposed Surfaces in Finished Areas: Clean exposed surfaces and protect as necessary to ensure freedom from damage and deterioration at time of Substantial Completion.
- H. Waste Disposal: Do not bury or burn waste materials on-site. Do not wash waste materials down sewers or into waterways. Comply with waste disposal requirements in Section 01 7419 "Construction Waste Management and Disposal."
- I. During handling and installation, clean and protect construction in progress and adjoining materials already in place. Apply protective covering where required to ensure protection from damage or deterioration at Substantial Completion.

- J. Clean and provide maintenance on completed construction as frequently as necessary through the remainder of the construction period. Adjust and lubricate operable components to ensure operability without damaging effects.
- K. Limiting Exposures: Supervise construction operations to assure that no part of the construction, completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period.

### 3.7 STARTING AND ADJUSTING

- A. Coordinate startup and adjusting of equipment and operating components with requirements in Section 01 9113 "General Commissioning Requirements."
- B. Start equipment and operating components to confirm proper operation. Remove malfunctioning units, replace with new units, and retest.
- C. Adjust equipment for proper operation. Adjust operating components for proper operation without binding.
- D. Test each piece of equipment to verify proper operation. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- E. Manufacturer's Field Service: Comply with qualification requirements in Section 01 4000 "Quality Requirements."

### 3.8 PROTECTION OF INSTALLED CONSTRUCTION

- A. Provide final protection and maintain conditions that ensure installed Work is without damage or deterioration at time of Substantial Completion.
- B. Comply with manufacturer's written instructions for temperature and relative humidity.

END OF SECTION 01 7300

## SECTION 01 7419 - CONSTRUCTION WASTE MANAGEMENT AND DISPOSAL

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for the following:

1. Salvaging nonhazardous demolition and construction waste.
2. Recycling nonhazardous demolition and construction waste.
3. Disposing of nonhazardous demolition and construction waste.

#### 1.2 DEFINITIONS

- A. Construction Waste: Building, structure, and site improvement materials and other solid waste resulting from construction, remodeling, renovation, or repair operations. Construction waste includes packaging.
- B. Demolition Waste: Building, structure, and site improvement materials resulting from demolition operations.
- C. Disposal: Removal of demolition or construction waste and subsequent salvage, recycling, or deposit in landfill, incinerator acceptable to authorities having jurisdiction, or designated spoil areas on Owner's property.
- D. Recycle: Recovery of demolition or construction waste for subsequent processing in preparation for reuse.
- E. Salvage: Recovery of demolition or construction waste and subsequent reuse in another facility.
- F. Salvage and Reuse: Recovery of demolition or construction waste and subsequent incorporation into the Work.

#### 1.3 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition and construction waste becomes property of Contractor.

#### 1.4 PERFORMANCE GOALS

- A. Salvage/Recycle Goals: Owner's intent is to salvage and recycle as much nonhazardous demolition waste as possible. Contractor is encouraged to use remaining salvageable or recyclable items to add value to the bid. Items that may be salvaged or recycled include all building and site components, packaging, and temporary construction elements.

- B. Comply with Salt Lake City's sustainability initiative.

- 1. Website: <https://www.slc.gov/sustainability/waste-management/construction-demolition-waste/>

#### 1.5 ACTION SUBMITTALS

- A. Waste Management Plan: Submit 3 copies of plan within 7 days of date established for the Notice to Proceed.
- B. Recycling and Processing Facility Records: Indicate receipt and acceptance of recyclable waste by recycling and processing facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.
- C. Landfill and Incinerator Disposal Records: Indicate receipt and acceptance of waste by landfills and incinerator facilities licensed to accept them. Include manifests, weight tickets, receipts, and invoices.
- D. Qualification Data: For refrigerant recovery technician.

#### 1.6 QUALITY ASSURANCE

- A. Regulatory Requirements: Comply with transportation and disposal regulations of authorities having jurisdiction.
- B. Waste Management Conference: Conduct conference at Project site to comply with requirements in Section 01 3100 "Project Management and Coordination." Review methods and procedures related to waste management including, but not limited to, the following:
  - 1. Review and discuss waste management plan including responsibilities of each contractor and waste management coordinator.
  - 2. Review requirements for documenting quantities of each type of waste and its disposition.
  - 3. Review and finalize procedures for materials separation and verify availability of containers and bins needed to avoid delays.
  - 4. Review procedures for periodic waste collection and transportation to recycling and disposal facilities.
  - 5. Review waste management requirements for each trade.

#### 1.7 WASTE MANAGEMENT PLAN

- A. General: Develop a waste management plan according to requirements in this Section. Distinguish between demolition and construction waste. Indicate quantities by weight or volume, but use same units of measure throughout waste management plan.

- B. Waste Identification: Indicate anticipated types and quantities of demolition and construction waste generated by the Work.
- C. Waste Management Plan: Include the following:
  - 1. Description of how minimum of 55 percent of waste will be recycled or reused.
  - 2. Description of efforts to be employed to reduce the amount of waste generated by the project.
  - 3. Description of procedure that will be used to train construction employees and ensure performance of proper recycling and reuse methods.
  - 4. Listing of total amount and types of waste reused, recycled, or composted and what amount and types of the waste will be taken to the Landfill.
    - a. List each type of waste and whether it will be salvaged, recycled, or disposed of in landfill or incinerator. Include points of waste generation, total quantity of each type of waste, quantity for each means of recovery, and handling and transportation procedures.
  - 5. Names of facilities where waste materials will be taken.
    - a. Recycled Materials: Include list of local receivers and processors and type of recycled materials each will accept. Include names, addresses, and telephone numbers.
    - b. Disposed Materials: Indicate how and where materials will be disposed of. Include name, address, and telephone number of each landfill and incinerator facility.
    - c. Handling and Transportation Procedures: Include method that will be used for separating recyclable waste including sizes of containers, container labeling, and designated location where materials separation will be performed.

## PART 2 - PRODUCTS (NOT USED)

## PART 3 - EXECUTION

### 3.1 PLAN IMPLEMENTATION

- A. General: Implement approved waste management plan. Provide handling, containers, storage, signage, transportation, and other items as required to implement waste management plan during the entire duration of the Contract.
  - 1. Comply with operation, termination, and removal requirements in Section 01 5000 "Temporary Facilities and Controls."
- B. Training: Train workers, subcontractors, and suppliers on proper waste management procedures, as appropriate for the Work.

1. Distribute waste management plan to everyone concerned within three days of submittal return.
  2. Distribute waste management plan to entities when they first begin work on-site. Review plan procedures and locations established for salvage, recycling, and disposal.
- C. Site Access and Temporary Controls: Conduct waste management operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
1. Designate and label specific areas on Project site necessary for separating materials that are to be salvaged and recycled.
  2. Comply with Section 01 5000 "Temporary Facilities and Controls" for controlling dust and dirt, environmental protection, and noise control.
- D. Provide bilingual signage at dumpsters at bins.

### 3.2 SALVAGING DEMOLITION WASTE

- A. Hardware: Remove all salvaged door hardware. Package all items associated with each item of hardware together.
- B. Equipment: Drain tanks, piping, and fixtures. Seal openings with caps or plugs. Protect equipment from exposure to weather.
- C. Plumbing Fixtures: Separate by type and size.
- D. Lighting Fixtures: Separate lamps by type and protect from breakage.
- E. Electrical Devices: Separate switches, receptacles, switchgear, transformers, meters, panelboards, circuit breakers, and other devices by type.

### 3.3 RECYCLING DEMOLITION AND CONSTRUCTION WASTE, GENERAL

- A. General: Recycle paper and beverage containers used by on-site workers.
- B. Recycling Incentives: Revenues, savings, rebates, tax credits, and other incentives received for recycling waste materials shall accrue to Contractor.
- C. Preparation of Waste: Prepare and maintain recyclable waste materials according to recycling or reuse facility requirements. Maintain materials free of dirt, adhesives, solvents, petroleum contamination, and other substances deleterious to the recycling process.
- D. Procedures: Separate recyclable waste from other waste materials, trash, and debris. Separate recyclable waste by type at Project site to the maximum extent practical according to approved construction waste management plan.



1. Provide appropriately marked containers or bins for controlling recyclable waste until removed from Project site. Include list of acceptable and unacceptable materials at each container and bin.
  - a. Inspect containers and bins for contamination and remove contaminated materials if found.
2. Stockpile processed materials on-site without intermixing with other materials. Place, grade, and shape stockpiles to drain surface water. Cover to prevent windblown dust.
3. Stockpile materials away from construction area. Do not store within drip line of remaining trees.
4. Store components off the ground and protect from the weather.
5. Remove recyclable waste from Owner's property and transport to recycling receiver or processor as often as required to prevent overfilling bins.

### 3.4 RECYCLING DEMOLITION WASTE

- A. Concrete: Remove reinforcement and other metals from concrete and sort with other metals.
  1. Pulverize concrete to maximum 1-1/2-inch size.
  2. Crush concrete and screen to comply with requirements in Section 31 2000 "Earth Moving" for use as satisfactory soil for fill or subbase.
- B. Wood Materials: Chip demolished wood.
- C. Metals: Separate metals by type.
  1. Remove and dispose of rebar, bolts, nuts, washers, and other rough hardware.
- D. Gypsum Board: Stack large clean pieces on wood pallets or in container and store in a dry location. Remove edge trim and sort with other metals. Remove and dispose of fasteners.
- E. Piping: Reduce piping to straight lengths and store by material and size. Separate supports, hangers, valves, sprinklers, and other components by material and size.
- F. Conduit: Reduce conduit to straight lengths and store by material and size.
- G. Lamps: Separate lamps by type and store according to requirements in 40 CFR 273.

### 3.5 RECYCLING CONSTRUCTION WASTE

- A. Packaging:
  1. Cardboard and Boxes: Break down packaging into flat sheets. Bundle and store in a dry location.
  2. Polystyrene Packaging: Separate and bag materials.

3. Pallets: As much as possible, require deliveries using pallets to remove pallets from Project site. For pallets that remain on-site, break down pallets into component wood pieces and comply with requirements for recycling wood.
4. Crates: Break down crates into component wood pieces and comply with requirements for recycling wood.

B. Wood Materials:

1. Clean Cut-Offs of Lumber: Grind or chip into small pieces.
2. Clean Sawdust: Bag sawdust that does not contain painted or treated wood.

C. Gypsum Board: Stack large clean pieces on wood pallets or in container and store in a dry location.

D. Paint: Seal containers and store by type.

3.6 DISPOSAL OF WASTE

A. General: Except for items or materials to be salvaged or recycled, remove waste materials from Project site and legally dispose of them in a landfill or incinerator acceptable to authorities having jurisdiction.

1. Except as otherwise specified, do not allow waste materials that are to be disposed of accumulate on-site.
2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.

B. Burning: Do not burn waste materials.

END OF SECTION 01 7419

## SECTION 01 7700 - CLOSEOUT PROCEDURES

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for contract closeout, including, but not limited to, the following:
  - 1. Substantial Completion procedures.
  - 2. Final completion procedures.
  - 3. Warranties.
  - 4. Final cleaning.
  - 5. Repair of the Work.
- B. Related Requirements:
  - 1. Section 01 7300 "Execution" for progress cleaning of Project site.
  - 2. Section 01 7823 "Operation and Maintenance Data" for operation and maintenance manual requirements.
  - 3. Section 01 7839 "Project Record Documents" for submitting record Drawings, record Specifications, and record Product Data.
  - 4. Section 01 7900 "Demonstration and Training" for requirements for instructing Owner's personnel.

#### 1.2 ACTION SUBMITTALS

- A. Product Data: For cleaning agents.
- B. Contractor's List of Incomplete Items: Initial submittal at Substantial Completion.
- C. Certified List of Incomplete Items: Final submittal at Final Completion.

#### 1.3 CLOSEOUT SUBMITTALS

- A. Certificates of Release: From authorities having jurisdiction.
- B. Certificate of Insurance: For continuing coverage.
- C. Field Report: For pest control inspection.

1.4 MAINTENANCE MATERIAL SUBMITTALS

- A. Schedule of Maintenance Material Items: For maintenance material submittal items specified in other Sections.

1.5 SUBSTANTIAL COMPLETION PROCEDURES

- A. See University of Utah U Facilities; General Conditions; Article 9 Tests and Inspections, Substantial and Final Completion, Uncovering, Correction of Work and Guaranty Period; 9.3 Inspections: Substantial and Final; 9.3.1 Substantial Completion Inspection.
- B. Contractor's List of Incomplete Items: Prepare and submit a list of items to be completed and corrected (Contractor's punch list), indicating the value of each item on the list and reasons why the Work is incomplete.
- C. Submittals Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
  - 1. Certificates of Release: Obtain and submit releases from authorities having jurisdiction permitting Owner unrestricted use of the Work and access to services and utilities. Include occupancy permits, operating certificates, and similar releases.
  - 2. Submit closeout submittals specified in other Division 01 Sections, including project record documents, operation and maintenance manuals, final completion construction photographic documentation, damage or settlement surveys, property surveys, and similar final record information.
  - 3. Submit closeout submittals specified in individual Sections, including specific warranties, workmanship bonds, maintenance service agreements, final certifications, and similar documents.
  - 4. Submit maintenance material submittals specified in individual Sections, including tools, spare parts, extra materials, and similar items, and deliver to location designated by Architect. Label with manufacturer's name and model number where applicable.
    - a. Schedule of Maintenance Material Items: Prepare and submit schedule of maintenance material submittal items, including name and quantity of each item and name and number of related Specification Section. Obtain Architect's signature for receipt of submittals.
  - 5. Submit testing, adjusting, and balancing records.
  - 6. Submit changeover information related to Owner's occupancy, use, operation, and maintenance.
- D. Procedures Prior to Substantial Completion: Complete the following a minimum of 10 days prior to requesting inspection for determining date of Substantial Completion. List items below that are incomplete at time of request.
  - 1. Advise Owner of pending insurance changeover requirements.

2. Make final changeover of permanent locks and deliver keys to Owner. Advise Owner's personnel of changeover in security provisions.
3. Complete startup and testing of systems and equipment.
4. Perform preventive maintenance on equipment used prior to Substantial Completion.
5. Instruct Owner's personnel in operation, adjustment, and maintenance of products, equipment, and systems. Submit demonstration and training video recordings specified in Section 01 7900 "Demonstration and Training."
6. Advise Owner of changeover in heat and other utilities.
7. Participate with Owner in conducting inspection and walkthrough with local emergency responders.
8. Terminate and remove temporary facilities from Project site, along with mockups, construction tools, and similar elements.
9. Complete final cleaning requirements, including touchup painting.
10. Touch up and otherwise repair and restore marred exposed finishes to eliminate visual defects.

E. Inspection: Submit a written request for inspection to determine Substantial Completion a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare the Certificate of Substantial Completion after inspection or will notify Contractor of items, either on Contractor's list or additional items identified by Architect, that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.
2. Results of completed inspection will form the basis of requirements for final completion.

## 1.6 FINAL COMPLETION PROCEDURES

A. See University of Utah Facilities Management; General Conditions; Article 9 Tests and Inspections, Substantial and Final Completion, Uncovering, Correction of Work and Guaranty Period; 9.2 Inspections: Substantial and Final; 9.2.2 Final Completion Inspection.

B. Submittals Prior to Final Completion: Before requesting final inspection for determining final completion, complete the following:

1. Submit a final Application for Payment according to Section 01 2900 "Payment Procedures."
2. Certified List of Incomplete Items: Submit certified copy of Architect's Substantial Completion inspection list of items to be completed or corrected (punch list), endorsed and dated by Architect. Certified copy of the list shall state that each item has been completed or otherwise resolved for acceptance.
3. Certificate of Insurance: Submit evidence of final, continuing insurance coverage complying with insurance requirements.
4. Submit pest-control final inspection report.

C. Inspection: Submit a written request for final inspection to determine acceptance a minimum of 10 days prior to date the work will be completed and ready for final inspection and tests. On

receipt of request, Architect will either proceed with inspection or notify Contractor of unfulfilled requirements. Architect will prepare a final Certificate for Payment after inspection or will notify Contractor of construction that must be completed or corrected before certificate will be issued.

1. Reinspection: Request reinspection when the Work identified in previous inspections as incomplete is completed or corrected.

#### 1.7 LIST OF INCOMPLETE ITEMS (PUNCH LIST)

- A. Organization of List: Include name and identification of each space and area affected by construction operations for incomplete items and items needing correction including, if necessary, areas disturbed by Contractor that are outside the limits of construction.

1. Organize list of spaces in sequential order, starting with exterior areas first and proceeding from lowest floor to highest floor.
2. Organize items applying to each space by major element, including categories for ceiling, individual walls, floors, equipment, and building systems.
3. Include the following information at the top of each page:
  - a. Project name.
  - b. Date.
  - c. Name of Architect.
  - d. Name of Contractor.
  - e. Page number.
4. Submit list of incomplete items in the following format:
  - a. MS Excel electronic file. Architect will return annotated file.

#### 1.8 SUBMITTAL OF PROJECT WARRANTIES

- A. Time of Submittal: Submit written warranties on request of Architect for designated portions of the Work where commencement of warranties other than date of Substantial Completion is indicated, or when delay in submittal of warranties might limit Owner's rights under warranty.
- B. Organize warranty documents into an orderly sequence based on the table of contents of Project Manual.
  1. Bind warranties and bonds in heavy-duty, three-ring, vinyl-covered, loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-by-11-inch paper.
  2. Provide heavy paper dividers with plastic-covered tabs for each separate warranty. Mark tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product and the name, address, and telephone number of Installer.

3. Identify each binder on the front and spine with the typed or printed title "WARRANTIES," Project name, and name of Contractor.
  4. Warranty Electronic File: Scan warranties and bonds and assemble complete warranty and bond submittal package into a single indexed electronic PDF file with links enabling navigation to each item. Provide bookmarked table of contents at beginning of document.
- C. Provide additional copies of each warranty to include in operation and maintenance manuals.

## PART 2 - PRODUCTS

### 2.1 MATERIALS

- A. Cleaning Agents: Use cleaning materials and agents recommended by manufacturer or fabricator of the surface to be cleaned. Do not use cleaning agents that are potentially hazardous to health or property or that might damage finished surfaces.
1. Use cleaning products that comply with Green Seal's GS-37, or if GS-37 is not applicable, use products that comply with the California Code of Regulations maximum allowable VOC levels.

## PART 3 - EXECUTION

### 3.1 FINAL CLEANING

- A. General: Perform final cleaning. Conduct cleaning and waste-removal operations to comply with local laws and ordinances and Federal and local environmental and antipollution regulations.
- B. Cleaning: Employ experienced workers or professional cleaners for final cleaning. Clean each surface or unit to condition expected in an average commercial building cleaning and maintenance program. Comply with manufacturer's written instructions.
1. Complete the following cleaning operations before requesting inspection for certification of Substantial Completion for entire Project or for a designated portion of Project:
    - a. Clean Project site, yard, and grounds, in areas disturbed by construction activities, including landscape development areas, of rubbish, waste material, litter, and other foreign substances.
    - b. Sweep paved areas broom clean. Remove petrochemical spills, stains, and other foreign deposits.
    - c. Remove tools, construction equipment, machinery, and surplus material from Project site.
    - d. Clean exposed exterior and interior hard-surfaced finishes to a dirt-free condition, free of stains, films, and similar foreign substances. Avoid disturbing natural

weathering of exterior surfaces. Restore reflective surfaces to their original condition.

- e. Remove debris and surface dust from limited access spaces, including roofs, plenums, shafts, trenches, equipment vaults, manholes, attics, and similar spaces.
- f. Vacuum carpet and similar soft surfaces, removing debris and excess nap; clean according to manufacturer's recommendations if visible soil or stains remain.
- g. Clean transparent materials, including mirrors and glass in doors and windows. Remove glazing compounds and other noticeable, vision-obscuring materials. Polish mirrors and glass, taking care not to scratch surfaces.
- h. Remove labels that are not permanent.
- i. Wipe surfaces of mechanical and electrical equipment, elevator equipment, and similar equipment. Remove excess lubrication, paint and mortar droppings, and other foreign substances.
- j. Clean plumbing fixtures to a sanitary condition, free of stains, including stains resulting from water exposure.
- k. Replace disposable air filters and clean permanent air filters. Clean exposed surfaces of diffusers, registers, and grills.
- l. Clean ducts, blowers, and coils if units were operated without filters during construction or that display contamination with particulate matter on inspection.
  - 1) Clean HVAC system in compliance with NADCA Standard 1992-01. Provide written report on completion of cleaning.
- m. Clean light fixtures, lamps, globes, and reflectors to function with full efficiency.
- n. Leave Project clean and ready for occupancy.

- C. Construction Waste Disposal: Comply with waste disposal requirements in Section 01 7419 "Construction Waste Management and Disposal."

### 3.2 REPAIR OF THE WORK

- A. Complete repair and restoration operations before requesting inspection for determination of Substantial Completion.
- B. Repair or remove and replace defective construction. Repairing includes replacing defective parts, refinishing damaged surfaces, touching up with matching materials, and properly adjusting operating equipment. Where damaged or worn items cannot be repaired or restored, provide replacements. Remove and replace operating components that cannot be repaired. Restore damaged construction and permanent facilities used during construction to specified condition.
  - 1. Remove and replace chipped, scratched, and broken glass, reflective surfaces, and other damaged transparent materials.
  - 2. Touch up and otherwise repair and restore marred or exposed finishes and surfaces. Replace finishes and surfaces that already show evidence of repair or restoration.



- a. Do not paint over "UL" and other required labels and identification, including mechanical and electrical nameplates. Remove paint applied to required labels and identification.
3. Replace parts subject to operating conditions during construction that may impede operation or reduce longevity.
4. Replace burned-out bulbs, bulbs noticeably dimmed by hours of use, and defective and noisy starters in fluorescent and mercury vapor fixtures to comply with requirements for new fixtures.

END OF SECTION 01 7700

## SECTION 01 7823 - OPERATION AND MAINTENANCE DATA

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for preparing operation and maintenance manuals, including the following:
  - 1. Operation and maintenance documentation directory.
  - 2. Emergency manuals.
  - 3. Operation manuals for systems, subsystems, and equipment.
  - 4. Product maintenance manuals.
  - 5. Systems and equipment maintenance manuals.
- B. Related Requirements:
  - 1. Section 01 3300 "Submittal Procedures" for submitting copies of submittals for operation and maintenance manuals.
  - 2. Section 01 9113 "General Commissioning Requirements" for verification and compilation of data into operation and maintenance manuals.

#### 1.2 DEFINITIONS

- A. System: An organized collection of parts, equipment, or subsystems united by regular interaction.
- B. Subsystem: A portion of a system with characteristics similar to a system.

#### 1.3 CLOSEOUT SUBMITTALS

- A. Manual Content: Operations and maintenance manual content is specified in individual Specification Sections to be reviewed at the time of Section submittals. Submit reviewed manual content formatted and organized as required by this Section.
  - 1. Architect and Commissioning Authority will comment on whether content of operations and maintenance submittals are acceptable.
  - 2. Where applicable, clarify and update reviewed manual content to correspond to revisions and field conditions.
- B. Format: Submit operations and maintenance manuals in the following format:
  - 1. PDF electronic file. Assemble each manual into a composite electronically indexed file. Submit on digital media acceptable to Architect.

- a. Name each indexed document file in composite electronic index with applicable item name. Include a complete electronically linked operation and maintenance directory.
    - b. Enable inserted reviewer comments on draft submittals.
  2. One paper copy. Include a complete operation and maintenance directory. Enclose title pages and directories in clear plastic sleeves.
- C. Manual Submittal: Submit each manual in final form prior to requesting inspection for Substantial Completion and at least 15 days before commencing demonstration and training. Architect and Commissioning Authority will return copy with comments.
1. Correct or revise each manual to comply with Architect's and Commissioning Authority's comments. Submit copies of each corrected manual within 15 days of receipt of Architect's and Commissioning Authority's comments and prior to commencing demonstration and training.

## PART 2 - PRODUCTS

### 2.1 OPERATION AND MAINTENANCE DOCUMENTATION DIRECTORY

- A. Directory: Prepare a single, comprehensive directory of emergency, operation, and maintenance data and materials, listing items and their location to facilitate ready access to desired information. Include a section in the directory for each of the following:
1. List of documents.
  2. List of systems.
  3. List of equipment.
  4. Table of contents.
- B. List of Systems and Subsystems: List systems alphabetically. Include references to operation and maintenance manuals that contain information about each system.
- C. List of Equipment: List equipment for each system, organized alphabetically by system. For pieces of equipment not part of system, list alphabetically in separate list.
- D. Tables of Contents: Include a table of contents for each emergency, operation, and maintenance manual.
- E. Identification: In the documentation directory and in each operation and maintenance manual, identify each system, subsystem, and piece of equipment with same designation used in the Contract Documents. If no designation exists, assign a designation according to ASHRAE Guideline 4, "Preparation of Operating and Maintenance Documentation for Building Systems."

## 2.2 REQUIREMENTS FOR EMERGENCY, OPERATION, AND MAINTENANCE MANUALS

- A. Organization: Unless otherwise indicated, organize each manual into a separate section for each system and subsystem, and a separate section for each piece of equipment not part of a system. Each manual shall contain the following materials, in the order listed:
  - 1. Title page.
  - 2. Table of contents.
  - 3. Manual contents.
- B. Title Page: Include the following information:
  - 1. Subject matter included in manual.
  - 2. Name and address of Project.
  - 3. Name and address of Owner.
  - 4. Date of submittal.
  - 5. Name and contact information for Contractor.
  - 6. Name and contact information for Architect.
  - 7. Name and contact information for Commissioning Authority.
  - 8. Names and contact information for major consultants to the Architect that designed the systems contained in the manuals.
  - 9. Cross-reference to related systems in other operation and maintenance manuals.
- C. Table of Contents: List each product included in manual, identified by product name, indexed to the content of the volume, and cross-referenced to Specification Section number in Project Manual.
  - 1. If operation or maintenance documentation requires more than one volume to accommodate data, include comprehensive table of contents for all volumes in each volume of the set.
- D. Manual Contents: Organize into sets of manageable size. Arrange contents alphabetically by system, subsystem, and equipment. If possible, assemble instructions for subsystems, equipment, and components of one system into a single binder.
- E. Manuals, Electronic Files: Submit manuals in the form of a multiple file composite electronic PDF file for each manual type required.
  - 1. Electronic Files: Use electronic files prepared by manufacturer where available. Where scanning of paper documents is required, configure scanned file for minimum readable file size.
  - 2. File Names and Bookmarks: Enable bookmarking of individual documents based on file names. Name document files to correspond to system, subsystem, and equipment names used in manual directory and table of contents. Group documents for each system and subsystem into individual composite bookmarked files, then create composite manual, so that resulting bookmarks reflect the system, subsystem, and equipment names in a readily navigated file tree. Configure electronic manual to display bookmark panel on opening file.

F. Manuals, Paper Copy: Submit manuals in the form of hard copy, bound and labeled volumes.

1. Binders: Heavy-duty, three-ring, vinyl-covered, loose-leaf binders, in thickness necessary to accommodate contents, sized to hold 8-1/2-by-11-inch paper; with clear plastic sleeve on spine to hold label describing contents and with pockets inside covers to hold folded oversize sheets.
  - a. If two or more binders are necessary to accommodate data of a system, organize data in each binder into groupings by subsystem and related components. Cross-reference other binders if necessary to provide essential information for proper operation or maintenance of equipment or system.
  - b. Identify each binder on front and spine, with printed title "OPERATION AND MAINTENANCE MANUAL," Project title or name, and subject matter of contents, and indicate Specification Section number on bottom of spine. Indicate volume number for multiple-volume sets.
2. Dividers: Heavy-paper dividers with plastic-covered tabs for each section of the manual. Mark each tab to indicate contents. Include typed list of products and major components of equipment included in the section on each divider, cross-referenced to Specification Section number and title of Project Manual.
3. Protective Plastic Sleeves: Transparent plastic sleeves designed to enclose diagnostic software storage media for computerized electronic equipment.
4. Supplementary Text: Prepared on 8-1/2-by-11-inch white bond paper.
5. Drawings: Attach reinforced, punched binder tabs on drawings and bind with text.
  - a. If oversize drawings are necessary, fold drawings to same size as text pages and use as foldouts.
  - b. If drawings are too large to be used as foldouts, fold and place drawings in labeled envelopes and bind envelopes in rear of manual. At appropriate locations in manual, insert typewritten pages indicating drawing titles, descriptions of contents, and drawing locations.

## 2.3 EMERGENCY MANUALS

A. Content: Organize manual into a separate section for each of the following:

1. Type of emergency.
2. Emergency instructions.
3. Emergency procedures.

B. Type of Emergency: Where applicable for each type of emergency indicated below, include instructions and procedures for each system, subsystem, piece of equipment, and component:

1. Fire.
2. Flood.
3. Gas leak.
4. Water leak.
5. Power failure.

6. Water outage.
  7. System, subsystem, or equipment failure.
  8. Chemical release or spill.
- C. Emergency Instructions: Describe and explain warnings, trouble indications, error messages, and similar codes and signals. Include responsibilities of Owner's operating personnel for notification of Installer, supplier, and manufacturer to maintain warranties.
- D. Emergency Procedures: Include the following, as applicable:
1. Instructions on stopping.
  2. Shutdown instructions for each type of emergency.
  3. Operating instructions for conditions outside normal operating limits.
  4. Required sequences for electric or electronic systems.
  5. Special operating instructions and procedures.

## 2.4 OPERATION MANUALS

- A. Content: In addition to requirements in this Section, include operation data required in individual Specification Sections and the following information:
1. System, subsystem, and equipment descriptions. Use designations for systems and equipment indicated on Contract Documents.
  2. Performance and design criteria if Contractor has delegated design responsibility.
  3. Operating standards.
  4. Operating procedures.
  5. Operating logs.
  6. Wiring diagrams.
  7. Control diagrams.
  8. Piped system diagrams.
  9. Precautions against improper use.
  10. License requirements including inspection and renewal dates.
- B. Descriptions: Include the following:
1. Product name and model number. Use designations for products indicated on Contract Documents.
  2. Manufacturer's name.
  3. Equipment identification with serial number of each component.
  4. Equipment function.
  5. Operating characteristics.
  6. Limiting conditions.
  7. Performance curves.
  8. Engineering data and tests.
  9. Complete nomenclature and number of replacement parts.
- C. Operating Procedures: Include the following, as applicable:

1. Startup procedures.
  2. Equipment or system break-in procedures.
  3. Routine and normal operating instructions.
  4. Regulation and control procedures.
  5. Instructions on stopping.
  6. Normal shutdown instructions.
  7. Seasonal and weekend operating instructions.
  8. Required sequences for electric or electronic systems.
  9. Special operating instructions and procedures.
- D. Systems and Equipment Controls: Describe the sequence of operation, and diagram controls as installed.
- E. Piped Systems: Diagram piping as installed and identify color-coding where required for identification.

## 2.5 PRODUCT MAINTENANCE MANUALS

- A. Content: Organize manual into a separate section for each product, material, and finish. Include source information, product information, maintenance procedures, repair materials and sources, and warranties and bonds, as described below.
- B. Source Information: List each product included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- C. Product Information: Include the following, as applicable:
1. Product name and model number.
  2. Manufacturer's name.
  3. Color, pattern, and texture.
  4. Material and chemical composition.
  5. Reordering information for specially manufactured products.
- D. Maintenance Procedures: Include manufacturer's written recommendations and the following:
1. Inspection procedures.
  2. Types of cleaning agents to be used and methods of cleaning.
  3. List of cleaning agents and methods of cleaning detrimental to product.
  4. Schedule for routine cleaning and maintenance.
  5. Repair instructions.
- E. Repair Materials and Sources: Include lists of materials and local sources of materials and related services.

- F. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
  - 1. Include procedures to follow and required notifications for warranty claims.

## 2.6 SYSTEMS AND EQUIPMENT MAINTENANCE MANUALS

- A. Content: For each system, subsystem, and piece of equipment not part of a system, include source information, manufacturers' maintenance documentation, maintenance procedures, maintenance and service schedules, spare parts list and source information, maintenance service contracts, and warranty and bond information, as described below.
- B. Source Information: List each system, subsystem, and piece of equipment included in manual, identified by product name and arranged to match manual's table of contents. For each product, list name, address, and telephone number of Installer or supplier and maintenance service agent, and cross-reference Specification Section number and title in Project Manual and drawing or schedule designation or identifier where applicable.
- C. Manufacturers' Maintenance Documentation: Manufacturers' maintenance documentation including the following information for each component part or piece of equipment:
  - 1. Standard maintenance instructions and bulletins.
  - 2. Drawings, diagrams, and instructions required for maintenance, including disassembly and component removal, replacement, and assembly.
  - 3. Identification and nomenclature of parts and components.
  - 4. List of items recommended to be stocked as spare parts.
- D. Maintenance Procedures: Include the following information and items that detail essential maintenance procedures:
  - 1. Test and inspection instructions.
  - 2. Troubleshooting guide.
  - 3. Precautions against improper maintenance.
  - 4. Disassembly; component removal, repair, and replacement; and reassembly instructions.
  - 5. Aligning, adjusting, and checking instructions.
  - 6. Demonstration and training video recording, if available.
- E. Maintenance and Service Schedules: Include service and lubrication requirements, list of required lubricants for equipment, and separate schedules for preventive and routine maintenance and service with standard time allotment.
  - 1. Scheduled Maintenance and Service: Tabulate actions for daily, weekly, monthly, quarterly, semiannual, and annual frequencies.
  - 2. Maintenance and Service Record: Include manufacturers' forms for recording maintenance.



- F. Spare Parts List and Source Information: Include lists of replacement and repair parts, with parts identified and cross-referenced to manufacturers' maintenance documentation and local sources of maintenance materials and related services.
- G. Maintenance Service Contracts: Include copies of maintenance agreements with name and telephone number of service agent.
- H. Warranties and Bonds: Include copies of warranties and bonds and lists of circumstances and conditions that would affect validity of warranties or bonds.
  - 1. Include procedures to follow and required notifications for warranty claims.

### PART 3 - EXECUTION

#### 3.1 MANUAL PREPARATION

- A. Emergency Manual: Assemble a complete set of emergency information indicating procedures for use by emergency personnel and by Owner's operating personnel for types of emergencies indicated.
- B. Product Maintenance Manual: Assemble a complete set of maintenance data indicating care and maintenance of each product, material, and finish incorporated into the Work.
- C. Operation and Maintenance Manuals: Assemble a complete set of operation and maintenance data indicating operation and maintenance of each system, subsystem, and piece of equipment not part of a system.
  - 1. Engage a factory-authorized service representative to assemble and prepare information for each system, subsystem, and piece of equipment not part of a system.
  - 2. Prepare a separate manual for each system and subsystem, in the form of an instructional manual for use by Owner's operating personnel.
- D. Manufacturers' Data: Where manuals contain manufacturers' standard printed data, include only sheets pertinent to product or component installed. Mark each sheet to identify each product or component incorporated into the Work. If data include more than one item in a tabular format, identify each item using appropriate references from the Contract Documents. Identify data applicable to the Work and delete references to information not applicable.
  - 1. Prepare supplementary text if manufacturers' standard printed data are not available and where the information is necessary for proper operation and maintenance of equipment or systems.
- E. Drawings: Prepare drawings supplementing manufacturers' printed data to illustrate the relationship of component parts of equipment and systems and to illustrate control sequence and flow diagrams. Coordinate these drawings with information contained in record Drawings to ensure correct illustration of completed installation.

1. Do not use original project record documents as part of operation and maintenance manuals.
  2. Comply with requirements of newly prepared record Drawings in Section 01 7839 "Project Record Documents."
- F. Comply with Section 01 7700 "Closeout Procedures" for schedule for submitting operation and maintenance documentation.

END OF SECTION 01 7823

## SECTION 01 7839 - PROJECT RECORD DOCUMENTS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for project record documents, including the following:
  - 1. Record Drawings.
  - 2. Record Specifications.
  - 3. Record Product Data.
  - 4. Miscellaneous record submittals.
- B. Related Requirements:
  - 1. Section 01 7700 "Closeout Procedures" for general closeout procedures.
  - 2. Section 01 7823 "Operation and Maintenance Data" for operation and maintenance manual requirements.

#### 1.2 CLOSEOUT SUBMITTALS

- A. Record Drawings: Comply with the following:
  - 1. Number of Copies: Submit one set of marked-up record prints.
  - 2. Number of Copies: Submit copies of record Drawings as follows:
    - a. Submittal:
      - 1) Submit one paper-copy set of marked-up record prints.
      - 2) Submit record digital data files and three sets of record digital data file plots.
      - 3) Plot each drawing file, whether or not changes and additional information were recorded.
- B. Record Specifications: Submit annotated PDF electronic files of Project's Specifications, including addenda and contract modifications.
- C. Record Product Data: Submit annotated PDF electronic files and directories of each submittal.
  - 1. Where record Product Data are required as part of operation and maintenance manuals, submit duplicate marked-up Product Data as a component of manual.
- D. Miscellaneous Record Submittals: See other Specification Sections for miscellaneous record-keeping requirements and submittals in connection with various construction activities. Submit annotated PDF electronic files and directories of each submittal.

## PART 2 - PRODUCTS

### 2.1 RECORD DRAWINGS

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.7 Documents and Samples at the Site, Certifying "As-Built".
- B. Record Prints: Maintain one set of marked-up paper copies of the Contract Drawings and Shop Drawings, incorporating new and revised drawings as modifications are issued.
  - 1. Preparation: Mark record prints to show the actual installation where installation varies from that shown originally. Require individual or entity who obtained record data, whether individual or entity is Installer, subcontractor, or similar entity, to provide information for preparation of corresponding marked-up record prints.
    - a. Give particular attention to information on concealed elements that would be difficult to identify or measure and record later.
    - b. Accurately record information in an acceptable drawing technique.
    - c. Record data as soon as possible after obtaining it.
    - d. Record and check the markup before enclosing concealed installations.
  - 2. Content: Types of items requiring marking include, but are not limited to, the following:
    - a. Dimensional changes to Drawings.
    - b. Revisions to details shown on Drawings.
    - c. Depths of foundations below first floor.
    - d. Locations and depths of underground utilities.
    - e. Revisions to routing of piping and conduits.
    - f. Revisions to electrical circuitry.
    - g. Actual equipment locations.
    - h. Duct size and routing.
    - i. Locations of concealed internal utilities.
    - j. Changes made by Change Order or Construction Change Directive.
    - k. Changes made following Architect's written orders.
    - l. Details not on the original Contract Drawings.
    - m. Field records for variable and concealed conditions.
    - n. Record information on the Work that is shown only schematically.
  - 3. Mark the Contract Drawings and Shop Drawings completely and accurately. Use personnel proficient at recording graphic information in production of marked-up record prints.
  - 4. Mark record sets with erasable, red-colored pencil. Use other colors to distinguish between changes for different categories of the Work at same location.
  - 5. Mark important additional information that was either shown schematically or omitted from original Drawings.
  - 6. Note Construction Change Directive numbers, alternate numbers, Change Order numbers, and similar identification, where applicable.

- C. Record Digital Data Files: Immediately before inspection for Certificate of Substantial Completion, review marked-up record prints with Architect. When authorized, prepare a full set of corrected digital data files of the Contract Drawings, as follows:
  - 1. Format: Annotated PDF electronic file with comment function enabled.
  - 2. Incorporate changes and additional information previously marked on record prints. Delete, redraw, and add details and notations where applicable.
  - 3. Refer instances of uncertainty to Architect for resolution.
  - 4. Architect will furnish Contractor one set of digital data files of the Contract Drawings for use in recording information.
    - a. See Section 01 3300 "Submittal Procedures" for requirements related to use of Architect's digital data files.
- D. Format: Identify and date each record Drawing; include the designation "PROJECT RECORD DRAWING" in a prominent location.
  - 1. Format: Annotated PDF electronic file with comment function enabled.
  - 2. Record Digital Data Files: Organize digital data information into separate electronic files that correspond to each sheet of the Contract Drawings. Name each file with the sheet identification. Include identification in each digital data file.
  - 3. Identification: As follows:
    - a. Project name.
    - b. Date.
    - c. Designation "PROJECT RECORD DRAWINGS."
    - d. Name of Architect.
    - e. Name of Contractor.

## 2.2 RECORD SPECIFICATIONS

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.7 Documents and Samples at the Site, Certifying "As-Built".
- B. Preparation: Mark Specifications to indicate the actual product installation where installation varies from that indicated in Specifications, addenda, and contract modifications.
  - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
  - 2. Mark copy with the proprietary name and model number of products, materials, and equipment furnished, including substitutions and product options selected.
  - 3. Record the name of manufacturer, supplier, Installer, and other information necessary to provide a record of selections made.
  - 4. Note related Change Orders, record Product Data, and record Drawings where applicable.
- C. Format: Submit record Specifications as annotated PDF electronic file or scanned PDF electronic file(s) of marked-up paper copy of Specifications.

## 2.3 RECORD PRODUCT DATA

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.7 Documents and Samples at the Site, Certifying “As-Built”.
- B. Preparation: Mark Product Data to indicate the actual product installation where installation varies substantially from that indicated in Product Data submittal.
  - 1. Give particular attention to information on concealed products and installations that cannot be readily identified and recorded later.
  - 2. Include significant changes in the product delivered to Project site and changes in manufacturer's written instructions for installation.
  - 3. Note related Change Orders, record Specifications, and record Drawings where applicable.
- C. Format: Submit record Product Data as annotated PDF electronic file or scanned PDF electronic file(s) of marked-up paper copy of Product Data.

## 2.4 MISCELLANEOUS RECORD SUBMITTALS

- A. Assemble miscellaneous records required by other Specification Sections for miscellaneous record keeping and submittal in connection with actual performance of the Work. Bind or file miscellaneous records and identify each, ready for continued use and reference.
- B. Format: Submit miscellaneous record submittals as PDF electronic file or scanned PDF electronic file(s) of marked-up miscellaneous record submittals.

# PART 3 - EXECUTION

## 3.1 RECORDING AND MAINTENANCE

- A. See University of Utah U Facilities; General Conditions; Article 4 Contractor; 4.7 Documents and Samples at the Site, Certifying “As-Built”.
- B. Recording: Maintain one copy of each submittal during the construction period for project record document purposes. Post changes and revisions to project record documents as they occur; do not wait until end of Project.
- C. Maintenance of Record Documents and Samples: Store record documents and Samples in the field office apart from the Contract Documents used for construction. Do not use project record documents for construction purposes. Maintain record documents in good order and in a clean, dry, legible condition, protected from deterioration and loss. Provide access to project record documents for Architect's reference during normal working hours.

END OF SECTION 01 7839

## SECTION 01 7900 - DEMONSTRATION AND TRAINING

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. Section includes administrative and procedural requirements for instructing Owner's personnel, including the following:
  - 1. Demonstration of operation of systems, subsystems, and equipment.
  - 2. Training in operation and maintenance of systems, subsystems, and equipment.
  - 3. Demonstration and training video recordings.

#### 1.2 INFORMATIONAL SUBMITTALS

- A. Instruction Program: Submit outline of instructional program for demonstration and training, including a list of training modules and a schedule of proposed dates, times, length of instruction time, and instructors' names for each training module. Include learning objective and outline for each training module.
  - 1. Indicate proposed training modules using manufacturer-produced demonstration and training video recordings for systems, equipment, and products in lieu of video recording of live instructional module.
- B. Attendance Record: For each training module, submit list of participants and length of instruction time.
- C. Evaluations: For each participant and for each training module, submit results and documentation of performance-based test.

#### 1.3 CLOSEOUT SUBMITTALS

- A. Demonstration and Training Video Recordings: Submit two copies within seven days of end of each training module.
  - 1. Identification: On each copy, provide an applied label with the following information:
    - a. Name of Project.
    - b. Name and address of videographer.
    - c. Name of Architect.
    - d. Name of Contractor.
    - e. Date of video recording.

2. Transcript: Prepared in PDF electronic format. Include a cover sheet with same label information as the corresponding video recording and a table of contents with links to corresponding training components. Include name of Project and date of video recording on each page.
3. At completion of training, submit complete training manual for Owner's use in PDF electronic file format on compact disc.

#### 1.4 QUALITY ASSURANCE

- A. Instructor Qualifications: A factory-authorized service representative, complying with requirements in Section 01 4000 "Quality Requirements," experienced in operation and maintenance procedures and training.
- B. Videographer Qualifications: A professional videographer who is experienced photographing demonstration and training events similar to those required.
- C. Preinstruction Conference: Conduct conference at Project site to comply with requirements in Section 01 3100 "Project Management and Coordination." Review methods and procedures related to demonstration and training including, but not limited to, the following:
  1. Inspect and discuss locations and other facilities required for instruction.
  2. Review and finalize instruction schedule and verify availability of educational materials, instructors' personnel, audiovisual equipment, and facilities needed to avoid delays.
  3. Review required content of instruction.
  4. For instruction that must occur outside, review weather and forecasted weather conditions and procedures to follow if conditions are unfavorable.

#### 1.5 COORDINATION

- A. Coordinate instruction schedule with Owner's operations. Adjust schedule as required to minimize disrupting Owner's operations and to ensure availability of Owner's personnel.
- B. Coordinate content of training modules with content of approved emergency, operation, and maintenance manuals. Do not submit instruction program until operation and maintenance data has been reviewed and approved by Architect.

### PART 2 - PRODUCTS

#### 2.1 INSTRUCTION PROGRAM

- A. Program Structure: Develop an instruction program that includes individual training modules for each system and for equipment not part of a system, as required by individual Specification Sections.



- B. Training Modules: Develop a learning objective and teaching outline for each module. Include a description of specific skills and knowledge that participant is expected to master. For each module, include instruction for the following as applicable to the system, equipment, or component:
1. Basis of System Design, Operational Requirements, and Criteria: Include the following:
    - a. System, subsystem, and equipment descriptions.
    - b. Performance and design criteria if Contractor is delegated design responsibility.
    - c. Operating standards.
    - d. Regulatory requirements.
    - e. Equipment function.
    - f. Operating characteristics.
    - g. Limiting conditions.
    - h. Performance curves.
  2. Documentation: Review the following items in detail:
    - a. Emergency manuals.
    - b. Operations manuals.
    - c. Maintenance manuals.
    - d. Project record documents.
    - e. Identification systems.
    - f. Warranties and bonds.
    - g. Maintenance service agreements and similar continuing commitments.
  3. Emergencies: Include the following, as applicable:
    - a. Instructions on meaning of warnings, trouble indications, and error messages.
    - b. Instructions on stopping.
    - c. Shutdown instructions for each type of emergency.
    - d. Operating instructions for conditions outside of normal operating limits.
    - e. Sequences for electric or electronic systems.
    - f. Special operating instructions and procedures.
  4. Operations: Include the following, as applicable:
    - a. Startup procedures.
    - b. Equipment or system break-in procedures.
    - c. Routine and normal operating instructions.
    - d. Regulation and control procedures.
    - e. Control sequences.
    - f. Safety procedures.
    - g. Instructions on stopping.
    - h. Normal shutdown instructions.
    - i. Operating procedures for emergencies.
    - j. Operating procedures for system, subsystem, or equipment failure.
    - k. Seasonal and weekend operating instructions.
    - l. Required sequences for electric or electronic systems.

- m. Special operating instructions and procedures.
- 5. Adjustments: Include the following:
  - a. Alignments.
  - b. Checking adjustments.
  - c. Noise and vibration adjustments.
  - d. Economy and efficiency adjustments.
- 6. Troubleshooting: Include the following:
  - a. Diagnostic instructions.
  - b. Test and inspection procedures.
- 7. Maintenance: Include the following:
  - a. Inspection procedures.
  - b. Types of cleaning agents to be used and methods of cleaning.
  - c. List of cleaning agents and methods of cleaning detrimental to product.
  - d. Procedures for routine cleaning
  - e. Procedures for preventive maintenance.
  - f. Procedures for routine maintenance.
  - g. Instruction on use of special tools.
- 8. Repairs: Include the following:
  - a. Diagnosis instructions.
  - b. Repair instructions.
  - c. Disassembly; component removal, repair, and replacement; and reassembly instructions.
  - d. Instructions for identifying parts and components.
  - e. Review of spare parts needed for operation and maintenance.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Assemble educational materials necessary for instruction, including documentation and training module. Assemble training modules into a training manual organized in coordination with requirements in Section 01 7823 "Operation and Maintenance Data."
- B. Set up instructional equipment at instruction location.

### 3.2 INSTRUCTION

- A. Engage qualified instructors to instruct Owner's personnel to adjust, operate, and maintain systems, subsystems, and equipment not part of a system.
  - 1. Owner will furnish an instructor to describe Owner's operational philosophy.
  - 2. Owner will furnish Contractor with names and positions of participants.
- B. Scheduling: Provide instruction at mutually agreed on times. For equipment that requires seasonal operation, provide similar instruction at start of each season.
  - 1. Schedule training with Owner, with at least seven days' advance notice.
- C. Training Location and Reference Material: Conduct training on-site in the completed and fully operational facility using the actual equipment in-place. Conduct training using final operation and maintenance data submittals.
- D. Evaluation: At conclusion of each training module, assess and document each participant's mastery of module by use of an oral performance-based test.
- E. Cleanup: Collect used and leftover educational materials and give to Owner. Remove instructional equipment. Restore systems and equipment to condition existing before initial training use.

### 3.3 DEMONSTRATION AND TRAINING VIDEO RECORDINGS

- A. General: Engage a qualified commercial videographer to record demonstration and training video recordings. Record each training module separately. Include classroom instructions and demonstrations, board diagrams, and other visual aids, but not student practice.
  - 1. At beginning of each training module, record each chart containing learning objective and lesson outline.
- B. Video: Provide minimum 640 x 480 video resolution converted to format file type acceptable to Architect, on electronic media.
  - 1. Electronic Media: Read-only format compact disc acceptable to Owner, with commercial-grade graphic label.
  - 2. File Hierarchy: Organize folder structure and file locations according to project manual table of contents. Provide complete screen-based menu.
  - 3. File Names: Utilize file names based upon name of equipment generally described in video segment, as identified in Project specifications.
  - 4. Contractor and Installer Contact File: Using appropriate software, create a file for inclusion on the Equipment Demonstration and Training DVD that describes the following for each Contractor involved on the Project, arranged according to Project table of contents:

- a. Name of Contractor/Installer.
  - b. Business address.
  - c. Business phone number.
  - d. Point of contact.
  - e. E-mail address.
- C. Narration: Describe scenes on video recording by audio narration by microphone while video recording is recorded. Include description of items being viewed.
- D. Transcript: Provide a transcript of the narration. Display images and running time captured from videotape opposite the corresponding narration segment.
- E. Preproduced Video Recordings: Provide video recordings used as a component of training modules in same format as recordings of live training.

END OF SECTION 01 7900

## SECTION 01 9113 – GENERAL COMMISSIONING REQUIREMENTS

### PART 1 - GENERAL REQUIREMENTS

#### 1.1 RELATED WORK

- A All other sections in Division 21, 22, and 23.
- B Specification Section 220800 – “General Commissioning Requirements”
- C Specification Section 260800 – “Electrical Systems Commissioning
- D Specification Section 230800 – “Mechanical Systems Commissioning”

#### 1.2 RELATED DOCUMENTS

- A Owners Project Requirements (OPR)
- B Basis of Design (BOD)
- C U of U Design Standards

#### 1.3 COMMISSIONING AGENT OF RECORD

- A The Commissioning Agent contracted directly with the Division of Facilities and Construction Management will be Utah New Vision Construction LLC. The contractors or any of their subcontractors are not responsible to hire the commissioning agent for this project.

#### 1.4 DESCRIPTION

- A. The purpose of the commissioning process is to provide the Owner/operator of the facility with a high level of assurance that the mechanical and associated electrical Systems have been installed in the prescribed manner, and operate within the performance guidelines set in the design intent. The Commissioning Authority shall provide the Owner with an unbiased, objective view of the systems installation, operation, and performance. This process is not to take away or reduce the responsibility of the design professionals or installing contractors to provide a finished product. Commissioning is intended to enhance the quality of system start-up and aid in the orderly transfer of systems to beneficial use by the owner. The Commissioning Authority will be a member of the construction team, cooperating and coordinating all commissioning activities with the design professionals, construction manager, contractors, subcontractors, manufacturers and equipment suppliers.

#### 1.5 SCOPE

- A The General systems commissioning shall include a demonstration by the Contractor with the assistance of the Commissioning Authority (CxA) of each piece of equipment to comply with the Owners Project Requirements (OPR) and the Construction Documents (CD). The commissioning process shall demonstrate that each piece of equipment is performing and operating to the OPR and CDs.

B Participants in General Systems Commissioning: Commissioning systems shall be conducted with representatives from the following entities (the required participants shall be confirmed with the commissioning agent prior to scheduling the commissioning).

1. General Contractor
2. Mechanical Contractor
3. General Contractor
4. BMS or ATC Contractor
5. Factory Authorized Service Personnel for all major pieces of equipment. This is not a sales representative but an authorized technician certified to work on the piece of equipment.
6. Water Treatment Contractor
7. The Electrical Contractor
8. Test and Balance Contractor
9. Owner's Representative
10. Electrical Engineer
11. Mechanical Engineer
12. Architectural Team

C Kickoff, Coordination and MEP Meetings

1. Weekly meetings shall be held by the CxA with full participation and attendance of all participants as indicated in the "Participants in General Systems Commissioning" section.
2. These meetings will be held at the CxA convenience and shall be scheduled on a regular basis.
3. Other meetings such as the Commissioning Kick-Off Meeting, Update Meetings, Controls Meeting, Submittal Meetings and other Coordination Meetings shall be attended by those participants as indicated in the "Participants in General Systems Commissioning"

D Submittal Reviews and Meetings

1. The CxA shall review each submittal in Division 22, 23, 26. The contractor shall look and ask for the CxA comments if the comments are not in the return submittal. It is the sole responsibility of the contractor to search out and ask for the CxA comments.
2. For major pieces of equipment the contractor, subcontractors, and suppliers shall be in attendance for a submittal review meeting with the Owner and CxA to review the submittal with the Owner and CxA and address any deficiencies. These major pieces of equipment are defined in the other commissioning specifications
3. Submittal reviews are NOT an approval but a courtesy review to help validate products submitted are in general compliance with the construction documents. It is the suppliers and contractors responsibility to verify the supplied product meets or exceeds the construction documents requirements or the supplier is to provide a separate letter noting each of the requirements that has not been achieved and MUST identify they are not in compliance with the construction documents and request a PR. Failure to do so may require modification or replacement of the product when onsite or installed

E Issues Log

1. An issues log shall be kept by the CxA. These issues will identify issues, defects, improper installations, and deficiencies of the installation and design. The issues log will have the issue, a potential resolution, the subcontractor responsible, the date of the issue found and the CxA who found the issue.
2. The issues log shall be immediately addressed every week by the contractor. If an issue lags beyond four (4) weeks the CxA shall request from the Owner and reduction in payment for services by the contractor.
3. When an item is completed and addressed by the contractor or subcontractor responsible, the party responsible shall sign off and deliver to the CxA for review. The sign off shall include how the contractor addressed the issue and the date in which the contractor addressed the issue. If the issue has not been addressed after re-inspection the contractor shall be liable for the CxA time and efforts as outlined later in this specification.

F Construction Checklists, Pre and Final Functional Testing Checklists, and Startup Checklists

1. The CxA shall develop construction checklists that will be executed by the CxA. The contractors and subcontractors shall review the checklists for compliance with the ability of their individual systems. If the contractor or subcontractors do not provide comments to the CxA then the CxA shall assume their procedures shall not harm nor deteriorate the individual systems. If a problem occurs during testing that causes a piece of equipment or system to malfunction, damage, or any other failure and the contractor or subcontractor has not in writing opposed such test then the contractor or subcontractor shall be liable for any damages and delays.
2. The contractor shall fill out checklists called Contractor Readiness Checklists. These shall be delivered in the commissioning plan and shall be used to show the CxA that the contractor is ready for Final Function Testing.
3. Startup Sheets shall be delivered to the CxA. The contractor responsible for the piece of equipment is also responsible for delivering those startup sheets to the CxA.
4. Functional Testing shall be attended by the members as defined in "Participants in General Systems Commissioning."
5. Should any of the aforementioned requirements not be met on the date that the commissioning process commences and or if deficiencies are observed during the commissioning process the commissioning will be considered a failure and the deficiencies will be required to be remedied and then addressed in writing prior to requesting a date for re-commissioning. There will be no additional costs allowed to the Contractor for re-commissioning sessions as may be required to address issues that are found to be in non-compliance with the requirements of this specification. The contractor shall be responsible for the CxA additional time due to absence of the member as outlined later in this specification.

G Current Facility Requirements and Operations and Maintenance Document

1. The contractors and subcontractors shall prepare a documents that contains the following pieces of information. This document shall include the following:

- a. A sequence of operations for the building
  - b. The building occupancy schedule
  - c. Equipment run-time schedules
  - d. Setpoints for all general equipment
  - e. Set lighting levels throughout the building
  - f. Minimum outside air requirements
  - g. Any changes in schedules or setpoints for different seasons, days of the week, and times of day
  - h. A systems narrative describing the mechanical systems and equipment
  - i. A preventive maintenance plan for building equipment described in the systems narrative
2. The document shall be delivered to the CxA by the contractor in a Microsoft Word (.doc or .docx) format

#### H Systems Manual

1. The contractors and subcontractors shall prepare a documents that contains the following pieces of information. This document shall include the following:
  - a. Construction record documents and specifications
  - b. Approved submittals
  - c. As-built drawings
  - d. As-built sequence of operation
  - e. Original setpoints for all systems commissioned
  - f. Recommended schedule for sensor recalibration
  - g. Equipment operations and maintenance manuals
  - h. Equipment preventive maintenance schedules
  - i. Confirmation of completed training for the owner and occupants

#### 1.6 SYSTEMS TO BE COMMISSIONED

- A. This list is not intended to be exhaustive. All Division 22, 23, 26 and 27 and any equipment, piping, balancing, controls, etc. that are defined in the entire cumulative sections of Division 22, 23, and 26 will go through commissioning. The list below is a representative sample of items that are typically commissioned.
  1. All electrical systems, including emergency and normal and fire alarm.
  2. All mechanical systems
  3. All plumbing systems
  4. All specialty electrical systems including nurse call, interface with bed panels and lighting controls.

#### 1.7 COORDINATION

- A The Commissioning Authority shall receive a copy of all construction documents, addenda, change orders, and appropriate approved submittals and shop drawings directly from the Contractor.



- B The Commissioning Authority shall disseminate written information and documents to all responsible parties relative to the nature and extent of the communication.
- C The Commissioning Authority is primarily responsible to the Owner, and as such, shall regularly appraise the architect, the contractor, and the Owner of progress, pending problems and/or disputes, and shall provide regular status reports on progress with each system. Any potential change in the contractual and/or financial obligations of the owner (credits, change orders, schedule changes, etc.) shall be identified and quantified as soon as possible.
- D The Commissioning Authority shall coordinate the schedule of commissioning activities with the construction schedule. It is possible that some procedures will be completed before the entire mechanical system is completed.

## 1.8 SCHEDULE

- A Final Commissioning shall not commence on the individual pieces of equipment, Test and Balance, Controls, and other mechanical systems until the Contractor Readiness Forms are delivered to the CxA.
- B Pre-Functional Commissioning shall commence during the progress of the project. Contractor Readiness checklist do not typically have to be filled out for the CxA to check out these systems. However, the contractor is responsible to inform and schedule the CxA to do Pre-Functional Checks.
- C Contractor schedules and scheduling is the responsibility of the Contractor. The Commissioning Authority shall provide commissioning scheduling information to the contractor for review and planning activities.
- D Individual dates are defined in the individual commissioning specifications for each spec section as defined in the other commissioning specifications.
- E Completion and acceptance of the general systems commissioning shall be a condition of Substantial Completion. The building shall be considered 'not ready to utilize for its intended use' until such time that the general systems commissioning is successfully completed.
  - 1. In the event that Substantial Completion is given by the Owner to the contractor and commissioning is not complete, then the warranty period for all pieces of mechanical systems shall not begin until the CxA gives their final Commissioning Report.

## 1.9 MISCELLANEOUS CONTRACTOR RESPONSIBILITIES

- A Means and Methods: The contractor is solely responsible for the means and methods of construction. While the CxA shall assist in construction, the final responsibility rests solely on the general and installation contractor.

- B Special Tools and Equipment: While the CxA retains tools in accordance with NEBB BSC Procedural Standards any specialized tools to test the equipment shall be provided to the CxA and used by the Contractor to prove compliance with the OPR and Construction Documents.

## PART 2 – PRODUCTS

(NOT USED)

## PART 3 – EXECUTION

### 3.1 COMMISSIONING KICKOFF MEETING

- A The CxA shall facilitate a Commissioning Kickoff Meeting after all mechanical, electrical, and general subcontractors are under contract with the General Contractor. The CxA shall invite the architect, engineers, and Owner's representatives to the meeting.
- B The General Contractor shall ensure that the following individuals are in attendance:
  - 1. The Mechanical Foreman and Project Manager
  - 2. The General Foreman and Project Manager
  - 3. The Controls Foreman and Project Manager
  - 4. The Test and Balance Project Manager
  - 5. The Electrical Foreman and Project Manager
  - 6. The Fire Protection Foreman and Project Manager
  - 7. The General Contractor Project Engineer, Superintendent, and Project Manager
- C The CxA shall keep meeting minutes and distribute to the individuals present.

### 3.2 DISTRIBUTION LIST

- A. The distribution list shall be developed during the Commissioning Kickoff Meeting. This distribution list shall be used for all distribution of commissioning activities. While every effort shall be made to distribute all pertinent information to the subcontractors by the CxA, the sole responsibility for subcontractors to receive information rest on the General Contractor.
- B If the subcontractors do not receive information in regards to commissioning activities and the CxA has to reschedule a meeting or appointment or testing activity, the contractor shall reimburse the CxA for any expenses that result.

### 3.3 COMMISSIONING PLAN

- A. The Commissioning Plan shall be developed by the CxA and delivered at the conclusion of the submittal process.
- B The Commissioning Plan will have the CxA Procedural Standards for testing, the PFAT checklists, the FAT checklists and the Contractor Readiness Checklists.

- C The subcontractors and contractors are responsible for reviewing the above checklists and provide comments to the CxA within 30 calendar days of receiving the commissioning plan. During this comment period the comments must be received in writing and the CxA will work with the individual contractors and subcontractors to ensure the safety of systems. After the 30 day period for comment any additional comments received shall be reviewed by the CxA, however, the subcontractor shall be liable for any cost associated with this review and any delays.

### 3.4 SUBMITTAL REVIEWS AND SUBMITTAL MEETINGS

- A. The CxA shall review all mechanical submittals. It is the responsibility of the contractor to ensure they receive the CxA reviews. The Architect is responsible for delivering the submittals to the CxA, however, in the return submittal if the contractor does not see our review or see an acknowledgement that we did not want to review the submittal it is the responsibility of the contractor to ask for the submittal from the CxA directly.
- B The subcontractor, supplier and manufacturer are responsible to submit with initial submittals a line by line submittal compliance document. The compliance document will follow the specification that the submittal is in reference too. The compliance document will have one of the following for each paragraph of the specification: Comply, Exception, or Unable to Comply. With each Exception and Unable to Comply the compliance document will have a detailed explanation.
- C The subcontractor, supplier and manufacturer shall attend a submittal review meeting before any piece of equipment shall be ordered. This meeting will be held and conducted by the Commissioning Authority at a place designated by Commissioning Authority (which typically is the General Contractors Trailer). During this meeting the CxA, Engineer, and Owner will review the submittal compliance document.
- D The submittals will be marked with Reviewed, Reviewed as Noted, Defer to Engineer, Note, or Revise and Resubmit. Only Revise and Resubmit items will have the expectation of a re-submittal. In the event that any item is marked as Revise and Resubmit contractor shall pay all expenses incurred by the Cx Authority for the re-review process.

### 3.5 BUILDING INFORMATION MODELING (BIM) REVIEWS

- A. The CxA shall review the BIM models at 90% completion for access issues. The file shall be delivered to the CxA in a NavisWorks format (.nwd).
- B The contractor may split the review up by floors. Partial floors shall not be reviewed by the CxA until the entire floor is completed to 90%.
- C The CxA shall deliver a floor plan with markups on areas of access concern.
- D BIM Model shall include the following:
  - 1. All duct work and air handling equipment. Ductwork shall show flanges. Model shall show insulation around duct work.
  - 2. All mechanical equipment.
  - 3. All hangers including unistrut, clevis, all-thread and strap material.

4. Duct fittings including HETO and flex and grills.
5. Electrical work and controls conduit cumulating 1.5" or larger.
6. Mechanical access zones
7. Fire/Smoke or fire dampers including access zones.
8. Mechanical piping larger than ¾".
9. Refrigerant lines, no matter the size.
10. Cable tray
11. Electrical equipment
12. All hangers and supports for electrical equipment.
13. All light fixtures
14. All power feeds including conduit or bus bars.
15. Outlets and switches where location is a priority for architectural.
16. Electrical equipment access zones.
17. All occupancy sensors, daylight sensors, exit signs, fire alarm strobes and horns, cameras, speakers, and AV equipment located in ceiling grid.
18. Natural gas lines larger than ½"
19. Plumbing lines larger than ½"
20. Insulation shall be shown with the correct sizing on plumbing lines.
21. All plumbing valves and cleanouts.
22. Access zones to plumbing valves and cleanouts.
23. Fire protection piping no matter the size.
24. Fire protection drops
25. Fire protection equipment
26. The entire steel structure including beams, columns, supports, braces, bent plate, supports or secondary supports.
27. All catwalks and their support systems.
28. All concrete structures include walls, columns or beams.
29. All access doors in the architectural ceiling for access to all electrical, plumbing and mechanical systems.
30. Ceiling grid
31. All walls windows and doors.
32. Lab hoods
33. Kitchen equipment and hoods

### 3.6 COORDINATION MEETINGS (MEP MEETINGS)

- A. The CxA shall conduct a bi-weekly coordination meeting. The mechanical, general, test and balance, electrical, and controls contractor shall attend these meetings. In the final month to six weeks of construction, these meetings will become weekly.
- B The purpose of these meetings is to coordinate installation, commissioning, and testing activities. These meetings will be conducted by the CxA and minutes from these meetings shall be delivered to those individuals described in the Distribution List section.

### 3.7 CONSTRUCTION OBSERVATION AND FIRST INSTALLS

- A. The CxA shall observe construction activities throughout the construction of the project. The contractors shall be available during these observations for information. An issues log as outlined in Part 1 shall be kept by the CxA.
- B First installs are not mockups. They are first installations of individual pieces of equipment that need to be installed in their location. First installs shall be required by the contractor and subcontractor as defined in the individual commissioning specifications.
- C Contractor shall coordinate and not prohibit observations and first installs. Subcontractors, Owner's representatives and engineers shall review the first installs for compliance.

### 3.8 CONTRACTOR READINESS CHECKLISTS

- A Contractor Readiness Checklists (CRC) shall be delivered by the CxA to the contracting team for the contracting team to fill out. The purpose of the CRCs to inform the CxA of the readiness of the contractor to begin Functional Testing on the mechanical system.
- B The CxA shall not begin Functional Testing of the system or any equipment until the CRCs are received. While some systems can be tested without a complete system the CxA shall have the final say on which can and cannot begin functional testing based on the completeness of the project.
- C If the contractor delivers the CRCs and the CxA finds the system is not functional then the contractor shall be liable for cost incurred by the CxA.

### 3.9 PRE FUNCTIONAL CHECKLISTS

- A The Pre Functional Checklists shall be developed by the CxA and delivered in the commissioning plan.
- B The Pre Functional Checklists shall be reviewed by the contractors and subcontractors and shall be executed by the CxA.
- C The CxA shall review 100% of all General systems installations.

### 3.10 FUNCTIONAL PERFORMANCE CHECKLISTS

- A The CxA shall execute Functional Performance Checks with the attendance of suppliers, BMS or ATC Contractor, mechanical contractors, electrical contractors, test and balance contractor, and general contractor at the request of the CxA.
- B Commissioning Authority shall develop and document the commissioning procedures to be used this will be delivered to the contractor in the commissioning plan and is called the Procedural Standards. Include a performance checklist and performance test data sheets for each system based on actual system configuration. These procedures shall be reviewed by the appropriate contractors and subcontractors for technical depth, clarity of documentation and completeness. Emphasis shall be placed on testing procedures that shall determine actual system performance and compliance with the design intent.

- C The Commissioning Authority shall determine the acceptance procedures for each system within general divisions as required. The acceptance procedures shall incorporate the commissioning standards and successful testing results as referred to throughout General specifications.
- D The appropriate contractor and vendor(s) shall be informed of what tests are to be performed and the expected results. Whereas some test results and interpretations may not become evident until the actual tests are performed, all parties shall have a reasonable understanding of the requirements. The Commissioning Plan shall address those requirements and be distributed to all parties involved with that particular system.
- E Acceptance procedures shall confirm the performance of systems to the extent of the design intent. When a system is accepted, the Owner shall be assured that the system is complete, works as intended, is correctly documented, and operator training has been performed.
- F During the functional performance testing the BMS or ATC contractor shall be in attendance to setup the CxA on the controls system and be in attendance throughout the sequence of operation checks.
- G The CxA shall review 100% and test 100% of all mechanical, electrical and plumbing systems.

### 3.11 TRENDING

- A Trending points shall be outlined in the Procedural Standards as delivered by the CxA in the commissioning plan.
- B A minimum Four (4) weeks of “Clean” trending (no mechanical, software, control loop or Building Management System “BMS” failures) shall be provided on “Any” or “All” BMS systems & points as directed by the C/A. Clean Trending shall be a requirement that is completed prior to Substantial Completion. Trends shall be coincident at 15 minute intervals with a cache able to handle four weeks of trending on a rollover basis.
- C Trending shall be submitted in a graphical Microsoft 2007 Format including all data submitted in the excel workbook. Graphs shall be line graphs shown on printable 11 x 17 pages. Graphs shall include annotations showing compliance with contract documents.
  - 1. ALL points shall be trended and submitted in the above format and as outlined by the Cx Authority. Contractor shall submit during submittal process what shall be trended per each graph to show functionality.
- D If the BMS contractor has the ability to setup the trends in their system and the CxA is allowed full access and the graphs and trends are able to come through on the CxA computer from a remote site then paragraph C shall be fulfilled through this paragraph. The CxA shall review the trends after the four weeks of clean trending.

### 3.12 OPERATION AND MAINTENANCE MANUALS

- A The contractor responsible for mechanical O&Ms shall deliver electronic copies of those O&M to the CxA at 50% billable completion of installed mechanical systems. The O&M manuals shall include installation requirements and maintenance requirements.
  - 1. The 50% mechanical billable draw shall be held up by the owner at the request of the CxA if the O&M manuals are not delivered.
- B The final O&M manual shall be reviewed by the CxA before delivery to the Owner. Any deficiencies shall be noted and the contractor shall remedy before final delivery.
- C The final O&M must be delivered to the Owner before training shall commence and it shall be one of the requirements for Substantial Completion.

### 3.13 CURRENT FACILITY REQUIREMENTS AND OPERATION AND MAINTENANCE PLAN

- A All contractors as defined in Participants in General Commissioning shall compile a Current Facility Requirements (CFR) and Operations and Maintenance (O&M) Plan as outlined in LEED v4 EA – “Fundamental Commissioning and Verification”.
- B The contractors shall provide the following in an editable Microsoft Word Format. (.doc or .docx) in a narrative format for use by the CxA to provide the final CFR and O&M Plan.
  - 1. Sequences of operation for the building
  - 2. Building occupancy schedule
  - 3. Equipment run-time schedules
  - 4. Setpoints for all General equipment
  - 5. Lighting levels throughout the building
  - 6. Minimum outside air requirements
  - 7. Changes in schedules or setpoints for different seasons, days of the week, and times of day
  - 8. Systems narrative describing the mechanical and electrical systems and equipment
  - 9. Preventive maintenance plan for building equipment described in the systems narrative
  - 10. Cx program that includes periodic Cx requirements, ongoing Cx tasks, and continuous tasks for critical facilities

### 3.14 SYSTEMS MANUAL

- A All contractors as defined in Participants in General Commissioning shall compile a Systems Manual as outlined in LEED v4 EA – “Enhanced Commissioning”.
- B The contractors shall provide the following in an editable Microsoft Word Format. (.doc or .docx) in a narrative format for use by the CxA to provide the final Systems Manual. The submittals shall be compiled by section in a .pdf format.
  - 1. Construction record documents and specifications
  - 2. Approved submittals
  - 3. As-built drawings
  - 4. As-built sequence of operation
  - 5. Original setpoints for all systems commissioned

6. Recommended schedule for sensor recalibration
7. Equipment operations and maintenance manuals
8. Equipment preventive maintenance schedules
9. Confirmation of completed training for the owner and occupants

### 3.15 TRAINING

- A The CxA shall be invited to all general training sessions by the General Contractor.
- B The training shall not commence until the system has been commissioned and proven ready for training.
- C The contractor shall schedule and coordinate training sessions for the Owner's staff for each system. Training shall be in a classroom setting with the appropriate schematics, handouts, and visual/audio training aids on-site with equipment.
- D The Commissioning Authority shall review agendas, which shall be submitted at least four weeks before training, and shall audit the training sessions. The agenda shall include but not limited to operational setpoints, runtime schedules, general operation and maintenance requirements, time and location for the training. Agendas shall conform to the Syllabus section in ASHRAE 0-2013-Appendix P and LEED v4 – EA – “Enhanced Commissioning”.
- E The training program shall include the following:
  1. Emergency instructions and procedures
  2. Operation instructions and procedures
  3. Troubleshooting procedures
  4. Maintenance and inspection procedures
  5. Repair procedures
  6. Upkeep of the systems manual and associated maintenance documentation logs
- F Evaluations shall be done of the training system by the attendees. The evaluations shall reflect ASHRAE 0-2013-Appendix P Evaluation Form.
  1. If the Evaluations from the training average rises above 2 (based on 1 being very well trained and 5 not at all trained) then the training shall recommence. All cost for the re-training shall be solely born by the contractor training, including any reimbursment to the Owner for the CxA, the Owners Operational Staff, and any other cost born by the owner for failure to comply with requirements.
- G The contractor shall provide a schedule for training times and dates. The schedule shall include location, who is training, trainers contact information, and the training that is to take place.
- H The appropriate installing contractors shall provide training on all the major systems per specifications, including peculiarities specific to this project.
- I The equipment vendors shall provide training on the specifics of each major equipment item including philosophy, troubleshooting, and repair techniques.



- J The automatic control vendor shall provide training on the control system per their specification section.
- K The contractor shall furnish a final video DVD set, above the owners requirements as defined elsewhere, to the CxA for their use and ownership and review. Included in those DVDs shall be the sign-in sheet for each training.

### 3.16 RECORD DRAWINGS OR REDLINES

- A The CxA shall review the “Redlines” or “Record Drawings” on a bi-weekly basis. Updating redlines shall be a term of a monthly draw and can hold up a monthly draw if the Record Drawings are not updated.
- B Record Drawings or Redlines shall be kept in a printed format above and beyond any BIM modeling. If record drawings are being kept on BIM a printed out version on a typical 2D flat sheet of paper large enough to read shall be kept as well in the General Contractors trailer.
- C The following requirements shall be meet for Redlines or Record Drawings:
  - 1. Underground: All underground piping no matter the size shall be shown with dimensions from walls (not gridlines) and elevations of the pipe at every ninety or y fitting and marked at every 20 feet on the drawings.
  - 2. Above Ground Concealed: All above ground piping no matter the size concealed in hard lid or behind walls shall be dimensioned from walls.
  - 3. Above Ground Accessible or Unconcealed: All above ground piping no matter the size shall be documented in the redlines. General location shall be sufficient as long as the general location is in the same area not separated by walls.
- D The final redlines shall be reviewed by the CxA before delivery to the Architect.

### 3.17 WARRANTY PERIOD AND CONTINUOUS COMMISSIONING

- A The CxA shall provide Continuous Commissioning during the One Year Warranty Period after substantial completion. During this time the CxA shall adjust settings on the BMS for optimization of the system, shall find issues with the system, and shall report issues to the contractors.
- B The contractor and subcontractors shall resolve issues immediately.

### 3.18 REPEATED WORK, TESTING, AND REVIEWS

- A Contractor shall, at no additional cost to the Owner, repeat the complete verification test procedure for each test for which acceptable results are not achieved. Repeat tests until acceptable results are achieved.
- B Contractor shall compensate the Owner for costs incurred as the result of tests review or inspection repeated. This includes the costs for the commissioning authority, design architect, design engineers, and Owner’s personnel for billed costs (including travel expenses) for the

University of Utah

Salt Lake City, Utah 84132

extraordinary participation of the Owner's representative, architect, commissioning authority or Owner's staff .

- C All retesting, inspection or review of equipment or re reviewing of startup sheets or re-reviewing of test and balance or re-reviewing of controls or re-reviewing of submittals shall be billed at a rate of \$250 per hour with a minimum of 4 hours billed per session.

END OF SECTION

This Page Intentionally Left Blank

## SECTION 02 4119 - SELECTIVE DEMOLITION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. Demolition and removal of selected portions of building or structure.

- B. Related Requirements:

- 1. Section 01 1000 "Summary" for restrictions on use of the premises and Owner-occupancy requirement.
  - 2. Section 01 7300 "Execution" for cutting and patching procedures.

#### 1.3 DEFINITIONS

- A. Remove: Detach items from existing construction and dispose of them off-site unless indicated to be salvaged or reinstalled.
- B. Remove and Reinstall: Detach items from existing construction, in a manner to prevent damage, prepare for reuse, and reinstall where indicated.
- C. Existing to Remain: Leave existing items that are not to be removed and that are not otherwise indicated to be salvaged or reinstalled.

#### 1.4 MATERIALS OWNERSHIP

- A. Unless otherwise indicated, demolition waste becomes property of Contractor.

#### 1.5 PREINSTALLATION MEETINGS

- A. Predemolition Conference: Conduct conference at Project site.
  - 1. Inspect and discuss condition of construction to be selectively demolished.
  - 2. Review structural load limitations of existing structure.

3. Review and finalize selective demolition schedule and verify availability of materials, demolition personnel, equipment, and facilities needed to make progress and avoid delays.
4. Review requirements of work performed by other trades that rely on substrates exposed by selective demolition operations.
5. Review areas where existing construction is to remain and requires protection.

#### 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For refrigerant recovery technician.
- B. Engineering Survey: Submit engineering survey of condition of building.
- C. Proposed Protection Measures: Submit report, including Drawings, that indicates the measures proposed for protecting individuals and property, for environmental protection, for dust control and, for noise control. Indicate proposed locations and construction of barriers.
- D. Schedule of Selective Demolition Activities: Indicate the following:
  1. Detailed sequence of selective demolition and removal work, with starting and ending dates for each activity. Ensure Owner's building manager's on-site operations are uninterrupted.
  2. Interruption of utility services. Indicate how long utility services will be interrupted.
  3. Coordination for shutoff, capping, and continuation of utility services.
  4. Use of elevator and stairs.
  5. Coordination of Owner's continuing occupancy of existing adjacent building and of Owner's partial occupancy of completed Work.
- E. Predemolition Photographs or Video: Show existing conditions of adjoining construction, including finish surfaces, that might be misconstrued as damage caused by demolition operations. Submit before Work begins.
- F. Statement of Refrigerant Recovery: Signed by refrigerant recovery technician responsible for recovering refrigerant, stating that all refrigerant that was present was recovered and that recovery was performed according to EPA regulations. Include name and address of technician and date refrigerant was recovered.

#### 1.7 QUALITY ASSURANCE

- A. Refrigerant Recovery Technician Qualifications: Certified by an EPA-approved certification program.

#### 1.8 FIELD CONDITIONS

- A. Owner will occupy portions of building immediately adjacent to selective demolition area. Conduct selective demolition so Owner's operations will not be disrupted.

1. Coordinate and cooperate with Owner on selective demolition Work to proceed with the Work under restrictions placed by the Owner.
- B. Conditions existing at time of inspection for bidding purpose will be maintained by Owner as far as practical.
- C. Notify Architect of discrepancies between existing conditions and Drawings before proceeding with selective demolition.
- D. Hazardous Materials: It is not expected that hazardous materials will be encountered in the Work.
  1. Hazardous materials will be removed by Owner before start of the Work.
  2. If suspected hazardous materials are encountered, do not disturb; immediately notify Architect and Owner. Hazardous materials will be removed by Owner under a separate contract.
- E. Storage or sale of removed items or materials on-site is not permitted.
- F. Utility Service: Maintain existing utilities indicated to remain in service and protect them against damage during selective demolition operations.
  1. Maintain fire-protection facilities in service during selective demolition operations.

## 1.9 COORDINATION

- A. Arrange selective demolition schedule so as not to interfere with Owner's operations.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Regulatory Requirements: Comply with governing EPA notification regulations before beginning selective demolition. Comply with hauling and disposal regulations of authorities having jurisdiction.
- B. Standards: Comply with ASSE A10.6 and NFPA 241.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Verify that utilities have been disconnected and capped before starting selective demolition operations.

- B. Review Project Record Documents of existing construction or other existing condition and hazardous material information provided by Owner. Owner does not guarantee that existing conditions are same as those indicated in Project Record Documents.
- C. Perform an engineering survey of condition of building to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures during selective building demolition operations.
- D. Survey of Existing Conditions: Record existing conditions by use of measured drawings, preconstruction photographs or video, and/or templates.

### 3.2 PREPARATION

- A. Refrigerant: Before starting demolition, remove refrigerant from mechanical equipment according to 40 CFR 82 and regulations of authorities having jurisdiction.

### 3.3 UTILITY SERVICES AND MECHANICAL/ELECTRICAL SYSTEMS

- A. Existing Services/Systems to Remain: Maintain services/systems indicated to remain and protect them against damage.
- B. Existing Services/Systems to Be Removed, Relocated, or Abandoned: Locate, identify, disconnect, and seal or cap off utility services and mechanical/electrical systems serving areas to be selectively demolished.
  - 1. Arrange to shut off utilities with utility companies.
  - 2. If services/systems are required to be removed or relocated, provide temporary services/systems that bypass area of selective demolition and that maintain continuity of services/systems to other parts of building.
  - 3. Disconnect, demolish, and remove fire-suppression systems, plumbing, and HVAC systems, equipment, and components indicated on Drawings to be removed.
    - a. Piping to Be Removed: Remove portion of piping indicated to be removed to within 6 inches of the main line, and cap or plug remaining piping with same or compatible piping material.
    - b. Equipment to Be Removed: Disconnect and cap services and remove equipment.
    - c. Ducts to Be Removed: Remove portion of ducts indicated to be removed and plug remaining ducts with same or compatible ductwork material.

### 3.4 PROTECTION

- A. Temporary Protection: Provide temporary barricades and other protection required to prevent injury to people and damage to adjacent buildings and facilities to remain.
  - 1. Provide protection to ensure safe passage of people around selective demolition area and to and from occupied portions of building.

2. Provide temporary weather protection, during interval between selective demolition of existing construction on exterior surfaces and new construction, to prevent water leakage and damage to structure and interior areas.
  3. Protect walls, ceilings, floors, and other existing finish work that are to remain or that are exposed during selective demolition operations.
  4. Cover and protect furniture, furnishings, and equipment that have not been removed.
  5. Comply with requirements for temporary enclosures, dust control, heating, and cooling specified in Section 01 5000 "Temporary Facilities and Controls."
  6. Provide Infection Control Risk Assessment (ICRA) and remediation measures to provide infection control beyond the demolition Work area.
- B. Temporary Shoring: Design, provide, and maintain shoring, bracing, and structural supports as required to preserve stability and prevent movement, settlement, or collapse of construction and finishes to remain, and to prevent unexpected or uncontrolled movement or collapse of construction being demolished.
1. Strengthen or add new supports when required during progress of selective demolition.
- C. Remove temporary barricades and protections where hazards no longer exist.

### 3.5 SELECTIVE DEMOLITION, GENERAL

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
1. Proceed with selective demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
  2. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping. Temporarily cover openings to remain.
  3. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
  4. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
  5. Maintain fire watch during and for at least 24 hours after flame-cutting operations.
  6. Maintain adequate ventilation when using cutting torches.
  7. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
  8. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
  9. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.



10. Dispose of demolished items and materials promptly. Comply with requirements in Section 01 7419 "Construction Waste Management and Disposal."
- B. Site Access and Temporary Controls: Conduct selective demolition and debris-removal operations to ensure minimum interference with roads, streets, walks, walkways, and other adjacent occupied and used facilities.
- C. Removed and Reinstalled Items:
  1. Clean and repair items to functional condition adequate for intended reuse.
  2. Pack or crate items after cleaning and repairing. Identify contents of containers.
  3. Protect items from damage during transport and storage.
  4. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.
- D. Existing Items to Remain: Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and reinstalled in their original locations after selective demolition operations are complete.

### 3.6 SELECTIVE DEMOLITION PROCEDURES FOR SPECIFIC MATERIALS

- A. Concrete: Demolish in small sections. Using power-driven saw, cut concrete to a depth of at least 3/4 inch at junctures with construction to remain. Dislodge concrete from reinforcement at perimeter of areas being demolished, cut reinforcement, and then remove remainder of concrete. Neatly trim openings to dimensions indicated.
- B. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, and then break up and remove.

### 3.7 DISPOSAL OF DEMOLISHED MATERIALS

- A. Remove demolition waste materials from Project site and recycle or dispose of them according to Section 01 7419 "Construction Waste Management and Disposal."
  1. Do not allow demolished materials to accumulate on-site.
  2. Remove and transport debris in a manner that will prevent spillage on adjacent surfaces and areas.
  3. Remove debris from elevated portions of building by chute, hoist, or other device that will convey debris to grade level in a controlled descent.
  4. Comply with requirements specified in Section 01 7419 "Construction Waste Management and Disposal."
- B. Burning: Do not burn demolished materials.

3.8 CLEANING

- A. Clean adjacent structures and improvements of dust, dirt, and debris caused by selective demolition operations. Return adjacent areas to condition existing before selective demolition operations began.

3.9 SELECTIVE DEMOLITION SCHEDULE

- A. Remove and Reinstall: Remove and reinstall items indicated on Drawings, including, but not limited to, the following:
  - 1. Indicated fire extinguisher cabinets.
  - 2. Indicated diffusers.
  - 3. Indicated grills.
  - 4. Indicated light fixtures.
  - 5. Indicated electrical devices.

END OF SECTION 02 4119

B L A N K   P A G E

## SECTION 05 5000 - METAL FABRICATIONS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

1. Steel framing and supports for countertops.
2. Steel framing and supports for healthcare equipment.
3. Steel framing and supports for mechanical and electrical equipment.
4. Steel framing and supports for applications where framing and supports are not specified in other Sections.
5. Slotted channel framing.

- B. Related Requirements:

1. Section 05 1200 "Structural Steel Framing" for steel framing supports and other steel items attached to the structural-steel framing.

#### 1.3 COORDINATION

- A. Coordinate selection of shop primers with topcoats to be applied over them. Comply with paint and coating manufacturers' written instructions to ensure that shop primers and topcoats are compatible with one another.
- B. Coordinate installation of metal fabrications that are anchored to or that receive other work. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors, that are to be embedded in concrete or masonry. Deliver such items to Project site in time for installation.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For the following:

1. Fasteners.
2. Shop primers.

3. Shrinkage-resisting grout.
4. Slotted channel framing.

B. Shop Drawings: Show fabrication and installation details. Include plans, elevations, sections, and details of metal fabrications and their connections. Show anchorage and accessory items. Provide Shop Drawings for the following:

1. Steel framing and supports for countertops.
2. Steel framing and supports for mechanical and electrical equipment.
3. Steel framing and supports for applications where framing and supports are not specified in other Sections.

## 1.5 INFORMATIONAL SUBMITTALS

- A. Welding certificates.
- B. Paint Compatibility Certificates: From manufacturers of topcoats applied over shop primers, certifying that shop primers are compatible with topcoats.
- C. Research Reports: For post-installed anchors.

## 1.6 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel in accordance with the following:
  1. AWS D1.1/D1.1M, "Structural Welding Code - Steel."

## 1.7 FIELD CONDITIONS

- A. Field Measurements: Verify actual locations of walls, floor slabs, decks, and other construction contiguous with metal fabrications by field measurements before fabrication.

## PART 2 - PRODUCTS

### 2.1 METALS

- A. Metal Surfaces, General: Provide materials with smooth, flat surfaces unless otherwise indicated. For metal fabrications exposed to view in the completed Work, provide materials without seam marks, roller marks, rolled trade names, or blemishes.
- B. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.

- C. Steel Plates, Shapes, and Bars: ASTM A36/A36M.
- D. Steel Tubing: ASTM A500/A500M, cold-formed steel tubing.
- E. Steel Pipe: ASTM A53/A53M, Standard Weight (Schedule 40) unless otherwise indicated.
- F. Steel Prestressing Strand: ASTM A416/A416M, Grade 270, low-relaxation, seven-wire, with 0.9-lb/sq. ft. zinc coating.
  - 1. Steel Prestressing Strand Fittings: Hot-dip galvanized-steel anchors and connectors with capability to sustain, without failure, a load equal to minimum breaking strength of steel prestressing strand with which they are used.
- G. Slotted Channel Framing: Cold-formed metal box channels (struts) complying with MFMA-4.
  - 1. Size of Channels: 1-5/8 by 1-5/8 inches.
  - 2. Material: Galvanized steel, ASTM A653/A653M, structural steel, Grade 33, with G90 coating; 0.079-inch nominal thickness.

## 2.2 FASTENERS

- A. General: Unless otherwise indicated, provide Type 304 stainless steel fasteners for exterior use and zinc-plated fasteners with coating complying with ASTM B633 or ASTM F1941/F1941M, Class Fe/Zn 5, at exterior walls. Select fasteners for type, grade, and class required.
  - 1. Provide stainless steel fasteners for fastening aluminum, stainless steel or nickel silver.
- B. Steel Bolts and Nuts: Regular hexagon-head bolts, ASTM A307, Grade A; with hex nuts, ASTM A563; and, where indicated, flat washers.
- C. High-Strength Bolts, Nuts, and Washers: ASTM F3125/F3125M, Grade A325, Type 3, heavy-hex steel structural bolts; ASTM A563, Grade DH3, heavy-hex carbon-steel nuts; and where indicated, flat washers.
- D. Stainless Steel Bolts and Nuts: Regular hexagon-head annealed stainless steel bolts, ASTM F593; with hex nuts, ASTM F594; and, where indicated, flat washers; Alloy Group 1.
  - 1. Hot-dip galvanize or provide mechanically deposited, zinc coating where item being fastened is indicated to be galvanized.
- E. Anchors, General: Capable of sustaining, without failure, a load equal to six times the load imposed when installed in unit masonry and four times the load imposed when installed in concrete, as determined by testing in accordance with ASTM E488/E488M, conducted by a qualified independent testing agency.
- F. Cast-in-Place Anchors in Concrete: Either threaded or wedge type unless otherwise indicated; galvanized ferrous castings, either ASTM A47/A47M malleable iron or ASTM A27/A27M cast

steel. Provide bolts, washers, and shims as needed, all hot-dip galvanized per ASTM F2329/F2329M.

- G. Post-Installed Anchors: Torque-controlled expansion anchors or chemical anchors.
  - 1. Material for Interior Locations: Carbon-steel components zinc plated to comply with ASTM B633 or ASTM F1941/F1941M, Class Fe/Zn 5, unless otherwise indicated.
- H. Slotted-Channel Inserts: Cold-formed, hot-dip galvanized-steel box channels (struts) complying with MFMA-4, 1-5/8 by 7/8 inches by length indicated with anchor straps or studs not less than 3 inches long at not more than 8 inches o.c. Provide with temporary filler and tee-head bolts, complete with washers and nuts, all zinc-plated to comply with ASTM B633, Class Fe/Zn 5, as needed for fastening to inserts.

## 2.3 MISCELLANEOUS MATERIALS

- A. Shop Primers: Provide primers that comply with Section 09 9123 "Interior Painting" and Section 09 9600 "High-Performance Coatings."
- B. Shrinkage-Resistant Grout: Factory-packaged, nonmetallic, nonstaining, noncorrosive, nongaseous grout complying with ASTM C1107/C1107M. Provide grout specifically recommended by manufacturer for interior and exterior applications.

## 2.4 FABRICATION, GENERAL

- A. Shop Assembly: Preassemble items in the shop to greatest extent possible. Disassemble units only as necessary for shipping and handling limitations. Use connections that maintain structural value of joined pieces. Clearly mark units for reassembly and coordinated installation.
- B. Cut, drill, and punch metals cleanly and accurately. Remove burrs and ease edges to a radius of approximately 1/32 inch unless otherwise indicated. Remove sharp or rough areas on exposed surfaces.
- C. Form bent-metal corners to smallest radius possible without causing grain separation or otherwise impairing work.
- D. Form exposed work with accurate angles and surfaces and straight edges.
- E. Weld corners and seams continuously to comply with the following:
  - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  - 2. Obtain fusion without undercut or overlap.
  - 3. Remove welding flux immediately.

4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.
- F. Form exposed connections with hairline joints, flush and smooth, using concealed fasteners or welds where possible. Where exposed fasteners are required, use Phillips flat-head (countersunk) fasteners unless otherwise indicated. Locate joints where least conspicuous.
- G. Fabricate seams and other connections that are exposed to weather in a manner to exclude water. Provide weep holes where water may accumulate.
- H. Cut, reinforce, drill, and tap metal fabrications as indicated to receive finish hardware, screws, and similar items.
- I. Provide for anchorage of type indicated; coordinate with supporting structure. Space anchoring devices to secure metal fabrications rigidly in place and to support indicated loads.
- J. Where units are indicated to be cast into concrete or built into masonry, equip with integrally welded steel strap anchors, 1/8 by 1-1/2 inches, with a minimum 6-inch embedment and 2-inch hook, not less than 8 inches from ends and corners of units and 24 inches o.c., unless otherwise indicated.

## 2.5 MISCELLANEOUS FRAMING AND SUPPORTS

- A. General: Provide steel framing and supports not specified in other Sections as needed to complete the Work.
- B. Fabricate units from steel shapes, plates, and bars of welded construction unless otherwise indicated. Fabricate to sizes, shapes, and profiles indicated and as necessary to receive adjacent construction.
  1. Fabricate units from slotted channel framing where indicated.
  2. Furnish inserts for units installed after concrete is placed.
- C. Prime miscellaneous framing and supports with primer specified in Section 09 9600 "High-Performance Coatings" where indicated.

## 2.6 GENERAL FINISH REQUIREMENTS

- A. Finish metal fabrications after assembly.
- B. Finish exposed surfaces to remove tool and die marks and stretch lines, and to blend into surrounding surface.



## 2.7 STEEL AND IRON FINISHES

- A. Shop prime iron and steel items not indicated to be galvanized unless they are to be embedded in concrete, sprayed-on fireproofing, or masonry, or unless otherwise indicated.
  - 1. Shop prime with primers specified in Section 09 9123 "Interior Painting" unless zinc-rich primer is indicated.
- B. Preparation for Shop Priming: Prepare surfaces to comply with requirements indicated below:
  - 1. Items Indicated to Receive Primers Specified in Section 09 9600 "High-Performance Coatings": SSPC-SP 6/NACE No. 3, "Commercial Blast Cleaning."
  - 2. Other Steel Items: SSPC-SP 3, "Power Tool Cleaning."
- C. Shop Priming: Apply shop primer to comply with SSPC-PA 1, "Paint Application Specification No. 1: Shop, Field, and Maintenance Painting of Steel," for shop painting.
  - 1. Stripe paint corners, crevices, bolts, welds, and sharp edges.

## PART 3 - EXECUTION

### 3.1 INSTALLATION, GENERAL

- A. Cutting, Fitting, and Placement: Perform cutting, drilling, and fitting required for installing metal fabrications. Set metal fabrications accurately in location, alignment, and elevation; with edges and surfaces level, plumb, true, and free of rack; and measured from established lines and levels.
- B. Fit exposed connections accurately together to form hairline joints. Weld connections that are not to be left as exposed joints but cannot be shop welded because of shipping size limitations. Do not weld, cut, or abrade surfaces of exterior units that have been hot-dip galvanized after fabrication and are for bolted or screwed field connections.
- C. Field Welding: Comply with the following requirements:
  - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  - 2. Obtain fusion without undercut or overlap.
  - 3. Remove welding flux immediately.
  - 4. At exposed connections, finish exposed welds and surfaces smooth and blended so no roughness shows after finishing and contour of welded surface matches that of adjacent surface.
- D. Fastening to In-Place Construction: Provide anchorage devices and fasteners where metal fabrications are required to be fastened to in-place construction. Provide threaded fasteners for

use with concrete and masonry inserts, toggle bolts, through bolts, lag screws, wood screws, and other connectors.

- E. Provide temporary bracing or anchors in formwork for items that are to be built into concrete, masonry, or similar construction.

### 3.2 INSTALLATION OF MISCELLANEOUS FRAMING AND SUPPORTS

- A. General: Install framing and supports to comply with requirements of items being supported, including manufacturers' written instructions and requirements indicated on Shop Drawings.

### 3.3 REPAIRS

- A. Touchup Painting:

1. Immediately after erection, clean field welds, bolted connections, and abraded areas. Paint uncoated and abraded areas with same material as used for shop painting to comply with SSPC-PA 1 for touching up shop-painted surfaces.
  - a. Apply by brush or spray to provide a minimum 2.0-mil dry film thickness.
2. Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint are specified in Section 09 9123 "Interior Painting."

END OF SECTION 05 5000

## SECTION 06 1053 - MISCELLANEOUS ROUGH CARPENTRY

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Wood blocking and nailers.

#### 1.3 DEFINITIONS

- A. Boards or Strips: Lumber of less than 2 inches nominal size in least dimension.
- B. Dimension Lumber: Lumber of 2 inches nominal or greater size but less than 5 inches nominal size in least dimension.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of process and factory-fabricated product. Indicate component materials and dimensions and include construction and application details.
  - 1. Include data for fire-retardant treatment from chemical treatment manufacturer and certification by treating plant that treated materials comply with requirements. Include physical properties of treated materials based on testing by a qualified independent testing agency.
  - 2. For fire-retardant treatments, include physical properties of treated lumber both before and after exposure to elevated temperatures, based on testing by a qualified independent testing agency according to ASTM D5664.
  - 3. For products receiving a waterborne treatment, include statement that moisture content of treated materials was reduced to levels specified before shipment to Project site.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Evaluation Reports: For the following, from ICC-ES:
  - 1. Fire-retardant-treated wood.
  - 2. Power-driven fasteners.

3. Post-installed anchors.

## 1.6 QUALITY ASSURANCE

- A. Testing Agency Qualifications: For testing agency providing classification marking for fire-retardant-treated material, an inspection agency acceptable to authorities having jurisdiction that periodically performs inspections to verify that the material bearing the classification marking is representative of the material tested.
- B. Certified Wood: Provide an invoice including vendor's chain-of-custody number, product cost, and entity being invoiced.
- C. Vendor Qualifications: A vendor that is certified for chain of custody by an FSC-accredited certification body.

## 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Stack lumber flat with spacers beneath and between each bundle to provide air circulation. Protect lumber from weather by covering with waterproof sheeting, securely anchored. Provide for air circulation around stacks and under coverings.

## PART 2 - PRODUCTS

### 2.1 WOOD PRODUCTS, GENERAL

- A. Lumber: DOC PS 20 and applicable rules of grading agencies indicated. If no grading agency is indicated, provide lumber that complies with the applicable rules of any rules-writing agency certified by the ALSC Board of Review. Provide lumber graded by an agency certified by the ALSC Board of Review to inspect and grade lumber under the rules indicated.
  1. Factory mark each piece of lumber with grade stamp of grading agency.
  2. Dress lumber, S4S, unless otherwise indicated.
- B. Maximum Moisture Content of Lumber: 15 percent for 2-inch nominal thickness or less, 19 percent for more than 2-inch nominal thickness unless otherwise indicated.

### 2.2 FIRE-RETARDANT-TREATED MATERIALS

- A. General: Where fire-retardant-treated materials are indicated, materials shall comply with requirements in this article, that are acceptable to authorities having jurisdiction, and with fire-test-response characteristics specified as determined by testing identical products per test method indicated by a qualified testing agency.

- B. Fire-Retardant-Treated Lumber by Pressure Process: Products with a flame-spread index of 25 or less when tested according to ASTM E84, and with no evidence of significant progressive combustion when the test is extended an additional 20 minutes, and with the flame front not extending more than 10.5 feet beyond the centerline of the burners at any time during the test.
  - 1. Treatment shall not promote corrosion of metal fasteners.
  - 2. Interior Type A: Treated materials shall have a moisture content of 28 percent or less when tested according to ASTM D3201 at 92 percent relative humidity. Use where exterior type is not indicated.
  - 3. Design Value Adjustment Factors: Treated lumber shall be tested according to ASTM D5664, and design value adjustment factors shall be calculated according to ASTM D6841.
- C. Identify fire-retardant-treated wood with appropriate classification marking of qualified testing agency.
- D. Application: Treat all miscellaneous carpentry unless otherwise indicated.

## 2.3 MISCELLANEOUS LUMBER

- A. General: Provide miscellaneous lumber indicated and lumber for support or attachment of other construction, including the following:
  - 1. Blocking.
  - 2. Nailers.
- B. Concealed Boards: 15 percent maximum moisture content of any of the following species and grades:
  - 1. Hem-fir or hem-fir (north), Construction or No. 2 Common grade; NLGA, WCLIB, or WWPA.
  - 2. Northern species, No. 2 Common grade; NLGA.
  - 3. Western woods, Construction or No. 2 Common grade; WCLIB or WWPA.
- C. For blocking not used for attachment of other construction, Utility, Stud, or No. 3 grade lumber of any species may be used provided that it is cut and selected to eliminate defects that will interfere with its attachment and purpose.
- D. For blocking and nailers used for attachment of other construction, select and cut lumber to eliminate knots and other defects that will interfere with attachment of other work.

## 2.4 FASTENERS

- A. General: Provide fasteners of size and type indicated that comply with requirements specified in this article for material and manufacture.

1. Where carpentry is in ground contact or in area of high relative humidity, provide fasteners with hot-dip zinc coating complying with ASTM A153/A153M.
- B. Nails, Brads, and Staples: ASTM F1667.
- C. Screws for Fastening to Metal Framing: ASTM C1002, length as recommended by screw manufacturer for material being fastened.
- D. Power-Driven Fasteners: Fastener systems with an evaluation report acceptable to authorities having jurisdiction, based on ICC-ES AC70.
- E. Post-Installed Anchors: Fastener systems with an evaluation report acceptable to authorities having jurisdiction as appropriate for the substrate.
  1. Material: Carbon-steel components, zinc plated to comply with ASTM B633, Class Fe/Zn 5.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION, GENERAL

- A. Framing Standard: Comply with AF&PA's WCD 1, "Details for Conventional Wood Frame Construction," unless otherwise indicated.
- B. Set carpentry to required levels and lines, with members plumb, true to line, cut, and fitted. Fit carpentry accurately to other construction. Locate nailers, blocking, and similar supports to comply with requirements for attaching other construction.
- C. Do not splice structural members between supports unless otherwise indicated.
- D. Provide blocking and framing as indicated and as required to support facing materials, fixtures, specialty items, and trim.
  1. Provide metal clips for fastening gypsum board or lath at corners and intersections where framing or blocking does not provide a surface for fastening edges of panels. Space clips not more than 16 inches o.c.
- E. Sort and select lumber so that natural characteristics do not interfere with installation or with fastening other materials to lumber. Do not use materials with defects that interfere with function of member or pieces that are too small to use with minimum number of joints or optimum joint arrangement.
- F. Securely attach carpentry work to substrate by anchoring and fastening as indicated, complying with the following:
  1. Table 2304.9.1, "Fastening Schedule," in ICC's International Building Code.
  2. ICC-ES evaluation report for fastener.

- G. Use steel common nails unless otherwise indicated. Select fasteners of size that will not fully penetrate members where opposite side will be exposed to view or will receive finish materials. Make tight connections between members. Install fasteners without splitting wood. Drive nails snug but do not countersink nail heads unless otherwise indicated.

### 3.2 INSTALLATION OF WOOD BLOCKING AND NAILER

- A. Install where indicated and where required for attaching other work. Form to shapes indicated and cut as required for true line and level of attached work. Coordinate locations with other work involved.
- B. Attach items to substrates to support applied loading. Recess bolts and nuts flush with surfaces unless otherwise indicated.

### 3.3 PROTECTION

- A. Protect wood that has been treated with inorganic boron (SBX) from weather. If, despite protection, inorganic boron-treated wood becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.
- B. Protect miscellaneous rough carpentry from weather. If, despite protection, miscellaneous rough carpentry becomes wet, apply EPA-registered borate treatment. Apply borate solution by spraying to comply with EPA-registered label.

END OF SECTION 06 1053

B L A N K   P A G E



## SECTION 06 4116 - PLASTIC-LAMINATE-FACED ARCHITECTURAL CABINETS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. Plastic-laminate-faced architectural cabinets and lockers.
  - 2. Wood furring, blocking, shims, and hanging strips for installing plastic-laminate-faced architectural cabinets unless concealed within other construction before cabinet installation.

- B. Related Requirements:

- 1. Section 06 1053 "Miscellaneous Rough Carpentry" for wood furring, blocking, shims, and hanging strips required for installing cabinets and concealed within other construction before cabinet installation.
  - 2. Division 12 sections for countertops at millwork.

#### 1.3 COORDINATION

- A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to support loads imposed by installed and fully loaded cabinets.

#### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product, including panel products high-pressure decorative laminate adhesive for bonding plastic laminate and cabinet hardware and accessories.
- B. Shop Drawings: Show location of each item, dimensioned plans and elevations, large-scale details, attachment devices, and other components.

1. Show locations and sizes of furring, blocking, and hanging strips, including concealed blocking and reinforcement specified in other Sections.
2. Show locations and sizes of cutouts and holes for items installed in architectural plastic-laminate cabinets.
3. Apply WI Certified Compliance Program label to Shop Drawings.

C. Samples for Verification: For the following:

1. Plastic Laminates: 8 by 10 inches, for each type, color, pattern, and surface finish required.
  - a. Provide one sample applied to core material with specified edge material applied to one edge.
2. Thermoset Decorative Panels: 8 by 10 inches 12 by 12 inches, for each color, pattern, and surface finish.
  - a. Provide edge banding on one edge.
3. Corner Pieces:
  - a. Cabinet-front frame joints between stiles and rails and at exposed end pieces, 18 inches high by 18 inches wide by 6 inches deep.
  - b. Miter joints for standing trim.
4. Exposed Cabinet Hardware and Accessories: One full-size unit for each type and finish.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Certificates: For the following:
  1. Thermoset decorative panels.
  2. High-pressure decorative laminate.
  3. Adhesives.
- C. Quality Standard Compliance Certificates: WI Certified Compliance Program.

1.7 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.
  1. Shop Certification: WI's Certified Compliance Program licensee.

- B. Installer Qualifications: Fabricator of products.
- C. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
  - 1. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

## 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Do not deliver cabinets until painting and similar operations that could damage woodwork have been completed in installation areas. If cabinets must be stored in other than installation areas, store only in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

## 1.9 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install cabinets until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature between 60 and 90 deg F and relative humidity between 25 and 55 percent during the remainder of the construction period.
- B. Field Measurements: Where cabinets are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication, and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
  - 1. Locate concealed framing, blocking, and reinforcements that support cabinets by field measurements before being enclosed, and indicate measurements on Shop Drawings.
- C. Established Dimensions: Where cabinets are indicated to fit to other construction, establish dimensions for areas where cabinets are to fit. Provide allowance for trimming at site and for minor vertical adjustments, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

## PART 2 - PRODUCTS

### 2.1 ARCHITECTURAL CABINET FABRICATORS

- A. Fabricators: Subject to compliance with requirements, provide products by one of the following:
  - 1. Boswell Wasatch Mill.
  - 2. Contempo Cabinet & Mill.
  - 3. Fetzer Architectural Woodwork
  - 4. Fondell Architectural Woodwork, Inc.

5. Granite Mill & Fixture Co.
6. Huetter Mill & Cabinet Inc.
7. Hurco Design and Manufacturing.
8. Johnson Brothers Planing Mill Inc.
9. Masterpiece Millwork.
10. MC Mill & Design
11. Pacific Cabinets, Inc.
12. Riverwoods Mill, Inc.
13. Westmark Products, Inc.

## 2.2 PLASTIC-LAMINATE-FACED ARCHITECTURAL CABINETS

- A. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of architectural plastic-laminate cabinets indicated for construction, finishes, installation, and other requirements.
  1. Provide inspections of fabrication and installation together with labels and certificates from WI certification program indicating that woodwork complies with requirements of grades specified.
  2. The Contract Documents contain selections chosen from options in the quality standard and additional requirements beyond those of the quality standard. Comply with those selections and requirements in addition to the quality standard.
- B. Grade: Custom.
- C. Regional Materials: Wood products shall be manufactured within 100 miles of Project site from materials that have been extracted, harvested, or recovered, as well as manufactured, within 100 miles of Project site.
- D. Certified Wood: Wood products shall be certified as "FSC Pure" or "FSC Mixed Credit" according to FSC STD-01-001 and FSC STD-40-004.
- E. Type of Construction: Frameless.
- F. Cabinet, Door, and Drawer Front Interface Style: Flush overlay.
- G. High-Pressure Decorative Laminate PL-2 and PL-3: NEMA LD 3, grades as indicated or if not indicated, as required by woodwork quality standard.
  1. Basis of Design Products: Subject to compliance with requirements, provide products PL-2 and PL-3, as indicated on Finish Legend in the Drawings, or equivalent high-pressure decorative laminates approved by Architect prior to bid and complying with requirements, by one of the following:
    - a. Arborite.
    - b. Formica Corporation.
    - c. Pionite; a Panolam Industries International, Inc. brand.
    - d. Wilsonart International Holdings.

H. Laminate Cladding for Exposed Surfaces:

1. Horizontal Surfaces: Grade HGS.
2. Postformed Surfaces: Grade HGP.
3. Vertical Surfaces: Grade HGS.
4. Edges: Grade HGS PVC edge banding, 0.12-inch-thick, matching laminate in color, pattern, and finish.
5. Pattern Direction: Vertically for drawer fronts, doors, and fixed panels.

I. Materials for Semiexposed Surfaces:

1. Surfaces Other Than Drawer Bodies: Thermoset decorative panels.
  - a. Edges of Thermoset Decorative Panel Shelves: PVC or polyester edge banding.
  - b. For semiexposed backs of panels with exposed plastic-laminate surfaces, provide surface of high-pressure decorative laminate, NEMA LD 3, Grade VGS.
2. Drawer Sides and Backs: Thermoset decorative panels with PVC or polyester edge banding.
3. Drawer Bottoms: Thermoset decorative panels.

J. Concealed Backs of Panels with Exposed Plastic-Laminate Surfaces: High-pressure decorative laminate, NEMA LD 3, Grade BKL.

K. Cabinet Door Fronts: Edge band door fronts on all four sides and seal with durable finish for easy cleaning.

L. Drawer Construction: Fabricate with exposed fronts fastened to subfront with mounting screws from interior of body.

1. Join subfronts, backs, and sides with glued rabbeted joints supplemented by mechanical fasteners or glued dovetail joints.

M. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed laminate surfaces complying with the following requirements:

1. As indicated on the Finish Legend.

## 2.3 WOOD MATERIALS

A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of woodwork and quality grade specified unless otherwise indicated.

1. Wood Moisture Content: 5 to 10 percent.

B. Core Materials at Wet Areas: At areas within 4 inches of finish floors in laboratories, classrooms, restrooms, janitorial closets, or any area where water may be present, use exterior grade plywood or lumber rated by AWI for exterior use.

- C. Composite Wood Products: Products shall be made using ultra-low-emitting formaldehyde resins as defined in the California Air Resources Board's "Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products" or shall be made with no added formaldehyde.
  - 1. Medium-Density Fiberboard: ANSI A208.2, Grade 130, made with binder containing no urea formaldehyde.
  - 2. Softwood Plywood: DOC PS 1. Exterior Grade.
  - 3. Veneer-Faced Panel Products (Hardwood Plywood): HPVA HP-1, made with adhesive containing no urea formaldehyde.
  - 4. Thermoset Decorative Panels: Particleboard or medium-density fiberboard finished with thermally fused, melamine-impregnated decorative paper and complying with requirements of NEMA LD 3, Grade VGL, for test methods 3.3, 3.4, 3.6, 3.8, and 3.10.

## 2.4 CABINET HARDWARE AND ACCESSORIES

- A. Frameless Concealed Hinges (European Type): ANSI/BHMA A156.9, B01602, 170 degrees of opening, self-closing.
  - 1. Basis of Design: 71T650X by Blum
- B. Cabinet Pulls:
  - 1. Basis of Design: 5102-SS – 4" CC Stainless Steel Solid Wire Pull by GlideRite Hardware.
    - a. Size: 4-5/16 inches long with 1-9/32-inch projection; 5/16-inch dia.
    - b. Finish: Stainless steel.
- C. Catches: Magnetic catches, BHMA A156.9, B03141.
- D. Shelf Rests: BHMA A156.9, B04013; polycarbonate, pin type with shelf hold-down clip.
- E. Drawer Slides: BHMA A156.9.
  - 1. Grade 1 and Grade 2: Side mounted and extending under bottom edge of drawer; full-extension type; stainless steel or Nylon rollers.
  - 2. Grade 1HD-100 and Grade 1HD-200: Side mounted; full-overtravel-extension type; zinc-plated-steel ball-bearing slides.
  - 3. For drawers not more than 3 inches high and not more than 24 inches wide, provide Grade 1.
  - 4. For drawers more than 3 inches high but not more than 6 inches high and not more than 24 inches wide, provide Grade 1HD-100.
  - 5. For drawers more than 6 inches high or more than 24 inches wide, provide Grade 1HD-200.
- F. Door Locks: BHMA A156.11, E07121.
- G. Drawer Locks: BHMA A156.11, E07041.

- H. Door and Drawer Silencers: BHMA A156.16, L03011.
- I. Padlock Hasp: Nonmoving steel padlock loop.
- J. Hooks: Manufacturer's standard ball-pointed type hooks, aluminum or steel; zinc plated.
- K. Coat Rods: 1-inch- diameter steel tube or rod, chrome finished.
- L. Exposed Hardware Finishes: For exposed hardware, provide finish that complies with BHMA A156.18 for BHMA finish number indicated.
  - 1. Satin Stainless Steel: BHMA 630.
- M. For concealed hardware, provide manufacturer's standard finish that complies with product class requirements in BHMA A156.9.
- N. Grommets for Cable Passage through Cabinets: 2-inch OD, black, molded-plastic grommets and matching plastic caps with slot for wire passage.
  - 1. Product: Subject to compliance with requirements, provide "OG series" by Doug Mockett & Company, Inc.

## 2.5 MISCELLANEOUS MATERIALS

- A. Furring, Blocking, Shims, and Hanging Strips: Softwood or hardwood lumber, kiln dried to less than 15 percent moisture content.
- B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls and at floors.
- C. Adhesives: Use adhesives that meet the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

## 2.6 FABRICATION

- A. Fabricate cabinets to dimensions, profiles, and details indicated.
  - 1. Fabricate cabinets to meet or exceed the latest AWI Quality Standards, Custom grade or better, except where more stringent requirements are specified.
- B. Complete fabrication, including assembly and hardware application, to maximum extent possible before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.

1. Notify Architect seven days in advance of the dates and times woodwork fabrication will be complete.
- C. Shop-cut openings to maximum extent possible to receive hardware, appliances, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.
- D. Seal interior joints in cabinets where sinks are installed using sealant product specified in Section 07 9200 "Joint Sealants."

### PART 3 - EXECUTION

#### 3.1 PREPARATION

- A. Before installation, condition cabinets to humidity conditions in installation areas for not less than 72 hours.

#### 3.2 INSTALLATION

- A. Grade: Install cabinets to comply with quality standard grade of item to be installed.
- B. Assemble cabinets and complete fabrication at Project site to the extent that it was not completed in the shop.
- C. Install cabinets level, plumb, true, and straight. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches.
- D. Scribe and cut cabinets to fit adjoining work, refinish cut surfaces, and repair damaged finish at cuts.
- E. Anchor cabinets to anchors or blocking built in or directly attached to substrates. Secure with countersunk, concealed fasteners and blind nailing. Use fine finishing nails for exposed fastening, countersunk and filled flush with woodwork.
  1. Use filler matching finish of items being installed.
- F. Cabinets: Install without distortion so doors and drawers fit openings properly and are accurately aligned. Adjust hardware to center doors and drawers in openings and to provide unencumbered operation. Complete installation of hardware and accessory items as indicated.
  1. Install cabinets with no more than 1/8 inch in 96-inch sag, bow, or other variation from a straight line.
  2. Fasten wall cabinets through back, near top and bottom, and at ends not more than 16 inches o.c. with No. 10 wafer-head sheet metal screws through metal backing or metal



framing behind wall finish or toggle bolts through metal backing or metal framing behind wall finish.

### 3.3 ADJUSTING AND CLEANING

- A. Repair damaged and defective cabinets, where possible, to eliminate functional and visual defects; where not possible to repair, replace woodwork. Adjust joinery for uniform appearance.
- B. Clean, lubricate, and adjust hardware.
- C. Clean cabinets on exposed and semiexposed surfaces.

### 3.4 PROTECTION

- A. Protect finishes of stainless steel wall base from damage during construction period. Remove temporary protective coverings at time of Substantial Completion.

END OF SECTION 06 4116

B L A N K   P A G E

## SECTION 06 4219 - PLASTIC-LAMINATE-FACED WOOD PANELING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Plastic-laminate-faced MDF wood paneling at low walls.
  - 2. Wood furring, blocking, shims, and hanging strips for installing plastic-laminate-faced wood paneling that is not concealed within other construction.

#### 1.3 COORDINATION

- A. Coordinate sizes and locations of framing, blocking, reinforcements, and other related units of Work specified in other Sections to ensure that paneling can be installed as indicated.

#### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For plastic-laminate-faced wood paneling.
  - 1. Include plans, elevations, sections, and attachment details.
  - 2. Show details full size.
  - 3. Show locations and sizes of furring and blocking, including concealed blocking specified in other Sections.
- C. Samples for Verification: For each type of exposed laminate, 8 by 10 inches.
  - 1. Provide one Sample applied to core material and with specified edge material applied to one edge.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and fabricator.
- B. Product Certificates: For each type of product.

1.7 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.
  - 1. Shop Certification: AWI's Quality Certification Program accredited participant or WI's Certified Compliance Program licensee.
- B. Installer Qualifications: Fabricator of products.
- C. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
  - 1. Build mockups of typical paneling as shown on Drawings.
  - 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Do not deliver paneling until painting and similar operations that might damage paneling have been completed in installation areas. Store paneling in installation areas or in areas where environmental conditions comply with requirements specified in "Field Conditions" Article.

1.9 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install paneling until building is enclosed, wet-work is complete, and HVAC system is operating and will maintain temperature between 60 and 90 deg F and relative humidity between 25 and 55 percent during the remainder of the construction period.
- B. Field Measurements: Where paneling is indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
  - 1. Locate concealed framing, blocking, and reinforcements that support paneling by field measurements before being enclosed/concealed by construction and indicate measurements on Shop Drawings.

- C. Established Dimensions: Where paneling is indicated to fit to other construction, establish dimensions for areas where woodwork is to fit. Provide allowance for trimming at site, and coordinate construction to ensure that actual dimensions correspond to established dimensions.

## PART 2 - PRODUCTS

### 2.1 PANELING FABRICATORS

- A. Fabricators: Subject to compliance with requirements, provide products by one of the following:
  - 1. Boswell Wasatch Mill.
  - 2. Contempo Cabinet & Mill.
  - 3. Fetzer Architectural Woodwork
  - 4. Fondell Architectural Woodwork, Inc.
  - 5. Granite Mill & Fixture Co.
  - 6. Huetter Mill & Cabinet Inc.
  - 7. Hurco Design and Manufacturing.
  - 8. Johnson Brothers Planing Mill Inc.
  - 9. Masterpiece Millwork.
  - 10. MC Mill & Design
  - 11. Pacific Cabinets, Inc.
  - 12. Riverwoods Mill, Inc.
  - 13. Westmark Products, Inc.

### 2.2 PANELING, GENERAL

- A. Quality Standard: Unless otherwise indicated, comply with the "Architectural Woodwork Standards" for grades of plastic-laminate-faced wood paneling (decorative laminate surfacing) indicated for construction, finishes, installation, and other requirements.

### 2.3 PLASTIC-LAMINATE-FACED WOOD PANELING

- A. Grade: Custom.
- B. High-Pressure Decorative Laminate: NEMA LD 3, grades as indicated or if not indicated, as required by quality standard.
- C. High-Pressure Decorative Laminate PL-2 and PL-3: NEMA LD 3, grades as indicated or if not indicated, as required by woodwork quality standard.
  - 1. Basis of Design Products: Subject to compliance with requirements, provide products PL-2 and PL-3, as indicated on Finish Legend in the Drawings, or equivalent high-pressure decorative laminates approved by Architect prior to bid and complying with requirements, by one of the following:

- a. Arborite.
  - b. Formica Corporation.
  - c. Pionite; a Panolam Industries International, Inc. brand.
  - d. Wilsonart International Holdings.
2. Faces: Grade SGF.
3. Backs: Grade BKH.
4. Exposed Edges: Same as faces or Grade VGS.
- D. Colors, Patterns, and Finishes: Provide materials and products that result in colors and textures of exposed surfaces complying with the following requirements:
  1. As indicated on Finish Legend.
- E. Panel Core: MDF.
  1. Thickness: 3/4 inch.
- F. Exposed Panel Edges: Plastic-laminate matching faces.
- G. Assemble panels by gluing and concealed fastening.

## 2.4 MATERIALS

- A. Materials, General: Provide materials that comply with requirements of referenced quality standard for each quality grade specified unless otherwise indicated.
- B. Wood Moisture Content: 5 to 10 percent.
- C. Composite Wood Products: Provide materials that comply with requirements of referenced quality standard for each quality grade specified unless otherwise indicated.
- D. Composite Wood Products: Products shall be made using ultra-low-emitting formaldehyde resins as defined in the California Air Resources Board's "Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products" or shall be made with no added formaldehyde.
  1. MDF: ANSI A208.2, Grade 130.

## 2.5 INSTALLATION MATERIALS

- A. Furring, Blocking, Shims, and Hanging Strips: Softwood or hardwood lumber, kiln-dried to less than 15 percent moisture content.
- B. Anchors: Select material, type, size, and finish required for each substrate for secure anchorage. Provide metal expansion sleeves or expansion bolts for post-installed anchors. Use nonferrous-metal or hot-dip galvanized anchors and inserts at inside face of exterior walls.

- C. Installation Adhesive: Product recommended by panel fabricator for each substrate for secure anchorage.

- 1. Adhesives shall have a VOC content of 70 g/L or less.

## 2.6 FABRICATION

- A. Complete fabrication, including assembly, to maximum extent possible, before shipment to Project site. Disassemble components only as necessary for shipment and installation. Where necessary for fitting at site, provide ample allowance for scribing, trimming, and fitting.
- B. Shop cut openings, to maximum extent possible, to receive hardware, appliances, plumbing fixtures, electrical work, and similar items. Locate openings accurately and use templates or roughing-in diagrams to produce accurately sized and shaped openings. Sand edges of cutouts to remove splinters and burrs.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Before installation, condition paneling to humidity conditions in installation areas.
- B. Before installing paneling, examine shop-fabricated work for completion and complete work as required, including removal of packing and backpriming.

### 3.2 INSTALLATION

- A. Grade: Install paneling to comply with quality standard grade of paneling to be installed.
- B. Install paneling level, plumb, true in line, and without distortion. Shim as required with concealed shims. Install level and plumb to a tolerance of 1/8 inch in 96 inches. Install with no more than 1/16 inch in 96-inch vertical cup or bow and 1/8 inch in 96-inch horizontal variation from a true plane.
  - 1. For flush paneling with revealed joints, install with variations in reveal width, alignment of top and bottom edges, and flushness between adjacent panels not exceeding 1/32 inch.
- C. Anchor paneling to supporting substrate with concealed panel-hanger clips. Do not use face fastening unless otherwise indicated.

### 3.3 ADJUSTING AND CLEANING

- A. Repair damaged and defective paneling, where possible, to eliminate defects. Where not possible to repair, replace paneling. Adjust for uniform appearance.

ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84132

Code Review

B. Clean paneling on exposed surfaces.

END OF SECTION 06 4219



## SECTION 07 8100 - APPLIED FIREPROOFING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes sprayed fire-resistive materials, matching existing.

#### 1.3 DEFINITIONS

- A. SFRM: Sprayed fire-resistive materials.

#### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
  - 1. Review products, design ratings, restrained and unrestrained conditions, densities, thicknesses, bond strengths, and other performance requirements.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Framing plans or schedules, or both, indicating the following:
  - 1. Extent of fireproofing for each construction and fire-resistance rating.
  - 2. Applicable fire-resistance design designations of a qualified testing and inspecting agency acceptable to authorities having jurisdiction.
  - 3. Minimum fireproofing thicknesses needed to achieve required fire-resistance rating of each structural component and assembly.
- C. Samples: For each exposed product and for each color and texture specified, in manufacturer's standard dimensions in size.

#### 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.

- B. Product Certificates: For each type of fireproofing.
- C. Evaluation Reports: For fireproofing, from ICC-ES.
- D. Field quality-control reports.

#### 1.7 QUALITY ASSURANCE

- A. Installer Qualifications: A firm or individual certified, licensed, or otherwise qualified by fireproofing manufacturer as experienced and with sufficient trained staff to install manufacturer's products according to specified requirements.

#### 1.8 PRECONSTRUCTION TESTING

- A. Preconstruction Adhesion and Compatibility Testing: Test for compliance with requirements for specified performance and test methods.
  - 1. Bond Strength: Test for cohesive and adhesive strength according to ASTM E 736. Provide bond strength indicated in referenced fire-resistance design, but not less than minimum specified in Part 2.
  - 2. Density: Test for density according to ASTM E 605. Provide density indicated in referenced fire-resistance design, but not less than minimum specified in Part 2.
  - 3. Verify that manufacturer, through its own laboratory testing or field experience, attests that primers or coatings are compatible with fireproofing.
  - 4. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
  - 5. For materials failing tests, obtain applied-fireproofing manufacturer's written instructions for corrective measures including the use of specially formulated bonding agents or primers.

#### 1.9 FIELD CONDITIONS

- A. Environmental Limitations: Do not apply fireproofing when ambient or substrate temperature is 44 deg F or lower unless temporary protection and heat are provided to maintain temperature at or above this level for 24 hours before, during, and for 24 hours after product application.
- B. Ventilation: Ventilate building spaces during and after application of fireproofing, providing complete air exchanges according to manufacturer's written instructions. Use natural means or, if they are inadequate, forced-air circulation until fireproofing dries thoroughly.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Assemblies: Provide fireproofing, including auxiliary materials, according to requirements of each fire-resistance design and manufacturer's written instructions.
- B. Source Limitations: Obtain fireproofing from single source.
- C. Fire-Resistance Design: Indicated on Drawings, tested according to ASTM E 119 or UL 263; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - 1. Steel wide flange beams at concrete slabs over steel deck are to be considered restrained.
  - 2. Open-web joists and the Penthouse roof are to be considered unrestrained.
- D. Asbestos: Provide products containing no detectable asbestos.
- E. Provide SFRM as required by IBC-2015. See Code Analysis on Sheet G101. SFRM may not be shown graphically in all instances on the Drawings, including HSS support members for Level B Mezzanine and Penthouse roof and open web joists.

### 2.2 SPRAYED FIRE-RESISTIVE MATERIALS

- A. Sprayed Fire-Resistive Material: Manufacturer's standard, factory-mixed, lightweight, dry formulation, complying with indicated fire-resistance design, and mixed with water at Project site to form a slurry or mortar before conveyance and application.
  - 1. Provide fireproofing material matching existing.
  - 2. Basis-of-Design Product: Subject to compliance with requirements, provide Isolatak International; Cafco 300 HS or a comparable product by one of the following:
    - a. Carbolite Company; a subsidiary of RPM International.
    - b. GCP Applied Technologies Inc. (formerly Grace Construction Products).
  - 3. Application: Where fireproofing is exposed to exterior conditions, use fireproofing designated for exterior use by a qualified testing agency acceptable to authorities having jurisdiction.
  - 4. Bond Strength: Minimum 430-lbf/sq. ft. cohesive and adhesive strength based on field testing according to ASTM E 736.
  - 5. Density: Not less than density specified in the approved fire-resistance design, according to ASTM E 605.
  - 6. Thickness: As required for fire-resistance design indicated, measured according to requirements of fire-resistance design or ASTM E 605, whichever is thicker, but not less than 0.375 inch.
  - 7. Combustion Characteristics: ASTM E 136.

8. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  - a. Flame-Spread Index: 0.
  - b. Smoke-Developed Index: 0.
9. Compressive Strength: Minimum 1,440 psi according to ASTM E 761.
10. Corrosion Resistance: No evidence of corrosion according to ASTM E 937.
11. Deflection: No cracking, spalling, or delamination according to ASTM E 759.
12. Effect of Impact on Bonding: No cracking, spalling, or delamination according to ASTM E 760.
13. Air Erosion: Maximum weight loss of 0.025 g/sq. ft. in 24 hours according to ASTM E 859.
14. Fungal Resistance: Treat products with manufacturer's standard antimicrobial formulation to result in no growth on specimens per ASTM G 21 or rating of 10 according to ASTM D 3274 when tested according to ASTM D 3273.
15. Finish: Spray-textured finish.

## 2.3 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that are compatible with fireproofing and substrates and are approved by UL or another testing and inspecting agency acceptable to authorities having jurisdiction for use in fire-resistance designs indicated.
- B. Substrate Primers: Primers approved by fireproofing manufacturer and complying with one or both of the following requirements:
  1. Primer and substrate are identical to those tested in required fire-resistance design by UL or another testing and inspecting agency acceptable to authorities having jurisdiction.
  2. Primer's bond strength in required fire-resistance design complies with specified bond strength for fireproofing and with requirements in UL's "Fire Resistance Directory" or in the listings of another qualified testing agency acceptable to authorities having jurisdiction, based on a series of bond tests according to ASTM E 736.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for substrates and other conditions affecting performance of the Work and according to each fire-resistance design.
  1. Verify that substrates are free of dirt, oil, grease, release agents, rolling compounds, mill scale, loose scale, incompatible primers, paints, and encapsulants, or other foreign substances capable of impairing bond of fireproofing with substrates under conditions of normal use or fire exposure.

2. Verify that objects penetrating fireproofing, including clips, hangers, support sleeves, and similar items, are securely attached to substrates.
  3. Verify that substrates receiving fireproofing are not obstructed by ducts, piping, equipment, or other suspended construction that will interfere with fireproofing application.
- B. Verify that concrete work on steel deck is complete before beginning fireproofing work.
  - C. Verify that roof construction, installation of rooftop HVAC equipment, and other related work are complete before beginning fireproofing work.
  - D. Conduct tests according to fireproofing manufacturer's written instructions to verify that substrates are free of substances capable of interfering with bond.
  - E. Prepare written report, endorsed by Installer, listing conditions detrimental to performance of the Work.
  - F. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Cover other work subject to damage from fallout or overspray of fireproofing materials during application.
- B. Clean substrates of substances that could impair bond of fireproofing.
- C. Prime substrates where included in fire-resistance design and where recommended in writing by fireproofing manufacturer unless compatible shop primer has been applied and is in satisfactory condition to receive fireproofing.

### 3.3 APPLICATION

- A. Construct fireproofing assemblies that are identical to fire-resistance design indicated and products as specified, tested, and substantiated by test reports; for thickness, primers, sealers, topcoats, finishing, and other materials and procedures affecting fireproofing work.
- B. Comply with fireproofing manufacturer's written instructions for mixing materials, application procedures, and types of equipment used to mix, convey, and apply fireproofing; as applicable to particular conditions of installation and as required to achieve fire-resistance ratings indicated.
- C. Coordinate application of fireproofing with other construction to minimize need to cut or remove fireproofing.
  1. Do not begin applying fireproofing until clips, hangers, supports, sleeves, and other items penetrating fireproofing are in place.

2. Defer installing ducts, piping, and other items that would interfere with applying fireproofing until application of fireproofing is completed.

D. Metal Decks:

1. Do not apply fireproofing to underside of metal deck substrates until concrete topping, if any, is completed.
2. Do not apply fireproofing to underside of metal roof deck until roofing is completed; prohibit roof traffic during application and drying of fireproofing.

E. Install auxiliary materials as required, as detailed, and according to fire-resistance design and fireproofing manufacturer's written instructions for conditions of exposure and intended use. For auxiliary materials, use attachment and anchorage devices of type recommended in writing by fireproofing manufacturer.

F. Spray apply fireproofing to maximum extent possible. After the spraying operation in each area, complete the coverage by trowel application or other placement method recommended in writing by fireproofing manufacturer.

G. Extend fireproofing in full thickness over entire area of each substrate to be protected.

H. Install body of fireproofing in a single course unless otherwise recommended in writing by fireproofing manufacturer.

I. Provide a uniform finish complying with description indicated for each type of fireproofing material and matching finish approved for required mockups.

J. Cure fireproofing according to fireproofing manufacturer's written instructions.

K. Do not install enclosing or concealing construction until after fireproofing has been applied, inspected, and tested and corrections have been made to deficient applications.

L. Finishes: Where indicated, apply fireproofing to produce the following finishes:

1. Spray-Textured Finish: Finish left as spray applied with no further treatment.

### 3.4 FIELD QUALITY CONTROL

A. Special Inspections: Owner will engage a qualified special inspector to perform the following special inspections:

1. Test and inspect as required by the IBC, Subsection 1705.13, "Sprayed Fire-Resistant Materials."

B. Perform the tests and inspections of completed Work in successive stages. Do not proceed with application of fireproofing for the next area until test results for previously completed applications of fireproofing show compliance with requirements. Tested values must equal or exceed values as specified and as indicated and required for approved fire-resistance design.

- C. Fireproofing will be considered defective if it does not pass tests and inspections.
  - 1. Remove and replace fireproofing that does not pass tests and inspections, and retest.
  - 2. Apply additional fireproofing, per manufacturer's written instructions, where test results indicate insufficient thickness, and retest.
- D. Prepare test and inspection reports.

### 3.5 CLEANING, PROTECTING, AND REPAIRING

- A. Cleaning: Immediately after completing spraying operations in each containable area of Project, remove material overspray and fallout from surfaces of other construction and clean exposed surfaces to remove evidence of soiling.
- B. Protect fireproofing, according to advice of manufacturer and Installer, from damage resulting from construction operations or other causes, so fireproofing is without damage or deterioration at time of Substantial Completion.
- C. As installation of other construction proceeds, inspect fireproofing and repair damaged areas and fireproofing removed due to work of other trades.
- D. Repair fireproofing damaged by other work before concealing it with other construction.
- E. Repair fireproofing by reapplying it using same method as original installation or using manufacturer's recommended trowel-applied product.

### 3.6 SFRM SCHEDULE

- A. Provide indicated UL designs for assemblies indicated below as indicated in Drawings Series G500:

| Application                                                    | Basis of Design |
|----------------------------------------------------------------|-----------------|
| Composite floor deck assemblies with 2-inch minimum concrete   | UL# D859        |
| Composite floor deck assemblies with 3-1/2-inch thick concrete | UL# D902        |
| Floor beams                                                    | UL# N759        |
| Columns – HSS members                                          | UL# X790        |
| Columns – wide flange                                          | UL# X829        |
| Columns – wide flange alternate                                | UL# X854        |

ACC LEVEL 3 OR EXPANSION REMODEL

University of Utah

Salt Lake City, Utah 84132

Code Review

END OF SECTION 07 8100



## SECTION 07 8413 - PENETRATION FIRESTOPPING

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Penetrations in fire-resistance-rated walls.
2. Penetrations in horizontal assemblies.
3. Penetrations in smoke barriers.

B. Related Sections:

1. Section 07 8443 "Joint Firestopping" for joints in or between fire-resistance-rated construction, at exterior curtain-wall/floor intersections, and in smoke barriers.

#### 1.2 COORDINATION

- A. Coordinate construction of openings and penetrating items to ensure that penetration firestopping systems can be installed according to specified firestopping system design.
- B. Coordinate sizing of sleeves, openings, core-drilled holes, or cut openings to accommodate penetration firestopping systems.

#### 1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Product Schedule: For each penetration firestopping system. Include location, illustration of firestopping system, and design designation of qualified testing and inspecting agency.
1. Engineering Judgments: Where Project conditions require modification to a qualified testing and inspecting agency's illustration for a particular penetration firestopping system, submit illustration, with modifications marked, approved by penetration firestopping system manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly. Obtain approval of authorities having jurisdiction prior to submittal.

## 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For each penetration firestopping system, for tests performed by a qualified testing agency.

## 1.6 CLOSEOUT SUBMITTALS

- A. Installer Certificates: From Installer indicating that penetration firestopping systems have been installed in compliance with requirements and manufacturer's written instructions.

## 1.7 QUALITY ASSURANCE

- A. Installer Qualifications: A firm that has been approved by FM Global according to FM Global 4991, "Approval of Firestop Contractors," or been evaluated by UL and found to comply with its "Qualified Firestop Contractor Program Requirements."

## 1.8 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install penetration firestopping when ambient or substrate temperatures are outside limits permitted by penetration firestopping manufacturers or when substrates are wet because of rain, frost, condensation, or other causes.
- B. Install and cure penetration firestopping per manufacturer's written instructions using natural means of ventilations or, where this is inadequate, forced-air circulation.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics:
  - 1. Perform penetration firestopping system tests by a qualified testing agency acceptable to authorities having jurisdiction.
  - 2. Test per testing standards referenced in "Penetration Firestopping Systems" Article. Provide rated systems complying with the following requirements:
    - a. Penetration firestopping systems shall bear classification marking of a qualified testing agency.
      - 1) UL in its "Fire Resistance Directory."

## 2.2 PENETRATION FIRESTOPPING SYSTEMS

- A. Penetration Firestopping Systems: Systems that resist spread of fire, passage of smoke and other gases, and maintain original fire-resistance rating of construction penetrated. Penetration firestopping systems shall be compatible with one another, with the substrates forming openings, and with penetrating items if any.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. 3M Fire Protection Products.
    - b. Hilti, Inc.
    - c. RectorSeal.
- B. Penetrations in Fire-Resistance-Rated Walls: Penetration firestopping systems with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg.
  - 1. F-Rating: Not less than the fire-resistance rating of constructions penetrated.
- C. Penetrations in Horizontal Assemblies: Penetration firestopping systems with ratings determined per ASTM E 814 or UL 1479, based on testing at a positive pressure differential of 0.01-inch wg.
  - 1. F-Rating: At least one hour, but not less than the fire-resistance rating of constructions penetrated.
  - 2. T-Rating: At least one hour, but not less than the fire-resistance rating of constructions penetrated except for floor penetrations within the cavity of a wall.
  - 3. W-Rating: Provide penetration firestopping systems showing no evidence of water leakage when tested according to UL 1479.
- D. Penetrations in Smoke Barriers: Penetration firestopping systems with ratings determined per UL 1479, based on testing at a positive pressure differential of 0.30-inch wg.
- E. Exposed Penetration Firestopping Systems: Flame-spread and smoke-developed indexes of less than 25 and 450, respectively, per ASTM E 84.
  - 1. Sealant shall have a VOC content of 250 g/L or less.
  - 2. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- F. Accessories: Provide components for each penetration firestopping system that are needed to install fill materials and to maintain ratings required. Use only those components specified by penetration firestopping system manufacturer and approved by qualified testing and inspecting agency for conditions indicated.
  - 1. Permanent forming/damming/backing materials.

2. Substrate primers.
3. Collars.
4. Steel sleeves.

## 2.3 FILL MATERIALS

- A. Latex Sealants: Single-component latex formulations that do not re-emulsify after cure during exposure to moisture.
- B. Firestop Devices: Factory-assembled collars formed from galvanized steel and lined with intumescent material sized to fit specific diameter of penetrant.
- C. Intumescent Composite Sheets: Rigid panels consisting of aluminum-foil-faced intumescent elastomeric sheet bonded to galvanized-steel sheet.
- D. Intumescent Putties: Nonhardening, water-resistant, intumescent putties containing no solvents or inorganic fibers.
- E. Intumescent Wrap Strips: Single-component intumescent elastomeric sheets with aluminum foil on one side.
- F. Pillows/Bags: Reusable heat-expanding pillows/bags consisting of glass-fiber cloth cases filled with a combination of mineral-fiber, water-insoluble expansion agents, and fire-retardant additives. Where exposed, cover openings with steel-reinforcing wire mesh to protect pillows/bags from being easily removed.
- G. Silicone Foams: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.
- H. Silicone Sealants: Single-component, silicone-based, neutral-curing elastomeric sealants.

## 2.4 MIXING

- A. Penetration Firestopping Materials: For those products requiring mixing before application, comply with penetration firestopping system manufacturer's written instructions for accurate proportioning of materials, water (if required), type of mixing equipment, selection of mixer speeds, mixing containers, mixing time, and other items or procedures needed to produce products of uniform quality with optimum performance characteristics for application indicated.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for opening configurations, penetrating items, substrates, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Surface Cleaning: Clean out openings immediately before installing penetration firestopping to comply with manufacturer's written instructions and with the following requirements:
  - 1. Remove from surfaces of opening substrates and from penetrating items foreign materials that could interfere with adhesion of penetration firestopping.
  - 2. Clean opening substrates and penetrating items to produce clean, sound surfaces capable of developing optimum bond with penetration firestopping. Remove loose particles remaining from cleaning operation.
  - 3. Remove laitance and form-release agents from concrete.
- B. Priming: Prime substrates where recommended in writing by manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

### 3.3 INSTALLATION

- A. General: Install penetration firestopping to comply with manufacturer's written installation instructions and published drawings for products and applications indicated.
- B. Install forming materials and other accessories of types required to support fill materials during their application and in the position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.
  - 1. After installing fill materials and allowing them to fully cure, remove combustible forming materials and other accessories not indicated as permanent components of firestopping.
- C. Install fill materials for firestopping by proven techniques to produce the following results:
  - 1. Fill voids and cavities formed by openings, forming materials, accessories, and penetrating items as required to achieve fire-resistance ratings indicated.
  - 2. Apply materials so they contact and adhere to substrates formed by openings and penetrating items.

3. For fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

### 3.4 IDENTIFICATION

- A. Wall Identification: Permanently label walls containing penetration firestopping systems with the words "FIRE AND/OR SMOKE BARRIER - PROTECT ALL OPENINGS," using lettering not less than 3 inches high and with minimum 0.375-inch strokes.
  1. Locate in accessible concealed floor, floor-ceiling, or attic space at 15 feet from end of wall and at intervals not exceeding 30 feet.
- B. Penetration Identification: Identify each penetration firestopping system with legible metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches of penetration firestopping system edge so labels are visible to anyone seeking to remove penetrating items or firestopping systems. Use mechanical fasteners or self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:
  1. The words "Warning - Penetration Firestopping - Do Not Disturb. Notify Building Management of Any Damage."
  2. Contractor's name, address, and phone number.
  3. Designation of applicable testing and inspecting agency.
  4. Date of installation.
  5. Manufacturer's name.
  6. Installer's name.

### 3.5 FIELD QUALITY CONTROL

- A. Owner will engage a qualified testing agency to perform tests and inspections according to ASTM E 2174.
- B. Where deficiencies are found or penetration firestopping system is damaged or removed because of testing, repair or replace penetration firestopping system to comply with requirements.
- C. Proceed with enclosing penetration firestopping systems with other construction only after inspection reports are issued and installations comply with requirements.

### 3.6 CLEANING AND PROTECTION

- A. Clean off excess fill materials adjacent to openings as the Work progresses by methods and with cleaning materials that are approved in writing by penetration firestopping manufacturers and that do not damage materials in which openings occur.

- B. Provide final protection and maintain conditions during and after installation that ensure that penetration firestopping is without damage or deterioration at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, immediately cut out and remove damaged or deteriorated penetration firestopping and install new materials to produce systems complying with specified requirements.

### 3.7 PENETRATION FIRESTOPPING SCHEDULE

- A. Where UL-classified systems are indicated, they refer to system numbers in UL's "Fire Resistance Directory" under product Category XHEZ.
- A. Firestopping with No Penetrating Items:
  - 1. UL-Classified Systems: C-AJ- F-A-W-L- 0001-0999.
  - 2. F-Rating: 1 or 2 hours, as indicated.
  - 3. T-Rating: 1 or 2 hours, as indicated.
  - 4. W-Rating: No leakage of water at completion of water leakage testing.
  - 5. Type of Fill Materials: As required to achieve rating.
- B. Firestopping for Metallic Pipes, Conduit, or Tubing:
  - 1. UL-Classified Systems: C-AJ- F-A- W-L- 1001-1999.
  - 2. F-Rating: 1 or 2 hours, as indicated.
  - 3. T-Rating: 1 or 2 hours, as indicated.
  - 4. W-Rating: No leakage of water at completion of water leakage testing.
  - 5. Type of Fill Materials: As required to achieve rating.
- C. Firestopping for Nonmetallic Pipe, Conduit, or Tubing:
  - 1. UL-Classified Systems: C-AJ- F-A- W-L- 2001-2999.
  - 1. F-Rating: 1 or 2 hours, as indicated.
  - 2. T-Rating: 1 or 2 hours, as indicated.
  - 3. W-Rating: No leakage of water at completion of water leakage testing.
  - 4. Type of Fill Materials: As required to achieve rating.
- D. Firestopping for Electrical Cables:
  - 1. UL-Classified Systems: C-AJ- F-A- W-L- 3001-3999.
  - 1. F-Rating: 1 or 2 hours, as indicated.
  - 2. T-Rating: 1 or 2 hours, as indicated.
  - 3. W-Rating: No leakage of water at completion of water leakage testing.
  - 4. Type of Fill Materials: As required to achieve rating.
- E. Firestopping for Cable Trays with Electric Cables:
  - 1. UL-Classified Systems: C-AJ- F-A- W-L- 4001-4999.
  - 1. F-Rating: 1 or 2 hours, as indicated.
  - 2. T-Rating: 1 or 2 hours, as indicated.

3. W-Rating: No leakage of water at completion of water leakage testing.
4. Type of Fill Materials: As required to achieve rating.

F. Firestopping for Insulated Pipes:

1. UL-Classified Systems: C-AJ- F-A- W-L- 5001-5999.
1. F-Rating: 1 or 2 hours, as indicated.
2. T-Rating: 1 or 2 hours, as indicated.
3. Type of Fill Materials: As required to achieve rating.
4. Firestopping for Miscellaneous Electrical Penetrants:

G. Firestopping for Miscellaneous Electrical Penetrants

1. UL-Classified Systems: C-AJ- F-A- W-L- 6001-6999.
2. F-Rating: 1 or 2 hours, as indicated.
3. T-Rating: 1 or 2 hours, as indicated.
4. W-Rating: No leakage of water at completion of water leakage testing.
5. Type of Fill Materials: As required to achieve rating.

H. Firestopping for Miscellaneous Mechanical Penetrants:

1. UL-Classified Systems: C-AJ- F-A- W-L- 7001-7999.
1. F-Rating: 1 or 2 hours, as indicated.
2. T-Rating: 1 or 2 hours, as indicated.
3. W-Rating: No leakage of water at completion of water leakage testing.
4. Type of Fill Materials: As required to achieve rating.

I. Firestopping for Groupings of Penetrants:

1. UL-Classified Systems: C-AJ- F-A-W-L- 8001-8999.
1. F-Rating: 1 or 2 hours, as indicated.
2. T-Rating: 1 or 2 hours, as indicated.
3. W-Rating: No leakage of water at completion of water leakage testing.
4. Type of Fill Materials: As required to achieve rating.

END OF SECTION 07 8413



## SECTION 07 8443 - JOINT FIRESTOPPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Joints in or between fire-resistance-rated constructions.
  - 2. Joints in smoke barriers.
- B. Related Requirements:
  - 1. Section 07 8413 "Penetration Firestopping" for penetrations in fire-resistance-rated walls, horizontal assemblies, and smoke barriers.

#### 1.3 COORDINATION

- A. Coordinate construction of joints to ensure that joint firestopping systems can be installed according to specified firestopping system design.
- B. Coordinate sizing of joints to accommodate joint firestopping systems.

#### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Product Schedule: For each joint firestopping system. Include location, illustration of firestopping system, and design designation of qualified testing agency.
  - 1. Engineering Judgments: Where Project conditions require modification to a qualified testing agency's illustration for a particular joint firestopping system condition, submit illustration, with modifications marked, approved by joint firestopping system

manufacturer's fire-protection engineer as an engineering judgment or equivalent fire-resistance-rated assembly.

## 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For each joint firestopping system, for tests performed by a qualified testing agency.

## 1.7 CLOSEOUT SUBMITTALS

- A. Installer Certificates: From Installer indicating that joint firestopping systems have been installed in compliance with requirements and manufacturer's written instructions.

## 1.8 QUALITY ASSURANCE

- A. Installer Qualifications: A firm that has been approved by FM Global according to FM Global 4991, "Approval of Firestop Contractors," or been evaluated by UL and found to comply with UL's "Qualified Firestop Contractor Program Requirements."

## 1.9 PROJECT CONDITIONS

- A. Environmental Limitations: Do not install joint firestopping systems when ambient or substrate temperatures are outside limits permitted by joint firestopping system manufacturers or when substrates are wet due to rain, frost, condensation, or other causes.
- B. Install and cure joint firestopping systems per manufacturer's written instructions using natural means of ventilation or, where this is inadequate, forced-air circulation.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics:
  - 1. Perform joint firestopping system tests by a qualified testing agency acceptable to authorities having jurisdiction.
  - 2. Test per testing standards referenced in "Joint Firestopping Systems" Article. Provide rated systems complying with the following requirements:
    - a. Joint firestopping systems shall bear classification marking of a qualified testing agency.

- 1) UL in its "Fire Resistance Directory."

## 2.2 JOINT FIRESTOPPING SYSTEMS

- A. Joint Firestopping Systems: Systems that resist spread of fire, passage of smoke and other gases, and maintain original fire-resistance rating of assemblies in or between which joint firestopping systems are installed. Joint firestopping systems shall accommodate building movements without impairing their ability to resist the passage of fire and hot gases.
- B. Joints in or between Fire-Resistance-Rated Construction: Provide joint firestopping systems with ratings determined per ASTM E 1966 or UL 2079.
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. 3M Fire Protection Products.
    - b. Hilti, Inc.
    - c. Nelson Firestop; a brand of Emerson Industrial Automation.
    - d. RectorSeal.
    - e. ROXUL.
    - f. Thermafiber, Inc.; an Owens Corning company.
  2. Fire-Resistance Rating: Equal to or exceeding the fire-resistance rating of the wall, floor, or roof in or between which it is installed.
- C. Joints in Smoke Barriers: Provide fire-resistive joint systems with ratings determined per UL 2079 based on testing at a positive pressure differential of 0.30-inch wg.
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. 3M Fire Protection Products.
    - b. Hilti, Inc.
    - c. Nelson Firestop; a brand of Emerson Industrial Automation.
    - d. RectorSeal.
    - e. ROXUL.
    - f. Thermafiber, Inc.; an Owens Corning company.
  2. L-Rating: Not exceeding 5.0 cfm/ft. of joint at both ambient and elevated temperatures.
- D. Exposed Joint Firestopping Systems: Flame-spread and smoke-developed indexes of less than 25 and 450, respectively, as determined per ASTM E 84.
  1. Sealant shall have a VOC content of 250 g/L or less.
  2. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

- E. Accessories: Provide components of fire-resistive joint systems, including primers and forming materials, that are needed to install elastomeric fill materials and to maintain ratings required. Use only components specified by joint firestopping system manufacturer and approved by the qualified testing agency for conditions indicated.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions, with Installer present, for compliance with requirements for joint configurations, substrates, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Surface Cleaning: Before installing fire-resistive joint systems, clean joints immediately to comply with fire-resistive joint system manufacturer's written instructions and the following requirements:
  - 1. Remove from surfaces of joint substrates foreign materials that could interfere with adhesion of elastomeric fill materials or compromise fire-resistive rating.
  - 2. Clean joint substrates to produce clean, sound surfaces capable of developing optimum bond with elastomeric fill materials. Remove loose particles remaining from cleaning operation.
  - 3. Remove laitance and form-release agents from concrete.
- B. Prime substrates where recommended in writing by joint firestopping system manufacturer using that manufacturer's recommended products and methods. Confine primers to areas of bond; do not allow spillage and migration onto exposed surfaces.

### 3.3 INSTALLATION

- A. General: Install fire-resistive joint systems to comply with manufacturer's written installation instructions and published drawings for products and applications indicated.
- B. Install forming materials and other accessories of types required to support elastomeric fill materials during their application and in position needed to produce cross-sectional shapes and depths required to achieve fire ratings indicated.
  - 1. After installing elastomeric fill materials and allowing them to fully cure, remove combustible forming materials and other accessories not indicated as permanent components of fire-resistive joint system.

- C. Install elastomeric fill materials for fire-resistive joint systems by proven techniques to produce the following results:
  - 1. Elastomeric fill voids and cavities formed by joints and forming materials as required to achieve fire-resistance ratings indicated.
  - 2. Apply elastomeric fill materials so they contact and adhere to substrates formed by joints.
  - 3. For elastomeric fill materials that will remain exposed after completing the Work, finish to produce smooth, uniform surfaces that are flush with adjoining finishes.

### 3.4 IDENTIFICATION

- A. Joint Identification: Identify joint firestopping systems with legible metal or plastic labels. Attach labels permanently to surfaces adjacent to and within 6 inches of joint edge so labels are visible to anyone seeking to remove or joint firestopping system. Use mechanical fasteners or self-adhering-type labels with adhesives capable of permanently bonding labels to surfaces on which labels are placed. Include the following information on labels:
  - 1. The words "Warning - Joint Firestopping - Do Not Disturb. Notify Building Management of Any Damage."
  - 2. Contractor's name, address, and phone number.
  - 3. Designation of applicable testing agency.
  - 4. Date of installation.
  - 5. Manufacturer's name.
  - 6. Installer's name.

### 3.5 FIELD QUALITY CONTROL

- A. Inspecting Agency: Owner will engage a qualified testing agency to perform tests and inspections according to ASTM E 2393.
- B. Where deficiencies are found or joint firestopping systems are damaged or removed due to testing, repair or replace joint firestopping systems so they comply with requirements.
- C. Proceed with enclosing joint firestopping systems with other construction only after inspection reports are issued and installations comply with requirements.

### 3.6 CLEANING AND PROTECTION

- A. Clean off excess elastomeric fill materials adjacent to joints as the Work progresses by methods and with cleaning materials that are approved in writing by joint firestopping system manufacturers and that do not damage materials in which joints occur.
- B. Provide final protection and maintain conditions during and after installation that ensure joint firestopping systems are without damage or deterioration at time of Substantial Completion. If damage or deterioration occurs despite such protection, cut out and remove damaged or

deteriorated fire-resistive joint systems immediately and install new materials to produce fire-resistive joint systems complying with specified requirements.

### 3.7 JOINT FIRESTOPPING SYSTEM SCHEDULE

- A. Where UL-classified systems are indicated, they refer to system numbers in UL's "Fire Resistance Directory" under product Category XHBN or Category XHDG.
- B. Head-of-Wall, Fire-Resistive Joint Firestopping Systems:
  - a. 0000-0999 for joints less than or equal to 2 inches.
  - b. 1000-1999 for joints greater than 2 inches and less than or equal to 6 inches.
  - 1. Assembly Rating: 1 hour or 2 hours as applicable to match rating of wall.
  - 2. Nominal Joint Width: As indicated.
- C. Bottom-of-Wall, Joint Firestopping Systems:
  - 1. UL-Classified Systems: BW-D-0000-0999.
  - 2. Assembly Rating: 1 hour or 2 hours as applicable to match rating of wall
  - 3. Nominal Joint Width: As indicated.

END OF SECTION 07 8443

## SECTION 07 9100 - PREFORMED JOINT SEALS AND MULLION TRIM CAPS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Preformed, foam joint seals.
  - 2. Sound barrier mullion trim caps for sound transmission control where interior partitions meet curtain wall

#### 1.3 COORDINATION

- A. Coordinate installation of mullion trim caps with adjacent construction to ensure that wall assemblies and joint sealants are protected against damage from the effects of age, corrosion, and other causes of deterioration.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product, including finishing materials.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for sound barrier wall end cap system.
- B. Shop Drawings: Show fabrication and installation details for wall end cap system.
  - 1. Include plans, elevations, component details, and attachment details.
  - 2. Include typical dimensioned cross-section(s) at the location where drywall partition terminates at the perimeter curtain wall, indicating materials and profiles of each wall end cap system member, fittings, joinery, finishes, fasteners, anchorages, and accessory items.
- C. Samples for Verification:
  - 1. Preformed Seals: For each type and color of preformed joint seal required, provide Samples with joint seals in 1/2-inch-wide joints formed between two 6-inch-long strips of material matching the appearance of exposed surfaces adjacent to joint seals.

2. Size: 6-inch sound barrier mullion trim cap sample and 2-inch by 3-1/2-inch custom color.

D. Preformed Joint Seal and Mullion Trim Cap Schedule: Include the following information:

1. Joint seal location and designation.
2. Joint width and movement capability.
3. Joint seal manufacturer and product name.
4. Joint seal color.

1.5 INFORMATIONAL SUBMITTALS

A. Qualification Data: For Installer.

B. Product Test Reports:

1. For each preformed joint seal for tests performed by a qualified testing agency.
2. For each sound barrier mullion trim cap assembly, for ASTM E 90 tests performed by a qualified third-party testing agency.

C. Warranties: For special warranties.

1.6 DELIVERY, STORAGE, AND HANDLING

- A. Do not deliver sound barrier mullion trim caps until spaces to receive them are clean, dry, and ready for their installation.
- B. Store sound barrier mullion trim caps in original undamaged packaging inside well-ventilated area protected from weather, moisture, soiling, extreme temperatures, and humidity.

1.7 WARRANTY

A. Preformed Seal Special Warranty: Installer agrees to repair or replace preformed joint seals that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Two years from date of Substantial Completion.

B. Special Manufacturer's Warranty: Manufacturer agrees to furnish preformed joint seals to repair or replace those that do not comply with performance and other requirements specified in this Section within specified warranty period.

1. Warranty Period: Five years from date of Substantial Completion.

C. Trim Cap Manufacturer's Warranty: Manufacturer agrees to repair or replace sound barrier mullion trim caps that fail in materials or workmanship within specified warranty period.



1. Warranty Period: Ten years limited warranty from date of Substantial Completion.
2. Limited warranty does not cover adjacent products or improper installation.

## 1.8 FIELD CONDITIONS

- A. Field Measurements: Verify actual locations of walls and other construction contiguous with mullion trim cap assembly by field measurements before fabrication and indicate measurements on Shop Drawings.

## PART 2 - PRODUCTS

### 2.1 PREFORMED, FOAM JOINT SEALS

- A. Preformed, Foam Joint Seals: Manufacturer's standard joint seal manufactured from urethane or EVA (ethylene vinyl acetate) foam with minimum density of 10 lb/cu. ft. and impregnated with a nondrying, water-repellent agent. Factory produce in precompressed sizes in roll or stick form to fit joint widths based on design criteria indicated, with factory- or field-applied adhesive for bonding to substrates.
  1. Basis of Design: EMSEAL Joint Systems, Ltd.; Quiet Joint
    - a. Subject to compliance with requirements, provide Basis of Design product or an equivalent product by one of the following manufacturers:
      - 1) BASF Corp. - Watson Bowman Acme Corp.
      - 2) MM Systems Corporation.
      - 3) Nystrom, Inc.
  2. Design Criteria:
    - a. Nominal Joint Width: Varies, see drawings.
    - b. STC Rating: Not less than STC 53.
  3. Joint Seal Color: Grey.

### 2.2 SOUND BARRIER MULLION TRIM CAP

- A. General: Provide sound barrier mullion trim caps of design, basic profile, materials, and operation indicated. Provide units with capability to accommodate variations in adjacent surfaces.
  1. Furnish units in lengths of sufficient additional length to allow for field trimming to required length to match variations in construction tolerances of adjacent systems.

- B. Basis of Design Product: Subject to compliance with requirements, provide the following product, or equivalent sound barrier system complying with requirements and approved by Architect prior to bid.
1. Product: MULL-it-OVER Products; Classic Sound Barrier Mullion Trim Cap with 1-Hour Fire Rating.
  2. Application: Fills gap between end of partition and exterior glass or mullion.
  3. Design:
    - a. STC: 60.
    - b. Fire-Resistance Rating: Certified to UL/ULC 2079/S115 testing. UL Assembly No. WW-S-1039.
      - 1) Rating: Not less than that of adjacent construction.
    - c. Snap Cover: Snap-on fastener cover.

## 2.3 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by preformed-joint-seal manufacturer for joint substrates indicated.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to preformed joint seal manufacturer, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces, and formulated to promote best adhesion to joint substrates.
- C. Fasteners: Fabricated from same basic metal and alloy as fastened metal unless otherwise indicated. Do not use metals that are incompatible with materials joined.
1. Self-Tapping or appropriate threaded fastener.
  2. Compatible with materials in contact with fasteners and not causing galvanic corrosion.
  3. Provide concealed fasteners for interconnecting mullion trim cap items and for attaching them to other work.

## 2.4 FABRICATION

- A. Coordinate dimensions and attachment methods of sound barrier mullion trim cap assembly with those of adjoining construction to produce integrated assemblies with closely fitting joints and with edges and surfaces aligned unless otherwise indicated.
- B. Form metal to profiles indicated, in maximum lengths to minimize joints. Produce flat, flush surfaces without cracking or grain separation at bends.
- C. Ship extrusions and generic profiles in custom lengths as required to meet project requirements or in standard incremental foot lengths and cut to exact length on jobsite.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine joints indicated to receive preformed joint seals, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting preformed-joint seal performance.
- B. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- C. Examine walls and adjacent curtain wall for suitable conditions where sound barrier wall end cap will be installed.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing preformed joint seals to comply with preformed joint seal manufacturer's written instructions and the following requirements:
  - 1. Remove all foreign material from joint substrates that could interfere with adhesion of preformed joint seal, including dust, paints (except for permanent protective coatings tested and approved for seal adhesion and compatibility by seal manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
  - 2. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint seals. Nonporous joint substrates include the following:
    - a. Metal.
- B. Joint Priming: Prime joint substrates where recommended by preformed joint seal manufacturer or as indicated by tests or prior experience. Apply primer to comply with joint seal manufacturer's written instructions. Confine primers to areas of joint seal bond; do not allow spillage or migration onto adjoining surfaces.

### 3.3 FOAM JOINT INSTALLATION

- A. General: Comply with preformed joint seal manufacturer's written installation instructions for products and applications indicated unless more stringent requirements apply.
- B. Installation of Preformed, Foam Joint Seals:
  - 1. Install each length of seal immediately after removing protective wrapping.

2. Firmly secure compressed joint seals to joint gap side to obtain full bond using exposed pressure-sensitive adhesive or field-applied adhesive as recommended by manufacturer.
3. Do not pull or stretch material. Produce seal continuity at splices, ends, turns, and intersections of joints.
4. For applications at low ambient temperatures, heat foam joint seal material in compliance with manufacturer's written instructions.

### 3.4 TRIM CAP INSTALLATION

- A. Measure and cut sound barrier wall end cap to proper lengths.
- B. Notch around horizontal mullions, sills, or other obstructions leaving appropriate gap for differential movement between the sound barrier wall end cap and the obstruction.
- C. Apply continuous bead of acoustical sealant to the unexposed side of extruded aluminum surface that will be in contact with the drywall edge.
- D. Place sound barrier wall end cap on the vertical surface of the drywall partition wall and loosely install fasteners in the top and bottom slotted holes of the wall end cap.
- E. Plumb the wall end cap leaving recommended gap spacing between the interior glass surface and the wall end cap. Foam gasket to be in contact with glass.
- F. Tighten top and bottom fasteners to secure end cap.
- G. Install additional fasteners at 12 inches on center, minimum.
- H. Install snap cover to conceal fasteners.
- I. Apply color matched sealant at joints of dissimilar materials as desired.

### 3.5 CLEANING

- A. After work is complete in adjacent areas, clean exposed surfaces with suitable cleaner that will not harm or attack the finish.
- B. Touchup Painting: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint are specified in Section 09 9123 "Interior Painting."

### 3.6 PROTECTION

- A. Protect sound barrier wall end caps from damage during installation, general construction activities, and until turnover of structure.
- B. Protect preformed joint seals from damage resulting from construction operations or other causes so seals are without deterioration or damage at time of Substantial Completion. If,

despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated seals immediately so installations with repaired areas are indistinguishable from original work.

END OF SECTION 07 9100

## SECTION 07 9200 - JOINT SEALANTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Silicone joint sealants.
  - 2. Nonstaining silicone joint sealants.
  - 3. Urethane joint sealants.
  - 4. Mildew-resistant joint sealants.
  - 5. Latex joint sealants.
  - 6. Acoustical joint sealants.

#### 1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each joint-sealant product.
- B. Samples for Initial Selection: Manufacturer's color charts consisting of strips of cured sealants showing the full range of colors available for each product exposed to view.
- C. Samples for Verification: For each kind and color of joint sealant required, provide Samples with joint sealants in 1/2-inch- wide joints formed between two 6-inch- long strips of material matching the appearance of exposed surfaces adjacent to joint sealants.
- D. Joint-Sealant Schedule: Include the following information:
  - 1. Joint-sealant application, joint location, and designation.
  - 2. Joint-sealant manufacturer and product name.
  - 3. Joint-sealant formulation.
  - 4. Joint-sealant color.

## 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified testing agency.
- B. Product Test Reports: For each kind of joint sealant, for tests performed by manufacturer and witnessed by a qualified testing agency.
- C. Preconstruction Laboratory Test Reports: From sealant manufacturer, indicating the following:
  - 1. Materials forming joint substrates and joint-sealant backings have been tested for compatibility and adhesion with joint sealants.
  - 2. Interpretation of test results and written recommendations for primers and substrate preparation are needed for adhesion.
- D. Preconstruction Field-Adhesion-Test Reports: Indicate which sealants and joint preparation methods resulted in optimum adhesion to joint substrates based on testing specified in "Preconstruction Testing" Article.
- E. Field-Adhesion-Test Reports: For each sealant application tested.
- F. Sample Warranties: For special warranties.

## 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An authorized representative who is trained and approved by manufacturer.
- B. Product Testing: Test joint sealants using a qualified testing agency.
  - 1. Testing Agency Qualifications: Qualified according to ASTM C 1021 to conduct the testing indicated.
- C. Mockups: Install sealant in mockups of assemblies specified in other Sections that are indicated to receive joint sealants specified in this Section. Use materials and installation methods specified in this Section.

## 1.7 PRECONSTRUCTION TESTING

- A. Preconstruction Laboratory Testing: Submit to joint-sealant manufacturers, for testing indicated below, samples of materials that will contact or affect joint sealants.
  - 1. Adhesion Testing: Use ASTM C 794 to determine whether priming and other specific joint preparation techniques are required to obtain rapid, optimum adhesion of joint sealants to joint substrates.
  - 2. Compatibility Testing: Use ASTM C 1087 to determine sealant compatibility when in contact with glazing and gasket materials.

3. Stain Testing: Use ASTM C 1248 to determine stain potential of sealant when in contact with masonry substrates.
  4. Submit manufacturer's recommended number of pieces of each type of material, including joint substrates, joint-sealant backings, and miscellaneous materials.
  5. Schedule sufficient time for testing and analyzing results to prevent delaying the Work.
  6. For materials failing tests, obtain joint-sealant manufacturer's written instructions for corrective measures, including use of specially formulated primers.
  7. Testing will not be required if joint-sealant manufacturers submit data that are based on previous testing, not older than 24 months, of sealant products for adhesion to, staining of, and compatibility with joint substrates and other materials matching those submitted.
- B. Preconstruction Field-Adhesion Testing: Before installing sealants, field test their adhesion to Project joint substrates as follows:
1. Locate test joints where indicated on Project or, if not indicated, as directed by Architect.
  2. Conduct field tests for each kind of sealant and joint substrate.
  3. Notify Architect seven days in advance of dates and times when test joints will be erected.
  4. Arrange for tests to take place with joint-sealant manufacturer's technical representative present.
    - a. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1.1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.
      - 1) For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.
  5. Report whether sealant failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. For sealants that fail adhesively, retest until satisfactory adhesion is obtained.
  6. Evaluation of Preconstruction Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing, in absence of other indications of noncompliance with requirements, will be considered satisfactory. Do not use sealants that fail to adhere to joint substrates during testing.

## 1.8 FIELD CONDITIONS

- A. Do not proceed with installation of joint sealants under the following conditions:
1. When ambient and substrate temperature conditions are outside limits permitted by joint-sealant manufacturer or are below 40 deg F.
  2. When joint substrates are wet.
  3. Where joint widths are less than those allowed by joint-sealant manufacturer for applications indicated.
  4. Where contaminants capable of interfering with adhesion have not yet been removed from joint substrates.



## 1.9 WARRANTY

- A. Special Installer's Warranty: Installer agrees to provide labor and materials required to repair or replace joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
  - 1. Warranty Period: Two years from date of Substantial Completion.
- B. Special Manufacturer's Warranty: Manufacturer agrees to furnish joint sealants to repair or replace those joint sealants that do not comply with performance and other requirements specified in this Section within specified warranty period.
  - 1. Warranty Period: Five years from date of Substantial Completion.
- C. Special warranties specified in this article exclude deterioration or failure of joint sealants from the following:
  - 1. Movement of the structure caused by stresses on the sealant exceeding sealant manufacturer's written specifications for sealant elongation and compression.
  - 2. Disintegration of joint substrates from causes exceeding design specifications.
  - 3. Mechanical damage caused by individuals, tools, or other outside agents.
  - 4. Changes in sealant appearance caused by accumulation of dirt or other atmospheric contaminants.

## PART 2 - PRODUCTS

### 2.1 JOINT SEALANTS, GENERAL

- A. Compatibility: Provide joint sealants, backings, and other related materials that are compatible with one another and with joint substrates under conditions of service and application, as demonstrated by joint-sealant manufacturer, based on testing and field experience.
- B. VOC Content of Interior Sealants: Sealants and sealant primers used inside the weatherproofing system shall comply with the following:
  - 1. Architectural sealants shall have a VOC content of 250 g/L or less.
  - 2. Sealants and sealant primers for nonporous substrates shall have a VOC content of 250 g/L or less.
  - 3. Sealants and sealant primers for nonporous substrates shall have a VOC content of 775 g/L or less.
  - 4. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

- C. Colors of Exposed Joint Sealants: As selected by Architect from manufacturer's full range. At areas where two varying colors abut, provide a clear joint. At areas where the same colors abut, provide a color matched caulk. Verify conditions with Architect before proceeding.

## 2.2 URETHANE JOINT SEALANTS

- A. Urethane, S, NS, 25, NT: Single-component, nonsag, nontraffic-use, plus 25 percent and minus 25 percent movement capability, urethane joint sealant; ASTM C 920, Type S, Grade NS, Class 25, Use NT.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. BASF Corporation; Construction Systems; MasterSeal CR 195 (Pre-2014: Sonolastic Ultra).
    - b. Bostik, Inc; Chem-Calk 915.
    - c. Sika Corporation; Joint Sealants; Sikaflex Textured Sealant.
- B. Urethane, S, P, 25, T, NT: Single-component, pourable, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, urethane joint sealant; ASTM C 920, Type S, Grade P, Class 25, Uses T and NT.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. BASF Corporation; Construction Systems; MasterSeal SL 1 (Pre-2014: Sonolastic SL1).
    - b. Pecora Corporation; NR-201.
    - c. Polymeric Systems, Inc; Flexiprene 952.
- C. Urethane, M, P, 25, T, NT: Multicomponent, pourable, plus 25 percent and minus 25 percent movement capability, traffic- and nontraffic-use, urethane joint sealant; ASTM C 920, Type M, Grade P, Class 25, Uses T and NT.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. BASF Corporation; Construction Systems; MasterSeal SL 2 (Pre-2014: Sonolastic SL2).
    - b. Bostik, Inc; Chem-Calk 555-SL.
    - c. Pecora Corporation; Urexpan NR 200.
    - d. Sika Corporation; Joint Sealants; Sikaflex 2c SL.

## 2.3 MILDEW-RESISTANT JOINT SEALANTS

- A. Mildew-Resistant Joint Sealants: Formulated for prolonged exposure to humidity with fungicide to prevent mold and mildew growth.

- B. Silicone, Mildew Resistant, Acid Curing, S, NS, 25, NT: Mildew-resistant, single-component, nonsag, plus 25 percent and minus 25 percent movement capability, nontraffic-use, acid-curing silicone joint sealant; ASTM C 920, Type S, Grade NS, Class 25, Use NT.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Dow Corning Corporation; DOW CORNING® 786 SILICONE SEALANT -.
  - b. GE Construction Sealants; Momentive Performance Materials Inc.; SCS1700 Sanitary.
  - c. Pecora Corporation; Pecora 860.

## 2.4 LATEX JOINT SEALANTS

- A. Acrylic Latex: Acrylic latex or siliconized acrylic latex, ASTM C 834, Type OP, Grade NF.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Franklin International; Titebond Painter's Plus Caulk.
  - b. May National Associates, Inc.; a subsidiary of Sika Corporation; Bondaflex Sil-A 700.
  - c. Pecora Corporation; AC-20.

## 2.5 ACOUSTICAL JOINT SEALANTS

- A. Acoustical Sealant for Exposed and Concealed Joints: Manufacturer's standard nonsag, paintable, nonstaining latex acoustical sealant complying with ASTM C 834.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Accumetric LLC; BOSS 826 Acoustical Sound Sealant.
  - b. Franklin International; Titebond GREENchoice Professional Acoustical Smoke & Sound Sealant.
  - c. GE Construction Sealants; Momentive Performance Materials Inc.; RCS20 Acoustical.
  - d. Grabber Construction Products; Acoustical Sealant GSC.
  - e. Pecora Corporation; AC-20 FTR or AIS-919.
  - f. USG Corporation; SHEETROCK
2. Colors of Exposed Acoustical Joint Sealants: As selected by Architect from manufacturer's full range of colors.

## 2.6 JOINT-SEALANT BACKING

- A. Sealant Backing Material, General: Nonstaining; compatible with joint substrates, sealants, primers, and other joint fillers; and approved for applications indicated by sealant manufacturer based on field experience and laboratory testing.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Adfast; Adseal BR 2600.
  - b. Alcot Plastics Ltd.; ALCOT Standard Backer Rod.
  - c. BASF Corporation; Construction Systems; MasterSeal 920 & 921(Pre-2014: Sonolastic Backer Rod).
- B. Cylindrical Sealant Backings: ASTM C 1330, Type C (closed-cell material with a surface skin), and of size and density to control sealant depth and otherwise contribute to producing optimum sealant performance.
- C. Bond-Breaker Tape: Polyethylene tape or other plastic tape recommended by sealant manufacturer for preventing sealant from adhering to rigid, inflexible joint-filler materials or joint surfaces at back of joint. Provide self-adhesive tape where applicable.

## 2.7 MISCELLANEOUS MATERIALS

- A. Primer: Material recommended by joint-sealant manufacturer where required for adhesion of sealant to joint substrates indicated, as determined from preconstruction joint-sealant-substrate tests and field tests.
- B. Cleaners for Nonporous Surfaces: Chemical cleaners acceptable to manufacturers of sealants and sealant backing materials, free of oily residues or other substances capable of staining or harming joint substrates and adjacent nonporous surfaces in any way, and formulated to promote optimum adhesion of sealants to joint substrates.
- C. Masking Tape: Nonstaining, nonabsorbent material compatible with joint sealants and surfaces adjacent to joints.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine joints indicated to receive joint sealants, with Installer present, for compliance with requirements for joint configuration, installation tolerances, and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Surface Cleaning of Joints: Clean out joints immediately before installing joint sealants to comply with joint-sealant manufacturer's written instructions and the following requirements:

1. Remove all foreign material from joint substrates that could interfere with adhesion of joint sealant, including dust, paints (except for permanent, protective coatings tested and approved for sealant adhesion and compatibility by sealant manufacturer), old joint sealants, oil, grease, waterproofing, water repellents, water, surface dirt, and frost.
  2. Clean porous joint substrate surfaces by brushing, grinding, mechanical abrading, or a combination of these methods to produce a clean, sound substrate capable of developing optimum bond with joint sealants. Remove loose particles remaining after cleaning operations above by vacuuming or blowing out joints with oil-free compressed air. Porous joint substrates include the following:
    - a. Concrete.
    - b. Unglazed surfaces of ceramic tile.
  3. Remove laitance and form-release agents from concrete.
  4. Clean nonporous joint substrate surfaces with chemical cleaners or other means that do not stain, harm substrates, or leave residues capable of interfering with adhesion of joint sealants. Nonporous joint substrates include the following:
    - a. Metal.
    - b. Glass.
    - c. Porcelain enamel.
    - d. Glazed surfaces of ceramic tile.
- B. Joint Priming: Prime joint substrates where recommended by joint-sealant manufacturer or as indicated by preconstruction joint-sealant-substrate tests or prior experience. Apply primer to comply with joint-sealant manufacturer's written instructions. Confine primers to areas of joint-sealant bond; do not allow spillage or migration onto adjoining surfaces.
- C. Masking Tape: Use masking tape where required to prevent contact of sealant or primer with adjoining surfaces that otherwise would be permanently stained or damaged by such contact or by cleaning methods required to remove sealant smears. Remove tape immediately after tooling without disturbing joint seal.

### 3.3 INSTALLATION OF JOINT SEALANTS

- A. General: Comply with joint-sealant manufacturer's written installation instructions for products and applications indicated, unless more stringent requirements apply.
- B. Sealant Installation Standard: Comply with recommendations in ASTM C 1193 for use of joint sealants as applicable to materials, applications, and conditions indicated.
- C. Install sealant backings of kind indicated to support sealants during application and at position required to produce cross-sectional shapes and depths of installed sealants relative to joint widths that allow optimum sealant movement capability.
  1. Do not leave gaps between ends of sealant backings.
  2. Do not stretch, twist, puncture, or tear sealant backings.

3. Remove absorbent sealant backings that have become wet before sealant application, and replace them with dry materials.
- D. Install bond-breaker tape behind sealants where sealant backings are not used between sealants and backs of joints.
- E. Install sealants using proven techniques that comply with the following and at the same time backings are installed:
  1. Place sealants so they directly contact and fully wet joint substrates.
  2. Completely fill recesses in each joint configuration.
  3. Produce uniform, cross-sectional shapes and depths relative to joint widths that allow optimum sealant movement capability.
- F. Tooling of Nonsag Sealants: Immediately after sealant application and before skinning or curing begins, tool sealants according to requirements specified in subparagraphs below to form smooth, uniform beads of configuration indicated; to eliminate air pockets; and to ensure contact and adhesion of sealant with sides of joint.
  1. Remove excess sealant from surfaces adjacent to joints.
  2. Use tooling agents that are approved in writing by sealant manufacturer and that do not discolor sealants or adjacent surfaces.
  3. Provide concave joint profile per Figure 8A in ASTM C 1193 unless otherwise indicated.

### 3.4 INSTALLATION OF ACOUSTICAL JOINT SEALANTS

- A. Comply with acoustical joint-sealant manufacturer's written installation instructions unless more stringent requirements apply.

### 3.5 FIELD QUALITY CONTROL

- A. Field-Adhesion Testing: Field test joint-sealant adhesion to joint substrates as follows:
  1. Extent of Testing: Test completed and cured sealant joints as follows:
    - a. Perform 10 tests for the first 1000 feet of joint length for each kind of sealant and joint substrate.
    - b. Perform one test for each 1000 feet of joint length thereafter or one test per each floor per elevation.
  2. Test Method: Test joint sealants according to Method A, Field-Applied Sealant Joint Hand Pull Tab, in Appendix X1 in ASTM C 1193 or Method A, Tail Procedure, in ASTM C 1521.
    - a. For joints with dissimilar substrates, verify adhesion to each substrate separately; extend cut along one side, verifying adhesion to opposite side. Repeat procedure for opposite side.

3. Inspect tested joints and report on the following:
  - a. Whether sealants filled joint cavities and are free of voids.
  - b. Whether sealant dimensions and configurations comply with specified requirements.
  - c. Whether sealants in joints connected to pulled-out portion failed to adhere to joint substrates or tore cohesively. Include data on pull distance used to test each kind of product and joint substrate. Compare these results to determine if adhesion complies with sealant manufacturer's field-adhesion hand-pull test criteria.
4. Record test results in a field-adhesion-test log. Include dates when sealants were installed, names of persons who installed sealants, test dates, test locations, whether joints were primed, adhesion results and percent elongations, sealant material, sealant configuration, and sealant dimensions.
5. Repair sealants pulled from test area by applying new sealants following same procedures used originally to seal joints. Ensure that original sealant surfaces are clean and that new sealant contacts original sealant.

- B. Evaluation of Field-Adhesion-Test Results: Sealants not evidencing adhesive failure from testing or noncompliance with other indicated requirements will be considered satisfactory. Remove sealants that fail to adhere to joint substrates during testing or to comply with other requirements. Retest failed applications until test results prove sealants comply with indicated requirements.

### 3.6 CLEANING

- A. Clean off excess sealant or sealant smears adjacent to joints as the Work progresses by methods and with cleaning materials approved in writing by manufacturers of joint sealants and of products in which joints occur.

### 3.7 PROTECTION

- A. Protect joint sealants during and after curing period from contact with contaminating substances and from damage resulting from construction operations or other causes so sealants are without deterioration or damage at time of Substantial Completion. If, despite such protection, damage or deterioration occurs, cut out, remove, and repair damaged or deteriorated joint sealants immediately so installations with repaired areas are indistinguishable from original work.

### 3.8 JOINT-SEALANT SCHEDULE

- A. Joint-Sealant Application: Interior joints in horizontal traffic surfaces.

1. Joint Locations:
  - a. Control and expansion joints in tile flooring.
  - b. Other joints as indicated on Drawings.

2. Joint Sealant: Urethane, S, P, 25, T, NT.
  3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- B. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces.
1. Joint Locations:
    - a. Control and expansion joints on exposed interior surfaces of exterior walls.
    - b. Tile control and expansion joints in non-wet areas.
    - c. Other joints as indicated on Drawings.
  2. Joint Sealant: Urethane, S, NS, 25, NT.
  3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
  4. Joint-Sealant Color for Joints in Tile: Custom color as selected by Architect.
- C. Joint-Sealant Application: Interior joints in vertical surfaces and horizontal nontraffic surfaces not subject to significant movement.
1. Joint Locations:
    - a. Control joints on exposed interior surfaces of exterior walls.
    - b. Perimeter joints between interior wall surfaces and frames of interior doors and windows.
    - c. Other joints as indicated on Drawings.
  2. Joint Sealant: Acrylic latex.
  3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
- D. Joint-Sealant Application: Mildew-resistant interior joints in vertical surfaces and horizontal nontraffic surfaces.
1. Joint Locations:
    - a. Joints between plumbing fixtures and adjoining walls, floors, and counters.
    - b. Tile control and expansion joints in wet areas.
    - c. Other joints as indicated on Drawings.
  2. Joint Sealant: Silicone, mildew resistant, acid curing, S, NS, 25, NT.
  3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.
  4. Joint-Sealant Color for Joints in Tile: Custom color as selected by Architect.
- E. Joint-Sealant Application: Acoustical.
1. Joint Locations:
    - a. Gypsum Board walls
  2. Joint Sealant: Acoustical sealant.
  3. Joint-Sealant Color: As selected by Architect from manufacturer's full range of colors.



ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84132

Code Review

END OF SECTION 07 9200

## SECTION 08 1113 - HOLLOW METAL FRAMES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes:
  - 1. Interior standard steel frames.
- B. Related Requirements:
  - 1. Section 08 7100 "Door Hardware" for door hardware for hollow-metal doorframes.

#### 1.3 DEFINITIONS

- A. Minimum Thickness: Minimum thickness of base metal without coatings according to NAAMM-HMMA 803 or SDI A250.8.

#### 1.4 COORDINATION

- A. Coordinate anchorage installation for hollow-metal frames. Furnish setting drawings, templates, and directions for installing anchorages, including sleeves, concrete inserts, anchor bolts, and items with integral anchors. Deliver such items to Project site in time for installation.
- B. Coordinate requirements for installation of door hardware, electrified door hardware, and access control and security systems.

#### 1.5 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.6 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, fire-resistance ratings, and finishes.

B. Shop Drawings: Include the following:

1. Elevations of each door type.
2. Details of doors, including vertical- and horizontal-edge details and metal thicknesses.
3. Frame details for each frame type, including dimensioned profiles and metal thicknesses.
4. Locations of reinforcement and preparations for hardware.
5. Details of each different wall opening condition.
6. Details of electrical raceway and preparation for electrified hardware, access control systems, and security systems.
7. Details of anchorages, joints, field splices, and connections.
8. Details of accessories.

C. Samples for Verification:

1. Finishes: For each type of exposed finish required, prepared on Samples of not less than 3 by 5 inches.
2. Fabrication: Prepare Samples approximately 12 by 12 inches to demonstrate compliance with requirements for quality of materials and construction. Show profile, corner joint, floor and wall anchors, and silencers.

D. Product Schedule: For hollow-metal frames, prepared by or under the supervision of supplier, using same reference numbers for details and openings as those on Drawings. Coordinate with final door hardware schedule.

1.7 INFORMATIONAL SUBMITTALS

- A. Product Test Reports: For each type of fire-rated hollow-metal frame assembly for tests performed by a qualified testing agency indicating compliance with performance requirements.

1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver hollow-metal work palletized, packaged, or crated to provide protection during transit and Project-site storage. Do not use nonvented plastic.

1. Provide additional protection to prevent damage to factory-finished units.

- B. Deliver welded frames with two removable spreader bars across bottom of frames, tack welded to jambs and mullions.

- C. Store hollow-metal frames vertically under cover at Project site with head up. Place on minimum 4-inch-high wood blocking. Provide minimum 1/4-inch space between each stacked door to permit air circulation.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Ceco Door; ASSA ABLOY.
  2. Curries Company; ASSA ABLOY.
  3. Deansteel Manufacturing Company, Inc.
  4. Fleming Door Products Ltd.; Assa Abloy Group Company.
  5. Gensteel Doors, Inc.
  6. Pioneer Industries.
  7. Republic Doors and Frames.
  8. Rocky Mountain Metals, Inc.
  9. Steelcraft; an Allegion brand.

### 2.2 PERFORMANCE REQUIREMENTS

- A. Fire-Rated Assemblies: Complying with NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.
1. Smoke- and Draft-Control Assemblies: Listed and labeled for smoke and draft control by a qualified testing agency acceptable to authorities having jurisdiction, based on testing according to UL 1784 and installed in compliance with NFPA 105.
- B. Fire-Rated, Borrowed-Lite Assemblies: Complying with NFPA 80 and listed and labeled by a qualified testing agency acceptable to authorities having jurisdiction, for fire-protection ratings indicated, based on testing according to NFPA 257 or UL 9.

### 2.3 INTERIOR STANDARD STEEL FRAMES

- A. Construct hollow-metal frames to comply with standards indicated for materials, fabrication, hardware locations, hardware reinforcement, tolerances, and clearances, and as specified.
1. Interior Frames: SDI A250.8. Frames:
    - a. Materials: Uncoated steel sheet, minimum thickness of 0.042 inch (18 gage).
    - b. Construction: Full profile welded.
    - c. Exposed Finish: Prime.

### 2.4 FRAME ANCHORS

- A. Jamb Anchors:

1. Type: Anchors of minimum size and type required by applicable door and frame standard, and suitable for performance level indicated.
  2. Quantity: Minimum of three anchors per jamb, with one additional anchor for frames with no floor anchor. Provide one additional anchor for each 24 inches of frame height above 7 feet.
  3. Postinstalled Expansion Anchor: Minimum 3/8-inch-diameter bolts with expansion shields or inserts, with manufacturer's standard pipe spacer.
- B. Floor Anchors: Provide floor anchors for each jamb and mullion that extends to floor.
- C. Material: ASTM A 879/A 879M, Commercial Steel (CS), 04Z coating designation; mill phosphatized.

## 2.5 MATERIALS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Cold-Rolled Steel Sheet: ASTM A 1008/A 1008M, Commercial Steel (CS), Type B; suitable for exposed applications.
- C. Inserts, Bolts, and Fasteners: Hot-dip galvanized according to ASTM A 153/A 153M.
- D. Power-Actuated Fasteners in Concrete: Fastener system of type suitable for application indicated, fabricated from corrosion-resistant materials, with clips or other accessory devices for attaching hollow-metal frames of type indicated.

## 2.6 FABRICATION

- A. Hollow-Metal Frames: Fabricate in one piece except where handling and shipping limitations require multiple sections. Where frames are fabricated in sections, provide alignment plates or angles at each joint, fabricated of metal of same or greater thickness as frames.
1. Provide countersunk, flat- or oval-head exposed screws and bolts for exposed fasteners unless otherwise indicated.
  2. Door Silencers: Except on weather-stripped frames, drill stops to receive door silencers as follows. Keep holes clear during construction.
    - a. Single-Door Frames: Drill stop in strike jamb to receive three door silencers.
    - b. Double-Door Frames: Drill stop in head jamb to receive two door silencers.
- B. Hardware Preparation: Factory prepare hollow-metal doors and frames to receive templated mortised hardware, and electrical wiring; include cutouts, reinforcement, mortising, drilling, and tapping according to SDI A250.6, the Door Hardware Schedule, and templates.
1. Reinforce frames to receive nontemplated, mortised, and surface-mounted door hardware.
  2. Comply with BHMA A156.115 for preparing hollow-metal frames for hardware.

## 2.7 STEEL FINISHES

- A. Prime Finish: Clean, pretreat, and apply manufacturer's standard primer.
  - 1. Shop Primer: Manufacturer's standard, fast-curing, lead- and chromate-free primer complying with SDI A250.10; recommended by primer manufacturer for substrate; compatible with substrate and field-applied coatings despite prolonged exposure.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Remove welded-in shipping spreaders installed at factory. Restore exposed finish by grinding, filling, and dressing, as required to make repaired area smooth, flush, and invisible on exposed faces. Touch up factory-applied finishes where spreaders are removed.
- B. Drill and tap frames to receive nontemplated, mortised, and surface-mounted door hardware.

### 3.2 INSTALLATION

- A. General: Install hollow-metal frames plumb, rigid, properly aligned, and securely fastened in place. Comply with approved Shop Drawings and with manufacturer's written instructions. Comply with SDI A250.11
- B. Set frames accurately in position; plumbed, aligned, and braced securely until permanent anchors are set. After wall construction is complete, remove temporary braces without damage to completed Work.
  - 1. Where frames are fabricated in sections, field splice at approved locations by welding face joint continuously; grind, fill, dress, and make splice smooth, flush, and invisible on exposed faces. Touch-up finishes.
  - 2. Install frames with removable stops located on secure side of opening.
- C. Fire-Rated Openings: Install frames according to NFPA 80.
- D. Floor Anchors: Secure with postinstalled expansion anchors.
  - 1. Floor anchors may be set with power-actuated fasteners instead of postinstalled expansion anchors if so indicated and approved on Shop Drawings.
- E. Solidly pack mineral-fiber insulation inside frames.
- F. Installation Tolerances: Adjust hollow-metal frames to the following tolerances:
  - 1. Squareness: Plus or minus 1/16 inch, measured at door rabbet on a line 90 degrees from jamb perpendicular to frame head.

2. Alignment: Plus or minus 1/16 inch, measured at jambs on a horizontal line parallel to plane of wall.
3. Twist: Plus or minus 1/16 inch, measured at opposite face corners of jambs on parallel lines, and perpendicular to plane of wall.
4. Plumbness: Plus or minus 1/16 inch, measured at jambs at floor.

### 3.3 CLEANING AND TOUCHUP

- A. Prime-Coat Touchup: Immediately after erection, sand smooth rusted or damaged areas of prime coat and apply touchup of compatible air-drying, rust-inhibitive primer.

END OF SECTION 08 1113

## SECTION 08 1416 - FLUSH WOOD DOORS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Solid-core doors with wood-veneer faces.
  - 2. Factory finishing flush wood doors.
  - 3. Factory fitting flush wood doors to frames and factory machining for hardware.
- B. Related Requirements:
  - 1. Section 08 8000 "Glazing" for glass view panels in flush wood doors.

#### 1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of door. Include details of core and edge construction and trim for openings. Include factory-finishing specifications.
- B. Shop Drawings: Indicate location, size, and hand of each door; elevation of each kind of door; construction details not covered in Product Data; and the following:
  - 1. Dimensions and locations of blocking.
  - 2. Dimensions and locations of mortises and holes for hardware.
  - 3. Dimensions and locations of cutouts.
  - 4. Undercuts.
  - 5. Requirements for veneer matching.
  - 6. Doors to be factory finished and finish requirements.
  - 7. Fire-protection ratings for fire-rated doors.
- C. Samples for Verification:



1. Factory finishes applied to actual door face materials, approximately 8 by 10 inches (200 by 250 mm), for each material and finish.
2. Corner sections of doors, approximately 8 by 10 inches (200 by 250 mm), with door faces and edges representing actual materials to be used.
  - a. Provide Samples for species of veneer and solid lumber required.
  - b. Finish veneer-faced door Samples with same materials proposed for factory-finished doors.
3. Frames for light openings, 6 inches (150 mm) long, for each material, type, and finish required.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Sample Warranty: For special warranty.
- B. Quality Standard Compliance Certificates: WI Certified Compliance Program certificates.

#### 1.6 QUALITY ASSURANCE

- A. Manufacturer Qualifications: A qualified manufacturer that is certified for chain of custody by an FSC-accredited certification body.
- B. Vendor Qualifications: A vendor that is certified for chain of custody by an FSC-accredited certification body.

#### 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Comply with requirements of referenced standard and manufacturer's written instructions.
- B. Package doors individually in plastic bags or cardboard cartons.
- C. Mark each door on top and bottom rail with opening number used on Shop Drawings.

#### 1.8 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install doors until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and HVAC system is operating and maintaining temperature between 60 and 90 deg F and relative humidity between 25 and 55 percent during remainder of construction period.

## 1.9 WARRANTY

- A. A. Special Warranty: Manufacturer agrees to repair or replace doors that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Warping (bow, cup, or twist) more than 1/4 inch in a 42-by-84-inch section.
    - b. Telegraphing of core construction in face veneers exceeding 0.01 inch in a 3-inch span.
  - 2. Warranty shall also include installation and finishing that may be required due to repair or replacement of defective doors.
  - 3. Warranty Period for Solid-Core Interior Doors: Life of installation.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Algoma Hardwoods, Inc.
  - 2. Eggers Industries.
  - 3. Graham Wood Doors; ASSA ABLOY Group company.
  - 4. Ipik Door Company.
  - 5. Marshfield DoorSystems, Inc.
  - 6. Mohawk Flush Doors, Inc.
  - 7. Oshkosh Door Company.
  - 8. VT Industries
- B. Source Limitations: Obtain flush wood doors from single manufacturer.

### 2.2 FLUSH WOOD DOORS, GENERAL

- A. Quality Standard: In addition to requirements specified, comply with AWI's, AWMAC's, and WI's "Architectural Woodwork Standards."
  - 1. Provide WI Certified Compliance Labels indicating that doors comply with requirements of grades specified.
  - 2. Contract Documents contain selections chosen from options in quality standard and additional requirements beyond those of quality standard. Comply with those selections and requirements in addition to quality standard.

- B. Regional Materials: Wood doors shall be manufactured within 100 miles (160 km) of Project site from materials that have been extracted, harvested, or recovered, as well as manufactured, within 100 miles (160 km) of Project site.
- C. Certified Wood: Wood doors shall be certified as "FSC Pure" or "FSC Mixed Credit" according to FSC STD-01-001 and FSC STD-40-004.
- D. Adhesives: Use adhesives that meet the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- E. Composite Wood Products: Products shall be made using ultra-low-emitting formaldehyde resins as defined in the California Air Resources Board's "Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products" or shall be made with no added formaldehyde.
- F. WDMA I.S.1-A Performance Grade:
  - 1. Heavy Duty unless otherwise indicated.
  - 2. Extra Heavy Duty: Public toilets, janitor's closets, exits, and patient rooms.
- G. Fire-Rated Wood Doors: Doors complying with NFPA 80 that are listed and labeled by a qualified testing agency, for fire-protection ratings indicated, based on testing at positive pressure according to NFPA 252 or UL 10C.
  - 1. Cores: Provide core specified or mineral core as needed to provide fire-protection rating indicated.
  - 2. Edge Construction: Provide edge construction with intumescent seals concealed by outer stile. Comply with specified requirements for exposed edges.
- H. Smoke- and Draft-Control Door Assemblies: Listed and labeled for smoke and draft control, based on testing according to UL 1784.
- I. Particleboard-Core Doors:
  - 1. Particleboard: ANSI A208.1, Grade LD-1, made with binder containing no urea-formaldehyde.
  - 2. Provide doors with glued-wood-stave or structural-composite-lumber cores instead of particleboard cores for doors indicated to receive exit devices.

## 2.3 VENEER-FACED DOORS FOR TRANSPARENT FINISH

- A. Interior Solid-Core Doors:
  - 1. Grade: Custom (Grade A faces).
  - 2. Species: Select white maple.
  - 3. Cut: Plain sliced (flat sliced).
  - 4. Match between Veneer Leaves: Book match.

5. Assembly of Veneer Leaves on Door Faces: Center-balance match.
6. Pair and Set Match: Provide for doors hung in same opening.
7. Room Match: Match door faces within each separate room or area of building. Corridor-door faces do not need to match where they are separated by 10 feet or more.
8. Exposed Vertical and Top Edges: Same species as faces - edge Type A.
9. Core: Particleboard.
10. Construction: Five plies with total facing veneer thickness not less than 1/16 inch. Stiles and rails are bonded to core, then entire unit is abrasive planed before veneering. Faces are bonded to core using a hot press.

## 2.4 LIGHT FRAMES

- A. Wood Beads for Light Openings in Wood Doors: Provide manufacturer's standard wood beads unless otherwise indicated.
  1. Wood Species: Same species as door faces.
  2. Profile: Flush rectangular beads.
- B. Wood-Veneered Beads for Light Openings in Fire-Rated Doors: Manufacturer's standard wood-veneered noncombustible beads matching veneer species of door faces and approved for use in doors of fire-protection rating indicated. Include concealed metal glazing clips where required for opening size and fire-protection rating indicated.

## 2.5 FABRICATION

- A. Factory fit doors to suit frame-opening sizes indicated. Comply with clearance requirements of referenced quality standard for fitting unless otherwise indicated.
  1. Comply with NFPA 80 requirements for fire-rated doors.
- B. Factory machine doors for hardware that is not surface applied. Locate hardware to comply with DHI-WDHS-3. Comply with final hardware schedules, door frame Shop Drawings, BHMA-156.115-W, and hardware templates.
  1. Coordinate with hardware mortises in metal frames to verify dimensions and alignment before factory machining.
- C. Openings: Factory cut and trim openings through doors.
  1. Light Openings: Trim openings with moldings of material and profile indicated.
  2. Glazing: Factory install glazing in doors indicated to be factory finished. Comply with applicable requirements in Section 08 8000 "Glazing."

## 2.6 FACTORY FINISHING

- A. General: Comply with referenced quality standard for factory finishing. Complete fabrication, including fitting doors for openings and machining for hardware that is not surface applied, before finishing.
  - 1. Finish faces, all four edges, edges of cutouts, and mortises. Stains and fillers may be omitted on top and bottom edges, edges of cutouts, and mortises.
- B. Factory finish doors.
- C. Transparent Finish:
  - 1. Grade: Custom.
  - 2. Finish: AWI's, AWMAC's, and WT's "Architectural Woodwork Standards" System 11, catalyzed polyurethane.
  - 3. Staining: Match Architect's sample.
  - 4. Effect: Open-grain finish.
  - 5. Sheen: Satin.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine doors and installed door frames, with Installer present, before hanging doors.
  - 1. Verify that installed frames comply with indicated requirements for type, size, location, and swing characteristics and have been installed with level heads and plumb jambs.
  - 2. Reject doors with defects.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Hardware: For installation, see Section 08 7100 "Door Hardware."
- B. Installation Instructions: Install doors to comply with manufacturer's written instructions and referenced quality standard, and as indicated.
  - 1. Install fire-rated doors according to NFPA 80.
  - 2. Install smoke- and draft-control doors according to NFPA 105.
- C. Factory-Fitted Doors: Align in frames for uniform clearance at each edge.
- D. Factory-Finished Doors: Restore finish before installation if fitting or machining is required at Project site.

3.3 ADJUSTING

- A. Operation: Rehang or replace doors that do not swing or operate freely.
- B. Finished Doors: Replace doors that are damaged or that do not comply with requirements. Doors may be repaired or refinished if Work complies with requirements and shows no evidence of repair or refinishing.

END OF SECTION 08 1416

## SECTION 08 3113 - ACCESS DOORS AND FRAMES (VBS)

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Access doors and frames for walls and ceilings.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, materials, individual components and profiles, and finishes.
- B. Samples: For each type of access door and frame and for each finish specified, complete assembly minimum 6 by 6 inches in size.
- C. Product Schedule: For access doors and frames. Use same designations indicated on Drawings.

### PART 2 - PRODUCTS

#### 2.1 ACCESS DOORS AND FRAMES

- A. Flush Access Doors with Exposed Flanges:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Acudor Products, Inc.
    - b. Babcock-Davis.
    - c. JL Industries, Inc.; a division of the Activar Construction Products Group.
    - d. Larsens Manufacturing Company.
    - e. Milcor; Commercial Products Group of Hart & Cooley, Inc.
  - 2. Description: Face of door flush with frame, with exposed flange and concealed hinge.
  - 3. Locations:

- a. Walls
  - b. Ceilings where directed by Architect.
- 4. Door Size: As indicated.
  - 5. Uncoated Steel Sheet for Door: Nominal 0.060 inch, 16 gage, factory primed.
  - 6. Frame Material: Same material, thickness, and finish as door.
  - 7. Latch and Lock: Prepared for mortise cylinder.

## 2.2 MATERIALS

- A. Steel Plates, Shapes, and Bars: ASTM A 36/A 36M.
- B. Steel Sheet: Uncoated or electrolytic zinc coated, ASTM A 879/A 879M, with cold-rolled steel sheet substrate complying with ASTM A 1008/A 1008M, Commercial Steel (CS), exposed.
- C. Frame Anchors: As recommended by access panel manufacturer.
- D. Inserts, Bolts, and Anchor Fasteners: Hot-dip galvanized steel according to ASTM A 153/A 153M or ASTM F 2329.

## 2.3 FABRICATION

- A. General: Provide access door and frame assemblies manufactured as integral units ready for installation.
- B. Metal Surfaces: For metal surfaces exposed to view in the completed Work, provide materials with smooth, flat surfaces without blemishes. Do not use materials with exposed pitting, seam marks, roller marks, rolled trade names, or roughness.
- C. Doors and Frames: Grind exposed welds smooth and flush with adjacent surfaces. Furnish mounting holes, attachment devices and fasteners of type required to secure access doors to types of supports indicated
  - 1. For concealed flanges with drywall bead, provide edge trim for gypsum panels securely attached to perimeter of frames.
- D. Latch and Lock Hardware:
  - 1. Quantity: Furnish number of latches and locks required to hold doors tightly closed.
  - 2. Keys: Furnish two keys per lock and key all locks alike.
  - 3. Mortise Cylinder Preparation: Where indicated, prepare door panel to accept cylinder specified in Section 08 7100 "Door Hardware."



## 2.4 FINISHES

- A. Comply with NAAMM's "Metal Finishes Manual for Architectural and Metal Products" for recommendations for applying and designating finishes.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.
- C. Painted Finishes: Comply with coating manufacturer's written instructions for cleaning, conversion coating, and applying and baking finish.
  - 1. Factory Primed: Apply manufacturer's standard, lead- and chromate-free, universal primer immediately after surface preparation and pretreatment.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Comply with manufacturer's written instructions for installing access doors and frames.

### 3.3 ADJUSTING

- A. Adjust doors and hardware, after installation, for proper operation.
- B. Remove and replace doors and frames that are warped, bowed, or otherwise damaged.

END OF SECTION 08 3113

## SECTION 08 3323 - OVERHEAD COILING DOORS

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Service doors.

B. Related Requirements:

1. Section 05 5000 "Metal Fabrications" for miscellaneous steel supports, door-opening framing, corner guards, and bollards.

#### 1.2 ACTION SUBMITTALS

A. Product Data: For each type and size of overhead coiling door and accessory.

1. Include construction details, material descriptions, dimensions of individual components, profiles for slats, and finishes.
2. Include rated capacities, operating characteristics, electrical characteristics, and furnished accessories.

B. Shop Drawings: For each installation and for special components not dimensioned or detailed in manufacturer's product data.

1. Include plans, elevations, sections, and mounting details.
2. Include details of equipment assemblies, and indicate dimensions, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include points of attachment and their corresponding static and dynamic loads imposed on structure.
4. Show locations of controls, locking devices, and other accessories.
5. Include diagrams for power, signal, and control wiring.

C. Samples for Initial Selection: Manufacturer's finish charts showing full range of colors and textures available for units with factory-applied finishes.

1. Include similar Samples of accessories involving color selection.

D. Samples for Verification: For each type of exposed finish on the following components, in manufacturer's standard sizes:

1. Curtain slats.
2. Bottom bar with sensor edge.
3. Guides.
4. Brackets.

5. Hood.
6. Locking device(s).
7. Include similar Samples of accessories involving color selection.

### 1.3 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Sample Warranty: For special warranty.

### 1.4 CLOSEOUT SUBMITTALS

- A. Special warranty.
- B. Maintenance Data: For overhead coiling doors to include in maintenance manuals.

### 1.5 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer for both installation and maintenance of units required for this Project.
  1. Maintenance Proximity: Not more than two hours' normal travel time from Installer's place of business to Project site.

### 1.6 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of doors that fail in materials or workmanship within specified warranty period.
  1. Warranty Period: Two years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Source Limitations: Obtain overhead coiling doors from single source from single manufacturer.
  1. Obtain operators and controls from overhead coiling-door manufacturer.

## 2.2 PERFORMANCE REQUIREMENTS

- A. Accessibility Standard: Comply with applicable provisions in the USDOJ's "2010 ADA Standards for Accessible Design" and ICC A117.1.
- B. Seismic Performance: Overhead coiling doors shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
  - 1. Component Importance Factor: 1.5.

## 2.3 DOOR ASSEMBLY

- A. Service Door: Overhead coiling door formed with curtain of interlocking metal slats.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. City-Gates.
    - b. Cookson Company.
    - c. Cornell.
    - d. Lawrence Roll-Up Doors, Inc.
    - e. McKeon Rolling Steel Door Company, Inc.
    - f. Overhead Door Corporation.
- B. Operation Cycles: Door components and operators capable of operating for not less than 100,000. One operation cycle is complete when a door is opened from the closed position to the fully open position and returned to the closed position.
- C. Air Infiltration: Maximum rate of 0.4 cfm/sq. ft. at 15 and 25 mph when tested according to ASTM E283 or DASMA 105.
- D. Door Curtain Material: Galvanized steel, or clear anodized aluminum as indicated on the drawings.
- E. Door Curtain Slats: Flat profile slats of 3-1/4-inch center-to-center height.
- F. Bottom Bar: Two angles, each not less than 1-1/2 by 1-1/2 by 1/8 inch thick; fabricated from hot-dip galvanized steel and finished to match door.
- G. Curtain Jamb Guides: Galvanized steel with exposed finish matching curtain slats, or clear anodized aluminum as indicated on the drawings..

## 2.4 DOOR ASSEMBLY

- A. Insulated Service Door: Door curtain of galvanized steel.
- B. Hood: Galvanized steel.
- C. Locking Devices: Equip door with locking device assembly.

1. Locking Device Assembly: Single-jamb side locking bars, operable from inside and outside with cylinders.

D. Electric Door Operator:

1. Usage Classification: Heavy duty, 25 or more cycles per hour and more than 90 cycles per day.
2. Operator Location: Through wall, unless indicated otherwise.
3. Safety: Listed according to UL 325 by a qualified testing agency for commercial or industrial use; moving parts of operator enclosed or guarded if exposed and mounted at 8 feet or lower.
4. Motor Exposure: Interior.
5. Motor Electrical Characteristics:
  - a. Horsepower: 1 hp.
  - b. Voltage: 208-V ac, single phase, 60 Hz.
6. Emergency Manual Operation: Push-up type.
7. Obstruction-Detection Device: Automatic electric sensor edge on bottom bar; self-monitoring type.
  - a. Sensor Edge Bulb Color: As selected by Architect from manufacturer's full range.
8. Control Station(s): Interior mounted.

E. Curtain Accessories: Equip door with push/pull handles.

F. Door Finish:

1. Baked-Enamel or Powder-Coated Finish: Color as selected by Architect from manufacturer's full range.
2. Interior Curtain-Slat Facing: Match finish of exterior curtain-slat face.

2.5 MATERIALS, GENERAL

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2.6 DOOR CURTAIN MATERIALS AND CONSTRUCTION

- A. Door Curtains: Fabricate overhead coiling-door curtain of interlocking metal slats, designed to withstand wind loading indicated, in a continuous length for width of door without splices. Unless otherwise indicated, provide slats of thickness and mechanical properties recommended by door manufacturer for performance, size, and type of door indicated, and as follows:
1. Steel Door Curtain Slats: Zinc-coated (galvanized), cold-rolled structural-steel sheet; complying with ASTM A653/A653M, with G90 zinc coating; nominal sheet thickness (coated) of 0.028 inch; and as required.

2. Metal Interior Curtain-Slat Facing: Match metal of exterior curtain-slat face, with minimum steel thickness of 0.010 inch.

- B. Curtain Jamb Guides: Manufacturer's standard angles or channels and angles of same material and finish as curtain slats unless otherwise indicated, with sufficient depth and strength to retain curtain, to allow curtain to operate smoothly, and to withstand loading. Slot bolt holes for guide adjustment. Provide removable stops on guides to prevent overtravel of curtain.

## 2.7 HOODS

- A. General: Form sheet metal hood to entirely enclose coiled curtain and operating mechanism at opening head. Contour to fit end brackets to which hood is attached. Roll and reinforce top and bottom edges for stiffness. Form closed ends for surface-mounted hoods and fascia for any portion of between-jamb mounting that projects beyond wall face. Equip hood with intermediate support brackets as required to prevent sagging.

1. Galvanized Steel: Nominal 0.028-inch-thick, hot-dip galvanized-steel sheet with G90 zinc coating, complying with ASTM A653/A653M.

- B. Removable Metal Soffit: Formed or extruded from same metal and with same finish as curtain if hood is mounted above ceiling unless otherwise indicated.

## 2.8 LOCKING DEVICES

- A. Locking Device Assembly: Fabricate with cylinder lock, spring-loaded dead bolt, operating handle, cam plate, and adjustable locking bars to engage through slots in tracks.

1. Lock Cylinders: As specified in Section 08 7100 "Door Hardware".

- B. Safety Interlock Switch: Equip power-operated doors with safety interlock switch to disengage power supply when door is locked.

## 2.9 CURTAIN ACCESSORIES

- A. Push/Pull Handles: Equip each push-up-operated or emergency-operated door with lifting handles on each side of door, finished to match door.

## 2.10 COUNTERBALANCE MECHANISM

- A. General: Counterbalance doors by means of manufacturer's standard mechanism with an adjustable-tension, steel helical torsion spring mounted around a steel shaft and contained in a spring barrel connected to top of curtain with barrel rings. Use grease-sealed bearings or self-lubricating graphite bearings for rotating members.

- B. Counterbalance Barrel: Fabricate spring barrel of manufacturer's standard hot-formed, structural-quality, seamless carbon-steel pipe, of sufficient diameter and wall thickness to

support rolled-up curtain without distortion of slats and to limit barrel deflection to not more than 0.03 in./ft. of span under full load.

- C. Counterbalance Spring: One or more oil-tempered, heat-treated steel helical torsion springs. Size springs to counterbalance weight of curtain, with uniform adjustment accessible from outside barrel. Secure ends of springs to barrel and shaft with cast-steel barrel plugs.
- D. Torsion Rod for Counterbalance Shaft: Fabricate of manufacturer's standard cold-rolled steel, sized to hold fixed spring ends and carry torsional load.
- E. Brackets: Manufacturer's standard mounting brackets of either cast iron or cold-rolled steel plate.

## 2.11 ELECTRIC DOOR OPERATORS

- A. General: Electric door operator assembly of size and capacity recommended and provided by door manufacturer for door and operation-cycles requirement specified, with electric motor and factory-prewired motor controls, starter, gear-reduction unit, solenoid-operated brake, clutch, control stations, control devices, integral gearing for locking door, and accessories required for proper operation.
  - 1. Comply with NFPA 70.
  - 2. Control equipment complying with NEMA ICS 1, NEMA ICS 2, and NEMA ICS 6, with NFPA 70 Class 2 control circuit, maximum 24-V ac or dc.
- B. Usage Classification: Electric operator and components capable of operating for not less than number of cycles per hour indicated for each door.
- C. Door Operator Location(s): Operator location indicated for each door.
  - 1. Through-Wall Mounted: Operator is mounted on other side of wall from coil side of door.
- D. Motors: Reversible-type motor with controller (disconnect switch) for motor exposure indicated for each door assembly.
  - 1. Electrical Characteristics: Minimum as indicated for each door assembly. If not indicated, large enough to start, accelerate, and operate door in either direction from any position, at a speed not less than 8 in./sec. and not more than 12 in./sec., without exceeding nameplate ratings or service factor.
  - 2. Operating Controls, Controllers, Disconnect Switches, Wiring Devices, and Wiring: Manufacturer's standard unless otherwise indicated.
  - 3. Coordinate wiring requirements and electrical characteristics of motors and other electrical devices with building electrical system and each location where installed.
- E. Limit Switches: Equip each motorized door with adjustable switches interlocked with motor controls and set to automatically stop door at fully opened and fully closed positions.

- F. Obstruction-Detection Devices: External entrapment protection consisting of indicated automatic safety sensor capable of protecting full width of door opening.
  - 1. Electric Sensor Edge: Automatic safety sensor edge, located within astragal or weather stripping mounted to bottom bar. Contact with sensor activates device. Connect to control circuit using manufacturer's standard take-up reel or self-coiling cable.
    - a. Self-Monitoring Type: Four-wire-configured device designed to interface with door operator control circuit to detect damage to or disconnection of sensor edge.
- G. Control Station: Three-button control station in fixed location with momentary-contact push-button controls labeled "Open" and "Stop" and sustained- or constant-pressure push-button control labeled "Close."
  - 1. Interior-Mounted Units: Full-guarded, surface-mounted, heavy-duty type, with general-purpose NEMA ICS 6, Type 1 enclosure.
- H. Emergency Manual Operation: Equip each electrically powered door with capability for emergency manual operation. Design manual mechanism so required force for door operation does not exceed 25 lbf.
- I. Emergency Operation Disconnect Device: Equip operator with hand-operated disconnect mechanism for automatically engaging manual operator and releasing brake for emergency manual operation while disconnecting motor without affecting timing of limit switch. Mount mechanism so it is accessible from floor level. Include interlock device to automatically prevent motor from operating when emergency operator is engaged.
- J. Motor Removal: Design operator so motor may be removed without disturbing limit-switch adjustment and without affecting emergency manual operation.

## 2.12 GENERAL FINISH REQUIREMENTS

- A. Comply with NAAMM/NOMMA 500 for recommendations for applying and designating finishes.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

## 2.13 STEEL AND GALVANIZED-STEEL FINISHES

- A. Baked-Enamel or Powder-Coat Finish: Manufacturer's standard baked-on finish consisting of prime coat and thermosetting topcoat. Comply with coating manufacturer's written instructions for cleaning, pretreatment, application, and minimum dry film thickness.



## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates areas and conditions, with Installer present, for compliance with requirements for substrate construction and other conditions affecting performance of the Work.
- B. Examine locations of electrical connections.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install overhead coiling doors and operating equipment complete with necessary hardware, anchors, inserts, hangers, and equipment supports; according to manufacturer's written instructions and as specified.
- B. Install overhead coiling doors, hoods, controls, and operators at the mounting locations indicated for each door.
- C. Accessibility: Install overhead coiling doors, switches, and controls along accessible routes in compliance with the accessibility standard.

### 3.3 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
  - 1. Complete installation and startup checks according to manufacturer's written instructions.
  - 2. After electrical circuitry has been energized, operate doors to confirm proper motor rotation and door performance.
  - 3. Test and adjust controls and safety devices. Replace damaged and malfunctioning controls and equipment.

### 3.4 ADJUSTING

- A. Adjust hardware and moving parts to function smoothly so that doors operate easily, free of warp, twist, or distortion.
- B. Lubricate bearings and sliding parts as recommended by manufacturer.
- C. Adjust seals to provide tight fit around entire perimeter.

### 3.5 MAINTENANCE SERVICE

- A. Initial Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by skilled employees of coiling-door Installer. Include

quarterly preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper door operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.

1. Perform maintenance, including emergency callback service, during normal working hours.
2. Include 24-hour-per-day, seven-day-per-week, emergency callback service.

### 3.6 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain overhead coiling doors.

END OF SECTION 08 3323

## SECTION 087100 - DOOR HARDWARE

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
    - 1. Commercial door hardware for the following:
      - a. Swinging doors.
      - b. Fire-rated swinging doors.
      - c. Other doors to the extent indicated.
    - 2. Cylinders for doors specified in other Sections.
    - 3. Electrified door hardware.
  - B. Related Sections include the following:
    - 1. Division 08 Section "Hollow Metal Frames"
    - 2. Division 08 Section "Flush Wood Doors"
    - 3. Division 26 Sections for connections to electrical power system and for low-voltage wiring work.
    - 4. Division 28 Section "Access Control" for access control devices installed at door openings and provided as part of a security access system.
    - 5. Division 28 Section "Intrusion Detection" for detection devices installed at door openings and provided as part of an intrusion detection system.
    - 6. Division 28 Section "Fire Detection and Alarm" for connections to building fire alarm system.
  - C. Products furnished, but not installed, under this Section include the following. Coordinating, purchasing, delivering, and scheduling remain requirements of this Section.
- #### 1.3 REFERENCED STANDARDS
- A. Provide hardware in accordance with the following standards in addition to those specified in Division 01 Section "References".
    - 1. American National Standards Institute (ANSI), A117.1: Accessible and Usable Buildings and Facilities, edition as adopted by local Authority Having Jurisdiction (AHJ).

2. Builders Hardware Manufacturer's Association (BHMA)
  - a. ANSI/BHMA A156.2: Bored and Preassembled Locks and Latches, 2011 edition
  - b. ANSI/BHMA A156.3: Exit Devices, 2008 edition
  - c. ANSI/BHMA A156.4: Door Controls - Closers, 2008 edition
  - d. ANSI/BHMA A156.13: Mortise Locks and Latches, 2012 edition
  - e. ANSI/BHMA A156.15: Release Devices – Closer Holder, Electromagnetic, and Electromechanical, 2011 edition
  - f. ANSI/BHMA A156.18: Materials and Finishes, 2006 edition
  - g. ANSI/BHMA A156.19: Power Assist and Low Energy Power Operated Doors, 2007 edition
3. Door and Hardware Institute (DHI)
  - a. Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames, 2004 edition
  - b. Installation Guide for Doors and Hardware, 1994 edition
  - c. Sequence and Format for the Hardware Schedule, 2001 edition
4. National Fire Protection Association (NFPA)
  - a. NFPA 70: National Electrical Code, edition as adopted by local AHJ.
  - b. NFPA 80: Standard for Fire Doors and Other Opening Protectives, edition as adopted by local AHJ.
  - c. NFPA 252: Standard Methods of Fire Tests of Door Assemblies, edition as adopted by local AHJ.

#### 1.4 SUBMITTALS

- A. Product Data: Include construction and installation details, material descriptions, dimensions of individual components and profiles, and finishes.
- B. Shop Drawings: Details of electrified door hardware, indicating the following:
  1. Wiring Diagrams: Power, signal, and control wiring. Include the following:
    - a. System schematic.
    - b. Point-to-point wiring diagram.
    - c. Riser diagram.
    - d. Elevation of each door.
  2. Detail interface between electrified door hardware and fire alarm, access control, security, building control system.
  3. Operation Narrative: Describe the operation of doors controlled by electrified door hardware.
- C. Samples for Verification: For exposed door hardware of each type, in specified finish, full size. Tag with full description for coordination with the door hardware sets. Submit Samples before, or concurrent with, submission of the final door hardware sets, if requested.

1. Samples will be returned to Contractor. Units that are acceptable and remain undamaged through submittal, review, and field comparison process may, after final check of operation, be incorporated into the Work, within limitations of keying requirements.
- D. Qualification Data: For Installer
- E. Product Test Reports: Based on evaluation of comprehensive tests performed by manufacturer and witnessed by a qualified testing agency, for locks, latches, and closers as requested.
- F. Maintenance Data: For each type of door hardware to include in maintenance manuals. Include final hardware and keying schedule.
- G. Warranty: Special warranty specified in this Section.
- H. Door Hardware Sets: Prepared by or under the supervision of Architectural Hardware Consultant, detailing fabrication and assembly of door hardware, as well as procedures and diagrams. Coordinate the final door hardware sets with doors, frames, and related work to ensure proper size, thickness, hand, function, and finish of door hardware.
  1. Format: Use same scheduling sequence and format and use same door numbers as in the Contract Documents.
  2. Content: Include the following information:
    - a. Identification number, location, hand, fire rating, and material of each door and frame.
    - b. Type, style, function, size, quantity, and finish of each door hardware item.
    - c. Complete designations of every item required for each door or opening including name and manufacturer.
    - d. Fastenings and other pertinent information.
    - e. Location of each door hardware set, cross-referenced to Drawings, both on floor plans and in door and frame schedule.
    - f. Explanation of abbreviations, symbols, and codes contained in schedule.
    - g. Mounting locations for door hardware.
    - h. Door and frame sizes and materials.
    - i. Description of each electrified door hardware function, including location, sequence of operation, and interface with other building control systems.
    - j. Sequence of Operation: Include description of component functions that occur in the following situations: authorized person wants to enter; authorized person wants to exit; unauthorized person wants to enter; unauthorized person wants to exit.
    - k. List of related door devices specified in other Sections for each door and frame.
  3. Submittal Sequence: Submit the final door hardware sets at earliest possible date, particularly where approval of the door hardware sets must precede fabrication of other work that is critical in Project construction schedule. Include Product Data, Samples, Shop Drawings of other work affected by door hardware, and other information essential to the coordinated review of the door hardware sets.

## 1.5 QUALITY ASSURANCE

- A. Installer Qualifications: An employer of workers trained and approved by lock manufacturer.
  - 1. Installer's responsibilities include supplying and installing door hardware and providing a qualified Architectural Hardware Consultant available during the course of the Work to consult with Contractor, Architect, and Owner about door hardware and keying.
  - 2. Installer shall have warehousing facilities in Project's vicinity.
- B. Scheduling Responsibility: Preparation of door hardware and keying schedules.
- C. Engineering Responsibility: Preparation of data for electrified door hardware, including Shop Drawings, based on testing and engineering analysis of manufacturer's standard units in assemblies similar to those indicated for this Project.
- D. Supplier's Qualifications: Must purchase products directly from the manufacturer to ensure appropriate warranty and service requirements.
- E. Architectural Hardware Consultant Qualifications: A person who is currently certified by DHI as an Architectural Hardware Consultant and who is experienced in providing consulting services for door hardware installations that are comparable in material, design, and extent to that indicated for this Project.
- F. Source Limitations: Obtain each type and variety of door hardware from a single manufacturer, unless otherwise indicated.
  - 1. Provide electrified door hardware from same manufacturer as mechanical door hardware, unless otherwise indicated. Manufacturers that perform electrical modifications and that are listed by a testing and inspecting agency acceptable to authorities having jurisdiction are acceptable.
- G. Fire-Rated Door Assemblies: Assemblies complying with NFPA 80 that are listed and labeled by a testing and inspecting agency acceptable to authorities having jurisdiction, for fire ratings indicated, based on testing according to NFPA 252 and UBC Standard 7-2.
  - 1. Test Pressure: After 5 minutes into the test, neutral pressure level in furnace shall be established at 40 inches (1016 mm) or less above the sill.
- H. Electrified Door Hardware: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

#### 1.6 DELIVERY, STORAGE, AND HANDLING

- A. Inventory door hardware on receipt and provide secure lock-up for door hardware delivered to Project site.
- B. Tag each item or package separately with identification related to the final door hardware sets, and include basic installation instructions, templates, and necessary fasteners with each item or package.

#### 1.7 COORDINATION

- A. Coordinate layout and installation of recessed hardware with floor construction. Cast anchoring inserts into concrete. Concrete, reinforcement, and formwork requirements are specified in Division 03.
- B. Templates: Distribute door hardware templates for doors, frames, and other work specified to be factory prepared for installing door hardware. Check Shop Drawings of other work to confirm that adequate provisions are made for locating and installing door hardware to comply with indicated requirements.
- C. Coordinate with aluminum entrance door supplier for door hardware installation.
- D. Electrical System Roughing-in: Coordinate layout and installation of electrified door hardware with connections to power supplies, fire alarm system and detection devices, access control system, security system, and building control system.
- E. Existing Openings: Where new hardware components are scheduled for application to existing construction or where modifications to existing door hardware are required, field verify existing conditions and coordinate installation of door hardware to suit opening conditions and to provide for proper operation.

#### 1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of door hardware that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Structural failures including excessive deflection, cracking, or breakage.
    - b. Faulty operation of operators and door hardware.
    - c. Deterioration of metals, metal finishes, and other materials beyond normal weathering and use.
  - 2. Warranty Period: Three (3) years from date of Substantial Completion, except as follows:
    - a. Continuous Hinges: Lifetime of Building
    - b. Grade 1 Cylindrical Locks: Ten (10) years from date of Substantial Completion.
    - c. Grade 1 Mortise Locks: Seven (7) years from date of Substantial Completion.
    - d. Exit Devices: Three (3) years from date of Substantial Completion.
    - e. Manual Closers: Thirty (30) years from date of Substantial Completion.
    - f. Automatic Operators: Two (2) years from date of Substantial Completion.
    - g. Electrified Hardware Items: One (1) year from date of Substantial Completion.

#### 1.9 MAINTENANCE SERVICE

- A. Maintenance Tools and Instructions: Furnish a complete set of specialized tools and maintenance instructions as needed for Owner's continued adjustment, maintenance, and removal and replacement of door hardware.

- B. Maintenance Service: Beginning at Substantial Completion, provide six (6) months' full maintenance by skilled employees of door hardware Installer. Provide parts and supplies same as those used in the manufacture and installation of original products.

#### 1.10 EXTRA MATERIALS

- A. Furnish full-size units of door hardware described below, before installation begins, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
- B. Door Hardware:
  - 1. 1 each Von Duprin 98-L x 626 Exit Devices
  - 2. 1 each Schlage Locksets
  - 3. 2 each LCN 4111 EDA MC x 689 Closers (One of Each Hand)
  - 4. 2 each LCN 4011 MC x 689 Closers (One of Each Hand)

### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

|                                 |                                      |
|---------------------------------|--------------------------------------|
| 1. Hinges:                      | Ives, Hager, McKinney                |
| 2. Continuous Hinges:           | Ives, Hager, Select,                 |
| 3. Operating Door Trim:         | Ives, Rockwood, Hager, Trimco        |
| 4. Electric Strikes:            | Von Duprin, HES                      |
| 5. Locks and Latches:           | Schlage, Owner's Standard            |
| 6. Electro-Magnetic Locks:      | Schlage Electronics, Securitron, SDC |
| 7. Keypad Locksets:             | Schlage, Owner's Standard            |
| 8. Cylinders and Cores:         | Furnished and keyed by Owner         |
| 9. Exit Devices:                | Von Duprin, Owner's Standard         |
| 10. Mechanical Door Closers:    | LCN, Owner's Standard                |
| 11. Closer Release Devices:     | LCN, ABH                             |
| 12. Automatic Operators:        | LCN, Stanley, Horton, Besam,         |
| 13. Accessories and Trim:       | Ives, Rockwood, Hager, Trimco        |
| 14. Overhead Stops and Holders: | Glynn Johnson, ABH                   |
| 15. Saddle Thresholds:          | Zero, National Guard, Pemko          |
| 16. Weather Strip and Gasket:   | Zero, National Guard, Pemko          |
| 17. Miscellaneous Hardware:     | Ives, Rockwood, Hager, Trimco        |
| 18. Emergency Access Key Box:   | Knox, Inc                            |
| 19. Key Cabinet:                | Lund Equipment                       |
- B. Substitutions submitted in compliance with Division 01 Section "Substitutions" requirements will be reviewed for conformance to basis of design.



## 2.2 SCHEDULED HARDWARE

- A. Requirements for design, grade, function, finish, size, and other distinctive qualities of each type of finish hardware are indicated in the "Hardware Schedule" at the end of this Section. Products are identified by using hardware designation numbers of the following:
  - 1. Manufacturer's Product Designations: The product designation and name of one manufacturer are listed for each hardware type required for the purpose of establishing minimum requirements. Provide either the product designated or, where more than one manufacturer is specified under the Article "Manufacturers" in Part 2 for each hardware type, the comparable product of one of the other manufacturers that complies with requirements.

## 2.3 MATERIALS AND FABRICATION

- A. General
  - 1. Manufacturer's Name Plate: Do not use manufacturers' products that have manufacturer's name or trade name displayed in a visible location (omit removable nameplates) except in conjunction with required fire-rated labels and as otherwise acceptable to Architect.
    - a. Manufacturer's identification will be permitted on rim of lock cylinders only.
  - 2. Base Metals: Produce hardware units of basic metal and forming method indicated using manufacturer's standard metal alloy, composition, temper, and hardness, but in no case of lesser (commercially recognized) quality than specified for applicable hardware units for finish designations indicated.
  - 3. Provide hardware manufactured to conform to published templates generally prepared for machine screw installation. Do not provide hardware that has been prepared for self-tapping sheet metal screws, except as specifically indicated.
- B. Fasteners
  - 1. Furnish screws for installation with each hardware item. Provide Phillips flat-head screws except as otherwise indicated. Furnish stainless steel (exposed under any condition) screws to match hardware finish or, if exposed in surfaces of other work, to match finish of this other work as closely as possible including "prepared for paint" surfaces to receive painted finish.
  - 2. Provide concealed fasteners for hardware units that are exposed when door is closed except to the extent no standard units of type specified are available with concealed fasteners. Use through bolts only as indicated in this section unless their use is the only means of reinforcing the work adequately to fasten the hardware securely. Where thru-bolts are used as a means of reinforcing the work, provide sleeves for each thru-bolt or use sex screw fasteners.

## 2.4 HINGES

- A. Acceptable Products:

1. Ives: 3CB1HW
2. Hager: AB750
3. McKinney: TB786

B. Requirements:

1. Quantity: Provide the following, unless otherwise indicated:
  - a. Two Hinges: For doors with heights up to 60 inches.
  - b. Three Hinges: For doors with heights 61 to 90 inches.
2. Template Requirements: Except for hinges and pivots to be installed entirely (both leaves) into wood doors and frames, provide only template-produced units.
3. Hinge Weight: As indicated in hardware sets.
4. Hinge Base Metal: Unless otherwise indicated, provide the following:
  - a. Exterior Hinges: Stainless steel with stainless-steel pin.
  - b. Interior Hinges: Steel with steel pin.
  - c. Hinges for Fire-Rated Assemblies: Steel with steel pin.
5. Hinge Options: Where indicated in door hardware sets or on Drawings:
  - a. Safety Stud: Designed for stud in one leaf to engage hole in opposing leaf.
  - b. Non-removable Pins: Provide set screw in hinge barrel that, when tightened into a groove in hinge pin, prevents removal of pin while door is closed; for out-swinging doors.
  - c. Corners: Square.
6. Fasteners: Comply with the following:
  - a. Machine Screws: For metal doors and frames. Install into drilled and tapped holes.
  - b. Wood Screws: For wood doors and frames.
  - c. Threaded-to-the-Head Wood Screws: For fire-rated wood doors.

2.5 CONTINUOUS HINGES

A. Acceptable Continuous Hinge Products:

1. Ives: 705-HT
2. Stanley: 651-HT
3. Hager: 790-900-HT
4. Select: SL300-HT

B. Acceptable Double Swing Continuous Hinge Products:

1. Pemko: DSH1000

C.

D. Flush Bolt Locking Behavioral Health Hinge Emergency Release Stop:

1. Pemko: ERS

E. Requirements:

1. Pin and Barrel Continuous Hinges: Shall be a twin self-lubricated nylon bearing type with stainless steel pin. The door leaf and jamb leaf shall be fully mortised. Vertical door loads shall be carried on minimum 3/4" bearings through a full 180 degrees. The door leaf and jamb leaf shall have template screw hole locations for future replacement needs.

F. Requirements:

1. Pin and Barrel Continuous Hinges: Shall be a twin self-lubricated nylon bearing type with stainless steel pin. The door leaf and jamb leaf shall be fully mortised. Vertical door loads shall be carried on minimum 3/4" bearings through a full 180 degrees. The door leaf and jamb leaf shall have template screw hole locations for future replacement needs.

2.6 ELECTRIC STRIKES

A. Acceptable Products:

1. Von Duprin: 6000 Series
2. HES: 1006 Series

B. Requirements:

1. Provide electric strikes that are continuous duty rated without the use of external rectifiers.
2. Provide electric strikes with function (fail safe, fail secure) and power requirements as scheduled.

2.7 LOCKS AND LATCHES

A. General:

1. Lock Chassis: Shall be made from steel, with locking spindles of stainless steel.
2. Latch Bolt: Shall be constructed of stainless steel with 3/4 inch throw on mortise locks and 1/2 inch throw otherwise. Latch to be deadlocking on keyed functions.
3. Lever Trim: Shall be pressure cast brass, bronze, zinc, or steel with wrought rose design. Levers are to be solid with no voids or plastic inserts.
4. Fire Rating: Lock shall be listed for up to 3 hours.
5. Strike Plates: Provide ANSI 4-7/8 inch strike plates. At pairs of doors, provide strike with 7/8 inch flat lip. At single doors, provide round-lipped strike with lip length as required to minimally clear jamb and trim. Provide dust box at each strike location.

B. Grade 1 Bored Locks

1. Acceptable Products:
  - a. Schlage: ND Series, Rhodes Lever
  - b. Owner's Standard
2. Provide cylindrical locks exceeding the ANSI/BHMA A156.2 Grade 1 performance standards for strength, security & durability in the categories below:
  - a. Abusive locked lever torque – minimum 3,100 inch-pounds without gaining access
  - b. Offset lever pull - minimum 1,600 foot pounds without gaining access. Simulates pry-bar attacks
  - c. Vertical lever impact - minimum 100 impacts without gaining access. Simulates sledgehammer-blows to trim, very aggressive abuse
  - d. Cycle life - minimum 16 million cycles Cycle life speaks to robustness of lock, ensuring operation after 10M cycles (BHMA requirement is 1M).
    - 1) With no visible lever sag Working after 15M cycles is not the same as working well. No droop and wobble means the lock still works like new after the test.
    - 2) Without the use of performance aids (i.e. set screws, spacers, etc.). Set screws and spacers are a poor fix for droop and wobble. Both add to installation complexity, and set screws can be tamper targets.
  - e. Door Prep: Provide lockset to install using a standard ANSI 161 door preparation.
  - f. Anti-Rotation Plate: Provide lockset with a mechanically interlocked anti-rotation plate. Anti-Rotation teeth or “bite tabs” are not acceptable. Locks without any rotation prevention devices are not acceptable.
  - g. Lever Return Springs: Provide each lever with two compression type return springs that are easily accessible without dismantling the lock chassis. Locks utilizing tension or torsion lever return springs are unacceptable. Locks with internal springs that require dismantling the lock chassis are unacceptable.
  - h. Lever Spindles: Provide lock with either milled or 1-piece deep drawn spindles. 2-piece interlocking stamped spindles are not acceptable.
  - i. Multi-Functionality: Provide modular lockset with capability to convert to a new lock function by changing key cams.
  - j. Vandal Resistant Lever: Where scheduled, provide lockset with lever that freely rotates even when locked to resist vandalism and abuse.

2.8 CYLINDERS AND CORES

A. Provided by Owner

B. Requirements:

- a. Temporary Construction Keying: Provide each cylinder housing and/or lock lever with keyed construction core during the construction period. Cores will remain

property of the contractor and will be returned upon installation of owner's permanent key system.

## 2.9 EXIT DEVICES

### A. Acceptable Products:

1. Von Duprin: 98 Series
2. Owner's Standard

### B. Requirements:

1. ANSI Grade: BHMA/ANSI A156.3, Grade 1.
2. Device Construction:
  - a. Exit device(s) shall have a mechanism case constructed of extruded aluminum, base plates constructed of cold rolled or cast steel, push pad of extruded aluminum with stainless steel covering or wrought stainless steel, and end caps with flush mounted, sloped design. At full-glass doors, provide exit devices with no exposed fasteners or rivets visible through glass. Where required by stile width, provide narrow-stile type device.
  - b. Latchbolt: Provide Pullman-type deadlocking latch bolts constructed of stainless steel. Where specified provide high security Pullman-type latchbolt that collapses to be square faced under high pull forces. Latch return springs shall be compression type. Tension and Torsion latch return springs are not acceptable. Latchbolts to be mollydagged.
  - c. Dogging Mechanism: where dogging or latch-retraction options are not specifically scheduled for non-fire rated doors, provide device with a hex-key activated hook-type dogging mechanism constructed of steel.
  - d. Plastic or nylon used for the push pad, or parts in the dogging mechanism or latchbolt mechanism are unacceptable.
  - e. Sound Dampening: Device shall be provided with factory-installed sound dampening materials.
  - f. Provide device type, function, and trim style as indicated in hardware schedules.
3. Where exit device(s) are provided for fire rated door, provide with fire listing and label indicating "Fire Exit Hardware". If device is mounted on wood doors, provide sex nuts and bolts.
4. Provide shim kits, filler plates, and other accessories as required for each opening.
5. Unless otherwise indicated in the sets, provide device with roller-type strike.
6. Where scheduled, provide removable mullions by same manufacturer as provided exit devices. Provide mullion stabilizers, key removable option, strike preps, and fire rating as indicated in sets.

## 2.10 MECHANICAL DOOR CLOSERS

### A. General:

1. Valves: Closers shall have separate valves for latch speed, main speed, and back check. Valves shall be staked to prevent accidental removal. Internal Pressure Relief Valves (PRVs) are prohibited. Provide closers at exterior doors with "Advanced Variable Backcheck" for further protection from wind and abuse forces.
2. Provide the appropriate closer body, handing, and brackets to mount closer inside the building on the least-public side of the door.
  - a. Where closers are to be mounted parallel arm, provide with heavy duty, fully forged arms.
  - b. Where closers are to be mounted regular arm and the opening can otherwise be opened to 180 degrees, provide closer with the appropriate special templating to allow 180 degree door swing. Where a special template is not available for 180 degree swing, provide closer arm with integrated stop.
3. Integrated Stop Closer Arms: Where a closer with integrated stop is required, provide the appropriate closer and arm as follows:
  - a. Parallel arm with spring-cushioned stop arm: Provide where door is otherwise able to open to 95 degrees and requires a parallel arm mount closer.
  - b. Parallel arm with dead stop arm: Provide where door is obstructed from opening to 95 degrees and requires a parallel arm mount closer.
  - c. Regular arm with push side surface-mounted overhead stop: Provide where door closer should mount on pull side of door.
4. Hold Open Arms: Provide closer arms with mechanical hold-opens as scheduled.
5. Provide closers with any special templates, brackets, plates, or other accessories required for interface with header, door, wall, and other hardware. Provide closers with screw packs containing thru-bolts, machine screws, and wood screws.
6. Closers to be application specific. Handed and sized appropriate to the opening.
7. Closers shall be provided with all-weather fluid and shall not require readjustment from 120 degrees F to -30 degrees F. Fluid shall be non-flaming and shall not fuel door or floor covering fires. Upon request, provide data indicating thermal properties of fluid.
8. Closers shall close and latch door when adjusted to meet accessibility requirements for door opening force: 8.5 lbs at exterior doors, 5 lbs at interior doors, and 15 lbs at labeled fire doors.

B. Heavy Duty Door Closers:

1. Acceptable Products:
  - a. LCN: 4011/4111
  - b. Owner's Standard
2. Requirements:
  - a. ANSI Grade: BHMA/ANSI A156.4, Grade 1.
  - b. Closer Construction: Closer shall have cast iron body with 1-1/2 inch steel piston, double heat treated pinion, 5/8 inch bearing journals, and full complement needle or caged ball bearings. Closer shall be adjustable from sizes 1 through 6.
  - c. Provide closers with spring size adjustment dial for ease of adjusting.

C. Closer Release Devices

1. Acceptable Products:

- a. LCN: SEM7800 Series
- b. ABH: 2000 Series

2. Requirements:

- a. Provide 35 pound electro-magnetic hold open device constructed of die cast metal or plastic. Electromagnet shall accept 120VAC, 24VDC, and/or 12VDC power from fire alarm. Provide mounting style as scheduled.

2.11 AUTOMATIC OPERATORS

A. Automatic Operators

1. Acceptable Products:

- a. LCN: 9500 Series
- b. Stanley: Magic Force
- c. Horton: HD Swing 4000LE
- d. Besam: SW100 Series

2. Requirements:

- a. Provide low energy automatic operator units that are electro-mechanical design complying with ANSI A156.19.
  - 1) Opening: Powered by DC motor working through reduction gears.
  - 2) Closing: Spring force.
  - 3) Manual, hydraulic, or chain drive closers: Not permitted.
  - 4) Operation: Motor is off when door is in closing mode. Door can be manually operated with power on or off without damage to operator. Provide variable adjustments, including opening and closing speed adjustment.
- b. Provide units with manual off/auto/hold-open switch, push and go function to activate power operator, vestibule interface delay, electric lock delay, hold-open delay adjustable from 2 to 30 seconds, and logic terminal to interface with accessories, mats, and sensors.
- c. Provide drop plates, brackets, or adapters for arms as required to suit details.
- d. Provide motion sensors and/or actuator switches for operation as specified. Provide weather-resistant actuators at exterior applications.
- e. Provide complete assemblies of controls, switches, power supplies, relays, and parts/material recommended and approved by manufacturer of automatic operator for each individual leaf.

B. Touch Operators

1. Acceptable Products:

- |    |          |           |
|----|----------|-----------|
| a. | LCN:     | 8310-836T |
| b. | Stanley: | equal     |
| c. | Horton:  | equal     |
| d. | Besam:   | equal     |

2.12 ARCHITECTURAL DOOR TRIM

A. Protection Plates

1. Acceptable Products:

- |    |           |             |
|----|-----------|-------------|
| a. | Ives:     | 8400 Series |
| b. | Rockwood: | K1050       |
| c. | Hager:    | 194S        |
| d. | Trimco:   | K Series    |

2. Requirements:

- a. Provide .050 inch thick stainless steel protection plates with height as scheduled. Plate shall have four beveled edges and countersunk screws. Provide plate with width as follows:
- 1) Pairs of Doors: Provide plate to be 1 inch less door width.
  - 2) Single Doors: Provide plate to be 2 inches less door width on push side, pull side mounted plates to be 1 inch less door width.

B. Door Stops and Holders

1. Acceptable Products:

- |    |           |           |       |
|----|-----------|-----------|-------|
| a. | Ives:     | WS406/407 | FS439 |
| b. | Rockwood: | 405/406   | 441H  |
| c. | Hager:    | 236W      | 242F  |
| d. | Trimco:   | 1270      | 1215  |

2. Requirements:

- a. Provide stops and holders as indicated in the hardware sets.
- b. Where wall bumpers are scheduled, provide concave rubber bumper where the adjacent lever trim incorporates a push-button. Otherwise, provide convex rubber bumpers.

2.13 GASKETS

A. General:

1. Provide weather strip and gasketing as scheduled.



2. Size weather strip and gasket to provide a continuous seal around opening and at meeting stiles.

B. Perimeter Seals

1. Acceptable Products:

- |    |                 |             |
|----|-----------------|-------------|
| a. | Zero:           | 488S-BK PSA |
| b. | National Guard: | 5050B       |
| c. | Pemko:          | S88D        |

C. Meeting Stiles

1. Acceptable Products:

- |    |                 |       |       |
|----|-----------------|-------|-------|
| a. | Zero:           | 56AA  | 557AA |
| b. | National Guard: | equal | equal |
| c. | Pemko:          | equal | equal |

2. Requirements

- a. Where overlapping astragals are scheduled on out-swinging doors, provide for mounting on the pull-side of the active leaf. Otherwise, provide for mounting on the push-side of the inactive leaf.

## 2.14 MISCELLANEOUS HARDWARE

A. Silencers

1. Acceptable Products:

- |    |           |       |
|----|-----------|-------|
| a. | Ives:     | SR64  |
| b. | Rockwood: | 608   |
| c. | Hager:    | 307D  |
| d. | Trimco:   | 1229A |

2. Requirements:

- a. Where indicated on single openings, provide 3 each rubber silencers on lock jamb.
- b. Where indicated on paired openings, provide 2 each rubber silencers on header.

## 2.15 ELECTRONIC ACCESSORIES

A. Power Supplies

1. Acceptable Products:

- |    |                                  |              |
|----|----------------------------------|--------------|
| a. | Von Duprin:                      | PS900 Series |
| b. | Match existing facility standard |              |

2. Requirements:

- a. Provide power supplies, recommended and approved by the manufacturer of the electrified locking component, for the operation of electrified locks, electrified exit devices, magnetic locks, electric strikes, and other components requiring a power supply.
- b. Provide the appropriate quantity of power supplies necessary for the proper operation of the electrified locking component and/or components as recommended by the manufacturer of the electrified locking components with consideration for each electrified component utilizing the power supply, the location of the power supply, and the approved wiring diagrams. Locate the power supplies as directed by the Architect.
- c. Provide a power supply that is regulated and filtered 24 VDC, or as required, and UL class 2 listed.
- d. Options: Provide the following options.
  - 1) Provide a power supply, where specified, with the internal capability of charging optional sealed backup batteries 24 VDC, or as required, in addition to operating the DC load.
  - 2) Provide sealed batteries for battery back-up at each power supply where scheduled.
  - 3) Provide keyed power supply cabinet.
  - 4) Provide a power supply complete requiring only 120VAC to the fused input and shall be supplied in an enclosure.
- e. Provide a power supply with emergency release terminals, where required, that allow the release of all devices upon activation of the fire alarm system complete with fire alarm input for initiating "no delay" exiting mode.

B. Electric Power Transfers

1. Acceptable Products:

- a. Von Duprin: EPT-10

2. Requirements:

- a. Provide edge-mounted electric power transfer with either two 18 gauge wires or ten 24 gauge wires as scheduled.

C. Door Contacts

1. Acceptable Products:

- a. Schlage Electronics: 679-05HM
- b. Securitron: DPS Series
- c. Security Door Controls: MC-4

2. Requirements:

- a. Provide concealed, edge-mounted door contacts as appropriate for door/frame material.
- b. Provide 7764 door contacts where scheduled on fire rated openings, otherwise provide 679-05 switches.

D. Motion Sensors Request to Exit

1. Acceptable Products:

- |    |                         |                   |
|----|-------------------------|-------------------|
| a. | Schlage Electronics:    | SCAN II 12/24 VDC |
| b. | Securitron:             | XMS Series        |
| c. | Security Door Controls: | MD31 Series       |

2. Requirements:

- a. Provide surface mounted infrared motion sensor as indicated in the sets.

E. Wire Harness and Power Supply:

1. Acceptable Products:

- |    |                         |       |        |
|----|-------------------------|-------|--------|
| a. | Schlage Electronics:    | CON-X | CON-6W |
| b. | Securitron:             | equal | equal  |
| c. | Security Door Controls: | equal | equal  |

2.16 FINISHES

- A. Match items to the manufacturer's standard color and texture finish for the latch and locksets (or push-pull units if no latch or locksets).
- B. Provide quality of finish, including thickness of plating or coating (if any), composition, hardness, and other qualities complying with manufacturer's standards, but in no case less than specified by referenced standards for the applicable units of hardware.
- C. The designations used in schedules and elsewhere to indicate hardware finishes are those listed in ANSI/BHMA A156.18, "Materials and Finishes," including coordination with the traditional U.S. finishes shown by certain manufacturers for their products.
- D. The designations used in schedules and elsewhere to indicate hardware finishes are the industry-recognized standard commercial finishes, except as otherwise noted.
  1. Brushed Chrome and/or Stainless Steel Appearance
    - a. Brushed Stainless Steel, no coating: ANSI 630.
    - b. Satin Chrome, Clear Coated: ANSI 626, ANSI 652.
    - c. Powder Coated Aluminum finish: ANSI 689.
    - d. Saddle and Panic Thresholds: Mill Aluminum finish.
    - e. Weatherstrip and Gasket: Clear Anodized Aluminum finish.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine doors and frames, with Installer present, for compliance with requirements for installation tolerances, labeled fire door assembly construction, wall and floor construction, and other conditions affecting performance.
- B. Examine roughing-in for electrical power systems to verify actual locations of wiring connections before electrified door hardware installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Steel Doors and Frames: Comply with DHI A115 Series.
  - 1. Surface-Applied Door Hardware: Drill and tap doors and frames according to ANSI A250.6.

### 3.3 INSTALLATION

- A. Pre-installation conference shall be conducted prior to installation of hardware at Project site. Meet with the, Owner, Contractor, installer, and manufacturer's representatives. A separate pre-installation conference shall be conducted prior to the installation of electronic security hardware with the electrical contractor Review catalogs, brochures, templates, installation instructions, and the approved hardware schedule. Survey installation procedures and workmanship, with special emphasis on unusual conditions, as to ensure correct technique of installation, and coordination with other work. Notify participants at least ten, 10 working days before conference.
- B. Hardware Installers must have a minimum of five (5) years' experience in installation of hardware. Provide verification of installer's qualification to Consultant for approval. All installers to attend review meetings with the hardware distributor.
- C. Install hardware using only manufacturer supplied and approved fasteners in strict adherence with manufacturers published installation instructions.
- D. Install head seal prior to installation of "PA"-parallel arm mounted door closers and push side mounted door stops/holders. Trim, cut and notch thresholds and saddles neatly to minimally fit the profile of the door frame. Install thresholds and saddles in a bed of caulking completely sealing the underside from water and air penetration.
- E. Mounting Heights: Mount door hardware units at heights indicated, as follows, unless otherwise indicated or required to comply with governing regulations.
  - 1. Standard Steel Doors and Frames: DHI's "Recommended Locations for Architectural Hardware for Standard Steel Doors and Frames."

- F. Install each door hardware item to comply with manufacturer's written instructions. Where cutting and fitting are required to install door hardware onto or into surfaces that are later to be painted or finished in another way, coordinate removal, storage, and reinstallation of surface protective trim units with finishing work specified in Division 09 Sections. Do not install surface-mounted items until finishes have been completed on substrates involved.
  - 1. Set units level, plumb, and true to line and location. Adjust and reinforce attachment substrates as necessary for proper installation and operation.
  - 2. Drill and countersink units that are not factory prepared for anchorage fasteners. Space fasteners and anchors according to industry standards.
- G. Furnish wiring diagrams to electrical contractor for use in installing electrical hardware products.
  - 1. Electrical contractor to run all wiring and make all final connections for electrified hardware. Hardware supplier shall be responsible to furnish all wiring diagrams to operate electrified hardware. Access control material and electrified hardware to interface at junction boxes.
- H. Boxed Power Supplies: Locate power supplies as indicated. Verify location with Architect.
  - 1. Configuration: Provide one power supply for each door opening.
  - 2. Configuration: Provide the least number of power supplies required to adequately serve doors with electrified door hardware.

### 3.4 FIELD QUALITY CONTROL

- A. Architectural Hardware Consultant: Architect shall engage a qualified Architectural Hardware Consultant to perform inspections and to prepare inspection reports.
- B. Architectural Hardware Consultant shall inspect door hardware and state in each report whether installed work complies with or deviates from requirements, including whether door hardware is properly installed and adjusted.

### 3.5 ADJUSTING

- A. Initial Adjustment: Adjust and check each operating item of door hardware and each door to ensure proper operation or function of every unit. Replace units that cannot be adjusted to operate as intended. Adjust door control devices to compensate for final operation of heating and ventilating equipment and to comply with referenced accessibility requirements.
  - 1. Electric Strikes: Adjust horizontal and vertical alignment of keeper to properly engage lock bolt.
  - 2. Door Closers: Unless otherwise required by authorities having jurisdiction, adjust sweep period so that, from an open position of 70 degrees, the door will take at least 3 seconds to move to a point 3 inches (75 mm) from the latch, measured to the leading edge of the door.

- B. Occupancy Adjustment: Approximately six months after date of Substantial Completion, Installer's Architectural Hardware Consultant shall examine and readjust, including adjusting operating forces, each item of door hardware as necessary to ensure function of doors, door hardware, and electrified door hardware.

### 3.6 CLEANING AND PROTECTION

- A. Clean adjacent surfaces soiled by door hardware installation.
- B. Clean operating items as necessary to restore proper function and finish.
- C. Provide final protection and maintain conditions that ensure that door hardware is without damage or deterioration at time of Substantial Completion.

### 3.7 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain door hardware and door hardware finishes. Refer to Division 01 Section "Demonstration and Training."

### 3.8 DOOR HARDWARE SETS

- A. The following schedule of hardware sets shall be considered a guide and the supplier is cautioned to refer to general conditions, special conditions, and the full requirements of this section. It shall be the hardware supplier's responsibility to furnish all required hardware.
- B. Where items of hardware are not definitely or correctly specified and are required for completion of the Work, a written statement of such omission, error, conflict, or other discrepancy shall be sent to the Architect, prior to date specified for receipt of bids, for clarification by addendum.
- C. Adjustments to the Contract Sum will not be allowed for omissions or items of hardware not clarified prior to bid opening.

**HW SET: 01**

**For use on Door #(s):**

3611.1                      3513.1

Each to have:

|   |    |                               |                                               |         |     |
|---|----|-------------------------------|-----------------------------------------------|---------|-----|
| 2 | EA | CONT. HINGE                   | 705-HT EPT                                    | 630     | IVE |
| 2 | EA | POWER TRANSFER                | EPT10 CON                                     | ✓ 689   | VON |
| 2 | EA | ELEC FIRE EXIT<br>HARDWARE    | LX-RX-QEL-9827-L-F-LBR-06-499F-<br>CON 24 VDC | ✓ 626   | VON |
| 2 | EA | RIM CYLINDER                  | PROVIDED BY UU                                | 626     |     |
| 1 | EA | SURF. AUTO OPERATOR           | 9553 STD2 HL/D MS AS REQ<br>(120/240 VAC)     | ✓ ANCLR | LCN |
| 1 | EA | FULL LENGTH TOUCH<br>ACTUATOR | 8310-836T                                     | ✓ 630   | LCN |
| 2 | EA | ARMOR PLATE                   | 8400 36" X 2" LDW B-CS                        | 630     | IVE |
| 2 | EA | WALL STOP                     | WS406/407CCV                                  | 630     | IVE |
| 1 | EA | GASKETING                     | 488SBK PSA                                    | BK      | ZER |
| 1 | EA | MEETING STILE                 | 557AA                                         | AA      | ZER |
| 1 | EA | MEETING STILE                 | 56AA                                          | AA      | ZER |
| 2 | EA | WIRE HARNESS                  | CON-X (LENGTH AS REQ'D)                       | ✓       | SCH |
| 2 | EA | POWER SUPPLY WIRE<br>HARNESS  | CON-6W                                        | ✓       | SCH |
| 1 | EA | CREDENTIAL READER             | BY DIV 28                                     | ✓       | B/O |
| 2 | EA | DOOR CONTACT                  | 679-05HM                                      | ✓ BLK   | SCE |
| 1 | EA | POWER SUPPLY                  | PS902 900-2RS-FA 120/240 VAC                  | ✓       | VON |

CARD IN. USER PRESENTS CREDENTIAL, EXIT DEVICE LATCHES RETRACT, AUTO OPERATOR ENGAGES AND OPENS BOTH DOOR LEAFS. FROM HALLWAY 3200, USER PUSHES ACTUATOR TO ENGAGE AUTO OPERATOR TO OPEN BOTH DOOR LEAFS. DOOR POSITIONS ARE MONITORED BY ACCESS CONTROL/SECURITY SYSTEM. REQUEST TO EXIT IS IN EXIT DEVICE PUSH BARS

**HW SET: 02**

**For use on Door #(s):**

3325.1                      3327                      3404.1

Each to have:

|   |    |                    |                            |       |     |
|---|----|--------------------|----------------------------|-------|-----|
| 3 | EA | HINGE              | 3CB1 5 X 4.5               | 630   | IVE |
| 1 | EA | POWER TRANSFER     | EPT10 CON                  | ✓ 689 | VON |
| 1 | EA | VANDL EU STOREROOM | ND96LDEU RHO RX 12V/24V DC | ✓ 626 | SCH |
| 1 | EA | KIL CYLINDER       | PROVIDED BY UU             | 626   |     |
| 1 | EA | SURFACE CLOSER     | 4011 MC                    | 689   | LCN |
| 1 | EA | KICK PLATE         | 8400 10" X 2" LDW B-CS     | 630   | IVE |
| 1 | EA | WALL STOP          | WS406/407CCV               | 630   | IVE |
| 1 | EA | GASKETING          | 488SBK PSA                 | BK    | ZER |
| 1 | EA | CREDENTIAL READER  | BY DIV 28                  | ✓     | B/O |
| 1 | EA | DOOR CONTACT       | 679-05HM                   | ✓ BLK | SCE |
|   |    | POWER SUPPLY       | BY DIV 28                  | ✓     | B/O |

CARD IN. USER PRESENTS CREDENTIAL, ELECTRIC LOCKSET LEVER RELEASES, USER OPENS DOOR TO ENTER. DOOR POSITION IS MONITORED BY SECURITY SYSTEM, REX IS IN THE LOCKSET LEVER.

**HW SET: 03**

**For use on Door #(s):**

3307.1                      3411                      3413

Each to have:

|   |    |                    |                            |       |     |
|---|----|--------------------|----------------------------|-------|-----|
| 3 | EA | HINGE              | 3CB1 4.5 X 4.5             | 630   | IVE |
| 1 | EA | POWER TRANSFER     | EPT10 CON                  | ✓ 689 | VON |
| 1 | EA | VANDL EU STOREROOM | ND96LDEU RHO RX 12V/24V DC | ✓ 626 | SCH |
| 1 | EA | KIL CYLINDER       | PROVIDED BY UU             | 626   |     |
| 1 | EA | SURFACE CLOSER     | 4011 MC                    | 689   | LCN |
| 1 | EA | KICK PLATE         | 8400 10" X 2" LDW B-CS     | 630   | IVE |
| 1 | EA | WALL STOP          | WS406/407CCV               | 630   | IVE |
| 1 | EA | GASKETING          | 488SBK PSA                 | BK    | ZER |
| 1 | EA | CREDENTIAL READER  | BY DIV 28                  | ✓     | B/O |
| 1 | EA | DOOR CONTACT       | 679-05HM                   | ✓ BLK | SCE |
|   |    | POWER SUPPLY       | BY DIV 28                  | ✓     | B/O |

CARD IN. USER PRESENTS CREDENTIAL, ELECTRIC LOCKSET LEVER RELEASES, USER OPENS DOOR TO ENTER. DOOR POSITION IS MONITORED BY SECURITY SYSTEM, REX IS IN THE LOCKSET LEVER.



**HW SET: 04**

**For use on Door #(s):**

3309

Each to have:

|   |    |                |                        |     |     |
|---|----|----------------|------------------------|-----|-----|
| 3 | EA | HINGE          | 3CB1 4.5 X 4.5         | 630 | IVE |
| 1 | EA | STOREROOM LOCK | ND80LD RHO             | 626 | SCH |
| 1 | EA | KIL CYLINDER   | PROVIDED BY UU         | 626 |     |
| 1 | EA | SURFACE CLOSER | 4011 MC                | 689 | LCN |
| 1 | EA | KICK PLATE     | 8400 10" X 2" LDW B-CS | 630 | IVE |
| 1 | EA | WALL STOP      | WS406/407CCV           | 630 | IVE |
| 3 | EA | GASKETING      | 488SBK PSA             | BK  | ZER |

**HW SET: 05**

**For use on Door #(s):**

3307B

Each to have:

|   |    |                |                        |     |     |
|---|----|----------------|------------------------|-----|-----|
| 3 | EA | HINGE          | 3CB1 4.5 X 4.5         | 630 | IVE |
| 1 | EA | ENTRANCE LOCK  | ND53LD RHO             | 626 | SCH |
| 1 | EA | KIL CYLINDER   | PROVIDED BY UU         | 626 |     |
| 1 | EA | SURFACE CLOSER | 4011 MC                | 689 | LCN |
| 1 | EA | KICK PLATE     | 8400 10" X 2" LDW B-CS | 630 | IVE |
| 1 | EA | WALL STOP      | WS406/407CCV           | 630 | IVE |
| 3 | EA | SILENCER       | SR64                   | GRY | IVE |

**HW SET: 06**

**For use on Door #(s):**

3521.1

Each to have:

|   |    |                |                        |     |     |
|---|----|----------------|------------------------|-----|-----|
| 3 | EA | HINGE          | 3CB1HW 5 X 4.5         | 630 | IVE |
| 1 | EA | STOREROOM LOCK | ND80LD RHO             | 626 | SCH |
| 1 | EA | KIL CYLINDER   | PROVIDED BY UU         | 626 |     |
| 1 | EA | SURFACE CLOSER | 4011 MC                | 689 | LCN |
| 1 | EA | KICK PLATE     | 8400 10" X 2" LDW B-CS | 630 | IVE |
| 1 | EA | WALL STOP      | WS406/407CCV           | 630 | IVE |
| 3 | EA | SILENCER       | SR64                   | GRY | IVE |

**HW SET: 07**

**For use on Door #(s):**

3327A

Each to have:

|   |    |                  |                                          |      |     |
|---|----|------------------|------------------------------------------|------|-----|
| 4 | EA | HINGE            | 3CB1 5 X 4.5                             | 630  | IVE |
| 1 | EA | DUTCH DOOR BOLT  | 054                                      | 626  | IVE |
| 1 | EA | STOREROOM LOCK   | ND80LD RHO                               | 626  | SCH |
| 1 | EA | KIL CYLINDER     | PROVIDED BY UU                           | 626  |     |
| 1 | EA | FIRE/LIFE CLOSER | 4040SE MC TBWMS 24V/120V<br>AC/DC AS REQ | 689  | LCN |
| 1 | EA | KICK PLATE       | 8400 10" X 2" LDW B-CS                   | 630  | IVE |
| 1 | EA | GASKETING        | 488SBK PSA                               | BK   | ZER |
| 1 | EA | ASTRAGAL         | 44STST                                   | STST | ZER |

OPERATION:DOOR HELD OPEN BY ELECTRONIC DOOR CLOSERCLOSER RELEASES UPON ALARM

**HW SET: 08**

**For use on Door #(s):**

3301                      3303                      3325.2                      3402.2                      T3309

Each to have:

|   |    |                |                        |     |     |
|---|----|----------------|------------------------|-----|-----|
| 3 | EA | HINGE          | 3CB1 4.5 X 4.5         | 630 | IVE |
| 1 | EA | PASSAGE SET    | ND10S RHO              | 626 | SCH |
| 1 | EA | SURFACE CLOSER | 4011 MC                | 689 | LCN |
| 1 | EA | KICK PLATE     | 8400 10" X 2" LDW B-CS | 630 | IVE |
| 1 | EA | WALL STOP      | WS406/407CCV           | 630 | IVE |
| 1 | EA | GASKETING      | 488SBK PSA             | BK  | ZER |

**HW SET: 09**

**For use on Door #(s):**

3404.2                      3415.1                      3415.2                      3521.2                      3611.2

Each to have:

|   |    |                |                        |     |     |
|---|----|----------------|------------------------|-----|-----|
| 3 | EA | HINGE          | 3CB1HW 5 X 4.5         | 630 | IVE |
| 1 | EA | PASSAGE SET    | ND10S RHO              | 626 | SCH |
| 1 | EA | SURFACE CLOSER | 4011 MC                | 689 | LCN |
| 1 | EA | KICK PLATE     | 8400 10" X 2" LDW B-CS | 630 | IVE |
| 1 | EA | WALL STOP      | WS406/407CCV           | 630 | IVE |
| 1 | EA | GASKETING      | 488SBK PSA             | BK  | ZER |

**HW SET: 10**

**For use on Door #(s):**

3307A T3307

Each to have:

|   |    |                |                        |     |     |
|---|----|----------------|------------------------|-----|-----|
| 3 | EA | HINGE          | 3CB1 4.5 X 4.5         | 630 | IVE |
| 1 | EA | ENTRANCE LOCK  | ND53LD RHO             | 626 | SCH |
| 1 | EA | KIL CYLINDER   | PROVIDED BY UU         | 626 |     |
| 1 | EA | SURFACE CLOSER | 4011 MC                | 689 | LCN |
| 1 | EA | KICK PLATE     | 8400 10" X 2" LDW B-CS | 630 | IVE |
| 1 | EA | WALL STOP      | WS406/407CCV           | 630 | IVE |
| 1 | EA | GASKETING      | 488SBK PSA             | BK  | ZER |

**HW SET: 11**

**For use on Door #(s):**

3315.1 3315.1

Each to have:

|   |    |                |                        |     |     |
|---|----|----------------|------------------------|-----|-----|
| 3 | EA | HINGE          | 3CB1 4.5 X 4.5         | 630 | IVE |
| 1 | EA | PUSH PLATE     | 8200 6" X 16"          | 630 | IVE |
| 1 | EA | PULL PLATE     | 8305 10" 4" X 16"      | 630 | IVE |
| 1 | EA | SURFACE CLOSER | 4011 MC                | 689 | LCN |
| 1 | EA | KICK PLATE     | 8400 10" X 2" LDW B-CS | 630 | IVE |
| 1 | EA | WALL STOP      | WS406/407CCV           | 630 | IVE |
| 1 | EA | GASKETING      | 488SBK PSA             | BK  | ZER |

**HW SET: 12**

**For use on Door #(s):**

3320 3335A

Each to have:

|    |      |                                            |
|----|------|--------------------------------------------|
| EA | NOTE | SALVAGED DOOR, ALL<br>HARDWARE IS EXISTING |
|----|------|--------------------------------------------|

## SECTION 08 8005 – INTERIOR GLAZING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes:
  - 1. Glass for interior doors
  - 2. Frosted glass film overlay.
  - 3. Glazing sealants and accessories.
- B. Related Requirements:
  - 1. Section 08 8813 "Fire-Resistant Glazing."

#### 1.3 DEFINITIONS

- A. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.
- B. Glass Thicknesses: Indicated by thickness designations in millimeters according to ASTM C 1036.
- C. IBC: International Building Code.

#### 1.4 COORDINATION

- A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.

#### 1.5 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
  - 1. Review and finalize construction schedule and verify availability of materials, Installer's personnel, equipment, and facilities needed to make progress and avoid delays.
  - 2. Review temporary protection requirements for glazing during and after installation.

## 1.6 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Glass Samples: For each type of the following products; 12 inches square.
  - 1. Clear glass with frosted glass film overlay.
- C. Glazing Accessory Samples: For sealants, in 12-inch lengths. Install sealant Samples between two strips of material representative in color of the adjoining framing system.
- D. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

## 1.7 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Certificates: For glass.
- C. Product Test Reports: For glazing sealants, for tests performed by a qualified testing agency.
  - 1. For glazing sealants, provide test reports based on testing current sealant formulations within previous 36-month period.
- D. Preconstruction adhesion and compatibility test report.
- E. Sample Warranties: For special warranties.
- F. Maintenance data for frosted glass films.

## 1.8 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Two extra pieces of tempered glass or 2 percent over the total quantity installed, whichever is greater. Provide each non-stock glass size to the Owner in storage crates. Coordinate with the Owner's Project Manager for delivery instructions.

## 1.9 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs glass installers for this Project who are certified under the National Glass Association's Certified Glass Installer Program.
- B. Sealant Testing Agency Qualifications: An independent testing agency qualified according to ASTM C 1021 to conduct the testing indicated.

1.10 DELIVERY, STORAGE, AND HANDLING

- A. Protect glazing materials according to manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

1.11 FIELD CONDITIONS

- A. Environmental Limitations: Do not proceed with glazing when ambient and substrate temperature conditions are outside limits permitted by glazing material manufacturers and when glazing channel substrates are wet from rain, frost, condensation, or other causes.
  - 1. Do not install glazing sealants when ambient and substrate temperature conditions are outside limits permitted by sealant manufacturer or are below 40 deg F.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Cardinal Glass Industries.
  - b. Guardian Industries Corp.
  - c. Oldcastle BuildingEnvelope.
  - d. Pilkington North America.
  - e. Viracon.
- B. Source Limitations for Glass: Obtain from single source from single manufacturer for each glass type.
- C. Source Limitations for Glazing Accessories: Obtain from single source from single manufacturer for each product and installation method.

2.2 PERFORMANCE REQUIREMENTS

- A. General: Installed glazing systems shall withstand normal thermal movement and impact loads (where applicable) without failure, including loss or glass breakage attributable to the following: defective manufacture, fabrication, or installation; failure of sealants or gaskets to remain watertight and airtight; deterioration of glazing materials; or other defects in construction.
- B. Safety Glazing: Where safety glazing is indicated, provide glazing that complies with 16 CFR 1201, Category II.

- C. Optical Performance Properties: Provide glass with performance properties specified, as indicated in manufacturer's published test data, based on procedures indicated below:

- 1. For monolithic-glass lites, properties are based on units with lites 6 mm thick.

## 2.3 GLASS PRODUCTS, GENERAL

- A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organizations below unless more stringent requirements are indicated. See these publications for glazing terms not otherwise defined in this Section or in referenced standards.
  - 1. GANA Publications: "Glazing Manual."
- B. Safety Glazing Labeling: Where safety glazing is indicated, permanently mark glazing with certification label of the SGCC or another certification agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, type of glass, thickness, and safety glazing standard with which glass complies.
- C. Thickness: Where glass thickness is indicated, it is a minimum. Provide glass that complies with performance requirements and is not less than the thickness indicated.

## 2.4 GLASS PRODUCTS

- A. Fully Tempered Float Glass G-3: ASTM C 1048, Kind FT (fully tempered), Condition A (uncoated) unless otherwise indicated, Type I, Class 1 (clear) or Class 2 (tinted) as indicated, Quality-Q3.
  - 1. Fabrication Process: By horizontal (roller-hearth) process with roll-wave distortion parallel to bottom edge of glass as installed unless otherwise indicated.

## 2.5 FROSTED GLASS VINYL FILM OVERLAY

- A. Cast PVC Film: Translucent, frosted glass, dimensionally stable cast PVC film, 2-mil minimum thickness, with pressure-sensitive clear adhesive back for adhering to glass and with releasable protective backing.
  - 1. Manufacturers: Subject to compliance with requirements, provide product by one of the following:
    - a. Avery Dennison Graphics Division.
    - b. FDC Graphic Films, Inc.
    - c. Spar-Cal Division, Spartan International.
    - d. 3M Commercial Graphics Division.
  - 2. Opacity: As selected by Architect.
  - 3. Color: As selected by Architect.

4. Use: Indicated interior applications.

## 2.6 GLAZING SEALANTS

### A. General:

1. Compatibility: Compatible with one another and with other materials they contact, including glass products, and glazing channel substrates, under conditions of service and application, as demonstrated by sealant manufacturer based on testing and field experience.
2. Suitability: Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated and for conditions existing at time of installation.
3. Field-applied sealants shall have a VOC content of not more than 250 g/L.
4. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range.

### B. Glazing Sealant: Neutral-curing silicone glazing sealant complying with ASTM C 920, Type S, Grade NS, Class 50, Use NT.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. BASF Building Systems.
  - b. Dow Corning Corporation.
  - c. GE Construction Sealants; Momentive Performance Materials Inc.
  - d. Sika Corporation.

## 2.7 GLAZING TAPES

### A. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C 1281 and AAMA 800 for products indicated below:

1. AAMA 804.3 tape, where indicated.
2. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
3. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.

### B. Expanded Cellular Glazing Tapes: Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:

1. AAMA 810.1, Type 1, for glazing applications in which tape acts as the primary sealant.
2. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.



## 2.8 MISCELLANEOUS GLAZING MATERIALS

- A. General: Provide products of material, size, and shape complying with referenced glazing standard, with requirements of manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.
- B. Cleaners, Primers, and Sealers: Types recommended by sealant or gasket manufacturer.
- C. Setting Blocks: Elastomeric material with a Shore, Type A durometer hardness of 85, plus or minus 5.
- D. Spacers: Elastomeric blocks or continuous extrusions of hardness required by glass manufacturer to maintain glass lites in place for installation indicated.
- E. Edge Blocks: Elastomeric material of hardness needed to limit glass lateral movement (side walking).
- F. Cylindrical Glazing Sealant Backing: ASTM C 1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.

## 2.9 FABRICATION OF GLAZING UNITS

- A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.
  - 1. Allow for thermal movements from ambient and surface temperature changes acting on glass framing members and glazing components.
    - a. Temperature Change: 120 deg F, ambient; 180 deg F, material surfaces.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine framing, glazing channels, and stops, with Installer present, for compliance with the following:
  - 1. Manufacturing and installation tolerances, including those for size, squareness, and offsets at corners.
  - 2. Minimum required face and edge clearances.
  - 3. Effective sealing between joints of glass-framing members.

- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.
- B. Examine glazing units to locate exterior and interior surfaces. Label or mark units as needed so that exterior and interior surfaces are readily identifiable. Do not use materials that leave visible marks in the completed Work.

### 3.3 GLAZING, GENERAL

- A. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials, unless more stringent requirements are indicated, including those in referenced glazing publications.
- B. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass includes glass with edge damage or other imperfections that, when installed, could weaken glass, impair performance, or impair appearance.
- C. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.
- D. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications, unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.
- E. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- F. Provide spacers for glass lites where length plus width is larger than 50 inches.
  - 1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances, unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
  - 2. Provide 1/8-inch minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.
- G. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.
- H. Set glass lites in each series with uniform pattern, draw, bow, and similar characteristics.

- I. Set glass lites with proper orientation so that coatings face exterior or interior as specified.

### 3.4 TAPE GLAZING

- A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.
- B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.
- C. Cover vertical framing joints by applying tapes to heads and sills first, then to jambs. Cover horizontal framing joints by applying tapes to jambs, then to heads and sills.
- D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.
- E. Do not remove release paper from tape until right before each glazing unit is installed.
- F. Apply heel bead of elastomeric sealant.
- G. Center glass lites in openings on setting blocks, and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.
- H. Apply cap bead of elastomeric sealant over exposed edge of tape.

### 3.5 GASKET GLAZING (DRY)

- A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.
- B. Insert soft compression gasket between glass and frame or fixed stop so it is securely in place with joints miter cut and bonded together at corners.
- C. Installation with Pressure-Glazing Stops: Center glass lites in openings on setting blocks, and press firmly against soft compression gasket. Install dense compression gaskets and pressure-glazing stops, applying pressure uniformly to compression gaskets. Compress gaskets to produce a weathertight seal without developing bending stresses in glass. Seal gasket joints with sealant recommended by gasket manufacturer.
- D. Install gaskets so they protrude past face of glazing stops.

### 3.6 SEALANT GLAZING (WET)

- A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances and to prevent sealant from extruding

into glass channel and blocking weep systems until sealants cure. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.

- B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.
- C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

### 3.7 FROSTED GLASS VINYL FILM OVERLAY INSTALLATION

- A. Cast PVC Film Installation: Apply squarely aligned to glass edges, uniformly smooth and free from tears, air bubbles, wrinkles, and rough edges. Apply in single sheet completely overlaying the back face of clean glass.
  - 1. Examine glass surfaces with Installer present, for compliance with manufacturing and installation tolerances, including size, squareness, and offsets at corners.
  - 2. Prepare surface and comply with application temperature limitations according to film manufacturer's written instructions.
  - 3. Install according to film manufacturer's written instructions.

### 3.8 CLEANING AND PROTECTION

- A. Immediately after installation remove nonpermanent labels and clean surfaces.
- B. Protect glass from contact with contaminating substances resulting from construction operations. Examine glass surfaces adjacent to or below masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains.
  - 1. If, despite such protection, contaminating substances do come into contact with glass, remove substances immediately as recommended in writing by glass manufacturer. Remove and replace glass that cannot be cleaned without damage to coatings.
- C. Remove and replace glass that is damaged during construction period.
- D. Wash glass on both exposed surfaces not more than four days before date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended in writing by glass manufacturer.

### 3.9 MONOLITHIC GLASS SCHEDULE

- A. Glass Type G-3: Clear fully tempered float glass.
  - 1. Minimum Thickness: 6 mm.
  - 2. Safety glazing required.

3. Frosted glass film: For glass units indicated on Door and Frame Schedule in the Drawings, apply to side of glass as directed by Architect.

- B. Fire-Rated Glazing: As specified in Section 08 8813 "Fire-Resistant Glazing."

END OF SECTION 08 8005

## SECTION 08 8813 - FIRE-RESISTANT GLAZING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Fire-resistance-rated glazing.
  - 2. Frosted glass film overlay.

#### 1.3 DEFINITIONS

- A. Glass Manufacturers: Firms that produce primary glass, fabricated glass, or both, as defined in referenced glazing publications.
- B. Glass Thicknesses: Indicated by thickness designations in millimeters according to ASTM C 1036.

#### 1.4 COORDINATION

- A. Coordinate glazing channel dimensions to provide necessary bite on glass, minimum edge and face clearances, and adequate sealant thicknesses, with reasonable tolerances.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Glass Samples: For each type of glass product; 12 inches square.
  - 1. Clear glass with frosted glass film overlay.
- C. Glazing Schedule: List glass types and thicknesses for each size opening and location. Use same designations indicated on Drawings.

1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For installers.
- B. Product Certificates: For each type of glass and glazing product, from manufacturer.
- C. Sample Warranties: For special warranties.

1.7 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. For fire-resistance-rated glass, provide two extra pieces of glass or 2 percent over the total quantity installed, whichever is greater. Provide each non-stock glass size to the Owner in storage crates. Coordinate with the Owner's Project Manager for delivery instructions.

1.8 QUALITY ASSURANCE

- A. Installer Qualifications: A qualified installer who employs glass installers for this Project who are certified under the National Glass Association's Certified Glass Installer Program.

1.9 DELIVERY, STORAGE, AND HANDLING

- A. Protect glazing materials according to manufacturer's written instructions. Prevent damage to glass and glazing materials from condensation, temperature changes, direct exposure to sun, or other causes.

1.10 FIELD CONDITIONS

- A. Environmental Limitations: Do not deliver or install fire-resistant glazing until spaces are enclosed and weathertight and temporary HVAC system is operating and maintaining ambient temperature conditions at occupancy levels during the remainder of the construction period.

1.11 WARRANTY

- A. Manufacturer's Special Warranty on Laminated Glass: Manufacturer agrees to replace laminated-glass units that deteriorate within specified warranty period. Deterioration of laminated glass is defined as defects developed from normal use that are not attributed to glass breakage or to maintaining and cleaning laminated glass contrary to manufacturer's written instructions. Defects include edge separation, delamination materially obstructing vision through glass, and blemishes exceeding those allowed by referenced laminated-glass standard.

1. Warranty Period: Five years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Source Limitations for Glass: Obtain from single source from single manufacturer for each glass type.
- B. Source Limitations for Glazing Accessories: Obtain from single source from single manufacturer for each product and installation method.

### 2.2 PERFORMANCE REQUIREMENTS

- A. General: Installed glazing systems shall withstand normal thermal movement and impact loads (where applicable) without failure, including loss or glass breakage attributable to the following: defective manufacture, fabrication, or installation; deterioration of glazing materials; or other defects in construction.

### 2.3 GLASS PRODUCTS, GENERAL

- A. Glazing Publications: Comply with published recommendations of glass product manufacturers and organization below unless more stringent requirements are indicated. Refer to these publications for glazing terms not otherwise defined in this Section or in referenced standards.
  1. GANA Publications: "Laminated Glazing Reference Manual" and "Glazing Manual."
- B. Safety Glazing Labeling: Permanently mark glazing with certification label of the Safety Glazing Certification Council or another certification agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, type of glass, glass thickness, and safety glazing standard with which glass complies.

### 2.4 GLASS PRODUCTS

- A. Laminated Glass: ASTM C 1172. Use materials that have a proven record of no tendency to bubble, discolor, or lose physical and mechanical properties after fabrication and installation.
  1. Construction: Laminate glass with polyvinyl butyral interlayer unless fire-protection or fire-resistance rating is based on another product.
  2. Interlayer Thickness: Provide thickness as needed to comply with requirements.
  3. Interlayer Color: Clear unless otherwise indicated.



## 2.5 FROSTED GLASS VINYL FILM OVERLAY

- A. Cast PVC Film: Translucent, frosted glass, dimensionally stable cast PVC film, 2-mil minimum thickness, with pressure-sensitive clear adhesive back for adhering to glass and with releasable protective backing.
  - 1. Manufacturers: Subject to compliance with requirements, provide product by one of the following:
    - a. Avery Dennison Graphics Division.
    - b. FDC Graphic Films, Inc.
    - c. Spar-Cal Division, Spartan International.
    - d. 3M Commercial Graphics Division.
  - 2. Opacity: As selected by Architect.
  - 3. Color: As selected by Architect.
  - 4. Use: Indicated 20-minute fire-resistance-rated glazing applications.

## 2.6 FIRE-RESISTANCE-RATED GLAZING

- A. Fire-Resistance-Rated Glazing: Listed and labeled by a testing agency acceptable to authorities having jurisdiction, for fire-resistance ratings indicated, based on testing according to ASTM E 119 or UL 263.
- B. Fire-Resistance-Rated Glazing Labeling: Permanently mark fire-resistance-rated glazing with certification label of a testing agency acceptable to authorities having jurisdiction. Label shall indicate manufacturer's name, test standard, that the glazing is approved for use in walls, and the fire-resistance rating in minutes.
- C. Laminated Glass with Intumescent Interlayers: Laminated glass made from multiple plies of uncoated, ultraclear float glass; with intumescent interlayers; and complying with 16 CFR 1201, Category II.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. AGC Glass Company North America, Inc.; Pyrobel.
    - b. SAFTI FIRST Fire Rated Glazing Solutions; SuperLite II-XLM 120.
    - c. Technical Glass Products; Pyrostop.
    - d. Vetrotech Saint-Gobain; SGG Contraflam.

## 2.7 GLAZING ACCESSORIES

- A. Provide glazing gaskets, glazing sealants, glazing tapes, setting blocks, spacers, edge blocks, and other glazing accessories that are compatible with glazing products and each other and are approved by testing agencies that listed and labeled fire-resistant glazing products with which products are used for applications and fire-protection ratings indicated.

- B. Glazing Sealants for Fire-Rated Glazing Products: Neutral-curing silicone glazing sealant complying with ASTM C 920, Type S, Grade NS, Class 50, Use NT. Comply with sealant and glass manufacturers' written instructions for selecting glazing sealants suitable for applications indicated.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Dow Corning Corporation.
    - b. GE Construction Sealants; Momentive Performance Materials Inc.
    - c. Tremco Commercial Sealants & Waterproofing.
  - 2. Sealants shall have a VOC content of 250 g/L or less.
  - 3. Colors of Exposed Glazing Sealants: As selected by Architect from manufacturer's full range.
- C. Back-Bedding Mastic Glazing Tapes: Preformed, butyl-based, 100 percent solids elastomeric tape; nonstaining and nonmigrating in contact with nonporous surfaces; with or without spacer rod as recommended in writing by tape and glass manufacturers for application indicated; and complying with ASTM C 1281 and AAMA 800 for products indicated below:
  - 1. AAMA 804.3 tape, where indicated.
  - 2. AAMA 806.3 tape, for glazing applications in which tape is subject to continuous pressure.
  - 3. AAMA 807.3 tape, for glazing applications in which tape is not subject to continuous pressure.
- D. Expanded Cellular Glazing Tapes: Closed-cell, PVC foam tapes; factory coated with adhesive on both surfaces; and complying with AAMA 800 for the following types:
  - 1. AAMA 810.1, Type 1, for glazing applications in which tape acts as the primary sealant.
  - 2. AAMA 810.1, Type 2, for glazing applications in which tape is used in combination with a full bead of liquid sealant.

## 2.8 MISCELLANEOUS GLAZING MATERIALS

- A. General: Provide products of material, size, and shape complying with referenced glazing standard, requirements of manufacturers of glass and other glazing materials for application indicated, and with a proven record of compatibility with surfaces contacted in installation.
- B. Cylindrical Glazing Sealant Backing: ASTM C 1330, Type O (open-cell material), of size and density to control glazing sealant depth and otherwise produce optimum glazing sealant performance.
- C. Perimeter Insulation for Fire-Resistive Glazing: Product that is approved by testing agency that listed and labeled fire-resistant glazing product with which it is used for application and fire-protection rating indicated.

## 2.9 FABRICATION OF GLAZING UNITS

- A. Fabricate glazing units in sizes required to fit openings indicated for Project, with edge and face clearances, edge and surface conditions, and bite complying with written instructions of product manufacturer and referenced glazing publications, to comply with system performance requirements.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine framing, glazing channels, and stops, with Installer present, for compliance with manufacturing and installation tolerances, including those for size, squareness, and offsets at corners, and for compliance with minimum required face and edge clearances.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Clean glazing channels and other framing members receiving glass immediately before glazing. Remove coatings not firmly bonded to substrates.
- B. Examine glazing units to locate fire side and protected side. Label or mark units as needed so that fire side and protected side are readily identifiable. Do not use materials that leave visible marks in the completed work.

### 3.3 GLAZING, GENERAL

- A. Use methods approved by testing agencies that listed and labeled fire-resistant glazing products.
- B. Comply with combined written instructions of manufacturers of glass, sealants, gaskets, and other glazing materials unless more stringent requirements are indicated, including those in referenced glazing publications.
- C. Protect glass edges from damage during handling and installation. Remove damaged glass from Project site and legally dispose of off Project site. Damaged glass is glass with edge damage or other imperfections that, when installed, could weaken glass and impair performance and appearance.
- D. Apply primers to joint surfaces where required for adhesion of sealants, as determined by preconstruction testing.
- E. Install setting blocks in sill rabbets, sized and located to comply with referenced glazing publications unless otherwise required by glass manufacturer. Set blocks in thin course of compatible sealant suitable for heel bead.

- F. Do not exceed edge pressures stipulated by glass manufacturers for installing glass lites.
- G. Provide spacers for glass lites where length plus width is larger than 50 inches.
  - 1. Locate spacers directly opposite each other on both inside and outside faces of glass. Install correct size and spacing to preserve required face clearances unless gaskets and glazing tapes are used that have demonstrated ability to maintain required face clearances and to comply with system performance requirements.
  - 2. Provide 1/8-inch minimum bite of spacers on glass and use thickness equal to sealant width. With glazing tape, use thickness slightly less than final compressed thickness of tape.
- H. Provide edge blocking where indicated or needed to prevent glass lites from moving sideways in glazing channel, as recommended in writing by glass manufacturer and according to requirements in referenced glazing publications.
- I. Set glass lites with proper orientation so that coatings face fire side or protected side as specified.

### 3.4 TAPE GLAZING

- A. Position tapes on fixed stops so that, when compressed by glass, their exposed edges are flush with or protrude slightly above sightline of stops.
- B. Install tapes continuously, but not necessarily in one continuous length. Do not stretch tapes to make them fit opening.
- C. Cover vertical framing joints by applying tapes to heads and sills first and then to jambs. Cover horizontal framing joints by applying tapes to jambs and then to heads and sills.
- D. Place joints in tapes at corners of opening with adjoining lengths butted together, not lapped. Seal joints in tapes with compatible sealant approved by tape manufacturer.
- E. Do not remove release paper from tape until right before each glazing unit is installed.
- F. Apply heel bead of elastomeric sealant.
- G. Center glass lites in openings on setting blocks and press firmly against tape by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.
- H. Apply cap bead of elastomeric sealant over exposed edge of tape.

### 3.5 GASKET GLAZING (DRY)

- A. Cut compression gaskets to lengths recommended by gasket manufacturer to fit openings exactly, with allowance for stretch during installation.

- B. Insert soft compression gasket between glass and frame or fixed stop, so it is securely in place with joints miter cut and bonded together at corners.
- C. Installation with Drive-in Wedge Gaskets: Center glass lites in openings on setting blocks and press firmly against soft compression gasket by inserting dense compression gaskets formed and installed to lock in place against faces of removable stops. Start gasket applications at corners and work toward centers of openings.
- D. Install gaskets so they protrude past face of glazing stops.

### 3.6 SEALANT GLAZING (WET)

- A. Install continuous spacers, or spacers combined with cylindrical sealant backing, between glass lites and glazing stops to maintain glass face clearances. Secure spacers or spacers and backings in place and in position to control depth of installed sealant relative to edge clearance for optimum sealant performance.
- B. Force sealants into glazing channels to eliminate voids and to ensure complete wetting or bond of sealant to glass and channel surfaces.
- C. Tool exposed surfaces of sealants to provide a substantial wash away from glass.

### 3.7 FROSTED GLASS VINYL FILM OVERLAY INSTALLATION

- A. Cast PVC Film Installation: Apply squarely aligned to glass edges, uniformly smooth and free from tears, air bubbles, wrinkles, and rough edges. Apply in single sheet completely overlaying the back face of clean glass.
  - 1. Examine glass surfaces with Installer present, for compliance with manufacturing and installation tolerances, including size, squareness, and offsets at corners.
  - 2. Prepare surface and comply with application temperature limitations according to film manufacturer's written instructions.
  - 3. Install according to film manufacturer's written instructions.

### 3.8 CLEANING AND PROTECTION

- A. Immediately after installation, remove nonpermanent labels and clean surfaces.
- B. Protect glass from contact with contaminating substances resulting from construction operations. Examine glass surfaces adjacent to or below exterior concrete and other masonry surfaces at frequent intervals during construction, but not less than once a month, for buildup of dirt, scum, alkaline deposits, or stains.
  - 1. If, despite such protection, contaminating substances do come into contact with glass, remove substances immediately as recommended in writing by glass manufacturer.

- C. Remove and replace glass that is damaged during construction period.
- D. Wash glass on both exposed surfaces in each area of Project not more than four days before date scheduled for inspections that establish date of Substantial Completion. Wash glass as recommended in writing by glass manufacturer.

### 3.9 FIRE-RESISTANT GLAZING SCHEDULE

- A. Glass Type FRGL-3: 45-minute fire-resistance-rated glazing with 450 deg F temperature-rise limitation; laminated glass with intumescent interlayers.
- B. Glass Type FRGL-4: 20-minute fire-resistance-rated glazing with 450 deg F temperature-rise limitation; laminated glass with intumescent interlayers.
  - 1. Frosted Glass Film: At indicated 20-minute fire-resistance-rated glazing units indicated on Door and Frame Schedule in the Drawings, apply to side of glass as directed by Architect.

END OF SECTION 08 8813

## SECTION 09 2116 - GYPSUM BOARD SHAFT WALL ASSEMBLIES

### 1.1 SUSTAINABILITY REQUIREMENTS

#### A. LEED 2009 for Healthcare:

1. Recycled content.
2. Regional materials.

### 1.2 GYPSUM BOARD SHAFT WALL ASSEMBLIES

- A. Fire-Resistance Rating: As indicated.
- B. STC Rating: 51, minimum.
- C. Gypsum shaft liner board, Type X.
- D. Non-load-bearing steel framing in manufacturer's standard profiles.
  - 1. Firestop tracks to allow movement.
- E. Finish Panels: Gypsum board.
- F. Sound attenuation blankets.

### 1.3 AUXILIARY MATERIALS

- A. Trim accessories.
- B. Steel drill screws.
- C. Track fasteners.
- D. Reinforcing.
- E. Acoustical sealant.
- F. Gypsum board cants.

END OF SECTION 09 2116

## SECTION 09 2216 - NON-STRUCTURAL METAL FRAMING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Non-load-bearing steel framing systems for interior gypsum board assemblies.
  - 2. Suspension systems for interior gypsum ceilings, soffits, and grid systems.
  - 3. Grid suspension systems for gypsum board ceilings.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Product Certificates: For each type of code-compliance certification for studs and tracks.
- B. Evaluation Reports: For embossed steel studs and tracks, from ICC-ES or other qualified testing agency acceptable to authorities having jurisdiction.

#### 1.5 QUALITY ASSURANCE

- A. Code-Compliance Certification of Studs and Tracks: Provide documentation that framing members are certified according to the product-certification program of the Certified Steel Stud Association the Steel Framing Industry Association or the Steel Stud Manufacturers Association.



## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For fire-resistance-rated assemblies that incorporate non-load-bearing steel framing, provide materials and construction identical to those tested in assembly indicated, according to ASTM E 119 by an independent testing agency.
- B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated on Drawings, according to ASTM E 90 and classified according to ASTM E 413-04 by an independent testing agency.
- C. Horizontal Deflection: For wall assemblies, limited to 1/240 of the wall height based on horizontal loading of 5 lbf/sq. ft.

### 2.2 FRAMING SYSTEMS

- A. Recycled Content of Steel Products: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. CEMCO; California Expanded Metal Products Co.
  - 2. Custom Stud.
  - 3. MarinoWARE.
  - 4. MRI Steel Framing, LLC.
  - 5. Phillips Manufacturing Co.
  - 6. SCAFCO Steel Stud Company.
  - 7. Steel Construction Systems.
  - 8. Steel Network, Inc. (The).
  - 9. Telling Industries.
- C. Framing Members, General: Comply with ASTM C 754-00 for conditions indicated.
  - 1. Steel Sheet Components: Comply with ASTM C 645-13 requirements for metal unless otherwise indicated.
  - 2. Protective Coating: ASTM A 653/A 653M, G40, hot-dip galvanized unless otherwise indicated.
- D. Studs and Tracks: ASTM C 645. Use either steel studs and tracks or embossed steel studs and tracks.
  - 1. Steel Studs and Tracks:
    - a. Minimum Base-Metal Thickness: As indicated on Structural Drawings.
    - b. Depth: As indicated on Drawings.

2. Embossed Steel Studs and Tracks: Roll-formed and embossed with surface deformations to stiffen the framing members so that they are structurally equivalent to conventional ASTM C 645 steel studs and tracks.
    - a. Minimum Base-Metal Thickness: As indicated on Structural Drawings.
    - b. Depth: As indicated on Drawings.
  - E. Slip-Type Head Joints: Where indicated, provide one of the following:
    1. Deflection Track: Steel sheet top track manufactured to prevent cracking of finishes applied to interior partition framing resulting from deflection of structure above; in thickness not less than indicated for studs and in width to accommodate depth of studs.
  - F. Flat Strap and Backing Plate: Steel sheet for blocking and bracing in length and width indicated.
    1. Minimum Base-Metal Thickness: As indicated on Structural Drawings.
  - G. Cold-Rolled Channel Bridging: Steel, minimum base-metal thickness as indicated on Structural Drawings, with minimum 1/2-inch- wide flanges.
    1. Depth: As indicated on Drawings.
    2. Clip Angle: Not less than 1-1/2 by 1-1/2 inches, 0.068-inch- thick, galvanized steel.
  - H. Hat-Shaped, Rigid Furring Channels: ASTM C 645.
    1. Minimum Base-Metal Thickness: As indicated on Structural Drawings.
    2. Depth: As indicated on Drawings.
  - I. Resilient Furring Channels: 1/2-inch- deep, steel sheet members designed to reduce sound transmission.
    1. Configuration: Asymmetrical or hat shaped.
  - J. Cold-Rolled Furring Channels: uncoated-steel thickness as indicated on Structural Drawings, with minimum 1/2-inch- wide flanges.
    1. Depth: As indicated on Drawings.
    2. Furring Brackets: Adjustable, corrugated-edge type of steel sheet with minimum uncoated-steel thickness as indicated on Structural Drawings.
    3. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- diameter wire, or double strand of 0.048-inch- diameter wire.
- 2.3 SUSPENSION SYSTEMS
- A. Tie Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.062-inch- diameter wire, or double strand of 0.048-inch- diameter wire.
  - B. Hanger Attachments to Concrete:

1. Anchors: Fabricated from corrosion-resistant materials with holes or loops for attaching wire hangers and capable of sustaining, without failure, a load equal to 5 times that imposed by construction as determined by testing according to ASTM E 488 by an independent testing agency.
  - a. Type: Cast-in-place anchor, designed for attachment to concrete forms, Postinstalled, chemical anchor, or Postinstalled, expansion anchor.
  - b. Material for Interior Locations: Carbon-steel components zinc-plated to comply with ASTM B 633 or ASTM F 1941, Class Fe/Zn 5, unless otherwise indicated.
- C. Wire Hangers: ASTM A 641/A 641M, Class 1 zinc coating, soft temper, 0.16 inch in diameter.
- D. Carrying Channels: Cold-rolled, commercial-steel sheet with a base-metal thickness as indicated on Structural Drawings and minimum 1/2-inch- wide flanges.
  1. Depth: As indicated on Drawings.
- E. Furring Channels (Furring Members):
  1. Cold-Rolled Channels: uncoated-steel thickness as indicated on Structural Drawings, with minimum 1/2-inch- wide flanges, 3/4 inch deep.
  2. Steel Studs and Runners: ASTM C 645.
    - a. Minimum Base-Metal Thickness: As indicated on Structural Drawings.
    - b. Depth: As indicated on Drawings.
  3. Embossed Steel Studs and Tracks: ASTM C 645.
    - a. Minimum Base-Metal Thickness: As indicated on Structural Drawings.
    - b. Depth: As indicated on Drawings.
  4. Hat-Shaped, Rigid Furring Channels: ASTM C 645, 7/8 inch deep.
    - a. Minimum Base-Metal Thickness: As indicated on Structural Drawings.
  5. Resilient Furring Channels: 1/2-inch- deep members designed to reduce sound transmission.
    - a. Configuration: Asymmetrical or hat shaped.
- F. Grid Suspension System for Gypsum Board Ceilings: ASTM C 645, direct-hung system composed of main beams and cross-furring members that interlock.
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Armstrong World Industries, Inc.
    - b. Chicago Metallic Corporation.
    - c. USG Corporation; Drywall Suspension System.

## 2.4 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards.
  - 1. Fasteners for Metal Framing: Of type, material, size, corrosion resistance, holding power, and other properties required to fasten steel members to substrates.
- B. Isolation Strip at Exterior Walls: Provide one of the following:
  - 1. Asphalt-Saturated Organic Felt: ASTM D 226, Type I (No. 15 asphalt felt), nonperforated.
  - 2. Foam Gasket: Adhesive-backed, closed-cell vinyl foam strips that allow fastener penetration without foam displacement, 1/8 inch thick, in width to suit steel stud size.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine areas and substrates, with Installer present, and including welded hollow-metal frames, cast-in anchors, and structural framing, for compliance with requirements and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Suspended Assemblies: Coordinate installation of suspension systems with installation of overhead structure to ensure that inserts and other provisions for anchorages to building structure have been installed to receive hangers at spacing required to support the Work and that hangers will develop their full strength.
  - 1. Furnish concrete inserts and other devices indicated to other trades for installation in advance of time needed for coordination and construction.
- B. Coordination with Sprayed Fire-Resistive Materials:
  - 1. Before sprayed fire-resistive materials are applied, attach offset anchor plates or ceiling runners (tracks) to surfaces indicated to receive sprayed fire-resistive materials. Where offset anchor plates are required, provide continuous plates fastened to building structure not more than 24 inches o.c.
  - 2. After sprayed fire-resistive materials are applied, remove them only to extent necessary for installation of non-load-bearing steel framing. Do not reduce thickness of fire-resistive materials below that required for fire-resistance ratings indicated. Protect adjacent fire-resistive materials from damage.

### 3.3 INSTALLATION, GENERAL

- A. Installation Standard: ASTM C 754.
  - 1. Gypsum Board Assemblies: Also comply with requirements in ASTM C 840 that apply to framing installation.
- B. Install supplementary framing, and blocking to support fixtures, equipment services, heavy trim, grab bars, toilet accessories, furnishings, or similar construction.
- C. Install bracing at terminations in assemblies.
- D. Do not bridge building control and expansion joints with non-load-bearing steel framing members. Frame both sides of joints independently.

### 3.4 INSTALLING FRAMED ASSEMBLIES

- A. Install framing system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
  - 1. Single-Layer Application: 16 inches o.c. unless otherwise indicated.
  - 2. Multilayer Application: 16 inches o.c. unless otherwise indicated.
  - 3. Tile Backing Panels: 16 inches o.c. unless otherwise indicated.
- B. Where studs are installed directly against exterior masonry walls or dissimilar metals at exterior walls, install isolation strip between studs and exterior wall.
- C. Install studs so flanges within framing system point in same direction.
- D. Install tracks at floors and overhead supports. Extend framing full height to structural supports or substrates above suspended ceilings except where partitions are indicated to terminate at suspended ceilings. Continue framing around ducts that penetrate partitions above ceiling.
  - 1. Slip-Type Head Joints: Where framing extends to overhead structural supports, install to produce joints at tops of framing systems that prevent axial loading of finished assemblies.
  - 2. Door Openings: Screw vertical studs at jambs to jamb anchor clips on door frames; install runner track section (for cripple studs) at head and secure to jamb studs.
    - a. Install two studs, minimum galvanized metal thickness as indicated on Structural Drawings, at each jamb unless otherwise indicated.
    - b. Install cripple studs at head adjacent to each jamb stud, with a minimum 1/2-inch clearance from jamb stud to allow for installation of control joint in finished assembly.
    - c. Extend jamb studs through suspended ceilings and attach to underside of structure above.

3. Other Framed Openings: Frame openings other than door openings the same as required for door openings unless otherwise indicated. Install framing below sills of openings to match framing required above door heads.
  4. Fire-Resistance-Rated Partitions: Install framing to comply with fire-resistance-rated assembly indicated and support closures and to make partitions continuous from floor to underside of solid structure.
  5. Sound-Rated Partitions: Install framing to comply with sound-rated assembly indicated.
  6. Where doors swing into an adjacent wall, provide backing plate or fire treated wood blocking between studs to support gypsum board at location where door levers meet the wall, to prevent damage and allow better mounting for wall-mounted door stops.
- E. Direct Furring:
1. Attach to concrete with stub nails, screws designed for masonry attachment, or powder-driven fasteners spaced 24 inches o.c.
- F. Installation Tolerance: Install each framing member so fastening surfaces vary not more than 1/8 inch from the plane formed by faces of adjacent framing.

### 3.5 INSTALLING SUSPENSION SYSTEMS

- A. Install suspension system components according to spacings indicated, but not greater than spacings required by referenced installation standards for assembly types.
1. Hangers: 48 inches o.c.
  2. Carrying Channels (Main Runners): 48 inches o.c.
  3. Furring Channels (Furring Members): 16 inches o.c.
- B. Isolate suspension systems from building structure where they abut or are penetrated by building structure to prevent transfer of loading imposed by structural movement.
- C. Suspend hangers from building structure as follows:
1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structural or suspension system.
    - a. Splay hangers only where required to miss obstructions and offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
  2. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with locations of hangers required to support standard suspension system members, install supplemental suspension members and hangers in the form of trapezes or equivalent devices.
    - a. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced installation standards.

3. Wire Hangers: Secure by looping and wire tying, either directly to structures or to inserts, eye screws, or other devices and fasteners that are secure and appropriate for substrate, and in a manner that will not cause hangers to deteriorate or otherwise fail.
  4. Do not attach hangers to steel roof deck.
  5. Do not attach hangers to permanent metal forms. Furnish cast-in-place hanger inserts that extend through forms.
  6. Do not attach hangers to rolled-in hanger tabs of composite steel floor deck.
  7. Do not connect or suspend steel framing from ducts, pipes, or conduit.
- D. Seismic Bracing: Sway-brace suspension systems with hangers used for support .
- E. Grid Suspension Systems: Attach perimeter wall track or angle where grid suspension systems meet vertical surfaces. Mechanically join main beam and cross-furring members to each other and butt-cut to fit into wall track.
- F. Installation Tolerances: Install suspension systems that are level to within 1/8 inch in 12 feet measured lengthwise on each member that will receive finishes and transversely between parallel members that will receive finishes.

END OF SECTION 09 2216

## SECTION 09 2900 - GYPSUM BOARD

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. Interior gypsum board.
  - 2. Tile backing panels.

- B. Related Requirements:

- 1. Section 09 2216 "Non-Structural Metal Framing" for non-structural framing and suspension systems that support gypsum board panels.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

#### 1.4 QUALITY ASSURANCE

- A. Mockups: Before beginning gypsum board installation, install mockups of at least 100 sq. ft. in surface area to demonstrate aesthetic effects and set quality standards for materials and execution.

- 1. Install mockups for the following:
    - a. Each level of gypsum board finish indicated for use in exposed locations.
  - 2. Apply or install final decoration indicated, including painting and wallcoverings, on exposed surfaces for review of mockups.
  - 3. Simulate finished lighting conditions for review of mockups.
  - 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.



## 1.5 DELIVERY, STORAGE AND HANDLING

- A. Store materials inside under cover and keep them dry and protected against weather, condensation, direct sunlight, construction traffic, and other potential causes of damage. Stack panels flat and supported on risers on a flat platform to prevent sagging.

## 1.6 FIELD CONDITIONS

- A. Environmental Limitations: Comply with ASTM C 840 requirements or gypsum board manufacturer's written recommendations, whichever are more stringent.
- B. Do not install paper-faced gypsum panels until installation areas are enclosed and conditioned.
- C. Do not install panels that are wet, those that are moisture damaged, and those that are mold damaged.
  - 1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
  - 2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Resistance-Rated Assemblies: For fire-resistance-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 119 by an independent testing agency.
- B. STC-Rated Assemblies: For STC-rated assemblies, provide materials and construction identical to those tested in assembly indicated according to ASTM E 90 and classified according to ASTM E 413 by an independent testing agency.
- C. Ceiling and wall materials shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

### 2.2 GYPSUM BOARD, GENERAL

- A. Regional Materials: Products shall be manufactured within 100 miles (160 km) of Project site from materials that have been extracted, harvested, or recovered, as well as manufactured, within 100 miles (160 km) of Project site.
- B. Size: Provide maximum lengths and widths available that will minimize joints in each area and that correspond with support system indicated.

## 2.3 INTERIOR GYPSUM BOARD

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. American Gypsum.
  - 2. CertainTeed Corporation.
  - 3. Georgia-Pacific Building Products.
  - 4. National Gypsum Company.
  - 5. PABCO Gypsum.
  - 6. USG Corporation.
- B. Gypsum Board, Type X: ASTM C 1396/C 1396M.
  - 1. Thickness: 5/8 inch.
  - 2. Long Edges: Tapered.
- C. Gypsum Ceiling Board: ASTM C 1396/C 1396M.
  - 1. Thickness: 1/2 inch.
  - 2. Long Edges: Tapered.

## 2.4 SPECIALTY GYPSUM BOARD

- A. Acoustically Enhanced Gypsum Board: ASTM C 1396/C 1396M. Multilayer products constructed of two layers of gypsum boards sandwiching a viscoelastic sound-absorbing polymer core.
  - 1. Products: Subject to compliance with requirements, available products that may be incorporated into the Work include, but are not limited to the following:
    - a. National Gypsum Company; SoundBreak XP.
    - b. Quiet Solution; Quiet Rock.
    - c. Temple-Inland Building Products by Georgia-Pacific; Comfort Guard Sound Deadening Board.
  - 2. Core: 5/8 inch, Type X.
  - 3. Long Edges: Tapered.

## 2.5 TILE BACKING PANELS

- A. Cementitious Backer Units: ANSI A118.9 and ASTM C 1288 or 1325, with manufacturer's standard edges.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. CertainTeed Corporation.
  - b. Custom Building Products.
  - c. FinPan, Inc.
  - d. James Hardie Building Products, Inc.
  - e. National Gypsum Company.
  - f. USG Corporation.
2. Thickness: 1/2 inch.
3. Mold Resistance: ASTM D 3273, score of 10 as rated according to ASTM D 3274.

## 2.6 TRIM ACCESSORIES

### A. Interior Trim: ASTM C 1047.

1. Material: Galvanized or aluminum-coated steel sheet, rolled zinc, plastic, or paper-faced galvanized steel sheet.
2. Shapes:
  - a. Cornerbead.
  - b. LC-Bead: J-shaped; exposed long flange receives joint compound.
  - c. Expansion (control) joint.

### B. Aluminum Trim: Extruded accessories of profiles and dimensions indicated.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Flannery, Inc.
  - b. Fry Reglet Corporation.
  - c. Gordon, Inc.
  - d. Pittcon Industries.
  - e. Tamlyn.
2. Aluminum: Alloy and temper with not less than the strength and durability properties of ASTM B221, Alloy 6063-T5.
3. Finish: Clear anodized.

## 2.7 JOINT TREATMENT MATERIALS

### A. General: Comply with ASTM C 475/C 475M.

### B. Joint Tape:

1. Interior Gypsum Board: Paper.
2. Tile Backing Panels: As recommended by panel manufacturer.

- C. Joint Compound for Interior Gypsum Board: For each coat use formulation that is compatible with other compounds applied on previous or for successive coats.
  - 1. Prefilling: At open joints and damaged surface areas, use setting-type taping compound.
  - 2. Embedding and First Coat: For embedding tape and first coat on joints, fasteners, and trim flanges, use setting-type taping compound.
    - a. Use setting-type compound for installing paper-faced metal trim accessories.
  - 3. Fill Coat: For second coat, use setting-type, sandable topping compound.
  - 4. Finish Coat: For third coat, use drying-type, all-purpose compound.
  - 5. Skim Coat: For final coat of Level 5 finish, use drying-type, all-purpose compound.
- D. Joint Compound for Tile Backing Panels:
  - 1. Cementitious Backer Units: As recommended by backer unit manufacturer.

## 2.8 AUXILIARY MATERIALS

- A. General: Provide auxiliary materials that comply with referenced installation standards and manufacturer's written recommendations.
- B. Laminating Adhesive: Adhesive or joint compound recommended for directly adhering gypsum panels to continuous substrate.
  - 1. Laminating adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 2. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- C. Steel Drill Screws: ASTM C 1002, unless otherwise indicated.
  - 1. Use screws complying with ASTM C 954 for fastening panels to steel members from 0.033 to 0.112 inch thick.
  - 2. For fastening cementitious backer units, use screws of type and size recommended by panel manufacturer.
- D. Sound Attenuation Blankets: ASTM C 665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.
  - 1. Fire-Resistance-Rated Assemblies: Comply with mineral-fiber requirements of assembly.
- E. Acoustical Joint Sealant: Manufacturer's standard nonsag, paintable, nonstaining latex sealant complying with ASTM C 834. Product effectively reduces airborne sound transmission through

perimeter joints and openings in building construction as demonstrated by testing representative assemblies according to ASTM E 90.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Grabber Construction Products.
  - b. Pecora Corporation.
  - c. Specified Technologies, Inc.
  - d. USG Corporation.
2. Sealant shall have a VOC content of 250 g/L or less.
3. Sealant shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine areas and substrates including welded hollow-metal frames and framing, with Installer present, for compliance with requirements and other conditions affecting performance.
- B. Examine panels before installation. Reject panels that are wet, moisture damaged, and mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 APPLYING AND FINISHING PANELS, GENERAL

- A. Comply with ASTM C 840.
- B. Install ceiling panels across framing to minimize the number of abutting end joints and to avoid abutting end joints in central area of each ceiling. Stagger abutting end joints of adjacent panels not less than one framing member.
- C. Install panels with face side out. Butt panels together for a light contact at edges and ends with not more than 1/16 inch of open space between panels. Do not force into place.
- D. Locate edge and end joints over supports, except in ceiling applications where intermediate supports or gypsum board back-blocking is provided behind end joints. Do not place tapered edges against cut edges or ends. Stagger vertical joints on opposite sides of partitions. Do not make joints other than control joints at corners of framed openings.
- E. Form control and expansion joints with space between edges of adjoining gypsum panels.

- F. Cover both faces of support framing with gypsum panels in concealed spaces (above ceilings, etc.), except in chases braced internally.
  - 1. Unless concealed application is indicated or required for sound, fire, air, or smoke ratings, coverage may be accomplished with scraps of not less than 8 sq. ft. in area.
  - 2. Fit gypsum panels around ducts, pipes, and conduits.
  - 3. Where partitions intersect structural members projecting below underside of floor/roof slabs and decks, cut gypsum panels to fit profile formed by structural members; allow 1/4- to 3/8-inch- wide joints to install sealant.
- G. Isolate perimeter of gypsum board applied to non-load-bearing partitions at structural abutments, except floors. Provide 1/4- to 1/2-inch- wide spaces at these locations and trim edges with edge trim where edges of panels are exposed. Seal joints between edges and abutting structural surfaces with acoustical sealant.
- H. Attachment to Steel Framing: Attach panels so leading edge or end of each panel is attached to open (unsupported) edges of stud flanges first.
- I. STC-Rated Assemblies: Seal construction at perimeters, behind control joints, and at openings and penetrations with a continuous bead of acoustical sealant. Install acoustical sealant at both faces of partitions at perimeters and through penetrations. Comply with ASTM C 919 and with manufacturer's written instructions for locating edge trim and closing off sound-flanking paths around or through assemblies, including sealing partitions above acoustical ceilings.
- J. Install sound attenuation blankets before installing gypsum panels unless blankets are readily installed after panels have been installed on one side.

### 3.3 APPLYING INTERIOR GYPSUM BOARD

- A. Install interior gypsum board in the following locations:
  - 1. Type X: Vertical surfaces unless otherwise indicated.
  - 2. Ceiling Type: Ceiling surfaces.
  - 3. Impact-Resistant Type: As indicated on Drawings.
  - 4. Acoustically Enhanced Type: As indicated on Drawings.
- B. Single-Layer Application:
  - 1. On ceilings, apply gypsum panels before wall/partition board application to greatest extent possible and at right angles to framing unless otherwise indicated.
  - 2. On partitions/walls, apply gypsum panels vertically (parallel to framing) unless otherwise indicated or required by fire-resistance-rated assembly, and minimize end joints.
    - a. Stagger abutting end joints not less than one framing member in alternate courses of panels.
    - b. At high walls, install panels horizontally unless otherwise indicated or required by fire-resistance-rated assembly.

3. Fastening Methods: Apply gypsum panels to supports with steel drill screws.

C. Multilayer Application:

1. On ceilings, apply gypsum board indicated for base layers before applying base layers on walls/partitions; apply face layers in same sequence. Apply base layers at right angles to framing members and offset face-layer joints one framing member, 16 inches minimum, from parallel base-layer joints, unless otherwise indicated or required by fire-resistance-rated assembly.
2. On partitions/walls, apply gypsum board indicated for base layers and face layers vertically (parallel to framing) with joints of base layers located over stud or furring member and face-layer joints offset at least one stud or furring member with base-layer joints, unless otherwise indicated or required by fire-resistance-rated assembly. Stagger joints on opposite sides of partitions.
3. Fastening Methods: Fasten base layers and face layers separately to supports with screws.

### 3.4 APPLYING TILE BACKING PANELS

- A. Cementitious Backer Units: ANSI A108.11, at locations indicated to receive tile.
- B. Where tile backing panels abut other types of panels in same plane, shim surfaces to produce a uniform plane across panel surfaces.

### 3.5 INSTALLING TRIM ACCESSORIES

- A. General: For trim with back flanges intended for fasteners, attach to framing with same fasteners used for panels. Otherwise, attach trim according to manufacturer's written instructions.
- B. Control Joints: Install control joints at locations indicated on Drawings, or if not indicated, according to ASTM C 840 and in specific locations approved by Architect for visual effect.
- C. Interior Trim: Install in the following locations:
  1. Cornerbead: Use at outside corners unless otherwise indicated.

### 3.6 IDENTIFICATION

- A. Marking and Identification: Where there is an accessible concealed floor, floor-ceiling or attic space, fire walls, fire barriers, fire partitions, smoke barriers and smoke partitions or any other wall required to have protected openings or penetrations shall be effectively and permanently identified with signs or stenciling in the concealed space. Such identification shall:
  1. Be located within 15 feet (4572 mm) of the end of each wall and at intervals not exceeding 30 feet (9144 mm) measured horizontally along the wall or partition.

2. Include lettering not less than 3 inches (76 mm) in height with a minimum 3/8-inch (9.5 mm) stroke in a contrasting color incorporating the suggested wording, "FIRE AND/OR SMOKE BARRIER-PROTECT ALL OPENINGS," or other wording.

### 3.7 FINISHING GYPSUM BOARD

- A. General: Treat gypsum board joints, interior angles, edge trim, control joints, penetrations, fastener heads, surface defects, and elsewhere as required to prepare gypsum board surfaces for decoration. Promptly remove residual joint compound from adjacent surfaces.
- B. Prefill open joints and damaged surface areas.
- C. Apply joint tape over gypsum board joints, except for trim products specifically indicated as not intended to receive tape.
- D. Gypsum Board Finish Levels: Finish panels to levels indicated below and according to ASTM C 840:
  1. Level 1: Ceiling plenum areas, concealed areas, and where indicated.
  2. Level 2: Panels that are substrate for tile.
  3. Level 4: At panel surfaces that will be exposed to view unless otherwise indicated.
    - a. Primer and its application to surfaces are specified in Section 09 9123 "Interior Painting."
  4. Level 5: Provide Level 5 finish on walls that are washed with light from light fixtures, including the following:
    - a. Walls with light fixtures mounted to them.
    - b. Walls where light fixture is mounted to ceiling within 12 inches of wall.
  5. Primer and its application to surfaces are specified in Section 09 9123 "Interior Painting."
- E. Cementitious Backer Units: Finish according to manufacturer's written instructions.

### 3.8 PROTECTION

- A. Protect adjacent surfaces from drywall compound and promptly remove from floors and other non-drywall surfaces. Repair surfaces stained, marred, or otherwise damaged during drywall application.
- B. Protect installed products from damage from weather, condensation, direct sunlight, construction, and other causes during remainder of the construction period.
- C. Remove and replace panels that are wet, moisture damaged, and mold damaged.



1. Indications that panels are wet or moisture damaged include, but are not limited to, discoloration, sagging, or irregular shape.
2. Indications that panels are mold damaged include, but are not limited to, fuzzy or splotchy surface contamination and discoloration.

END OF SECTION 09 2900

## SECTION 09 3013 - CERAMIC TILING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. Porcelain tile.
  - 2. Crack isolation membrane.
  - 3. Quartz solid surfacing thresholds.
  - 4. Metal edge strips.

- B. Related Requirements:

- 1. Section 07 9200 "Joint Sealants" for sealing of expansion, contraction, control, and isolation joints in tile surfaces.
  - 2. Section 09 2900 "Gypsum Board" for cementitious backer units.
  - 3. Section 09 3023 "Glass Tiling" for glass wall tiles.
  - 4. Section 12 3662 "Quartz Agglomerate Wall Tops" for other quartz agglomerate requirements applicable to thresholds.

#### 1.3 DEFINITIONS

- A. General: Definitions in the ANSI A108 series of tile installation standards and in ANSI A137.1 apply to Work of this Section unless otherwise specified.
- B. ANSI A108 Series: ANSI A108.01, ANSI A108.02, ANSI A108.1A, ANSI A108.1B, ANSI A108.1C, ANSI A108.4, ANSI A108.5, ANSI A108.6, ANSI A108.8, ANSI A108.9, ANSI A108.10, ANSI A108.11, ANSI A108.12, ANSI A108.13, ANSI A108.14, ANSI A108.15, ANSI A108.16, and ANSI A108.17, which are contained in its "Specifications for Installation of Ceramic Tile."
- C. Module Size: Actual tile size plus joint width indicated.
- D. Face Size: Actual tile size, excluding spacer lugs.

#### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
  - 1. Review requirements in ANSI A108.01 for substrates and for preparation by other trades.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Show locations of each type of tile and tile pattern. Show widths, details, and locations of expansion, contraction, control, and isolation joints in tile substrates and finished tile surfaces.
- C. Samples for Initial Selection: For grout.
- D. Samples for Verification:
  - 1. Full-size units of each type and composition of tile and for each color and finish required. For ceramic mosaic tile in color blend patterns, provide full sheets of each color blend.
  - 2. Assembled samples mounted on a rigid panel, with grouted joints, for each type and composition of tile and for each color and finish required. Make samples at least 12 inches square, but not fewer than four tiles. Use grout of type and in color or colors approved for completed Work.
  - 3. Full-size units of each type of trim and accessory for each color and finish required.
  - 4. Solid surfacing thresholds in 6-inch lengths.

#### 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Master Grade Certificates: For each shipment, type, and composition of tile, signed by tile manufacturer and Installer.
- C. Product Certificates: For each type of product.
- D. Product Test Reports: For tile-setting and -grouting products and certified porcelain tile.

#### 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Tile and Trim Units: Furnish quantity of full-size units equal to 3 percent of amount installed for each type, composition, color, pattern, and size indicated.
2. Grout: Furnish quantity of grout equal to 3 percent of amount installed for each type, composition, and color indicated.

#### 1.8 QUALITY ASSURANCE

##### A. Installer Qualifications:

1. Installer is a five-star member of the National Tile Contractors Association or a Trowel of Excellence member of the Tile Contractors' Association of America.
2. Installer's supervisor for Project holds the International Masonry Institute's Foreman Certification.
3. Installer employs Ceramic Tile Education Foundation Certified Installers or installers recognized by the U.S. Department of Labor as Journeyman Tile Layers.

##### B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.

1. Build mockup of each type of floor tile installation.
2. Build mockup of each type of wall tile installation.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

#### 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store packaged materials in original containers with seals unbroken and labels intact until time of use. Comply with requirements in ANSI A137.1 for labeling tile packages.
- B. Store tile and cementitious materials on elevated platforms, under cover, and in a dry location.
- C. Store aggregates where grading and other required characteristics can be maintained and contamination can be avoided.
- D. Store liquid materials in unopened containers and protected from freezing.

#### 1.10 FIELD CONDITIONS

- A. Environmental Limitations: Do not install tile until construction in spaces is complete and ambient temperature and humidity conditions are maintained at the levels indicated in referenced standards and manufacturer's written instructions.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Source Limitations for Tile: Obtain tile of each type from single source or producer.
  - 1. Obtain tile of each type and color or finish from same production run and of consistent quality in appearance and physical properties for each contiguous area.
- B. Source Limitations for Setting and Grouting Materials: Obtain ingredients of a uniform quality for each mortar, adhesive, and grout component from single manufacturer and each aggregate from single source or producer.
  - 1. Obtain setting and grouting materials, except for unmodified Portland cement and aggregate, from single manufacturer.
  - 2. Obtain crack isolation membrane, except for sheet products, from manufacturer of setting and grouting materials.
- C. Source Limitations for Other Products: Obtain each of the following products specified in this Section from a single manufacturer:
  - 1. Crack isolation membrane.
  - 2. Metal edge strips.

### 2.2 THRESHOLDS

- A. General: Fabricate to sizes and profiles indicated or required to provide transition between adjacent floor finishes.
  - 1. Bevel edges at 1:2 slope, with lower edge of bevel aligned with or up to 1/16 inch above adjacent floor surface. Finish bevel to match top surface of threshold. Limit height of threshold to 1/2 inch or less above adjacent floor surface.
- B. Quartz Thresholds: ASTM C 503/C 503M, with a minimum abrasion resistance of 10 according to ASTM C 1353 or ASTM C 241/C 241M and with honed finish.
  - 1. Description: Basis of Design: Item QS-3 on Finish Legend in Drawings (Daltile, One Quartz, Mesa Dune NQ89 Polished).

### 2.3 PRODUCTS, GENERAL

- A. ANSI Ceramic Tile Standard: Provide tile that complies with ANSI A137.1 for types, compositions, and other characteristics indicated.
  - 1. Provide tile complying with Standard grade requirements unless otherwise indicated.

- B. ANSI Standards for Tile Installation Materials: Provide materials complying with ANSI A108.02, ANSI standards referenced in other Part 2 articles, ANSI standards referenced by TCNA installation methods specified in tile installation schedules, and other requirements specified.
- C. Factory Blending: For tile exhibiting color variations within ranges, blend tile in factory and package so tile units taken from one package show same range in colors as those taken from other packages and match approved Samples.
- D. Mounting: For factory-mounted tile, provide back- or edge-mounted tile assemblies as standard with manufacturer unless otherwise indicated.
  - 1. Where tile is indicated for installation in wet areas, do not use back- or edge-mounted tile assemblies unless tile manufacturer specifies in writing that this type of mounting is suitable for installation indicated and has a record of successful in-service performance.

## 2.4 TILE PRODUCTS

- A. Ceramic Tile Types PT-3: Porcelain floor tile.
  - 1. Basis of Design: Subject to compliance with requirements, provide Daltile Chord product PT-3 indicated on Finish Legend in Drawings, or equivalent products approved by Architect prior to bid, by another manufacturer.
  - 2. Composition: Porcelain.
  - 3. Face Size: As indicated on Finish Legend in Drawings.
  - 4. Thickness: 5/8 inch.
  - 5. Face: Plain with square or cushion edges.
  - 6. Tile Color and Pattern: As indicated on Finish Legend in Drawings.
  - 7. Grout Color: As indicated on Finish Legend in Drawings, or if not indicated, as selected by Architect from `manufacturer's full range.
  - 8. Trim Units: Coordinated with sizes and coursing of adjoining flat tile and matching color and other characteristics of adjoining flat tile. Provide shapes as follows, selected from manufacturer's standard shapes:
    - a. PC-1: Base for Medium Bed Mortar Installations with PT-3: Straight, module size as indicated on Finish legend in Drawings.
- B. Ceramic Tile Types CT-1: Ceramic wall tile.
  - 1. Basis of Design: Subject to compliance with requirements, provide Daltile Color Wheel Linear product indicated on Finish Legend in Drawings, or equivalent products approved by Architect prior to bid, by another manufacturer.
  - 2. Composition: Porcelain.
  - 3. Face Size: As indicated on Finish Legend in Drawings.
  - 4. Thickness: 5/8 inch.
  - 5. Face: Plain with square or cushion edges.
  - 6. Tile Color and Pattern: As indicated on Finish Legend in Drawings.

7. Grout Color: As indicated on Finish Legend in Drawings, or if not indicated, as selected by Architect from `manufacturer's full range.

## 2.5 THRESHOLDS

- A. General: Fabricate to sizes and profiles indicated or required to provide transition between adjacent floor finishes.
  1. Bevel edges at 1:2 slope, with lower edge of bevel aligned with or up to 1/16 inch above adjacent floor surface. Finish bevel to match top surface of threshold. Limit height of threshold to 1/2 inch or less above adjacent floor surface.
- B. Quartz Thresholds: ASTM C 503/C 503M, with a minimum abrasion resistance of 10 according to ASTM C 1353 or ASTM C 241/C 241M and with honed finish.
  1. Description: Basis of Design – QS-3 Daltile, One Quartz, Mesa Dune NQ89 Polished.

## 2.6 CRACK ISOLATION MEMBRANE

- A. General: Manufacturer's standard product that complies with ANSI A118.12 for high performance and is recommended by the manufacturer for the application indicated. Include reinforcement and accessories recommended by manufacturer.
- B. Fluid-Applied Membrane: Liquid-latex rubber or elastomeric polymer.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Custom Building Products; RedGard Waterproofing and Crack Prevention Membrane.
    - b. LATICRETE SUPERCAP, LLC; Laticrete Hydro Barrier.
    - c. MAPEI Corporation; Mapelastic™ AquaDefense.

## 2.7 SETTING MATERIALS

- A. Modified Dry-Set Mortar (Thinset): ANSI A118.4.
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Custom Building Products.
    - b. Laticrete International, Inc.
    - c. MAPEI Corporation.
    - d. Merkrete by Parex USA, Inc.
- B. Medium-Bed, Latex-Portland Cement Mortar: Comply with requirements in ANSI A118.4. Provide product that is approved by manufacturer for application thickness of 5/8 inch.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Custom Building Products.
  - b. Laticrete International, Inc.
  - c. MAPEI Corporation.
  - d. Merkrete by Parex USA, Inc.

## 2.8 GROUT MATERIALS

- A. Water-Cleanable Epoxy Grout: ANSI A118.3, with a VOC content of 65 g/L or less.
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Custom Building Products.
    - b. Laticrete International, Inc.
    - c. MAPEI Corporation.
    - d. Merkrete by Parex USA, Inc.
  2. Provide product capable of withstanding continuous and intermittent exposure to temperatures of up to 140 and 212 deg F, respectively, and certified by manufacturer for intended use.

## 2.9 MISCELLANEOUS MATERIALS

- A. Trowelable Underlayments and Patching Compounds: Latex-modified, portland cement-based formulation provided or approved by manufacturer of tile-setting materials for installations indicated.
- B. Metal Edge Strips: Angle or L-shaped, height to match tile and setting-bed thickness, metallic or combination of metal and PVC or neoprene base, designed specifically for flooring applications; stainless-steel, ASTM A 666, 300 Series exposed-edge material as noted in drawings. To be provided at all exposed tile edges.
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Blanke Corporation.
    - b. Ceramic Tool Company, Inc.
    - c. Schluter Systems L.P.
  2. Stainless Steel Metal Edge Strips:
    - a. Basis of Design: Schluter® Schiene by Schluter Systems L.P.
- C. Vapor-Retarder Membrane: Polyethylene sheeting, ASTM D 4397, 4.0 mils thick.



- D. Tile Cleaner: A neutral cleaner capable of removing soil and residue without harming tile and grout surfaces, specifically approved for materials and installations indicated by tile and grout manufacturers.
- E. Floor Sealer: Manufacturer's standard product for sealing grout joints and that does not change color or appearance of grout.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
    - a. Custom Building Products.
  - 2. Grout sealers shall comply with requirements of FloorScore certification.
  - 3. Products shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

## 2.10 MIXING MORTARS AND GROUT

- A. Mix mortars and grouts to comply with referenced standards and mortar and grout manufacturers' written instructions.
- B. Add materials, water, and additives in accurate proportions.
- C. Obtain and use type of mixing equipment, mixer speeds, mixing containers, mixing time, and other procedures to produce mortars and grouts of uniform quality with optimum performance characteristics for installations indicated.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
  - 1. Verify that substrates for setting tile are firm; dry; clean; free of coatings that are incompatible with tile-setting materials, including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.
  - 2. Verify that concrete substrates for tile floors installed with bonded mortar bed comply with surface finish requirements in ANSI A108.01 for installations indicated.
    - a. Verify that surfaces that received a steel trowel finish have been mechanically scarified.

- b. Verify that protrusions, bumps, and ridges have been removed by sanding or grinding.
  - 3. Verify that installation of grounds, anchors, recessed frames, electrical and mechanical units of work, and similar items located in or behind tile has been completed.
  - 4. Verify that joints and cracks in tile substrates are coordinated with tile joint locations; if not coordinated, adjust joint locations in consultation with Architect.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Fill cracks, holes, and depressions in concrete substrates for tile floors installed with thinset mortar with trowelable leveling and patching compound specifically recommended by tile-setting material manufacturer.
- B. Where indicated, prepare substrates to receive waterproofing by applying a reinforced mortar bed that complies with ANSI A108.1A and is sloped 1/4 inch per foot toward drains.
- C. Blending: For tile exhibiting color variations, verify that tile has been factory blended and packaged so tile units taken from one package show same range of colors as those taken from other packages and match approved Samples. If not factory blended, either return to manufacturer or blend tiles at Project site before installing.

### 3.3 CERAMIC TILE INSTALLATION

- A. Comply with TCNA's "Handbook for Ceramic, Glass, and Stone Tile Installation" for TCNA installation methods specified in tile installation schedules. Comply with parts of the ANSI A108 series "Specifications for Installation of Ceramic Tile" that are referenced in TCNA installation methods, specified in tile installation schedules, and apply to types of setting and grouting materials used.
  - 1. For the following installations, follow procedures in the ANSI A108 series of tile installation standards for providing 95 percent mortar coverage:
    - a. Tile floors in wet areas.
    - b. Tile floors consisting of rib-backed tiles.
- B. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.
- C. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile.

- D. Provide manufacturer's standard trim shapes where necessary to eliminate exposed tile edges.
- E. Where accent tile differs in thickness from field tile, vary setting-bed thickness so that tiles are flush.
- F. Jointing Pattern: Lay tile in grid pattern unless otherwise indicated. Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize the use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.
  - 1. For tile mounted in sheets, make joints between tile sheets same width as joints within tile sheets so joints between sheets are not apparent in finished work.
  - 2. Where adjoining tiles on floor, base, walls, or trim are specified or indicated to be same size, align joints.
  - 3. Where tiles are specified or indicated to be whole integer multiples of adjoining tiles on floor, base, walls, or trim, align joints unless otherwise indicated.
- G. Joint Widths: Unless otherwise indicated, install tile with the following joint widths:
  - 1. Porcelain Tile: 3/16 inch.
- H. Lay out tile wainscots to dimensions indicated or to next full tile beyond dimensions indicated.
- I. Expansion Joints: Provide expansion joints and other sealant-filled joints, including control, contraction, and isolation joints, where indicated. Form joints during installation of setting materials, mortar beds, and tile. Do not saw-cut joints after installing tiles.
  - 1. Where joints occur in concrete substrates, locate joints in tile surfaces directly above them.
- J. Quartz Solid Surfacing Thresholds: Install quartz thresholds in same type of setting bed as adjacent floor unless otherwise indicated.
  - 1. At locations where mortar bed (thickset) would otherwise be exposed above adjacent floor finishes, set thresholds in latex-portland cement mortar (thinset).
  - 2. Do not extend crack isolation membrane under thresholds set in latex-portland cement mortar. Fill joints between such thresholds and adjoining tile set on crack isolation membrane with elastomeric sealant.
- K. Metal Edge Strips: Install at locations indicated.
- L. Grout Sealer: Apply grout sealer to cementitious grout joints in tile floors according to grout-sealer manufacturer's written instructions. As soon as grout sealer has penetrated grout joints, remove excess sealer and sealer from tile faces by wiping with soft cloth.

### 3.4 INSTALLATION OF TILE BACKING PANEL

- A. Install panels and treat joints according to ANSI A108.11 and manufacturer's written instructions for type of application indicated.

### 3.5 INSTALLATION OF CRACK ISOLATION MEMBRANE

- A. Install crack isolation membrane to comply with ANSI A108.17 and manufacturer's written instructions to produce membrane of uniform thickness that is bonded securely to substrate.
- B. Allow crack isolation membrane to cure before installing tile or setting materials over it.

### 3.6 ADJUSTING AND CLEANING

- A. Remove and replace tile that is damaged or that does not match adjoining tile. Provide new matching units, installed as specified and in a manner to eliminate evidence of replacement.
- B. Cleaning: On completion of placement and grouting, clean all ceramic tile surfaces so they are free of foreign matter.
  - 1. Remove grout residue from tile as soon as possible.
  - 2. Clean grout smears and haze from tile according to tile and grout manufacturer's written instructions but no sooner than 10 days after installation. Use only cleaners recommended by tile and grout manufacturers and only after determining that cleaners are safe to use by testing on samples of tile and other surfaces to be cleaned. Protect metal surfaces and plumbing fixtures from effects of cleaning. Flush surfaces with clean water before and after cleaning.

### 3.7 PROTECTION

- A. Protect installed tile work with kraft paper or other heavy covering during construction period to prevent staining, damage, and wear. If recommended by tile manufacturer, apply coat of neutral protective cleaner to completed tile walls and floors.
- B. Prohibit foot and wheel traffic from tiled floors for at least seven days after grouting is completed.
- C. Before final inspection, remove protective coverings and rinse neutral protective cleaner from tile surfaces.

### 3.8 INTERIOR CERAMIC TILE INSTALLATION SCHEDULE

- A. Interior Floor Installations, Concrete Subfloor:
  - 1. Ceramic Tile Installation: TCNA F125-Full; thinset mortar on crack isolation membrane.

- a. Ceramic Tile Type: Floor tile.
- b. Thinset Mortar: Medium-bed, modified dry-set mortar.
- c. Grout: Water-cleanable epoxy grout.

B. Interior Wall Installations, Metal Studs or Furring:

- 1. Ceramic Tile Installation: TCNA W244C; thinset mortar on cementitious backer units.
  - a. Ceramic Tile Type: Typical wall tile.
  - b. Thinset Mortar: Modified dry-set mortar.
  - c. Grout: Water-cleanable epoxy grout.

END OF SECTION 09 3013

## SECTION 09 3023 - GLASS TILING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. Glass tile.

- B. Related Requirements:

- 1. Section 07 9200 "Joint Sealants" for sealing of expansion, contraction, control, and isolation joints in tile surfaces.
  - 2. Section 09 2900 "Gypsum Board" for cementitious backer units.

#### 1.3 DEFINITIONS

- A. General: Definitions in the ANSI A108 series of tile installation standards and in ANSI A137.2 apply to Work of this Section unless otherwise specified.
- B. ANSI A108 Series: ANSI A108.01, ANSI A108.02, ANSI A108.1A, ANSI A108.1B, ANSI A108.1C, ANSI A108.4, ANSI A108.5, ANSI A108.6, ANSI A108.8, ANSI A108.9, ANSI A108.10, ANSI A108.11, ANSI A108.12, ANSI A108.13, ANSI A108.14, ANSI A108.15, ANSI A108.16, and ANSI A108.17, which are contained in its "Specifications for Installation of Ceramic Tile."
- C. Module Size: Actual tile size plus joint width indicated.
- D. Face Size: Actual tile size, excluding spacer lugs.

#### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
  - 1. Review requirements in ANSI A108.01 for substrates and for preparation by other trades.

## 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Show locations of each type of tile and tile pattern. Show widths, details, and locations of expansion, contraction, control, and isolation joints in tile substrates and finished tile surfaces.
- C. Samples for Initial Selection: For grout, involving color selection.
- D. Samples for Verification:
  - 1. Full-size units of each type and composition of tile and for each color and finish required.
  - 2. Assembled samples mounted on a rigid panel, with grouted joints, for each type and composition of tile and for each color and finish required. Make samples at least 12 inches square, but not fewer than four tiles. Use grout of type and in color or colors approved for completed Work.

## 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Master Grade Certificates: For each shipment, type, and composition of tile, signed by tile manufacturer and Installer.
- C. Product Certificates: For each type of product.
- D. Product Test Reports: For tile-setting and -grouting products.

## 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match and are from same production runs as products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Tile Units: Furnish quantity of full-size units equal to 3 percent of amount installed for each type, composition, color, pattern, and size indicated.
  - 2. Grout: Furnish quantity of grout equal to 3 percent of amount installed for each type, composition, and color indicated.

## 1.8 QUALITY ASSURANCE

- A. Installer Qualifications:
  - 1. Installer is a five-star member of the National Tile Contractors Association or a Trowel of Excellence member of the Tile Contractors' Association of America.

2. Installer's supervisor for Project holds the International Masonry Institute's Foreman Certification.
  3. Installer employs Ceramic Tile Education Foundation Certified Installers or installers recognized by the U.S. Department of Labor as Journeyman Tile Layers.
- B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
1. Build mockup of glass tile installation.
  2. Approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.
  3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

#### 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store packaged materials in original containers with seals unbroken and labels intact until time of use. Comply with requirements in ANSI A137.2 for labeling tile packages.
- B. Store tile on elevated platforms, under cover, and in a dry location.
- C. Store aggregates where grading and other required characteristics can be maintained and contamination can be avoided.
- D. Store liquid materials in unopened containers and protected from freezing.

#### 1.10 FIELD CONDITIONS

- A. Environmental Limitations: Do not install tile until construction in spaces is complete and ambient temperature and humidity conditions are maintained at the levels indicated in referenced standards and manufacturer's written instructions.

### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Source Limitations for Tile: Obtain tile from single source or producer.
  1. Obtain tile of each type and color or finish from same production run and of consistent quality in appearance and physical properties for each contiguous area.
- B. Source Limitations for Setting and Grouting Materials: Obtain ingredients of a uniform quality for each mortar, adhesive, and grout component from single manufacturer and each aggregate from single source or producer.



1. Obtain setting and grouting materials, except for unmodified Portland cement and aggregate, from single manufacturer.
  2. Obtain waterproof membrane, except for sheet products, from manufacturer of setting and grouting materials.
- C. Source Limitations for Other Products: Obtain each of the following products specified in this Section from a single manufacturer:
1. Joint sealants.

## 2.2 PRODUCTS, GENERAL

- A. ANSI Glass Tile Standard: Provide glass tile that complies with ANSI A137.2 for types and other characteristics indicated.
1. Provide tile complying with Standard grade requirements.
- B. ANSI Standards for Tile Installation Materials: Provide materials complying with ANSI A108.02, ANSI standards referenced in other Part 2 articles, ANSI standards referenced by TCNA installation methods specified in tile installation schedules, and other requirements specified.
- C. Factory Blending: For tile exhibiting color variations within ranges, blend tile in factory and package so tile units taken from one package show same range in colors as those taken from other packages and match approved Samples.
- D. Mounting: For factory-mounted tile, provide back- or edge-mounted tile assemblies as standard with manufacturer unless otherwise indicated.

## 2.3 TILE PRODUCTS

- A. Glass Tile Type GT-2: Glass wall tile.
1. Basis of Design Subject to compliance with requirements, provide item GT-2, Alair glass and stone tile blend by Daltile, as indicated on Finish Legend in Drawings, or an equivalent product approved by Architect prior to bid, by another manufacturer.
  2. Module Size: As indicated on Finish legend.
  3. Tile Color and Pattern: As indicated on Finish Legend.
  4. Grout Color: As selected by Architect from manufacturer's full range.

## 2.4 SETTING MATERIALS

- A. Improved Modified Dry-Set Mortar (Thinset): ANSI A118.15; white, unless otherwise indicated.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. ARDEX Americas.
  - b. Custom Building Products.
  - c. LATICRETE SUPERCAP, LLC.
  - d. MAPEI Corporation.
  - e. Merkrete by Parex USA, Inc.
2. For wall applications, provide mortar that complies with requirements for nonsagging mortar in addition to the other requirements in ANSI A118.15.

## 2.5 GROUT MATERIALS

- A. Water-Cleanable Epoxy Grout: ANSI A118.3, with a VOC content of 65 g/L.
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. ARDEX Americas.
    - b. Bostik, Inc.
    - c. Custom Building Products.
    - d. LATICRETE SUPERCAP, LLC.
    - e. MAPEI Corporation.
    - f. Merkrete by Parex USA, Inc.

## 2.6 MISCELLANEOUS MATERIALS

- A. Metal Edge Strips: Angle or L-shaped, height to match tile and setting-bed thickness, metallic or combination of metal and PVC or neoprene base, designed specifically for flooring applications; stainless-steel, ASTM A 666, 300 Series exposed-edge material.
  1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Schluter Systems L.P.; Schiene, stainless steel.
- B. For basis of design edge trim at tile, see Finish Schedule Sheet AF100 in Drawings.
- C. Tile Cleaner: A neutral cleaner capable of removing soil and residue without harming tile and grout surfaces, specifically approved for materials and installations indicated by tile and grout manufacturers.

## 2.7 MIXING MORTARS AND GROUT

- A. Mix mortars and grouts to comply with referenced standards and mortar and grout manufacturers' written instructions.
- B. Add materials, water, and additives in accurate proportions.
- C. Obtain and use type of mixing equipment, mixer speeds, mixing containers, mixing time, and other procedures to produce mortars and grouts of uniform quality with optimum performance characteristics for installations indicated.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions where tile will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
  - 1. Verify that substrates for setting tile are firm; dry; clean; free of coatings that are incompatible with tile-setting materials, including curing compounds and other substances that contain soap, wax, oil, or silicone; and comply with flatness tolerances required by ANSI A108.01 for installations indicated.
  - 2. Verify that concrete substrates for tile floors installed with thinset mortar comply with surface finish requirements in ANSI A108.01 for installations indicated.
    - a. Verify that surfaces that received a steel trowel finish have been mechanically scarified.
    - b. Verify that protrusions, bumps, and ridges have been removed by sanding or grinding.
  - 3. Verify that installation of grounds, anchors, recessed frames, electrical and mechanical units of work, and similar items located in or behind tile has been completed.
  - 4. Verify that joints and cracks in tile substrates are coordinated with tile joint locations; if not coordinated, adjust joint locations in consultation with Architect.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Where indicated, prepare substrates to receive waterproofing by applying a reinforced mortar bed that complies with ANSI A108.1A and is sloped 1/4 inch per foot toward drains.
- B. Blending: For tile exhibiting color variations, verify that tile has been factory blended and packaged so tile units taken from one package show same range of colors as those taken from

other packages and match approved Samples. If not factory blended, either return to manufacturer or blend tiles at Project site before installing.

### 3.3 GLASS TILE INSTALLATION

- A. Comply with TCNA's "Handbook for Ceramic, Glass, and Stone Tile Installation" for TCNA installation methods specified in tile installation schedules. Comply with parts of the ANSI A108 series "Specifications for Installation of Ceramic Tile" that are referenced in TCNA installation methods, specified in tile installation schedules, and apply to types of setting and grouting materials used.
- B. Extend tile work into recesses and under or behind equipment and fixtures to form complete covering without interruptions unless otherwise indicated. Terminate work neatly at obstructions, edges, and corners without disrupting pattern or joint alignments.
- C. Accurately form intersections and returns. Perform cutting and drilling of tile without marring visible surfaces. Carefully grind cut edges of tile abutting trim, finish, or built-in items for straight aligned joints. Fit tile closely to electrical outlets, piping, fixtures, and other penetrations so plates, collars, or covers overlap tile. Repair tile back coating to provide consistent visual appearance. Tiles with variations in appearance due to chipping of back coating will be rejected.
- D. Jointing Pattern: Lay tile in grid pattern unless otherwise indicated. Lay out tile work and center tile fields in both directions in each space or on each wall area. Lay out tile work to minimize the use of pieces that are less than half of a tile. Provide uniform joint widths unless otherwise indicated.
  - 1. For tile mounted in sheets, make joints between tile sheets same width as joints within tile sheets so joints between sheets are not apparent in finished work.
- E. Joint Widths: Unless otherwise indicated, install tile with the following joint widths:
  - 1. Glass Wall Tile: 1/16 inch.
- F. Metal Edge Strips: Install at locations indicated.

### 3.4 CLEANING AND PROTECTING

- A. Cleaning: On completion of placement and grouting, clean all tile surfaces so they are free of foreign matter.
  - 1. Remove grout residue from tile as soon as possible.
  - 2. Clean grout smears and haze from tile according to tile and grout manufacturer's written instructions but no sooner than 10 days after installation. Use only cleaners recommended by tile and grout manufacturers and only after determining that cleaners are safe to use by testing on samples of tile and other surfaces to be cleaned. Protect metal surfaces and

- plumbing fixtures from effects of cleaning. Flush surfaces with clean water before and after cleaning.
3. Remove temporary protective coating by method recommended by coating manufacturer and that is acceptable to tile and grout manufacturer. Trap and remove coating to prevent drain clogging.
- B. Protect installed tile work with kraft paper or other heavy covering during construction period to prevent staining, damage, and wear. If recommended by tile manufacturer, apply coat of neutral protective cleaner to completed tile walls.
- C. Before final inspection, remove protective coverings and rinse neutral protective cleaner from tile surfaces.

### 3.5 INTERIOR GLASS TILE INSTALLATION SCHEDULE

- A. Interior Wall Installations, Metal Studs or Furring:
1. Glass Tile Installation: TCNA W244C or TCNA W244F; thinset mortar on cementitious backer units.
    - a. Glass Tile Type: Glass tile
    - b. Thinset Mortar: Improved modified dry-set mortar.
    - c. Grout: Water-cleanable epoxy grout.

END OF SECTION 09 3023

## SECTION 09 5113 - ACOUSTICAL PANEL CEILINGS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes acoustical panels and exposed suspension systems for ceilings. Panel types include the following:
  - 1. Large format reveal edge acoustical panels.
  - 2. Reveal edge acoustical panels.
  - 3. Vinyl-faced flush edge acoustical panels.
- B. Products furnished, but not installed under this Section, include anchors, clips, and other ceiling attachment devices to be cast in concrete.
- C. Products furnished, but not installed under this Section, include anchors, clips, and other ceiling attachment devices to be cast in concrete.

#### 1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Delegated-Design Submittal: For seismic restraints for ceiling systems.
  - 1. Include design calculations for seismic restraints including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
  - 1. Ceiling suspension-system members.

2. Structural members to which suspension systems will be attached.
3. Method of attaching hangers to building structure.
  - a. Furnish layouts for cast-in-place anchors, clips, and other ceiling attachment devices whose installation is specified in other Sections.
4. Carrying channels or other supplemental support for hanger-wire attachment where conditions do not permit installation of hanger wires at required spacing.
5. Size and location of initial access modules for acoustical panels.
6. Items penetrating finished ceiling and ceiling-mounted items including the following:
  - a. Lighting fixtures.
  - b. Diffusers.
  - c. Grilles.
  - d. Speakers.
  - e. Sprinklers.
  - f. Access panels.
  - g. Perimeter moldings

B. Qualification Data: For testing agency.

C. Product Test Reports: For each acoustical panel ceiling, for tests performed by a qualified testing agency.

D. Evaluation Reports: For each acoustical panel ceiling suspension system and anchor and fastener type, from ICC-ES.

E. Field quality-control reports.

## 1.6 CLOSEOUT SUBMITTALS

A. Maintenance Data: For finishes to include in maintenance manuals.

## 1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Acoustical Ceiling Panels: Full-size panels equal to 2 percent of quantity installed.
2. Suspension-System Components: Quantity of each exposed component equal to 2 percent of quantity installed.
3. Hold-Down Clips: Equal to 2 percent of quantity installed.

## 1.8 QUALITY ASSURANCE

A. Testing Agency Qualifications: Qualified according to NVLAP for testing indicated.

- B. Mockups: Build mockups to verify selections made under sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
  - 1. Build mockup of typical ceiling area as shown on Drawings.
  - 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

#### 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Deliver acoustical panels, suspension-system components, and accessories to Project site in original, unopened packages and store them in a fully enclosed, conditioned space where they will be protected against damage from moisture, humidity, temperature extremes, direct sunlight, surface contamination, and other causes.
- B. Before installing acoustical panels, permit them to reach room temperature and a stabilized moisture content.
- C. Handle acoustical panels carefully to avoid chipping edges or damaging units in any way.

#### 1.10 FIELD CONDITIONS

- A. Environmental Limitations: Do not install acoustical panel ceilings until spaces are enclosed and weatherproof, wet work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. Source Limitations: Obtain each type of acoustical ceiling panel and its supporting suspension system from single source from single manufacturer.

#### 2.2 PERFORMANCE REQUIREMENTS

- A. Ceiling products shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- B. Seismic Performance: Acoustical ceiling shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- C. Surface-Burning Characteristics: Comply with ASTM E 84; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.



1. Flame-Spread Index: Comply with ASTM E 1264 for Class A materials.
2. Smoke-Developed Index: 50 or less.

### 2.3 ACOUSTICAL PANELS, GENERAL

- A. Acoustical Panel Standard: Provide manufacturer's standard panels according to ASTM E 1264 and designated by type, form, pattern, acoustical rating, and light reflectance unless otherwise indicated.
- B. Acoustical Panel Colors and Patterns: Match appearance characteristics indicated for each product type.
  1. Where appearance characteristics of acoustical panels are indicated by referencing pattern designations in ASTM E 1264 and not manufacturers' proprietary product designations, provide products selected by Architect from each manufacturer's full range that comply with requirements indicated for type, pattern, color, light reflectance, acoustical performance, edge detail, and size.
- C. Sound-Attenuation Blankets: ASTM C 665, Type I (blankets without membrane facing) produced by combining thermosetting resins with mineral fibers manufactured from glass, slag wool, or rock wool.

### 2.4 LARGE FORMAT ACOUSTICAL PANELS –

- A. Product: Item ACT-1 indicated on Finish Legend (Armstrong Ultima.)
- B. Classification: Provide panels complying with ASTM E 1264 for type, form, and pattern as follows:
  1. Type and Form: Type IV, mineral base with membrane-faced overlay; Form 2, water felted.
  2. Pattern: E (lightly textured).
- C. Color: White.
- D. NRC: Not less than 0.75.
- E. CAC: Not less than 35.
- F. Edge/Joint Detail: Beveled, tegular edges.
- G. Thickness: 3/4 inch.
- H. Modular Size: 2 by 6 inches.
- I. Broad Spectrum Antimicrobial Fungicide and Bactericide Treatment: Provide acoustical panels treated with manufacturer's standard antimicrobial formulation that inhibits fungus, mold,

mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D 3273 and evaluated according to ASTM D 3274 or ASTM G 21.

## 2.5 REVEAL EDGE ACOUSTICAL PANELS – ACT-2

- A. Product: Item ACT-2 indicated on Finish Legend (Armstrong Ultima.)
- B. Classification: Provide panels complying with ASTM E 1264 for type, form, and pattern as follows:
  - 1. Type and Form: Type IV, mineral base with membrane-faced overlay; Form 2, water felted.
  - 2. Pattern: E (lightly textured).
- C. Color: White.
- D. NRC: Not less than 0.75.
- E. CAC: Not less than 35.
- F. Edge/Joint Detail: Beveled, tegular edges.
- G. Thickness: 3/4 inch.
- H. Modular Size: 24 by 24 inches.
- I. Broad Spectrum Antimicrobial Fungicide and Bactericide Treatment: Provide acoustical panels treated with manufacturer's standard antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D 3273 and evaluated according to ASTM D 3274 or ASTM G 21.

## 2.6 WATER-REPELLENT-MEMBRANE-FACED ACOUSTICAL PANELS – ACT-3

- A. Basis of Design Subject to compliance with requirements, provide one of the following:
  - 1. Item ACT-3 on Finish Legend in the Drawings (Armstrong Ultima Health Zone.)
- B. Classification: Provide panels complying with ASTM E 1264 for type, form, and pattern as follows:
  - 1. Type and Form: Type IV, mineral base with membrane-faced overlay; Form 2, water felted.
  - 2. Pattern: E (lightly textured).
- C. Color: White.

- D. CAC: Not less than 38.
- E. NRC: Not less than 0.75.
- F. LR: 0.86
- G. Edge/Joint Detail: Flush.
- H. Thickness: 3/4 inch.
- I. Modular Size: 24 by 24 inches.
- J. Broad Spectrum Antimicrobial Fungicide and Bactericide Treatment: Provide acoustical panels treated with manufacturer's standard antimicrobial formulation that inhibits fungus, mold, mildew, and gram-positive and gram-negative bacteria and showing no mold, mildew, or bacterial growth when tested according to ASTM D 3273 and evaluated according to ASTM D 3274 or ASTM G 21.
- K. Tile Hold Down Clips: Provide hold down clips in all negative pressure patient rooms.

## 2.7 METAL SUSPENSION SYSTEMS, GENERAL

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Armstrong World Industries, Inc.
  - 2. CertainTeed Corporation.
  - 3. Chicago Metallic Corporation.
  - 4. USG Interiors, Inc.; Subsidiary of USG Corporation.
- B. Metal Suspension-System Standard: Provide manufacturer's standard direct-hung metal suspension systems of types, structural classifications, and finishes indicated that comply with applicable requirements in ASTM C 635/C 635M.
- C. Recycled Content: Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
- D. Wide-Face, Capped, Double-Web, Steel Suspension System: Main and cross runners roll formed from cold-rolled steel sheet; prepainted, electrolytically zinc coated, or hot-dip galvanized, G30 coating designation; with prefinished 15/16-inch-wide metal caps on flanges.
  - 1. Structural Classification: Heavy-duty system.
  - 2. End Condition of Cross Runners: Override (stepped) type.
  - 3. Face Design: Flat, flush.
  - 4. Cap Material: Cold-rolled steel or aluminum.
  - 5. Cap Finish: Painted to match color of acoustical unit.

## 2.8 ACCESSORIES

- A. Attachment Devices: Size for five times the design load indicated in ASTM C 635/C 635M, Table 1, "Direct Hung," unless otherwise indicated. Comply with seismic design requirements.
  - 1. Anchors in Concrete: Anchors of type and material indicated below, with holes or loops for attaching hangers of type indicated and with capability to sustain, without failure, a load equal to five times that imposed by ceiling construction, as determined by testing according to ASTM E 488 or ASTM E 1512 as applicable, conducted by a qualified testing and inspecting agency.
    - a. Type: Cast-in-place or postinstalled bonded anchors.
    - b. Corrosion Protection: Carbon-steel components zinc plated to comply with ASTM B 633, Class Fe/Zn 5 (0.005 mm) for Class SC 1 service condition.
- B. Wire Hangers, Braces, and Ties: Provide wires complying with the following requirements:
  - 1. Zinc-Coated, Carbon-Steel Wire: ASTM A 641/A 641M, Class 1 zinc coating, soft temper.
  - 2. Size: Select wire diameter so its stress at three times hanger design load (ASTM C 635/C 635M, Table 1, "Direct Hung") will be less than yield stress of wire, but provide not less than 0.135-inch- diameter wire.
- C. Hanger Rods: Mild steel, zinc coated or protected with rust-inhibitive paint.
- D. Angle Hangers: Angles with legs not less than 7/8 inch wide; formed with 0.04-inch- thick, galvanized-steel sheet complying with ASTM A 653/A 653M, G90 coating designation; with bolted connections and 5/16-inch- diameter bolts.
- E. Seismic Stabilizer Bars: Manufacturer's standard perimeter stabilizers designed to accommodate seismic forces.
- F. Seismic Struts: Manufacturer's standard compression struts designed to accommodate seismic forces.
- G. Seismic Clips: Manufacturer's standard seismic clips designed and spaced to secure acoustical panels in place.
- H. Hold-Down Clips: Where indicated, provide manufacturer's standard hold-down clips spaced 24 inches o.c. on all cross tees.

## 2.9 METAL EDGE MOLDINGS AND TRIM

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Armstrong World Industries, Inc.
  - 2. CertainTeed Corporation.

3. Chicago Metallic Corporation.
  4. USG Interiors, Inc.; Subsidiary of USG Corporation.
- B. Roll-Formed, Sheet-Metal Edge Moldings and Trim: Type and profile indicated or, if not indicated, manufacturer's standard moldings for edges and penetrations that comply with seismic design requirements; formed from sheet metal of same material, finish, and color as that used for exposed flanges of suspension-system runners.
1. Provide manufacturer's standard edge moldings that fit acoustical panel edge details and suspension systems indicated and that match width and configuration of exposed runners unless otherwise indicated.
  2. For lay-in panels with reveal edge details, provide stepped edge molding that forms reveal of same depth and width as that formed between edge of panel and flange at exposed suspension member.
  3. For circular penetrations of ceiling, provide edge moldings fabricated to diameter required to fit penetration exactly.

## 2.10 ACOUSTICAL SEALANT

- A. Acoustical Sealant: As specified in Section 07 9200 "Joint Sealants."

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, including structural framing to which acoustical panel ceilings attach or abut, with Installer present, for compliance with requirements specified in this and other Sections that affect ceiling installation and anchorage and with requirements for installation tolerances and other conditions affecting performance of acoustical panel ceilings.
- B. Examine acoustical panels before installation. Reject acoustical panels that are wet, moisture damaged, or mold damaged.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Measure each ceiling area and establish layout of acoustical panels to balance border widths at opposite edges of each ceiling. Avoid using less-than-half-width panels at borders, and comply with layout shown on reflected ceiling plans.
- B. Layout openings for penetrations centered on the penetrating items.

### 3.3 INSTALLATION

- A. Install acoustical panel ceilings according to ASTM C 636/C 636M, seismic design requirements, and manufacturer's written instructions.
- B. Suspend ceiling hangers from building's structural members and as follows:
  - 1. Install hangers plumb and free from contact with insulation or other objects within ceiling plenum that are not part of supporting structure or of ceiling suspension system.
  - 2. Splay hangers only where required to miss obstructions; offset resulting horizontal forces by bracing, countersplaying, or other equally effective means.
  - 3. Where width of ducts and other construction within ceiling plenum produces hanger spacings that interfere with location of hangers at spacings required to support standard suspension-system members, install supplemental suspension members and hangers in form of trapezes or equivalent devices.
  - 4. Secure wire hangers to ceiling-suspension members and to supports above with a minimum of three tight turns. Connect hangers directly either to structures or to inserts, eye screws, or other devices that are secure and appropriate for substrate and that will not deteriorate or otherwise fail due to age, corrosion, or elevated temperatures.
  - 5. Secure flat, angle, channel, and rod hangers to structure, including intermediate framing members, by attaching to inserts, eye screws, or other devices that are secure and appropriate for both the structure to which hangers are attached and the type of hanger involved. Install hangers in a manner that will not cause them to deteriorate or fail due to age, corrosion, or elevated temperatures.
  - 6. Do not support ceilings directly from permanent metal forms or floor deck. Fasten hangers to cast-in-place hanger inserts, postinstalled mechanical or adhesive anchors, or power-actuated fasteners that extend through forms into concrete.
  - 7. When steel framing does not permit installation of hanger wires at spacing required, install carrying channels or other supplemental support for attachment of hanger wires.
  - 8. Do not attach hangers to steel deck tabs.
  - 9. Do not attach hangers to steel roof deck. Attach hangers to structural members.
  - 10. Space hangers not more than 48 inches o.c. along each member supported directly from hangers unless otherwise indicated; provide hangers not more than 8 inches from ends of each member.
  - 11. Size supplemental suspension members and hangers to support ceiling loads within performance limits established by referenced standards and publications.
- C. Secure bracing wires to ceiling suspension members and to supports with a minimum of four tight turns. Suspend bracing from building's structural members as required for hangers, without attaching to permanent metal forms, steel deck, or steel deck tabs. Fasten bracing wires into concrete with cast-in-place or postinstalled anchors.
- D. Install edge moldings and trim of type indicated at perimeter of acoustical ceiling area and where necessary to conceal edges of acoustical panels.
  - 1. Apply acoustical sealant in a continuous ribbon concealed on back of vertical legs of moldings before they are installed.

2. Screw attach moldings to substrate at intervals not more than 16 inches o.c. and not more than 3 inches from ends, leveling with ceiling suspension system to a tolerance of 1/8 inch in 12 feet. Miter corners accurately and connect securely.
  3. Do not use exposed fasteners, including pop rivets, on moldings and trim.
- E. Install suspension-system runners so they are square and securely interlocked with one another. Remove and replace dented, bent, or kinked members.
- F. Install acoustical panels with undamaged edges and fit accurately into suspension-system runners and edge moldings. Scribe and cut panels at borders and penetrations to provide a neat, precise fit.
1. Arrange directionally patterned acoustical panels as follows:
    - a. As indicated on reflected ceiling plans.
  2. For reveal-edged panels on suspension-system runners, install panels with bottom of reveal in firm contact with top surface of runner flanges.
  3. Paint cut edges of panel remaining exposed after installation; match color of exposed panel surfaces using coating recommended in writing for this purpose by acoustical panel manufacturer.
  4. Install hold-down clips in areas indicated, in areas required by authorities having jurisdiction, and for fire-resistance ratings; space as recommended by panel manufacturer's written instructions unless otherwise indicated.
  5. Protect lighting fixtures and air ducts to comply with requirements indicated for fire-resistance-rated assembly.

### 3.4 ERECTION TOLERANCES

- A. Suspended Ceilings: Install main and cross runners level to a tolerance of 1/8 inch in 12 feet, non-cumulative.
- B. Moldings and Trim: Install moldings and trim to substrate and level with ceiling suspension system to a tolerance of 1/8 inch in 12 feet, non-cumulative.

### 3.5 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections and prepare test reports.
- B. Perform the following tests and inspections of completed installations of acoustical panel ceiling hangers and anchors and fasteners in successive stages and when installation of ceiling suspension systems on each floor has reached 20 percent completion, but no panels have been installed. Do not proceed with installations of acoustical panel ceiling hangers for the next area until test results for previously completed installations of acoustical panel ceiling hangers show compliance with requirements.

1. Within each test area, testing agency will select one of every 10 power-actuated fasteners and postinstalled anchors used to attach hangers to concrete and will test them for 200 lbf of tension; it will also select one of every two postinstalled anchors used to attach bracing wires to concrete and will test them for 440 lbf of tension.
  2. When testing discovers fasteners and anchors that do not comply with requirements, testing agency will test those anchors not previously tested until 20 pass consecutively and then will resume initial testing frequency.
- C. Acoustical panel ceiling hangers, anchors, and fasteners will be considered defective if they do not pass tests and inspections.
- D. Prepare test and inspection reports.

### 3.6 CLEANING

- A. Clean exposed surfaces of acoustical panel ceilings, including trim, edge moldings, and suspension-system members. Comply with manufacturer's written instructions for cleaning and touchup of minor finish damage.
- B. Remove and replace ceiling components that cannot be successfully cleaned and repaired to permanently eliminate evidence of damage.

END OF SECTION 09 5113



## SECTION 09 6513 - RESILIENT BASE AND ACCESSORIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Thermoplastic-rubber base.
  - 2. Rubber molding accessories.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Samples for Initial Selection: For each type of product indicated, if not indicated in Finish Legend.
- C. Samples for Verification: For each type of product indicated and for each color, texture, and pattern required in manufacturer's standard-size Samples, but not less than 12 inches long.
- D. Product Schedule: For resilient base and accessory products.

#### 1.4 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Furnish not less than 10 linear feet for every 500 linear feet or fraction thereof, of each type, color, pattern, and size of resilient product installed.

#### 1.5 QUALITY ASSURANCE

- A. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
  - 1. Coordinate mockups in this Section with mockups specified in other Sections.

2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
3. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

#### 1.6 DELIVERY, STORAGE, AND HANDLING

- A. Store resilient products and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F.

#### 1.7 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive resilient products during the following time periods:
  1. 48 hours before installation.
  2. During installation.
  3. 48 hours after installation.
- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.
- C. Install resilient products after other finishing operations, including painting, have been completed.

### PART 2 - PRODUCTS

#### 2.1 PERFORMANCE REQUIREMENTS

- A. Products shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

#### 2.2 THERMOSET-RUBBER BASE - RB-1

- A. Basis of Design Subject to compliance with requirements, provide one of the following:
  1. 29 Moonrock; Johnsonite; a Tarkett company, as indicated at item RB-1 on Finish Legend in Drawings.
  2. Equivalent product, approved by Architect prior to bid and complying with requirements and with Division 01, by one of the following manufacturers.

- a. Burke Mercer Flooring Products; a division of Burke Industries Inc.
  - b. Johnsonite; a Tarkett company.
  - c. Roppe Corporation, USA.
  - d. VPI Corporation.
- B. Product Standard: ASTM F 1861, Type TP (rubber, thermoplastic).
  - 1. Group: I (solid, homogeneous).
  - 2. Style and Location:
    - a. Style B, Cove: Provide in areas with resilient floor coverings.
- C. Thickness: 0.125 inch.
- D. Height: 4 inches.
- E. Lengths: Coils in manufacturer's standard length.
- F. Outside Corners: Job formed.
- G. Inside Corners: Job formed.
- H. Colors: As indicated on Finish Legend in Drawings.

## 2.3 RUBBER MOLDING ACCESSORY

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to the following:
  - 1. Roppe Corporation, USA.
  - 2. VPI Corporation.
- B. Description: Rubber carpet edge for glue-down applications, reducer strip for resilient flooring, joiner for tile and carpet, and transition strips.
- C. Profile and Dimensions: As indicated.
- D. Locations: Provide rubber molding accessories in areas indicated.
- E. Colors and Patterns: As selected by Architect from full range of industry colors.

## 2.4 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by resilient-product manufacturer for applications indicated.

- B. Adhesives: Water-resistant type recommended by resilient-product manufacturer for resilient products and substrate conditions indicated.
  - 1. Adhesives shall have a VOC content of 50 g/L or less.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
  - 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of resilient products.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.
  - 1. Installation of resilient products indicates acceptance of surfaces and conditions.

### 3.2 PREPARATION

- A. Prepare substrates according to manufacturer's written instructions to ensure adhesion of resilient products.
- B. Concrete Substrates for Resilient Stair Accessories: Prepare horizontal surfaces according to ASTM F 710.
  - 1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
  - 2. Remove substrate coatings and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by manufacturer. Do not use solvents.
  - 3. Alkalinity and Adhesion Testing: Perform tests recommended by manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
  - 4. Moisture Testing: Perform tests so that each test area does not exceed 200 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.
    - a. Anhydrous Calcium Chloride Test: ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
    - b. Relative Humidity Test: Using in-situ probes, ASTM F 2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.

- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install resilient products until they are the same temperature as the space where they are to be installed.
  - 1. At least 48 hours in advance of installation, move resilient products and installation materials into spaces where they will be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by resilient products.

### 3.3 RESILIENT BASE INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient base.
- B. Apply resilient base to walls, columns, pilasters, casework and cabinets in toe spaces, and other permanent fixtures in rooms and areas where base is required.
- C. Install resilient base in lengths as long as practical without gaps at seams and with tops of adjacent pieces aligned.
- D. Tightly adhere resilient base to substrate throughout length of each piece, with base in continuous contact with horizontal and vertical substrates.
- E. Do not stretch resilient base during installation.
- F. Preformed Corners: Install preformed corners before installing straight pieces.
- G. Job-Formed Corners:
  - 1. Inside Corners: Use straight pieces of maximum lengths possible and form with returns not less than 3 inches in length.
    - a. Miter corners to minimize open joints.

### 3.4 RESILIENT ACCESSORY INSTALLATION

- A. Comply with manufacturer's written instructions for installing resilient accessories.
- B. Resilient Molding Accessories: Butt to adjacent materials and tightly adhere to substrates throughout length of each piece. Install reducer strips at edges of floor covering that would otherwise be exposed.

### 3.5 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting resilient products.
- B. Perform the following operations immediately after completing resilient-product installation:
  - 1. Remove adhesive and other blemishes from exposed surfaces.
  - 2. Sweep and vacuum horizontal surfaces thoroughly.
  - 3. Damp-mop horizontal surfaces to remove marks and soil.
- C. Protect resilient products from mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period.
- D. Cover resilient products subject to wear and foot traffic until Substantial Completion.

END OF SECTION 09 6513

## SECTION 09 6543 - LINOLEUM FLOORING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Linoleum sheet flooring.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: For each type of linoleum flooring.
  - 1. Include flooring layouts, locations of seams, edges, columns, doorways, enclosing partitions, built-in furniture, cabinets, and cutouts.
  - 2. Show details of special patterns.
- C. Samples for Initial Selection: For each type of linoleum flooring indicated.
- D. Samples for Verification: For each type of linoleum flooring, in manufacturer's standard size, but not less than 6-by-9-inch sections of each different color and pattern required.
  - 1. Heat-Welding Bead: Include manufacturer's standard-size Samples, but not less than 9 inches long, of each color required.
- E. Heat-Welded Seam Samples: For each linoleum flooring product and welding bead color and pattern combination required; with seam running lengthwise and in center of 6-by-9-inch Sample applied to rigid backing and prepared by Installer for this Project.
- F. Product Schedule: For linoleum flooring. Use same designations indicated on Drawings.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For each type of linoleum flooring to include in maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Floor Tile: Furnish one box for every 50 boxes or fraction thereof, of each type, color, and pattern of floor tile installed.
  - 2. Sheet Flooring: Furnish not less than 10 linear feet for every 500 linear feet or fraction thereof, in roll form and in full roll width for each type, color, and pattern of sheet flooring installed.

1.7 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are competent in techniques required by manufacturer for flooring installation and seaming methods indicated.
  - 1. Engage an installer who employs workers for this Project who are trained or certified by flooring manufacturer for installation techniques required.
    - a. Contact manufacturer's rep Julie Jones for additional information and guidance. [Julie.jones@forbo.com](mailto:Julie.jones@forbo.com); 801-209-8143.
- B. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
  - 1. Coordinate mockups in this Section with mockups specified in other Sections.
    - a. Size: Minimum 100 sq. ft. for each type, color, and pattern in locations directed by Architect.
  - 2. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
  - 3. Install Mockup in presence of a senior technical installation representative from flooring manufacturer. The senior technical installation representative shall be on site to witness and comment on the seaming and installation procedures.
  - 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.



## 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Store flooring and installation materials in dry spaces protected from the weather, with ambient temperatures maintained within range recommended by manufacturer, but not less than 50 deg F or more than 90 deg F.
  - 1. Sheet Flooring: Store rolls upright.

## 1.9 FIELD CONDITIONS

- A. Maintain ambient temperatures within range recommended by manufacturer, but not less than 70 deg F or more than 95 deg F, in spaces to receive flooring during the following periods:
  - 1. 72 hours before installation.
  - 2. During installation.
  - 3. 72 hours after installation.
- B. After installation and until Substantial Completion, maintain ambient temperatures within range recommended by manufacturer, but not less than 55 deg F or more than 95 deg F.
- C. Close spaces to traffic during flooring installation.
- D. Close spaces to traffic for 72 hours after flooring installation.
- E. Install flooring after other finishing operations, including painting, have been completed.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Fire-Test-Response Characteristics: For linoleum flooring, as determined by testing identical products according to ASTM E648 or NFPA 253 by a qualified testing agency.
  - 1. Critical Radiant Flux Classification: Class I, not less than 0.45 W/sq. cm.
- B. Flooring products shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

### 2.2 LINOLEUM SHEET FLOORING

- A. Products: Provide Items SG-1, SG-2, SG-3 and SG-5 (Marmoleum linoleum sheet flooring by Forbo Industries, Inc.,) as indicated on Finish Legend in Drawings.
- B. Linoleum Sheet Flooring: ASTM F2034.
  - 1. Roll Size: In manufacturer's standard length, but not less than 78 inches wide.

- C. Thickness: 0.10 inch.
- D. Heat-Welding Bead: For seamless installation, solid-strand product of linoleum flooring manufacturer.
  - 1. Colors: As selected by Architect from manufacturer's full range.
- E. Integral-Flash-Cove-Base Accessories:
  - 1. Cove Strip: 1-inch radius, provided or approved by manufacturer.
  - 2. Cove-Base Cap Strip: Square stainless steel cap, provided or approved by manufacturer.
  - 3. Corners: Metal inside and outside corners and end stops or approved by resilient sheet flooring manufacturer.
- F. Colors and Patterns: As indicated on Finish Legend in Drawings.

## 2.3 INSTALLATION MATERIALS

- A. Trowelable Leveling and Patching Compounds: Latex-modified, portland-cement-based or blended hydraulic-cement-based formulation provided or approved by linoleum flooring manufacturer for applications indicated.
- B. Adhesives: Water-resistant type recommended by flooring and adhesive manufacturers to suit products and substrate conditions indicated.
  - 1. Adhesives shall have a VOC content of 50 g/L or less.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, with Installer present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
  - 1. Verify that finishes of substrates comply with tolerances and other requirements specified in other Sections and that substrates are free of cracks, ridges, depressions, scale, and foreign deposits that might interfere with adhesion of flooring.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Prepare substrates according to linoleum flooring manufacturer's written instructions to ensure adhesion of flooring.
- B. Concrete Substrates: Prepare according to ASTM F710.

1. Verify that substrates are dry and free of curing compounds, sealers, and hardeners.
  2. Remove substrate coatings and other substances that are incompatible with flooring adhesives and that contain soap, wax, oil, or silicone, using mechanical methods recommended by linoleum flooring manufacturer. Do not use solvents.
  3. Alkalinity and Adhesion Testing: Perform tests recommended by linoleum flooring manufacturer. Proceed with installation only after substrate alkalinity falls within range on pH scale recommended by manufacturer in writing, but not less than 5 or more than 9 pH.
  4. Moisture Testing: Perform tests so that each test area does not exceed 200 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.
    - a. Anhydrous Calcium Chloride Test: ASTM F1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
    - b. Relative Humidity Test: Using in-situ probes, ASTM F2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.
- C. Fill cracks, holes, and depressions in substrates with trowelable leveling and patching compound; remove bumps and ridges to produce a uniform and smooth substrate.
- D. Do not install flooring until materials are the same temperature as space where they are to be installed.
1. At least 72 hours in advance of installation, move flooring and installation materials into spaces where they will be installed.
- E. Immediately before installation, sweep and vacuum clean substrates to be covered by flooring.

### 3.3 INSTALLATION, GENERAL

- A. Comply with manufacturer's written instructions for installing flooring.
- B. Scribe and cut flooring to butt neatly and tightly to vertical surfaces and permanent fixtures, including built-in furniture, cabinets, pipes, outlets, edgings, thresholds, door frames, and nosings.
- C. Extend flooring into toe spaces, door reveals, closets, and similar openings.
- D. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on flooring as marked on substrates. Use chalk or other nonpermanent marking device.
- E. Install flooring on covers for telephone and electrical ducts and similar items in installation areas. Maintain overall continuity of color and pattern between pieces of flooring installed on covers and adjoining flooring. Tightly adhere flooring edges to substrates that abut covers and to cover perimeters.

- F. Adhere flooring to substrates using a full spread of adhesive applied to substrate to produce a completed installation without open cracks, voids, raising and puckering at joints, telegraphing of adhesive spreader marks, and other surface imperfections.
- G. Heat-Welded Seams: For seamless installation, comply with ASTM F1516. Rout joints and heat weld with welding bead to fuse sections permanently into a seamless flooring installation. Prepare, weld, and finish seams to produce surfaces flush with adjoining flooring surfaces. Use where net fit seams are not specified to be used.
  - 1. A welded seam can also be achieved with a 1 mm prepared groove, filled with Marmoleum ETU paste weld.
  - 2. Net Fit Seams: Seams must be undescribed, with no fullness or gaps, follow manufactures installation guidelines - material must be placed into wet adhesive and rolled immediately with a hand seam roller. It is also crucial to roll each drop, or cut, of the installed material immediately after placement into the adhesive with a 100-pound roller in both directions, first through the width and then the length, to achieve proper adhesive transfer. Additional rolling after the seaming is complete, as well as before you leave the room, or thirty minutes after the initial rolling, is suggested to ensure that the material is flat and fully adhered.) If there are any gaps, fill the gaps with Forbo's ETU paste weld.
    - a. Use net fit seams where SG-1 material adjoins other sheets of SG-1 material, with the following exceptions:
      - 1) At corners of SG-1 material, use heat-welded seams.
      - 2) Where SG-1 material adjoins SG-2 or SG-3 material, use heat welded seams.
        - a) Color of Heat Welds Between Linoleum Materials: Where SG-1 adjoins SG-2 or SG-3 materials, match weld color to the darker (SG-2 or SG-3) material.

### 3.4 LINOLEUM SHEET FLOORING INSTALLATION

- A. Unroll linoleum sheet flooring and allow it to stabilize before cutting and fitting.
- B. Lay out linoleum sheet flooring as follows:
  - 1. Maintain uniformity of flooring direction.
  - 2. Minimize number of seams; place seams in inconspicuous and low-traffic areas, at least 6 inches away from parallel joints in flooring substrates.
  - 3. Match edges of flooring for color shading at seams.
  - 4. Avoid cross seams.
  - 5. Eliminate deformations that result from hanging method used during drying process (stove bar marks).
- C. Integral-Flash-Cove Base: Cove flooring 4 inches up vertical surfaces. Support flooring at horizontal and vertical junction with cove strip. Butt at top against cap strip.

1. Install metal corners at inside and outside corners.

### 3.5 CLEANING AND PROTECTION

- A. Comply with manufacturer's written instructions for cleaning and protecting linoleum flooring.
- B. Perform the following operations immediately after completing linoleum flooring installation:
  1. Remove adhesive and other blemishes from surfaces.
  2. Sweep and vacuum surfaces thoroughly.
  3. Damp-mop surfaces to remove marks and soil.
    - a. Do not wash floor coverings for 72 hours after installation.
- C. Protect floor coverings against mars, marks, indentations, and other damage from construction operations and placement of equipment and fixtures during remainder of construction period. Use protection methods indicated or recommended in writing by manufacturer.
  1. Cover linoleum floor coverings with undyed, untreated building paper until inspection for Substantial Completion. If using tape to adhere building paper, please test prior to ensure that Tape residue will not damage the factory applied Top Shield.
    - a. Allow drying room film (yellow film caused by linseed oil oxidation) to disappear before Substantial Completion.
  2. Do not move heavy and sharp objects directly over floor covering surfaces. Place plywood or hardboard panels over floor coverings and under objects while they are being moved. Slide or roll objects over panels without moving panels.

END OF SECTION 09 6543

## SECTION 09 6813 - TILE CARPETING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes:
  - 1. Modular, tufted carpet tile.
- B. Related Requirements:
  - 1. Section 09 6513 "Resilient Base and Accessories" for resilient wall base and accessories installed with carpet tile.

#### 1.3 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.
  - 1. Review methods and procedures related to carpet tile installation including, but not limited to, the following:
    - a. Review delivery, storage, and handling procedures.
    - b. Review ambient conditions and ventilation procedures.
    - c. Review subfloor preparation procedures.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include manufacturer's written data on physical characteristics, durability, and fade resistance.
  - 2. Include installation recommendations for each type of substrate.
- B. Sustainable Design Submittals:
  - 1. Product Data: For adhesives, indicating VOC content.
  - 2. Laboratory Test Reports: For adhesives, indicating compliance with requirements for low-emitting materials.

3. Laboratory Test Reports: For flooring products, indicating compliance with requirements for low-emitting materials.
- C. Shop Drawings: Show the following:
1. Columns, doorways, enclosing walls or partitions, built-in cabinets, and locations where cutouts are required in carpet tiles.
  2. Carpet tile type, color, and dye lot.
  3. Type of subfloor.
  4. Type of installation.
  5. Pattern of installation.
  6. Pattern type, location, and direction.
  7. Pile direction.
  8. Type, color, and location of edge, transition, and other accessory strips.
  9. Transition details to other flooring materials.
- D. Samples for Verification: For each of the following products and for each color and texture required. Label each Sample with manufacturer's name, material description, color, pattern, and designation indicated on Drawings and in schedules.
1. Carpet Tile: Full-size Sample.
  2. Exposed Edge, Transition, and Other Accessory Stripping: 9-inch- long Samples.
- E. Product Schedule: For carpet tile. Use same designations indicated on Drawings.
- F. Sustainable Product Certification: Provide ANSI/NSF 140 certification for carpet products.

## 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer.
- B. Product Test Reports: For carpet tile, for tests performed by a qualified testing agency.
- C. Sample Warranty: For special warranty.

## 1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For carpet tiles to include in maintenance manuals. Include the following:
  1. Methods for maintaining carpet tile, including cleaning and stain-removal products and procedures and manufacturer's recommended maintenance schedule.
  2. Precautions for cleaning materials and methods that could be detrimental to carpet tile.

## 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Carpet Tile: Full-size units equal to 5 percent of amount installed for each type indicated, but not less than 10 sq. yd.

#### 1.8 QUALITY ASSURANCE

- A. Installer Qualifications: An experienced installer who is certified by the International Certified Floorcovering Installers Association at the Commercial II certification level.
- B. Mockups: Build mockups to verify selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for fabrication and installation.
  1. Build mockups at locations and in sizes as directed by Architect.
  2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

#### 1.9 DELIVERY, STORAGE, AND HANDLING

- A. Comply with CRI's "CRI Carpet Installation Standard."

#### 1.10 FIELD CONDITIONS

- A. Comply with CRI 104 for temperature, humidity, and ventilation limitations.
- B. Environmental Limitations: Do not deliver or install carpet tiles until spaces are enclosed and weathertight, wet-work in spaces is complete and dry, and ambient temperature and humidity conditions are maintained at levels planned for building occupants during the remainder of the construction period.
- C. Do not install carpet tiles over concrete slabs until slabs have cured and are sufficiently dry to bond with adhesive and concrete slabs have pH range recommended by carpet tile manufacturer.
- D. Where demountable partitions or other items are indicated for installation on top of carpet tiles, install carpet tiles before installing these items.

#### 1.11 WARRANTY

- A. Special Warranty for Carpet Tiles: Manufacturer agrees to repair or replace components of carpet tile installation that fail in materials or workmanship within specified warranty period.
  1. Warranty does not include deterioration or failure of carpet tile due to unusual traffic, failure of substrate, vandalism, or abuse.
  2. Failures include, but are not limited to, the following:
    - a. More than 10 percent edge raveling, snags, and runs.
    - b. Dimensional instability.
    - c. Excess static discharge.



- d. Loss of tuft-bind strength.
    - e. Loss of face fiber.
    - f. Delamination.
    - g. Peaks or valleys resulting from faulty installation, such as seaming or seam failure.
  3. Warranty Period: 10 years from date of Substantial Completion.
- B. Installer Guarantee for Carpet Tiles: Installer agrees in writing to reinstall or repair carpet that is wrinkled and to correct any other condition due to faulty installation, such as "peaks" or "valley" in seaming or seam failure, within specified warranty period.
  1. Guarantee does not include deterioration or failure of carpet tile due to unusual traffic, failure of substrate, vandalism, or abuse.
  2. Repairs or replacements made under the guarantee shall be provided by the Contractor at no additional charge.
  3. Carpet products shall be guaranteed in accordance with manufacturer's standard guarantee for category type.
  4. Guarantee Period: 2 years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Products: Provide carpet tile products by The Mohawk group, as indicated on Finish Legend on Sheet AF100 in Drawings.

### 2.2 CARPET TILE CPT-3

- A. Product: Mohawk Group (The); Mohawk Carpet, LLC; Streetscapes GT308.
- B. Color: Match Architect's samples.
- C. Pattern: Match Architect's samples.
- D. Fiber Type: Duracolor® Premium Nylon.
- E. Pile Characteristic: Tufted patterned-tip-shear pile.
- F. Density: 8,415 oz./cu. yd.
- G. Pile Thickness: 0.077 inches for finished carpet tile.
- H. Stitches: 11.4 stitches per inch.
- I. Gage: 1/12 ends per inch.
- J. Face Weight: 18 oz./sq. yd.

- K. Backing System: EcoFlex NXT.
- L. Size: 24 by 24 inches.
- M. Applied Treatments:
  - 1. Soil-Resistance Treatment: Manufacturer's standard treatment.
  - 2. Antimicrobial Treatment: Manufacturer's standard treatment that protects carpet tiles as follows:
    - a. Antimicrobial Activity: Not less than 2-mm halo of inhibition for gram-positive bacteria, not less than 1-mm halo of inhibition for gram-negative bacteria, and no fungal growth, according to AATCC 174.
- N. Performance Characteristics:
  - 1. Dry Breaking Strength: Not less than 100 lbf according to ASTM D 2646.
  - 2. Dimensional Tolerance: Within 1/32 inch of specified size dimensions, as determined by physical measurement.
  - 3. Dimensional Stability: 0.2 percent or less according to ISO 2551 (Aachen Test).
  - 4. Electrostatic Propensity: Less than 3.5 kV according to AATCC 134.

## 2.3 INSTALLATION ACCESSORIES

- A. Trowelable Leveling and Patching Compounds: Latex-modified, hydraulic-cement-based formulation provided or recommended by carpet tile manufacturer.
- B. Adhesives: Water-resistant, mildew-resistant, nonstaining, pressure-sensitive type to suit products and subfloor conditions indicated, that comply with flammability requirements for installed carpet tile, and are recommended by carpet tile manufacturer for releasable installation.
  - 1. Adhesives shall have a VOC content of 50 g/L or less.
  - 2. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for maximum moisture content, alkalinity range, installation tolerances, and other conditions affecting carpet tile performance.
- B. Examine carpet tile for type, color, pattern, and potential defects.

- C. Concrete Slabs: Verify that finishes comply with requirements specified in Section 03 3000 "Cast-in-Place Concrete" and that surfaces are free of cracks, ridges, depressions, scale, and foreign deposits.
  - 1. Moisture Testing: Perform tests so that each test area does not exceed 200 sq. ft., and perform no fewer than three tests in each installation area and with test areas evenly spaced in installation areas.
    - a. Anhydrous Calcium Chloride Test: ASTM F 1869. Proceed with installation only after substrates have maximum moisture-vapor-emission rate of 3 lb of water/1000 sq. ft. in 24 hours.
    - b. Relative Humidity Test: Using in situ probes, ASTM F 2170. Proceed with installation only after substrates have a maximum 75 percent relative humidity level measurement.
    - c. Perform additional moisture tests recommended in writing by adhesive and carpet tile manufacturers. Proceed with installation only after substrates pass testing.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. General: Comply with CRI's "Carpet Installation Standards" and with carpet tile manufacturer's written installation instructions for preparing substrates indicated to receive carpet tile.
- B. Use trowelable leveling and patching compounds, according to manufacturer's written instructions, to fill cracks, holes, depressions, and protrusions in substrates. Fill or level cracks, holes and depressions 1/16 inch wide or wider, and protrusions more than 1/32 inch unless more stringent requirements are required by manufacturer's written instructions.
- C. Concrete Substrates: Remove coatings, including foreign matter, dust, moisture, curing compounds, and other substances that are incompatible with adhesives and that contain soap, wax, oil, or silicone, without using solvents. Use mechanical methods recommended in writing by adhesive and carpet tile manufacturers.
- D. Broom and vacuum clean substrates to be covered immediately before installing carpet tile.
- E. Notify Owner in writing of any conditions which will be detrimental to the carpet installation. The start of carpet installation shall be an indication of acceptance of the floor by the installation contractor.

### 3.3 INSTALLATION

- A. General: Comply with CRI's "CRI Carpet Installation Standard," Section 18, "Modular Carpet" and with carpet tile manufacturer's written installation instructions.
- B. Installation Method: As recommended in writing by carpet tile manufacturer.
- C. Maintain dye lot integrity. Do not mix dye lots in same area.

- D. Cut and fit carpet tile to butt tightly to vertical surfaces, permanent fixtures, and built-in furniture including cabinets, pipes, outlets, edgings, thresholds, and nosings. Bind or seal cut edges as recommended by carpet tile manufacturer.
- E. Extend carpet tile into toe spaces, door reveals, closets, open-bottomed obstructions, removable flanges, alcoves, and similar openings.
- F. Maintain reference markers, holes, and openings that are in place or marked for future cutting by repeating on finish flooring as marked on subfloor. Use nonpermanent, nonstaining marking device.
- G. Install pattern parallel to walls and borders.

### 3.4 CLEANING AND PROTECTION

- A. Perform the following operations immediately after installing carpet tile:
  - 1. Remove excess adhesive, seam sealer, and other surface blemishes using cleaner recommended by carpet tile manufacturer.
  - 2. Remove yarns that protrude from carpet tile surface.
  - 3. Vacuum carpet tile using commercial machine with face-beater element.
- B. Protect installed carpet tile to comply with CRI's "Carpet Installation Standard," Section 20, "Protecting Indoor Installations."
- C. Protect carpet tile against damage from construction operations and placement of equipment and fixtures during the remainder of construction period. Use protection methods indicated or recommended in writing by carpet tile manufacturer.

END OF SECTION 09 6813

## SECTION 09 9123 - INTERIOR PAINTING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes surface preparation and the application of paint systems on the following interior substrates:
  - 1. Steel.
  - 2. Gypsum board.
  - 3. Gypsum board wall in Restrooms and behind sinks, and elsewhere where indicated.

#### 1.3 DEFINITIONS

- A. Gloss Level 3 (Eggshell): 10 to 25 units at 60 degrees and 10 to 35 units at 85 degrees, according to ASTM D 523.
- B. Gloss Level 4 (Satin): 20 to 35 units at 60 degrees and not less than 35 units at 85 degrees, according to ASTM D 523.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product. Include preparation requirements and application instructions.
- B. Samples for Verification: For each type of paint system and in each color and gloss of topcoat.
  - 1. Submit Samples on rigid backing, 8 inches square.
  - 2. Step coats on Samples to show each coat required for system.
  - 3. Label each coat of each Sample.
  - 4. Label each Sample for location and application area.
- C. Product List: Cross-reference to paint system and locations of application areas. Use same designations indicated on Drawings and in schedules. Include color designations.

## 1.5 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same product run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Paint: 5 percent, but not less than 1 gal. of each material and color applied.

## 1.6 QUALITY ASSURANCE

- A. Mockups: Apply mockups of each paint system indicated and each color and finish selected to verify preliminary selections made under Sample submittals and to demonstrate aesthetic effects and set quality standards for materials and execution.
  - 1. Architect will select one surface to represent surfaces and conditions for application of each paint system specified in Part 3.
    - a. Vertical and Horizontal Surfaces: Provide samples of at least 100 sq. ft.
    - b. Other Items: Architect will designate items or areas required.
  - 2. Final approval of color selections will be based on mockups.
    - a. If preliminary color selections are not approved, apply additional mockups of additional colors selected by Architect at no added cost to Owner.
  - 3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
  - 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

## 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Store materials not in use in tightly covered containers in well-ventilated areas with ambient temperatures continuously maintained at not less than 45 deg F.
  - 1. Maintain containers in clean condition, free of foreign materials and residue.
  - 2. Remove rags and waste from storage areas daily.

## 1.8 FIELD CONDITIONS

- A. Apply paints only when temperature of surfaces to be painted and ambient air temperatures are between 50 and 95 deg F.
- B. Do not apply paints when relative humidity exceeds 85 percent; at temperatures less than 5 deg F above the dew point; or to damp or wet surfaces.

1.9 WARRANTY

- A. Use paints that carry a minimum 5-year warranty.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by Sherwin-Williams; Paint Stores Group.

2.2 PAINT, GENERAL

- A. MPI Standards: Unless indicated otherwise, provide products that comply with MPI standards indicated and that are listed in its "MPI Approved Products List."
- B. Material Compatibility:
  - 1. Provide materials for use within each paint system that are compatible with one another and substrates indicated, under conditions of service and application as demonstrated by manufacturer, based on testing and field experience.
  - 2. For each coat in a paint system, provide products recommended in writing by manufacturers of topcoat for use in paint system and on substrate indicated.
- C. VOC Content: For field applications that are inside the weatherproofing system, paints and coatings shall comply with VOC content limits of authorities having jurisdiction and the following VOC content limits:
  - 1. Flat Paints and Coatings: 50 g/L.
  - 2. Nonflat Paints and Coatings: 50 g/L.
  - 3. Primers, Sealers, and Undercoaters: 100 g/L.
  - 4. Rust-Preventive Coatings: 100 g/L.
  - 5. Zinc-Rich Industrial Maintenance Primers: 100 g/L.
  - 6. Pretreatment Wash Primers: 420 g/L.
- D. Low-Emitting Materials: For field applications that are inside the weatherproofing system, 90 percent of paints and coatings shall comply with the requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- E. Paint Colors: Close match colors P-1, P-2, P-3, P-4, P-7 and P-9, as indicated on Finish Legend in Drawings, or if not indicated, as selected by Architect from manufacturer's full range.
- F. Epoxy Paint Colors: Close match EP-2, EP-3, EP-4, and EP-7, indicated on Finish Legend in Drawings, or if not indicated, as selected by Architect from manufacturer's full range.

## 2.3 SOURCE QUALITY CONTROL

- A. Testing of Paint Materials: Owner reserves the right to invoke the following procedure:
  - 1. Owner will engage the services of a qualified testing agency to sample paint materials. Contractor will be notified in advance and may be present when samples are taken. If paint materials have already been delivered to Project site, samples may be taken at Project site. Samples will be identified, sealed, and certified by testing agency.
  - 2. Testing agency will perform tests for compliance with product requirements.
  - 3. Owner may direct Contractor to stop applying coatings if test results show materials being used do not comply with product requirements. Contractor shall remove noncomplying paint materials from Project site, pay for testing, and repaint surfaces painted with rejected materials. Contractor will be required to remove rejected materials from previously painted surfaces if, on repainting with complying materials, the two paints are incompatible.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions, with Applicator present, for compliance with requirements for maximum moisture content and other conditions affecting performance of the Work.
- B. Maximum Moisture Content of Substrates: When measured with an electronic moisture meter as follows:
  - 1. Gypsum Board: 12 percent.
- C. Gypsum Board Substrates: Verify that finishing compound is sanded smooth.
- D. Verify suitability of substrates, including surface conditions and compatibility with existing finishes and primers.
- E. Proceed with coating application only after unsatisfactory conditions have been corrected.
  - 1. Application of coating indicates acceptance of surfaces and conditions.

### 3.2 PREPARATION

- A. Comply with manufacturer's written instructions and recommendations in "MPI Manual" applicable to substrates indicated.
- B. Remove hardware, covers, plates, and similar items already in place that are removable and are not to be painted. If removal is impractical or impossible because of size or weight of item, provide surface-applied protection before surface preparation and painting.



1. After completing painting operations, use workers skilled in the trades involved to reinstall items that were removed. Remove surface-applied protection if any.
- C. Clean substrates of substances that could impair bond of paints, including dust, dirt, oil, grease, and incompatible paints and encapsulants.
  1. Remove incompatible primers and reprime substrate with compatible primers or apply tie coat as required to produce paint systems indicated.
- D. Steel Substrates: Remove rust, loose mill scale, and shop primer, if any. Clean using methods recommended in writing by paint manufacturer, but not less than the following:
  1. SSPC-SP 3, "Power Tool Cleaning."
- E. Shop-Primed Steel Substrates: Clean field welds, bolted connections, and abraded areas of shop paint, and paint exposed areas with the same material as used for shop priming to comply with SSPC-PA 1 for touching up shop-primed surfaces.

### 3.3 APPLICATION

- A. Apply paints according to manufacturer's written instructions and to recommendations in "MPI Manual."
  1. Use applicators and techniques suited for paint and substrate indicated.
  2. Paint surfaces behind movable equipment and furniture same as similar exposed surfaces. Before final installation, paint surfaces behind permanently fixed equipment or furniture with prime coat only.
  3. Paint front and backsides of access panels, removable or hinged covers, and similar hinged items to match exposed surfaces.
  4. Do not paint over labels of independent testing agencies or equipment name, identification, performance rating, or nomenclature plates.
  5. Primers specified in painting schedules may be omitted on items that are factory primed or factory finished if acceptable to topcoat manufacturers.
- B. If undercoats or other conditions show through topcoat, apply additional coats until cured film has a uniform paint finish, color, and appearance.
- C. Apply paints to produce surface films without cloudiness, spotting, holidays, laps, brush marks, roller tracking, runs, sags, ropiness, or other surface imperfections. Cut in sharp lines and color breaks.
- D. Painting Fire Suppression, Plumbing, HVAC, Electrical, Communication, and Electronic Safety and Security Work:
  1. Paint the following work where exposed in equipment rooms:
    - a. Equipment, including panelboards and switch gear.
    - b. Uninsulated metal piping.
    - c. Uninsulated plastic piping.

- d. Pipe hangers and supports.
  - e. Metal conduit.
  - f. Plastic conduit.
  - g. Tanks that do not have factory-applied final finishes.
  - h. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.
- 2. Paint the following work where exposed in occupied spaces:
  - a. Equipment, including panelboards.
  - b. Uninsulated metal piping.
  - c. Uninsulated plastic piping.
  - d. Pipe hangers and supports.
  - e. Metal conduit.
  - f. Plastic conduit.
  - g. Duct, equipment, and pipe insulation having cotton or canvas insulation covering or other paintable jacket material.
  - h. Other items as directed by Architect.
- 3. Paint portions of internal surfaces of metal ducts, without liner, behind air inlets and outlets that are visible from occupied spaces.

### 3.4 FIELD QUALITY CONTROL

- A. Dry Film Thickness Testing: Owner may engage the services of a qualified testing and inspecting agency to inspect and test paint for dry film thickness.
  - 1. Contractor shall touch up and restore painted surfaces damaged by testing.
  - 2. If test results show that dry film thickness of applied paint does not comply with paint manufacturer's written recommendations, Contractor shall pay for testing and apply additional coats as needed to provide dry film thickness that complies with paint manufacturer's written recommendations.

### 3.5 CLEANING AND PROTECTION

- A. At end of each workday, remove rubbish, empty cans, rags, and other discarded materials from Project site.
- B. After completing paint application, clean spattered surfaces. Remove spattered paints by washing, scraping, or other methods. Do not scratch or damage adjacent finished surfaces.
- C. Protect work of other trades against damage from paint application. Correct damage to work of other trades by cleaning, repairing, replacing, and refinishing, as approved by Architect, and leave in an undamaged condition.
- D. At completion of construction activities of other trades, touch up and restore damaged or defaced painted surfaces.

### 3.6 INTERIOR PAINTING SCHEDULE

#### A. Steel Substrates:

1. Latex System, Alkyd Primer MPI INT 5.1Q:
  - a. Prime Coat: Primer, alkyd, anti-corrosive, for metal, MPI #79.
    - 1) Sherwin-Williams: Pro Industrial Pro-Cryl Primer, B66-1310 Series.
  - b. Intermediate Coat: Latex, interior, matching topcoat.
  - c. Topcoat: Latex, interior (MPI Gloss Level 4), MPI #43.
    - 1) Sherwin-Williams: ProMar 200 Zero VOC; Interior Latex Semi-Gloss - B31W02651/B31WQ2651.

#### B. Gypsum Board Substrates:

1. High-Performance Architectural Latex System MPI INT 9.2B (Ceilings and Walls):
  - a. Prime Coat: Primer sealer, latex, interior, MPI #50.
    - 1) Sherwin-Williams: ProMar 200 Zero; Interior Latex Primer - B28W02600/B28WQ2600.
  - b. Intermediate Coat: Latex, interior, high performance architectural, matching topcoat.
  - c. Topcoat: Latex, interior, high performance architectural (MPI Gloss Level 3), MPI #139.
    - 1) Sherwin-Williams: ProMar 200 HP Zero VOC; Interior Acrylic Eg-Shel – B20W01951.
2. High-Performance Architectural Latex System MPI INT 9.2B (Epoxy-coated walls in Restrooms, behind sinks, and elsewhere where indicated.)
  - a. Prime Coat: Primer sealer, latex, interior, MPI #50.
    - 1) Sherwin-Williams: ProMar 200 Zero; Interior Latex Primer - B28W02600/B28WQ2600.
  - b. Intermediate Coat: Latex, interior, high performance architectural, matching topcoat.
  - c. Topcoat: Latex, interior, high performance architectural (MPI Gloss Level 3), MPI #139.
    - 1) Sherwin-Williams: Pro Industrial Waterbased Catalyzed Epoxy; Epoxy Eg-Shel - B73-360 Series.

ACC LEVEL 3 OR EXPANSION REMODEL

University of Utah

Salt Lake City, Utah 84132

Code Review

END OF SECTION 09 9123

## SECTION 10 2123 - CUBICLES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Curtain tracks and curtain carriers.
  - 2. IV tracks and hangers.
  - 3. Cubicle privacy curtains.
  - 4. Cubicle acoustical privacy curtains.
- B. Related Sections include the following:
  - 1. Section 06 1053 "Miscellaneous Rough Carpentry" for wood blocking for mounting items requiring anchorage.
  - 2. Section 09 2216 "Non-Structural Metal Framing" for metal framing and furring for mounting items requiring anchorage.

#### 1.3 DEFINITIONS

- A. IV: Intravenous.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: Include durability, fade resistance, and fire-test-response characteristics for each type of curtain fabric indicated.
  - 1. Include data on each type of applied curtain treatment.
- B. Shop Drawings: Show layout and types of cubicles, sizes of curtains, number of carriers, anchorage details, and conditions requiring accessories. Indicate dimensions taken from field measurements.
  - 1. Include details on blocking above ceiling and in walls.
- C. Coordination Drawings: Reflected ceiling plans drawn to scale and coordinating penetrations and ceiling-mounted items. Show the following:

1. Ceiling suspension assembly members.
2. Method of attaching track hangers to building structure.
3. Ceiling-mounted items including light fixtures, diffusers, grilles, speakers, sprinklers, and access panels.

D. Samples for Verification: Full-size units of each type of the following products:

1. Curtain Fabrics: 12-inch-square swatch or larger Sample as required to show complete pattern repeat, from dye lot used for the Work, with specified treatments applied. Mark top and face of material.
2. Mesh Top: Not less than 4 inches square.
3. Curtain Track: Not less than 4 inches long.
4. Curtain Carrier: Full-size unit.
5. IV Track: Not less than 4 inches long.

1.5 INFORMATION SUBMITTALS

- A. Cubicle Schedule: Use same room designations as indicated on Drawings.
- B. Product Certificates: Signed by manufacturers of tracks and curtains certifying that products furnished comply with requirements.

1.6 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For tracks and curtains to include in maintenance manuals specified in Division 01.

1.7 DELIVERY, STORAGE AND HANDLING

- A. Deliver materials in unopened factory packaging to the jobsite.
- B. Inspect materials at delivery to assure that specified products have been received.
- C. Store in original packaging in a climate-controlled location away from direct sunlight.

1.8 PROJECT CONDITIONS

- A. Field Measurements: Where cubicles are indicated to fit to other construction, verify dimensions of other construction by field measurements before fabrication and indicate measurements on Shop Drawings. Coordinate fabrication schedule with construction progress to avoid delaying the Work.
- B. Environmental Limitations: Do not install cubicles until spaces are enclosed and weatherproof, wet work in spaces is complete and dry, work above ceilings is complete, and ambient temperature and humidity conditions are maintained at the levels indicated for Project when occupied for its intended use.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

A. Curtains: Provide curtain fabrics with the following characteristics:

1. Fabrics are launderable to a temperature of not less than 160 deg F.
2. Fabrics are flame resistant and are identical to those that have passed NFPA 701 and (CAL19) California Administrative Code Title 19-Public Safety, Section 1237, Flame Resistance, Small Scale Test, when tested by a testing and inspecting agency acceptable to authorities having jurisdiction.
  - a. Identify fabrics with appropriate markings of applicable testing and inspecting agency.
3. Fabrics reduce bacterial growth and are identical to those that have passed ASTM E2149, when tested by a testing and inspecting agency acceptable to authorities having jurisdiction.
4. Fabrics repel liquids when tested in accordance with AATCC-22, AATCC-118 and AATCC-193.

### 2.2 MANUFACTURERS

- A. Match existing: New tracks are intended to match existing.
- B. Basis of Design Products: Subject to compliance with requirements, provide the named Basis of Design product or an equivalent comparable product, approved by Architect prior to bid, by one of the following manufacturers:
1. ADC Hospital Equipment, Division of Automatic Devices Company.
  2. A. R. Nelson Co.
  3. Colton, Inc.
  4. Construction Specialties, Inc.
  5. Imperial Fastener Company.
  6. InPro Clickeze Privacy Systems
  7. Salsbury Industries.

### 2.3 CURTAIN TRACKS

- A. Basis-of-Design: Colton, Inc.; SKS-Track and Accessories.
- B. Extruded-Aluminum Track: Not less than 3/4 inches wide by 3/4-inch-high.
1. Basis of Design Product: Colton, Inc.; SKS-3003-25 or approved equal.
  2. Finish: Baked enamel.

- C. Track Accessories: Fabricate splices, end caps, connectors, end stops, coupling and joining sleeves, wall flanges, brackets, ceiling clips, and other accessories from same material and with same finish as track.
  - 1. End Stop:
    - a. Basis of Design Product: Colton, Inc.; SKS-52301-25 or approved equal.
- D. Curtain Carriers: One-piece glide with ball-bearings and stainless steel hook.
  - 1. Basis of Design Product: Colton, Inc.; SKS-52107 or approved equal
- E. Exposed Fasteners: Stainless steel.
- F. Concealed Fasteners: Hot-dip galvanized.

## 2.4 IV SUPPORT SYSTEMS

- A. Basis-of-Design: Imperial Fastener Company; Track 1000 with carrier 1007, splice 1009, and adjustable hanger 3001.
- B. Extruded-Aluminum IV Track: Not less than 1-9/16 inches wide by 15/16-inch-high; with minimum wall thickness of 0.075 inch.
  - 1. Curved Track: Factory fabricated 12-inch- radius bends.
  - 2. Finish: Baked enamel.
- C. IV Carriers: Four nylon rollers and steel or stainless-steel axles, with ball bearings, with hanger loop fabricated from 1/4-inch-diameter stainless steel.
- D. Telescoping IV Hangers: 3/4-inch stainless-steel main shaft and a 3/8-inch stainless-steel inner shaft, vertically adjustable 16 inches; with 8 non-folding 1/4-inch stainless-steel arms with loops and a stainless-steel top loop to attach to carrier.
  - 1. Top Loop: Coated for nonconductivity.
  - 2. Adjustment Control: Push button.

## 2.5 PRIVACY CURTAINS (PC-1)

- A. Basis of Design Product: Item PC-1 on Finish Legend in Drawings (Clickeze Inpro Corp.; Clickeze® EZE™ Swap™ Cubicle Curtain Snap Panel System).
- B. Curtain Fabric: Non-woven, 100 percent polyester fabric, modified with nano-molecular, antibacterial and water repellent technologies. Provide fabric that is anti-bacterial, and stain-resistant.
  - 1. Basis of Design: Inpro Corp.; Shield Fabric.
    - a. Type: Shield Classic, or equal.



- b. Color and Pattern: Aloft; Mocha.
- C. Mesh Top: Open-weave, No. 50 nylon mesh, with 1/2-inch holes. Provide mesh that is flame-resistant, washable, and dry-cleanable. Provide mesh continuous across all panels.
  - 1. Basis of Design: Clickeze Inpro Corp.; Eze-Mesh.
    - a. Color: Snow.
- D. Mesh Curtain Grommets: Two-piece, rolled-edge, rustproof, nickel-plated brass; spaced not more than 6 inches o.c.; machined into top hem header of mesh.
- E. Curtain Snaps:
  - 1. Bottom Mesh Footer: Rustproof, nickel-plated brass snaps with off -white plastic cover, spaced 4.6 inches on center and machined into bottom mesh footer.
  - 2. Top Curtain Header: Rustproof, nickel-plated brass, double-sided snaps spaced 4.6 inches on center and machined into top curtain header.
- F. Curtain Tieback: Nickel-plated brass chain; one at each curtain termination.
- G. Provide curtains with specified Radio Frequency Identification (RFID) chip sewn into bottom left of hem.

## 2.6 RADIO FREQUENCY IDENTIFICATION (RFID) CHIPS

- A. RFID: Provide curtains with Radio Frequency Identification (RFID) chip sewn into bottom left of hem in all curtains. Use RFID chips and software as approved by owner's Environmental Services (EVS) provider and install as per their recommendations.
  - 1. Approved Product: Invengo; LINTRAK® C15 UHF Tag.
  - 2. Minimum Characteristics:
    - a. Frequency: 860 to 960 MHz.
    - b. Dimensions: 0.82 inches thick by 2.63 inches wide by 0.59 inches high.
    - c. Performance: 20 feet.\Operating Protocol: EPC global UHF Class 21 Gen 2, ISO 18000-63.
    - d. IC: Impinj Monza 5.
    - e. EPC Memory: Standard 96 bits, up to 128 bits.
    - f. Data Retention: 50 years min.
    - g. UHF Module: Epoxy encapsulated chip.
    - h. Antenna: Multi-threads, woven, stainless steel.
    - i. Maximum temperature: 428 deg, F for 30 sec.
    - j. Exposure: 2.5 bars.
    - k. Warranty: 200 cycles for 3 years.
    - l. Applied Tag Performance Certification: European EPC Competence Center.

## 2.7 CURTAIN FABRICATION

### A. Fabricate curtains to comply with the following requirements:

1. Horizontal Width: Provide finished panel width equal to 66 inches.
  - a. Curtain Hems: Manufacture curtain panel with 1-1/4-inch double turned hems on all 4 sides. Along top horizontal width and side connecting to vertical panels, machine double-sided snaps into fabric and set at 4.6 inches on center. Width tolerance plus or minus 3 inches.
2. Vertical Length: Finished fabric panel vertical length of 66 inches.
3. Mesh Top: Continuous across all panels. Mesh height and width varies to accommodate specific application.
  - a. Mesh Top Hem: not less than 1 inch and not more than 1-1/2 inches wide, triple thickness, reinforced with integral web, and double lock stitched. Include 4-ounce nickel-plated grommets, 6 inches on center for carriers.
    - 1) Provide mesh top that is of a standard size based on application. See Drawings for standard sizing guidelines. Do not provide custom sizes.
  - b. Mesh Bottom Hem: Single-turned and reinforced with webbed tape stitched with double needle lock stitch no less than 1-1/4 inches in width.
  - c. Mesh Side Hems: Double turned and stitched with double needle lock stitch no less than 1-1/4 inches in width.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- #### A. Examine areas and conditions in which the cubicle tracking systems will be installed.
1. Verify that required backing and support for tracks are properly installed.
  2. Complete all finishing operations, including painting, before beginning installation of shield fabric products.

### 3.2 PREPARATION

- #### A. Prior to installation, clean substrate to remove dust, debris and loose particles.

### 3.3 INSTALLATION

- #### A. General: Install tracks level and plumb, according to manufacturer's written instructions. Provide track fabricated from one continuous length up to 16 feet.
1. Curtain Track Mounting: Surface.

2. IV Track Mounting: Surface.

- B. Surface Track Mounting: Fasten surface-mounted tracks at intervals of not less than 24 inches. Fasten support at each splice and tangent point of each corner. Center fasteners in track to ensure unencumbered carrier operation. Attach track to ceiling as follows:
  - 1. Mechanically fasten directly to bottom of concrete deck with anchor screws.
  - 2. Mechanically fasten directly to finished ceiling with toggle bolts.
  - 3. Mechanically fasten to suspended ceiling grid with screws.
- C. Track Accessories: Install splices, end caps, connectors, end stops, coupling and joining sleeves, and other accessories as required for a secure and operational installation.
  - 1. Provide one locking switch unit for each pair of beds.
- D. IV Hangers: Unless otherwise indicated, install one IV hook on each IV track and hang one IV hanger.
- E. Curtains: Hang curtains on each curtain track. Secure with curtain tieback.
  - 1. Mesh Top Size: Provide standard size based on application. See Drawings for standard sizing guidelines. Do not provide custom sizes.
  - 2. Fabric Curtain Size: 66 inches by 66 inches.

3.4 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain safety loading units.
  - 1. Train Owner's maintenance personnel on procedures and schedules for changing curtains and maintaining cubicles.
  - 2. Schedule training with Owner with at least seven days' advance notice.

3.5 PROTECTION

- A. Protect installed recessed track openings with nonresidue adhesive tape to prevent debris from ceiling finishing operations from impeding carrier operation.

3.6 CLEANING

- A. At completion of the installation, remove any debris and clean surfaces in accordance with the fabric Manufacturer's clean-up and maintenance instructions.

END OF SECTION 10 2123

## SECTION 10 2239 - FOLDING PANEL PARTITIONS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. **Electrically** operated, acoustical panel partitions.

- B. Related Requirements:

- 1. Section 05 5000 "Metal Fabrications" for supports that attach supporting tracks to overhead structural system.
  - 2. Section 09 7200 "Wall Coverings" for vinyl wall coverings installed on folding panel partitions.
  - 3. **Electrical Sections for electrical service and connections for motor operators, controls, and limit switches and for system disconnect switches.**

#### 1.3 DEFINITIONS

- A. STC: Sound Transmission Class.

#### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product.

- B. Sustainable Design Submittals:

- 1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

- C. Shop Drawings: For operable panel partitions.

1. Include plans, elevations, sections, details, ~~numbered panel installation sequence~~, and attachments to other work.
  2. Indicate stacking and operating clearances. Indicate location and installation requirements for hardware and track, blocking, and direction of travel.
- D. Samples for Initial Selection: For each type of exposed material, finish, covering, or facing.
1. Include Samples of accessories involving color selection.
- E. Samples for Verification: For each type of exposed material, finish, covering, or facing, prepared on Samples of size indicated below:
1. Panel Edge Material: Not less than 3 inches long.
  2. Hardware: One of each exposed door-operating device.
- F. Delegated-Design Submittal: For operable panel partitions.
1. Include design calculations for seismic restraints that brace tracks to structure above.

#### 1.6 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
1. Partition track, track supports and bracing, switches, turning space, and storage layout.
  2. Suspended ceiling components.
  3. Structural members to which suspension systems are attached.
  4. Size and location of initial access modules for acoustical tile.
  5. Items penetrating finished ceiling, including the following:
    - a. Lighting fixtures.
    - b. HVAC ductwork, outlets, and inlets.
    - c. Speakers.
    - d. Sprinklers.
    - e. Smoke detectors.
    - f. Access panels.
- B. Setting Drawings: For embedded items and cutouts required in other work, including support-beam, mounting-hole template.
- C. Qualification Data: For Installer.
- D. Seismic Qualification Certificates: For operable panel partitions, tracks, accessories, and components, from manufacturer. Include seismic capacity of partition assemblies to remain in vertical position during a seismic event and the following:
1. Basis for Certification: Indicate whether certification is based on analysis, testing, or experience data, according to ASCE/SEI 7.

2. Detailed description of partition anchorage devices on which the certification is based and their installation requirements.

- E. Product Certificates: For each type of operable panel partition.
- F. Product Test Reports: For each operable panel partition, for tests performed by a qualified testing agency.
- G. Field quality-control reports.
- H. Sample Warranty: For manufacturer's special warranty.

#### 1.7 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For operable panel partitions to include in maintenance manuals.
  1. In addition to items specified in Section 01 7823 "Operation and Maintenance Data," include the following:
    - a. Panel finish facings and finishes for exposed trim and accessories. Include precautions for cleaning materials and methods that could be detrimental to finishes and performance.
    - b. Seals, hardware, track, track switches, carriers, and other operating components.
    - c. **Electric operator and controls.**

#### 1.8 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials, from the same production run, that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  1. Panel Finish-Facing Material: Furnish full width in quantity to cover both sides of two panels when installed.

#### 1.9 QUALITY ASSURANCE

- A. Installer Qualifications: An entity that employs installers and supervisors who are trained and approved by manufacturer.

#### 1.10 DELIVERY, STORAGE, AND HANDLING

- A. Protectively package and sequence panels in order for installation. Clearly mark packages and panels with numbering system used on Shop Drawings. Do not use permanent markings on panels.

## 1.11 WARRANTY

- A. Special Warranty: Manufacturer agrees to repair or replace components of operable panel partitions that fail in materials or workmanship within specified warranty period.
  - 1. Failures include, but are not limited to, the following:
    - a. Faulty operation of operable panel partitions.
    - b. Deterioration of metals, metal finishes, and other materials beyond normal use.
  - 2. Warranty Period: Two years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Delegated Design: Engage a qualified professional engineer, as defined in Section 01 4000 "Quality Requirements," to design seismic bracing of tracks to structure above.
- B. Seismic Performance: Operable panel partitions shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
  - 1. The term "withstand" means "the partition panels will remain in place without separation of any parts from the system when subjected to the seismic forces specified."
- C. Acoustical Performance: Provide operable panel partitions tested by a qualified testing agency for the following acoustical properties according to test methods indicated:
  - 1. Sound-Transmission Requirements: Operable panel partition assembly tested for laboratory sound-transmission loss performance according to ASTM E 90, determined by ASTM E 413, and rated for not less than the STC indicated.
- D. Fire-Test-Response Characteristics: Provide panels with finishes complying with one of the following as determined by testing identical products by UL or another testing and inspecting agency acceptable to authorities having jurisdiction:
  - 1. Surface-Burning Characteristics: Comply with ASTM E 84 or UL 723; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
    - a. Flame-Spread Index: 25 or less.
    - b. Smoke-Developed Index: 450 or less.
  - 2. Fire Growth Contribution: Complying with acceptance criteria of local code and authorities having jurisdiction when tested according to NFPA 265 Method B Protocol or NFPA 286.

- E. **Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.**

## 2.2 OPERABLE ACOUSTICAL PANELS

- A. Operable Acoustical Panels: Partition system, including panels, seals, finish facing, suspension system, operators, and accessories.
1. **Basis-of-Design Product:** Subject to compliance with requirements, provide the following product or an equivalent product, approved prior to bid, by another manufacturer:
    - a. **Modernfold, Inc.;** Acousti-Seal Encore **Automated - #20 Track System.**
- B. Panel Operation: **Electrically operated, continuously hinged** panels.
- C. Panel Construction: As required to support panel from suspension components and with reinforcement for hardware attachment. Fabricate panels with tight hairline joints and concealed fasteners. Fabricate panels so finished in-place partition is rigid; level; plumb; aligned, with tight joints and uniform appearance; and free of bow, warp, twist, deformation, and surface and finish irregularities.
- D. Dimensions: Fabricate operable acoustical panel partitions to form an assembled system of dimensions indicated and verified by field measurements.
1. Panel Width: Equal widths.
- E. STC: Not less than 52.
- F. Panel Weight: 8.2 lb/sq. ft. maximum.
- G. Panel Thickness: Not less than 4-1/4 inches.
- H. Panel Materials:
1. **Recycled Content:** Postconsumer recycled content plus one-half of preconsumer recycled content not less than 25 percent.
  2. **Adhesives:** Use adhesives that meet the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
  3. Steel Frame: Steel sheet, manufacturer's standard nominal minimum thickness for uncoated steel.
  4. Steel Face/Liner Sheets: Tension-leveled steel sheet, 16-gage minimum nominal thickness for uncoated steel.
- I. Panel Closure: Horizontally expanding panel edge with removable crank.
- J. Hardware: Manufacturer's standard as required to operate operable panel partition and accessories; with decorative, protective finish.



1. Hinges: Concealed (invisible).
  - a. SOSS® Invisible laminated hinge with antifriction segments mounted between each heat treated link. Hinge to be attached directly to panel frame. Welded internal hinge bracket shall support the hinge and allow for adjustment of hinge plates. Concealed hinges mounted into panel edge or vertical astragal are not acceptable.

K. Finish Facing:

1. **Lower 36 inches: Vinyl wallcovering specified in Section 09 7200 "Wall Coverings"**
2. **Above 36 inches: Write/erase wall covering.**

2.3 SEALS

- A. General: Provide seals that produce operable panel partitions complying with performance requirements and the following:
  1. Manufacturer's standard seals unless otherwise indicated.
  2. Seals fitting tight at contact surfaces and sealing continuously between adjacent panels and between operable panel partition perimeter and adjacent surfaces, when operable panel partition is extended and closed.
- B. Vertical Seals: Deep-nesting, interlocking metal astragals mounted on each edge of panel, with continuous PVC acoustical seal.
- C. Horizontal Top and Bottom Seal System:
  1. Basis of Design: Modernfold Sureset™ top and bottom seal system.

2.4 PANEL FINISH FACINGS

- A. Description: Finish facings for panels that comply with indicated fire-test-response characteristics and that are factory applied to operable panel partitions with appropriate backing, using mildew-resistant nonstaining adhesive as recommended by facing manufacturer's written instructions.
  1. Apply one-piece, seamless facings free of air bubbles, wrinkles, blisters, and other defects, with invisible seams complying with Shop Drawings for location, and with no gaps or overlaps. Horizontal seams are not permitted. Tightly secure and conceal raw and selvage edges of facing for finished appearance.
  2. Match facing pattern 72 inches above finished floor.
- B. Vinyl Wall Covering: As specified in Section 09 7200 "Wall Coverings"
  1. Apply up to 36 inches above finished floor.

- C. Cap-Trimmed Edges: Protective perimeter-edge trim with tight hairline joints concealing edges of panel and finish facing, finished as follows:
  - 1. Steel, Painted: ~~Finished with manufacturer's color as selected by Architect from manufacturer's full range.~~ Provide in consistent color:
    - a. Color: Smoke Gray.

## 2.5 ELECTRIC OPERATORS

- A. Factory-assembled electric operation system of size and capacity recommended and provided by operable panel partition manufacturer for partition specified; with electric motor and factory-prewired motor controls, speed reducer, chain drive, control stations, control devices, and accessories required for operation. Include wiring from control stations to motor. Coordinate operator wiring requirements and electrical characteristics with building electrical system.
- B. Comply with NFPA 70.
- C. Control Equipment: Comply with NEMA ICS 1, NEMA ICS 2, and NEMA ICS 6.
- D. Motor Electrical Characteristics:
  - 1. Horsepower: Manufacturer's standard.
  - 2. Volts: 480.
  - 3. Phase: Three phase.
  - 4. Hertz: 60.
- E. Control Stations: Two single-key-operated, constant-pressure control stations located remotely from each other on opposite sides and opposite ends of partition run. Wire in series to require simultaneous activation of both key stations to operate partition. Each three-position control station labeled "Open," "Close," and " Stop." Furnish two keys per station.
- F. Obstruction-Detection Devices: Equip each motorized operable panel partition with indicated automatic safety sensor that causes operator to immediately stop and reverse direction.
  - 1. Sensor Edge: Contact-pressure-sensitive safety edge along partition's leading edge.
- G. Limit Switches: Adjustable switches, interlocked with motor controls and set to automatically stop operable panel partition at fully extended and fully stacked positions.
- H. Emergency Release Mechanism: Quick disconnect-release of electric-motor drive system, permitting manual operation in event of operating failure.
- I. Electric Interlock: Equip each motorized operable panel partition with electric interlocks at locations indicated, to prevent operation of operable panel partition under the following conditions:

1. **On storage pocket door, to prevent operation if door is not in fully open position.**

## 2.6 SUSPENSION SYSTEMS

- A. Tracks: Steel or aluminum mounted directly to overhead structural support, designed for operation, size, and weight of operable panel partition indicated. Size track to support partition operation and storage without damage to suspension system, operable panel partitions, or adjacent construction. Limit track deflection to no more than 0.10 inch between bracket supports. Provide a continuous system of track sections and accessories to accommodate configuration and layout indicated for partition operation and storage.
  1. Panel Guide: Aluminum guide on both sides of the track to facilitate straightening of the panels; finished with factory-applied, decorative, protective finish.
  2. Head Closure Trim: As required for acoustical performance; with factory-applied, decorative, protective finish.
- B. Carriers: Trolley system as required for configuration type, size, and weight of partition and for easy operation; with ball-bearing wheels.
- C. Steel Finish: Manufacturer's standard, factory-applied, corrosion-resistant, protective coating unless otherwise indicated.

## 2.7 ACCESSORIES

- A. **Storage Pocket Door: Where pocket door is indicated, full height at end of partition runs to conceal stacked partition; of same materials, finish, construction, thickness, and acoustical qualities as panels; complete with operating hardware and acoustical seals at soffit, floor, and jambs. Hinges in finish to match other exposed hardware.**
  1. **Manufacturer's standard method to secure storage pocket door in closed position.**
  2. **Rim Lock: Key-operated lock cylinder, keyed to master key system, to secure storage pocket door in closed position. Include two keys per lock.**
- B. Work Surfaces: Quantities, placement, and size indicated.
  1. Surface: Porcelain steel marker/projection surface.
  2. Surface Color: As selected by Architect from manufacturer's full range.
  3. Size: **Full width of panel from 36 inches above finished floor to top of panel.**
  4. Trim: Aluminum slip-on or snap-on trim with no visible screws or exposed joints and with corners mitered to a neat, hairline joint.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine flooring, structural support, and opening, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of operable panel partitions.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install operable panel partitions and accessories after other finishing operations, including painting, have been completed in area of partition installation.
- B. Install panels from marked packages in numbered sequence indicated on Shop Drawings.
- C. Broken, cracked, chipped, deformed, or unmatched panels are not acceptable.
- D. Broken, cracked, deformed, or unmatched gasketing or gasketing with gaps at butted ends is not acceptable.
- E. Light-Leakage Test: Illuminate one side of partition installation and observe vertical joints and top and bottom seals for voids. Adjust partitions for alignment and full closure of vertical joints and full closure along top and bottom seals.

### 3.3 ADJUSTING

- A. Adjust operable panel partitions, hardware, and other moving parts to function smoothly, and lubricate as recommended by manufacturer.
- B. Adjust storage pocket doors to operate smoothly and easily, without binding or warping.**
- C. Verify that safety devices are properly functioning.

### 3.4 MAINTENANCE SERVICE

- A. Maintenance Service: Beginning at Substantial Completion, maintenance service shall include 12 months' full maintenance by manufacturer's authorized service representative. Include quarterly preventive maintenance, repair or replacement of worn or defective components, lubrication, cleaning, and adjusting as required for proper operable-partition operation. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.

**3.5 DEMONSTRATION**

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain operable panel partitions.**

END OF SECTION 10 2239

## SECTION 10 2600 - WALL AND DOOR PROTECTION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Wall guards.
  - 2. Corner guards.
  - 3. Abuse-resistant wall coverings.
  - 4. High-traffic protective wall coverings.
- B. Related Sections:
  - 1. Section 08 7100 "Door Hardware" for metal armor, kick, mop, and push plates.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, impact strength, dimensions of individual components and profiles, and finishes.
- B. Sustainable Design Submittals:
  - 1. Product Data: For adhesives, indicating VOC content.
  - 2. Laboratory Test Reports: For adhesives, indicating compliance with requirements for low-emitting materials.
- C. Shop Drawings: For each type of wall and door protection showing locations and extent.
  - 1. Include plans, elevations, sections, and attachment details. Show handrail design and support spacing required to withstand structural loads.
- D. Samples for Verification: For each type of exposed finish on the following products, prepared on Samples of size indicated below:
  - 1. Wall Guards: 12 inches long. Include examples of joinery, corners, and field splices.
  - 2. Corner Guards: 12 inches long. Include example top caps.
  - 3. Abuse-Resistant Wall Covering: 6 by 6 inches square.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Material Certificates: For each impact-resistant plastic material, from manufacturer.
- B. Material Test Reports: For each impact-resistant plastic material.
- C. Warranty: Sample of special warranty.

#### 1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For each impact-resistant wall protection unit to include in maintenance manuals.
  - 1. Include recommended methods and frequency of maintenance for maintaining optimum condition of plastic covers under anticipated traffic and use conditions. Include precautions against using cleaning materials and methods that may be detrimental to plastic finishes and performance.

#### 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: An employer of workers trained and approved by manufacturer.
- B. Source Limitations: Obtain impact-resistant wall protection units from single source from single manufacturer.
- C. Product Options: Drawings indicate size, profiles, and dimensional requirements of impact-resistant wall protection units and are based on the specific system indicated. Refer to Section 01 4000 "Quality Requirements."
- D. Surface-Burning Characteristics: Provide impact-resistant, plastic wall protection units with surface-burning characteristics as determined by testing identical products per ASTM E 84, NFPA 255, or UL 723 by UL or another qualified testing agency.
- E. Preinstallation Conference: Conduct conference at Project site.

#### 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Store impact-resistant wall protection units in original undamaged packages and containers inside well-ventilated area protected from weather, moisture, soiling, extreme temperatures, and humidity.
  - 1. Maintain room temperature within storage area at not less than 70 deg F during the period plastic materials are stored.
  - 2. Keep plastic sheet material out of direct sunlight.
  - 3. Store plastic wall protection components for a minimum of 72 hours, or until plastic material attains a minimum room temperature of 70 deg F.
    - a. Store corner-guard covers in a vertical position.

- b. Store wall-guard and bumper rails in a horizontal position.

## 1.8 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of impact-resistant wall protection units that fail in materials or workmanship within specified warranty period.
  1. Failures include, but are not limited to, the following:
    - a. Structural failures.
    - b. Deterioration of plastic and other materials beyond normal use.
  2. Warranty Period: Five years from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Source Limitations: Obtain wall- and door-protection products of each type from single source from single manufacturer.

### 2.2 PERFORMANCE REQUIREMENTS

- A. Surface Burning Characteristics: Comply with ASTM E 84 or UL 723; testing by a qualified testing agency. Identify products with appropriate markings of applicable testing agency.
  1. Flame-Spread Index: 25 or less.
  2. Smoke-Developed Index: 450 or less.
- B. Regulatory Requirements: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines for Buildings and Facilities and ICC A117.1.

### 2.3 WALL GUARDS

- A. Crash Rail: Heavy-duty assembly consisting of continuous snap-on plastic cover installed over concealed retainer; designed to withstand impacts.
  1. Product: Koroseal Interior Products; Korogard C600.
  2. Cover: Extruded rigid plastic, minimum 0.100-inch wall thickness; as follows:
    - a. Profile: Convex.
      - 1) Dimensions: Nominal 6 inches high by 1-1/16 inch deep.
      - 2) Surface: Uniform.



- b. Color and Texture: As selected by Architect from manufacturer's full range.
  - 3. Continuous Retainer: Minimum 0.080-inch-thick, one-piece, extruded aluminum.
  - 4. Bumper: Continuous, resilient bumper cushion(s).
  - 5. End Caps and Corners: Prefabricated, injection-molded plastic; matching color cover; field adjustable for close alignment with snap-on cover.
  - 6. Accessories: Concealed splices and mounting hardware.
  - 7. Mounting: Surface mounted directly to wall.
- B. Bumper Rail (Rub Rail): Standard-duty assembly consisting of continuous snap-on plastic cover installed over concealed retainer; designed to withstand impacts.
- 1. Product: Koroseal Interior Products; Korogard B200.
  - 2. Cover: Extruded rigid plastic, minimum 0.078-inch wall thickness; as follows:
    - a. Profile: Half-round profile, nominal 1-1/2 inches high by 7/8 inch deep.
    - b. Color and Texture: As selected by Architect from manufacturer's full range.
  - 3. Continuous Retainer: Minimum 0.080-inch-thick, one-piece, extruded aluminum.
  - 4. Bumper: Continuous, resilient bumper cushion(s).
  - 5. End Caps and Corners: Prefabricated, injection-molded plastic; matching color cover; field adjustable for close alignment with snap-on cover.
  - 6. Accessories: Concealed splices and mounting hardware.
  - 7. Mounting: Surface mounted directly to wall.

## 2.4 CORNER GUARDS

- A. Surface-Mounted, Adhered, Plastic-Cover Corner Guards: Manufacturer's standard assembly.
- 1. Product: Item CG-1 as indicated on Finish Legend in Drawings (Koroseal Interior Products; Korogard F620).
  - 2. Cover: Extruded rigid plastic, minimum 0.06-inch wall thickness; as follows:
    - a. Profile: Nominal 1-1/2-inch-long leg and 1/4-inch corner radius.
    - b. Height: As indicated in Drawings.
    - c. Color and Texture: As selected by Architect from manufacturer's full range.

## 2.5 ABUSE-RESISTANT WALL COVERINGS

- A. Protective Sheet Wall Covering: Fabricated from semirigid, plastic sheet wall-covering material.
- 1. Product: Item WP-1 indicated on Finish Legend in the Drawings (Koroseal Interior Products; Korogard Protective Wallcovering).
  - 2. Size: As indicated.
  - 3. Sheet Thickness: 0.060 inch.
  - 4. Color and Texture: As indicated on Finish Legend in Drawings.
  - 5. Height: As indicated.

6. Joints: Butt Joints or 1/16-inch caulked joints to be taped at application of caulk; Caulk color to match manufacturer color of sheet wall covering.
7. Mounting: Adhesive.

## 2.6 HIGH-TRAFFIC PROTECTIVE WALLCOVERINGS

- A. Semi-Rigid Laminated Sheet Wallcovering: Semi-rigid, embossed, impact-resistant, capped vinyl-plastic sheets. Comply with Class I/A fire performance characteristics and be chemical- and stain-resistant.
  1. Product: Koroseal Interior Products; Traffic Patterns Decorative Wall Protection Wallcovering, Traffic Patterns® Series: Polyvinyl fluoride film-capped.
    - a. Sheet Thickness: 0.060 0.030 inch thick.
    - b. Height: As indicated in Drawings.
    - c. Pattern and Color: As selected by Architect.
    - d. Adhesive and Primer: As recommended by manufacturer.
    - e. Joints: 1/16-inch caulked joints to be taped at application of caulk; Caulk to be Sikaflex color Stone or approved equal.

## 2.7 MATERIALS

- A. Plastic Materials: Chemical- and stain-resistant, high-impact-resistant plastic with integral color throughout; extruded and sheet material as required, thickness as indicated.
- B. Stainless-Steel Sheet: ASTM A 240/A 240M or ASTM A 666, Type 304, stretcher-leveled standard of flatness.
- C. Fasteners: Aluminum, nonmagnetic stainless-steel, or other noncorrosive metal screws, bolts, and other fasteners compatible with items being fastened. Use security-type fasteners where exposed to view.
- D. Adhesive: As recommended by protection product manufacturer.
  1. Adhesives shall have a VOC content of 70 g/L or less.
  2. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

## 2.8 FABRICATION

- A. Fabricate impact-resistant wall protection units to comply with requirements indicated for design, dimensions, and member sizes, including thicknesses of components.
- B. Factory Assembly: Assemble components in factory to greatest extent possible to minimize field assembly. Disassemble only as necessary for shipping and handling.

- C. Quality: Fabricate components with uniformly tight seams and joints and with exposed edges rolled. Provide surfaces free of wrinkles, chips, dents, uneven coloration, and other imperfections. Fabricate members and fittings to produce flush, smooth, and rigid hairline joints.

## 2.9 FINISHES

- A. Protect finishes on exposed surfaces from damage by applying a strippable, temporary protective covering before shipping.
- B. Appearance of Finished Work: Noticeable variations in same piece are not acceptable. Variations in appearance of adjoining components are acceptable if they are within the range of approved Samples and are assembled or installed to minimize contrast.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and wall areas, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine walls to which wall and door protection will be attached for blocking, grounds, and other solid backing that have been installed in the locations required for secure attachment of support fasteners.
  - 1. For wall and door protection attached with adhesive, verify compatibility with and suitability of substrates, including compatibility with existing finishes or primers.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Complete finishing operations, including painting, before installing impact-resistant wall protection system components.
- B. Before installation, clean substrate to remove dust, debris, and loose particles.

### 3.3 INSTALLATION

- A. Installation Quality: Install wall and door protection according to manufacturer's written instructions, level, plumb, and true to line without distortions. Do not use materials with chips, cracks, voids, stains, or other defects that might be visible in the finished Work.
- B. Mounting Heights: Install wall and door protection in locations and at mounting heights indicated on Drawings.

- C. Accessories: Provide splices, mounting hardware, anchors, trim, joint moldings, and other accessories required for a complete installation.
  - 1. Provide anchoring devices and suitable locations to withstand imposed loads.
  - 2. Where splices occur in horizontal runs of more than 20 feet, splice aluminum retainers and plastic covers at different locations along the run, but no closer than 12 inches apart.
  - 3. Adjust end and top caps as required to ensure tight seams.
- D. Abuse-Resistant Wall Covering: Install top and edge moldings, corners, and divider bars as required for a complete installation.
- E. Tape off all caulk lines. Caulk sheet to sheet at corners. Provide caulked seams at vertical transitions as noted above in the product section.

### 3.4 CLEANING

- A. Immediately after completion of installation, clean plastic covers and accessories using a standard, ammonia-based, household cleaning agent.
- B. Remove excess adhesive using methods and materials recommended in writing by manufacturer.
- C. Unless otherwise indicated, clean metals by washing thoroughly with water and soap, rinsing with clean water, and drying with soft cloths.
- D. Restore finishes damaged during installation and construction period so no evidence remains of correction work. Return items that cannot be refinished in the field to the shop; make required alterations and refinish entire unit or provide new units.

END OF SECTION 10 2600

## SECTION 10 2800 – TOILET AND BATH ACCESSORIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Public-use washroom accessories.
  - 2. Underlavatory guards.
- B. Owner-Furnished Items: Provide blocking, rough framing, nailers, and other items as required to support toilet and bath accessories, including for Owner-furnished and Owner-installed items.
  - 1. GelSan Dispensers.
  - 2. Hand Towel Dispensers.
  - 3. Soap Dispensers.
  - 4. Waste receptacles.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include the following:
  - 1. Construction details and dimensions.
  - 2. Anchoring and mounting requirements, including requirements for cutouts in other work and substrate preparation.
  - 3. Material and finish descriptions.
  - 4. Features that will be included for Project.
  - 5. Manufacturer's warranty.
- B. Samples: Full size, for each accessory item to verify design, operation, and finish requirements.
  - 1. Approved full-size Samples will be returned and may be used in the Work.
- C. Product Schedule: Indicating types, quantities, sizes, and installation locations by room of each accessory required.
  - 1. Identify locations using room designations indicated.

1.4 INFORMATIONAL SUBMITTALS

- A. Warranty: Sample of special warranty.

1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For toilet and bath accessories to include in maintenance manuals.

1.6 QUALITY ASSURANCE

- A. Source Limitations: For products listed together in the same Part 2 articles, obtain products from single source from single manufacturer.
- B. Inserts and Anchorages: Furnish inserts and anchoring devices which must be set in concrete or built into masonry; coordinate design of wall construction with Owner-supplied items.

1.7 COORDINATION

- A. Coordinate accessory locations with other work to prevent interference with clearances required for access by people with disabilities, and for proper installation, adjustment, operation, cleaning, and servicing of accessories.
- B. Deliver inserts and anchoring devices set into concrete or masonry as required to prevent delaying the Work.

1.8 WARRANTY

- A. Special Mirror Warranty: Manufacturer's standard form in which manufacturer agrees to replace mirrors that develop visible silver spoilage defects and that fail in materials or workmanship within specified warranty period.
  - 1. Warranty Period: 15 years from date of Substantial Completion.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Stainless Steel: ASTM A 666, Type 304, 0.031-inch minimum nominal thickness unless otherwise indicated.
- B. Fasteners: Screws, bolts, and other devices of same material as accessory unit and tamper-and-theft resistant where exposed, and of galvanized steel where concealed.
- C. Mirrors: ASTM C 1503, Mirror Glazing Quality, clear-glass mirrors, nominal 6.0 mm thick.

## 2.2 PUBLIC-USE WASHROOM ACCESSORIES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. American Specialties, Inc.
  - 2. Bobrick Washroom Equipment, Inc.
  - 3. Bradley Corporation.
  - 4. GAMCO Specialty Accessories; a division of Bobrick.
- B. Mirror Unit:
  - 1. Frame: Stainless-steel channel.
    - a. Corners: Welded and ground smooth.
  - 2. Hangers: Produce rigid, tamper- and theft-resistant installation, using method indicated below.
    - a. One-piece, galvanized steel, wall-hanger device with spring-action locking mechanism to hold mirror unit in position with no exposed screws or bolts.
  - 3. Size: 24 inches wide by 36 inches high.

## 2.3 UNDERLAVATORY GUARDS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Plumberex Specialty Products, Inc.
  - 2. Truebro by IPS Corporation.
- B. Underlavatory Guard:
  - 1. Description: Insulating pipe covering for supply and drain piping assemblies that prevent direct contact with and burns from piping; allow service access without removing coverings.
  - 2. Material and Finish: Antimicrobial, molded plastic, white.

## 2.4 FABRICATION

- A. General: Fabricate units with tight seams and joints, and exposed edges rolled. Hang doors and access panels with full-length, continuous hinges. Equip units for concealed anchorage and with corrosion-resistant backing plates.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install accessories according to manufacturers' written instructions, using fasteners appropriate to substrate indicated and recommended by unit manufacturer. Install units level, plumb, and firmly anchored in locations and at heights indicated.
- B. Stud Walls: Provide stud walls with a 20-gauge minimum thickness strap on solid blocking at accessory locations for mounting.
- C. Grab Bars: Install to withstand a downward load of at least 250 lbf, when tested according to ASTM F 446.

#### 3.2 ADJUSTING AND CLEANING

- A. Adjust accessories for unencumbered, smooth operation. Replace damaged or defective items.
- B. Remove temporary labels and protective coatings.
- C. Clean and polish exposed surfaces according to manufacturer's written recommendations.

END OF SECTION 10 2800



## SECTION 10 4413 - FIRE PROTECTION CABINETS

### 1.1 PRODUCTS

#### A. Fire-Protection Cabinets:

1. Type: Fire extinguisher.
2. Cabinet Construction: Nonrated.
3. Mounting: Semirecessed.
4. Door Style: Fully glazed panel with frame.
5. Door Glazing: Tempered float glass (clear).
6. Finish:
  - a. Steel: Baked enamel or powder coat.

END OF SECTION 10 4413

SECTION 10 4416 - FIRE EXTINGUISHERS

1.1 WARRANTY

- A. Materials and Workmanship: Six years.

1.2 PERFORMANCE REQUIREMENTS

- A. Fire Extinguishers: Complying with NFPA 10.

1.3 PRODUCTS

- A. Portable Hand-Carried Fire Extinguishers:
  - 1. Multipurpose dry-chemical type.
- B. Mounting brackets.

END OF SECTION 10 4416

## SECTION 10 5123 - PLASTIC-LAMINATE-CLAD LOCKERS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Plastic-laminate-clad lockers and benches.
  - 2. Wood furring, blocking, shims, and hanging strips for installing plastic-laminate-faced lockers and locker benches that are not concealed within other construction.
- B. Related Requirements:
  - 1. Section 06 1053 "Miscellaneous Rough Carpentry" for wood furring, blocking, and shims required for installing lockers and concealed within other construction before locker installation.

#### 1.3 COORDINATION

- A. Coordinate sizes and locations of framing, blocking, furring, reinforcements, and other related units of Work specified in other Sections to support loads imposed by installed and fully loaded lockers.

#### 1.4 PREINSTALLATION MEETINGS

- A. Preinstallation Conference: Conduct conference at Project site.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each type of plastic-laminate-clad locker.
- B. Sustainable Design Submittals:
  - 1. Product Data: For recycled content, indicating postconsumer and preconsumer recycled content and cost.

2. Product Certificates: For materials manufactured within 100 miles (160 km) of Project, indicating location of material manufacturer and point of extraction, harvest, or recovery for each raw material. Include distance to Project and cost for each raw material.
  3. Chain-of-Custody Certificates: For certified wood products. Include statement of costs.
  4. Laboratory Test Reports: For adhesives, indicating compliance with requirements for low-emitting materials.
  5. Laboratory Test Reports: For composite wood products, indicating compliance with requirements for low-emitting materials.
- C. Shop Drawings: For plastic-laminate-clad lockers. Include plans, elevations, sections, details, and attachments to other work.
1. Show locker trim and accessories.
  2. Include locker identification system and numbering sequence.
  3. Show locations and sizes of cutouts and holes for items installed in plastic-laminate architectural cabinets.
  4. Show accessible locker locations.
- D. Samples for Initial Selection:
1. Plastic laminates.
  2. Thermoset decorative panels.
  3. Locker equipment.
- E. Samples for Verification: For the following products:
1. Plastic laminates, 8 by 10 inches, for each type, color, pattern, and surface finish, with one sample applied to core material and specified edge material applied to one edge.
  2. Thermoset decorative panels, 8 by 10 inches, for each color, pattern, and surface finish, with edge banding on one edge.

## 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Product Certificates: For the following:
1. Composite wood products.
  2. Thermoset decorative panels.
  3. High-pressure decorative laminate.

## 1.7 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For adjusting, repairing, and replacing locker doors and latching mechanisms to include in maintenance manuals.

## 1.8 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Full-size units of the following metal locker hardware items equal to 10 percent of amount installed for each type and finish installed, but no fewer than five units:
    - a. Locks.
    - b. Blank identification plates.
    - c. Hooks.

## 1.9 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom fabricate products similar to those required for this Project and whose products have a record of successful in-service performance.
- B. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project.
- C. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
  - 1. Build mockups of typical plastic-laminate-faced locker as shown on Drawings.
  - 2. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

## 1.10 DELIVERY, STORAGE, AND HANDLING

- A. Do not deliver plastic-laminate-clad lockers until spaces to receive them are clean, dry, and ready for their installation.

## 1.11 FIELD CONDITIONS

- A. Field Measurements: Verify actual dimensions of recessed openings by field measurements before fabrication.
- B. Environmental Limitations: Do not deliver or install cabinets until building is enclosed, wet work is complete, and HVAC system is operating and maintaining temperature between 60 and 90 deg F and relative humidity between 25 and 55 percent during the remainder of the construction period.

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Accessibility Requirements: Provide accessible lockers at 5 percent of any plastic-laminate-clad locker bank or area. For accessible lockers, comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines and ICC A117.1.

1. Provide specified digital keypad locks at each accessible locker.

### 2.2 PLASTIC-LAMINATE-CLAD LOCKERS

- A. Grade: Custom.
- B. Dimensions: As indicated in Drawings.
- C. Locker Arrangement: Single tier, double tier, triple tier, and Z-shaped double tier, as indicated.
- D. Body: One-piece, plastic-laminate facing sheets pressure laminated to core material without splices or joints in facings or cores; with laminate applied to edges before faces to seal edges and prevent laminate from being pried loose. Seal exposed core material at cutouts.
1. Core Material: Particleboard.
    - a. Sides: 5/8-inch thickness.
    - b. Shelves: 3/4-inch thickness.
    - c. Backs: 1/4-inch thickness.
  2. Interior Surfaces: Thermoset decorative panels.
- E. Doors: One piece; 3/4-inch- thick industrial grade particle board with plastic-laminate facing sheets pressure laminated to core material without splices or joints in facings or cores; with laminate applied to edges before faces to seal edges and prevent laminate from being pried loose.
- F. Edges: Grade VGS plastic laminate matching exterior plastic laminate.
- G. Frameless Concealed Hinges (European Type): BHMA A156.9, B01602, 123 degrees of opening, self-closing, with manufacturer's lifetime guarantee.
- H. Projecting Door Handle and Latch: Finger-lift latch control designed for use with either built-in combination locks or padlocks; positive automatic latching, chromium plated; pry and vandal resistant.
1. Latch Hooks: Equip doors 48 inches and higher with three latch hooks and doors less than 48 inches high with two latch hooks; fabricated from 0.105-inch nominal-thickness

- steel sheet; welded or riveted to full-height door strikes; with resilient silencer on each latch hook.
- 2. Latching Mechanism: Manufacturer's standard, rattle-free latching mechanism and moving components isolated to prevent metal-to-metal contact, and incorporating a prelocking device that allows locker door to be locked while door is open and then closed without unlocking or damaging lock or latching mechanism.
- I. Clothes Hooks: Manufacturer's standard ceiling-hung double-pronged aluminum clothes hooks.
- J. Locks:
  - 1. Combination padlocks.
  - 2. Digital keypad locks.
- K. Coat Rods: Manufacturer's standard nickel-plated rods.
- L. Identification Plates: Manufacturer's standard, etched, embossed, or stamped satin chrome plates, with numbers and letters at least 3/8 inch high.
- M. Plastic-Laminate Finish: One color and pattern.
  - 1. Color and Pattern: As selected by Architect from manufacturer's full range.

## 2.3 WOOD MATERIALS

- A. Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of lockers and quality grade specified unless otherwise indicated.
  - 1. Wood Moisture Content: 5 to 10 percent.
- B. Composite Wood Products: Provide materials that comply with requirements of referenced quality standard for each type of locker and quality grade specified unless otherwise indicated.
- C. Composite Wood Products: Products shall be made using ultra-low-emitting formaldehyde resins as defined in the California Air Resources Board's "Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products" or shall be made with no added formaldehyde.
  - 1. Particleboard: ANSI A208.1, Grade M-2.

## 2.4 LOCKS

- A. Combination Padlock: Provide hasp for user-provided locks.
- B. Digital Keypad Lock: Where indicated in the drawings and at all accessible lockers, provide battery-powered electronic keypad with reprogrammable manager and owner codes that override access. Three consecutive incorrect code entries shall disable lock for three minutes.

1. Designed for shared or temporary access by multiple users, with user-defined code to lock and unlock. Provide LED indicator to show when lock is in use.
2. Basis of Design Product: DK Series by Digilock. Provide basis of design product or equivalent product with at least the following characteristics:
  - a. Battery operated with low battery indicator light.
  - b. Four digit code.
  - c. Master key override, for supervisory control.
  - d. Shared Use: User set code is reprogrammable when door is unlocked.
  - e. Assigned Use: Administrator set code is reprogrammable by use of key.
  - f. Dead locking bolt.
  - g. Spring bolt latch.
  - h. Finish: Brushed Nickel.

## 2.5 MATERIALS

- A. Plastic Laminate: NEMA LD 3, general-purpose HGS grade, 0.048-inch nominal thickness.
- B. Aluminum Castings: ASTM B 26/B 26M.
- C. Aluminum Extrusions: ASTM B 221.
- D. Adhesives: Use adhesives that meet the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- E. Thermoset Decorative Panels: Particleboard or medium-density fiberboard finished with thermally fused, melamine-impregnated decorative paper and complying with requirements of NEMA LD 3, Grade VGL, for test methods 3.3, 3.4, 3.6, 3.8, and 3.10.

## 2.6 LOCKER BENCHES

- A. Provide bench units with overall assembly height of 17-1/2 inches.
- B. Bench Tops: Manufacturer's standard one-piece units, with rounded corners and edges.
  1. Size: Minimum 9-1/2 inches wide by 1-1/4 inches thick except provide 20- to 24-inch-wide tops where accessible benches are indicated.
  2. Plastic laminate over particleboard core, with two steel tubes running full length of top and positioned to receive pedestal fasteners.
    - a. Color: Match metal lockers.
- C. Materials:
  1. Plastic Laminate: NEMA LD 3, Grade HGP.
  2. Composite Wood Products: Products shall be made using ultra-low-emitting formaldehyde resins as defined in the California Air Resources Board's "Airborne Toxic



Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products" or shall be made with no added formaldehyde.

- a. Particleboard: ANSI A208.1, Grade M-2.

## 2.7 FABRICATION

- A. Fabricate plastic-laminate-clad lockers square, rigid, and without warp and with plastic laminate faces flat and free of dents or distortion. Make exposed edges safe to touch and free of sharp edges and burrs. Provide with finish free from scratches or chips.
- B. Fabricate each plastic-laminate-clad locker with an individual door and frame; individual top, bottom, and back; and common intermediate uprights separating compartments.
- C. Equipment: Provide each locker with an identification plate and the following equipment:
  - 1. Single-Tier Units: Shelf, one double-prong ceiling hook, and two single-prong wall hooks.
  - 2. Double-Tier Units: One double-prong ceiling hook and two single-prong wall hooks.
  - 3. Double-Tier Z-shaped Units: One double-prong ceiling hook and two single-prong wall hooks.
  - 4. Triple-Tier Units: One double-prong ceiling hook.
  - 5. Coat Rods: For each compartment of each locker.
- D. Construction: Fabricate plastic-laminate-clad lockers using manufacturer's standard connections providing solid and secure, anti-racking construction for preassembly at plant prior to shipping.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine walls, floors, and support bases, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. General: Install level, plumb, and true; shim as required, using concealed shims.
  - 1. Install plastic-laminate-clad lockers in accordance with manufacturer's instructions and approved Shop Drawings.
  - 2. Attach lockers to supporting construction with anchors best suited to substrate conditions.
- B. Equipment and Accessories: Fit exposed connections of closures accurately together to form tight, hairline joints, with concealed fasteners and splice plates.

1. Attach hooks with at least two fasteners.
2. Identification Plates: Identify plastic-laminate-clad lockers with identification indicated on Drawings.
  - a. Attach plates to each locker door, near top, centered, with at least two aluminum rivets.

### 3.3 ADJUSTING, CLEANING, AND PROTECTION

- A. Clean, lubricate, and adjust hardware. Adjust doors and latches to operate easily without binding.
- B. Protect plastic-laminate-clad lockers from damage, abuse, dust, dirt, stain, or paint. Do not permit use during construction.
- C. Touch up marred finishes, or replace plastic lockers that cannot be restored to factory-finished appearance. Use only materials and procedures recommended or furnished by locker manufacturer.

END OF SECTION 10 5126

## SECTION 12 2413 - ROLLER WINDOW SHADES

### 1.1 PRODUCTS

- A. Motorized and manual, chain-and-clutch operating mechanism.
- B. Roller Mounting Configuration: Single roller and Double roller, offset with outside roller over and inside roller under.
- C. Installation Accessories: Recessed shade pocket.
- D. Shadeband Materials: Complying with NFPA 701.
  - 1. Light-Filtering Fabric: PVC-coated fiberglass.
  - 2. Light-Blocking Fabric: Fiberglass textile with PVC film bonded to both sides.
- E. Product Safety Standard: WCMA A 100.1.

### 1.2 INSTALLATION

- A. Outside of jamb installation.
- B. Factory-authorized representative to train Owner's personnel to maintain motorized operators.

END OF SECTION 12 2413

## SECTION 12 3661 - SOLID SURFACING COUNTERTOPS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Solid surface material countertops.
  - 2. Solid surface material backsplashes.
  - 3. Solid surface material end splashes.
  - 4. Solid surface material sills and benches.
- B. Related Requirements:
  - 1. Section 22 4100 "Residential Plumbing Fixtures" for plumbing fittings.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For countertop materials.
- B. Shop Drawings: For countertops. Show materials, finishes, edge and backsplash profiles, methods of joining, and cutouts for plumbing fixtures.
  - 1. Show locations and details of joints.
- C. Samples for Verification: For the following products:
  - 1. Countertop material, 6 inches square.
  - 2. One full-size quartz agglomerate countertop, with front edge and backsplash, 8 by 10 inches, of construction and in configuration specified.

#### 1.4 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For solid surface material countertops to include in maintenance manuals. Include Product Data for care products used or recommended by Installer and names, addresses, and telephone numbers of local sources for products.

1.5 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate countertops similar to that required for this Project, and whose products have a record of successful in-service performance.
- B. Installer Qualifications: Fabricator of countertops.

1.6 FIELD CONDITIONS

- A. Field Measurements: Verify dimensions of countertops by field measurements before countertop fabrication is complete.

1.7 COORDINATION

- A. Coordinate locations of utilities that will penetrate countertops or backsplashes.

PART 2 - PRODUCTS

2.1 SOLID-SURFACE-MATERIAL COUNTERTOPS SS-3

- A. Solid Surface Material: Homogeneous-filled plastic resin complying with ICPA SS-1.
  - 1. Basis-of-Design Product: Subject to compliance with requirements, provide item SS-3 indicated on Finish Legend in the Drawings (Corian), or equivalent products approved by Architect prior to bid, by another manufacturer.
  - 2. Integral Sink Bowls: Comply with CSA B45.5/IAPMO Z124.
  - 3. Colors and Patterns: As indicated on Finish Legend in Drawings.
- B. Composite Wood Products: Products shall be made using ultra-low-emitting formaldehyde resins as defined in the California Air Resources Board's "Airborne Toxic Control Measure to Reduce Formaldehyde Emissions from Composite Wood Products" or shall be made with no added formaldehyde. Thickness not less than 3/4 inch.
- C. Plywood: Exterior softwood plywood complying with DOC PS 1, Grade C-C Plugged, touch sanded. Thickness not less than 3/4 inch.

2.2 SOLID-SURFACE-MATERIAL WINDOWSILLS AND BENCHES SS-2

- A. Solid Surface Material: Homogeneous-filled plastic resin complying with ICPA SS-1.
  - 1. Basis-of-Design Product: Subject to compliance with requirements, provide item SS-2 indicated on Finish Legend in the Drawings (Wilsonart), or equivalent products approved by Architect prior to bid, by another manufacturer.

2. Colors and Patterns: As indicated on Finish Legend in Drawings.

B. Front: Straight, slightly eased at top.

C. Sills: 13mm thick, solid surface material.

## 2.3 COUNTERTOP FABRICATION

A. Fabricate countertops according to solid surface material manufacturer's written instructions and to the AWI/AWMAC/WT's "Architectural Woodwork Standards."

1. Grade: Custom.

B. Configuration: Provide countertops with the following front and backsplash style:

1. Front: Straight, slightly eased at top.
2. Backsplash: Straight, slightly eased at corner.
3. End Splash: Matching backsplash.

C. Countertops: 1/2-inch- thick, solid surface material with front edge built up with same material.

D. Backsplashes: 1/2-inch- thick, solid surface material.

E. Fabricate tops with shop-applied edges and backsplashes unless otherwise indicated. Comply with solid surface material manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.

1. Install integral sink bowls in countertops in the shop.

F. Joints: Fabricate countertops without joints.

G. Cutouts and Holes:

1. Undercounter Plumbing Fixtures: Make cutouts for fixtures in shop using template or pattern furnished by fixture manufacturer. Form cutouts to smooth, even curves.
  - a. Provide vertical edges, slightly eased at juncture of cutout edges with top and bottom surfaces of countertop and projecting 3/16 inch into fixture opening.
2. Counter-Mounted Plumbing Fixtures: Prepare countertops in shop for field cutting openings for counter-mounted fixtures. Mark tops for cutouts and drill holes at corners of cutout locations. Make corner holes of largest radius practical.
3. Fittings: Drill countertops in shop for plumbing fittings, undercounter soap dispensers, and similar items.

## 2.4 ACCESSORIES

### A. Waste Counter Opening Ring:

1. Basis-of-Design Product: Bobrick Model 529.
2. Product: 6-inch opening, 5-inch deep ring
3. Material and Finish: Not less than nominal 0.05-inch- thick stainless steel, No. 4 finish (satin).
4. Caulk ring to solid surface

## 2.5 INSTALLATION MATERIALS

### A. Adhesive: Product recommended by solid surface material manufacturer.

1. Adhesives shall have a VOC content of 70 g/L or less.
2. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

### B. Sealant for Countertops: Comply with applicable requirements in Section 07 9200 "Joint Sealants."

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates to receive solid surface material countertops and conditions under which countertops will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of countertops.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install all solid surface over manufacturers recommended backing substrate.
- B. Install countertops level to a tolerance of 1/8 inch in 8 feet.
- C. Fasten countertops by screwing through corner blocks of base units into underside of countertop. Pre-drill holes for screws as recommended by manufacturer. Align adjacent surfaces and, using adhesive in color to match countertop, form seams to comply with manufacturer's written instructions. Carefully dress joints smooth, remove surface scratches, and clean entire surface.

1. Install backsplashes and endsplashes to comply with manufacturer's written instructions for adhesives, sealers, fabrication, and finishing.
- D. Complete cutouts not finished in shop. Mask areas of countertops adjacent to cutouts to prevent damage while cutting. Make cutouts to accurately fit items to be installed, and at right angles to finished surfaces unless beveling is required for clearance. Ease edges slightly to prevent snipping.
  1. Seal edges of cutouts in particleboard subtops by saturating with varnish.
- E. Apply sealant to gaps at walls; comply with Section 07 9200 "Joint Sealants."

END OF SECTION 12 3661



B L A N K   P A G E

## SECTION 12 3662 - QUARTZ AGGLOMERATE WALL TOPS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Quartz agglomerate low wall tops.
- B. Related Requirements:
  - 1. Section 09 3013 "Ceramic Tiling" for quartz agglomerate thresholds.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For wall top materials.
- B. Shop Drawings: For wall tops. Show materials, finishes, profiles, and methods of joining.
  - 1. Show locations and details of joints.
  - 2. Show direction of directional pattern, if any.
- C. Samples for Verification: For the following products:
  - 1. Wall top material, 6 inches square.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For fabricator.

#### 1.5 CLOSEOUT SUBMITTALS

- A. Maintenance Data: For quartz agglomerate wall tops to include in maintenance manuals. Include Product Data for care products used or recommended by Installer and names, addresses, and telephone numbers of local sources for products.

1.6 QUALITY ASSURANCE

- A. Fabricator Qualifications: Shop that employs skilled workers who custom-fabricate wall tops similar to that required for this Project, and whose products have a record of successful in-service performance.
- B. Installer Qualifications: Fabricator of wall tops.

1.7 FIELD CONDITIONS

- A. Field Measurements: Verify dimensions of wall tops by field measurements after low walls are installed but before wall top fabrication is complete.

PART 2 - PRODUCTS

2.1 QUARTZ AGGLOMERATE WALL TOP MATERIALS (QS-1)

- A. Quartz Agglomerate: Solid sheets consisting of quartz aggregates bound together with a matrix of filled plastic resin and complying with ICPA SS-1, except for composition.
  - 1. Basis-of-Design Product: Subject to compliance with requirements, provide items QS-1, indicated on Finish Legend, or equivalent products, approved by Architect prior to bid, by another manufacturer.
  - 2. Colors and Patterns: As indicated on Finish Legend in Drawings.

2.2 WALL TOP FABRICATION

- A. Fabricate wall tops according to quartz agglomerate manufacturer's written instructions and the AWI/AWMAC/WI's "Architectural Woodwork Standards."
  - 1. Grade: Custom.
- B. Configuration:
  - 1. Front: Straight, slightly eased at top.
- C. Wall tops: 1/2-inch-thick, quartz agglomerate with front edge built up with same material.
- D. Joints: Fabricate wall tops without joints.

2.3 INSTALLATION MATERIALS

- A. Adhesive: Product recommended by quartz agglomerate manufacturer.
  - 1. Adhesives shall have a VOC content of 70 g/L or less.

2. Adhesive shall comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- B. Sealant for Wall Tops: Comply with applicable requirements in Section 07 9200 "Joint Sealants."

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates to receive quartz agglomerate wall tops and conditions under which wall tops will be installed, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of wall tops.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 INSTALLATION

- A. Install all quartz agglomerate materials on manufacturer's recommended backing substrate.
- B. Install wall tops level to a tolerance of 1/8 inch in 8 feet, 1/4 inch maximum. Do not exceed 1/64-inch difference between planes of adjacent units.
- C. Secure wall tops to wall with adhesive according to quartz agglomerate manufacturer's written instructions. Align adjacent surfaces and, using adhesive in color to match wall tops, form seams to comply with quartz agglomerate manufacturer's written instructions. Carefully dress joints smooth, remove surface scratches, and clean entire surface.
- D. Apply sealant to gaps at walls; comply with Section 07 9200 "Joint Sealants."

END OF SECTION 12 3662

## SECTION 211000 - WATER-BASED FIRE-SUPPRESSION SYSTEMS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the C
- B. Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following fire-suppression piping inside the building:
  - 1. Wet-pipe sprinkler systems.
  - 2. Description:
- B. Related Sections include the following:
  - 1. Division 10 Section "Fire Extinguisher Cabinets" and "Fire Extinguishers" for cabinets and fire extinguishers.
  - 2. Division 22 Section "Facility Water Distribution Piping" for piping outside the building.
  - 3. Division 28 Section "Fire Detection and Alarm" for alarm devices not specified in this Section.
- C. All black steel sprinkler pipe shall have a wall thickness less than or equal to schedule 40 and greater than schedule 10.
  - 1. Exception: Pipe with a nominal pipe size of 6 inches and greater may be schedule 10.

#### D. Summary Table:

| Item                                | Summary                                                               |
|-------------------------------------|-----------------------------------------------------------------------|
| Underground service entrance piping | Existing to remain                                                    |
| Interior pipe type                  | Mains: Schedule 40<br>Branchlines: Threadable thinwall or schedule 40 |
| Sprinkler Finish                    | Flat Plate Concealed, except uprights and storage                     |
| Extended Coverage                   | Not Allowed                                                           |
| Center of Tile                      | Required, Center thirds are acceptable for rectangular tiles          |
| Flexible Sprinkler Drops            | Designers preference                                                  |
| FM Global                           | No                                                                    |

|               |                                                                                                                |
|---------------|----------------------------------------------------------------------------------------------------------------|
| Calculations  | Not required                                                                                                   |
| Alarm Device  | Horn/Strobe                                                                                                    |
| FDC           | Existing to remain                                                                                             |
| Special Items | Provide black or stainless-steel sprinkler cover plates as determined by architect in all wood style ceilings. |
| Seismic       |                                                                                                                |

### 1.3 DEFINITIONS

- A. CPVC: Chlorinated polyvinyl chloride plastic.
- B. CR: Chlorosulfonated polyethylene synthetic rubber.
- C. High-Pressure Piping System: Fire-suppression piping system designed to operate at working pressure higher than standard 175 psig.
- D. PE: Polyethylene plastic.
- E. Underground Service-Entrance Piping: Underground service piping below the building.

### 1.4 SYSTEM DESCRIPTIONS

- A. Semi-Automatic Wet-Type, Class III Standpipe System: Includes NPS 1-1/2 hose stations and NPS 2-1/2 hose connections. Has open water-supply valve and is capable of supplying water demand for fire sprinklers only. Piping is wet, but water must be pumped in to standpipes to satisfy demand.
- B. Wet-Pipe Sprinkler System: Automatic sprinklers are attached to piping containing water and that is connected to water supply. Water discharges immediately from sprinklers when they are opened. Sprinklers open when heat melts fusible link or destroys frangible device. Hose connections are included if indicated.

### 1.5 PERFORMANCE REQUIREMENTS

- A. Standard Piping System Component Working Pressure: Listed for at least 175 psig.
- B. High-Pressure Piping System Component Working Pressure: Listed for 250 psig minimum 300 psig.
- C. Fire-suppression standpipe system design shall be approved by authorities having jurisdiction.
  - 1. Minimum residual pressure at each hose-connection outlet is the following:

- a. NPS 1-1/2 Hose Connections: 65 psig.
  - b. NPS 2-1/2 Hose Connections: 100 psig.
2. Unless otherwise indicated, the following is maximum residual pressure at required flow at each hose-connection outlet:
  - a. NPS 1-1/2 Hose Connections: 100 psig.
  - b. NPS 2-1/2 Hose Connections: 175 psig.
- D. Design sprinkler piping according to the following and obtain approval from engineer, prior to submitting to other authorities having jurisdiction:
  1. Maintain existing design basis.
  2. Margin of Safety for Available Water Flow and Pressure: 10 percent, including losses through water-service piping, valves, and backflow preventers.
  3. Sprinkler Occupancy Hazard Classifications:
    - a. Automobile Parking Areas: Ordinary Hazard, Group 1.
    - b. Building Service Areas: Ordinary Hazard, Group 1.
    - c. Electrical Equipment Rooms: Ordinary Hazard, Group 1.
    - d. General Storage Areas: Ordinary Hazard, Group 1.
    - e. Laundries: Ordinary Hazard, Group 1.
    - f. Mechanical Equipment Rooms: Ordinary Hazard, Group 1.
    - g. Office and Public Areas: Light Hazard.
  4. Minimum Density for Automatic-Sprinkler Piping Design:
    - a. Light-Hazard Occupancy: 0.10 gpm over 1500-sq. ft. area.
    - b. Ordinary-Hazard, Group 1 Occupancy: 0.15 gpm over 1500-sq. ft. area.
    - c. Special Occupancy Hazard: As determined by authorities having jurisdiction.
  5. Maximum Protection Area per Sprinkler: Per UL listing.
  6. Maximum Protection Area per Sprinkler:
    - a. Office Spaces: 225 sq. ft..
    - b. Storage Areas: 130 sq. ft..
    - c. Mechanical Equipment Rooms: 130 sq. ft..
    - d. Electrical Equipment Rooms: 130 sq. ft..
    - e. Other Areas: According to NFPA 13 recommendations, unless otherwise indicated.
  7. Total Combined Hose-Stream Demand Requirement: According to NFPA 13, unless otherwise indicated:
    - a. Light-Hazard Occupancies: 100 gpm for 30 minutes.
    - b. Ordinary-Hazard Occupancies: 250 gpm for 60 to 90 minutes.

- c. Extra-Hazard Occupancies: 500 gpm for 90 to 120 minutes.
- 8. Sprinklers are to be installed throughout the premises, as required by NFPA 13.
- E. Seismic Performance: Fire-suppression piping shall be capable of withstanding the effects of earthquake motions determined according to NFPA 13.

## 1.6 SUBMITTALS

- A. Product Data: For the following:
  - 1. Piping materials, including dielectric fittings, flexible connections, and sprinkler specialty fittings.
  - 2. Pipe hangers and supports, including seismic restraints.
  - 3. Valves, including listed fire-protection valves, unlisted general-duty valves, and specialty valves and trim.
  - 4. Air compressors, including electrical data.
  - 5. Sprinklers, escutcheons, and guards. Include sprinkler flow characteristics, mounting, finish, and other pertinent data.
  - 6. Hose connections, including size, type, and finish.
  - 7. Fire department connections, including type; number, size, and arrangement of inlets; caps and chains; size and direction of outlet; escutcheon and marking; and finish.
  - 8. Alarm devices, including electrical data.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Fire-hydrant flow test report.
- D. Seismic Calculations.
- E. Approved Sprinkler Piping Drawings: Working plans, prepared according to NFPA 13, that have been approved by authorities having jurisdiction, including hydraulic calculations, if applicable. Drawings are to be approved by Engineer prior to submission to State Fire Marshal.
- F. Field Test Reports and Certificates: Indicate and interpret test results for compliance with performance requirements and as described in NFPA 13 and NFPA 14. Include "Contractor's Material and Test Certificate for Aboveground Piping" and "Contractor's Material and Test Certificate for Underground Piping."
- G. Welding certificates.
- H. Field quality-control test reports.
- I. Operation and Maintenance Data: For standpipe and sprinkler specialties to include in emergency, operation, and maintenance manuals.



## 1.7 QUALITY ASSURANCE

### A. Installer Qualifications:

1. An experienced installer who has designed and installed fire-suppression piping similar to that indicated for this Project and obtained design approval and inspection approval from authorities having jurisdiction. The Engineer requires evidence to support the ability of the contractor to perform work in the scope and volume as specified. A contractor, who cannot show such experience, may be found not suitable to perform the work. The following are the approved contractors for this project:

#### a. PRE-APPROVED CONTRACTORS LIST

- 1) A&D Fire
- 2) Alta Fire
- 3) Certified Fire
- 4) Chaparral Fire (A-1 National)
- 5) Delta Fire
- 6) Kimco Fire
- 7) Preferred Fire Protection
- 8) Quality Fire Protection
- 9) FireTrol
- 10) FireFly Fire Protection
- 11) Simplex-Grinnell
- 12) State Fire DC Specialties
- 13) The Safety Team
- 14) Western Automatic
- 15) Or prior approved equal

- b. A contractor not listed in the "PRE-APPROVED CONTRACTORS LIST" must receive prior approval from the engineer to bid this project.

- ### B. Installer's responsibilities include designing, fabricating, and installing fire-suppression systems and providing professional engineering services needed to assume engineering responsibility. Base calculations on results of fire-hydrant flow test.

1. Engineering Responsibility: Preparation of working plans, calculations, and field test reports by a qualified professional engineer or NICET Level III technician.

- ### C. Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX.

- ### D. NFPA Standards: Fire-suppression-system equipment, specialties, accessories, installation, and testing shall comply with the following:

1. NFPA 13, "Installation of Sprinkler Systems."
2. NFPA 13R, "Installation of Sprinkler Systems in Residential Occupancies up to and Including Four Stories in Height."
3. NFPA 14, "Installation of Standpipe, Private Hydrant, and Hose Systems."
4. NFPA 24, "Installation of Private Fire Service Mains and Their Appurtenances."

E. International Conference of Building Code Officials codes and standards complying with the following:

1. IBC-2018, "International Building Code."
2. IFC-2018, "International Fire Code."

F. Utah Amendments

1. Title 15A

## 1.8 COORDINATION

A. Coordinate layout and installation of sprinklers with other construction that penetrates ceilings, including light fixtures, HVAC equipment, and partition assemblies.

## 1.9 EXTRA MATERIALS

A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Sprinkler Cabinets: Finished, wall-mounting, steel cabinet with hinged cover, with space for minimum of six spare sprinklers plus sprinkler wrench. Include number of sprinklers required by NFPA 13 and sprinkler wrench. Include a minimum of six spare sprinklers for each type and rating of sprinkler head in the project per CMS and CDC requirement. The minimum number of sprinklers per NFPA 13 shall be required regardless of how many head types there are. There is no upper limit of spare sprinklers. Include separate cabinet with sprinklers and wrench for each type of sprinkler on Project.

## 1.10 General Engineering Quality

A. Unless noted otherwise the following applies:

1. The maximum water velocity shall not exceed 32-fps.
2. Submit the calculations using the reduced flow data.
3. When calculating flexible drops, the contractor shall use the maximum number of bends for the associated length. The value is to be taken from the UL tests (unless the material is only FM approved).
4. In the event of multiple (3) submittal rejections (including revise and resubmit) a meeting shall be held at the engineer's office at the engineer time of choosing and the designer, fire sprinkler contractor, and general contractor shall be physically in attendance to discuss the required modifications to the design.

## 1.11 Contract Completion

A. Incomplete and Unacceptable work:

1. If additional site visits or design work is required by the Engineer or Architect because of the use of incomplete or unacceptable work by the Contractor, then the Contractor shall reimburse the Engineer and Architect for all additional time and expenses involved.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

### 2.2 DUCTILE-IRON PIPE AND FITTINGS

- A. Mechanical-Joint, Ductile-Iron Pipe: AWWA C151, with mechanical-joint bell end and plain end.

1. Mechanical-Joint, Ductile-Iron Fittings: AWWA C110, Class 53, ductile- or gray-iron standard pattern or AWWA C153, ductile-iron compact pattern.
2. Glands, Gaskets, and Bolts: AWWA C111, ductile- or gray-iron gland, rubber gasket, and steel bolts and nuts.

- B. Push-on-Joint, Ductile-Iron Pipe: AWWA C151, with push-on-joint bell end and plain end.

1. Push-on-Joint, Ductile-Iron Fittings: AWWA C110, ductile- or gray-iron standard pattern or AWWA C153, ductile-iron compact pattern.
2. Gaskets: AWWA C111, rubber.

### 2.3 C-900 TUBE AND FITTINGS

- A. PVC, AWWA Pipe: AWWA C900, Class 150, with bell end with gasket and spigot end.

1. Comply with UL 1285 for fire-service mains if indicated.
2. PVC Fabricated Fittings: AWWA C900, Class 150, with bell-and-spigot or double-bell ends. Include elastomeric gasket in each bell.
3. PVC Molded Fittings: AWWA C907, Class 150, with bell-and-spigot or double-bell ends. Include elastomeric gasket in each bell.
4. Push-on-Joint, Ductile-Iron Fittings: AWWA C110, ductile- or gray-iron standard pattern or AWWA C153, ductile-iron compact pattern.
  - a. Gaskets: AWWA C111, rubber.

5. Mechanical-Joint, Ductile-Iron Fittings: AWWA C110, ductile- or gray-iron standard pattern or AWWA C153, ductile-iron compact pattern.
  - a. Glands, Gaskets, and Bolts: AWWA C111, ductile- or gray-iron glands, rubber gaskets, and steel bolts.

## 2.4 STAINLESS STEEL IN BUILDING RISER

- A. Continuous from the factory, no field formed fittings in the stainless steel riser. Field modifications are not allowed. Restrain with thrust block, per NFPA 24, rods as required by manufacture.
  1. Inlet: AWWA C900/DIP
  2. Outlet: AWWA 606

## 2.5 STEEL PIPE AND FITTINGS

- A. Threaded-End, Standard-Weight Steel Pipe: ASTM A 53/A 53M, ASTM A 135, or ASTM A 795, hot-dip galvanized where indicated and with factory- or field-formed threaded ends.
  1. Cast-Iron Threaded Flanges: ASME B16.1.
  2. Malleable-Iron Threaded Fittings: ASME B16.3.
  3. Gray-Iron Threaded Fittings: ASME B16.4.
  4. Steel Threaded Pipe Nipples: ASTM A 733, made of ASTM A 53/A 53M or ASTM A 106, Schedule 40, seamless steel pipe hot-dip galvanized where indicated. Include ends matching joining method.
  5. Steel Threaded Couplings: ASTM A 865 hot-dip galvanized-steel pipe where indicated.
- B. Plain-End, Standard-Weight Steel Pipe: ASTM A 53/A 53M, ASTM A 135, or ASTM A 795 hot-dip galvanized-steel pipe where indicated.
  1. Locking-Lug Fittings: UL 213, ductile-iron body with retainer lugs that require one-quarter turn to secure pipe in fitting not allowed.
- C. Plain-End, Standard-Weight Steel Pipe: ASTM A 53/A 53M, ASTM A 135, or ASTM A 795 hot-dip galvanized-steel pipe where indicated.
  1. Steel Welding Fittings: ASTM A 234/A 234M, and ASME B16.9 or ASME B16.11.
  2. Steel Flanges and Flanged Fittings: ASME B16.5.
- D. Grooved-End, Standard-Weight Steel Pipe: ASTM A 53/A 53M, ASTM A 135, or ASTM A 795, hot-dip galvanized where indicated and with factory- or field-formed, roll-grooved ends.

1. Grooved-Joint Piping Systems:
  - a. Manufacturers:
    - 1) Anvil International, Inc.
    - 2) Bull Moose Tube, Inc
    - 3) Central Sprinkler Corp.
    - 4) Victaulic Co. of America.
    - 5) Ward Manufacturing.
    - 6) Wheatland Tube
  - b. Grooved-End Fittings: UL-listed, ASTM A 536, ductile-iron casting with OD matching steel-pipe OD.
  - c. Grooved-End-Pipe Couplings: UL 213 and AWWA C606, rigid pattern, unless otherwise indicated; gasketed fitting matching steel-pipe OD. Include ductile-iron housing with keys matching steel-pipe and fitting grooves, prelubricated rubber gasket listed for use with housing, and steel bolts and nuts.
- E. Threaded-End, Threadable, Thinwall Steel Pipe: ASTM A 135 or ASTM A 795, with wall thickness less than Schedule 40 and greater than Schedule 10, and with factory- or field-formed threaded ends.
  1. Cast-Iron Threaded Flanges: ASME B16.1.
  2. Malleable-Iron Threaded Fittings: ASME B16.3.
  3. Gray-Iron Threaded Fittings: ASME B16.4.
  4. Steel Threaded Pipe Nipples: ASTM A 733, made of ASTM A 53/A 53M or ASTM A 106, Schedule 40, seamless steel pipe.
  5. Steel Threaded Couplings: ASTM A 865.
- F. Plain-End, Threadable, Thinwall Steel Pipe: ASTM A 135 or ASTM A 795, with wall thickness less than Schedule 40 and greater than Schedule 10.
  1. Locking-Lug Fittings: UL 213, ductile-iron body with retainer lugs that require one-quarter turn to secure pipe in fitting not allowed.
- G. Plain-End, Threadable, Thinwall Steel Pipe: ASTM A 135 or ASTM A 795, with wall thickness less than Schedule 40 and greater than Schedule 10.
  1. Steel Welding Fittings: ASTM A 234/A 234M, and ASME B16.9 or ASME B16.11.
  2. Steel Flanges and Flanged Fittings: ASME B16.5.
- H. Grooved-End, Threadable, Thinwall Steel Pipe: ASTM A 135 or ASTM A 795, with wall thickness less than Schedule 40 and greater than Schedule 10, and with factory- or field-formed, roll-grooved ends.
  1. Grooved-Joint Piping Systems:
    - a. Manufacturers:

- 1) Anvil International, Inc.
  - 2) Bull Moose Tube, Inc
  - 3) Central Sprinkler Corp.
  - 4) Victaulic Co. of America.
  - 5) Ward Manufacturing.
  - 6) Wheatland Tube
- b. Grooved-End Fittings: UL-listed, ASTM A 536, ductile-iron casting with OD matching steel-pipe OD.
- c. Grooved-End-Pipe Couplings: UL 213 and AWWA C606, rigid pattern, unless otherwise indicated; gasketed fitting matching steel-pipe OD. Include ductile-iron housing with keys matching steel-pipe and fitting grooves, prelubricated rubber gasket listed for use with housing, and steel bolts and nuts.
- I. Plain-End, Schedule 10 Steel Pipe: ASTM A 135 or ASTM A 795, Schedule 10 is not allowed.
- J. Plain-End, Nonstandard OD, Thinwall Steel Pipe: ASTM A 135 or ASTM A 795, with wall thickness less than Schedule 10 is not allowed.
- K. Plain-End, Hybrid Steel Pipe: ASTM A 135 or ASTM A 795, lightwall, with wall thickness less than Schedule 10 and greater than Schedule 5 is not allowed.
- L. Grooved-End, Hybrid Steel Pipe: ASTM A 135 or ASTM A 795, lightwall, with wall thickness less than Schedule 10 and greater than Schedule 5; with factory- or field-formed, roll-grooved ends are not allowed.
- M. Schedule 5 Steel Pipe: ASTM A 135 or ASTM A 795, lightwall, with plain ends is not allowed.

## 2.6 CPVC TUBE AND FITTINGS

- A. CPVC is not allowed on this project.

## 2.7 COPPER TUBE AND FITTINGS

- A. Soft Copper Tube: ASTM B 88, Type L, water tube, annealed temper; with plain ends.
1. Copper fittings: ASME B16.18, cast-copper-alloy or ASME B16.22, wrought-copper, solder-joint pressure type. Furnish only wrought-copper fittings if indicated.
  2. Brazing Filler Metals: AWS A5.8, BCuP-3 or BCuP-4.
- B. Plain-End, Hard Copper Tube: ASTM B 88, Type K or ASTM B 88, Type L, water tube, drawn temper.

1. Copper Fittings: ASME B16.18, cast-copper-alloy or ASME B16.22, wrought-copper, solder-joint pressure type. Furnish only wrought-copper fittings if indicated.
  2. Bronze Flanges: ASME B16.24, Class 150, with solder-joint end. Furnish Class 300 flanges if required to match tubing system.
  3. Copper Unions: MSS SP-123, cast-copper-alloy, hexagonal-stock body with ball-and-socket metal-to-metal seating surfaces, and solder-joint or threaded ends.
  4. Copper, Mechanically Formed Tee Option: For forming T-branch on copper water tube not allowed.
  5. Brazing Filler Metals: AWS A5.8, BCuP-3 or BCuP-4.
- C. Grooved-End, Hard Copper Tube: ASTM B 88, Type K or ASTM B 88, Type L, water tube, drawn temper; with factory- or field-formed, roll-grooved ends.
1. Copper, Mechanically Formed Tee Option: For forming T-branch on copper water tube not allowed.
  2. Grooved-Joint Systems:
    - a. Manufacturers:
      - 1) Anvil International, Inc.
      - 2) Victaulic Co. of America.
    - b. Grooved-End Copper Fittings: ASTM B 75, copper tube or ASTM B 584, bronze casting. Fittings may have ends factory or field expanded to steel-pipe OD if required for copper tube systems using grooved-end-pipe couplings.
    - c. Grooved-End-Tube Couplings: UL 213, rigid pattern, unless otherwise indicated; gasketed fitting equivalent to AWWA C606, but made to match copper-tube OD. Include ductile-iron housing with keys matching steel-pipe and fitting grooves, prelubricated rubber gasket listed for use with housing, and steel bolts and nuts. Use grooved-end-pipe couplings for tube and fitting that have expanded ends.

## 2.8 FLEXIBLE SPRINKLER DROPS

- A. Flexible connectors shall be FM approved with exterior wire braid and have materials suitable for system fluid. Include 175-psig minimum working-pressure rating and ends according to the following:
1. NPS 1: Threaded.
- B. Manufacturers:
1. Flex-Head
  2. Victaulic
- C. Stainless-Steel-Hose/Steel Pipe, Flexible Connectors: Corrugated, stainless-steel, inner tubing covered with stainless-steel wire braid. Include steel nipples or flanges, welded to hose.

- D. Stainless-Steel-Hose/Stainless-Steel Pipe, Flexible Connectors: Corrugated, stainless-steel, inner tubing covered with stainless-steel wire braid. Include stainless-steel nipples or flanges, welded to hose.

## 2.9 FLEXIBLE PIPE CONNECTORS (SEISMIC)

- A. Flexible connectors shall be FM approved with exterior wire braid and have materials suitable for system fluid. Include 175-psig minimum working-pressure rating and ends according to the following:

1. NPS 2 and Smaller: Threaded.
2. NPS 2-1/2 and Larger: Flanged.
3. Option for NPS 2-1/2 and Larger: Grooved for use with grooved-end-pipe couplings.

- B. Manufacturers:

1. Flexicraft Industries.
2. Flex-Pression, Ltd.
3. Metraflex, Inc.

- C. Bronze-Hose, Flexible Connectors: Corrugated, bronze, inner tubing covered with bronze wire braid. Include copper-tube ends or bronze flanged ends, braze welded to hose.

- D. Stainless-Steel-Hose/Steel Pipe, Flexible Connectors: Corrugated, stainless-steel, inner tubing covered with stainless-steel wire braid. Include steel nipples or flanges, welded to hose.

- E. Stainless-Steel-Hose/Stainless-Steel Pipe, Flexible Connectors: Corrugated, stainless-steel, inner tubing covered with stainless-steel wire braid. Include stainless-steel nipples or flanges, welded to hose.

## 2.10 CORROSION-PROTECTIVE ENCASEMENT FOR PIPING

- A. Encasement for Underground Metal Piping: ASTM A 674 or AWWA C105, PE film, 0.008-inch minimum thickness, tube or sheet.

## 2.11 SPRINKLER SPECIALTY FITTINGS

- A. Sprinkler specialty fittings shall be FMG approved with 175-psig minimum working-pressure rating, and made of materials compatible with piping. Sprinkler specialty fittings shall have 250-psig minimum working-pressure rating if fittings are components of high-pressure piping systems.
- B. Sprinkler Drain and Alarm Test Fittings: Cast- or ductile-iron body, with threaded or locking-lug inlet and outlet, test valve, and orifice and sight glass.



1. Manufactures:
  - a. Central Sprinkler Corp.
  - b. Fire-End and Croker Corp.
  - c. Viking Corp.
  - d. Victaulic Co. of America.
- C. Sprinkler Branch-Line Test Fittings: Brass body with threaded inlet, capped drain outlet, and threaded outlet for sprinkler.
- D. Sprinkler Inspector's Test Fitting: Cast- or ductile-iron housing with threaded inlet and drain outlet and sight glass.
- E. Drop-Nipple Fittings: UL 1474, adjustable with threaded inlet and outlet, and seals.
- F. Dry-Pipe-System Fittings: UL listed for dry-pipe service.

## 2.12 LISTED FIRE-PROTECTION VALVES

- A. Valves shall be FMG approved, with 175-psig minimum pressure rating. Valves shall have 250-psig minimum pressure rating if valves are components of high-pressure piping system.
- B. Gate Valves with Wall Indicator Posts:
  1. Gate Valves: UL 262, cast-iron body, bronze mounted, with solid disc, nonrising stem, operating nut, and flanged ends.
  2. Indicator Posts: UL 789, horizontal-wall type, cast-iron body, with hand wheel, extension rod, locking device, and cast-iron barrel.
  3. Manufacturers:
    - a. Grinnell Fire Protection.
    - b. McWane, Inc.; Kennedy Valve Div.
    - c. NIBCO.
    - d. Stockham.
- C. Ball Valves: Comply with UL 1091, except with ball instead of disc.
  1. NPS 1-1/2 and Smaller: Bronze body with threaded ends.
  2. NPS 2 and NPS 2-1/2: Bronze body with threaded ends or ductile-iron body with grooved ends.
  3. NPS 3: Ductile-iron body with grooved ends.
  4. Manufacturers:
    - a. NIBCO.
    - b. Victaulic Co. of America.

D. Butterfly Valves: UL 1091.

1. NPS 2 and Smaller: Bronze body with threaded ends.
  - a. Manufacturers:
    - 1) Global Safety Products, Inc.
    - 2) Milwaukee Valve Company.
2. NPS 2-1/2 and Larger: Bronze, cast-iron, or ductile-iron body; wafer type or with flanged or grooved ends.
  - a. Manufacturers:
    - 1) Central Sprinkler Corp.
    - 2) McWane, Inc.; Kennedy Valve Div.
    - 3) Mueller Company.
    - 4) NIBCO.
    - 5) Victaulic Co. of America.

E. Check Valves NPS 2 and Larger: UL 312, swing type, cast-iron body with flanged or grooved ends.

1. Manufacturers:
  - a. American Cast Iron Pipe Co.; Waterous Co.
  - b. Central Sprinkler Corp.
  - c. Clow Valve Co.
  - d. Crane Co.; Crane Valve Group; Crane Valves.
  - e. Crane Co.; Crane Valve Group; Jenkins Valves.
  - f. Fivalco
  - g. Globe Fire Sprinkler Corporation.
  - h. Grinnell Fire Protection.
  - i. Hammond Valve.
  - j. McWane, Inc.; Kennedy Valve Div.
  - k. Mueller Company.
  - l. NIBCO.
  - m. Potter-Roemer; Fire Protection Div.
  - n. Reliable Automatic Sprinkler Co., Inc.
  - o. Star Sprinkler Inc.
  - p. Stockham.
  - q. United Brass Works, Inc.
  - r. Victaulic Co. of America.
  - s. Watts Industries, Inc.; Water Products Div.

F. Gate Valves: UL 262, OS&Y type.

1. NPS 2 and Smaller: Bronze body with threaded ends.

a. Manufacturers:

- 1) Crane Co.; Crane Valve Group; Crane Valves.
- 2) Fivalco.
- 3) Hammond Valve.
- 4) NIBCO.
- 5) United Brass Works, Inc.

2. NPS 2-1/2 and Larger: Cast-iron body with flanged ends.

a. Manufacturers:

- 1) Clow Valve Co.
- 2) Crane Co.; Crane Valve Group; Crane Valves.
- 3) Crane Co.; Crane Valve Group; Jenkins Valves.
- 4) Fivalco
- 5) Hammond Valve.
- 6) Milwaukee Valve Company.
- 7) Mueller Company.
- 8) NIBCO.
- 9) United Brass Works, Inc.

G. Indicating Valves: UL 1091, with integral indicating device and ends matching connecting piping.

1. Indicator: Electrical, 115-V ac, prewired, single-circuit, supervisory switch and Visual.
2. NPS 2 and Smaller: Ball or butterfly valve with bronze body and threaded ends.

a. Manufacturers:

- 1) Milwaukee Valve Company.
- 2) NIBCO.
- 3) Victaulic Co. of America.

3. NPS 2-1/2 and Larger: Butterfly valve with cast- or ductile-iron body; wafer type or with flanged or grooved ends.

a. Manufacturers:

- 1) Central Sprinkler Corp.
- 2) Grinnell Fire Protection.
- 3) McWane, Inc.; Kennedy Valve Div.
- 4) Milwaukee Valve Company.
- 5) NIBCO.
- 6) Victaulic Co. of America.

H. Supervised Normally Closed Valve

1. Indicator: Electrical, 115-V ac, prewired, single-circuit, supervisory switch and visual to send signal on partial close.

- a. Manufactures:

- 1) NIBCO.
- 2) Victaulic Co. of America.

## 2.13 UNLISTED GENERAL-DUTY VALVES

- A. Ball Valves NPS 2 and Smaller: MSS SP-110, 2-piece copper-alloy body with chrome-plated brass ball, 600-psig minimum CWP rating, blowout-proof stem, and threaded ends.
- B. Check Valves NPS 2 and Smaller: MSS SP-80, Type 4, Class 125 minimum, swing type with bronze body, nonmetallic disc, and threaded ends.
- C. Gate Valves NPS 2 and Smaller: MSS SP-80, Type 2, Class 125 minimum, with bronze body, solid wedge, and threaded ends.
- D. Globe Valves NPS 2 and Smaller: MSS SP-80, Type 2, Class 125 minimum, with bronze body, nonmetallic disc, and threaded ends.

## 2.14 SPECIALTY VALVES

- A. Sprinkler System Control Valves: FMG approved, cast- or ductile-iron body with flanged or grooved ends, and 175-psig minimum pressure rating. Control valves shall have 250-psig minimum pressure rating if valves are components of high-pressure piping system.

1. Manufacturers:

- a. Globe Fire Sprinkler Corporation.
- b. Reliable Automatic Sprinkler Co., Inc.
- c. Victaulic Co. of America.
- d. Viking Corp.

## 2.15 SPRINKLERS

- A. Sprinklers shall be UL listed or FMG approved, with 175-psig minimum pressure rating. Sprinklers shall have 250-psig minimum 300-psig pressure rating if sprinklers are components of high-pressure piping system.
- B. Sprinklers shall have 250-psig minimum 300-psig pressure rating if sprinklers are components of high-pressure piping system.
- C. Manufacturers:

1. Globe Fire Sprinkler Corporation.
2. Reliable Automatic Sprinkler Co., Inc.
3. Victaulic Co. of America.
4. Viking Corp.
5. Tyco Fire

D. Automatic Sprinklers: With heat-responsive element complying with the following:

1. UL 199, for nonresidential applications.
2. UL 1626, for residential applications.

E. Sprinkler Types and Categories: Nominal 1/2-inch orifice for "Ordinary" temperature classification rating, unless otherwise indicated or required by application.

1. Open Sprinklers: UL 199, without heat-responsive element.
  - a. Orifice: 1/2 inch, with discharge coefficient K between 5.3 and 5.8.
  - b. Orifice: 17/32 inch, with discharge coefficient K between 7.4 and 8.2.

F. Sprinkler types, features, and options as follows:

1. Concealed ceiling sprinklers, including cover plate.
2. Extended-coverage sprinklers, not allowed unless approved in writing prior to bidding.
3. Flow-control sprinklers, with automatic open and shutoff feature.
4. Flush ceiling sprinklers, including escutcheon, not allowed.
5. Institution sprinklers, made with a small, breakaway projection.
6. Pendent sprinklers.
7. Pendent, dry-type sprinklers.
8. Quick-response sprinklers.
9. Sidewall sprinklers.
10. Sidewall, dry-type sprinklers.
11. Upright sprinklers.

G. Sprinkler Finishes: Chrome plated, bronze, and painted. Finishes as approved by FM Global.

H. Special Coatings: Wax, lead, and corrosion-resistant paint.

I. Sprinkler Escutcheons: Materials, types, and finishes for the following sprinkler mounting applications. Escutcheons for concealed, flush, and recessed-type sprinklers are specified with sprinklers.

1. Ceiling Mounting: Flat plate concealed, white.
2. Sidewall Mounting: Flat plate concealed, white.

J. Sprinkler Guards: Wire-cage type, including fastening device for attaching to sprinkler.

## 2.16 HOSE CONNECTIONS

### A. Manufacturers:

1. Central Sprinkler Corp.
2. Elkhart Brass Mfg. Co., Inc.
3. Fire-End and Croker Corp.
4. Fivalco
5. Grinnell Fire Protection.
6. Guardian Fire Equipment Incorporated.
7. McWane, Inc.; Kennedy Valve Div.
8. Mueller Company.
9. Potter-Roemer; Fire-Protection Div.
10. United Brass Works, Inc.

B. Description: UL 668, brass or bronze, 300-psig minimum pressure rating, hose valve for connecting fire hose. Include angle or gate pattern design; female NPS inlet and male hose outlet; and lugged cap, gasket, and chain. Include NPS 1-1/2 or NPS 2-1/2, and hose valve threads according to NFPA 1963 and matching local fire department threads.

1. Valve Operation: Nonadjustable type, unless pressure-regulating type is indicated.
2. Finish: Rough metal.

## 2.17 FIRE DEPARTMENT CONNECTIONS

A. Existing to remain.

## 2.18 ALARM DEVICES

A. Alarm-device types shall match piping and equipment connections.

B. Electrically Operated Alarm: UL 464, with 8-inch- minimum- diameter, vibrating-type, metal alarm bell with red-enamel factory finish and suitable for outdoor use.

### 1. Manufacturers:

- a. Potter Electric Signal Company.
- b. System Sensor.

C. Electrically Operated Alarm: Horn/Strobe, NEMA 3R minimum suitable for outdoor use.

### 1. Manufacturers:

- a. Potter Electric Signal Company.
- b. System Sensor.

- D. Water-Flow Indicator: UL 346, electrical-supervision, paddle-operated-type, water-flow detector with 250-psig pressure rating and designed for horizontal or vertical installation. Include two single-pole, double-throw circuit switches for isolated alarm and auxiliary contacts, 7 A, 125-V ac and 0.25 A, 24-V dc; complete with factory-set, field-adjustable retard element to prevent false signals and tamperproof cover that sends signal if removed.

1. Manufacturers:

- a. ADT Security Services, Inc.
- b. Grinnell Fire Protection.
- c. ITT McDonnell & Miller.
- d. Potter Electric Signal Company.
- e. System Sensor.
- f. Viking Corp.
- g. Watts Industries, Inc.; Water Products Div.

- E. Pressure Switch: UL 753, electrical-supervision-type, water-flow switch with retard feature. Include single-pole, double-throw, normally closed contacts and design that operates on rising pressure and signals water flow.

1. Manufacturers:

- a. Grinnell Fire Protection.
- b. Potter Electric Signal Company.
- c. System Sensor.
- d. Viking Corp.

- F. Valve Supervisory Switch: UL 753, electrical, single-pole, double-throw switch with normally closed contacts. Include design that signals controlled valve is in other than fully open position.

1. Manufacturers:

- a. McWane, Inc.; Kennedy Valve Div.
- b. Potter Electric Signal Company.
- c. System Sensor.

- G. Indicator-Post Supervisory Switch: UL 753, electrical, single-pole, double-throw switch with normally closed contacts. Include design that signals controlled indicator-post valve is in other than fully open position.

1. Manufacturers:

- a. Potter Electric Signal Company.
- b. System Sensor.

## 2.19 PRESSURE GAGES

### A. Manufacturers:

1. Brecco Corporation.
2. Dresser Equipment Group; Instrument Div.
3. Marsh Bellofram.
4. WIKA Instrument Corporation.

### B. Description: UL 393, 3-1/2- to 4-1/2-inch- diameter, dial pressure gage with range of 0 to 250 psig minimum.

1. Water System Piping: Include caption "WATER" or "AIR/WATER" on dial face.
2. Air System Piping: Include retard feature and caption "AIR" or "AIR/WATER" on dial face.

## 2.20 DOUBLE CHECK VALVE ASSEMBLIES

### A. Manufacturers

1. Ames
2. Backflow Direct
3. Febco
4. Wilkins
5. Watts

### B. Description; Resilient seated, spring loaded with testable outlets provided, as required by Authorities Having Jurisdiction.

## PART 3 - EXECUTION

### 3.1 EARTHWORK

#### A. Refer to Division 31 Section "Earth Moving" for excavating, trenching, and backfilling.

### 3.2 EXAMINATION

- A. Examine roughing-in for hose connections and stations to verify actual locations of piping connections before installation.
- B. Examine walls and partitions for suitable thicknesses, fire- and smoke-rated construction, framing for hose-station cabinets, and other conditions where hose connections and stations are to be installed.



- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.3 PIPING APPLICATIONS

- A. Shop weld pipe joints where welded piping is indicated.
- B. Do not use welded joints for galvanized-steel pipe.
- C. Flanges, flanged fittings, unions, nipples, and transition and special fittings with finish and pressure ratings same as or higher than system's pressure rating may be used in aboveground applications, unless otherwise indicated.
- D. Piping between Fire Department Connections and Check Valves: Galvanized, standard-weight steel pipe with grooved ends; grooved-end fittings; grooved-end-pipe couplings; and grooved joints.
- E. Underground Service-Entrance Piping: Ductile-iron, push-on or mechanical-joint pipe and fittings and restrained joints. Include corrosion-protective encasement.
- F. Sprinkler Main Piping: Use the following:
  - 1. NPS 6 and Smaller: Standard-weight steel pipe with threaded ends, or grooved ends. No plain ends allowed.
  - 2. Outlets shall be welded.
    - a. Victaulic Brand Mechanical tee fittings may be used in lieu of welded outlets.
- G. Branch line piping: Use the following:
  - 1. NPS 1-1/4 and Smaller: Threadable steel pipe with threaded ends; cast- or malleable-iron threaded fittings; and threaded joints.
    - a. Victaulic Brand Mechanical tee fittings may be used
- H. Standpipes and mains: Use the following:
  - 1. NPS 4 to NPS 6: Schedule 40 steel pipe with grooved ends & Welded outlets.
  - 2. NPS 3 and Smaller: Schedule 40 steel pipe with threaded ends, or grooved ends. No plain ends allowed.

### 3.4 VALVE APPLICATIONS

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:

1. Fire-Protection-Service Valves: UL listed and FM approved for applications where required by NFPA 13 and NFPA 14.
2. General-Duty Valves: For applications where UL-listed and FM-approved valves are not required by NFPA 13 and NFPA 14.
  - a. Shutoff Duty: Use gate, ball, or butterfly valves.
  - b. Throttling Duty: Use globe, ball, or butterfly valves.

### 3.5 JOINT CONSTRUCTION

- A. Refer to Division 23 Section "Common Work Result for HVAC" for basic piping joint construction.
- B. Ductile-Iron-Piping, Grooved Joints: Use ductile-iron pipe with radius-cut-grooved ends; ductile-iron, grooved-end fittings; and ductile-iron, keyed couplings. Assemble joints with couplings, gaskets, lubricant, and bolts according to coupling manufacturer's written instructions.
- C. Steel-Piping, Grooved Joints: Use Schedule 40 steel pipe with cut or roll-grooved ends and Schedule 30 or thinner steel pipe with roll-grooved ends; steel, grooved-end fittings; and steel, keyed couplings. Assemble joints with couplings, gaskets, lubricant, and bolts according to coupling manufacturer's written instructions. Use gaskets listed for dry-pipe service for dry piping.

### 3.6 WATER-SUPPLY CONNECTION

- A. Install shutoff Backflow preventions assemblies, valve, pressure gage's, drain, and other accessories at connection to water service.

### 3.7 PIPING INSTALLATION

- A. Refer to Division 23 Section "Common Work Result for HVAC" for basic piping installation.
- B. Locations and Arrangements: Drawing plans, schematics, and diagrams indicate general location and arrangement of piping. Install piping as indicated, as far as practical.
  1. Deviations from approved working plans for piping require written approval from authorities having jurisdiction. File written approval with Architect before deviating from approved working plans.
- C. Install underground service-entrance piping according to NFPA 24 and with restrained joints.
- D. Make connections between underground and above-ground piping using bolted flange.

- E. Install mechanical sleeve seal at pipe penetrations in basement and foundation walls. Refer to Division 23 Section "Common Work Result for HVAC."
- F. Use approved fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.
- G. Install unions adjacent to each valve in pipes NPS 2 and smaller. Unions are not required on flanged devices or in piping installations using grooved joints.
- H. Install flanges or flange adapters on valves, apparatus, and equipment having NPS 2-1/2 and larger connections.
- I. Install "Inspector's Test Connections" in sprinkler piping, complete with shutoff valve, sized and located according to NFPA 13.
- J. Install sprinkler piping with drains for complete system drainage.
- K. Install sprinkler zone control valves, check valves, test assemblies, and drain risers adjacent to standpipes when sprinkler piping is connected to standpipes.
- L. Install drain valves on standpipes.
- M. Install ball drip valves to drain piping between fire department connections and check valves. Drain to floor drain or outside building.
- N. Install alarm devices in piping systems.
- O. Hangers and Supports: Comply with NFPA 13 for hanger materials. Install according to NFPA 13 for sprinkler piping and to NFPA 14 for standpipes.
  - 1. No powder driven studs allowed.
  - 2. Wrap-around braces are to be provided at end of branch lines.
- P. Earthquake Protection: Install piping according to NFPA 13-9.3 requirements, to protect from earthquake damage. Seismic Bracing shall be designed to withstand vertical forces and movement.
- Q. Install piping with grooved joints according to manufacturer's written instructions. Construct rigid piping joints, unless otherwise indicated, or required by NFPA 13 for flexibility in seismic zones.
- R. Install pressure gages on riser or feed main, at each sprinkler test connection, and at top of each standpipe. Include pressure gages with connection not less than NPS 1/4 and with soft metal seated globe valve, arranged for draining pipe between gage and valve. Install gages to permit removal, and install where they will not be subject to freezing.
- S. When a fire pipe crosses a seismic expansion joint it shall have a Metraflex fire loop installed at the joint in accordance with NFPA 13 chapter 9.

### 3.8 SPECIALTY SPRINKLER FITTING INSTALLATION

- A. Install specialty sprinkler fittings according to manufacturer's written instructions.

### 3.9 VALVE INSTALLATION

- A. Refer to Division 23 Section "Valves" for installing general-duty valves. Install fire-protection specialty valves, trim, fittings, controls, and specialties according to NFPA 13 and NFPA 14, manufacturer's written instructions, and authorities having jurisdiction.
- B. Valves: Install fire-protection-service valves supervised-open, located to control sources of water supply except from fire department connections. Provide permanent identification signs indicating portion of system controlled by each valve.
- C. Double Check Valve Assemblies: Install valves in vertical up or horizontal position, per listings and for proper direction of flow.
- D. Deluge Valves: Install in vertical position, in proper direction flow, in main supply to deluge system.

### 3.10 SPRINKLER APPLICATIONS

- A. General: All sprinklers are to be quick response type. Sprinkler heads shall be of the latest design closed spray type for 155°F unless specified otherwise or required by code. Extended coverage heads shall not be used. Orifices larger than 1/2" may be used as required by density and spacing demands. Use sprinklers according to the following applications:
  - 1. Rooms without Ceilings: Upright and/or pendent sprinklers. Provide mechanical guards on all heads at or below 7'-0" height above the floor or where damage from room occupant use may occur.
  - 2. Rooms with Ceilings: Concealed sprinklers unless indicated otherwise.
  - 3. Wall Mounting: Concealed sidewall sprinklers unless indicated otherwise.
  - 4. Institutional sprinklers shall be installed in areas of detention, correctional or mental health care facilities.
  - 5. Spaces Subject to Freezing: Upright; pendent, dry-type; and sidewall, dry-type sprinklers.
  - 6. Provide freeze proof type automatic sprinkler heads serving unconditioned spaces, areas subject to freezing and in other areas requiring their use.
  - 7. Heads located within the air streams of unit heaters or other heat-emitting equipment shall be selected for proper temperature rating.
  - 8. Sprinkler Finishes: Use sprinklers with the following finishes:
    - a. Upright, Pendent, and Sidewall Sprinklers: Chrome in finished spaces exposed to view; rough bronze in unfinished spaces not exposed to view.
    - b. Concealed Sprinklers: Rough brass, with White cover plate to match ceiling color.

B. Sprinklers: Use the following:

1. All sprinklers shall be listed, quick response type.
2. Sprinkler in future finish spaces (shelled) 10' x 10' spacing shall be pendants/uprights installed with 1 x ½" bushing, to accommodate future finishes.
3. Finish ceiling spaces shall have flat-plate concealed sprinklers.

3.11 SPRINKLER INSTALLATION

- A. Every effort shall be required to ensure that the heads form a symmetrical pattern in the ceiling with the ceiling grid if included, as well as lights, diffusers and grilles. Offsets shall be made in piping to accommodate ductwork in the ceiling. Heads shall be symmetrical in all ceilings and all piping run parallel or perpendicular to building lines. Heads shall be linearly aligned in corridors.
1. In no case shall sprinkler heads be installed closer than approved distances from ceiling obstructions and HVAC ductwork.
  2. Sprinkler heads shall not conflict with tile grids.
  3. Sprinkler heads shall be located near center of corridors.
- B. Where layout of sprinkler heads is shown on reflected ceiling plans the locations shall be followed unless approval is obtained from the Architect or such locations shown do not meet the requirements of NFPA-13. In either case, approval of the Architect shall be obtained in writing before sprinkler head locations are changed. If the installation of additional heads is needed to conform to NFPA 13 requirements in areas where heads are shown on reflected ceiling plans, they shall be included in the contract price.
- C. Install sprinklers in patterns indicated.
- D. Do not install pendent or sidewall, wet-type sprinklers in areas subject to freezing. Use dry-type sprinklers with water supply from heated space.
- E. Future finish shelled and tenant finish; Shell spaces shall be piped to accommodate future. Install sprinklers with 1" x ½" bushings, and space heads at a maximum spacing of 100 sq. ft. per head. Occupancy shall be Ordinary-Hazard Group 1 Design.
- F. Concealed type sprinkler shall be installed in the following areas:
1. All areas.

3.12 HOSE-CONNECTION INSTALLATION

- A. Install hose connections adjacent to standpipes, unless otherwise indicated.
- B. Install freestanding hose connections for access and minimum passage restriction.

- C. Install NPS 2-1/2 hose connections with quick-disconnect NPS 2-1/2 by NPS 1-1/2 reducer adapter, cap and chain.

### 3.13 FIRE DEPARTMENT CONNECTION INSTALLATION

- A. When installing the Fire Department Connection, the contractor is to ensure that there are no permanent obstruction(s) as to the fire department access. If an obstruction is present immediately notify the designer and the design team before proceeding with the installation.
- B. Coordinate the exact location with the Architect and the Authority Having Jurisdiction.
- C. Install ball drip valves at each check valve for fire department connection. Drain to floor drain or outside building.

### 3.14 CONNECTIONS

- A. Connect water-supply piping and standpipes and sprinklers where indicated.
- B. Connect piping to specialty valves, hose valves, specialties, fire department connections, and accessories.
- C. Electrical Connections: Power wiring is specified in Division 28.
- D. Connect alarm devices to fire alarm.

### 3.15 LABELING AND IDENTIFICATION

- A. Install labeling and pipe markers on equipment and piping according to requirements in NFPA 13 and NFPA 14 and in Division 23 Section "Common Work Result for HVAC."

### 3.16 FIELD QUALITY CONTROL

- A. Flush, test, and inspect sprinkler piping according to NFPA 13, "System Acceptance" Chapter.
- B. Flush, test, and inspect standpipes according to NFPA 14, "Tests and Inspection" Chapter.
- C. Replace piping system components that do not pass test procedures and retest to demonstrate compliance. Repeat procedure until satisfactory results are obtained.
- D. When making a mechanical tee connection the coupon shall be attached at the mechanical tee.
- E. Report test results promptly and in writing to Architect and authorities having jurisdiction.

- F. Whether the underground serving the sprinkler system is done by this contractor or another, this contractor will be responsible to assure and have in his possession a certificate that the underground has been flushed and tested by the contractor who installed it in accordance with NFPA-24 prior to connection of the underground piping to the overhead sprinkler system.

### 3.17 CLEANING

- A. Clean dirt and debris from sprinklers.
- B. Remove and replace sprinklers having paint other than factory finish.

### 3.18 PROTECTION

- A. Protect sprinklers from damage until Substantial Completion.

### 3.19 COMMISSIONING

- A. Verify that specialty valves, trim, fittings, controls, and accessories are installed and operate correctly.
- B. Verify that specified tests of piping are complete and that "Material Test Certificates" are complete.
- C. Verify that damaged sprinklers and sprinklers with paint or coating not specified are replaced with new, correct type.
- D. Verify that sprinklers are correct types, have correct finishes and temperature ratings, and have guards as required for each application.
- E. Verify that hose connections and fire department connections have threads compatible with local fire department equipment.
- F. Fill wet-pipe sprinkler piping with water.
- G. Fill standpipes with water.
- H. Verify that hose connections are correct type and size.
- I. Coordinate with fire alarm tests. Operate as required.

### 3.20 DEMONSTRATION & TESTS

- A. Demonstrate equipment, specialties, and accessories. Review operating and maintenance information.

- B. All tests will be conducted as required by the local authority having jurisdiction, and in no case less than those required by NFPA standards. As a minimum, piping in the sprinkler system shall be tested at a water pressure at 200 psi for a period of not less two hours, or at 50 psi in excess of the normal pressure when the normal pressure is above 150 psi. Bracing shall be in place, and air shall be removed from the system through the hydrants and drain valves before the test pressure is applied. No apparent leaks will be permitted on interior or underground piping.
- C. The local jurisdiction having authority and the Utah State Fire Marshal's office (where required) shall be notified at least three working days in advance of all tests and flushing. This includes any flushing of underground, hydrostatic testing, or flow testing that may be required.
- D. This contractor shall make all the required tests to the sprinkler system as required by code. He shall be responsible to assure that the Contractor Test Certificates for the overhead, backflow and underground work are completed and delivered to the owner's insurance underwriter to assure proper insurance credit.
- E. All tests requiring the witnessing by local authorities will be the responsibility of this contractor. If tests are not run or do not have the proper witness, then they will be run later and all damage caused by the system, or caused in uncovering the system for such test, will be borne by this contractor.

### 3.21 WARRANTY

- A. This contractor shall warranty the sprinkler system and all its components for one year from the date of acceptance by the owner. Any costs incurred to extend any warranties of materials to assure this time frame shall be borne by this contractor.
- B. Provide Operation and Maintenance Manuals with correct as-builts test certificates and warranties included. A minimum 6 sets to be provided in red 3-ring binders. Include a current adopted version of NFPA 25 softbound copy left with owner.
- C. Electronic copy of AutoCAD as-built drawings shall also be provided on CD, with each O&M Manual.

### 3.22 FIELD QUALITY CONTROL

- A. Flush, test and inspect sprinkler piping according to NFPA 13, "System Acceptance" Chapter.
- B. Replace piping system components that do not pass test procedures and retest to demonstrate compliance. Repeat procedure until satisfactory results are obtained.
- C. Report test results promptly and in writing to Architect and authorities having jurisdiction.



ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84104

Code Review

END OF SECTION 21 1000

## SECTION 22 0500 - COMMON WORK RESULTS FOR PLUMBING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Piping materials and installation instructions common to most piping systems.
  - 2. Transition fittings.
  - 3. Dielectric fittings.
  - 4. Grout.
  - 5. Equipment installation requirements common to equipment sections.
  - 6. Painting and finishing.
  - 7. Concrete bases.
  - 8. Supports and anchorages.

#### 1.3 SEISMIC REQUIREMENTS

- A. Seismic Performance: Equipment, pipe hangers and supports shall withstand the effects of earthquake motions determined according to SEI/ASCE 7 and with the requirements specified in Section 220548 " Vibration and Seismic Controls for Plumbing Piping and Equipment."
  - 1. For components with a seismic importance factor of 1.0 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified."
  - 2. For components with a seismic importance factor of 1.5 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified and the system will be fully operational after the seismic event."

#### 1.4 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe chases, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, and crawlspaces.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces and mechanical equipment rooms, accessible pipe shafts, accessible plumbing chases and accessible tunnels.

- C. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- D. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and in chases.
- E. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.
- F. The following are industry abbreviations for rubber materials:
  - 1. EPDM: Ethylene-propylene-diene terpolymer rubber.
  - 2. NBR: Acrylonitrile-butadiene rubber.

#### 1.5 SUBMITTALS

- A. Product Data: For the following:
  - 1. Transition fittings.
  - 2. Dielectric fittings.
- B. Welding certificates.

#### 1.6 QUALITY ASSURANCE

- A. Steel Support Welding: Qualify processes and operators according to AWS D1.1, "Structural Welding Code--Steel."
- B. Electrical Characteristics for Plumbing Equipment: Equipment of higher electrical characteristics may be furnished provided such proposed equipment is approved in writing and connecting electrical services, circuit breakers, and conduit sizes are appropriately modified. If minimum energy ratings or efficiencies are specified, equipment shall comply with requirements.

#### 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.
- B. Store plastic pipes protected from direct sunlight. Support to prevent sagging and bending.

#### 1.8 COORDINATION

- A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for plumbing installations.

- B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.
- C. Coordinate requirements for access panels and doors for plumbing items requiring access that are concealed behind finished surfaces. Access panels and doors are specified in Division 08 Section "Access Doors and Frames."

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. In other Part 2 articles where subparagraph titles below introduce lists, the following requirements apply for product selection:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by the manufacturers specified.

### 2.2 PIPE, TUBE, AND FITTINGS

- A. Refer to individual Division 22 piping Sections for pipe, tube, and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

### 2.3 JOINING MATERIALS

- A. Refer to individual Division 22 piping Sections for special joining materials not listed below.
- B. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
  - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness unless thickness or specific material is indicated.
    - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
    - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
  - 2. AWWA C110, rubber, flat face, 1/8 inch thick, unless otherwise indicated; and full-face or ring type, unless otherwise indicated.
- C. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.
- D. Plastic, Pipe-Flange Gasket, Bolts, and Nuts: Type and material recommended by piping system manufacturer, unless otherwise indicated.
- E. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.

- F. Brazing Filler Metals: AWS A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing, unless otherwise indicated; and AWS A5.8, BAg1, silver alloy for refrigerant piping, unless otherwise indicated.

## 2.4 TRANSITION FITTINGS

- A. Flexible Transition Couplings for Underground Nonpressure Drainage Piping: ASTM C 1173 with elastomeric sleeve, ends same size as piping to be joined, and corrosion-resistant metal band on each end.
  - 1. Manufacturers:
    - a. Cascade Waterworks Mfg. Co.
    - b. Fernco, Inc.
    - c. Mission Rubber Company.
    - d. Plastic Oddities, Inc.

## 2.5 DIELECTRIC FITTINGS

- A. Description: Combination fitting of copper alloy and ferrous materials with threaded, solder-joint, plain, or weld-neck end connections that match piping system materials.
- B. Insulating Material: Suitable for system fluid, pressure, and temperature.
- C. Dielectric Flanges: Factory-fabricated, companion-flange assembly, for 150- or 300-psig minimum working pressure as required to suit system pressures.
  - 1. Manufacturers:
    - a. Capitol Manufacturing Co.
    - b. Central Plastics Company.
    - c. Epco Sales, Inc.
    - d. Watts Industries, Inc.; Water Products Div.
- D. Dielectric-Flange Kits: Companion-flange assembly for field assembly. Include flanges, full-face- or ring-type neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.
  - 1. Manufacturers:
    - a. Advance Products & Systems, Inc.
    - b. Calpico, Inc.
    - c. Central Plastics Company.
    - d. Pipeline Seal and Insulator, Inc.
  - 2. Separate companion flanges and steel bolts and nuts shall have 150- or 300-psig minimum working pressure where required to suit system pressures.

E. Dielectric Couplings: Galvanized-steel coupling with inert and noncorrosive, thermoplastic lining; threaded ends; and 300-psig minimum working pressure at 225 deg F.

1. Manufacturers:

- a. Calpico, Inc.
- b. Lochinvar Corp.

F. Dielectric Nipples: Electroplated steel nipple with inert and noncorrosive, thermoplastic lining; plain, threaded, or grooved ends; and 300-psig minimum working pressure at 225 deg F.

1. Manufacturers:

- a. Perfection Corp.
- b. Precision Plumbing Products, Inc.
- c. Sioux Chief Manufacturing Co., Inc.
- d. Victaulic Co. of America.

## 2.6 GROUT

A. Description: ASTM C 1107, Grade B, nonshrink and nonmetallic, dry hydraulic-cement grout.

- 1. Characteristics: Post-hardening, volume-adjusting, nonstaining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
- 2. Design Mix: 5000-psi, 28-day compressive strength.
- 3. Packaging: Premixed and factory packaged.

## PART 3 - EXECUTION

### 3.1 SEISMIC REQUIREMENTS

- A. Comply with SEI/ASCE 7 and with requirements for seismic seismic-restraint devices in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."

### 3.2 PIPING SYSTEMS - COMMON REQUIREMENTS

- A. Install piping according to the following requirements and Division 22 Sections specifying piping systems.
- B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.

- C. Install piping in concealed locations, unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- F. Install piping to permit valve servicing.
- G. Install piping at indicated slopes.
- H. Install piping free of sags and bends.
- I. Install fittings for changes in direction and branch connections.
- J. Install piping to allow application of insulation.
- K. Select system components with pressure rating equal to or greater than system operating pressure.
- L. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Refer to Division 07 Section "Penetration Firestopping" for materials.
- M. Verify final equipment locations for roughing-in.
- N. Refer to equipment specifications in other Sections of these Specifications for roughing-in requirements.

### 3.3 PIPING JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 22 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.
- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8.

- F. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- G. Welded Joints: Construct joints according to AWS D10.12, using qualified processes and welding operators according to Part 1 "Quality Assurance" Article.
- H. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.

### 3.4 PIPING CONNECTIONS

- A. Make connections according to the following, unless otherwise indicated:
  - 1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
  - 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.
  - 3. Wet Piping Systems: Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.

### 3.5 EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- A. Install equipment to allow maximum possible headroom unless specific mounting heights are not indicated.
- B. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.
- C. Install plumbing equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
- D. Install equipment to allow right of way for piping installed at required slope.

### 3.6 PAINTING

- A. Painting of plumbing systems, equipment, and components is specified in Division 09 Sections "Interior Painting" and "Exterior Painting."
- B. Damage and Touchup: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.



### 3.7 CONCRETE BASES

- A. Concrete Bases: Anchor equipment to concrete base according to equipment manufacturer's written instructions and according to seismic codes at Project.
  - 1. Construct concrete bases of dimensions indicated, but not less than 4 inches larger in both directions than supported unit.
  - 2. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of the base.
  - 3. Install epoxy-coated anchor bolts for supported equipment that extend through concrete base, and anchor into structural concrete floor.
  - 4. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
  - 5. Install anchor bolts to elevations required for proper attachment to supported equipment.
  - 6. Install anchor bolts according to anchor-bolt manufacturer's written instructions.

### 3.8 ERECTION OF METAL SUPPORTS AND ANCHORAGES

- A. Refer to Division 05 Section "Metal Fabrications" for structural steel.
- B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor plumbing materials and equipment.
- C. Field Welding: Comply with AWS D1.1.

### 3.9 ERECTION OF WOOD SUPPORTS AND ANCHORAGES

- A. Cut, fit, and place wood grounds, nailers, blocking, and anchorages to support, and anchor plumbing materials and equipment.
- B. Select fastener sizes that will not penetrate members if opposite side will be exposed to view or will receive finish materials. Tighten connections between members. Install fasteners without splitting wood members.
- C. Attach to substrates as required to support applied loads.

### 3.10 GROUTING

- A. Mix and install grout for plumbing equipment base bearing surfaces, pump and other equipment base plates, and anchors.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms as required for placement of grout.
- D. Avoid air entrapment during placement of grout.

- E. Place grout, completely filling equipment bases.
- F. Place grout on concrete bases and provide smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout.

3.11 CROSS OVER LADDER

- A. All piping at walking level that must be crossed for equipment maintenance and service shall have a cross-over ladder.

END OF SECTION 22 0500

## SECTION 22 0517 - SLEEVES AND SLEEVE SEALS FOR PLUMBING PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Sleeves.
  - 2. Sleeve-seal systems.
  - 3. Grout.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

### PART 2 - PRODUCTS

#### 2.1 SLEEVES

- A. Cast-Iron Wall Pipes: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.
- B. Galvanized-Steel Wall Pipes: ASTM A 53, Schedule 40, with plain ends and welded steel collar; zinc coated.
- C. Galvanized-Steel-Pipe Sleeves: ASTM A 53, Type E, Grade B, Schedule 40, zinc coated, with plain ends.
- D. PVC-Pipe Sleeves: ASTM D 1785, Schedule 40.
- E. Galvanized-Steel-Sheet Sleeves: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.

#### 2.2 SLEEVE-SEAL SYSTEMS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Advance Products & Systems, Inc.
2. CALPICO, Inc.
3. Link-Seal
4. Metraflex Company (The).
5. Pipeline Seal and Insulator, Inc.
6. Proco Products, Inc.
7. Hilti, cast in place system

B. Description: Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.

1. Sealing Elements: EPDM-rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
2. Pressure Plates: Carbon steel.
3. Connecting Bolts and Nuts: Carbon steel, with corrosion-resistant coating, of length required to secure pressure plates to sealing elements.

## 2.3 GROUT

- A. Standard: ASTM C 1107, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- B. Characteristics: Nonshrink; recommended for interior and exterior applications.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

## PART 3 - EXECUTION

### 3.1 SLEEVE INSTALLATION

- A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.
- B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide 1-inch annular clear space between piping and concrete slabs and walls.
  1. Sleeves are not required for core-drilled holes.
- C. Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed.
  1. Permanent sleeves are not required for holes in slabs formed by molded-PE or -PP sleeves.
  2. Cut sleeves to length for mounting flush with both surfaces.

- a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.
3. Using grout, seal the space outside of sleeves in slabs and walls without sleeve-seal system.
- D. Install sleeves for pipes passing through interior partitions.
  1. Cut sleeves to length for mounting flush with both surfaces.
  2. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
  3. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint. Comply with requirements for sealants specified in Division 07 Section "Joint Sealants."
  4. For sound-rated partitions, fill the opening between sleeve and piping with insulation prior to sealing.
- E. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements for firestopping specified in Division 07 Section "Penetration Firestopping."

### 3.2 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building.
- B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

### 3.3 SLEEVE AND SLEEVE-SEAL SCHEDULE

- A. Use sleeves and sleeve seals for the following piping-penetration applications:
  1. Exterior Concrete Walls above Grade:
    - a. Piping Smaller Than NPS 6: Cast-iron wall sleeves.
    - b. Piping NPS 6 and Larger: Cast-iron wall sleeves.
  2. Exterior Concrete Walls below Grade:
    - a. Piping Smaller Than NPS 6: Cast-iron wall sleeves with sleeve-seal system.
      - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.

- b. Piping NPS 6 and Larger: Cast-iron wall sleeves with sleeve-seal system.
    - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
- 3. Concrete Slabs-on-Grade:
  - a. Piping Smaller Than NPS 6: Cast-iron wall sleeves with sleeve-seal system.
    - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
  - b. Piping NPS 6 and Larger: Cast-iron wall sleeves with sleeve-seal system.
    - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
- 4. Concrete Slabs above Grade:
  - a. Piping Smaller Than NPS 6: Galvanized-steel-pipe sleeves.
  - b. Piping NPS 6 and Larger: Galvanized-steel-pipe sleeves.
- 5. Interior Partitions:
  - a. Piping Smaller Than NPS 6: Galvanized-steel-pipe sleeves.
  - b. Piping NPS 6 and Larger: Galvanized-steel-sheet sleeves.

END OF SECTION 22 0517

## SECTION 22 0518 - ESCUTCHEONS FOR PLUMBING PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Escutcheons.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

### PART 2 - PRODUCTS

#### 2.1 ESCUTCHEONS

- A. One-Piece, Cast-Brass Type: With polished, chrome-plated finish and setscrew fastener.
- B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with chrome-plated finish and spring-clip fasteners.
- C. One-Piece, Stamped-Steel Type: With chrome-plated finish and spring-clip fasteners.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.
- B. Install escutcheons with ID to 2 inch (50mm), tube, and insulation of insulated piping and with OD that completely covers opening.
  - 1. Escutcheons for New Piping:

- a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type with polished, chrome-plated finish.
- b. Chrome-Plated Piping: One-piece, cast-brass type with polished, chrome-plated finish.
- c. Insulated Piping: One-piece, stamped-steel type with chrome-plated finish.
- d. Bare Piping 2 inch and Smaller at Wall and Floor Penetrations in Finished Spaces: One-piece, cast-brass type with polished, chrome-plated finish.
- e. Bare Piping Larger than 2 inch at Wall and Floor Penetrations in Finished Spaces: One-piece, stamped-steel type with polished, chrome-plated finish.
- f. Bare Piping 2 inch and Smaller at Ceiling Penetrations in Finished Spaces: One-piece, cast-brass type with polished, chrome-plated finish.
- g. Bare Piping Larger than 2 inch at Ceiling Penetrations in Finished Spaces: One-piece, stamped-steel type with polished, chrome-plated finish.
- h. Bare Piping 2 inch and Smaller in Unfinished Service Spaces: One-piece, cast-brass type with polished, chrome-plated or rough-brass finish.
- i. Bare Piping Larger than 2 inch in Unfinished Service Spaces: One-piece, stamped-steel type with polished, chrome-plated finish.
- j. Bare Piping 2 inch and Smaller in Equipment Rooms: One-piece, cast-brass type with polished, chrome-plated or rough-brass finish.
- k. Bare Piping in Equipment Rooms Larger than 2 inch: One-piece, stamped-steel type with chrome- or cadmium-plated finish.

### 3.2 FIELD QUALITY CONTROL

- A. Replace broken and damaged escutcheons and floor plates using new materials.

END OF SECTION 22 0518



## SECTION 22 0519 - METERS AND GAGES FOR PLUMBING PIPING

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Section Includes:

1. Bimetallic-actuated thermometers.
2. Liquid-in-glass thermometers.
3. Thermowells.
4. Dial-type pressure gages.
5. Gage attachments.

#### 1.2 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

#### 1.3 INFORMATIONAL SUBMITTALS

- A. Product certificates.

#### 1.4 CLOSEOUT SUBMITTALS

- A. Operation and maintenance data.

### PART 2 - PRODUCTS

#### 2.1 BIMETALLIC-ACTUATED THERMOMETERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Ashcroft Inc.
2. Ernst Flow Industries.
3. Marsh Bellofram.
4. Miljoco Corporation.
5. Nanmac Corporation.
6. Noshok.
7. Palmer Wahl Instrumentation Group.
8. REOTEMP Instrument Corporation.
9. Tel-Tru Manufacturing Company.
10. Trerice, H. O. Co.
11. Watts Regulator Co.; a div. of Watts Water Technologies, Inc.

12. Weiss Instruments, Inc.
  13. WIKA Instrument Corporation - USA.
  14. Winters Instruments - U.S.
  15. Weksler
- B. Standard: ASME B40.200.
- C. Case: Liquid-filled and sealed type(s); stainless steel with 5 inch nominal diameter.
- D. Dial: Nonreflective aluminum with permanently etched scale markings and scales in deg F and deg C.
- E. Connector Type(s): Union joint, adjustable angle, with unified-inch screw threads.
- F. Connector Size: 1/2 inch, with ASME B1.1 screw threads.
- G. Stem: 0.25 or 0.375 inch in diameter; stainless steel.
- H. Window: Plain glass or plastic.
- I. Ring: Stainless steel.
- J. Element: Bimetal coil.
- K. Pointer: Dark-colored metal.
- L. Accuracy: Plus or minus 1 percent of scale range.

## 2.2 LIQUID-IN-GLASS THERMOMETERS

- A. Metal-Case, Industrial-Style, Liquid-in-Glass Thermometers:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following
    - a. Flo Fab Inc.
    - b. Miljoco Corporation.
    - c. Palmer Wahl Instrumentation Group.
    - d. Tel-Tru Manufacturing Company.
    - e. Trerice, H. O. Co.
    - f. Weiss Instruments, Inc.
    - g. Winters Instruments - U.S.
    - h. Weksler
  2. Standard: ASME B40.200.
  3. Case: Cast aluminum 7-inch nominal size unless otherwise indicated.
  4. Case Form: Adjustable angle unless otherwise indicated.
  5. Tube: Glass with magnifying lens and blue or red organic liquid.

6. Tube Background: Nonreflective aluminum with permanently etched scale markings graduated in deg F and deg C.
7. Window: Glass or plastic.
8. Stem: Aluminum and of length to suit installation.
  - a. Design for Thermowell Installation: Bare stem.
9. Connector: 1-1/4 inches, with ASME B1.1 screw threads.
10. Accuracy: Plus or minus 1 percent of scale range or one scale division, to a maximum of 1.5 percent of scale range.

## 2.3 THERMOWELLS

### A. Thermowells:

1. Standard: ASME B40.200.
2. Description: Pressure-tight, socket-type fitting made for insertion into piping tee fitting.
3. Material for Use with Copper Tubing: CNR or CUNI.
4. Material for Use with Steel Piping: CRES.
5. Type: Stepped shank unless straight or tapered shank is indicated.
6. External Threads: NPS 1/2, ASME B1.20.1 pipe threads.
7. Internal Threads: 1/2, with ASME B1.1 screw threads.
8. Bore: Diameter required to match thermometer bulb or stem.
9. Insertion Length: Length required to match thermometer bulb or stem.
10. Lagging Extension: Include on thermowells for insulated piping and tubing.
11. Bushings: For converting size of thermowell's internal screw thread to size of thermometer connection.

### B. Heat-Transfer Medium: Mixture of graphite and glycerin.

### C. Description: Pressure-tight, socket-type metal fitting made for insertion into piping and of type, diameter, and length required to hold thermometer.

## 2.4 PRESSURE GAGES

### A. Direct-Mounted, Metal-Case, Dial-Type Pressure Gages:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following
  - a. AMETEK, Inc.; U.S. Gauge.
  - b. Ashcroft Inc.
  - c. Ernst Flow Industries.
  - d. Flo Fab Inc.
  - e. Marsh Bellofram.
  - f. Miljoco Corporation.
  - g. Noshok.
  - h. Palmer Wahl Instrumentation Group.

- i. REOTEMP Instrument Corporation.
  - j. Tel-Tru Manufacturing Company.
  - k. Trerice, H. O. Co.
  - l. Watts Regulator Co.; a div. of Watts Water Technologies, Inc.
  - m. Weiss Instruments, Inc.
  - n. WIKA Instrument Corporation - USA.
  - o. Winters Instruments - U.S.
  - p. Weksler
- 2. Standard: ASME B40.100.
  - 3. Case: Liquid-filled Open-front, pressure relief type(s); cast aluminum or drawn steel; 4-1/2-inch nominal diameter.
  - 4. Pressure-Element Assembly: Bourdon tube unless otherwise indicated.
  - 5. Pressure Connection: Brass, with NPS 1/4 or NPS 1/2, ASME B1.20.1 pipe threads and bottom-outlet type unless back-outlet type is indicated.
  - 6. Movement: Mechanical, with link to pressure element and connection to pointer.
  - 7. Dial: Nonreflective aluminum with permanently etched scale markings graduated in psi and kPa.
  - 8. Pointer: Dark-colored metal.
  - 9. Window: Glass or plastic.
  - 10. Ring: Metal or Brass.
  - 11. Accuracy: Grade A, plus or minus 1 percent of middle half of scale range.

## 2.5 GAGE ATTACH TEST PLUGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Flow Design, Inc.
  - 2. MG Piping Products Co.
  - 3. National Meter, Inc.
  - 4. Peterson Equipment Co., Inc.
  - 5. Sisco Manufacturing Co.
  - 6. Trerice, H. O. Co.
  - 7. Weksler.
  - 8. Watts Industries, Inc.; Water Products Div.
- B. Description: Corrosion-resistant brass or stainless-steel body with core inserts and gasketed and threaded cap, with extended stem for units to be installed in insulated piping.
- C. Minimum Pressure and Temperature Rating: 500 psig at 200 deg F.
- D. Core Inserts: One or two self-sealing rubber valves.
  - 1. Insert material for water service at 20 to 200 deg F shall be CR.
  - 2. Insert material for water service at minus 30 to plus 275 deg F shall be EPDM.

- E. Test Kit: Furnish one test kit(s) containing one pressure gage and adaptor, one thermometer, and carrying case. Pressure gage, adapter probes, and thermometer sensing elements shall be of diameter to fit test plugs and of length to project into piping.
  - 1. Pressure Gage: Small bourdon-tube insertion type with 2- to 3-inch- diameter dial and probe. Dial range shall be 0 to 200 psig.
  - 2. Low-Range Thermometer: Small bimetallic insertion type with 1- to 2-inch- diameter dial and tapered-end sensing element. Dial ranges shall be 25 to 125 deg F.
  - 3. High-Range Thermometer: Small bimetallic insertion type with 1- to 2-inch- diameter dial and tapered-end sensing element. Dial ranges shall be 0 to 220 deg F.
  - 4. Carrying case shall have formed instrument padding.

## 2.6 ATTACHMENTS

- A. Snubbers: ASME B40.100, brass; with NPS 1/4 or NPS 1/2, ASME B1.20.1 pipe threads and piston porous-metal-type surge-dampening device. Include extension for use on insulated piping.
- B. Valves: Brass or stainless-steel needle, with NPS 1/4 or NPS 1/2, ASME B1.20.1 pipe threads.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install thermowells with socket extending a minimum of 2 inches into fluid one-third of pipe diameter to center of pipe and in vertical position in piping tees.
- B. Install thermowells of sizes required to match thermometer connectors. Include bushings if required to match sizes.
- C. Install thermowells with extension on insulated piping.
- D. Fill thermowells with heat-transfer medium.
- E. Install direct-mounted thermometers in thermowells and adjust vertical and tilted positions.
- F. Install direct-mounted pressure gages in piping tees with pressure gage located on pipe at the most readable position.
- G. Install valve and snubber in piping for each pressure gage for fluids.
- H. Install thermometers in the following locations:
  - 1. Inlet and outlet of each water heater.
  - 2. Inlets and outlets of each domestic water heat exchanger.
  - 3. Inlet and outlet of each domestic hot-water storage tank.
  - 4. Inlet and outlet of each remote domestic water chiller.

- I. Install pressure gages in the following locations:
  - 1. Building water service entrance into building.
  - 2. Inlet and outlet of each pressure-reducing valve.
  - 3. Suction and discharge of each domestic water pump.
- J. Install meters and gages adjacent to machines and equipment to allow service and maintenance of meters, gages, machines, and equipment.
- K. Adjust faces of meters and gages to proper angle for best visibility.
- L. Install remote-mounting dial thermometers on panel, with tubing connecting panel and thermometer bulb supported to prevent kinks. Use minimum tubing length.
- M. Install test plugs in tees in piping.
- N. Install permanent indicator on walls or brackets in accessible and readable positions.

### 3.2 THERMOMETER SCHEDULE

- A. Thermometers at inlet and outlet of each domestic water heater shall be one of the following:
  - 1. Liquid-filled Sealed, bimetallic-actuated type.
  - 2. Industrial-style, liquid-in-glass type.
- B. Thermometers at inlets and outlets of each domestic water heat exchanger shall be one of the following:
  - 1. Liquid-filled Sealed, bimetallic-actuated type.
  - 2. Industrial-style, liquid-in-glass type.
- C. Thermometers at inlet and outlet of each domestic hot-water storage tank shall be one of the following:
  - 1. Liquid-filled Sealed, bimetallic-actuated type.
  - 2. Industrial-style, liquid-in-glass type.
- D. Thermometer stems shall be of length to match thermowell insertion length.

### 3.3 THERMOMETER SCALE-RANGE SCHEDULE

- A. Scale Range for Domestic Cold-Water Piping: 0 to 150 deg F and minus 20 to plus 70 deg C.
- B. Scale Range for Domestic Hot-Water Piping: 20 to 240 deg F and 0 to 150 deg C.

### 3.4 PRESSURE-GAGE SCHEDULE

- A. Pressure gages at discharge of each water service into building shall be one of the following:

1. Liquid-filled Sealed Open-front, pressure-relief, direct-mounted, metal case.
- B. Pressure gages at inlet and outlet of each water pressure-reducing valve shall be one of the following:
  1. Liquid-filled Sealed Open-front, pressure-relief, direct mounted, metal case.
- C. Pressure gages at suction and discharge of each domestic water pump shall be one of the following:
  1. Liquid-filled Sealed Open-front, pressure-relief, direct-mounted, metal case.

### 3.5 PRESSURE-GAGE SCALE-RANGE SCHEDULE

- A. Scale Range for Water Service Piping 0 to 160 psi and 0 to 1100 kPa.
- B. Scale Range for Domestic Water Piping: 0 to 160 psi and 0 to 1100 kPa.

END OF SECTION 22 0519

## SECTION 22 0523 - GENERAL-DUTY VALVES FOR PLUMBING PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

##### A. Section Includes:

1. Bronze angle valves.
2. Bronze ball valves.
3. Iron, single-flange butterfly valves.
4. High performance butterfly valves.
5. Bronze lift check valves.
6. Bronze swing check valves.
7. Iron swing check valves.
8. Iron swing check valves with closure control.
9. Iron, center-guided check valves.
10. Iron, plate-type check valves.
11. Bronze gate valves.
12. Bronze globe valves.
13. Iron globe valves.
14. Chainwheels.

##### B. Related Sections:

1. Division 22 plumbing piping Sections for specialty valves applicable to those Sections only.
2. Division 22 Section "Identification for Plumbing Piping and Equipment" for valve tags and schedules.
3. Division 33 water distribution piping Sections for general-duty and specialty valves for site construction piping.

#### 1.3 DEFINITIONS

- A. CWP: Cold working pressure.
- B. EPDM: Ethylene propylene copolymer rubber.
- C. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.
- D. NRS: Nonrising stem.



E. OS&Y: Outside screw and yoke.

F. RS: Rising stem.

G. SWP: Steam working pressure.

#### 1.4 SUBMITTALS

A. Product Data: For each type of valve indicated.

#### 1.5 QUALITY ASSURANCE

A. Source Limitations for Valves: Obtain each type of valve from single source from single manufacturer.

B. ASME Compliance:

1. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
2. ASME B31.1 for power piping valves.
3. ASME B31.9 for building services piping valves.

C. NSF Compliance: NSF 61 for valve materials for potable-water service.

#### 1.6 DELIVERY, STORAGE, AND HANDLING

A. Prepare valves for shipping as follows:

1. Protect internal parts against rust and corrosion.
2. Protect threads, flange faces, grooves, and weld ends.
3. Set angle, gate, and globe valves closed to prevent rattling.
4. Set ball and plug valves open to minimize exposure of functional surfaces.
5. Set butterfly valves closed or slightly open.
6. Block check valves in either closed or open position.

B. Use the following precautions during storage:

1. Maintain valve end protection.
2. Store valves indoors and maintain at higher than ambient dew point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.

C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.

## PART 2 - PRODUCTS

### 2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Refer to valve schedule articles for applications of valves.
- B. Valve Pressure and Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- C. Valve Sizes: Same as upstream piping unless otherwise indicated.
- D. Valve Actuator Types:
  - 1. Gear Actuator: For quarter-turn valves NPS 8 and larger.
  - 2. Handwheel: For valves other than quarter-turn types.
  - 3. Handlever: For quarter-turn valves NPS 6 and smaller except plug valves.
  - 4. Wrench: For plug valves with square heads. Furnish Owner with 1 wrench for every 5 plug valves, for each size square plug-valve head.
  - 5. Chainwheel: Device for attachment to valve handwheel, stem, or other actuator; of size and with chain for mounting height, as indicated in the "Valve Installation" Article.
- E. Valves in Insulated Piping: With 2-inch stem extensions and the following features:
  - 1. Gate Valves: With rising stem.
  - 2. Ball Valves: With extended operating handle of non-thermal-conductive material, and protective sleeve that allows operation of valve without breaking the vapor seal or disturbing insulation.
  - 3. Butterfly Valves: With extended neck.
- F. Valve-End Connections:
  - 1. Flanged: With flanges according to ASME B16.1 for iron valves.
  - 2. Grooved: With grooves according to AWWA C606.
  - 3. Solder Joint: With sockets according to ASME B16.18.
  - 4. Threaded: With threads according to ASME B1.20.1.
- G. Valve Bypass and Drain Connections: MSS SP-45.

### 2.2 BRONZE ANGLE VALVES

- A. Class 125, Bronze Angle Valves with Bronze Disc:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Hammond Valve.
    - b. Milwaukee Valve Company.

2. Description:

- a. Standard: MSS SP-80, Type 1.
- b. CWP Rating: 200 psig.
- c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
- d. Ends: Threaded.
- e. Stem and Disc: Bronze.
- f. Packing: Asbestos free.
- g. Handwheel: Malleable iron, bronze, or aluminum.

2.3 BRONZE BALL VALVES

A. Two-Piece, Full-Port, Bronze Ball Valves with Bronze Trim:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Valve, Inc.
  - b. Conbraco Industries, Inc.; Apollo Valves.
  - c. Crane Co.; Crane Valve Group; Crane Valves.
  - d. Hammond Valve.
  - e. Lance Valves; a division of Advanced Thermal Systems, Inc.
  - f. Milwaukee Valve Company.
  - g. NIBCO INC.
  - h. Red-White Valve Corporation.
  - i. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
- 2. Description:
  - a. Standard: MSS SP-110.
  - b. SWP Rating: 150 psig.
  - c. CWP Rating: 600 psig.
  - d. Body Design: Two piece.
  - e. Body Material: Bronze.
  - f. Ends: Threaded.
  - g. Seats: PTFE.
  - h. Stem: Bronze.
  - i. Ball: Chrome-plated brass.
  - j. Port: Full.
  - k. Class: 250

B. Two-Piece, Full-Port, Bronze Ball Valves with Stainless-Steel Trim:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Conbraco Industries, Inc.; Apollo Valves.
  - b. Crane Co.; Crane Valve Group; Crane Valves.
  - c. Hammond Valve.

- d. Lance Valves; a division of Advanced Thermal Systems, Inc.
- e. Milwaukee Valve Company.
- f. NIBCO INC.
- g. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-110.
- b. SWP Rating: 150 psig.
- c. CWP Rating: 600 psig.
- d. Body Design: Two piece.
- e. Body Material: Bronze.
- f. Ends: Threaded.
- g. Seats: PTFE.
- h. Stem: Stainless steel.
- i. Ball: Stainless steel, vented.
- j. Port: Full.
- k. Class: 250

C. Three-Piece, Full-Port, Bronze Ball Valves with Bronze Trim:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Conbraco Industries, Inc.; Apollo Valves.
- b. DynaQuip Controls.
- c. Hammond Valve.
- d. Milwaukee Valve Company.
- e. NIBCO INC.
- f. Red-White Valve Corporation.

2. Description:

- a. Standard: MSS SP-110.
- b. SWP Rating: 150 psig.
- c. CWP Rating: 600 psig.
- d. Body Design: Three piece.
- e. Body Material: Bronze.
- f. Ends: Threaded.
- g. Seats: PTFE.
- h. Stem: Bronze.
- i. Ball: Chrome-plated brass.
- j. Port: Full.
- k. Class: 250

D. Three-Piece, Full-Port, Bronze Ball Valves with Stainless-Steel Trim:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Conbraco Industries, Inc.; Apollo Valves.
- b. Hammond Valve.
- c. Milwaukee Valve Company.
- d. NIBCO INC.

2. Description:

- a. Standard: MSS SP-110.
- b. SWP Rating: 150 psig.
- c. CWP Rating: 600 psig.
- d. Body Design: Three piece.
- e. Body Material: Bronze.
- f. Ends: Threaded.
- g. Seats: PTFE.
- h. Stem: Stainless steel.
- i. Ball: Stainless steel, vented.
- j. Port: Full.
- k. Class: 250

2.4 IRON, SINGLE-FLANGE BUTTERFLY VALVES

A. 200 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Aluminum-Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. ABZ Valve and Controls; a division of ABZ Manufacturing, Inc.
- b. Conbraco Industries, Inc.; Apollo Valves.
- c. Cooper Cameron Valves; a division of Cooper Cameron Corporation.
- d. Crane Co.; Crane Valve Group; Jenkins Valves.
- e. Crane Co.; Crane Valve Group; Stockham Division.
- f. DeZurik Water Controls.
- g. Flo Fab Inc.
- h. Hammond Valve.
- i. Kitz Corporation.
- j. Milwaukee Valve Company.
- k. NIBCO INC.
- l. Norriseal; a Dover Corporation company.
- m. Red-White Valve Corporation.
- n. Spence Strainers International; a division of CIRCOR International, Inc.
- o. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-67, Type I.
- b. CWP Rating: 200 psig.
- c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.

- d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
- e. Seat: EPDM.
- f. Stem: One- or two-piece stainless steel.
- g. Disc: Aluminum bronze.

B. 200 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Ductile-Iron Disc:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. ABZ Valve and Controls; a division of ABZ Manufacturing, Inc.
- b. American Valve, Inc.
- c. Conbraco Industries, Inc.; Apollo Valves.
- d. Cooper Cameron Valves; a division of Cooper Cameron Corporation.
- e. Crane Co.; Crane Valve Group; Center Line.
- f. Crane Co.; Crane Valve Group; Stockham Division.
- g. DeZurik Water Controls.
- h. Flo Fab Inc.
- i. Hammond Valve.
- j. Kitz Corporation.
- k. Milwaukee Valve Company.
- l. Mueller Steam Specialty; a division of SPX Corporation.
- m. NIBCO INC.
- n. Norriseal; a Dover Corporation company.
- o. Spence Strainers International; a division of CIRCOR International, Inc.
- p. Sure Flow Equipment Inc.
- q. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-67, Type I.
- b. CWP Rating: 200 psig.
- c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
- d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
- e. Seat: EPDM.
- f. Stem: One- or two-piece stainless steel.
- g. Disc: Nickel-plated or -coated ductile iron.

C. 200 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Stainless-Steel Disc:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the:

- a. ABZ Valve and Controls; a division of ABZ Manufacturing, Inc.
- b. American Valve, Inc.
- c. Conbraco Industries, Inc.; Apollo Valves.
- d. Cooper Cameron Valves; a division of Cooper Cameron Corporation.
- e. Crane Co.; Crane Valve Group; Jenkins Valves.
- f. Crane Co.; Crane Valve Group; Stockham Division.

- g. DeZurik Water Controls.
- h. Flo Fab Inc.
- i. Hammond Valve.
- j. Kitz Corporation.
- k. Milwaukee Valve Company.
- l. Mueller Steam Specialty; a division of SPX Corporation.
- m. NIBCO INC.
- n. Norriseal; a Dover Corporation company.
- o. Red-White Valve Corporation.
- p. Spence Strainers International; a division of CIRCOR International, Inc.
- q. Sure Flow Equipment Inc.
- r. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-67, Type I.
- b. CWP Rating: 200 psig.
- c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
- d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
- e. Seat: EPDM.
- f. Stem: One- or two-piece stainless steel.
- g. Disc: Stainless steel.

2.5 HIGH PERFORMANCE BUTTERFLY VALVES

A. 200 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Aluminum-Bronze Disc:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Apollo Valves.
- 2. Description:
  - a. Standard: MSS SP-67, Type I.
  - b. CWP Rating: 200 psig.
  - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
  - d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
  - e. Seat: EPDM.
  - f. Stem: One- or two-piece stainless steel.
  - g. Disc: Aluminum bronze.

2.6 BRONZE LIFT CHECK VALVES

A. Class 125, Lift Check Valves with Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Crane Co.; Crane Valve Group; Crane Valves.
  - b. Crane Co.; Crane Valve Group; Jenkins Valves.
  - c. Crane Co.; Crane Valve Group; Stockham Division.
2. Description:
  - a. Standard: MSS SP-80, Type 1.
  - b. CWP Rating: 200 psig.
  - c. Body Design: Vertical flow.
  - d. Body Material: ASTM B 61 or ASTM B 62, bronze.
  - e. Ends: Threaded.
  - f. Disc: Bronze.

## 2.7 BRONZE SWING CHECK VALVES

### A. Class 125, Bronze Swing Check Valves with Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Valve, Inc.
  - b. Crane Co.; Crane Valve Group; Crane Valves.
  - c. Crane Co.; Crane Valve Group; Jenkins Valves.
  - d. Crane Co.; Crane Valve Group; Stockham Division.
  - e. Hammond Valve.
  - f. Kitz Corporation.
  - g. Milwaukee Valve Company.
  - h. NIBCO INC.
  - i. Powell Valves.
  - j. Red-White Valve Corporation.
  - k. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
  - l. Zy-Tech Global Industries, Inc.
2. Description:
  - a. Standard: MSS SP-80, Type 3.
  - b. CWP Rating: 200 psig.
  - c. Body Design: Horizontal flow, Y pattern.
  - d. Body Material: ASTM B 62, bronze.
  - e. Ends: Threaded.
  - f. Disc: Bronze.

### B. Class 150, Bronze Swing Check Valves with Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:



- a. American Valve, Inc.
- b. Crane Co.; Crane Valve Group; Crane Valves.
- c. Crane Co.; Crane Valve Group; Jenkins Valves.
- d. Crane Co.; Crane Valve Group; Stockham Division.
- e. Kitz Corporation.
- f. Milwaukee Valve Company.
- g. NIBCO INC.
- h. Red-White Valve Corporation.
- i. Zy-Tech Global Industries, Inc.

2. Description:

- a. Standard: MSS SP-80, Type 3.
- b. CWP Rating: 300 psig.
- c. Body Design: Horizontal flow.
- d. Body Material: ASTM B 62, bronze.
- e. Ends: Threaded.
- f. Disc: Bronze.

2.8 IRON SWING CHECK VALVES

A. Class 250, Iron Swing Check Valves with Metal Seats:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Crane Co.; Crane Valve Group; Crane Valves.
- b. Crane Co.; Crane Valve Group; Jenkins Valves.
- c. Crane Co.; Crane Valve Group; Stockham Division.
- d. Hammond Valve.
- e. Milwaukee Valve Company.
- f. NIBCO INC.
- g. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-71, Type I.
- b. CWP Rating: 500 psig.
- c. Body Design: Clear or full waterway.
- d. Body Material: ASTM A 126, gray iron with bolted bonnet.
- e. Ends: Flanged.
- f. Trim: Bronze.
- g. Gasket: Asbestos free.

2.9 IRON SWING CHECK VALVES WITH CLOSURE CONTROL

A. Class 125, Iron Swing Check Valves with Lever- and Spring-Closure Control:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. NIBCO INC.
2. Description:
  - a. Standard: MSS SP-71, Type I.
  - b. CWP Rating: 200 psig.
  - c. Body Design: Clear or full waterway.
  - d. Body Material: ASTM A 126, gray iron with bolted bonnet.
  - e. Ends: Flanged.
  - f. Trim: Bronze.
  - g. Gasket: Asbestos free.
  - h. Closure Control: Factory-installed, exterior lever and spring.

## 2.10 IRON, CENTER-GUIDED CHECK VALVES

### A. Class 250, Iron, Compact-Wafer, Center-Guided Check Valves with Metal Seat:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. APCO Willamette Valve and Primer Corporation.
  - b. Crispin Valve.
  - c. DFT Inc.
  - d. Flo Fab Inc.
  - e. Hammond Valve.
  - f. Metraflex, Inc.
  - g. Milwaukee Valve Company.
  - h. NIBCO INC.
  - i. Sure Flow Equipment Inc.
  - j. Val-Matic Valve & Manufacturing Corp.
2. Description:
  - a. Standard: MSS SP-125.
  - b. CWP Rating: 400 psig.
  - c. Body Material: ASTM A 126, gray iron.
  - d. Style: Compact wafer, spring loaded.
  - e. Seat: Bronze.

### B. Class 300, Iron, Compact-Wafer, Center-Guided Check Valves with Metal Seat:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. APCO Willamette Valve and Primer Corporation.
  - b. Crispin Valve.

- c. Val-Matic Valve & Manufacturing Corp.

2. Description:

- a. Standard: MSS SP-125.
- b. CWP Rating: 500 psig.
- c. Body Material: ASTM A 395/A 395M or ASTM A 536, ductile iron.
- d. Style: Compact wafer, spring loaded.
- e. Seat: Bronze.

2.11 IRON, PLATE-TYPE CHECK VALVES

A. Class 250, Iron, Dual-Plate Check Valves with Metal Seat:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. APCO Willamette Valve and Primer Corporation.
  - b. Crane Co.; Crane Valve Group; Crane Valves.
- 2. Description:
  - a. Standard: API 594.
  - b. CWP Rating: 400 psig.
  - c. Body Design: Wafer, spring-loaded plates.
  - d. Body Material: ASTM A 126, gray iron.
  - e. Seat: Bronze.

B. Class 300, Iron, Dual-Plate Check Valves with Metal Seat:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. APCO Willamette Valve and Primer Corporation.
  - b. Crane Co.; Crane Valve Group; Crane Valves.
  - c. Mueller Steam Specialty; a division of SPX Corporation.
  - d. Val-Matic Valve & Manufacturing Corp.
- 2. Description:
  - a. Standard: API 594.
  - b. CWP Rating: 500 psig.
  - c. Body Design: Wafer, spring-loaded plates.
  - d. Body Material: ASTM A 395/A 395M or ASTM A 536, ductile iron.
  - e. Seat: Bronze.

C. Class 250, Iron, Dual-Plate Check Valves with Resilient Seat:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. APCO Willamette Valve and Primer Corporation.
  - b. Crane Co.; Crane Valve Group; Crane Valves.
  - c. Sure Flow Equipment Inc.
2. Description:
  - a. Standard: API 594.
  - b. CWP Rating: 400 psig.
  - c. Body Design: Wafer, spring-loaded plates.
  - d. Body Material: ASTM A 126, gray iron.
  - e. Seat: EPDM or NBR.

D. Class 300, Iron, Dual-Plate Check Valves with Resilient Seat:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. APCO Willamette Valve and Primer Corporation.
  - b. Val-Matic Valve & Manufacturing Corp.
2. Description:
  - a. Standard: API 594.
  - b. CWP Rating: 500 psig.
  - c. Body Design: Wafer, spring-loaded plates.
  - d. Body Material: ASTM A 395/A 395M or ASTM A 536, ductile iron.
  - e. Seat: EPDM or NBR.

2.12 BRONZE GLOBE VALVES

A. Class 125, Bronze Globe Valves with Bronze Disc:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Crane Co.; Crane Valve Group; Crane Valves.
  - b. Crane Co.; Crane Valve Group; Stockham Division.
  - c. Hammond Valve.
  - d. Kitz Corporation.
  - e. Milwaukee Valve Company.
  - f. NIBCO INC.
  - g. Powell Valves.
  - h. Red-White Valve Corporation.
  - i. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
  - j. Zy-Tech Global Industries, Inc.
  - k. Conbraco

- l. Apollo
2. Description:
  - a. Standard: MSS SP-80, Type 1.
  - b. CWP Rating: 200 psig.
  - c. Body Material: ASTM B 62, bronze with integral seat and screw-in bonnet.
  - d. Ends: Threaded or solder joint.
  - e. Stem and Disc: Bronze.
  - f. Packing: Asbestos free.
  - g. Handwheel: Malleable iron, bronze, or aluminum.

## 2.13 IRON GLOBE VALVES

### A. Class 125, Iron Globe Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Crane Co.; Crane Valve Group; Crane Valves.
  - b. Crane Co.; Crane Valve Group; Jenkins Valves.
  - c. Crane Co.; Crane Valve Group; Stockham Division.
  - d. Hammond Valve.
  - e. Kitz Corporation.
  - f. Milwaukee Valve Company.
  - g. NIBCO INC.
  - h. Powell Valves.
  - i. Red-White Valve Corporation.
  - j. Watts Regulator Co.; a division of Watts Water Technologies, Inc.
  - k. Zy-Tech Global Industries, Inc.
  - l. Conbraco
  - m. Apollo
2. Description:
  - a. Standard: MSS SP-85, Type I.
  - b. CWP Rating: 200 psig.
  - c. Body Material: ASTM A 126, gray iron with bolted bonnet.
  - d. Ends: Flanged.
  - e. Trim: Bronze.
  - f. Packing and Gasket: Asbestos free.

### B. Class 250, Iron Globe Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Crane Co.; Crane Valve Group; Crane Valves.
  - b. Crane Co.; Crane Valve Group; Jenkins Valves.

- c. Crane Co.; Crane Valve Group; Stockham Division.
- d. Hammond Valve.
- e. Milwaukee Valve Company.
- f. NIBCO INC.
- g. Watts Regulator Co.; a division of Watts Water Technologies, Inc.

2. Description:

- a. Standard: MSS SP-85, Type I.
- b. CWP Rating: 500 psig.
- c. Body Material: ASTM A 126, gray iron with bolted bonnet.
- d. Ends: Flanged.
- e. Trim: Bronze.
- f. Packing and Gasket: Asbestos free.

2.14 CHAINWHEELS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- 1. Babbitt Steam Specialty Co.
- 2. Roto Hammer Industries.
- 3. Trumbull Industries.

B. Description: Valve actuation assembly with sprocket rim, brackets, and chain.

- 1. Brackets: Type, number, size, and fasteners required to mount actuator on valve.
- 2. Attachment: For connection to ball butterfly and plug valve stems.
- 3. Sprocket Rim with Chain Guides: Aluminum, of type and size required for valve.
- 4. Chain: Hot-dip, galvanized steel, of size required to fit sprocket rim.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- B. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.
- C. Examine threads on valve and mating pipe for form and cleanliness.
- D. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.

- E. Do not attempt to repair defective valves; replace with new valves.

### 3.2 VALVE INSTALLATION

- A. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- B. Locate valves for easy access and provide separate support where necessary.
- C. Install valves in horizontal piping with stem at or above center of pipe.
- D. Install valves in position to allow full stem movement.
- E. Install chainwheels on operators for ball butterfly gate globe and plug valves NPS 4 and larger and more than 96 inches above floor. Extend chains to 60 inches above finished floor.
- F. Install check valves for proper direction of flow and as follows:
  - 1. Swing Check Valves: In horizontal position with hinge pin level.
  - 2. Center-Guided and Plate-Type Check Valves: In horizontal or vertical position, between flanges.
  - 3. Lift Check Valves: With stem upright and plumb.

### 3.3 ADJUSTING

- A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

### 3.4 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. If valve applications are not indicated, use the following:
  - 1. Shutoff Service: Ball or butterfly valves.
  - 2. Butterfly Valve Dead-End Service: Single-flange (lug) type.
  - 3. Throttling Service Globe, angle, ball or butterfly valves.
  - 4. Pump-Discharge Check Valves:
    - a. NPS 2 and Smaller: Bronze swing check valves with bronze disc.
    - b. NPS 2-1/2 and Larger for Domestic Water: Iron swing check valves with lever and weight or with spring or iron, center-guided, metal or resilient-seat check valves.
    - c. NPS 2-1/2 and Larger for Sanitary Waste and Storm Drainage: Iron swing check valves with lever and weight or spring.
- B. If valves with specified SWP classes or CWP ratings are not available, the same types of valves with higher SWP classes or CWP ratings may be substituted.
- C. Select valves, except wafer types, with the following end connections:

1. For Copper Tubing, NPS 2 and Smaller: Threaded ends except where solder-joint valve-end option is indicated in valve schedules below.
2. For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
3. For Copper Tubing, NPS 5 and Larger: Flanged ends.
4. For Steel Piping, NPS 2 and Smaller: Threaded ends.
5. For Steel Piping, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
6. For Steel Piping, NPS 5 and Larger: Flanged ends.

### 3.5 LOW-PRESSURE, COMPRESSED-AIR VALVE SCHEDULE (150 PSIG OR LESS)

#### A. Pipe NPS 2 and Smaller:

1. Bronze Valves: May be provided with solder-joint ends instead of threaded ends.
2. Ball Valves: One, Two, or Three piece, full, regular or reduced port, with brass, bronze or stainless-steel trim.
3. Bronze Lift Check Valves: Class 125, bronze disc.
4. Bronze Swing Check Valves: Class 125, bronze disc.

#### B. Pipe NPS 2-1/2 and Larger:

1. Iron Valves, NPS 2-1/2 to NPS 4: May be provided with threaded ends instead of flanged ends.
2. Iron, Single-Flange Butterfly Valves: 200 CWP, NBR seat, aluminum-bronze, ductile-iron or stainless-steel disc.
3. Iron Swing Check Valves: Class 125, metal seats.
4. Iron, Center-Guided Check Valves: Class 125, globe, metal seat.
5. Iron, Plate-Type Check Valves: Class 125; dual plate; metal seat.

### 3.6 DOMESTIC, HOT- AND COLD-WATER VALVE SCHEDULE

#### A. Pipe NPS 2 and Smaller:

1. Bronze Valves: May be provided with solder-joint ends instead of threaded ends.
2. Bronze Angle Valves: Class 125 or Class 150, bronze disc.
3. Ball Valves: One, Two or Three piece, full, bronze with bronze or stainless-steel trim.
4. Bronze Swing Check Valves: Class 125 or Class 150, bronze disc.
5. Bronze Globe Valves: Class 125 or Class 150, bronze disc.

#### B. Pipe NPS 2-1/2 and Larger:

1. Iron Valves, NPS 2-1/2 to NPS 4: May be provided with threaded ends instead of flanged ends.
2. Ball Valves: One, Two or Three piece, full or, regular port, bronze with bronze or stainless-steel trim.
3. Iron, Single-Flange Butterfly Valves: 200 CWP, EPDM seat, aluminum-bronze, ductile-iron or stainless-steel disc.



4. Iron Swing Check Valves: Class 125 or Class 250, metal seats.
5. Iron Swing Check Valves with Closure Control: Class 125, lever and spring weight.
6. Iron, Center-Guided Check Valves: Class 125, Class 150, Class 250 or Class 300, compact-wafer, metal seat.
7. Iron, Plate-Type Check Valves: Class 125, Class 150, Class 250 or Class 300; single plate; metal seat.
8. Iron Globe Valves: Class 125 or Class 250.

END OF SECTION 22 0523

## SECTION 22 0529 - HANGERS AND SUPPORTS FOR PLUMBING PIPING AND EQUIPMENT

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following hangers and supports for plumbing system piping and equipment:
  - 1. Steel pipe hangers and supports.
  - 2. Trapeze pipe hangers.
  - 3. Metal framing systems.
  - 4. Thermal-hanger shield inserts.
  - 5. Fastener systems.
  - 6. Pipe stands.
  - 7. Pipe positioning systems.
  - 8. Equipment supports.
- B. Related Sections include the following:
  - 1. Division 05 Section "Metal Fabrications" for structural-steel shapes and plates for trapeze hangers for pipe and equipment supports.
  - 2. Division 21 Section "Water-Based Fire-Suppression Systems" for pipe hangers for fire-suppression piping.
  - 3. Division 22 Section "Expansion Fittings and Loops for Plumbing Piping" for pipe guides and anchors.
  - 4. Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment" for vibration isolation devices.

#### 1.3 DEFINITIONS

- A. MSS: Manufacturers Standardization Society for The Valve and Fittings Industry Inc.
- B. Terminology: As defined in MSS SP-90, "Guidelines on Terminology for Pipe Hangers and Supports."

#### 1.4 PERFORMANCE REQUIREMENTS

- A. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.

- B. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
- C. Seismic Performance: Plumbing equipment, hangers and supports shall withstand the effects of earthquake motions determined according to SEI/ASCE 7 and with the requirements specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
  - 1. For components with a seismic importance factor of 1.0 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified."
  - 2. For components with a seismic importance factor of 1.5 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified and the system will be fully operational after the seismic event."

## 1.5 SUBMITTALS

- A. Product Data: For the following:
  - 1. Steel pipe hangers and supports.
  - 2. Thermal-hanger shield inserts.
  - 3. Powder-actuated fastener systems.
  - 4. Pipe positioning systems.
  - 5. Mechanical Anchors: ICC-ES Evaluation Reports validating 'Cracked Concrete' testing per A.C. 193 must be provided for anchors resisting seismic loads and/or supporting life-safety systems including fire sprinkler systems.
- B. Shop Drawings: Signed and sealed by a qualified professional engineer. Show fabrication and installation details and include calculations for the following:
  - 1. Trapeze pipe hangers. Include Product Data for components.
  - 2. Metal framing systems. Include Product Data for components.
  - 3. Pipe stands. Include Product Data for components.
  - 4. Equipment supports.
- C. Welding certificates.
- D. Delegated-Design Submittal:
  - 1. Design calculations and detailed fabrication and assembly of pipe anchors and alignment guides, hangers and supports for multiple pipes, expansion joints and loops, and attachments of the same to the building structure.
  - 2. Locations of pipe anchors and alignment guides and expansion joints and loops.
  - 3. Locations of and details for penetrations, including sleeves and sleeve seals for exterior walls, floors, basement, and foundation walls.
  - 4. Seismic calculations and detailed analysis: Indicate fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events.

Indicate association with vibration isolation devices. Project specific design documentation and calculations shall be prepared and stamped by a registered professional engineer who is responsible for the seismic restraint design and who is licensed in the state where the project is being constructed (ASCE 7, 13.2.1.1).

## 1.6 QUALITY ASSURANCE

- A. Welding: Qualify procedures and personnel according to AWS D1.1, "Structural Welding Code--Steel.", AWS D1.4, "Structural Welding Code--Reinforcing Steel." and ASME Boiler and Pressure Vessel Code: Section IX.
- B. Welding: Qualify procedures and personnel according to the following:
  - 1. AWS D1.1, "Structural Welding Code--Steel."
  - 2. AWS D1.2, "Structural Welding Code--Aluminum."
  - 3. AWS D1.4, "Structural Welding Code--Reinforcing Steel."
  - 4. ASME Boiler and Pressure Vessel Code: Section IX.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

### 2.2 STEEL PIPE HANGERS AND SUPPORTS

- A. Description: MSS SP-58, Types 1 through 58, factory-fabricated components. Refer to Part 3 "Hanger and Support Applications" Article for where to use specific hanger and support types.
- B. Manufacturers:
  - 1. Anvil International.
  - 2. AAA Technology & Specialties Co., Inc.
  - 3. Bergen-Power Pipe Supports.
  - 4. B-Line Systems, Inc.; a division of Cooper Industries.
  - 5. Carpenter & Paterson, Inc.
  - 6. Empire Industries, Inc.
  - 7. ERICO/Michigan Hanger Co.
  - 8. Globe Pipe Hanger Products, Inc.
  - 9. Grinnell Corp.
  - 10. GS Metals Corp.

11. National Pipe Hanger Corporation.
12. PHD Manufacturing, Inc.
13. PHS Industries, Inc.
14. Piping Technology & Products, Inc.
15. Tolco Inc.
16. Simpson Strong-Tie Co.

C. Galvanized, Metallic Coatings: Pregalvanized or hot dipped.

D. Nonmetallic Coatings: Plastic coating, jacket, or liner.

E. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion for support of bearing surface of piping.

## 2.3 TRAPEZE PIPE HANGERS

A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural-steel shapes with MSS SP-58 hanger rods, nuts, saddles, and U-bolts.

## 2.4 METAL FRAMING SYSTEMS

A. Description: MFMA-3, shop- or field-fabricated pipe-support assembly made of steel channels and other components.

B. Manufacturers:

1. Anvil International.
2. B-Line Systems, Inc.; a division of Cooper Industries.
3. ERICO/Michigan Hanger Co.; ERISTRUT Div.
4. GS Metals Corp.
5. Hilti, Inc.
6. Power-Strut Div.; Tyco International, Ltd.
7. Thomas & Betts Corporation.
8. Tolco Inc.
9. Unistrut Corp.; Tyco International, Ltd.

C. Coatings: Manufacturer's standard finish unless bare metal surfaces are indicated.

D. Nonmetallic Coatings: Plastic coating, jacket, or liner.

## 2.5 THERMAL-HANGER SHIELD INSERTS

A. Description: 100-psig- minimum, compressive-strength insulation insert encased in sheet metal shield.

B. Manufacturers:

1. Carpenter & Paterson, Inc.
  2. ERICO/Michigan Hanger Co.
  3. PHS Industries, Inc.
  4. Pipe Shields, Inc.
  5. Rilco Manufacturing Company, Inc.
  6. Value Engineered Products, Inc.
- C. Insulation-Insert Material for Cold Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate with vapor barrier.
- D. Insulation-Insert Material for Hot Piping: Water-repellent treated, ASTM C 533, Type I calcium silicate.
- E. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- F. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- G. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

## 2.6 FASTENER SYSTEMS

- A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
1. Manufacturers:
    - a. Hilti, Inc.
    - b. MKT Fastening, LLC.
    - c. Powers Fasteners.
    - d. Simpson Strong-Tie Co.
- B. Mechanical-Expansion Anchors and Concrete Screws: Insert-wedge-type stainless steel, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used. For anchors resisting seismic loads and/or supporting life- safety systems including fire sprinkler systems, Anchors shall have been tested for 'Cracked Concrete' per A.C. 193 per a valid ICC-ES Evaluation Report. Manufacturers with these anchors have been designated below with: '\*'
1. Manufacturers:
    - a. B-Line Systems, Inc.; a division of Cooper Industries.
    - b. Empire Industries, Inc.
    - c. Hilti, Inc.
    - d. ITW Ramset/Red Head.
    - e. MKT Fastening, LLC.
    - f. Powers Fasteners.
    - g. Simpson Strong-Tie Co. \*

## 2.7 PIPE STAND FABRICATION

- A. Pipe Stands, General: Shop or field-fabricated assemblies made of manufactured corrosion-resistant components to support roof-mounted piping.
- B. Compact Pipe Stand: One-piece plastic unit with integral-rod-roller, pipe clamps, or V-shaped cradle to support pipe, for roof installation without membrane penetration.
  - 1. Manufacturers:
    - a. Anvil International.
    - b. ERICO/Michigan Hanger Co.
    - c. MIRO Industries.
    - d. Unipure
- C. Low-Type, Single-Pipe Stand: One-piece stainless-steel base unit with plastic roller, for roof installation without membrane penetration.
  - 1. Manufacturers:
    - a. MIRO Industries.
- D. High-Type, Single-Pipe Stand: Assembly of base, vertical and horizontal members, and pipe support, for roof installation without membrane penetration.
  - 1. Manufacturers:
    - a. Anvil International.
    - b. ERICO/Michigan Hanger Co.
    - c. MIRO Industries.
    - d. Portable Pipe Hangers.
  - 2. Base: Stainless steel.
  - 3. Vertical Members: Two or more cadmium-plated-steel or stainless-steel, continuous-thread rods.
  - 4. Horizontal Member: Cadmium-plated-steel or stainless-steel rod with plastic or stainless-steel, roller-type pipe support.
- E. High-Type, Multiple-Pipe Stand: Assembly of bases, vertical and horizontal members, and pipe supports, for roof installation without membrane penetration.
  - 1. Manufacturers:
    - a. Anvil International.
    - b. Portable Pipe Hangers.
  - 2. Bases: One or more plastic.
  - 3. Vertical Members: Two or more protective-coated-steel channels.
  - 4. Horizontal Member: Protective-coated-steel channel.
  - 5. Pipe Supports: Galvanized-steel, clevis-type pipe hangers.

- F. Curb-Mounting-Type Pipe Stands: Shop- or field-fabricated pipe support made from structural-steel shape, continuous-thread rods, and rollers for mounting on permanent stationary roof curb.

## 2.8 PIPE POSITIONING SYSTEMS

- A. Description: IAPMO PS 42, system of metal brackets, clips, and straps for positioning piping in pipe spaces for plumbing fixtures for commercial applications.
- B. Manufacturers:
  - 1. C & S Mfg. Corp.
  - 2. HOLDRITE Corp.; Hubbard Enterprises.
  - 3. Samco Stamping, Inc.

## 2.9 EQUIPMENT SUPPORTS

- A. Description: Welded, shop- or field-fabricated equipment support made from structural-steel shapes.

## 2.10 MISCELLANEOUS MATERIALS

- A. Structural Steel: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
  - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
  - 2. Design Mix: 5000-psi, 28-day compressive strength.

## PART 3 - EXECUTION

### 3.1 HANGER AND SUPPORT APPLICATIONS

- A. Specific hanger and support requirements are specified in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-69 for pipe hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized, metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.



- E. Use padded hangers for piping that is subject to scratching.
- F. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated stationary pipes, NPS 1/2 to NPS 30.
  - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of 120 to 450 deg F pipes, NPS 4 to NPS 16, requiring up to 4 inches of insulation.
  - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes, NPS 3/4 to NPS 24, requiring clamp flexibility and up to 4 inches of insulation.
  - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes, NPS 1/2 to NPS 24, if little or no insulation is required.
  - 5. Pipe Hangers (MSS Type 5): For suspension of pipes, NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
  - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated stationary pipes, NPS 3/4 to NPS 8.
  - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 8.
  - 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 8.
  - 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated stationary pipes, NPS 1/2 to NPS 2.
  - 10. Split Pipe-Ring with or without Turnbuckle-Adjustment Hangers (MSS Type 11): For suspension of noninsulated stationary pipes, NPS 3/8 to NPS 8.
  - 11. Extension Hinged or 2-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated stationary pipes, NPS 3/8 to NPS 3.
  - 12. U-Bolts (MSS Type 24): For support of heavy pipes, NPS 1/2 to NPS 30.
  - 13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
  - 14. Pipe Saddle Supports (MSS Type 36): For support of pipes, NPS 4 to NPS 36, with steel pipe base stanchion support and cast-iron floor flange.
  - 15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes, NPS 4 to NPS 36, with steel pipe base stanchion support and cast-iron floor flange and with U-bolt to retain pipe.
  - 16. Adjustable, Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes, NPS 2-1/2 to NPS 36, if vertical adjustment is required, with steel pipe base stanchion support and cast-iron floor flange.
  - 17. Single Pipe Rolls (MSS Type 41): For suspension of pipes, NPS 1 to NPS 30, from 2 rods if longitudinal movement caused by expansion and contraction might occur.
  - 18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes, NPS 2-1/2 to NPS 20, from single rod if horizontal movement caused by expansion and contraction might occur.
  - 19. Complete Pipe Rolls (MSS Type 44): For support of pipes, NPS 2 to NPS 42, if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
  - 20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes, NPS 2 to NPS 24, if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.

21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes, NPS 2 to NPS 30, if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- G. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers, NPS 3/4 to NPS 20.
  2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers, NPS 3/4 to NPS 20, if longer ends are required for riser clamps.
- H. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
  2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
  3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
  4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
  5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- I. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel or Malleable Concrete Inserts (MSS Type 18 or Simpson Blue Banger Concrete insert with UL & FM approvals): For upper attachment to suspend pipe hangers from concrete ceiling.
  2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction to attach to top flange of structural shape.
  3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
  4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
  5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
  6. C-Clamps (MSS Type 23): For structural shapes.
  7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
  8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
  9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
  10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
  11. Malleable Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
  12. Welded-Steel Brackets: For support of pipes from below, or for suspending from above by using clip and rod. Use one of the following for indicated loads:
    - a. Light (MSS Type 31): 750 lb.
    - b. Medium (MSS Type 32): 1500 lb.

- c. Heavy (MSS Type 33): 3000 lb.
- 13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
- 14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
- 15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- J. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Steel Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
  - 2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
  - 3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- K. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
  - 2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
  - 3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41 roll hanger with springs.
  - 4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.
  - 5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from hanger.
  - 6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from base support.
  - 7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to absorb expansion and contraction of piping system from trapeze support.
  - 8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
    - a. Horizontal (MSS Type 54): Mounted horizontally.
    - b. Vertical (MSS Type 55): Mounted vertically.
    - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- L. Comply with MSS SP-69 for trapeze pipe hanger selections and applications that are not specified in piping system Sections.
- M. Comply with MFMA-102 for metal framing system selections and applications that are not specified in piping system Sections.

- N. Use powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where required in concrete construction.
- O. Use pipe positioning systems in pipe spaces behind plumbing fixtures to support supply and waste piping for plumbing fixtures.

### 3.2 HANGER AND SUPPORT INSTALLATION

- A. Comply with SEI/ASCE 7 and with requirements for seismic-restraint devices in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- B. Steel Pipe Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from building structure.
- C. Trapeze Pipe Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping and support together on field-fabricated trapeze pipe hangers.
  - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified above for individual pipe hangers.
  - 2. Field fabricate from ASTM A 36/A 36M, steel shapes selected for loads being supported. Weld steel according to AWS D1.1.
- D. Metal Framing System Installation: Arrange for grouping of parallel runs of piping and support together on field-assembled metal framing systems.
- E. Thermal-Hanger Shield Installation: Install in pipe hanger or shield for insulated piping.
- F. Fastener System Installation:
  - 1. Install powder-actuated fasteners for use in lightweight concrete or concrete slabs less than 4 inches thick in concrete after concrete is placed and completely cured. Use operators that are licensed by powder-actuated tool manufacturer. Install fasteners according to powder-actuated tool manufacturer's operating manual. Powder actuated fasteners shall not be used for seismic bracing attachments.
  - 2. Install mechanical-expansion anchors in concrete after concrete is placed and completely cured. Install fasteners according to manufacturer's written instructions. For anchors resisting seismic loads and/or supporting life-safety systems including fire sprinkler systems, anchors shall have been tested for 'Cracked Concrete' per A.C. 193 and shall have a valid ICC-ES Evaluation Report
- G. Pipe Stand Installation:
  - 1. Pipe Stand Types except Curb-Mounting Type: Assemble components and mount on smooth roof surface. Do not penetrate roof membrane.

2. Curb-Mounting-Type Pipe Stands: Assemble components or fabricate pipe stand and mount on permanent, stationary roof curb. Refer to Division 07 Section "Roof Accessories" for curbs.
- H. Pipe Positioning System Installation: Install support devices to make rigid supply and waste piping connections to each plumbing fixture. Refer to Division 22 Section "Plumbing Fixtures" for plumbing fixtures.
- I. Install hangers and supports complete with necessary inserts, bolts, rods, nuts, washers, and other accessories.
- J. Equipment Support Installation: Fabricate from welded-structural-steel shapes.
- K. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- L. Install lateral bracing with pipe hangers and supports to prevent swaying.
- M. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- N. Load Distribution: Install hangers and supports so piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- O. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and so maximum pipe deflections allowed by ASME B31.9 (for building services piping) are not exceeded.
- P. Insulated Piping: Comply with the following:
  1. Attach clamps and spacers to piping.
    - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
    - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
    - c. Do not exceed pipe stress limits according to ASME B31.9 for building services piping.
  2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.
    - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
  3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.

- a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
4. Shield Dimensions for Pipe: Not less than the following:
  - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
  - b. NPS 4: 12 inches long and 0.06 inch thick.
  - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
  - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
  - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
5. Pipes NPS 8 and Larger: Include wood inserts.
6. Insert Material: Length at least as long as protective shield.
7. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

### 3.3 EQUIPMENT SUPPORTS

- A. Fabricate structural-steel stands to suspend equipment from structure overhead or to support equipment above floor.
- B. Grouting: Place grout under supports for equipment and make smooth bearing surface.
- C. Provide lateral bracing, to prevent swaying, for equipment supports. For applications where seismic bracing is required, 'Cracked Concrete' expansion anchors or concrete screws tested per A.C. 193 must be provided for seismic bracing anchorage where post-installed anchors are required.

### 3.4 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers and equipment supports.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1 procedures for shielded metal arc welding, appearance and quality of welds, and methods used in correcting welding work, and with the following:
  1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  2. Obtain fusion without undercut or overlap.
  3. Remove welding flux immediately.
  4. Finish welds at exposed connections so no roughness shows after finishing and contours of welded surfaces match adjacent contours.

### 3.5 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches .

### 3.6 PAINTING

- A. Touch Up: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
  - 1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils.
- B. Touch Up: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal are specified in Division 09 painting Sections.
- C. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION 22 0529

SECTION 22 0548 - VIBRATION AND SEISMIC CONTROLS FOR PLUMBING PIPING AND EQUIPMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section includes the following restraints and vibration isolation as defined in Section 230548 "Vibration Isolation and Seismic Controls for HVAC" for the following:
  - 1. Plumbing Piping.
  - 2. Plumbing Equipment.

PART 2 - PRODUCTS

2.1 (NOT USED)

PART 3 - EXECUTION

3.1 (NOT USED)

END OF SECTION



## SECTION 22 0553 - IDENTIFICATION FOR PLUMBING PIPING AND EQUIPMENT

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. Equipment labels.
  - 2. Warning signs and labels.
  - 3. Pipe labels.
  - 4. Stencils.
  - 5. Valve tags.
  - 6. Warning tags.
  - 7. Ceiling grid

#### 1.3 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Samples: For color, letter style, and graphic representation required for each identification material and device.
- C. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- D. Valve numbering scheme.
- E. Valve Schedules: For each piping system to include in maintenance manuals.

#### 1.4 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

## PART 2 - PRODUCTS

### 2.1 EQUIPMENT LABELS

#### A. Plastic Labels for Equipment:

1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.
2. Letter Color: White.
3. Background Color: Blue.
4. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
6. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
7. Fasteners: Stainless-steel rivets or self-tapping screws.
8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

#### B. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified.

#### C. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number and identify Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

### 2.2 WARNING SIGNS AND LABELS

#### A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, 1/16 inch thick, and having predrilled holes for attachment hardware.

#### B. Letter Color: Black.

#### C. Background Color: Yellow.

#### D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.

#### E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.

#### F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.

- G. Fasteners: Stainless-steel rivets or self-tapping screws.
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Label Content: Include caution and warning information, plus emergency notification instructions.

## 2.3 PIPE LABELS

- A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.
- B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to cover full circumference of pipe and to attach to pipe without fasteners or adhesive.
- C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.
- D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings, pipe size, and an arrow indicating flow direction.
  - 1. Flow-Direction Arrows: Integral with piping system service lettering to accommodate both directions, or as separate unit on each pipe label to indicate flow direction.
  - 2. Lettering Size: At least 1-1/2 inches high.

## 2.4 STENCILS

- A. Stencils: Prepared with letter sizes according to ASME A13.1 for piping; and minimum letter height of 3/4 inch for access panel and door labels, equipment labels, and similar operational instructions.
  - 1. Stencil Material: Fiberboard or metal.
  - 2. Stencil Paint: Exterior, gloss, alkyd enamel black unless otherwise indicated. Paint may be in pressurized spray-can form.
  - 3. Identification Paint: Exterior, alkyd enamel in colors according to ASME A13.1 unless otherwise indicated.

## 2.5 VALVE TAGS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
  - 1. Tag Material: Brass, 0.032-inch minimum thickness, and having predrilled or stamped holes for attachment hardware.
  - 2. Fasteners: Brass wire-link or beaded chain; or S-hook.
- B. Valve Schedules: For each piping system, on 8-1/2-by-11-inch bond paper. Tabulate valve number, piping system, system abbreviation (as shown on valve tag), location of valve (room

or space), normal-operating position (open, closed, or modulating), and variations for identification. Mark valves for emergency shutoff and similar special uses.

1. Valve-tag schedule shall be included in operation and maintenance data.

## 2.6 WARNING TAGS

- A. Warning Tags: Preprinted or partially preprinted, accident-prevention tags, of plasticized card stock with matte finish suitable for writing.
  1. Size: 3 by 5-1/4 inches minimum.
  2. Fasteners: Brass grommet and wire.
  3. Nomenclature: Large-size primary caption such as "DANGER," "CAUTION," or "DO NOT OPERATE."
  4. Color: Yellow background with black lettering.

## 2.7 CEILING GRID

- A. Provide valve identification for all plumbing and med gas valves located above the ceiling on the ceiling grid below the valve.

# PART 3 - EXECUTION

## 3.1 PREPARATION

- A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

## 3.2 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

## 3.3 PIPE LABEL INSTALLATION

- A. Piping Color-Coding: Painting of piping is specified in Division 09.
- B. Stenciled Pipe Label Option: Stenciled labels may be provided instead of manufactured pipe labels, at Installer's option. Install stenciled pipe labels, complying with ASME A13.1, on each piping system.
  1. Identification Paint: Use for contrasting background.
  2. Stencil Paint: Use for pipe marking.

C. Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:

1. Near each valve and control device.
2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
4. At access doors, manholes, and similar access points that permit view of concealed piping.
5. Near major equipment items and other points of origination and termination.
6. Spaced at maximum intervals of 25 feet along each main run. Branch piping & piping in congested areas are to have labels spaced at maximum intervals of 6 feet.
7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.
8. On hard lid ceilings where piping enters and exits the room.

D. Pipe Label Color Schedule:

1. Low-Pressure, Compressed-Air Piping:
  - a. Background Color: Comply with ASME A13.1.
  - b. Letter Color: Comply with ASME A13.1.
2. Medium-Pressure, Compressed-Air Piping:
  - a. Background Color: Comply with ASME A13.1.
  - b. Letter Color: Comply with ASME A13.1.
3. Domestic Water Piping:
  - a. Background Color: Comply with ASME A13.1.
  - b. Letter Color: Comply with ASME A13.1.
4. Sanitary Waste and Storm Drainage Piping:
  - a. Background Color: Comply with ASME A13.1.
  - b. Letter Color: Comply with ASME A13.1.

### 3.4 VALVE-TAG INSTALLATION

- A. Install tags on valves and control devices in piping systems, except check valves; valves within factory-fabricated equipment units; shutoff valves; faucets; convenience and lawn-watering hose connections; and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.
- B. Valve-Tag Application Schedule: Tag valves according to size, shape, and color scheme and with captions similar to those indicated in the following subparagraphs:
  1. Valve-Tag Size and Shape:

- a. Cold Water: 1-1/2 inches, round.
- b. Hot Water: 1-1/2 inches, round.
- c. Low-Pressure Compressed Air: 1-1/2 inches, round.
- d. High-Pressure Compressed Air: 1-1/2 inches, round.

2. Valve-Tag Color:

- a. Cold Water: Comply with ASME A13.1.
- b. Hot Water: Comply with ASME A13.1.
- c. Low-Pressure Compressed Air: Comply with ASME A13.1.
- d. High-Pressure Compressed Air: Comply with ASME A13.1.

3. Letter Color:

- a. Cold Water: Comply with ASME A13.1.
- b. Hot Water: Comply with ASME A13.1.
- c. Low-Pressure Compressed Air: Comply with ASME A13.1.
- d. High-Pressure Compressed Air: Comply with ASME A13.1.

3.5 WARNING-TAG INSTALLATION

- A. Write required message on, and attach warning tags to, equipment and other items where required.

END OF SECTION 22 0553

## SECTION 22 0719 - PLUMBING PIPING INSULATION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes insulating the following plumbing piping services:
  - 1. Domestic cold-water piping.
  - 2. Domestic hot-water piping.
  - 3. Domestic recirculating hot-water piping.
  - 4. Roof drains and rainwater leaders.
  - 5. Supplies and drains for handicap-accessible lavatories and sinks 3.1

#### 1.3 DEFINITIONS:

- A. Refer to Section 220500 "Common Work Results for Plumbing".

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory- and field-applied, if any).
- B. LEED Submittals:
  - 1. Product Data for Credit IEQ 4.1: For adhesives and sealants, documentation including printed statement of VOC content and chemical components.
  - 2. Laboratory Test Reports for Credit IEQ 4: For adhesives and sealants, documentation indicating that product complies with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- C. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
  - 1. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
  - 2. Detail attachment and covering of heat tracing inside insulation.
  - 3. Detail insulation application at pipe expansion joints for each type of insulation.

4. Detail insulation application at elbows, fittings, flanges, valves, and specialties for each type of insulation.
5. Detail removable insulation at piping specialties, equipment connections, and access panels.
6. Detail application of field-applied jackets.
7. Detail application at linkages of control devices.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.

#### 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84 by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
  1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
  2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

#### 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

#### 1.8 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment."
- B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.



- C. Coordinate installation and testing of heat tracing.

## 1.9 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

## PART 2 - PRODUCTS

### 2.1 INSULATION MATERIALS

- A. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule," "Outdoor, Aboveground Piping Insulation Schedule," and "Outdoor, Underground Piping Insulation Schedule" articles for where insulating materials shall be applied.
- B. Insulation for below-ambient service requires a vapor-barrier.
- C. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- D. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- E. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- F. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- G. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Aeroflex USA, Inc.; Aerocel.
    - b. Armacell LLC; AP Armaflex.
    - c. K-Flex USA; Insul-Lock, Insul-Tube, and K-FLEX LS.
- H. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553:
  - 1. Type II and ASTM C 1290, Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 2. Products: Subject to compliance with requirements, provide one of the following:

- a. CertainTeed Corp.; SoftTouch Duct Wrap.
- b. Johns Manville; Microlite.
- c. Knauf Insulation; Friendly Feel Duct Wrap.
- d. Manson Insulation Inc.; Alley Wrap.
- e. Owens Corning; SOFTR All-Service Duct Wrap.

I. Mineral-Fiber, Preformed Pipe Insulation:

- 1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Fibrex Insulations Inc.; Coreplus 1200.
  - b. Johns Manville; Micro-Lok.
  - c. Knauf Insulation; 1000-Degree Pipe Insulation.
  - d. Manson Insulation Inc.; Alley-K.
  - e. Owens Corning; Fiberglas Pipe Insulation.
- 2. Type I, 850 Deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A,
  - a. Without factory-applied jacket with factory-applied ASJ-SSL. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.

J. Prefabricated Thermal Insulating Fitting Covers: Comply with ASTM C 450 for dimensions used in preforming insulation to cover valves, elbows, tees, and flanges.

2.2 INSULATING CEMENTS

A. Mineral-Fiber Insulating Cement: Comply with ASTM C 195.

- 1. Products: Subject to compliance with requirements, provide the following:
  - a. Ramco Insulation, Inc.; Super-Stik.

B. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449.

- 1. Products: Subject to compliance with requirements, provide the following:
  - a. Ramco Insulation, Inc.; Ramcote 1200 and Quik-Cote.

2.3 ADHESIVES

A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated, unless otherwise indicated.

B. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.

- 1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Aeroflex USA, Inc.; AeroSeal.
  - b. Armacell LLC; Armaflex 520 Adhesive.

- c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-75.
    - d. K-Flex USA; R-373 Contact Adhesive.
  - 2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-127.
    - b. Eagle Bridges - Marathon Industries; 225.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-60/85-70.
    - d. Mon-Eco Industries, Inc.; 22-25.
  - 2. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- D. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-82.
    - b. Eagle Bridges - Marathon Industries; 225.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-20.
    - d. Mon-Eco Industries, Inc.; 22-25.
  - 2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- E. PVC Jacket Adhesive: Compatible with PVC jacket.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Dow Corning Corporation; 739, Dow Silicone.
    - b. Johns Manville; Zeston Perma-Weld, CEEL-TITE Solvent Welding Adhesive.
    - c. P.I.C. Plastics, Inc.; Welding Adhesive.
    - d. Speedline Corporation; Polyco VP Adhesive.
  - 2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

## 2.4 MASTICS

- A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.
  - 1. For indoor applications, use mastics that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below-ambient services.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 30-80/30-90.
    - b. Vimasco Corporation; 749.
  - 2. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm at 43-mil dry film thickness.
  - 3. Service Temperature Range: Minus 20 to plus 180 deg F .
  - 4. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
  - 5. Color: White.
- C. Vapor-Barrier Mastic: Solvent based; suitable for indoor use on below-ambient services.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-30.
    - b. Eagle Bridges - Marathon Industries; 501.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 30-35.
    - d. Mon-Eco Industries, Inc.; 55-10.
  - 2. Water-Vapor Permeance: ASTM F 1249, 0.05 perm at 35-mil dry film thickness.
  - 3. Service Temperature Range: 0 to 180 deg F.
  - 4. Solids Content: ASTM D 1644, 44 percent by volume and 62 percent by weight.
  - 5. Color: White.
- D. Vapor-Barrier Mastic: Solvent based; suitable for outdoor use on below-ambient services.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; Encacel.
    - b. Eagle Bridges - Marathon Industries; 570.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 60-95/60-96.
  - 2. Water-Vapor Permeance: ASTM F 1249, 0.05 perm at 30-mil dry film thickness.
  - 3. Service Temperature Range: Minus 50 to plus 220 deg F .

4. Solids Content: ASTM D 1644, 33 percent by volume and 46 percent by weight.
5. Color: White.

E. Breather Mastic: Water based; suitable for indoor and outdoor use on above-ambient services.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-10.
  - b. Eagle Bridges - Marathon Industries; 550.
  - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 46-50.
  - d. Mon-Eco Industries, Inc.; 55-50.
  - e. Vimasco Corporation; WC-1/WC-5.
2. Water-Vapor Permeance: ASTM F 1249, 1.8 perms at 0.0625-inch dry film thickness.
3. Service Temperature Range: Minus 20 to plus 180 deg F .
4. Solids Content: 60 percent by volume and 66 percent by weight.
5. Color: White.

## 2.5 SEALANTS

A. ASJ Flashing Sealants and PVC Jacket Flashing Sealants:

1. Products: Subject to compliance with requirements, provide the following:
  - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-76.
2. Materials shall be compatible with insulation materials, jackets, and substrates.
3. Fire- and water-resistant, flexible, elastomeric sealant.
4. Service Temperature Range: Minus 40 to plus 250 deg F .
5. Color: White.
6. For indoor applications, sealants shall have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

## 2.6 FACTORY-APPLIED JACKETS

A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:

1. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.

## 2.7 FIELD-APPLIED JACKETS

A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.

- B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Johns Manville; Zeston.
  - b. P.I.C. Plastics, Inc.; FG Series.
  - c. Proto Corporation; LoSmoke.
  - d. Speedline Corporation; SmokeSafe.
2. Adhesive: As recommended by jacket material manufacturer.
3. Color: PVC, white: 30 mils thick..
4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
  - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

C. Metal Jacket:

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; Metal Jacketing Systems.
  - b. ITW Insulation Systems; Aluminum and Stainless Steel Jacketing.
  - c. RPR Products, Inc.; Insul-Mate.
2. Aluminum Jacket: Comply with ASTM B 209 (ASTM B 209M), Alloy 3003, 3005, 3105, or 5005, Temper H-14.
  - a. Sheet and roll stock ready for shop or field sizing or factory cut and rolled to size.
  - b. Finish and thickness are indicated in field-applied jacket schedules.
  - c. Moisture Barrier for Indoor Applications: 1-mil- thick, heat-bonded polyethylene and kraft paper. 3-mil- thick, heat-bonded polyethylene and kraft paper.
  - d. Moisture Barrier for Outdoor Applications: 3-mil- thick, heat-bonded polyethylene and kraft paper.
  - e. Factory-Fabricated Fitting Covers:
    - 1) Same material, finish, and thickness as jacket.
    - 2) Preformed 2-piece or gore, 45- and 90-degree, short- and long-radius elbows.
    - 3) Tee covers.
    - 4) Flange and union covers.
    - 5) End caps.
    - 6) Beveled collars.
    - 7) Valve covers.
    - 8) Field fabricate fitting covers only if factory-fabricated fitting covers are not available.

## 2.8 TAPES

- A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ABI, Ideal Tape Division; 428 AWF ASJ.
    - b. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0836.
    - c. Compac Corporation; 104 and 105.
    - d. Venture Tape; 1540 CW Plus, 1542 CW Plus, and 1542 CW Plus/SQ.
  2. Width: 3 inches.
  3. Thickness: 11.5 mils.
  4. Adhesion: 90 ounces force/inch in width.
  5. Elongation: 2 percent.
  6. Tensile Strength: 40 lbf/inch in width.
  7. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.
- B. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ABI, Ideal Tape Division; 370 White PVC tape.
    - b. Compac Corporation; 130.
    - c. Venture Tape; 1506 CW NS.
  2. Width: 2 inches.
  3. Thickness: 6 mils.
  4. Adhesion: 64 ounces force/inch in width.
  5. Elongation: 500 percent.
  6. Tensile Strength: 18 lbf/inch in width.
- C. Aluminum-Foil Tape: Vapor-retarder tape with acrylic adhesive.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ABI, Ideal Tape Division; 488 AWF.
    - b. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0800.
    - c. Compac Corporation; 120.
    - d. Venture Tape; 3520 CW.
  2. Width: 2 inches.
  3. Thickness: 3.7 mils.
  4. Adhesion: 100 ounces force/inch in width.
  5. Elongation: 5 percent.
  6. Tensile Strength: 34 lbf/inch in width.

## 2.9 SECUREMENTS

- A. Staples: Outward-clinching insulation staples, nominal 3/4-inch- wide, stainless steel or Monel.

## 2.10 PROTECTIVE SHIELDING GUARDS

### A. Protective Shielding Pipe Covers:

- 1. Manufacturers: Subject to compliance with requirements provide products by one of the following:
  - a. Engineered Brass Company.
  - b. Insul-Tect Products Co.; a subsidiary of MVG Molded Products.
  - c. McGuire Manufacturing.
  - d. Plumberex.
  - e. Truebro; a brand of IPS Corporation.
  - f. Zurn Industries, LLC; Tubular Brass Plumbing Products Operation.
- 2. Description: Manufactured plastic wraps for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with Americans with Disabilities Act (ADA) requirements.

### B. Protective Shielding Piping Enclosures:

- 1. Manufacturers: Subject to compliance with requirements provide products by one of the following:
  - a. Truebro; a brand of IPS Corporation.
  - b. Zurn Industries, LLC; Tubular Brass Plumbing Products Operation.
- 2. Description: Manufactured plastic enclosure for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with ADA requirements.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
  - 1. Verify that systems to be insulated have been tested and are free of defects.
  - 2. Verify that surfaces to be insulated are clean and dry.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.



### 3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Coordinate insulation installation with the trade installing heat tracing. Comply with requirements for heat tracing that apply to insulation.
- C. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless-steel surfaces, use demineralized water.

### 3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.
- B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of pipe system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- G. Keep insulation materials dry during application and finishing.
- H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- I. Install insulation with least number of joints practical.
- J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  - 1. Install insulation continuously through hangers and around anchor attachments.
  - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
  - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.

- K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- L. Install insulation with factory-applied jackets as follows:
  - 1. Draw jacket tight and smooth.
  - 2. Cover circumferential joints with 3-inch wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
  - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at:
    - a. 2 inches o.c.
    - b. For below-ambient services, apply vapor-barrier mastic over staples.
  - 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.
- M. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- P. For above-ambient services, do not install insulation to the following:
  - 1. Vibration-control devices.
  - 2. Testing agency labels and stamps.
  - 3. Nameplates and data plates.
  - 4. Cleanouts.

### 3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.

4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.
- C. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
  1. Seal penetrations with flashing sealant.
  2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
  4. Seal jacket to wall flashing with flashing sealant.
- D. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- E. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.
  1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.
- F. Insulation Installation at Floor Penetrations:
  1. Pipe: Install insulation continuously through floor penetrations.
  2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

### 3.5 GENERAL PIPE INSULATION INSTALLATION

- A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.
- B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:
  1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
  2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
  3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt

- each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
  5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
  6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.
  7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.
  8. For services not specified to receive a field-applied jacket except for flexible install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
  9. Stencil or label the outside insulation jacket of each union with the word "union." Match size and color of pipe labels.
- C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.
- D. Install removable insulation covers at locations indicated. Installation shall conform to the following:
1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
  2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.
  3. Construct removable valve insulation covers in same manner as for flanges, except divide the two-part section on the vertical center line of valve body.
  4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe

insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.

5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

### 3.6 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

- A. Seal longitudinal seams and end joints with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- B. Insulation Installation on Pipe Flanges:
  1. Install pipe insulation to outer diameter of pipe flange.
  2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
  3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
  4. Secure insulation to flanges and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- C. Insulation Installation on Pipe Fittings and Elbows:
  1. Install mitered sections of pipe insulation.
  2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.
- D. Insulation Installation on Valves and Pipe Specialties:
  1. Install preformed valve covers manufactured of same material as pipe insulation when available.
  2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
  3. Install insulation to flanges as specified for flange insulation application.
  4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

### 3.7 INSTALLATION OF MINERAL-FIBER INSULATION

- A. Insulation Installation on Straight Pipes and Tubes:
  1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
  2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.

3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward clinched staples at 6 inches o.c.
4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch , and seal joints with flashing sealant.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
4. Install insulation to flanges as specified for flange insulation application.

### 3.8 FIELD-APPLIED JACKET INSTALLATION

- A. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints. Seal with manufacturer's recommended adhesive.
  1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.
- B. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.

### 3.9 PIPING INSULATION SCHEDULE, GENERAL

- A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.
- B. Insulation shall have a k value that meets the minimum requirements of the latest International Energy Conservation Code (IECC).
- C. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
  - 1. Drainage piping located in crawl spaces.
  - 2. Underground piping.
  - 3. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

### 3.10 INDOOR PIPING INSULATION SCHEDULE

- A. Domestic Cold Water:
  - 1. NPS 1-1/2 and Smaller: Insulation shall be one of the following:
    - a. Flexible Elastomeric:
      - 1) 1/2 inch thick
    - b. Mineral-Fiber, Preformed Pipe Insulation, Type I:
      - 1) 1/2 inch thick
  - 2. NPS 2 and Larger: Insulation shall be one of the following:
    - a. Flexible Elastomeric:
      - 1) 1/2 inches thick.
    - b. Mineral-Fiber, Preformed Pipe Insulation:
      - 1) 1/2 inches thick.
- B. Domestic Hot and Recirculated Hot Water:
  - 1. NPS 1-1/2 and Smaller: Insulation shall be the following:
    - a. Mineral-Fiber, Preformed Pipe Insulation, Type I:
      - 1) 1 inch thick.
  - 2. NPS 2 and Larger: Insulation shall be the following:
    - a. Mineral-Fiber, Preformed Pipe Insulation, Type I:
      - 1) 1-1/2 inches thick
- C. Domestic Chilled Water (Potable):
  - 1. All Pipe Sizes: Insulation shall be one of the following:

- a. Flexible Elastomeric: 1 inch thick.
    - b. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
  - D. Storm water and Overflow:
    - 1. All Pipe Sizes: Insulation shall be one of the following:
      - a. Flexible Elastomeric: 1/2 inch thick.
      - b. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1/2 inch thick.
  - E. Roof Drain and Overflow Drain Bodies:
    - 1. All Pipe Sizes: Insulation shall be one of the following:
      - a. Flexible Elastomeric: 1/2 inch thick.
      - b. Mineral-Fiber, Blanket Insulation, Type I: 1/2 inch thick.
      - c. Drain Manufacturer's Pre-formed bowl Insulation: 1/2 inch thick.
  - F. Sanitary Waste Piping Where Heat Tracing Is Installed:
    - 1. All Pipe Sizes: Insulation shall be the following:
      - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1-1/2 inches thick.
  - G. Floor Drains, Traps, and Sanitary Drain Piping within 10 Feet of Drain Receiving Condensate and Equipment Drain Water below 60 Deg F :
    - 1. All Pipe Sizes: Insulation shall be one of the following:
      - a. Flexible Elastomeric:
        - 1) 3/4 inch thick.
      - b. Mineral-Fiber, Preformed Pipe Insulation, Type I:
        - 1) 3/4 inch thick.
  - H. Hot Service Drains:
    - 1. All Pipe Sizes: Insulation shall be the following:
      - a. Mineral-Fiber, Preformed Pipe, Type I or II: 1 inch thick.
  - I. Hot Service Vents:
    - 1. All Pipe Sizes: Insulation shall be the following:
      - a. Mineral-Fiber, Preformed Pipe, Type I or II: 1 inch thick.
- 3.11 OUTDOOR, ABOVEGROUND PIPING INSULATION SCHEDULE
- A. Domestic Water Piping:



1. All Pipe Sizes: Insulation shall be one of the following:
    - a. Flexible Elastomeric: 2 inches thick.
    - b. Mineral-Fiber, Preformed Pipe Insulation, Type I: 2 inches thick.
  - B. Domestic Hot and Recirculated Hot Water:
    1. All Pipe Sizes: Insulation shall be the following:
      - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 2 inches thick.
  - C. Sanitary Waste Piping Where Heat Tracing Is Installed:
    1. All Pipe Sizes: Insulation shall be the following:
      - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 2 inches thick.
  - D. Hot Service Drains:
    1. All Pipe Sizes: Insulation shall be the following:
      - a. Mineral-Fiber, Preformed Pipe Insulation, Type I: 1 inch thick.
  - E. Hot Service Vents:
    1. All Pipe Sizes: Insulation shall be the following:
      - a. Mineral-Fiber, Preformed Pipe Insulation, Type II: 1 inch thick.
- 3.12 INDOOR, FIELD-APPLIED JACKET SCHEDULE
- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
  - B. If more than one material is listed, selection from materials listed is Contractor's option.
  - C. Piping, Concealed:
    1. None.
  - D. Piping, Exposed:
    1. PVC:
      - a. PVC, white: 30 mils thick.
- 3.13 OUTDOOR, FIELD-APPLIED JACKET SCHEDULE
- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.

B. If more than one material is listed, selection from materials listed is Contractor's option.

C. Piping, Concealed:

1. None.

D. Piping, Exposed:

1. Aluminum, Stucco Embossed: 0.016 inch thick.

3.14 UNDERGROUND, FIELD-INSTALLED INSULATION JACKET

A. For underground direct-buried piping applications, install underground direct-buried jacket over insulation material.

END OF SECTION 22 0719

## SECTION 22 1116 - DOMESTIC WATER PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Under-building-slab and aboveground domestic water pipes, tubes, and fittings inside buildings.
  - 2. Encasement for piping.

#### 1.3 SEISMIC REQUIREMENTS

- A. Seismic Performance: Pipe hangers and supports shall withstand the effects of earthquake motions determined according to SEI/ASCE 7 and with the requirements specified in Section 230548 "Vibration and Seismic Controls for HVAC."
  - 1. For piping with a seismic importance factor of 1.0 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified."
  - 2. For piping with a seismic importance factor of 1.5 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified and the system will be fully operational after the seismic event."

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For transition fittings and dielectric fittings.
- B. LEED Submittals:
  - 1. Product Data for Credit IEQ 4.1: For solvent cements and adhesive primers, documentation including printed statement of VOC content.
  - 2. Laboratory Test Reports for Credit IEQ 4: For solvent cements and adhesive primers, documentation indicating that products comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

C. Delegated-Design Submittal:

1. Design calculations and detailed fabrication and assembly of pipe anchors and alignment guides, hangers and supports for multiple pipes, expansion joints and loops, and attachments of the same to the building structure.
2. Locations of pipe anchors and alignment guides and expansion joints and loops.
3. Locations of and details for penetrations, including sleeves and sleeve seals for exterior walls, floors, basement, and foundation walls.

1.5 INFORMATIONAL SUBMITTALS

- A. System purging and disinfecting activities report.
- B. Field quality-control reports.

1.6 FIELD CONDITIONS

- A. Interruption of Existing Water Service: Do not interrupt water service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary water service according to requirements indicated:
  1. Notify Construction Manager or owner no fewer than two days in advance of proposed interruption of water service.

PART 2 - PRODUCTS

2.1 PIPING MATERIALS

- A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.
- B. Potable-water piping and components shall comply with NSF 14 and NSF 61. Plastic piping components shall be marked with "NSF-pw."
- C. All piping shall be American made and tested; no import pipe will be permitted.
- D. All exposed water supply piping in toilet rooms, custodial rooms and kitchens shall be chromium plated.
- E. All piping installed in or passing through a plenum must be plenum rated, fire wrapped, or installed in a metal conduit.

2.2 COPPER TUBE AND FITTINGS

- A. Hard Copper Tube: ASTM B 88, Type K and ASTM B 88, Type L water tube, drawn temper.

- B. Soft Copper Tube: ASTM B 88, Type K and ASTM B 88, Type L water tube, annealed temper.
- C. Cast-Copper, Solder-Joint Fittings: ASME B16.18, pressure fittings.
- D. Wrought-Copper, Solder-Joint Fittings: ASME B16.22, wrought-copper pressure fittings.
- E. Bronze Flanges: ASME B16.24, Class 150, with solder-joint ends.
- F. Copper Unions:
  - 1. MSS SP-123.
  - 2. Cast-copper-alloy, hexagonal-stock body.
  - 3. Ball-and-socket, metal-to-metal seating surfaces.
  - 4. Solder-joint or threaded ends.
- G. Appurtenances for Grooved-End Copper Tubing:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Victaulic Company.

## 2.3 PIPING JOINING MATERIALS

- A. Pipe-Flange Gasket Materials:
  - 1. AWWA C110/A21.10, rubber, flat face, 1/8 inch thick or ASME B16.21, nonmetallic and asbestos free unless otherwise indicated.
  - 2. Full-face or ring type unless otherwise indicated.
- B. Metal, Pipe-Flange Bolts and Nuts: ASME B18.2.1, carbon steel unless otherwise indicated.
- C. Solder Filler Metals: ASTM B 32, lead-free alloys.
- D. Flux: ASTM B 813, water flushable.
- E. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys for general-duty brazing unless otherwise indicated.

## 2.4 TRANSITION FITTINGS

- A. General Requirements:
  - 1. Same size as pipes to be joined.
  - 2. Pressure rating at least equal to pipes to be joined.
  - 3. End connections compatible with pipes to be joined.
- B. Fitting-Type Transition Couplings: Manufactured piping coupling or specified piping system fitting.

- C. Sleeve-Type Transition Coupling: AWWA C219.
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Cascade Waterworks Manufacturing.
    - b. Dresser, Inc.; Piping Specialties Products.
    - c. Ford Meter Box Company, Inc. (The).
    - d. JCM Industries.
    - e. Romac Industries, Inc.
    - f. Smith-Blair, Inc.; a Sensus company.
    - g. Viking Johnson.

## 2.5 DIELECTRIC FITTINGS

- A. General Requirements: Assembly of copper alloy and ferrous materials with separating nonconductive insulating material. Include end connections compatible with pipes to be joined.
- B. Dielectric Nipples and Waterways:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Elster Perfection Corporation.
    - b. Grinnell Mechanical Products; Tyco Fire Products LP.
    - c. Matco-Norca.
    - d. Clearflow/Perfection Corp.
    - e. Precision Plumbing Products, Inc.
    - f. Victaulic Company.
  - 2. Standard: IAPMO PS 66 or ASTM F-1545-97.
  - 3. Electroplated steel nipple or waterway complying with ASTM F 1545 or ANSI/NSF-61 Compliant.
  - 4. Pressure Rating and Temperature: 300 psig at 225 deg F.
  - 5. End Connections: Male threaded or grooved.
  - 6. Lining: Inert and noncorrosive, propylene or LTHS.

## PART 3 - EXECUTION

### 3.1 EARTHWORK

- A. Comply with requirements in Division 31 Section "Earth Moving" for excavating, trenching, and backfilling.

### 3.2 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of domestic water piping. Indicated locations and arrangements are used to size pipe and calculate friction

loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.

- B. Install copper tubing under building slab according to CDA's "Copper Tube Handbook."
- C. Install underground copper tube in PE encasement according to ASTM A 674 or AWWA C105/A21.5.
- D. Install shutoff valve, hose-end drain valve, strainer, pressure gage, and test tee with valve inside the building at each domestic water-service entrance. Comply with requirements for pressure gages in Division 22 Section "Meters and Gages for Plumbing Piping" and with requirements for drain valves and strainers in Division 22 Section "Domestic Water Piping Specialties."
- E. Install shutoff valve immediately upstream of each dielectric fitting.
- F. Install water-pressure-reducing valves downstream from shutoff valves. Comply with requirements for pressure-reducing valves in Division 22 Section "Domestic Water Piping Specialties."
- G. Install domestic water piping with 0.25 percent slope downward toward drain and plumb.
  - 1. Piping will be drained seasonally for freeze protection.
- H. Install seismic restraints on piping. Comply with SEI/ASCE 7 and with requirements for seismic-restraint devices in Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- I. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- J. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- K. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal, and coordinate with other services occupying that space.
- L. Install piping to permit valve servicing.
- M. Install nipples, unions, special fittings, and valves with pressure ratings the same as or higher than the system pressure rating used in applications below unless otherwise indicated.
- N. Install piping free of sags and bends.
- O. Install fittings for changes in direction and branch connections.
- P. Install unions in copper tubing at final connection to each piece of equipment, machine, and specialty.

- Q. Install pressure gages on suction and discharge piping for each plumbing pump and packaged booster pump. Comply with requirements for pressure gages in Division 22 Section "Meters and Gages for Plumbing Piping."
- R. Install thermostats in hot-water circulation piping. Comply with requirements for thermostats in Division 22 Section "Domestic Water Pumps."
- S. Install thermometers on inlet and outlet piping from each water heater. Comply with requirements for thermometers in Division 22 Section "Meters and Gages for Plumbing Piping."
- T. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Division 22 Section "Sleeves and Sleeve Seals for Plumbing Piping."
- U. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Division 22 Section "Sleeves and Sleeve Seals for Plumbing Piping."
- V. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Division 22 Section "Escutcheons for Plumbing Piping."

### 3.3 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipes, tubes, and fittings before assembly.
- C. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged.
- D. Brazed Joints for Copper Tubing: Comply with CDA's "Copper Tube Handbook," "Braze Joints" chapter.
- E. Soldered Joints for Copper Tubing: Apply ASTM B 813, water-flushable flux to end of tube. Join copper tube and fittings according to ASTM B 828 or CDA's "Copper Tube Handbook."
- F. Flanged Joints: Select appropriate asbestos-free, nonmetallic gasket material in size, type, and thickness suitable for domestic water service. Join flanges with gasket and bolts according to ASME B31.9.
- G. Joints for Dissimilar-Material Piping: Make joints using adapters compatible with materials of both piping systems.



### 3.4 TRANSITION FITTING INSTALLATION

- A. Install transition couplings at joints of dissimilar piping.
- B. Transition Fittings in Underground Domestic Water Piping:
  - 1. Fittings for NPS 1-1/2 and Smaller: Fitting-type coupling.
  - 2. Fittings for NPS 2 and Larger: Sleeve-type coupling.

### 3.5 DIELECTRIC FITTING INSTALLATION

- A. Install dielectric fittings in piping at connections of dissimilar metal piping and tubing.
- B. Dielectric Fittings for NPS 2 and Smaller: Use dielectric nipples/waterways.
- C. Dielectric Fittings for NPS 2-1/2 to NPS 4: Use dielectric nipples/waterways.
- D. Dielectric Fittings for NPS 5 and Larger: Use dielectric nipples/waterways.

### 3.6 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements for seismic-restraint devices in Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- B. Comply with requirements for pipe hanger, support products, and installation in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment."
  - 1. Vertical Piping: MSS Type 8 or 42, clamps.
  - 2. Individual, Straight, Horizontal Piping Runs:
    - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    - c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.
  - 3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
  - 4. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Support vertical piping and tubing at base and at each floor.
- D. Rod diameter may be reduced one size for double-rod hangers, to a minimum of 3/8 inch.
- E. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 3/4 and Smaller: 60 inches with 3/8-inch rod.
  - 2. NPS 1 and NPS 1-1/4: 72 inches with 3/8-inch rod.
  - 3. NPS 1-1/2 and NPS 2: 96 inches with 3/8-inch rod.
  - 4. NPS 2-1/2: 108 inches with 1/2-inch rod.

5. NPS 3 to NPS 5: 10 feet with 1/2-inch rod.
6. NPS 6: 10 feet with 5/8-inch rod.
7. NPS 8: 10 feet with 3/4-inch rod.

- F. Install supports for vertical copper tubing every 10 feet.
- G. Support piping and tubing not listed in this article according to MSS SP-69 and manufacturer's written instructions.

### 3.7 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. When installing piping adjacent to equipment and machines, allow space for service and maintenance.
- C. Connect domestic water piping to exterior water-service piping. Use transition fitting to join dissimilar piping materials.
- D. Connect domestic water piping to water-service piping with shutoff valve; extend and connect to the following:
1. Water Heaters: Cold-water inlet and hot-water outlet piping in sizes indicated, but not smaller than sizes of water heater connections.
  2. Plumbing Fixtures: Cold- and hot-water-supply piping in sizes indicated, but not smaller than that required by plumbing code. Comply with requirements for connection sizes in Division 22 plumbing fixture Sections.
  3. Equipment: Cold- and hot-water-supply piping as indicated, but not smaller than equipment connections. Provide shutoff valve and union for each connection. Use flanges instead of unions for NPS 2-1/2 and larger.

### 3.8 IDENTIFICATION

- A. Identify system components. Comply with requirements for identification materials and installation in Division 22 Section "Identification for Plumbing Piping and Equipment."
- B. Label pressure piping with system operating pressure.

### 3.9 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
1. Piping Inspections:
    - a. Do not enclose, cover, or put piping into operation until it has been inspected and approved by authorities having jurisdiction.

- b. During installation, notify authorities having jurisdiction at least one day before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction:
      - 1) Roughing-in Inspection: Arrange for inspection of piping before concealing or closing in after roughing in and before setting fixtures.
      - 2) Final Inspection: Arrange for authorities having jurisdiction to observe tests specified in "Piping Tests" Subparagraph below and to ensure compliance with requirements.
    - c. Reinspection: If authorities having jurisdiction find that piping will not pass tests or inspections, make required corrections and arrange for reinspection.
    - d. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
  - 2. Piping Tests:
    - a. Fill domestic water piping. Check components to determine that they are not air bound and that piping is full of water.
    - b. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit a separate report for each test, complete with diagram of portion of piping tested.
    - c. Leave new, altered, extended, or replaced domestic water piping uncovered and unconcealed until it has been tested and approved. Expose work that was covered or concealed before it was tested.
    - d. Cap and subject piping to static water pressure of 50 psig above operating pressure, without exceeding pressure rating of piping system materials. Isolate test source and allow it to stand for four hours. Leaks and loss in test pressure constitute defects that must be repaired.
    - e. Repair leaks and defects with new materials, and retest piping or portion thereof until satisfactory results are obtained.
    - f. Prepare reports for tests and for corrective action required.
  - B. Domestic water piping will be considered defective if it does not pass tests and inspections.
  - C. Prepare test and inspection reports.
- 3.10 ADJUSTING
- A. Perform the following adjustments before operation:
    - 1. Close drain valves, hydrants, and hose bibbs.
    - 2. Open shutoff valves to fully open position.
    - 3. Open throttling valves to proper setting.
    - 4. Adjust balancing valves in hot-water-circulation return piping to provide adequate flow.
      - a. Manually adjust ball-type balancing valves in hot-water-circulation return piping to provide hot-water flow in each branch.
      - b. Adjust calibrated balancing valves to flows indicated.

5. Remove plugs used during testing of piping and for temporary sealing of piping during installation.
6. Remove and clean strainer screens. Close drain valves and replace drain plugs.
7. Remove filter cartridges from housings and verify that cartridges are as specified for application where used and are clean and ready for use.
8. Check plumbing specialties and verify proper settings, adjustments, and operation.

### 3.11 CLEANING

#### A. Clean and disinfect potable domestic water piping as follows:

1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
2. Use purging and disinfecting procedures prescribed by authorities having jurisdiction; if methods are not prescribed, use procedures described in either AWWA C651 or AWWA C652 or follow procedures described below:
  - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
  - b. Fill and isolate system according to either of the following:
    - 1) Fill system or part thereof with water/chlorine solution with at least 50 ppm of chlorine. Isolate with valves and allow to stand for 24 hours.
    - 2) Fill system or part thereof with water/chlorine solution with at least 200 ppm of chlorine. Isolate and allow to stand for three hours.
  - c. Flush system with clean, potable water until no chlorine is in water coming from system after the standing time.
  - d. Repeat procedures if biological examination shows contamination.
  - e. Submit water samples in sterile bottles to authorities having jurisdiction.

#### B. Clean non-potable domestic water piping as follows:

1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
2. Use purging procedures prescribed by authorities having jurisdiction or; if methods are not prescribed, follow procedures described below:
  - a. Flush piping system with clean, potable water until dirty water does not appear at outlets.
  - b. Submit water samples in sterile bottles to authorities having jurisdiction. Repeat procedures if biological examination shows contamination.

#### C. Prepare and submit reports of purging and disinfecting activities. Include copies of water-sample approvals from authorities having jurisdiction.

#### D. Clean interior of domestic water piping system. Remove dirt and debris as work progresses.

### 3.12 PIPING SCHEDULE

- A. Some piping types and sizes mentioned in this section may not be used on this project.
- B. Transition and special fittings with pressure ratings at least equal to piping rating may be used in applications below unless otherwise indicated.
- C. Flanges and unions may be used for aboveground piping joints unless otherwise indicated.
- D. All exposed water supply piping in toilet rooms, custodial rooms and kitchens shall be chromium plated.
- E. Under-building-slab, domestic water, building-service piping, NPS 3 and smaller, shall be the following:
  - 1. Soft copper tube, ASTM B 88, Type K; wrought-copper, brazed joints and fittings.
- F. Under-building-slab, domestic water piping, NPS 2 and smaller, shall be the following:
  - 1. Hard copper tube, ASTM B 88, Type K; wrought-copper, brazed joints and fittings.
- G. Aboveground domestic water piping, NPS 2 and smaller, shall be the following:
  - 1. Hard copper tube, ASTM B 88, Type L; cast- copper, solder-joint fittings; and soldered joints.
- H. Aboveground domestic water piping, NPS 2-1/2 to NPS 4, shall be the following:
  - 1. Hard copper tube, ASTM B 88, Type L; cast- copper, brazed-joint fittings; and brazed joints.
  - 2. Victaulic grooved joints
- I. Aboveground domestic water piping, NPS 5 and larger, shall be the following:
  - 1. Hard copper tube, ASTM B 88, Type L; cast- copper, brazed-joint fittings; and brazed joints.
  - 2. Victaulic grooved joints

### 3.13 VALVE SCHEDULE

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
  - 1. Shutoff Duty: Use ball for piping NPS 3 and smaller. Use butterfly or ball, with flanged ends for piping NPS 4 and larger.
  - 2. Throttling Duty: Use ball valves for piping NPS 2 and smaller. Use butterfly or ball valves with flanged ends for piping NPS 2-1/2 and larger.
  - 3. Hot-Water Circulation Piping, Balancing Duty: Calibrated balancing valves.

4. Drain Duty: Hose-end drain valves.
- B. Use check valves to maintain correct direction of domestic water flow to and from equipment.

END OF SECTION 22 1116

## SECTION 22 1119 - DOMESTIC WATER PIPING SPECIALTIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following domestic water piping specialties:
  - 1. Vacuum breakers.
  - 2. Backflow preventers.
  - 3. Water pressure-reducing valves.
  - 4. Balancing valves.
  - 5. Temperature-actuated water mixing valves.
  - 6. Strainers.
  - 7. Outlet boxes.
  - 8. Hose bibbs.
  - 9. Wall hydrants.
  - 10. Drain valves.
  - 11. Water hammer arresters.
  - 12. Water meters
- B. Related Sections include the following:
  - 1. Division 22 Section "Meters and Gages for Plumbing Piping" for thermometers, pressure gages, and flow meters in domestic water piping.
  - 2. Division 22 Section "Emergency Plumbing Fixtures" for water tempering equipment.
  - 3. Division 22 Section "Pressure Water Coolers" for water filters for water coolers.

#### 1.3 PERFORMANCE REQUIREMENTS

- A. Minimum Working Pressure for Domestic Water Piping Specialties: 125 psig, unless otherwise indicated.

#### 1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Field quality-control test reports.

- D. Operation and Maintenance Data: For domestic water piping specialties to include in emergency, operation, and maintenance manuals.

## 1.5 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. NSF Compliance:
  - 1. Comply with NSF 14, "Plastics Piping Components and Related Materials," for plastic domestic water piping components.
  - 2. Comply with NSF 61, "Drinking Water System Components - Health Effects; Sections 1 through 9."

## PART 2 - PRODUCTS

### 2.1 VACUUM BREAKERS

- A. Pipe-Applied, Atmospheric-Type Vacuum Breakers:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Ames Co.
    - b. Cash Acme.
    - c. Conbraco Industries, Inc.
    - d. FEBCO; SPX Valves & Controls.
    - e. Rain Bird Corporation.
    - f. Toro Company (The); Irrigation Div.
    - g. Watts Industries, Inc.; Water Products Div.
    - h. Zurn Plumbing Products Group; Wilkins Div.
  - 2. Standard: ASSE 1001.
  - 3. Size: NPS 1/4 to NPS 3, as required to match connected piping.
  - 4. Body: Bronze.
  - 5. Inlet and Outlet Connections: Threaded.
  - 6. Finish: Chrome plated.
- B. Hose-Connection Vacuum Breakers:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Arrowhead Brass Products, Inc.
    - b. Cash Acme.



- c. Conbraco Industries, Inc.
    - d. MIFAB, Inc.
    - e. Prier Products, Inc.
    - f. Watts Industries, Inc.; Water Products Div.
    - g. Woodford Manufacturing Company.
    - h. Zurn Plumbing Products Group; Light Commercial Operation.
    - i. Zurn Plumbing Products Group; Wilkins Div.
  - 2. Standard: ASSE 1011.
  - 3. Body: Bronze, nonremovable, with manual drain.
  - 4. Outlet Connection: Garden-hose threaded complying with ASME B1.20.7.
  - 5. Finish: Chrome or nickel plated.
- C. Pressure Vacuum Breakers:
- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Ames Co.
    - b. Conbraco Industries, Inc.
    - c. FEBCO; SPX Valves & Controls.
    - d. Flomatic Corporation.
    - e. Toro Company (The); Irrigation Div.
    - f. Watts Industries, Inc.; Water Products Div.
    - g. Zurn Plumbing Products Group; Wilkins Div.
  - 2. Standard: ASSE 1020.
  - 3. Operation: Continuous-pressure applications.
  - 4. Pressure Loss: 5 psig maximum, through middle 1/3 of flow range.
  - 5. Accessories:
    - a. Valves: Ball type, on inlet and outlet.
- D. Spill-Resistant Vacuum Breakers:
- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Conbraco Industries, Inc.
    - b. Watts Industries, Inc.; Water Products Div.
  - 2. Standard: ASSE 1056.
  - 3. Operation: Continuous-pressure applications.
  - 4. Accessories:
    - a. Valves: Ball type, on inlet and outlet.

## 2.2 BACKFLOW PREVENTERS

### A. Reduced-Pressure-Principle Backflow Preventers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Ames Co.
  - b. Conbraco Industries, Inc.
  - c. FEBCO; SPX Valves & Controls.
  - d. Flomatic Corporation.
  - e. Watts Industries, Inc.; Water Products Div.
  - f. Zurn Plumbing Products Group; Wilkins Div.
2. Standard: ASSE 1013.
3. Operation: Continuous-pressure applications.
4. Pressure Loss: 12 psig maximum, through middle 1/3 of flow range.
5. Body: Bronze for NPS 2 and smaller; cast iron with interior lining complying with AWWA C550 or that is FDA approved] for NPS 2-1/2 and larger.
6. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
7. Accessories:
  - a. Valves: Ball type with threaded ends on inlet and outlet of NPS 2 and smaller; outside screw and yoke gate-type with flanged ends on inlet and outlet of NPS 2-1/2 and larger.
  - b. Air-Gap Fitting: ASME A112.1.2, matching backflow-preventer connection.

### B. Double-Check Backflow-Prevention Assemblies:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Ames Co.
  - b. Conbraco Industries, Inc.
  - c. FEBCO; SPX Valves & Controls.
  - d. Flomatic Corporation.
  - e. Watts Industries, Inc.; Water Products Div.
  - f. Zurn Plumbing Products Group; Wilkins Div.
2. Standard: ASSE 1015.
3. Operation: Continuous-pressure applications, unless otherwise indicated.
4. Pressure Loss: 5 psig maximum, through middle 1/3 of flow range.
5. Body: Bronze for NPS 2 and smaller; cast iron with interior lining complying with AWWA C550 or that is FDA approved for NPS 2-1/2 and larger.
6. End Connections: Threaded for NPS 2 and smaller; [flanged] <Insert type> for NPS 2-1/2 and larger.
7. Accessories:

- a. Valves: Ball type with threaded ends on inlet and outlet of NPS 2 and smaller; outside screw and yoke gate-type with flanged ends on inlet and outlet of NPS 2-1/2 and larger.

C. Beverage-Dispensing-Equipment Backflow Preventers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Conbraco Industries, Inc.
  - b. Watts Industries, Inc.; Water Products Div.
  - c. Zurn Plumbing Products Group; Wilkins Div.
2. Standard: ASSE 1022.
3. Operation: Continuous-pressure applications.
4. Size: NPS 1/4 or NPS 3/8.
5. Body: Stainless steel.
6. End Connections: Threaded.

D. Dual-Check-Valve Backflow Preventers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Cash Acme.
  - b. Conbraco Industries, Inc.
  - c. FEBCO; SPX Valves & Controls.
  - d. Flomatic Corporation.
  - e. Ford Meter Box Company, Inc. (The).
  - f. Honeywell Water Controls.
  - g. McDonald, A. Y. Mfg. Co.
  - h. Mueller Co.; Water Products Div.
  - i. Watts Industries, Inc.; Water Products Div.
  - j. Zurn Plumbing Products Group; Wilkins Div.
2. Standard: ASSE 1024.
3. Operation: Continuous-pressure applications.
4. Body: Bronze with union inlet.

E. Carbonated-Beverage-Dispenser, Dual-Check-Valve Backflow Preventers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Cash Acme.
  - b. Lancer Corporation.
  - c. Watts Industries, Inc.; Water Products Div.
2. Standard: ASSE 1032.
3. Operation: Continuous-pressure applications.

4. Size: NPS 1/4 or NPS 3/8.
5. Body: Stainless steel.
6. End Connections: Threaded.

## 2.3 WATER PRESSURE-REDUCING VALVES

### A. Water Regulators: (Direct Type)

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Cash Acme.
  - b. Conbraco Industries, Inc.
  - c. Honeywell Water Controls.
  - d. Watts Industries, Inc.; Water Products Div.
  - e. Zurn Plumbing Products Group; Wilkins Div.
2. Standard: ASSE 1003.
3. Pressure Rating: Class 250
4. Body: Bronze, provide chrome-plated finish if connected to chrome plated or stainless steel piping for NPS 2 and smaller; cast iron with interior lining complying with AWWA C550 or that is FDA approved for NPS 2-1/2 and NPS 3.
5. Valves for Booster Heater Water Supply: Include integral bypass.
6. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and NPS 3.

### B. Water Control Valves: (Pilot type)

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. CLA-VAL Automatic Control Valves.
  - b. Mifab Corp; Beeco.
  - c. Watts Industries, Inc.; Ames Fluid Control Systems.
  - d. Watts Industries, Inc.; Watts ACV.
  - e. Zurn Plumbing Products Group; Wilkins Div.
2. Description: Pilot-operation, diaphragm-type, single-seated main water control valve.
3. Pressure Rating: Initial working pressure of 150 psig minimum with AWWA C550 or FDA-approved, interior epoxy coating. Include small pilot-control valve, restrictor device, specialty fittings, and sensor piping.
4. Main Valve Body: Cast- or ductile-iron body with AWWA C550 or FDA-approved, interior epoxy coating; or stainless-steel body.
5. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.

## 2.4 BALANCING VALVES

### A. Copper-Alloy Calibrated Balancing Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Armstrong International, Inc.
  - b. Flo Fab Inc.
  - c. ITT Industries; Bell & Gossett Div.
  - d. NIBCO INC.
  - e. TAC Americas.
  - f. Taco, Inc.
  - g. Victaulic
  - h. Watts Industries, Inc.; Water Products Div.
  - i. Nexus
  - j. Bell & Gossett
2. Type: Ball or Y-pattern globe valve with two readout ports and memory setting indicator.
3. Body: bronze,
4. Size: Same as connected piping, but not larger than NPS 2.
5. Accessories: Meter hoses, fittings, valves, differential pressure meter, and carrying case.

B. Cast-Iron Calibrated Balancing Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Armstrong International, Inc.
  - b. Flo Fab Inc.
  - c. ITT Industries; Bell & Gossett Div.
  - d. NIBCO INC.
  - e. TAC Americas.
  - f. Watts Industries, Inc.; Water Products Div.
  - g. Nexus
  - h. Bell & Gosset
2. Type: Adjustable with Y-pattern globe valve, two readout ports, and memory-setting indicator.
3. Size: Same as connected piping, but not smaller than NPS 2-1/2.

C. Accessories: Meter hoses, fittings, valves, differential pressure meter, and carrying case.

2.5 TEMPERATURE-ACTUATED WATER MIXING VALVES

A. Water-Temperature Limiting Devices:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Acorn Engineering; Acorn Controls
  - b. Cash Acme.

- c. Conbraco Industries, Inc.
    - d. Honeywell Water Controls.
    - e. Leonard Valve Company.
    - f. Powers; a Watts Industries Co.
    - g. Symmons Industries, Inc.
    - h. Taco, Inc.
    - i. Watts Industries, Inc.; Water Products Div.
    - j. Zurn Plumbing Products Group; Wilkins Div.
  - 2. Standard: ASSE 1017.
  - 3. Pressure Rating: 125 psig.
  - 4. Type: Thermostatically controlled water mixing valve.
  - 5. Material: Bronze body with corrosion-resistant interior components.
  - 6. Connections: Threaded union inlets and outlet.
  - 7. Accessories: Check stops on hot- and cold-water supplies, and adjustable, temperature-control handle.
  - 8. Valve Finish: Rough bronze.
- B. Primary, Thermostatic, Water Mixing Valves:
- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Acorn Engineering[ Acorn Controls.
    - b. Lawler Manufacturing Company, Inc.
    - c. Leonard Valve Company.
    - d. Powers; a Watts Industries Co.
    - e. Symmons Industries, Inc.
  - 2. Standard: ASSE 1017.
  - 3. Pressure Rating: 125 psig.
  - 4. Type: Exposed-mounting, thermostatically controlled water mixing valve.
  - 5. Material: Bronze body with corrosion-resistant interior components.
  - 6. Connections: Threaded union inlets and outlet.
  - 7. Accessories: Manual temperature control, check stops on hot- and cold-water supplies, and adjustable, temperature-control handle.
  - 8. Valve Pressure Rating: 125 psig minimum, unless otherwise indicated.
  - 9. Valve Finish: Chrome plated.
  - 10. Piping Finish: Copper.
- C. Individual-Fixture, Water Tempering Valves:
- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Cash Acme.
    - b. Conbraco Industries, Inc.
    - c. Honeywell Water Controls.
    - d. Lawler Manufacturing Company, Inc.
    - e. Leonard Valve Company.

- f. Powers; a Watts Industries Co.
  - g. Watts Industries, Inc.; Water Products Div.
  - h. Zurn Plumbing Products Group; Wilkins Div.
- 2. Standard: ASSE 1070, thermostatically controlled water tempering valve.
- 3. Pressure Rating: 125 psig minimum, unless otherwise indicated.
- 4. Body: Bronze body with corrosion-resistant interior components.
- 5. Temperature Control: Adjustable.
- 6. Inlets and Outlet: Threaded.
- 7. Finish: Rough or chrome-plated bronze.

## 2.6 STRAINERS FOR DOMESTIC WATER PIPING

### A. Y-Pattern Strainers:

- 1. Pressure Rating: Class 250
- 2. Body: Bronze for NPS 2 and smaller; cast iron with interior lining complying with AWWA C550 or FDA-approved, epoxy coating and for NPS 2-1/2 and larger.
- 3. End Connections: Threaded for NPS 2 and smaller; flanged for NPS 2-1/2 and larger.
- 4. Screen: Stainless steel with round perforations, unless otherwise indicated.
- 5. Perforation Size:
  - a. Strainers NPS 2 and Smaller: 0.020 inch.
  - b. Strainers NPS 2-1/2 to NPS 4: 0.045 inch.
  - c. Strainers NPS 5 and Larger: 0.10 inch.
- 6. Drain: Factory-installed, hose-end drain valve.
- 7. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Flo Fab Inc.
  - b. ITT Industries; Bell & Gossett Div.
  - c. NIBCO INC.
  - d. TAC Americas.
  - e. Taco, Inc.
  - f. Victaulic
  - g. Watts Industries, Inc.; Water Products Div.
  - h. Nexus
  - i. Bell & Gossett

## 2.7 OUTLET BOXES

### A. Icemaker Outlet Boxes:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Acorn Engineering Company.
    - b. Guy Gray Manufacturing Co., Inc.
    - c. IPS Corporation.
    - d. LSP Products Group, Inc.
    - e. Oatey.
    - f. Plastic Oddities; a division of Diverse Corporate Technologies.
    - g. Symmons Industries, Inc.
    - h. Watts Industries, Inc.; Water Products Div.
    - i. Whitehall Manufacturing; a div. of Acorn Engineering Company.
    - j. Zurn Plumbing Products Group; Light Commercial Operation.
  2. Mounting: Recessed.
  3. Material and Finish: Enameled-steel or epoxy-painted-steel or plastic box and faceplate.
  4. Faucet: Combination, valved fitting or separate hot- and cold-water, valved fittings complying with ASME A112.18.1. Include garden-hose thread complying with ASME B1.20.7 on outlets.
  5. Supply Shutoff Fittings: NPS 1/2 gate, globe, or ball valves and NPS 1/2 copper, water tubing.
  6. Drain: NPS 2 standpipe and P-trap for direct waste connection to drainage piping.
  7. Inlet Hoses: Two 60-inch- long, rubber household clothes washer inlet hoses with female, garden-hose-thread couplings. Include rubber washers.
  8. Drain Hose: One 48-inch- long, rubber household clothes washer drain hose with hooked end.
- B. Water Outlet Boxes:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Acorn Engineering Company.
    - b. IPS Corporation.
    - c. LSP Products Group, Inc.
    - d. Oatey.
    - e. Plastic Oddities; a division of Diverse Corporate Technologies.
  2. Mounting: Recessed.
  3. Material and Finish: Enameled-steel or epoxy-painted-steel or plastic box and faceplate.
  4. Faucet: Valved fitting complying with ASME A112.18.1. Include NPS 1/2 or smaller copper tube outlet.
  5. Supply Shutoff Fitting: NPS 1/2 gate, globe, or ball valve and NPS 1/2 copper, water tubing.
- 2.8 HOSE BIBBS
- A. Hose Bibbs:
1. Standard: ASME A112.18.1 for sediment faucets.
  2. Body Material: Bronze.
  3. Seat: Bronze, replaceable.
  4. Supply Connections: NPS 1/2 or NPS 3/4 threaded or solder-joint inlet.



5. Outlet Connection: Garden-hose thread complying with ASME B1.20.7.
6. Pressure Rating: 125 psig.
7. Vacuum Breaker: Integral or field-installation, nonremovable, drainable, hose-connection vacuum breaker complying with ASSE 1011.
8. Finish for Equipment Rooms: Rough bronze, or chrome or nickel plated.
9. Finish for Service Areas: Chrome or nickel plated.
10. Finish for Finished Rooms: Chrome or nickel plated.
11. Operation for Equipment Rooms: Wheel handle or operating key.
12. Operation for Service Areas: Wheel handle.
13. Operation for Finished Rooms: Operating key.
14. Include operating key with each operating-key hose bibb.
15. Include integral wall flange with each chrome- or nickel-plated hose bibb.

## 2.9 WALL HYDRANTS

### A. Nonfreeze Wall Hydrants:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam Company.
  - b. MIFAB, Inc.
  - c. Prier Products, Inc.
  - d. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - e. Tyler Pipe; Wade Div.
  - f. Watts Drainage Products Inc.
  - g. Woodford Manufacturing Company.
  - h. Zurn Plumbing Products Group; Light Commercial Operation.
  - i. Zurn Plumbing Products Group; Specification Drainage Operation.
2. Standard: ASME A112.21.3M for concealed-outlet, self-draining wall hydrants.
3. Pressure Rating: 125 psig.
4. Operation: Loose key.
5. Casing and Operating Rod: Of length required to match wall thickness. Include wall clamp.
6. Inlet: NPS 3/4 or NPS 1.
7. Outlet: Concealed, with integral vacuum breaker and garden-hose thread complying with ASME B1.20.7.
8. Box: Deep, flush mounting with cover.
9. Box and Cover Finish: Polished nickel bronze.
10. Operating Keys: Two with each wall hydrant.

## 2.10 DRAIN VALVES

### A. Ball-Valve-Type, Hose-End Drain Valves:

1. Standard: MSS SP-110 for standard-port, two-piece ball valves.
2. Pressure Rating: 400-psig minimum CWP.

3. Size: NPS 3/4.
4. Body: Copper alloy.
5. Ball: Chrome-plated brass.
6. Seats and Seals: Replaceable.
7. Handle: Vinyl-covered steel.
8. Inlet: Threaded or solder joint.
9. Outlet: Threaded, short nipple with garden-hose thread complying with ASME B1.20.7 and cap with brass chain.

## 2.11 WATER HAMMER ARRESTERS

### A. Water Hammer Arresters:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. AMTROL, Inc.
  - b. Josam Company.
  - c. MIFAB, Inc.
  - d. PPP Inc.
  - e. Sioux Chief Manufacturing Company, Inc.
  - f. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - g. Tyler Pipe; Wade Div.
  - h. Watts Drainage Products Inc.
  - i. Zurn Plumbing Products Group; Specification Drainage Operation.
2. Standard: ASSE 1010 or PDI-WH 201.
3. Type: Metal bellows or Copper tube with piston.
4. Size: ASSE 1010, Sizes AA and A through F or PDI-WH 201, Sizes A through F.

## 2.12 WATER METERS

### A. Displacement-Type Water Meters:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. AALIANT; a Venture Measurement product line.ABB.Badger Meter, Inc.
  - b. Carlon Meter.
  - c. Mueller Co. Ltd.; a subsidiary of Mueller Water Products Inc.
  - d. Rockwell
  - e. Schlumberger Limited; Water Services.
  - f. Sensus.
2. Description:
  - a. Standard: AWWA C700.
  - b. Pressure Rating: 150-psig working pressure.

- c. Body Design: Nutating disc; totalization meter.
- d. Registration: In gallons or cubic feet as required by utility company.
- e. Case: Bronze.
- f. End Connections: Threaded.

B. Compound-Type Water Meters:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. ABB.
  - b. Badger Meter, Inc.
  - c. Master Meter, Inc.
  - d. Mueller Co. Ltd.; a subsidiary of Mueller Water Products Inc.
  - e. Rockwell
  - f. Schlumberger Limited; Water Services.
  - g. Sensus.
- 2. Description:
  - a. Standard: AWWA C702.
  - b. Pressure Rating: 150-psig working pressure.
  - c. Body Design: With integral mainline and bypass meters; totalization meter.
  - d. Registration: In gallons or cubic feet as required by utility company.
  - e. Case: Bronze.
  - f. Pipe Connections: Flanged.

- C. Remote Registration System: Direct-reading type complying with AWWA C706; modified with signal-transmitting assembly, low-voltage connecting wiring, and remote register assembly as required by utility company.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Refer to Division 22 Section "Common Work Results for Plumbing" for piping joining materials, joint construction, and basic installation requirements.
- B. Install backflow preventers in each water supply to mechanical equipment and systems and to other equipment and water systems that may be sources of contamination. Comply with authorities having jurisdiction.
  - 1. Locate backflow preventers in same room as connected equipment or system.
  - 2. Install drain for backflow preventers with atmospheric-vent drain connection with air-gap fitting, fixed air-gap fitting, or equivalent positive pipe separation of at least two pipe diameters in drain piping and pipe to floor drain. Locate air-gap device attached to or under backflow preventer. Simple air breaks are not acceptable for this application.
  - 3. Do not install bypass piping around backflow preventers.

- C. Install water control valves with inlet and outlet shutoff valves. Install pressure gages on inlet and outlet.
- D. Install balancing valves in locations where they can easily be adjusted.
- E. Install temperature-actuated water mixing valves with check stops or shutoff valves on inlets and with shutoff valve on outlet.
  - 1. Install thermometers and water regulators if specified.
  - 2. Install cabinet-type units recessed in or surface mounted on wall as specified.
- F. Install Y-pattern strainers for water on supply side of each control valve, water pressure-reducing valve, solenoid valve, and pump.
- G. Install outlet boxes recessed in wall. Install 2-by-4-inch fire-retardant-treated-wood blocking wall reinforcement between studs. Fire-retardant-treated-wood blocking is specified in Division 06 Section "Rough Carpentry."
- H. Install water hammer arresters in water piping according to PDI-WH 201.
- I. Install water meters per manufacturers requirements.
- J. Install all reducing valves in an accessible space 5 feet above finished floor.
- K. Install ball valve on strainer to allow for draining.

### 3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping and specialties.
- B. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- C. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

### 3.3 LABELING AND IDENTIFYING

- A. Equipment Nameplates and Signs: Install engraved plastic-laminate equipment nameplate or sign on or near each of the following:
  - 1. Pressure vacuum breakers.
  - 2. Reduced-pressure-principle backflow preventers.
  - 3. Double-check backflow-prevention assemblies.
  - 4. Carbonated-beverage-machine backflow preventers.
  - 5. Dual-check-valve backflow preventers.
  - 6. Water pressure-reducing valves.

7. Calibrated balancing valves.
8. Primary, thermostatic, water mixing valves.
9. Primary water tempering valves.
10. Outlet boxes.

- B. Distinguish among multiple units, inform operator of operational requirements, indicate safety and emergency precautions, and warn of hazards and improper operations, in addition to identifying unit. Nameplates and signs are specified in Division 22 Section "Identification for Plumbing Piping and Equipment."

### 3.4 FIELD QUALITY CONTROL

- A. Perform the following tests and prepare test reports:
  1. Test each backflow preventer according to authorities having jurisdiction and the device's reference standard.
- B. Remove and replace malfunctioning domestic water piping specialties and retest as specified above.

### 3.5 ADJUSTING

- A. Set field-adjustable pressure set points of water pressure-reducing valves.
- B. Set field-adjustable flow set points of balancing valves.
- C. Set field-adjustable temperature set points of temperature-actuated water mixing valves.

END OF SECTION 22 1119

## SECTION 22 1316 - SANITARY WASTE AND VENT PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Pipe, tube, and fittings.
  - 2. Specialty pipe fittings.

#### 1.3 DEFINITIONS

- A. EPDM: Ethylene-propylene-diene terpolymer rubber.
- B. PVC: Polyvinyl chloride plastic.

#### 1.4 PERFORMANCE REQUIREMENTS

- A. Components and installation shall be capable of withstanding the following minimum working pressure unless otherwise indicated:
  - 1. Soil, Waste, and Vent Piping: 10-foot head of water.
- B. Seismic Performance: Soil, waste, and vent piping and support and installation shall withstand the effects of earthquake motions determined according to SEI/ASCE 7 and with the requirements specified in Section 230548 "Vibration and Seismic Controls for HVAC."
  - 1. For piping with a seismic importance factor of 1.0 the term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."
  - 2. For piping with a seismic importance factor of 1.5 the term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

B. LEED Submittals:

1. Product Data for Credit IEQ 4.1: For solvent cements and adhesive primers, documentation including printed statement of VOC content.
2. Laboratory Test Reports for Credit IEQ 4: For solvent cements and adhesive primers, documentation indicating that products comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

1.6 INFORMATIONAL SUBMITTALS

A. Seismic Qualification Certificates: For waste and vent piping, accessories, and components, from manufacturer.

1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
2. Detailed description of piping anchorage devices on which the certification is based and their installation requirements.

B. LEED Submittals:

1. Product Data for Credit IEQ 4.1: For solvent cements and adhesive primers, documentation including printed statement of VOC content.

C. Field quality-control reports.

1.7 QUALITY ASSURANCE

A. Piping materials shall bear label, stamp, or other markings of specified testing agency.

B. Comply with NSF/ANSI 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-dwv" for plastic drain, waste, and vent piping; "NSF-sewer" for plastic sewer piping; "NSF-drain" for plastic drain piping, and "NSF-tubular" for plastic continuous waste piping.

1.8 PROJECT CONDITIONS

A. Interruption of Existing Sanitary Waste Service: Do not interrupt service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary service according to requirements indicated:

1. Notify Construction Manager no fewer than two days in advance of proposed interruption of sanitary waste service.

## PART 2 - PRODUCTS

### 2.1 PIPING MATERIALS

- A. Comply with requirements in "Piping Schedule" Article for applications of pipe, tube, fitting materials, and joining methods for specific services, service locations, and pipe sizes.

### 2.2 HUBLESS, CAST-IRON SOIL PIPE AND FITTINGS

- A. Pipe and Fittings: All cast-iron waste, vent and sewer pipe and fittings shall conform to the requirements of CISPI Standard 301 and ASTM A 888. All products shall be marked with the collective trademark of the Cast Soil Pipe Institute and shall be listed by NSF International or receive prior approval of the engineer. All cast-iron pipe and fittings shall be American made and tested. Non-compliant import cast-iron products will not be permitted. Any non-compliant cast-iron product installed by the contractor on this project will be replaced at the contractor's expense and shall include all repairs, patching, painting and other incidental work required to return the project to its pre-remediation state.

- B. Pipe shall be epoxy coated.

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. AB&I Foundry
  - b. Charlotte Pipe
  - c. Tyler Pipe
  - d. NewAge Epoxy

- C. CISPI, Hubless-Piping Couplings:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. ANACO.
  - b. Ideal
  - c. Mission Rubber Company; a division of MCP Industries, Inc.
  - d. Tyler Pipe.
- 2. Standards: ASTM C 1277 and CISPI 310.
- 3. Description: Stainless-steel corrugated shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.
- 4. Listing: Couplings shall be listed by NSF International. Each coupling shall be embossed with the NSF seal.

- D. Heavy-Duty, Hubless-Piping Couplings:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:



- a. Husky SD 4000.
  - b. Clamp-All Corp HI-TORQ 125.
2. Standards: ASTM C 1277 and ASTM C 1540.
3. Description: Stainless-steel shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.

## 2.3 PVC PIPE AND FITTINGS

- A. Solid-Wall PVC Pipe: ASTM D 2665, drain, waste, and vent.
- B. PVC Socket Fittings: ASTM D 2665, made to ASTM D 3311, drain, waste, and vent patterns and to fit Schedule 40 pipe.
- C. Adhesive Primer: ASTM F 656.
  1. Adhesive primer shall have a VOC content of 550 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- D. Solvent Cement: ASTM D 2564.
  1. PVC solvent cement shall have a VOC content of 510 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

## PART 3 - EXECUTION

### 3.1 EARTH MOVING

- A. Comply with requirements for excavating, trenching, and backfilling specified in Division 31 Section "Earth Moving."

### 3.2 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
- C. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- D. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.

- E. Install piping to permit valve servicing.
- F. Install piping at indicated slopes.
- G. Install piping free of sags and bends.
- H. Install fittings for changes in direction and branch connections.
- I. Install piping to allow application of insulation.
- J. Install seismic restraints on piping. Comply with SEI/ASCE 7 and with requirements for seismic-restraint devices specified in Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- K. Make changes in direction for soil and waste drainage and vent piping using appropriate branches, bends, and long-sweep bends. Sanitary tees and short-sweep 1/4 bends may be used on vertical stacks if change in direction of flow is from horizontal to vertical. Use long-turn, double Y-branch and 1/8-bend fittings if two fixtures are installed back to back or side by side with common drain pipe. Straight tees, elbows, and crosses may be used on vent lines. Do not change direction of flow more than 90 degrees. Use proper size of standard increasers and reducers if pipes of different sizes are connected. Reducing size of drainage piping in direction of flow is prohibited.
- L. Lay buried building drainage piping beginning at low point of each system. Install true to grades and alignment indicated, with unbroken continuity of invert.
- M. Install soil and waste drainage and vent piping at the following minimum slopes unless otherwise indicated:
  - 1. Building Sanitary Drain: 2 percent downward in direction of flow for piping.
  - 2. Horizontal Sanitary Drainage Piping: 2 percent downward in direction of flow.
  - 3. Vent Piping: 1 percent down toward vertical fixture vent or toward vent stack.
- N. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
  - 1. Install encasement on underground piping according to ASTM A 674 or AWWA C105/A 21.5.
- O. Install underground PVC piping according to ASTM D 2321.
- P. Install engineered soil and waste drainage and vent piping systems as follows:
  - 1. Combination Waste and Vent: Comply with standards of authorities having jurisdiction.
- Q. Plumbing Specialties:
  - 1. Install cleanouts at grade and extend to where building sanitary drains connect to building sanitary sewers in sanitary drainage gravity-flow piping. Install cleanout fitting with closure plug inside the building in sanitary drainage force-main piping. Comply with

- requirements for cleanouts specified in Division 22 Section "Sanitary Waste Piping Specialties."
2. Install drains in sanitary drainage gravity-flow piping. Comply with requirements for drains specified in Division 22 Section "Sanitary Waste Piping Specialties."
  3. Install cleanout fitting with closure plug inside the building in sanitary force-main piping.
- R. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.
- S. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Division 22 Section "Sleeves and Sleeve Seals for Plumbing Piping."
- T. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Division 22 Section "Sleeves and Sleeve Seals for Plumbing Piping."
- U. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Division 22 Section "Escutcheons for Plumbing Piping."
- V. Vents shall extend full size through roof and shall project minimum 18-in above the roof.

### 3.3 JOINT CONSTRUCTION

- A. Join hubless, cast-iron soil piping according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-piping coupling joints.
- B. Plastic, Nonpressure-Piping, Solvent-Cement Joints: Clean and dry joining surfaces. Join pipe and fittings according to the following:
1. Comply with ASTM F 402 for safe-handling practice of cleaners, primers, and solvent cements.
  2. PVC Piping: Join according to ASTM D 2855 and ASTM D 2665 Appendixes.

### 3.4 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements for seismic-restraint devices specified in Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- B. Comply with requirements for pipe hanger and support devices and installation specified in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment."
1. Install carbon-steel pipe hangers for horizontal piping in noncorrosive environments.
  2. Install stainless-steel pipe hangers for horizontal piping in corrosive environments.
  3. Install carbon-steel pipe support clamps for vertical piping in noncorrosive environments.
  4. Install stainless-steel pipe support clamps for vertical piping in corrosive environments.
  5. Vertical Piping: MSS Type 8 or Type 42, clamps.
  6. Install individual, straight, horizontal piping runs:

- a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    - c. Longer Than 100 Feet if Indicated: MSS Type 49, spring cushion rolls.
  7. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
  8. Base of Vertical Piping: MSS Type 52, spring hangers.
  - C. Support horizontal piping and tubing within 12 inches of each fitting and coupling or valve and coupling.
  - D. Support vertical piping and tubing at base and at each floor.
  - E. Rod diameter may be reduced one size for double-rod hangers, with 3/8-inch minimum rods.
  - F. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:
    1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
    2. NPS 3: 60 inches with 1/2-inch rod.
    3. NPS 4 and NPS 5: 60 inches with 5/8-inch rod.
    4. NPS 6 and NPS 8: 60 inches with 3/4-inch rod.
    5. NPS 10 and NPS 12: 60 inches with 7/8-inch rod.
    6. Spacing for 10-foot lengths may be increased to 10 feet. Spacing for fittings is limited to 60 inches.
  - G. Install supports for vertical cast-iron soil piping every 15 feet.
  - H. Install hangers for PVC piping with the following maximum horizontal spacing and minimum rod diameters:
    1. NPS 1-1/2 and NPS: 48 inches with 3/8-inch rod.
    2. NPS 3: 48 inches with 1/2-inch rod.
    3. NPS 4 and NPS 5: 48 inches with 5/8-inch rod.
    4. NPS 6 and NPS 8: 48 inches with 3/4-inch rod.
    5. NPS 10 and NPS 12: 48 inches with 7/8-inch rod.
  - I. Install supports for vertical PVC piping every 48 inches.
  - J. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.
- 3.5 CONNECTIONS
- A. Drawings indicate general arrangement of piping, fittings, and specialties.
  - B. Connect soil and waste piping to exterior sanitary sewerage piping. Use transition fitting to join dissimilar piping materials.

- C. Connect drainage and vent piping to the following:
  - 1. Plumbing Fixtures: Connect drainage piping in sizes indicated, but not smaller than required by plumbing code.
  - 2. Plumbing Fixtures and Equipment: Connect atmospheric vent piping in sizes indicated, but not smaller than required by authorities having jurisdiction.
  - 3. Plumbing Specialties: Connect drainage and vent piping in sizes indicated, but not smaller than required by plumbing code.
  - 4. Install test tees (wall cleanouts) in conductors near floor and floor cleanouts with cover flush with floor.
  - 5. Comply with requirements for cleanouts and drains specified in Division 22 Section "Sanitary Waste Piping Specialties."
  - 6. Equipment: Connect drainage piping as indicated. Provide shutoff valve if indicated and union for each connection. Use flanges instead of unions for connections NPS 2-1/2 and larger.
- D. Where installing piping adjacent to equipment, allow space for service and maintenance of equipment.
- E. Make fixture and equipment connections according to the following unless otherwise indicated:
  - 1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
  - 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.

### 3.6 IDENTIFICATION

- A. Identify exposed sanitary waste and vent piping. Comply with requirements for identification specified in Division 22 Section "Identification for Plumbing Piping and Equipment."

### 3.7 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.
  - 1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in and before setting fixtures.
  - 2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test sanitary drainage and vent piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:

1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
2. Leave uncovered and unconcealed new, altered, extended, or replaced drainage and vent piping until it has been tested and approved. Expose work that was covered or concealed before it was tested.
3. Roughing-in Plumbing Test Procedure: Test drainage and vent piping except outside leaders on completion of roughing-in. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water. From 15 minutes before inspection starts to completion of inspection, water level must not drop. Inspect joints for leaks.
4. Finished Plumbing Test Procedure: After plumbing fixtures have been set and traps filled with water, test connections and prove they are gastight and watertight. Plug vent-stack openings on roof and building drains where they leave building. Introduce air into piping system equal to pressure of 1-inch wg. Use U-tube or manometer inserted in trap of water closet to measure this pressure. Air pressure must remain constant without introducing additional air throughout period of inspection. Inspect plumbing fixture connections for gas and water leaks.
5. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
6. Prepare reports for tests and required corrective action.

### 3.8 CLEANING AND PROTECTION

- A. Clean interior of piping. Remove dirt and debris as work progresses.
- B. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.

### 3.9 PIPING SCHEDULE

- A. Flanges and unions may be used on aboveground pressure piping unless otherwise indicated.
- B. Aboveground, soil and waste piping NPS 3 and smaller shall be the following:
  1. Hubless, cast-iron soil pipe and fittings CISPI hubless-piping couplings; and coupled joints.
  2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- C. Aboveground, soil and waste piping NPS 4 and larger shall be the following:
  1. Hubless, cast-iron soil pipe and fittings heavy-duty hubless-piping couplings; and coupled joints.
  2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- D. Aboveground, vent piping NPS 3 and smaller shall be the following:

1. Hubless, cast-iron soil pipe and fittings CISPI hubless-piping couplings; and coupled joints.
  2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- E. Aboveground, vent piping NPS 4 and larger shall be the following:
1. Hubless, cast-iron soil pipe and fittings CISPI hubless-piping couplings; and coupled joints.
  2. Dissimilar Pipe-Material Couplings: Unshielded, nonpressure transition couplings.
- F. Aboveground Grease, soil, waste and vent piping shall be any of the following:
1. Hubless, cast-iron soil pipe and fittings heavy-duty hubless-piping couplings; and coupled joints.
  2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- G. Underground Grease, soil, waste and vent piping shall be any of the following:
1. Hubless, cast-iron soil pipe and fittings heavy-duty hubless-piping couplings; and coupled joints.
  2. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints. Rated for High Temperatures.
- H. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- I. Underground, soil, waste, and vent piping NPS 3 and smaller shall be the following:
1. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints. All underground waste piping in boiler room shall be rated for high temperatures.
  2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.
- J. Underground, soil and waste piping NPS 4 and larger shall be the following:
1. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints. All underground waste piping in boiler room shall be rated for high temperatures.
  2. Dissimilar Pipe-Material Couplings: Shielded, nonpressure transition couplings.

END OF SECTION 22 1316

## SECTION 22 1319 - SANITARY WASTE PIPING SPECIALTIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following sanitary drainage piping specialties:
  - 1. Cleanouts.
  - 2. Floor drains.
  - 3. Channel drainage systems.
  - 4. Roof flashing assemblies.
  - 5. Through-penetration firestop assemblies.
  - 6. Miscellaneous sanitary drainage piping specialties.
  - 7. Flashing materials.
- B. Related Sections include the following:
  - 1. Division 22 Section "Storm Drainage Piping Specialties" for trench drains for storm water, channel drainage systems for storm water, roof drains, and catch basins.

#### 1.3 SEISMIC REQUIREMENTS

- A. Seismic Performance: Plumbing equipment, hangers and supports shall withstand the effects of earthquake motions determined according to SEI/ASCE 7 and with the requirements specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment.

#### 1.4 DEFINITIONS

- A. FOG: Fats, oils, and greases.
- B. FRP: Fiberglass-reinforced plastic.
- C. HDPE: High-density polyethylene plastic.
- D. PE: Polyethylene plastic.
- E. PP: Polypropylene plastic.
- F. PVC: Polyvinyl chloride plastic.



## 1.5 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Field quality-control test reports.
- C. Operation and Maintenance Data: For drainage piping specialties to include in emergency, operation, and maintenance manuals.

## 1.6 QUALITY ASSURANCE

- A. Drainage piping specialties shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 14, "Plastics Piping Components and Related Materials," for plastic sanitary piping specialty components.

## 1.7 COORDINATION

- A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified in Division 03.
- B. Coordinate size and location of roof penetrations.

# PART 2 - PRODUCTS

## 2.1 CLEANOUTS

- A. Exposed Metal Cleanouts:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Josam Company; Josam Div.
    - b. MIFAB, Inc.
    - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
    - d. Tyler Pipe; Wade Div.
    - e. Watts Drainage Products Inc.
    - f. Zurn Plumbing Products Group; Specification Drainage Operation.
  - 2. Standard: ASME A112.36.2M for cast iron for cleanout test tee.
  - 3. Size: Same as connected drainage piping
  - 4. Body Material: Hubless, cast-iron soil pipe test tee as required to match connected piping.
  - 5. Closure: Countersunk, brass plug.
  - 6. Closure Plug Size: Same as or not more than one size smaller than cleanout size.

7. Closure: Stainless-steel plug with seal.

B. Metal Floor Cleanouts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam Company; Josam Div.
  - b. Oatey.
  - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - d. Tyler Pipe; Wade Div.
  - e. Watts Drainage Products Inc.
  - f. Zurn Plumbing Products Group; Light Commercial Operation.
  - g. Zurn Plumbing Products Group; Specification Drainage Operation.
2. Standard: ASME A112.36.2M for adjustable housing cleanout.
3. Size: Same as connected branch.
4. Type: Adjustable housing.
5. Body or Ferrule: Cast iron.
6. Clamping Device: Required.
7. Outlet Connection: Inside calk.
8. Closure: Brass plug with tapered threads.
9. Adjustable Housing Material: Cast iron with threads.
10. Frame and Cover Material and Finish: Nickel-bronze, copper alloy.
11. Frame and Cover Shape: Round.
12. Top Loading Classification: Heavy Duty.
13. Riser: ASTM A 74, Service class, cast-iron drainage pipe fitting and riser to cleanout.
14. Standard: ASME A112.3.1.
15. Size: Same as connected branch.
16. Housing: Stainless steel.
17. Closure: Stainless steel with seal.
18. Riser: Stainless-steel drainage pipe fitting to cleanout.

C. Cast-Iron Wall Cleanouts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam Company; Josam Div.
  - b. MIFAB, Inc.
  - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - d. Tyler Pipe; Wade Div.
  - e. Watts Drainage Products Inc.
  - f. Zurn Plumbing Products Group; Specification Drainage Operation.
2. Standard: ASME A112.36.2M. Include wall access.
3. Size: Same as connected drainage piping.
4. Body: Hub-and-spigot, cast-iron soil pipe T-branch as required to match connected piping.
5. Closure: Countersunk, brass plug.

6. Closure Plug Size: Same as or not more than one size smaller than cleanout size.
7. Wall Access: Round, flat, chrome-plated brass or stainless-steel cover plate with screw.
8. Wall Access: Round, stainless-steel wall-installation frame and cover.

## 2.2 FLOOR DRAINS

### A. Cast-Iron Floor Drains:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam Company; Josam Div.
  - b. MIFAB, Inc.
  - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - d. Tyler Pipe; Wade Div.
  - e. Watts Drainage Products Inc.
  - f. Zurn Plumbing Products Group; Specification Drainage Operation.
2. Standard: ASME A112.6.3.
3. Body Material: Gray iron.
4. Seepage Flange: Required.
5. Anchor Flange: Not required.
6. Outlet: Bottom.
7. Trap Material: Cast iron>.
8. Trap Pattern: Deep-seal P-trap>.
9. Trap Features: Trap-seal primer valve drain connection>.

## 2.3 CHANNEL DRAINAGE SYSTEMS

### A. Plastic Channel Drainage Systems:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam.
  - b. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - c. Zurn Plumbing Products Group; Flo-Thru Operation.
  - d. NDS Inc.
2. Type: Modular system of channel sections, grates, and appurtenances; designed so grates fit into channel recesses without rocking or rattling.
  - a. Channel Sections: Interlocking-joint, SMC/GRP, HDPE or PE modular units, with end caps. Include flat, rounded, or inclined bottom, with level invert and with outlets in number, sizes, and locations indicated. Provide drain lengths indicated on drawings.

- 1) Dimensions: 4 inches wide. Include number of units required to form total lengths indicated.
- b. Grates: With slots or perforations and widths and thickness that fit recesses in channel sections.
  - 1) Material: Gray iron.
- c. Supports, Anchors, and Setting Devices: Manufacturer's standard, unless otherwise indicated.
- d. Channel-Section Joining and Fastening Materials: As recommended by system manufacturer.

## 2.4 THROUGH-PENETRATION FIRESTOP ASSEMBLIES

### A. Through-Penetration Firestop Assemblies:

1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. ProSet Systems Inc.
3. Standard: UL 1479 assembly of sleeve and stack fitting with firestopping plug.
4. Size: Same as connected soil, waste, or vent stack.
5. Sleeve: Molded PVC plastic, of length to match slab thickness and with integral nailing flange on one end for installation in cast-in-place concrete slabs.
6. Stack Fitting: ASTM A 48/A 48M, gray-iron, hubless-pattern, wye branch with neoprene O-ring at base and gray-iron plug in thermal-release harness. Include PVC protective cap for plug.
7. Special Coating: Corrosion resistant on interior of fittings.

## 2.5 MISCELLANEOUS SANITARY DRAINAGE PIPING SPECIALTIES

### A. Deep-Seal Traps:

1. Description: Cast-iron or bronze casting, with inlet and outlet matching connected piping and cleanout trap-seal primer valve connection.
2. Size: Same as connected waste piping.
  - a. NPS 2: 4-inch- minimum water seal.
  - b. NPS 2-1/2 and Larger: 5-inch- minimum water seal.

### B. Floor-Drain, Trap-Seal Primer Fittings:

1. Description: Cast iron, with threaded inlet and threaded or spigot outlet, and trap-seal primer valve connection.
2. Size: Same as floor drain outlet with NPS 1/2 side inlet.

C. Air-Gap Fittings:

1. Standard: ASME A112.1.2, for fitting designed to ensure fixed, positive air gap between installed inlet and outlet piping.
2. Body: Bronze or cast iron.
3. Inlet: Opening in top of body.
4. Outlet: Larger than inlet.
5. Size: Same as connected waste piping and with inlet large enough for associated indirect waste piping.

D. Sleeve Flashing Device:

1. Description: Manufactured, cast-iron fitting, with clamping device, that forms sleeve for pipe floor penetrations of floor membrane. Include galvanized-steel pipe extension in top of fitting that will extend 1 inch > above finished floor and galvanized-steel pipe extension in bottom of fitting that will extend through floor slab.
2. Size: As required for close fit to riser or stack piping.

E. Stack Flashing Fittings:

1. Description: Counterflashing-type, cast-iron fitting, with bottom recess for terminating roof membrane, and with threaded or hub top for extending vent pipe.
2. Size: Same as connected stack vent or vent stack.

F. Vent Cap Filters:

1. Description: Activated carbon filter in housing for installation at vent terminal as manufactured by Sweet Filter.
2. Size: Same as connected stack vent or vent stack.

## 2.6 FLASHING MATERIALS

A. Lead Sheet: ASTM B 749, Type L51121, copper bearing, with the following minimum weights and thicknesses, unless otherwise indicated:

1. General Use: 4.0-lb/sq. ft., 0.0625-inch thickness.
2. Vent Pipe Flashing: 3.0-lb/sq. ft., 0.0469-inch thickness.
3. Burning: 6-lb/sq. ft., 0.0938-inch thickness.

B. Elastic Membrane Sheet: ASTM D 4068, flexible, chlorinated polyethylene, 40-mil minimum thickness.

C. Fasteners: Metal compatible with material and substrate being fastened.

- D. Metal Accessories: Sheet metal strips, clamps, anchoring devices, and similar accessory units required for installation; matching or compatible with material being installed.
- E. Bituminous Coating: SSPC-Paint 12, solvent-type, bituminous mastic.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Comply with requirements for seismic-restraint devices in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- B. Refer to Division 22 Section "Common Work Results for Plumbing" for piping joining materials, joint construction, and basic installation requirements.
- C. Install backwater valves in building drain piping. For interior installation, provide cleanout deck plate flush with floor and centered over backwater valve cover, and of adequate size to remove valve cover for servicing.
- D. Install cleanouts in aboveground piping and building drain piping according to the following, unless otherwise indicated:
  - 1. Size same as drainage piping up to NPS 4. Use NPS 4 for larger drainage piping unless larger cleanout is indicated.
  - 2. Locate at each change in direction of piping greater than 45 degrees.
  - 3. Locate at minimum intervals of 50 feet for piping NPS 4 and smaller and 100 feet for larger piping.
  - 4. Locate at base of each vertical soil and waste stack.
- E. For floor cleanouts for piping below floors, install cleanout deck plates with top flush with finished floor.
- F. For cleanouts located in concealed piping, install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall.
- G. Install floor drains at low points of surface areas to be drained. Set grates of drains flush with finished floor, unless otherwise indicated.
  - 1. Position floor drains for easy access and maintenance.
  - 2. Set floor drains below elevation of surrounding finished floor to allow floor drainage. Set with grates depressed according to the following drainage area radii:
    - a. Radius, 30 Inches or Less: Equivalent to 1 percent slope, but not less than 1/4-inch total depression.
    - b. Radius, 30 to 60 Inches: Equivalent to 1 percent slope.
    - c. Radius, 60 Inches or Larger: Equivalent to 1 percent slope, but not greater than 1-inch total depression.

3. Install floor-drain flashing collar or flange so no leakage occurs between drain and adjoining flooring. Maintain integrity of waterproof membranes where penetrated.
  4. Install individual traps for floor drains connected to sanitary building drain, unless otherwise indicated.
- H. Assemble plastic channel drainage system components according to manufacturer's written instructions. Install on support devices so that top will be flush with adjacent surface.
- I. Assemble stainless steel channel drainage system components according to manufacturer's written instructions. Install on support devices so that top will be flush with adjacent surface.
- J. Install deep-seal traps on all floor drains and other waste outlets, if indicated.
- K. Install floor-drain, trap-seal primer fittings on inlet to floor drains that require trap-seal primer connection.
1. Exception: Fitting may be omitted if trap has trap-seal primer connection.
  2. Size: Same as floor drain inlet.
- L. Install air-gap fittings on draining-type backflow preventers and on indirect-waste piping discharge into sanitary drainage system.
- M. Install sleeve flashing device with each riser and stack passing through floors with waterproof membrane.
- N. Install vent cap filters on each vent pipe passing through roof.
- O. Install wood-blocking reinforcement for wall-mounting-type specialties.
- P. Install traps on plumbing specialty drain outlets. Omit traps on indirect wastes unless trap is indicated.
- Q. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding pipe fittings.

### 3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment to allow service and maintenance.

### 3.3 FLASHING INSTALLATION

- A. Fabricate flashing from single piece unless large pans, sumps, or other drainage shapes are required. Join flashing according to the following if required:

1. Lead Sheets: Burn joints of lead sheets 6.0-lb/sq. ft., 0.0938-inch thickness or thicker. Solder joints of lead sheets 4.0-lb/sq. ft., 0.0625-inch thickness or thinner.
- B. Install sheet flashing on pipes, sleeves, and specialties passing through or embedded in floors and roofs with waterproof membrane.
  1. Pipe Flashing: Sleeve type, matching pipe size, with minimum length of 10 inches, and skirt or flange extending at least 8 inches around pipe.
  2. Sleeve Flashing: Flat sheet, with skirt or flange extending at least 8 inches around sleeve.
  3. Embedded Specialty Flashing: Flat sheet, with skirt or flange extending at least 8 inches around specialty.
- C. Set flashing on floors and roofs in solid coating of bituminous cement.
- D. Secure flashing into sleeve and specialty clamping ring or device.
- E. Install flashing for piping passing through roofs with counterflashing or commercially made flashing fittings, according to Division 07 Section "Sheet Metal Flashing and Trim."
- F. Extend flashing up vent pipe passing through roofs and turn down into pipe, or secure flashing into cast-iron sleeve having calking recess.
- G. Fabricate and install flashing and pans, sumps, and other drainage shapes.

### 3.4 FIELD QUALITY CONTROL

- A. Perform tests and inspections and prepare test reports.
- B. Tests and Inspections:
  1. Leak Test: After installation, charge system and test for leaks. Repair leaks and retest until no leaks exist.
  2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.

### 3.5 PROTECTION

- A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.
- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION 22 1319



## SECTION 22 1413 - FACILITY STORM DRAINAGE PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following storm drainage piping inside the building:
  - 1. Pipe, tube, and fittings.
  - 2. Special pipe fittings.
- B. Related Sections include the following:
  - 1. Division 22 Section "Sump Pumps."

#### 1.3 DEFINITIONS

- A. LLDPE: Linear, low-density polyethylene plastic.
- B. PE: Polyethylene plastic.
- C. PVC: Polyvinyl chloride plastic.
- D. TPE: Thermoplastic elastomer.

#### 1.4 PERFORMANCE REQUIREMENTS

- A. Components and installation shall be capable of withstanding the following minimum working-pressure, unless otherwise indicated:
  - 1. Storm Drainage Piping: 10-foot head of water.
- B. Seismic Performance: Plumbing equipment, hangers and supports shall withstand the effects of earthquake motions determined according to SEI/ASCE 7 and with the requirements specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
  - 1. For components with a seismic importance factor of 1.0 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified."

2. For components with a seismic importance factor of 1.5 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified and the system will be fully operational after the seismic event."

## 1.5 SUBMITTALS

- A. Product Data: For pipe, tube, fittings, and couplings.
- B. Shop Drawings:
  1. Controlled-Flow Storm Drainage System: Include calculations, plans, and details.
- C. Field quality-control inspection and test reports.
- D. Delegated-Design Submittal:
  1. Design calculations and detailed fabrication and assembly of pipe anchors and alignment guides, hangers and supports for multiple pipes, expansion joints and loops, and attachments of the same to the building structure.
  2. Locations of pipe anchors and alignment guides and expansion joints and loops.
  3. Locations of and details for penetrations, including sleeves and sleeve seals for exterior walls, floors, basement, and foundation walls.

## 1.6 QUALITY ASSURANCE

- A. Piping materials shall bear label, stamp, or other markings of specified testing agency.
- B. Comply with NSF 14, "Plastics Piping Systems Components and Related Materials," for plastic piping components. Include marking with "NSF-drain" for plastic drain piping and "NSF-sewer" for plastic sewer piping.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

### 2.2 PIPING MATERIALS

- A. Refer to Part 3 "Piping Applications" Article for applications of pipe, tube, fitting, and joining materials.

## 2.3 HUBLESS CAST-IRON SOIL PIPE AND FITTINGS

- A. Pipe and Fittings: ASTM A 888 or CISPI 301. All waste, vent, sewer and storm lines shall be soil pipe and fittings that conform to the requirements of CISPI Standard 301, ASTM A \*\* and shall be marked with the collective trademark of the Cast Soil Pipe Institute or Receive Prior approval of the engineer and manufactured by AB&I Foundry, Tyler Pipe, or Charlotte Pipe. In addition all Cast iron shall be American made and tested, no “non compliant” import cast iron will be permitted.
- B. Heavy-Duty, Hubless-Piping Couplings:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Husky HD 2000.
    - b. Clamp-All Corp HI-TORQ 80.
    - c. Ideal HD
    - d. Mission HW.
    - e. Tyler Pipe Widebody.
  - 2. Standards: ASTM C 1277 and ASTM C 1540.
  - 3. Description: Stainless-steel shield with stainless-steel bands and tightening devices; and ASTM C 564, rubber sleeve with integral, center pipe stop.

## 2.4 SPECIAL PIPE FITTINGS

- A. Flexible, Nonpressure Pipe Couplings: Comply with ASTM C 1173, elastomeric, sleeve-type, reducing or transition pattern. Include shear ring, ends of same sizes as piping to be joined, and corrosion-resistant-metal tension band and tightening mechanism on each end.
  - 1. Manufacturers:
    - a. Dallas Specialty & Mfg. Co.
    - b. Fernco, Inc.
    - c. Logan Clay Products Company (The).
    - d. Mission Rubber Co.
    - e. NDS, Inc.
    - f. Plastic Oddities, Inc.
  - 2. Sleeve Materials:
    - a. For Cast-Iron Soil Pipes: ASTM C 564, rubber.
    - b. For Plastic Pipes: ASTM F 477, elastomeric seal or ASTM D 5926, PVC.
    - c. For Dissimilar Pipes: ASTM D 5926, PVC or other material compatible with pipe materials being joined.
- B. Shielded Nonpressure Pipe Couplings: ASTM C 1460, elastomeric or rubber sleeve with full-length, corrosion-resistant outer shield and corrosion-resistant-metal tension band and tightening mechanism on each end.

1. Manufacturers:
  - a. Cascade Waterworks Mfg. Co.
  - b. Mission Rubber Co.

## PART 3 - EXECUTION

### 3.1 EXCAVATION

- A. Refer to Division 31 Section "Earth Moving" for excavating, trenching, and backfilling.

### 3.2 PIPING APPLICATIONS

- A. Flanges and unions may be used on aboveground pressure piping, unless otherwise indicated.
- B. Aboveground storm drainage piping shall be the following:
  1. Hubless cast-iron soil pipe and fittings; heavy-duty shielded, stainless-steel couplings; and coupled joints.
- C. Underground storm drainage piping shall be the following ( to 6" above finished floor):
  1. Solid-wall PVC pipe, PVC socket fittings, and solvent-cemented joints.
  2. Hub-and spigot cast-iron soil pipe, hub-and spigot cast-iron soil pipe fittings, neoprene rubber gasket, and compression joints.

### 3.3 PIPING INSTALLATION

- A. Storm sewer and drainage piping outside the building are specified in Division 33 Section "Storm Utility Drainage Piping."
- B. Comply with SEI/ASCE 7 and with requirements for seismic-restraint devices in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- C. Basic piping installation requirements are specified in Division 22 Section "Common Work Results for Plumbing."
- D. Install cleanouts at grade and extend to where building storm drains connect to building storm sewers. Cleanouts are specified in Division 22 Section "Storm Drainage Piping Specialties."
- E. Install cleanout fitting with closure plug inside the building in storm drainage force-main piping.
- F. Install cast-iron sleeve with water stop and mechanical sleeve seal at each service pipe penetration through foundation wall. Select number of interlocking rubber links required to make installation watertight. Sleeves and mechanical sleeve seals are specified in Division 22 Section "Common Work Results for Fire Plumbing."

- G. Install cast-iron soil piping according to CISPI's "Cast Iron Soil Pipe and Fittings Handbook," Chapter IV, "Installation of Cast Iron Soil Pipe and Fittings."
  - 1. Install encasement on underground piping according to ASTM A 674 or AWWA C105.
- H. Make changes in direction for storm drainage piping using appropriate branches, bends, and long-sweep bends. Do not change direction of flow more than 90 degrees. Use proper size of standard increasers and reducers if pipes of different sizes are connected. Reducing size of drainage piping in direction of flow is prohibited.
- I. Lay buried building storm drainage piping beginning at low point of each system. Install true to grades and alignment indicated, with unbroken continuity of invert. Place hub ends of piping upstream. Install required gaskets according to manufacturer's written instructions for use of lubricants, cements, and other installation requirements. Maintain swab in piping and pull past each joint as completed.
- J. Install storm drainage piping at the following minimum slopes, unless otherwise indicated:
  - 1. Building Storm Drain: 1 percent downward in direction of flow for piping NPS 3 and smaller; 1 percent downward in direction of flow for piping NPS 4 and larger.
  - 2. Horizontal Storm-Drainage Piping: 1 percent downward in direction of flow.
- K. Sleeves are not required for cast-iron soil piping passing through concrete slabs-on-grade if slab is without membrane waterproofing.
- L. Install underground PVC storm drainage piping according to ASTM D 2321.
- M. Do not enclose, cover, or put piping into operation until it is inspected and approved by authorities having jurisdiction.

### 3.4 JOINT CONSTRUCTION

- A. Basic piping joint construction requirements are specified in Division 22 Section "Common Work Results Plumbing."
- B. Hubless Cast-Iron Soil Piping Coupled Joints: Join according to CISPI 310 and CISPI's "Cast Iron Soil Pipe and Fittings Handbook" for hubless-coupling joints.
- C. PVC Nonpressure Piping Joints: Join piping according to ASTM D 2665.

### 3.5 HANGER AND SUPPORT INSTALLATION

- A. Seismic-restraint devices are specified in Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- B. Pipe hangers and supports are specified in Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment." Install the following:

1. Vertical Piping: MSS Type 8 or Type 42, clamps.
  2. Individual, Straight, Horizontal Piping Runs: According to the following:
    - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    - b. Longer than 100 Feet: MSS Type 43, adjustable roller hangers.
    - c. Longer than 100 Feet, if indicated: MSS Type 49, spring cushion rolls.
  3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
  4. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Install supports according to Division 22 Section "Hangers and Supports for Plumbing Piping and Equipment."
- D. Support vertical piping and tubing at base and at each floor.
- E. Rod diameter may be reduced 1 size for double-rod hangers, with 3/8-inch minimum rods.
- F. Install hangers for cast-iron soil piping with the following maximum horizontal spacing and minimum rod diameters:
1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
  2. NPS 3: 60 inches with 1/2-inch rod.
  3. NPS 4 and NPS 5: 60 inches with 5/8-inch rod.
  4. NPS 6: 60 inches with 3/4-inch rod.
  5. NPS 8 to NPS 12: 60 inches with 7/8-inch rod.
  6. Spacing for 10-foot lengths may be increased to 10 feet. Spacing for fittings is limited to 60 inches.
- G. Install supports for vertical cast-iron soil piping every 15 feet.
- H. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.

### 3.6 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect interior storm drainage piping to exterior storm drainage piping. Use transition fitting to join dissimilar piping materials.
- C. Connect storm drainage piping to roof drains and storm drainage specialties.

### 3.7 FIELD QUALITY CONTROL

- A. During installation, notify authorities having jurisdiction at least 24 hours before inspection must be made. Perform tests specified below in presence of authorities having jurisdiction.

1. Roughing-in Inspection: Arrange for inspection of piping before concealing or closing-in after roughing-in.
  2. Final Inspection: Arrange for final inspection by authorities having jurisdiction to observe tests specified below and to ensure compliance with requirements.
- B. Reinspection: If authorities having jurisdiction find that piping will not pass test or inspection, make required corrections and arrange for reinspection.
- C. Reports: Prepare inspection reports and have them signed by authorities having jurisdiction.
- D. Test storm drainage piping according to procedures of authorities having jurisdiction or, in absence of published procedures, as follows:
1. Test for leaks and defects in new piping and parts of existing piping that have been altered, extended, or repaired. If testing is performed in segments, submit separate report for each test, complete with diagram of portion of piping tested.
  2. Leave uncovered and unconcealed new, altered, extended, or replaced storm drainage piping until it has been tested and approved. Expose work that was covered or concealed before it was tested.
  3. Test Procedure: Test storm drainage piping on completion of roughing-in. Close openings in piping system and fill with water to point of overflow, but not less than 10-foot head of water. From 15 minutes before inspection starts to completion of inspection, water level must not drop. Inspect joints for leaks.
  4. Repair leaks and defects with new materials and retest piping, or portion thereof, until satisfactory results are obtained.
  5. Prepare reports for tests and required corrective action.

### 3.8 CLEANING

- A. Clean interior of piping. Remove dirt and debris as work progresses.
- B. Protect drains during remainder of construction period to avoid clogging with dirt and debris and to prevent damage from traffic and construction work.
- C. Place plugs in ends of uncompleted piping at end of day and when work stops.

END OF SECTION 22 1413

## SECTION 22 1423 - STORM DRAINAGE PIPING SPECIALTIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following storm drainage piping specialties:
  - 1. Cleanouts.
  - 2. Roof drains.
  - 3. Miscellaneous storm drainage piping specialties.
  - 4. Flashing materials.
- B. Related Sections include the following:
  - 1. Division 22 Section "Sanitary Waste Piping Specialties" for backwater valves, floor drains, trench drains and channel drainage systems connected to sanitary sewer, air admittance valves, FOG disposal systems, grease interceptors and removal devices, oil interceptors, and solid interceptors.

#### 1.3 DEFINITIONS

- A. PUR: Polyurethane plastic.
- B. PVC: Polyvinyl chloride plastic.

#### 1.4 SUBMITTALS

- A. Product Data: For each type of product indicated.

#### 1.5 QUALITY ASSURANCE

- A. Drainage piping specialties shall bear label, stamp, or other markings of specified testing agency.

#### 1.6 COORDINATION

- A. Coordinate size and location of roof penetrations.



## PART 2 - PRODUCTS

### 2.1 CLEANOUTS

#### A. Exposed Metal Cleanouts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam Company; Josam Div.
  - b. MIFAB, Inc.
  - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - d. Sioux Chief Manufacturing Company, Inc
  - e. Tyler Pipe; Wade Div.
  - f. Watts Drainage Products Inc.
  - g. Zurn Plumbing Products Group; Specification Drainage Operation.
2. Standard: ASME A112.36.2M for cast iron for cleanout test tee.
3. Size: Same as connected drainage piping
4. Body Material: Hubless, cast-iron soil pipe test tee as required to match connected piping.
5. Closure: Countersunk, brass plug.
6. Closure Plug Size: Same as or not more than one size smaller than cleanout size.
7. Closure: Stainless-steel plug with seal.

#### B. Metal Floor Cleanouts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam Company; Josam Div.
  - b. Oatey.
  - c. Sioux Chief Manufacturing Company, Inc.
  - d. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - e. Tyler Pipe; Wade Div.
  - f. Watts Drainage Products Inc.
  - g. Zurn Plumbing Products Group; Light Commercial Operation.
  - h. Zurn Plumbing Products Group; Specification Drainage Operation.
2. Standard: ASME A112.36.2M for adjustable housing cleanout.
3. Size: Same as connected branch.
4. Type: Adjustable housing.
5. Body or Ferrule: Cast iron.
6. Clamping Device: Required.
7. Outlet Connection: Inside calk.
8. Closure: [Brass plug with tapered threads.
9. Adjustable Housing Material: Cast iron with threads.
10. Frame and Cover Material and Finish: Stainless steel.
11. Frame and Cover Shape: Round.

12. Top Loading Classification: Heavy Duty.
13. Riser: ASTM A 74, Service class, cast-iron drainage pipe fitting and riser to cleanout.
14. Standard: ASME A112.3.1.
15. Size: Same as connected branch.
16. Housing: Stainless steel.
17. Closure: Stainless steel with seal.
18. Riser: Stainless-steel drainage pipe fitting to cleanout.

C. Cast-Iron Wall Cleanouts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Josam Company; Josam Div.
  - b. MIFAB, Inc.
  - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - d. Sioux Chief Manufacturing Company, Inc
  - e. Tyler Pipe; Wade Div.
  - f. Watts Drainage Products Inc.
  - g. Zurn Plumbing Products Group; Specification Drainage Operation.
2. Standard: ASME A112.36.2M. Include wall access.
3. Size: Same as connected drainage piping.
4. Body: Hubless, cast-iron soil pipe test tee as required to match connected piping.
5. Closure: Countersunk, brass plug.
6. Closure Plug Size: Same as or not more than one size smaller than cleanout size.
7. Wall Access: Round, flat, chrome-plated brass or stainless-steel cover plate with screw.

2.2 ROOF DRAINS

A. Metal Roof Drains:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
2. Basis-of-Design Product: See Schedule at end of this section for drain descriptions:
  - a. Josam Company; Josam Div.
  - b. MIFAB, Inc.
  - c. Smith, Jay R. Mfg. Co.; Division of Smith Industries, Inc.
  - d. Sioux Chief Manufacturing Company, Inc
  - e. Tyler Pipe; Wade Div.
  - f. Watts Drainage Products Inc.
  - g. Zurn Plumbing Products Group; Specification Drainage Operation.
3. Standard: ASME A112.21.2M.
4. Body Material Cast iron.
5. Combination Flashing Ring and Gravel Stop: Required.
6. Dome Material: Cast iron.
7. Extension Collars: Required.

8. Underdeck Clamp Required.
9. Sump Receiver: Required.

B. Conductor Nozzles:

1. Description: Bronze body with threaded inlet and bronze wall flange with mounting holes.
2. Size: Same as connected conductor.

2.3 FLASHING MATERIALS

- A. Elastic Membrane Sheet: ASTM D 4068, flexible, chlorinated polyethylene, 40-mil minimum thickness.
- B. Fasteners: Metal compatible with material and substrate being fastened.
- C. Metal Accessories: Sheet metal strips, clamps, anchoring devices, and similar accessory units required for installation; matching or compatible with material being installed.
- D. Bituminous Coating: SSPC-Paint 12, solvent-type, bituminous mastic.

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Refer to Division 22 Section "Common Work Results for Plumbing" for piping joining materials, joint construction, and basic installation requirements.
- B. Install cleanouts in aboveground piping and building drain piping according to the following, unless otherwise indicated:
  1. Size same as drainage piping up to NPS 4. Use NPS 4 for larger drainage piping unless larger cleanout is indicated.
  2. Locate at each change in direction of piping greater than 45 degrees.
  3. Locate at minimum intervals of 50 feet for piping NPS 4 and smaller and 100 feet for larger piping.
  4. Locate at base of each vertical soil and waste stack.
- C. For floor cleanouts for piping below floors, install cleanout deck plates with top flush with finished floor.
- D. For cleanouts located in concealed piping, install cleanout wall access covers, of types indicated, with frame and cover flush with finished wall.
- E. Install roof drains at low points of roof areas according to roof membrane manufacturer's written installation instructions. Roofing materials are specified in Division 07.

1. Install roof-drain flashing collar or flange so that there will be no leakage between drain and adjoining roofing. Maintain integrity of waterproof membranes where penetrated.
  2. Position roof drains for easy access and maintenance.
- F. Install manufactured, gray-iron downspout boots at grade with top 18 inches above grade. Secure to building wall.
- G. Install conductor nozzles at exposed bottom of conductors where they spill onto grade.
- H. Install escutcheons at wall, floor, and ceiling penetrations in exposed finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding pipe fittings.

### 3.2 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.

### 3.3 FLASHING INSTALLATION

- A. Fabricate flashing from single piece unless large pans, sumps, or other drainage shapes are required. Join flashing according to the following if required:
1. Lead Sheets: Burn joints of lead sheets 6.0-lb/sq. ft., 0.0938-inch thickness or thicker. Solder joints of lead sheets 4.0-lb/sq. ft., 0.0625-inch thickness or thinner.
- B. Install sheet flashing on pipes, sleeves, and specialties passing through or embedded in floors and roofs with waterproof membrane.
1. Pipe Flashing: Sleeve type, matching pipe size, with minimum length of 10 inches, and skirt or flange extending at least 8 inches around pipe.
  2. Sleeve Flashing: Flat sheet, with skirt or flange extending at least 8 inches around sleeve.
  3. Embedded Specialty Flashing: Flat sheet, with skirt or flange extending at least 8 inches around specialty.
- C. Set flashing on floors and roofs in solid coating of bituminous cement.
- D. Secure flashing into sleeve and specialty clamping ring or device.
- E. Fabricate and install flashing and pans, sumps, and other drainage shapes.

### 3.4 PROTECTION

- A. Protect drains during remainder of construction period to avoid clogging with dirt or debris and to prevent damage from traffic or construction work.

- B. Place plugs in ends of uncompleted piping at end of each day or when work stops.

END OF SECTION 22 1423

## SECTION 22 4000 - PLUMBING FIXTURES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following conventional plumbing fixtures and related components:
  - 1. Faucets for lavatories bathtub/showers showers and sinks.
  - 2. Flushometers.
  - 3. Toilet seats.
  - 4. Protective shielding guards.
  - 5. Fixture supports.
  - 6. Water closets.
  - 7. Urinals.
  - 8. Lavatories.
  - 9. Commercial sinks.
  - 10. Bathtubs.
  - 11. Service sinks.
- B. Related Sections include the following:
  - 1. Division 10 Section "Toilet, Bath, and Laundry Accessories."
  - 2. Division 22 Section "Domestic Water Piping Specialties" for backflow preventers, floor drains, and specialty fixtures not included in this Section.
  - 3. Division 22 Section "Emergency Plumbing Fixtures."
  - 4. Division 22 Section "Drinking Fountains and Water Coolers."

#### 1.3 DEFINITIONS

- A. Accessible Fixture: Plumbing fixture that can be approached, entered, and used by people with disabilities.
- B. Cast Polymer: Cast-filled-polymer-plastic material. This material includes cultured-marble and solid-surface materials.
- C. Cultured Marble: Cast-filled-polymer-plastic material with surface coating.
- D. Fitting: Device that controls the flow of water into or out of the plumbing fixture. Fittings specified in this Section include supplies and stops, faucets and spouts, shower heads and tub

spouts, drains and tailpieces, and traps and waste pipes. Piping and general-duty valves are included where indicated.

- E. FRP: Fiberglass-reinforced plastic.
- F. PMMA: Polymethyl methacrylate (acrylic) plastic.
- G. PVC: Polyvinyl chloride plastic.
- H. Solid Surface: Nonporous, homogeneous, cast-polymer-plastic material with heat-, impact-, scratch-, and stain-resistance qualities.

#### 1.4 WARRANTY

- A. Provide a one year factory warranty for all fixtures, faucets and valves from the date of substantial completion.

#### 1.5 SUBMITTALS

- A. Product Data: For each type of plumbing fixture indicated. Include selected fixture and trim, fittings, accessories, appliances, appurtenances, equipment, and supports. Indicate materials and finishes, dimensions, construction details, and flow-control rates.
- B. Shop Drawings: Diagram power, signal, and control wiring.
- C. Operation and Maintenance Data: For plumbing fixtures to include in emergency, operation, and maintenance manuals.
- D. Warranty: Special warranty specified in this Section.

#### 1.6 QUALITY ASSURANCE

- A. Source Limitations: Obtain plumbing fixtures, faucets, and other components of each category through one source from a single manufacturer.
  - 1. Exception: If fixtures, faucets, or other components are not available from a single manufacturer, obtain similar products from other manufacturers specified for that category.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- C. Regulatory Requirements: Comply with requirements in ICC A117.1, "Accessible and Usable Buildings and Facilities"; Public Law 90-480, "Architectural Barriers Act"; and Public Law 101-336, "Americans with Disabilities Act"; for plumbing fixtures for people with disabilities.

- D. Regulatory Requirements: Comply with requirements in Public Law 102-486, "Energy Policy Act," about water flow and consumption rates for plumbing fixtures.
- E. NSF Standard: Comply with NSF 61, "Drinking Water System Components--Health Effects," for fixture materials that will be in contact with potable water.
- F. Select combinations of fixtures and trim, faucets, fittings, and other components that are compatible.
- G. Comply with the following applicable standards and other requirements specified for plumbing fixtures:
  - 1. Enameled, Cast-Iron Fixtures: ASME A112.19.1M.
  - 2. Porcelain-Enameled, Formed-Steel Fixtures: ASME A112.19.4M.
  - 3. Slip-Resistant Bathing Surfaces: ASTM F 462.
  - 4. Solid-Surface-Material Lavatories and Sinks: ANSI/ICPA SS-1.
  - 5. Stainless-Steel Residential Sinks: ASME A112.19.3.
  - 6. Vitreous-China Fixtures: ASME A112.19.2M.
  - 7. Water-Closet, Flushometer Tank Trim: ASSE 1037.
  - 8. Whirlpool Bathtub Fittings: ASME A112.19.8M.
- H. Comply with the following applicable standards and other requirements specified for lavatory and sink faucets:
  - 1. Backflow Protection Devices for Faucets with Side Spray: ASME A112.18.3M.
  - 2. Backflow Protection Devices for Faucets with Hose-Thread Outlet: ASME A112.18.3M.
  - 3. Diverter Valves for Faucets with Hose Spray: ASSE 1025.
  - 4. Faucets: ASME A112.18.1.
  - 5. Hose-Connection Vacuum Breakers: ASSE 1011.
  - 6. Hose-Coupling Threads: ASME B1.20.7.
  - 7. Integral, Atmospheric Vacuum Breakers: ASSE 1001.
  - 8. NSF Potable-Water Materials: NSF 61.
  - 9. Pipe Threads: ASME B1.20.1.
  - 10. Sensor-Actuated Faucets and Electrical Devices: UL 1951.
  - 11. Supply Fittings: ASME A112.18.1.
  - 12. Brass Waste Fittings: ASME A112.18.2.
  - 13. NSF61 Appendage G-AB 1953. Lead free potable drinking faucets.
- I. Comply with the following applicable standards and other requirements specified for bathtub/shower and shower faucets:
  - 1. Backflow Protection Devices for Hand-Held Showers: ASME A112.18.3M.
  - 2. Combination, Pressure-Equalizing and Thermostatic-Control Antiscald Faucets: ASSE 1016.
  - 3. Deck-Mounted Bath/Shower Transfer Valves: ASME 18.7.
  - 4. Faucets: ASME A112.18.1.
  - 5. Hand-Held Showers: ASSE 1014.
  - 6. High-Temperature-Limit Controls for Thermal-Shock-Preventing Devices: ASTM F 445.
  - 7. Hose-Coupling Threads: ASME B1.20.7.



8. Manual-Control Antiscald Faucets: ASTM F 444.
9. Pipe Threads: ASME B1.20.1.
10. Pressure-Equalizing-Control Antiscald Faucets: ASTM F 444 and ASSE 1016.
11. Sensor-Actuated Faucets and Electrical Devices: UL 1951.
12. Thermostatic-Control Antiscald Faucets: ASTM F 444 and ASSE 1016.

J. Comply with the following applicable standards and other requirements specified for miscellaneous fittings:

1. Atmospheric Vacuum Breakers: ASSE 1001.
2. Brass and Copper Supplies: ASME A112.18.1.
3. Dishwasher Air-Gap Fittings: ASSE 1021.
4. Manual-Operation Flushometers: ASSE 1037.
5. Plastic Tubular Fittings: ASTM F 409.
6. Brass Waste Fittings: ASME A112.18.2.
7. Sensor-Operation Flushometers: ASSE 1037 and UL 1951.
8. NSF61 Appendage G-AB 1953. Lead free potable drinking faucets.

K. Comply with the following applicable standards and other requirements specified for miscellaneous components:

1. Disposers: ASSE 1008 and UL 430.
2. Dishwasher Air-Gap Fittings: ASSE 1021.
3. Flexible Water Connectors: ASME A112.18.6.
4. Floor Drains: ASME A112.6.3.
5. Grab Bars: ASTM F 446.
6. Hose-Coupling Threads: ASME B1.20.7.
7. Off-Floor Fixture Supports: ASME A112.6.1M.
8. Pipe Threads: ASME B1.20.1.
9. Plastic Toilet Seats: ANSI Z124.5.
10. Supply and Drain Protective Shielding Guards: ICC A117.1.

## 1.7 EXTRA MATERIALS

A. Furnish extra materials described below that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Faucet Washers and O-Rings: Equal to 10 percent of amount of each type and size installed.
2. Faucet Cartridges and O-Rings: Equal to 5 percent of amount of each type and size installed.
3. Flushometer Valve, Repair Kits: Equal to 10 percent of amount of each type installed, but no fewer than 12 of each type.
4. Provide hinged-top wood or metal box, or individual metal boxes, with separate compartments for each type and size of extra materials listed above.
5. Toilet Seats: Equal to 5 percent of amount of each type installed.

## PART 2 - PRODUCTS

### 2.1 LAVATORY FAUCETS

#### A. Lavatory Faucets:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Chicago Faucets.
  - b. T & S Brass and Bronze Works, Inc.

### 2.2 BATHTUB/SHOWER FAUCETS

#### A. Bathtub/Shower Faucets:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Chicago Faucets.
  - b. Leonard Valve Company.
  - c. Moen, Inc.
  - d. Powers; a Watts Industries Co.
  - e. Symmons Industries, Inc.
  - f. T & S Brass and Bronze Works, Inc.

### 2.3 SHOWER FAUCETS

#### A. Shower Faucets:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Chicago Faucets.
  - b. Leonard Valve Company.
  - c. Moen, Inc.
  - d. Powers; a Watts Industries Co.
  - e. Symmons Industries, Inc.
  - f. T & S Brass and Bronze Works, Inc.

### 2.4 SINK FAUCETS

#### A. Sink Faucets:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

- a. Chicago Faucets.
- b. T & S Brass and Bronze Works, Inc.

## 2.5 FLUSHOMETERS

### A. Flushometers:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Sloan Valve Company.
  - b. Zurn Plumbing Products Group; Commercial Brass Operation.

## 2.6 TOILET SEATS

### A. Toilet Seats:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Bemis Manufacturing Company.
  - b. Centoco Manufacturing Corp.
  - c. Church Seats.
  - d. Olsonite Corp.
  - e. Sperzel.
- 2. Description: Toilet seat for water-closet-type fixture.
  - a. Material: Molded, solid plastic with antimicrobial agent.
  - b. Configuration: Open front without cover.
  - c. Size: Elongated.
  - d. Hinge Type: CK, check.
  - e. Class: Heavy-duty commercial.
  - f. Color: White.

## 2.7 PROTECTIVE SHIELDING GUARDS

### A. Protective Shielding Pipe Covers:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Engineered Brass Co.
  - b. Insul-Tect Products Co.; a Subsidiary of MVG Molded Products.
  - c. McGuire Manufacturing Co., Inc.
  - d. Plumberex Specialty Products Inc.

- e. TCI Products.
  - f. TRUEBRO, Inc.
  - g. Zurn Plumbing Products Group; Tubular Brass Plumbing Products Operation.
2. Description: Manufactured plastic wraps for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with Americans with Disabilities Act (ADA) requirements. Product shall also meet the ASTM E 84 25/450 smoke and flame rating.

B. Protective Shielding Piping Enclosures:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. TRUEBRO, Inc.
2. Description: Manufactured plastic enclosure for covering plumbing fixture hot- and cold-water supplies and trap and drain piping. Comply with ADA requirements.

2.8 FIXTURE SUPPORTS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Josam Company.
2. MIFAB Manufacturing Inc.
3. Smith, Jay R. Mfg. Co.
4. Tyler Pipe; Wade Div.
5. Watts Drainage Products Inc.; a div. of Watts Industries, Inc.
6. Zurn Plumbing Products Group; Specification Drainage Operation.

B. Urinal Supports:

1. Description: Type I, urinal carrier with fixture support plates and coupling with seal and fixture bolts and hardware matching fixture for wall-mounting, urinal-type fixture. Include steel uprights with feet.
2. Accessible-Fixture Support: Include rectangular steel uprights.

C. Lavatory Supports:

1. Description: Type II, lavatory carrier with concealed arms and tie rod for wall-mounting, lavatory-type fixture. Include steel uprights with feet.
2. Accessible-Fixture Support: Include rectangular steel uprights.

2.9 WATER CLOSETS

A. Water Closets:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Standard Companies, Inc.
  - b. Eljer.
  - c. Kohler Co.

## 2.10 URINALS

### A. Urinals:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Standard Companies, Inc.
  - b. Eljer.
  - c. Kohler Co.

## 2.11 LAVATORIES

### A. Lavatories:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Standard Companies, Inc.
  - b. Eljer.
  - c. Kohler Co.

### B. Stainless Steel Lavatories:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Willoughby.
  - b. Whitehall.

## 2.12 COMMERCIAL SINKS

### A. Commercial Sinks:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Elkay Manufacturing Co.
  - b. Just Manufacturing Company.

## 2.13 BATHTUBS

### A. Bathtubs

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Standard Companies, Inc.
  - b. Eljer.
  - c. Kohler Co.

## 2.14 SERVICE SINKS

### A. Service Sinks:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Standard Companies, Inc.
  - b. Eljer.
  - c. Kohler Co.
  - d. Acorn.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine roughing-in of water supply and sanitary drainage and vent piping systems to verify actual locations of piping connections before plumbing fixture installation.
- B. Examine cabinets, counters, floors, and walls for suitable conditions where fixtures will be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Assemble plumbing fixtures, trim, fittings, and other components according to manufacturers' written instructions.
- B. Install off-floor supports, affixed to building substrate, for wall-mounting fixtures.
  1. Use carrier supports with waste fitting and seal for back-outlet fixtures.
  2. Use carrier supports without waste fitting for fixtures with tubular waste piping.
  3. Use chair-type carrier supports with rectangular steel uprights for accessible fixtures.

- C. Install back-outlet, wall-mounting fixtures onto waste fitting seals and attach to supports.
- D. Install floor-mounting fixtures on closet flanges or other attachments to piping or building substrate.
- E. Install wall-mounting fixtures with tubular waste piping attached to supports.
- F. Install counter-mounting fixtures in and attached to casework.
- G. Install fixtures level and plumb according to roughing-in drawings.
- H. Install water-supply piping with stop on each supply to each fixture to be connected to water distribution piping. Attach supplies to supports or substrate within pipe spaces behind fixtures. Install stops in locations where they can be easily reached for operation.
  - 1. Exception: Use ball, gate, or globe valves if supply stops are not specified with fixture. Valves are specified in Division 22 Section "General-Duty Valves for Plumbing Piping."
- I. Install trap and tubular waste piping on drain outlet of each fixture to be directly connected to sanitary drainage system.
- J. Install tubular waste piping on drain outlet of each fixture to be indirectly connected to drainage system.
- K. Install flushometer valves for accessible water closets and urinals with handle mounted on wide side of compartment. Install other actuators in locations that are easy for people with disabilities to reach.
- L. Install toilet seats on water closets.
- M. Install faucet-spout fittings with specified flow rates and patterns in faucet spouts if faucets are not available with required rates and patterns. Include adapters if required.
- N. Install water-supply flow-control fittings with specified flow rates in fixture supplies at stop valves.
- O. Install faucet flow-control fittings with specified flow rates and patterns in faucet spouts if faucets are not available with required rates and patterns. Include adapters if required.
- P. Install shower flow-control fittings with specified maximum flow rates in shower arms.
- Q. Install traps on fixture outlets.
  - 1. Exception: Omit trap on fixtures with integral traps.
  - 2. Exception: Omit trap on indirect wastes, unless otherwise indicated.
- R. Install escutcheons at piping wall ceiling penetrations in exposed, finished locations and within cabinets and millwork. Use deep-pattern escutcheons if required to conceal protruding fittings. Escutcheons are specified in Division 22 Section "Common Work Results for Plumbing."

- S. Set bathtubs and service basins in leveling bed of cement grout. Grout is specified in Division 22 Section "Common Work Results for Plumbing."
- T. Seal joints between fixtures and walls, floors, and countertops using sanitary-type, one-part, mildew-resistant silicone sealant. Match sealant color to fixture color. Sealants are specified in Division 07 Section "Joint Sealants."
- U. All plumbing fixtures are to be mounted at the height specified on the Architectural drawings.

### 3.3 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect fixtures with water supplies, stops, and risers, and with traps, soil, waste, and vent piping. Use size fittings required to match fixtures.
- C. Ground equipment according to Division 26 Section "Grounding and Bonding for Electrical Systems."
- D. Connect wiring according to Division 26 Section "Low-Voltage Electrical Power Conductors and Cables."

### 3.4 FIELD QUALITY CONTROL

- A. Verify that installed plumbing fixtures are categories and types specified for locations where installed.
- B. Check that plumbing fixtures are complete with trim, faucets, fittings, and other specified components.
- C. Inspect installed plumbing fixtures for damage. Replace damaged fixtures and components.
- D. Test installed fixtures after water systems are pressurized for proper operation. Replace malfunctioning fixtures and components, then retest. Repeat procedure until units operate properly.
- E. Install fresh batteries in sensor-operated mechanisms.

### 3.5 ADJUSTING

- A. Operate and adjust faucets and controls. Replace damaged and malfunctioning fixtures, fittings, and controls.
- B. Adjust water pressure at faucets and flushometer valves to produce proper flow and stream.
- C. Replace washers and seals of leaking and dripping faucets and stops.



- D. Install fresh batteries in sensor-operated mechanisms.

### 3.6 CLEANING

- A. Clean fixtures, faucets, and other fittings with manufacturers' recommended cleaning methods and materials. Do the following:
  - 1. Remove faucet spouts and strainers, remove sediment and debris, and reinstall strainers and spouts.
  - 2. Remove sediment and debris from drains.
- B. After completing installation of exposed, factory-finished fixtures, faucets, and fittings, inspect exposed finishes and repair damaged finishes.

### 3.7 PROTECTION

- A. Provide protective covering for installed fixtures and fittings.
- B. Do not allow use of plumbing fixtures for temporary facilities unless approved in writing by Owner.

END OF SECTION 22 4000

## SECTION 22 4500 - EMERGENCY PLUMBING FIXTURES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following emergency plumbing fixtures:
  - 1. Emergency showers.
  - 2. Eyewash equipment.
  - 3. Combination units.
  - 4. Water-tempering equipment.
- B. Related Sections include the following:
  - 1. Division 22 Section "Domestic Water Piping Specialties" for backflow preventers.
  - 2. Division 22 Section "Sanitary Waste Piping Specialties" for floor drains.

#### 1.3 DEFINITIONS

- A. Accessible Fixture: Emergency plumbing fixture that can be approached, entered, and used by people with disabilities.
- B. Plumbed Emergency Plumbing Fixture: Fixture with fixed, potable-water supply.
- C. Self-Contained Emergency Plumbing Fixture: Fixture with flushing-fluid-solution supply.
- D. Tepid: Moderately warm.

#### 1.4 WARRANTY

- A. Provide a one year factory warranty for all fixtures, faucets and valves from the date of substantial completion.

#### 1.5 SUBMITTALS

- A. Product Data: For each type of product indicated. Include flow rates and capacities, furnished specialties, and accessories.
- B. Shop Drawings: Diagram power, signal, and control wiring.

- C. Product Certificates: Submit certificates of performance testing specified in "Source Quality Control" Article.
- D. Field quality-control test reports.
- E. Operation and Maintenance Data: For emergency plumbing fixtures to include in maintenance manuals.

## 1.6 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. ANSI Standard: Comply with ANSI Z358.1, "Emergency Eyewash and Shower Equipment."
- C. Regulatory Requirements: Comply with requirements in ICC A117.1, "Accessible and Usable Buildings and Facilities"; Public Law 90-480, "Architectural Barriers Act" ; and Public Law 101-336, "Americans with Disabilities Act" ; for plumbing fixtures for people with disabilities.
- D. NSF Standard: Comply with NSF 61, "Drinking Water System Components--Health Effects," for fixture materials that will be in contact with potable water.

## PART 2 - PRODUCTS

### 2.1 EYE/FACE WASH EQUIPMENT

- A. Eye/Face Wash Equipment:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 2. Basis-of-Design Product: Subject to compliance with requirements, provide Guardian G1806 recessed swing down Eye/Face Wash Unit complete with thermostatic mixing valve or a comparable product by one of the following:
    - a. Bradley Corporation.
    - b. Encon Safety Products.
    - c. Guardian Equipment Co.
    - d. Haws Corporation.
    - e. Lab Safety Supply Inc.
    - f. Murdock, Inc.
    - g. Sellstrom Manufacturing Co.
    - h. Speakman Company.
    - i. Stingray Systems.
    - j. WaterSaver Faucet Co.
    - k. Western Emergency Equipment.

- l. Acorn Engineering
  3. Description: Plumbed, recessed eye/face wash equipment.
    - a. Capacity: Deliver potable water at rate not less than 3.0 gpm for at least 15 minutes.
    - b. Supply Piping: NPS 1/2 chrome-plated brass or stainless steel with flow regulator and stay-open control valve.
    - c. Control-Valve Actuator: swing down.
- B. Standard, Freestanding, Plumbed Eyewash Units,:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Acorn Safety; a division of Acorn Engineering Company.
    - b. Bradley Corporation.
    - c. Encon Safety Products.
    - d. Guardian Equipment Co.
    - e. Haws Corporation.
    - f. Sellstrom Manufacturing Company.
    - g. Speakman Company.
    - h. Stngray Systems.
    - i. WaterSaver Faucet Co.
  2. Capacity: Not less than 3.0 gpm for at least 15 minutes.
  3. Supply Piping: NPS 1/2 chrome-plated brass or stainless steel with flow regulator and stay-open control valve.
  4. Control-Valve Actuator: Paddle.
  5. Spray-Head Assembly: Two receptor-mounted spray heads.
  6. Receptor: Stainless-steel bowl.
  7. Mounting: Pedestal.

## 2.2 COMBINATION UNITS

- A. Combination Units:
  1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Bradley Corporation.
    - b. Chicago Faucets.
    - c. Encon Safety Products.
    - d. Guardian Equipment Co.
    - e. Haws Corporation.
    - f. Lab Safety Supply Inc.
    - g. Murdock, Inc.
    - h. Sellstrom Manufacturing Co.
    - i. Speakman Company.

- j. Stingray Systems.
- k. WaterSaver Faucet Co.
- l. Western Emergency Equipment.
- m. Acorn Engineering

B. Combination Units:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. B-L-S Industries, Inc.
  - b. Encon Safety Products.
  - c. Guardian Equipment Co.
  - d. Haws Corporation.
  - e. Speakman Company.
  - f. Stingray Systems.
  - g. Western Emergency Equipment.

C. Recessed Shower Units:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. B-L-S Industries, Inc.
  - b. Encon Safety Products.
  - c. Guardian Equipment Co.
  - d. Haws Corporation.
  - e. Speakman Company.
  - f. Stingray Systems.
  - g. Western Emergency Equipment.

## 2.3 WATER-TEMPERING EQUIPMENT

A. Water-Tempering Equipment:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Armstrong International, Inc.
  - b. Bradley Corporation.
  - c. Encon Safety Products.
  - d. Haws Corporation.
  - e. Lawler Manufacturing Co., Inc.
  - f. Leonard Valve Company.
  - g. Powers, a Watts Industries Co.
  - h. Speakman Company.
  - i. Stingray Systems.
  - j. Therm-Omega-Tech, Inc.
  - k. Western Emergency Equipment.

2. Description: Factory-fabricated, hot- and cold-water-tempering equipment with thermostatic mixing valve.
  - a. Thermostatic Mixing Valve: Designed to provide 85 deg F tepid, potable water at emergency plumbing fixtures, to maintain temperature at plus or minus 5 deg F throughout required 15-minute test period, and in case of unit failure to continue cold-water flow, with union connections, controls, metal piping, and corrosion-resistant enclosure. Provide flow rate required to equipment being served.

## 2.4 SOURCE QUALITY CONTROL

- A. Certify performance of plumbed emergency plumbing fixtures by independent testing agency acceptable to authorities having jurisdiction.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine roughing-in for water piping systems to verify actual locations of piping connections before plumbed emergency plumbing fixture installation.
  1. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 EMERGENCY PLUMBING FIXTURE INSTALLATION

- A. Assemble emergency plumbing fixture piping, fittings, control valves, and other components.
- B. Install fixtures level and plumb.
- C. Fasten fixtures to substrate.
- D. Install shutoff valves in water-supply piping to fixtures. Use ball, gate, or globe valve if specific type valve is not indicated. Install valves chained or locked in open position if permitted. Install valves in locations where they can easily be reached for operation. Valves are specified in Division 22 Section "General-Duty Valves for Plumbing Piping."
  1. Exception: Omit shutoff valve on supply to group of plumbing fixtures that includes emergency plumbing fixture.
  2. Exception: Omit shutoff valve on supply to emergency equipment if prohibited by authorities having jurisdiction.
- E. Install shutoff valve and strainer in steam piping and shutoff valve in condensate return piping.
- F. Install dielectric fitting in supply piping to fixture if piping and fixture connections are made of different metals. Dielectric fittings are specified in Division 22 Section "Common Work Results for Plumbing."

- G. Install thermometers in supply and outlet piping connections to water-tempering equipment. Thermometers are specified in Division 22 Section "Meters and Gages for Plumbing Piping."
- H. Install escutcheons on piping wall and ceiling penetrations in exposed, finished locations. Escutcheons are specified in Division 22 Section "Common Work Results for Plumbing."
- I. Fill self-contained fixtures with flushing fluid.
- J. Install equipment nameplates or equipment markers on fixtures and equipment signs on water-tempering equipment. Identification materials are specified in Division 22 Section "Identification for Plumbing Piping and Equipment."

### 3.3 CONNECTIONS

- A. Piping installation requirements are specified in other Division 22 Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Connect cold-water-supply piping to plumbed emergency plumbing fixtures not having water-tempering equipment.
- C. Connect hot- and cold-water-supply piping to hot- and cold-water-tempering equipment. Connect output from water-tempering equipment to emergency plumbing fixtures.

### 3.4 FIELD QUALITY CONTROL

- A. Mechanical-Component Testing: After plumbing connections have been made, test for compliance with requirements. Verify ability to achieve indicated capacities and temperatures.
- B. Electrical-Component Testing: After electrical circuitry has been energized, test for compliance with requirements.
  - 1. Test and adjust controls and safeties.
- C. Repair or replace malfunctioning units. Retest as specified above after repairs or replacements are made.
- D. Report test results in writing.

### 3.5 ADJUSTING

- A. Adjust or replace fixture flow regulators for proper flow.
- B. Adjust equipment temperature settings.

END OF SECTION 22 4500

## SECTION 22 6113 - COMPRESSED-AIR PIPING FOR LABORATORY AND HEALTHCARE FACILITIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Medical compressed-air piping, designated "medical air."
  - 2. Gas-powered-tool compressed-air piping, designated "instrument air."
  - 3. Healthcare laboratory compressed-air piping, designated "instrument air."

#### 1.3 DEFINITIONS

- A. Medical compressed-air piping systems include medical air, and, instrument air.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and testing agency.
- B. Seismic Qualification Certificates: For medical compressed-air manifolds, accessories, and components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- C. Material Certificates: Signed by Installer certifying that medical compressed-air piping materials comply with requirements in NFPA 99 for positive-pressure medical gas systems.
- D. Brazing certificates.



- E. Field quality-control reports.

## 1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For compressed-air piping specialties to include in emergency, operation, and maintenance manuals.

## 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Quick-Coupler Service Connections: Furnish complete noninterchangeable medical compressed-air pressure outlets.
    - a. Medical Air: Equal to 10 percent of amount installed.
    - b. Instrument Air: Equal to 10 percent of amount installed.
  - 2. D.I.S.S. Service Connections: Furnish complete medical compressed-air pressure outlets complying with CGA V-5.
    - a. Medical Air D.I.S.S. No. 1160: Equal to 10 percent of amount installed, but no fewer than 10 units.
    - b. Instrument Air D.I.S.S. No. 1160: Equal to 10 percent of amount installed, but no fewer than 10 units.

## 1.8 QUALITY ASSURANCE

- A. Installer Qualifications:
  - 1. Medical Air Piping Systems for Healthcare Facilities: According to ASSE Standard #6010 for medical-gas-system installers.
  - 2. Shape-Memory-Metal Coupling Joints: An authorized representative who is trained and approved by manufacturer.
- B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the vacuum piping testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL, and that is acceptable to authorities having jurisdiction.
  - 1. Qualify testing personnel according to ASSE Standard #6020 for medical-gas-system inspectors and ASSE Standard #6030 for medical-gas-system verifiers.
- C. Brazing: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code, Section IX, "Welding and Brazing Qualifications"; or AWS B2.2, "Standard for Brazing Procedure and Performance Qualification."

## PART 2 - PRODUCTS

### 2.1 SYSTEM DESCRIPTION

- A. Medical air operating at 50 to 55 psig.
- B. Instrument air operating at 175 psig.

### 2.2 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Medical compressed-air manifolds shall withstand the effects of earthquake motions determined according to ASCE/SEI 7 and with the requirements specified in Section 220548 Vibration and Seismic Controls for Plumbing Piping and Equipment.
  - 1. The term "withstand" means "the manifold will remain in place without separation of any parts when subjected to the seismic forces specified and the manifold will be fully operational after the seismic event."
  - 2. Component Importance Factor is 1.5.

### 2.3 PIPES, TUBES, AND FITTINGS

- A. Comply with NFPA 99 for medical air piping materials.
- B. Comply with ASME B31.9, "Building Services Piping," for instrument air piping operating at 150 psig or less.
- C. Copper Medical Gas Tube: ASTM B 819, Type K and Type L, seamless, drawn temper, that has been manufacturer cleaned, purged, and sealed for medical gas service or according to CGA G-4.1 for oxygen service. Include standard color marking "OXY," "MED," "OXY/MED," "OXY/ACR," or "ACR/MED" in green for Type K tube and in blue for Type L tube.
- D. Wrought-Copper Fittings: ASME B16.22, solder-joint pressure type that has been manufacturer cleaned, purged, and bagged for oxygen service according to CGA G-4.1.
- E. Copper Unions: ASME B16.22 or MSS SP-123, wrought-copper or cast-copper alloy.
- F. Cast-Copper-Alloy Flanges: ASME B16.24, Class 150.
  - 1. Pipe-Flange Gasket Materials: ASME B16.21, nonmetallic, flat, asbestos free, 1/8-inch maximum thickness, full-face type.
  - 2. Flange Bolts and Nuts: ASME B18.2.1, carbon steel.
- G. Shape-Memory-Metal Couplings:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Aerofit, Inc.
  - b. Smart Tap, Inc.
3. Description: Cryogenic compression fitting made of nickel-titanium, shape-memory alloy, and that has been manufacturer cleaned, purged, and sealed for oxygen service according to CGA G-4.1.

H. Flexible Pipe Connectors:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Flex-Hose Co., Inc.
  - b. Flexicraft Industries.
  - c. Hyspan Precision Products, Inc.
  - d. Mercer Gasket & Shim, Inc.
  - e. Metraflex Company (The).
  - f. Proco Products, Inc.
  - g. Unaflex.
  - h. Universal Metal Hose; a Hyspan Co.
3. Description: Corrugated-bronze tubing with bronze wire-braid covering and ends brazed to inner tubing.
  - a. Working-Pressure Rating: 200 psig minimum.
  - b. End Connections: Plain-end copper tube.

2.4 JOINING MATERIALS

- A. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys.
- B. Threaded-Joint Tape: PTFE.

2.5 VALVES

- A. General Requirements for Valves: Manufacturer cleaned, purged, and bagged according to CGA G-4.1 for oxygen service.
- B. Zone-Valve Box Assemblies: Box with medical gas valves, tube extensions, and gages.
  1. Zone-Valve Boxes:
    - a. Steel Box with Aluminum Cover:

- 1) Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- 2) Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:

- a) Allied Healthcare Products Inc.
- b) Amico Corporation.
- c) Ohio Medical Corporation.
- d) BeaconMedaes
- e) Patton's Medical

- b. Description: Formed steel box with cover, anchors for recessed mounting, holes with grommets in box sides for tubing extension protection, and of size for single or multiple valves with pressure gages and in sizes required to permit manual operation of valves. Medical air and medical vacuum tubing, valves, and gages may be incorporated in zone valve boxes for medical gases.

- 1) Interior Finish: Factory-applied white enamel.
- 2) Cover Plate: Aluminum with frangible or removable windows.
- 3) Valve-Box Windows: Clear or tinted transparent plastic with labeling that includes rooms served, according to NFPA 99.

C. Ball Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Allied Healthcare Products Inc.; Chemetron Division.
  - b. Amico Corporation.
  - c. BeaconMedaes.
  - d. Conbraco Industries, Inc.
  - e. Marwin Valve; a division of Richards Industries.
  - f. NIBCO INC.
  - g. Ohio Medical Corporation.
  - h. Tri-Tech Medical Inc.
  - i. Patton's Medical
3. Standard: MSS SP-110.
4. Description: Three-piece body, brass or bronze.
5. Pressure Rating: 300 psig minimum.
6. Ball: Full-port, chrome-plated brass.
7. Seats: PTFE or TFE.
8. Handle: Lever type with locking device.
9. Stem: Blowout proof with PTFE or TFE seal.
10. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.

D. Check Valves:

1. Manufacturers: Subject to compliance with requirements provide products by one of the following:
2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Allied Healthcare Products Inc.; Chemetron Division.
  - b. Amico Corporation.
  - c. BeaconMedaes.
  - d. Conbraco Industries, Inc.
  - e. Ohio Medical Corporation.
  - f. Patton's Medical
  - g. Tri-Tech Medical Inc.
3. Description: In-line pattern, bronze.
4. Pressure Rating: 300 psig minimum.
5. Operation: Spring loaded.
6. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.

E. Safety Valves:

1. Bronze body.
2. ASME-construction, poppet, pressure-relief type.
3. Settings to match system requirements.

F. Pressure Regulators:

1. Bronze body and trim.
2. Spring-loaded, diaphragm-operated, relieving type.
3. Manual pressure-setting adjustment.
4. Rated for 250-psig minimum inlet pressure.
5. Capable of controlling delivered air pressure within 0.5 psig for each 10-psig inlet pressure.

2.6 MEDICAL COMPRESSED-AIR SERVICE CONNECTIONS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- B. Basis-of-Design Product: Subject to compliance with requirements, provide Chemetron compatible outlets by one of the following:
  1. BeaconMedaes.
- C. General Requirements for Medical Compressed-Air Service Connections:
  1. Suitable for specific medical air pressure and service listed.
  2. Include roughing-in assemblies, finishing assemblies, and cover plates.
  3. Individual cover plates are not required if service connection is in multiple unit or assembly with cover plate.
  4. Recessed-type units made for concealed piping unless otherwise indicated.

D. Roughing-in Assembly:

1. Steel outlet box for recessed mounting and concealed piping.
2. Brass-body outlet block with secondary check valve that will prevent gas flow when primary valve is removed.
3. Double seals that will prevent air leakage.
4. ASTM B 819, NPS 3/8 copper outlet tube brazed to valve with service marking and tube-end dust cap.

E. Finishing Assembly:

1. Brass housing with primary check valve.
2. Double seals that will prevent air leakage.
3. Cover plate with gas-service label.

F. Quick-Coupler Pressure Service Connections:

1. Outlets for medical air and instrument air with noninterchangeable keyed indexing to prevent interchange between services.
2. Constructed to permit one-handed connection and removal of equipment.
3. With positive-locking ring that retains equipment stem in valve during use.

G. D.I.S.S. Pressure Service Connections: Outlets, complying with CGA V-5, with threaded indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment.

1. Medical Air: D.I.S.S. No. 1160.
2. Instrument Air: D.I.S.S. No. 1160.

H. Cover Plates:

1. One piece.
2. Aluminum or stainless steel.
3. Permanent, color-coded, identifying label matching corresponding service.

2.7 MEDICAL COMPRESSED-AIR PRESSURE CONTROL PANELS

A. Manufacturers: Subject to compliance with requirements provide products by one of the following:

B. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:

1. Allied Healthcare Products Inc.; Chemetron Division.
2. Amico Corporation.
3. BeaconMedaes.
4. Patton's Medical

C. Description:

1. Steel box and support brackets for recessed roughing-in with stainless-steel or anodized-aluminum cover plate with printed operating instructions.
2. Manifold assembly consisting of inlet supply valve, inlet supply pressure gage, line-pressure control regulator, outlet supply pressure gage, D.I.S.S. service connection, and piping outlet for remote service connection.
3. Minimum Working Pressure: 200 psig.
4. Line-Pressure Control Regulator: Self-relieving diaphragm type with precision manual adjustment.
5. Pressure Gages: 0 to 300 psig.
6. Service Connection: CGA V-5, D.I.S.S. No. 1160, instrument air outlet.
7. Before final assembly, provide temporary dust shield and U-tube for testing.
8. Label cover plate "Air Pressure Control."

## 2.8 NITROGEN

- A. Comply with USP 32 - NF 27 for oil-free dry nitrogen.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Cleaning of Medical Gas Tubing: If manufacturer-cleaned and -capped fittings or tubing is not available or if precleaned fittings or tubing must be recleaned because of exposure, have supplier or separate agency acceptable to authorities having jurisdiction perform the following procedures:
  1. Clean medical gas tube and fittings, valves, gages, and other components of oil, grease, and other readily oxidizable materials as required for oxygen service according to CGA G-4.1.
  2. Wash medical gas tubing and components in hot, alkaline-cleaner-water solution of sodium carbonate or trisodium phosphate in proportion of 1 lb of chemical to 3 gal. of water.
    - a. Scrub to ensure complete cleaning.
    - b. Rinse with clean, hot water to remove cleaning solution.

### 3.2 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of compressed-air piping. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, air-compressor sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Comply with NFPA 99 for installation of compressed-air piping.

- C. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal and coordinate with other services occupying that space.
- F. Install piping adjacent to equipment and specialties to allow service and maintenance.
- G. Install compressed-air piping with 1 percent slope downward in direction of flow.
- H. Install nipples, unions, special fittings, and valves with pressure ratings same as or higher than system pressure rating used in applications specified in "Piping Schedule" Article unless otherwise indicated.
- I. Install eccentric reducers, if available, where compressed-air piping is reduced in direction of flow, with bottoms of both pipes and reducer fitting flush.
- J. Install branch connections to compressed-air mains from top of main. Provide drain leg and drain trap at end of each main and branch and at low points.
- K. Install thermometer and pressure gage on discharge piping from each air compressor and on each receiver. Comply with requirements in Section 220519 "Meters and Gages for Plumbing Piping."
- L. Install piping to permit valve servicing.
- M. Install piping free of sags and bends.
- N. Install fittings for changes in direction and for branch connections.
- O. Install medical air piping to medical air service connections specified in this Section, to medical air service connections in equipment specified in Section 226313 "Gas Piping for Laboratory and Healthcare Facilities," and to equipment specified in other Sections requiring medical air service.
- P. Piping Restraint Installation: Install seismic restraints on compressed-air piping. Seismic-restraint devices are specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- Q. Install compressed-air service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.
- R. Connect compressed-air piping to air compressors and to compressed-air outlets and equipment requiring compressed-air service.



- S. Install unions in copper compressed-air tubing adjacent to each valve and at final connection to each machine, specialty, and piece of equipment.
- T. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."
- U. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

### 3.3 VALVE INSTALLATION

- A. Install shutoff valve at each connection to and from compressed-air equipment and specialties.
- B. Install check valves to maintain correct direction of compressed-air flow from compressed-air equipment.
- C. Install valve boxes recessed in wall and anchored to substrate. Single boxes may be used for multiple valves that serve same area or function.
- D. Install zone valves and gages in valve boxes. Rotate valves to angle that prevents closure of cover when valve is in closed position.
- E. Install pressure regulators on compressed-air piping where reduced pressure is required.
- F. Install flexible pipe connectors in discharge piping and in inlet air piping from remote air-inlet filter of each air compressor.

### 3.4 JOINT CONSTRUCTION

- A. Remove scale, slag, dirt, and debris from outside of cleaned tubing and fittings before assembly.
- B. Threaded Joints: Apply appropriate tape to external pipe threads.
- C. Brazed Joints: Join copper tube and fittings according to CDA's "Copper Tube Handbook," "Brazed Joints" chapter. Continuously purge joint with oil-free dry nitrogen during brazing.
- D. Flanged Joints: Install flange on copper tubes. Use pipe-flange gasket between flanges. Join flanges with gasket and bolts according to ASME B31.9 for bolting procedure.
- E. Shape-Memory-Metal Coupling Joints: Join new copper tube to existing tube according to procedures developed by fitting manufacturer for installation of shape-memory-metal coupling joints.

### 3.5 COMPRESSED-AIR SERVICE COMPONENT INSTALLATION

- A. Install compressed-air pressure control panel in walls. Attach to substrate.

### 3.6 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices.
- B. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support devices.
- C. Vertical Piping: MSS Type 8 or Type 42, clamps.
- D. Individual, Straight, Horizontal Piping Runs:
  - 1. 100 Feet and Less: MSS Type 1, adjustable, steel, clevis hangers.
  - 2. Longer Than 100 Feet: MSS Type 43, adjustable, roller hangers.
- E. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for trapeze hangers.
- F. Base of Vertical Piping: MSS Type 52, spring hangers.
- G. Support horizontal piping within 12 inches of each fitting and coupling.
- H. Rod diameter may be reduced one size for double-rod hangers, with 3/8-inch- minimum rods.
- I. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 1/4: 60 inches with 3/8-inch rod.
  - 2. NPS 3/8 and NPS 1/2: 72 inches with 3/8-inch rod.
  - 3. NPS 3/4: 84 inches with 3/8-inch rod.
  - 4. NPS 1: 96 inches with 3/8-inch rod.
  - 5. NPS 1-1/4: 108 inches with 3/8-inch rod.
  - 6. NPS 1-1/2: 10 feet with 3/8-inch rod.
  - 7. NPS 2: 11 feet with 3/8-inch rod.
  - 8. NPS 2-1/2: 13 feet with 1/2-inch rod.
  - 9. NPS 3: 14 feet with 1/2-inch rod.
  - 10. NPS 3-1/2: 15 feet with 1/2-inch rod.
  - 11. NPS 4: 16 feet with 1/2-inch rod.
- J. Install supports for vertical copper tubing every 10 feet.

### 3.7 IDENTIFICATION

- A. Install identifying labels and devices for medical compressed-air piping systems according to NFPA 99. Use the following or similar captions and color-coding for piping products where required by NFPA 99:
  - 1. Medical Air: Black letters on yellow background.

2. Instrument Air: White letters on red background.
3. Medical Laboratory Air: Black letters on yellow-and-white checkerboard background.

### 3.8 FIELD QUALITY CONTROL FOR MEDICAL COMPRESSED-AIR PIPING IN HEALTHCARE FACILITIES

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections of medical compressed-air piping in healthcare facilities and to prepare test and inspection reports.
- B. Tests and Inspections:
  1. Medical Compressed-Air Testing Coordination: Perform tests, inspections, verifications, and certification of medical compressed-air piping systems concurrently with tests, inspections, and certification of medical gas piping and medical vacuum piping systems.
  2. Preparation: Perform the following Installer tests according to requirements in NFPA 99 and ASSE Standard #6010:
    - a. Initial blowdown.
    - b. Initial pressure test.
    - c. Cross-connection test.
    - d. Piping purge test.
    - e. Standing pressure test for positive-pressure medical compressed-air piping.
    - f. Repair leaks and retest until no leaks exist.
  3. System Verification: Perform the following tests and inspections according to NFPA 99, ASSE Standard #6020, and ASSE Standard #6030:
    - a. Standing pressure test.
    - b. Individual-pressurization or pressure-differential cross-connection test.
    - c. Valve test.
    - d. Master and area alarm tests.
    - e. Piping purge test.
    - f. Piping particulate test.
    - g. Piping purity test.
    - h. Final tie-in test.
    - i. Operational pressure test.
    - j. Medical air purity test.
    - k. Verify correct labeling of equipment and components.
  4. Testing Certification: Certify that specified tests, inspections, and procedures have been performed and certify report results. Include the following:
    - a. Inspections performed.
    - b. Procedures, materials, and gases used.
    - c. Test methods used.
    - d. Results of tests.

- C. Remove and replace components that do not pass tests and inspections and retest as specified above.

### 3.9 PROTECTION

- A. Protect tubing from damage.
- B. Retain sealing plugs in tubing, fittings, and specialties until installation.
- C. Clean tubing not properly sealed, and where sealing is damaged, according to "Preparation" Article.

### 3.10 PIPING SCHEDULE

- A. Connect new tubing to existing tubing with memory-metal couplings.
- B. Flanges may be used where connection to flanged equipment is required.
- C. Medical Air Piping and Instrument Air Piping: Type L, copper medical gas tube; wrought-copper fittings; and brazed joints.

### 3.11 VALVE SCHEDULE

- A. Shutoff Valves: Ball valve with manufacturer-installed ASTM B 819, copper-tube extensions.
- B. Zone Valves: Ball valve with manufacturer-installed ASTM B 819, copper-tube extensions with pressure gage on one copper-tube extension.

END OF SECTION 22 6113

## SECTION 22 6213 - VACUUM PIPING FOR LABORATORY AND HEALTHCARE FACILITIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Medical-surgical vacuum piping, designated "medical vacuum."
  - 2. Waste anesthetic gas disposal piping, designated "WAGD."

#### 1.3 DEFINITIONS

- A. WAGD: Waste anesthetic gas disposal.
- B. Medical vacuum piping systems include medical vacuum, WAGD, dental vacuum, HVE, and medical laboratory vacuum piping systems.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and testing agency.
- B. Material Certificates: Signed by Installer certifying that medical vacuum piping materials comply with requirements in NFPA 99.
- C. Brazing certificates.
- D. Field quality-control reports.

#### 1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For vacuum piping specialties to include in emergency, operation, and maintenance manuals.

## 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Quick-Coupler Service Connections: Furnish complete noninterchangeable medical vacuum suction inlets.
    - a. Medical Vacuum: Equal to 10 percent of amount installed, but no fewer than 10 units.
    - b. WAGD: Equal to 10 percent of amount installed, but no fewer than 10 units.
  - 2. D.I.S.S. Service Connections: Furnish complete medical vacuum suction inlets complying with CGA V-5.
    - a. Medical Vacuum D.I.S.S. No. 1220: Equal to 10 percent of amount installed, but no fewer than 10 units.
    - b. WAGD D.I.S.S. No. 2220: Equal to 10 percent of amount installed, but no fewer than 10 units.

## 1.8 QUALITY ASSURANCE

- A. Installer Qualifications:
  - 1. Medical Vacuum Piping Systems for Healthcare Facilities: According to ASSE Standard #6010 for medical-gas-system installers.
  - 2. Shape-Memory-Metal Coupling Joints: An authorized representative who is trained and approved by manufacturer.
- B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the vacuum piping testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL, and that is acceptable to authorities having jurisdiction.
  - 1. Qualify testing personnel according to ASSE Standard #6020 for medical-gas-system inspectors and ASSE Standard #6030 for medical-gas-system verifiers.
- C. Brazing: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code, Section IX, "Welding and Brazing Qualifications"; or AWS B2.2, "Standard for Brazing Procedure and Performance Qualification."

## PART 2 - PRODUCTS

### 2.1 SYSTEM DESCRIPTION

- A. Medical vacuum operating at 15 in. Hg.

- B. WAGD operating at 15 in. Hg.

## 2.2 PIPES, TUBES, AND FITTINGS

- A. Comply with NFPA 99 for medical vacuum piping materials.
- B. Copper Medical Gas Tube: ASTM B 819, Type L, seamless, drawn temper that has been manufacturer cleaned, purged, and sealed for medical gas service or according to CGA G-4.1 for oxygen service. Include standard color marking "OXY," "MED," "OXY/MED," "OXY/ACR," or "ACR/MED" in blue.
- C. Wrought-Copper Fittings: ASME B16.22, solder-joint pressure type that has been manufacturer cleaned, purged, and sealed for medical gas service or according to CGA G-4.1 for oxygen service.
- D. Copper Unions: ASME B16.22 or MSS SP-123, wrought-copper or cast-copper alloy.
- E. Cast-Copper-Alloy Flanges: ASME B16.24, Class 150.
  - 1. Pipe-Flange Gasket Materials: ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness, full-face type.
  - 2. Flange Bolts and Nuts: ASME B18.2.1, carbon steel.
- F. Shape-Memory-Metal Couplings:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
    - a. Aerofit, Inc.
    - b. Smart Tap, Inc.
  - 3. Description: Cryogenic compression fitting made of nickel-titanium, shape-memory alloy, and that has been manufacturer cleaned, purged, and sealed for oxygen service according to CGA G-4.1.
- G. Flexible Pipe Connectors:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 2. Basis-of-Design Product: Subject to compliance with requirements, product by one of the following:
    - a. Flex-Hose Co., Inc.
    - b. Flexicraft Industries.
    - c. Hyspan Precision Products, Inc.
    - d. Mercer Gasket & Shim, Inc.
    - e. Metraflex Company (The).

- f. Proco Products, Inc.
  - g. Unaflex.
  - h. Universal Metal Hose; a Hyspan Co.
- 3. Description: Corrugated-bronze tubing with bronze wire-braid covering and ends brazed to inner tubing.
  - a. Working-Pressure Rating: 200 psig minimum.
  - b. End Connections: Plain-end copper tube.

## 2.3 JOINING MATERIALS

- A. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- B. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys.
- C. Threaded-Joint Tape: PTFE.

## 2.4 VALVES

- A. General Requirements for Valves: Manufacturer cleaned, purged, and bagged according to CGA G-4.1 for oxygen service.
  - 1. Exception: Factory cleaning and bagging are not required for valves for WAGD service.
- B. Zone-Valve Box Assemblies: Box with medical gas valves, tube extensions, and gages.
  - 1. Zone-Valve Boxes:
    - a. Steel Box with Aluminum Cover:
      - 1) Manufacturers: Subject to compliance with requirements, provide products by one of the following:
      - 2) Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
        - a) Allied Healthcare Products Inc.
        - b) Amico Corporation.
        - c) Ohio Medical Corporation.
        - d) BeaconMedaes
        - e) Patton's Medical
    - b. Description: Formed steel box with cover, anchors for recessed mounting, holes with grommets in box sides for tubing extension protection, and of size for single or multiple valves with pressure gages and in sizes required to permit manual operation of valves. Medical air and medical vacuum tubing, valves, and gages may be incorporated in zone valve boxes for medical gases.



- 1) Interior Finish: Factory-applied white enamel.
- 2) Cover Plate: Aluminum with frangible or removable windows.
- 3) Valve-Box Windows: Clear or tinted transparent plastic with labeling that includes rooms served, according to NFPA 99.

C. Copper-Alloy Ball Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Allied Healthcare Products Inc.; Chemetron Division.
  - b. Amico Corporation.
  - c. BeaconMedaes.
  - d. Conbraco Industries, Inc.
  - e. Marwin Valve; a division of Richards Industries.
  - f. NIBCO INC.
  - g. Ohio Medical Corporation.
  - h. Tri-Tech Medical Inc.
  - i. Patton's Medical
3. Standard: MSS SP-110.
4. Description: Three-piece body, brass or bronze.
5. Pressure Rating: 300 psig minimum.
6. Ball: Full-port, chrome-plated brass.
7. Seats: PTFE or TFE.
8. Handle: Lever type with locking device.
9. Stem: Blowout proof with PTFE or TFE seal.
10. Ends: manufacturer-installed ASTM B 819, copper-tube extensions with pressure gage on one copper-tube extension.

D. Check Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Allied Healthcare Products Inc.; Chemetron Division.
  - b. Amico Corporation.
  - c. BeaconMedaes.
  - d. Conbraco Industries, Inc.
  - e. Ohio Medical Corporation.
  - f. Tri-Tech Medical Inc.
  - g. Patton's Medical
3. Description: In-line pattern, bronze.
4. Pressure Rating: 300 psig minimum.
5. Operation: Spring loaded.

6. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.

## 2.5 MEDICAL VACUUM SERVICE CONNECTIONS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- B. Basis-of-Design Product: Subject to compliance with requirements, provide Chemetron compatible product by one of the following:
  1. BeaconMedaes.
- C. General Requirements for Medical Vacuum Service Connections:
  1. Suitable for specific medical vacuum service listed.
  2. Include roughing-in assemblies, finishing assemblies, and cover plates.
  3. Individual cover plates are not required if service connection is in multiple unit or assembly with cover plate.
  4. Recessed-type units made for concealed piping unless otherwise indicated.
- D. Roughing-in Assembly:
  1. Steel outlet box for recessed mounting and concealed piping.
  2. Brass-body inlet block.
  3. Seals that will prevent vacuum leakage.
  4. ASTM B 819, NPS 3/8 copper outlet tube brazed to valve with service marking and tube-end dust cap.
- E. Finishing Assembly:
  1. Brass housing with primary check valve.
  2. Seals that will prevent vacuum leakage.
  3. Cover plate with gas-service label.
- F. Quick-Coupler Suction Service Connections:
  1. Inlets for medical vacuum and WAGD with noninterchangeable keyed indexing to prevent interchange between services.
  2. Constructed to permit one-handed connection and removal of equipment.
  3. With positive-locking ring that retains equipment stem in valve during use.
- G. D.I.S.S. Suction Service Connections:
  1. Inlets complying with CGA V-5.
  2. Threaded indexing to prevent interchange between services.
  3. Constructed to permit one-handed connection and removal of equipment.
  4. Medical Vacuum: CGA V-5, D.I.S.S. No. 1220.
  5. WAGD: CGA V-5, D.I.S.S. No. 2220.

- H. Vacuum Bottle Brackets: One piece, with pattern and finish matching corresponding service cover plate.
- I. Cover Plates:
  - 1. One piece.
  - 2. Aluminum or stainless steel.
  - 3. Permanent, color-coded, identifying label matching corresponding service.

## 2.6 NITROGEN

- A. Comply with USP 32 - NF 27 for oil-free dry nitrogen.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Cleaning of Medical Gas Tubing: If manufacturer-cleaned and -capped fittings or tubing is not available or if precleaned fittings or tubing must be recleaned because of exposure, have supplier or separate agency acceptable to authorities having jurisdiction perform the following procedures:
  - 1. Clean medical gas tube and fittings, valves, gages, and other components of oil, grease, and other readily oxidizable materials as required for oxygen service according to CGA G-4.1.
  - 2. Wash medical gas tubing and components in hot, alkaline-cleaner-water solution of sodium carbonate or trisodium phosphate in proportion of 1 lb of chemical to 3 gal. of water.
    - a. Scrub to ensure complete cleaning.
    - b. Rinse with clean, hot water to remove cleaning solution.

### 3.2 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of vacuum piping. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, vacuum producer sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Comply with NFPA 99 for installation of vacuum piping.
- C. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.

- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal and coordinate with other services occupying that space.
- F. Install piping adjacent to equipment and specialties to allow service and maintenance.
- G. Install vacuum piping with 1 percent slope downward in direction of flow.
- H. Install nipples, unions, special fittings, and valves with pressure ratings same as or higher than piping pressure rating used in applications specified in "Piping Schedule" Article unless otherwise indicated.
- I. Install eccentric reducers, if available, where vacuum piping is reduced in direction of flow, with bottoms of both pipes and reducer fitting flush.
- J. Provide drain leg and drain trap at end of each main and branch and at low points.
- K. Install thermometer and vacuum gage on inlet piping to each vacuum producer and on each receiver and separator. Comply with requirements in Section 220519 "Meters and Gages for Plumbing Piping."
- L. Install piping to permit valve servicing.
- M. Install piping free of sags and bends.
- N. Install fittings for changes in direction and for branch connections. Extruded-tee branch outlets in copper tubing may be made where specified.
- O. Install medical vacuum piping from medical vacuum service connections specified in this Section, to equipment specified in Section 226219 "Vacuum Equipment for Laboratory and Healthcare Facilities," and to equipment specified in other Sections requiring medical vacuum service.
- P. Piping Restraint Installation: Install seismic restraints on vacuum piping. Seismic-restraint devices are specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- Q. Install medical vacuum service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.
- R. Install medical vacuum bottle bracket adjacent to each wall-mounted medical vacuum service connection suction inlet.
- S. Connect vacuum piping to vacuum producers and to equipment requiring vacuum service.
- T. Install unions in copper vacuum tubing adjacent to each valve and at final connection to each machine, specialty, and piece of equipment.

- U. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."
- V. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

### 3.3 VALVE INSTALLATION

- A. Install shutoff valve at each connection to and from vacuum equipment and specialties.
- B. Install check valves to maintain correct direction of vacuum flow to vacuum-producing equipment.
- C. Install valve boxes recessed in wall and anchored to substrate. Single boxes may be used for multiple valves that serve same area or function.
- D. Install zone valves and gages in valve boxes. Rotate valves to angle that prevents closure of cover when valve is in closed position.
- E. Install flexible pipe connectors in suction inlet piping to each vacuum producer.

### 3.4 JOINT CONSTRUCTION

- A. Ream ends of pipes and tubes and remove burrs.
- B. Remove scale, slag, dirt, and debris from outside of cleaned tubing and fittings before assembly.
- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Threaded Joints: Apply appropriate tape to external pipe threads.
- E. Brazed Joints: Join copper tube and fittings according to CDA's "Copper Tube Handbook," "Braze Joints" chapter. Do not use flux. Continuously purge joint with oil-free dry nitrogen during brazing.
- F. Flanged Joints:
  - 1. Copper Tubing: Install flange on copper tubes. Use pipe-flange gasket between flanges. Join flanges with gasket and bolts according to ASME B31.9 for bolting procedure.
  - 2. PVC Piping: Install PVC flange on PVC pipes. Use pipe-flange gasket between flanges. Join flanges with gasket and bolts according to ASME B31.9 for bolting procedure.
- G. Shape-Memory-Metal Coupling Joints: Join new copper tube to existing tube according to procedures developed by fitting manufacturer for installation of shape-memory-metal coupling joints.

### 3.5 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices.
- B. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support devices.
- C. Vertical Piping: MSS Type 8 or Type 42, clamps.
- D. Individual, Straight, Horizontal Piping Runs:
  - 1. 100 Feet and Less: MSS Type 1, adjustable, steel, clevis hangers.
  - 2. Longer Than 100 Feet: MSS Type 43, adjustable, roller hangers.
- E. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for trapeze hangers.
- F. Base of Vertical Piping: MSS Type 52, spring hangers.
- G. Support horizontal piping within 12 inches of each fitting and coupling.
- H. Rod diameter may be reduced one size for double-rod hangers, with 3/8-inch- minimum rods.
- I. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 1/4: 60 inches with 3/8-inch rod.
  - 2. NPS 3/8 and NPS 1/2: 72 inches with 3/8-inch rod.
  - 3. NPS 3/4: 84 inches with 3/8-inch rod.
  - 4. NPS 1: 96 inches with 3/8-inch rod.
  - 5. NPS 1-1/4: 108 inches with 3/8-inch rod.
  - 6. NPS 1-1/2: 10 feet with 3/8-inch rod.
  - 7. NPS 2: 11 feet with 3/8-inch rod.
  - 8. NPS 2-1/2: 13 feet with 1/2-inch rod.
  - 9. NPS 3: 14 feet with 1/2-inch rod.
  - 10. NPS 3-1/2: 15 feet with 1/2-inch rod.
  - 11. NPS 4: 16 feet with 1/2-inch rod.
  - 12. NPS 6: 20 feet with 5/8-inch rod.
- J. Install supports for vertical copper tubing every 10 feet.

### 3.6 IDENTIFICATION

- A. Install identifying labels and devices for laboratory vacuum piping, valves, and specialties. Comply with requirements in Section 220553 "Identification for Plumbing Piping and Equipment."

- B. Install identifying labels and devices for medical vacuum piping systems according to NFPA 99. Use the following or similar captions and color-coding for piping products where required by NFPA 99:

- 1. Medical Vacuum: Black letters on white background.
- 2. WAGD: White letters on violet background.

### 3.7 FIELD QUALITY CONTROL FOR HEALTHCARE FACILITY MEDICAL VACUUM PIPING

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections of medical vacuum piping systems in healthcare facilities and to prepare test and inspection reports.

- B. Tests and Inspections:

- 1. Medical Vacuum Testing Coordination: Perform tests, inspections, verifications, and certification of medical vacuum piping systems concurrently with tests, inspections, and certification of medical compressed-air piping and medical gas piping systems.
- 2. Preparation: Perform the following Installer tests according to requirements in NFPA 99 and ASSE Standard #6010:
  - a. Initial blowdown.
  - b. Initial pressure test.
  - c. Cross-connection test.
  - d. Piping purge test.
  - e. Standing pressure test for vacuum systems.
  - f. Repair leaks and retest until no leaks exist.
- 3. System Verification: Perform the following tests and inspections according to NFPA 99, ASSE Standard #6020, and ASSE Standard #6030:
  - a. Standing pressure test.
  - b. Individual-pressurization or pressure-differential cross-connection test.
  - c. Valve test.
  - d. Master and area alarm tests.
  - e. Piping purge test.
  - f. Final tie-in test.
  - g. Operational vacuum test.
  - h. Verify correct labeling of equipment and components.
- 4. Testing Certification: Certify that specified tests, inspections, and procedures have been performed and certify report results. Include the following:
  - a. Inspections performed.
  - b. Procedures, materials, and gases used.
  - c. Test methods used.
  - d. Results of tests.

- C. Remove and replace components that do not pass tests and inspections and retest as specified above.

### 3.8 FIELD QUALITY CONTROL FOR LABORATORY FACILITY NONMEDICAL VACUUM PIPING

- A. Testing Agency: Engage qualified testing agency to perform field tests and inspections of vacuum piping in nonmedical laboratory facilities and to prepare test and inspection reports.
- B. Tests and Inspections:
  - 1. Piping Leak Tests for Vacuum Piping: Test new and modified parts of existing piping. Cap and fill vacuum piping with oil-free, dry nitrogen. Isolate test source and let stand for four hours to equalize temperature. Refill system, if required, to test pressure; hold for two hours with no drop in pressure.
    - a. Test Pressure for Copper Tubing: 100 psig.
  - 2. Repair leaks and retest until no leaks exist.
  - 3. Inspect filters for proper operation.
- C. Remove and replace components that do not pass tests and inspections and retest as specified above.

### 3.9 PROTECTION

- A. Protect tubing from damage.
- B. Retain sealing plugs in tubing, fittings, and specialties until installation.
- C. Clean tubing not properly sealed, and where sealing is damaged, according to "Preparation" Article.

### 3.10 PIPING SCHEDULE

- A. Connect new copper tubing to existing copper tubing with memory-metal couplings.
- B. Flanges may be used where connection to flanged equipment is required.
- C. Medical Vacuum Piping: Use copper medical gas tube, wrought-copper fittings, and brazed joints.
- D. WAGD Piping: Use copper medical gas tube, wrought-copper fittings, and brazed joints.

### 3.11 VALVE SCHEDULE

- A. Shutoff Valves:



1. Copper Tubing: Copper-alloy ball valve with manufacturer-installed ASTM B 819, copper-tube extensions.
- B. Zone Valves: Copper-alloy ball valve with manufacturer-installed ASTM B 819, copper-tube extensions with pressure gage on one copper-tube extension.

END OF SECTION 22 6213

## SECTION 22 6313 - GAS PIPING FOR LABORATORY AND HEALTHCARE FACILITIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Carbon dioxide piping, designated "medical carbon dioxide."
  - 2. Nitrogen piping, designated "medical nitrogen."
  - 3. Nitrous oxide piping, designated "medical nitrous oxide."
  - 4. Oxygen piping, designated "medical oxygen."

#### 1.3 DEFINITIONS

- A. CR: Chlorosulfonated polyethylene synthetic rubber.
- B. Medical gas piping systems include medical carbon dioxide, medical nitrogen, medical nitrous oxide, and medical oxygen for healthcare facility patient care.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
- B. Shop Drawings: Include diagrams for power, signal, and control wiring.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For Installer and testing agency.
- B. Seismic Qualification Certificates: For gas manifolds and bulk gas storage tanks, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

- C. Material Certificates: Signed by Installer certifying that medical gas piping materials comply with requirements in NFPA 99 for positive-pressure medical gas systems.
- D. Brazing certificates.
- E. Certificates of Shop Inspection and Data Report for Bulk Gas Storage Tanks: As required by ASME Boiler and Pressure Vessel Code.
- F. Field quality-control reports.

#### 1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For medical and specialty gas piping specialties to include in emergency, operation, and maintenance manuals.

#### 1.7 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Quick-Coupler Service Connections: Furnish complete noninterchangeable medical gas pressure outlets and suction inlets.
    - a. Medical Carbon Dioxide: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - b. Medical Nitrous Oxide: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - c. Medical Oxygen: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - d. Medical Air: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - e. Instrument Air: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - f. Medical Vacuum: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - g. WAGD: Equal to 10 percent of quantity installed, but no fewer than 10 units.
  - 2. D.I.S.S. Service Connections: Furnish complete medical gas pressure outlets and suction inlets complying with CGA V-5.
    - a. Medical Carbon Dioxide D.I.S.S. No. 1080: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - b. Medical Nitrogen D.I.S.S. No. 1120: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - c. Medical Nitrous Oxide D.I.S.S. No. 1040: Equal to 10 percent of quantity installed, but no fewer than 10 units.
    - d. Medical Oxygen D.I.S.S. No. 1240: Equal to 10 percent of quantity installed, but no fewer than 10 units.

- e. Medical Air D.I.S.S. No. 1160: Equal to 10 percent of quantity installed, but no fewer than 10 units.
- f. Instrument Air D.I.S.S. No. 1160: Equal to 10 percent of quantity installed, but no fewer than 10 units.
- g. Medical Vacuum D.I.S.S. No. 1220: Equal to 10 percent of quantity installed, but no fewer than 10 units.
- h. WAGD D.I.S.S. No. 2220: Equal to 10 percent of quantity installed, but no fewer than 10 units.

## 1.8 QUALITY ASSURANCE

### A. Installer Qualifications:

- 1. Medical Gas Piping Systems for Healthcare Facilities: According to ASSE Standard #6010 for medical-gas-system installers.
- 2. Bulk Medical Gas Systems for Healthcare Facilities: According to ASSE Standard #6015 for bulk-medical-gas-system installers.
- 3. Shape-Memory-Metal Coupling Joints: An authorized representative who is trained and approved by manufacturer.

### B. Testing Agency Qualifications: An independent testing agency, with the experience and capability to conduct the medical gas piping testing indicated, that is a member of the Medical Gas Professional Healthcare Organization or is an NRTL, and that is acceptable to authorities having jurisdiction.

- 1. Qualify testing personnel according to ASSE Standard #6020 for medical-gas-system inspectors and ASSE Standard #6030 for medical-gas-system verifiers.

### C. Brazing: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code, Section IX, "Welding and Brazing Qualifications"; or AWS B2.2, "Standard for Brazing Procedure and Performance Qualification."

## PART 2 - PRODUCTS

### 2.1 SYSTEM DESCRIPTION

- A. Medical carbon dioxide operating at 50 to 55 psig.
- B. Medical helium operating at 50 to 55 psig.
- C. Medical nitrogen operating at 160 to 185 psig.
- D. Medical nitrous oxide operating at 50 to 55 psig.
- E. Medical oxygen operating at 50 to 55 psig.

## 2.2 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Medical gas manifolds shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
  - 1. The term "withstand" means "the medical gas manifolds will remain in place without separation of any parts when subjected to the seismic forces specified and the manifolds and tanks will be fully operational after the seismic event."
  - 2. Component Importance Factor is 1.5.

## 2.3 PIPES, TUBES, AND FITTINGS

- A. Comply with NFPA 99 for medical gas piping materials.
- B. Copper Medical Gas Tube: ASTM B 819, Type K and Type L, seamless, drawn temper that has been manufacturer cleaned, purged, and sealed for medical gas service; or according to CGA G-4.1 for oxygen service. Include standard color marking "OXY," "MED," "OXY/MED," "OXY/ACR," or "ACR/MED" in green for Type K tube and blue for Type L tube.
- C. Wrought-Copper Fittings: ASME B16.22, solder-joint pressure type that has been manufacturer cleaned, purged, and bagged for oxygen service according to CGA G-4.1.
- D. Copper Unions: ASME B16.22 or MSS SP-123, wrought-copper or cast-copper alloy.
- E. Cast-Copper-Alloy Flanges: ASME B16.24, Class 150.
  - 1. Pipe-Flange Gasket Materials: ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch - maximum thickness, full-face type.
  - 2. Flange Bolts and Nuts: ASME B18.2.1, carbon steel.
- F. Shape-Memory-Metal Couplings:
  - 1. Manufacturers: Subject to compliance with requirements provide products by one of the following:
  - 2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
    - a. Aerofit, Inc.
    - b. Smart Tap, Inc.
  - 3. Description: Cryogenic compression fitting made of nickel-titanium, shape-memory alloy, and that has been manufacturer cleaned, purged, and sealed for oxygen service according to CGA G-4.1.

## 2.4 JOINING MATERIALS

- A. Brazing Filler Metals: AWS A5.8/A5.8M, BCuP Series, copper-phosphorus alloys.

- B. Threaded-Joint Tape: PTFE.
- C. Solvent Cement for Joining PVC Piping: ASTM D 2564. Include primer complying with ASTM F 656.

## 2.5 VALVES

- A. General Requirements for Valves: Manufacturer cleaned, purged, and bagged according to CGA G-4.1 for oxygen service.
- B. Zone-Valve Box Assemblies: Box with medical gas valves, tube extensions, and gages.

### 1. Zone-Valve Boxes:

#### a. Steel Box with Aluminum Cover:

- 1) Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- 2) Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a) Allied Healthcare Products Inc.
  - b) Amico Corporation.
  - c) Ohio Medical Corporation.
  - d) Patton's Medical

- b. Description: Formed steel box with cover, anchors for recessed mounting, holes with grommets in box sides for tubing extension protection, and of size for single or multiple valves with pressure gages and in sizes required to permit manual operation of valves. Medical air and medical vacuum tubing, valves, and gages may be incorporated in zone valve boxes for medical gases.

- 1) Interior Finish: Factory-applied white enamel.
- 2) Cover Plate: Aluminum with frangible or removable windows.
- 3) Valve-Box Windows: Clear or tinted transparent plastic with labeling that includes rooms served, according to NFPA 99.

### C. Ball Valves:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- 2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Allied Healthcare Products Inc.; Chemetron Division.
  - b. Amico Corporation.
  - c. BeaconMedaes.
  - d. Conbraco Industries, Inc.
  - e. Marwin Valve; a division of Richards Industries.

- f. NIBCO INC.
  - g. Ohio Medical Corporation.
  - h. Tri-Tech Medical Inc.
  - i. Patton's Medical
- 3. Standard: MSS SP-110.
- 4. Description: Three-piece body, brass or bronze.
- 5. Pressure Rating: 300 psig minimum.
- 6. Ball: Full-port, chrome-plated brass.
- 7. Seats: PTFE or TFE.
- 8. Handle: Lever[ type with locking device].
- 9. Stem: Blowout proof with PTFE or TFE seal.
- 10. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.

D. Check Valves:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- 2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Allied Healthcare Products Inc.; Chemetron Division.
  - b. Amico Corporation.
  - c. BeaconMedaes.
  - d. Conbraco Industries, Inc.
  - e. Ohio Medical Corporation.
  - f. Tri-Tech Medical Inc.
  - g. Patton's Medical
- 3. Description: In-line pattern, bronze.
- 4. Pressure Rating: 300 psig minimum.
- 5. Operation: Spring loaded.
- 6. Ends: Manufacturer-installed ASTM B 819, copper-tube extensions.

E. Emergency Oxygen Connections: Low-pressure oxygen inlet assembly for connection to building oxygen piping systems.

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- 2. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:
  - a. Allied Healthcare Products Inc.; Chemetron Division.
  - b. Amico Corporation.
  - c. BeaconMedaes.
  - d. Ohio Medical Corporation.
  - e. Tri-Tech Medical Inc.
  - f. Patton's Medical

3. Enclosure: Weatherproof hinged locking cover with caption similar to "Emergency Low-Pressure Gaseous Oxygen Inlet."
4. Inlet: Manufacturer-installed, NPS 1 or NPS 1-1/4, ASTM B 819, copper tubing with NPS 1 minimum ball valve.
5. Safety Valve: Bronze-body pressure relief valve set at 75 or 80 psig.
6. Instrumentation: Pressure gage.

F. Safety Valves:

1. Bronze body.
2. ASME-construction, poppet, pressure-relief type.
3. Settings to match system requirements.

G. Pressure Regulators:

1. Bronze body and trim.
2. Spring-loaded, diaphragm-operated, relieving type.
3. Manual pressure-setting adjustment.
4. Rated for 250-psig minimum inlet pressure.
5. Capable of controlling delivered gas pressure within 0.5 psig for each 10-psig inlet pressure.

2.6 MEDICAL GAS SERVICE CONNECTIONS

- A. Manufacturers: Subject to compliance with requirements provide products by one of the following:
- B. Basis-of-Design Product: Subject to compliance with requirements, provide Chemetron Compatible product by one of the following:
1. BeaconMedaes.
- C. General Requirements for Medical Gas Service Connections:
1. Suitable for specific medical gas pressure and suction service listed.
  2. Include roughing-in assemblies, finishing assemblies, and cover plates.
  3. Individual cover plates are not required if service connection is in multiple unit or assembly with cover plate.
  4. Recessed-type units made for concealed piping unless otherwise indicated.
- D. Roughing-in Assembly:
1. Steel outlet box for recessed mounting and concealed piping.
  2. Brass-body outlet block with secondary check valve that will prevent gas flow when primary valve is removed. Suction inlets to be without secondary valve.
  3. Double seals that will prevent gas leakage.
  4. ASTM B 819, NPS 3/8 copper outlet tube brazed to valve with service marking and tube-end dust cap.

E. Finishing Assembly:



1. Brass housing with primary check valve.
  2. Double seals that will prevent gas leakage.
  3. Cover plate with gas-service label.
- F. Quick-Coupler Pressure Service Connections: Outlets for carbon dioxide nitrous oxide and oxygen with noninterchangeable keyed indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment, and with positive-locking ring that retains equipment stem in valve during use.
- G. Quick-Coupler Pressure Service Connections: Outlets for instrument air with noninterchangeable keyed indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment, and with positive-locking ring that retains equipment stem in valve during use.
- H. Quick-Coupler Suction Service Connections: Inlets for medical vacuum with noninterchangeable keyed indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment, and with positive-locking ring that retains equipment stem in valve during use.
- I. D.I.S.S. Pressure Service Connections: Outlets, complying with CGA V-5, with threaded indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment.
1. Medical Carbon Dioxide: D.I.S.S. No. 1080.
  2. Medical Nitrogen: D.I.S.S. No. 1120.
  3. Medical Nitrous Oxide: D.I.S.S. No. 1040.
  4. Medical Oxygen: D.I.S.S. No. 1240.
- J. D.I.S.S. Pressure Service Connections: Outlets, complying with CGA V-5, with threaded indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment.
1. Medical Air: D.I.S.S. No. 1160.
  2. Instrument Air: D.I.S.S. No. 1160.
- K. D.I.S.S. Suction Service Connections: Inlets, complying with CGA V-5, with threaded indexing to prevent interchange between services, constructed to permit one-handed connection and removal of equipment.
1. Medical Vacuum: D.I.S.S. No. 1220.
  2. WAGD: D.I.S.S. No. 2220.
- L. Cover Plates: One piece, aluminum or stainless steel and permanent, color-coded, identifying label matching corresponding service.

## 2.7 MEDICAL NITROGEN PRESSURE CONTROL PANELS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

B. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:

1. Allied Healthcare Products Inc.; Chemetron Division.
2. Amico Corporation.
3. BeaconMedaes.
4. Ohio Medical Corporation.
5. Tri-Tech Medical Inc.
6. Patton's Medical

C. Description:

1. Steel box and support brackets for recessed roughing-in with stainless-steel or anodized-aluminum cover plate with printed operating instructions.
2. Manifold assembly consisting of inlet supply valve, inlet supply pressure gage, line-pressure control regulator, outlet supply pressure gage, D.I.S.S. service connection, and piping outlet for remote service connection.
3. Minimum Working Pressure: 200 psig.
4. Line-Pressure Control Regulator: Self-relieving diaphragm type with precision manual adjustment.
5. Pressure Gages: 0 to 300 psig.
6. Service Connection: CGA V-5, D.I.S.S. No. 1120, nitrogen outlet.
7. Before final assembly, provide temporary dust shield and U-tube for testing.
8. Label cover plate "Nitrogen Pressure Control."

## 2.8 MEDICAL GAS MANIFOLDS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

B. Basis-of-Design Product: Subject to compliance with requirements, provide product by one of the following:

1. Acme Cryogenics.
2. Allied Healthcare Products Inc.; Chemetron Division.
3. Amico Corporation.
4. BeaconMedaes.
5. Ohio Medical Corporation.
6. Tri-Tech Medical Inc.
7. Patton's Medical

C. Comply with NFPA 99 for high-pressure medical gas cylinders.

D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

E. Central Control-Panel Unit:

1. Supply and delivery pressure gages.
2. Electrical alarm-system connections and transformer.

3. Indicator lights or devices.
4. Manifold connection.
5. Pressure changeover switch.
6. Line-pressure regulator.
7. Shutoff valves.
8. Safety valve.

F. Manifold and Headers:

1. Duplex, nonferrous-metal header for number of cylinders indicated, divided into two equal banks.
2. Designed for 2000-psig minimum inlet pressure except nitrous oxide manifolds may be designed for 800 psig and carbon dioxide manifolds may be designed for 1500 psig.
3. Cylinder-bank headers with inlet (pigtail) connections complying with CGA V-1.
4. Individual inlet check valves, shutoff valve, pressure regulator, check valve, and pressure gage.

G. Operation: Automatic, pressure-switch-activated changeover from one cylinder bank to the other when first bank becomes exhausted, without line-pressure fluctuation or resetting of regulators and without supply interruption by shutoff of either cylinder-bank header.

H. Mounting: Wall with mounting brackets for manifold control cabinet and headers.

I. Label manifold control unit with permanent label identifying medical gas type and system operating pressure.

## 2.9 GAS CYLINDER STORAGE RACKS

- A. Wall Storage Racks: Fabricate racks with chain restraints for upright cylinders as indicated or provide equivalent manufactured wall racks.
- B. Freestanding Storage Racks: Fabricate racks as indicated or provide equivalent manufactured storage racks.

## 2.10 NITROGEN

- A. Comply with USP 32 - NF 27 for oil-free dry nitrogen.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Cleaning of Medical Gas Tubing: If manufacturer-cleaned and -capped fittings or tubing is not available or if precleaned fittings or tubing must be recleaned because of exposure, have supplier or separate agency acceptable to authorities having jurisdiction perform the following procedures:

1. Clean medical gas tube and fittings, valves, gages, and other components of oil, grease, and other readily oxidizable materials as required for oxygen service according to CGA G-4.1.
2. Wash medical gas tubing and components in hot, alkaline-cleaner-water solution of sodium carbonate or trisodium phosphate in proportion of 1 lb of chemical to 3 gal. of water.
  - a. Scrub to ensure complete cleaning.
  - b. Rinse with clean, hot water to remove cleaning solution.

### 3.2 EARTHWORK

- A. Comply with requirements in Section 312000 "Earth Moving" for excavating, trenching, and backfilling and for underground warning tapes.

### 3.3 PIPING INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of gas piping. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, and other design considerations. Install piping as indicated unless deviations to layout are approved on coordination drawings.
- B. Comply with NFPA 99 for installation of medical gas piping.
- C. Install piping concealed from view and protected from physical contact by building occupants unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal and coordinate with other services occupying that space.
- F. Install piping adjacent to equipment and specialties to allow service and maintenance.
- G. Install nipples, unions, special fittings, and valves with pressure ratings same as or higher than system pressure rating used in applications specified in "Piping Schedule" Article unless otherwise indicated.
- H. Install piping to permit valve servicing.
- I. Install piping free of sags and bends.
- J. Install fittings for changes in direction and for branch connections.

- K. Install medical gas piping to medical gas service connections specified in this Section, to medical gas service connections in equipment specified in this Section, and to equipment specified in other Sections requiring medical gas service.
- L. Install exterior, buried medical gas piping in protective conduit fabricated with PVC pipe and fittings. Do not extend conduit through foundation wall.
- M. Piping Restraint Installation: Install seismic restraints on piping. Comply with requirements for seismic-restraint devices specified in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment."
- N. Install medical gas service connections recessed in walls. Attach roughing-in assembly to substrate; attach finishing assembly to roughing-in assembly.
- O. Connect gas piping to gas sources and to gas outlets and equipment requiring gas service.
- P. Install unions in copper tubing adjacent to each valve and at final connection to each specialty and piece of equipment.
- Q. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."
- R. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."
- S. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

### 3.4 VALVE INSTALLATION

- A. Install shutoff valve at each connection to gas laboratory and healthcare equipment and specialties.
- B. Install check valves to maintain correct direction of gas flow from laboratory and healthcare gas supplies.
- C. Install valve boxes recessed in wall and anchored to substrate. Single boxes may be used for multiple valves that serve same area or function.
- D. Install zone valves and gages in valve boxes. Arrange valves so largest valve is lowest. Rotate valves to angle that prevents closure of cover when valve is in closed position.
- E. Install pressure regulators on gas piping where reduced pressure is required.
- F. Install emergency oxygen connection with pressure relief valve and full-size discharge piping to outside, with check valve downstream from pressure relief valve, and with ball valve and check valve in supply main from bulk oxygen storage tank.

### 3.5 JOINT CONSTRUCTION

- A. Remove scale, slag, dirt, and debris from outside of cleaned tubing and fittings before assembly.
- B. Threaded Joints: Apply appropriate tape to external pipe threads.
- C. Brazed Joints: Join copper tube and fittings according to CDA's "Copper Tube Handbook," "Braze Joints" chapter. Continuously purge joint with oil-free, dry nitrogen during brazing.
- D. Shape-Memory-Metal Coupling Joints: Join new copper tube to existing tube according to procedures developed by fitting manufacturer for installation of shape-memory-metal coupling joints.

### 3.6 GAS SERVICE COMPONENT INSTALLATION

- A. Assemble patient-service console with service connections. Install with supplies concealed in walls. Attach console box or mounting bracket to substrate.
- B. Install nitrogen pressure-control panels in walls. Attach to substrate.
- C. Install gas manifolds anchored to substrate.
- D. Install gas cylinders and connect to manifold piping.
- E. Install gas manifolds with seismic restraints.

### 3.7 HANGER AND SUPPORT INSTALLATION

- A. Comply with requirements in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices.
- B. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support devices.
- C. Vertical Piping: MSS Type 8 or Type 42, clamps.
- D. Individual, Straight, Horizontal Piping Runs:
  - 1. 100 Feet and Less: MSS Type 1, adjustable, steel, clevis hangers.
  - 2. Longer Than 100 Feet: MSS Type 43, adjustable, roller hangers.
- E. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for trapeze hangers.
- F. Base of Vertical Piping: MSS Type 52, spring hangers.
- G. Support horizontal piping within 12 inches of each fitting and coupling.

- H. Rod diameter may be reduced one size for double-rod hangers, with 3/8-inch- minimum rods.
- I. Install hangers for copper tubing with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 1/4: 60 inches with 3/8-inch rod.
  - 2. NPS 3/8 and NPS 1/2: 72 inches with 3/8-inch rod.
  - 3. NPS 3/4: 84 inches with 3/8-inch rod.
  - 4. NPS 1: 96 inches with 3/8-inch rod.
  - 5. NPS 1-1/4: 108 inches with 3/8-inch rod.
  - 6. NPS 1-1/2: 10 feet with 3/8-inch rod.
  - 7. NPS 2: 11 feet with 3/8-inch rod.
  - 8. NPS 2-1/2: 13 feet with 1/2-inch rod.
  - 9. NPS 3: 14 feet with 1/2-inch rod.
  - 10. NPS 3-1/2: 15 feet with 1/2-inch rod.
  - 11. NPS 4: 16 feet with 1/2-inch rod.
  - 12. NPS 6: 20 feet with 5/8-inch rod.
- J. Install supports for vertical copper tubing every 10 feet.

### 3.8 IDENTIFICATION

- A. Install identifying labels and devices for specialty gas piping, valves, and specialties. Comply with requirements in Section 220553 "Identification for Plumbing Piping and Equipment."
- B. Install identifying labels and devices for healthcare medical gas piping systems according to NFPA 99. Use the following or similar captions and color-coding for piping products where required by NFPA 99:
  - 1. Carbon Dioxide: Black or white letters on gray background.
  - 2. Nitrogen: White letters on black background.
  - 3. Nitrous Oxide: White letters on blue background.
  - 4. Oxygen: White letters on green background or green letters on white background.

### 3.9 FIELD QUALITY CONTROL FOR HEALTHCARE FACILITY MEDICAL GAS

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Tests and Inspections:
  - 1. Medical Gas Piping Testing Coordination: Perform tests, inspections, verifications, and certification of medical gas piping systems concurrently with tests, inspections, and certification of medical compressed-air piping and medical vacuum piping systems.
  - 2. Preparation: Perform the following Installer tests according to requirements in NFPA 99 and ASSE Standard #6010:
    - a. Initial blowdown.
    - b. Initial pressure test.

- c. Cross-connection test.
    - d. Piping purge test.
    - e. Standing pressure test for positive-pressure medical gas piping.
    - f. Standing pressure test for vacuum systems.
    - g. Repair leaks and retest until no leaks exist.
  - 3. System Verification: Perform the following tests and inspections according to NFPA 99, ASSE Standard #6020, and ASSE Standard #6030:
    - a. Standing pressure test.
    - b. Individual-pressurization or pressure-differential cross-connection test.
    - c. Valve test.
    - d. Master and area alarm tests.
    - e. Piping purge test.
    - f. Piping particulate test.
    - g. Piping purity test.
    - h. Final tie-in test.
    - i. Operational pressure test.
    - j. Medical gas concentration test.
    - k. Medical air purity test.
    - l. Verify correct labeling of equipment and components.
    - m. Verify medical gas supply sources.
  - 4. Testing Certification: Certify that specified tests, inspections, and procedures have been performed and certify report results. Include the following:
    - a. Inspections performed.
    - b. Procedures, materials, and gases used.
    - c. Test methods used.
    - d. Results of tests.
  - C. Remove and replace components that do not pass tests and inspections and retest as specified above.
  - D. Prepare test and inspection reports.
- 3.10 FIELD QUALITY CONTROL FOR LABORATORY FACILITY SPECIALTY GAS
- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
  - B. Tests and Inspections:
    - 1. Piping Leak Tests for Specialty Gas Piping: Test new and modified parts of existing piping. Cap and fill specialty gas piping with oil-free, dry nitrogen to pressure of 50 psig above system operating pressure, but not less than 150 psig. Isolate test source and let stand for four hours to equalize temperature. Refill system, if required, to test pressure; hold for two hours with no drop in pressure.
    - 2. Repair leaks and retest until no leaks exist.
    - 3. Inspect specialty gas regulators for proper operation.



- C. Remove and replace components that do not pass tests and inspections and retest as specified above.
- D. Prepare test and inspection reports.

3.11 PROTECTION

- A. Protect tubing from damage.
- B. Retain sealing plugs in tubing, fittings, and specialties until installation.
- C. Clean tubing not properly sealed, and where sealing is damaged, according to "Preparation" Article.

3.12 DEMONSTRATION

- A. Engage factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain bulk gas storage tanks.

3.13 PIPING SCHEDULE

- A. Connect new tubing to existing tubing with memory-metal couplings.

3.14 VALVE SCHEDULE

- A. Shutoff Valves: Ball valve with manufacturer-installed ASTM B 819, copper-tube extensions.
- B. Zone Valves: Ball valve with manufacturer-installed ASTM B 819, copper-tube extensions with pressure gage on one copper-tube extension.

END OF SECTION 22 6313

SECTION 22 6600 - CHEMICAL-WASTE SYSTEMS FOR LABORATORY AND HEALTHCARE FACILITIES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
  - 1. Single-wall piping.

1.3 DEFINITIONS

- A. CR: Chlorosulfonated polyethylene synthetic rubber.
- B. FPM: Vinylidene fluoride-hexafluoro propylene copolymer rubber.

1.4 PERFORMANCE REQUIREMENTS

- A. Single-Wall Piping Pressure Rating: 10 feet head of water.
- B. Delegated Design: Design seismic restraints for aboveground piping, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. LEED Submittals:
  - 1. Product Data for Credit IEQ 4.1: For solvent cements and adhesive primers, documentation including printed statement of VOC content.
  - 2. Laboratory Test Reports for Credit IEQ 4: For solvent cements and adhesive primers, documentation indicating that products comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

- C. Delegated-Design Submittal: For seismic restraints of aboveground piping, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

#### 1.6 INFORMATIONAL SUBMITTALS

- A. Profile Drawings for Outdoor Underground Piping: Show system piping in elevation. Draw profiles at horizontal scale of not less than 1 inch equals 50 feet and vertical scale of not less than 1 inch equals 5 feet. Indicate underground structures and pipes. Show types, sizes, materials, and elevations of other utilities crossing system piping.
- B. Coordination Drawings: Show pipe sizes, locations, and elevations. Show other piping in same trench and clearances from sewerage system piping. Indicate interface and spatial relationship between piping and proximate structures.
- C. Field quality-control test reports.

#### 1.7 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. NFPA Compliance: Comply with NFPA 70, "National Electrical Code."

#### 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Deliver and store piping and specialties with sealing plugs in ends or with end protection.
- B. Do not store plastic pipe or fittings in direct sunlight.
- C. Protect pipe, fittings, and seals from dirt and damage.

#### 1.9 PROJECT CONDITIONS

- A. Interruption of Existing Chemical-Waste Service: Do not interrupt chemical-waste service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary chemical-waste service according to requirements indicated:
  - 1. Notify Construction Manager no fewer than two days in advance of proposed interruption of chemical-waste service.

## PART 2 - PRODUCTS

### 2.1 SINGLE-WALL PIPE AND FITTINGS

- A. PP Drainage Pipe and Fittings: ASTM F 1412, pipe extruded and drainage-pattern fittings molded, with Schedule 40 dimensions, from PP resin with fire-retardant additive complying with ASTM D 4101; with fusion-joint ends.
1. Exception: Pipe and fittings made from PP resin without fire-retardant additive may be used for underground installation.
  2. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. IPEX Inc.
    - b. Orion Fittings, Inc.; a division of Watts Water Technologies, Inc.
    - c. Sloane, George Fischer Inc.
    - d. Town & Country Plastics, Inc.
    - e. Watts Industries (Canada) Inc.
    - f. Zurn Plumbing Products Group; Chemical Drainage Systems.
    - g. Spears Manufacturing Co.
- B. High-Silicon-Iron, Hub-and-Plain-End Pipe and Fittings: ASTM A 861, pipe and drainage-pattern fittings; acid-resistant packing; and lead caulking materials.
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Flowserve Corporation; Foundry Operations.

### 2.2 JOINING MATERIALS

- A. Couplings: Assemblies with combination of clamps, gaskets, sleeves, and threaded or flanged parts; compatible with piping and system liquid; and made by piping manufacturer for joining system piping.
- B. Adapters and Transition Fittings: Assemblies with combination of clamps, couplings, adapters, gaskets, and threaded or flanged parts; compatible with piping and system liquid; and made for joining different piping materials.
- C. Flanges: Assemblies of companion flanges and gaskets complying with ASME B16.21 and compatible with system liquid, and bolts and nuts.

### 2.3 PIPING SPECIALTIES

- A. High-Silicon-Iron Dilution Traps:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Flowserve Corporation; Foundry Operations.
  2. Standard: ASTM A 861.
  3. Size: NPS 1-1/2 or NPS 2 as required for fixture and waste.
  4. End Connections: Mechanical.
- B. Corrosion-Resistant Traps:
1. Type: P-trap or drum trap.
  2. Size: NPS 1-1/2 or NPS 2, as required to match connected piping.
  3. High-Silicon Iron: ASTM A 861, with horizontal outlet and hub-and-plain or plain ends to match connecting piping.
  4. PP: ASTM D 4101, with mechanical-joint pipe connections.
- C. High-Silicon-Iron Floor Drains:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Flowserve Corporation; Foundry Operations.
  2. Standard: ASTM A 861.
  3. Body: With integral flashing flange and weep holes; and with flashing ring and stainless-steel strip.
  4. Top: 8-3/4-inch diameter with grate.
  5. Size: NPS 2, NPS 3, NPS 4, or NPS 6 outlet as indicated.
- D. PP Floor Drains:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. IPEX Inc.
    - b. Orion Fittings, Inc.; a division of Watts Water Technologies, Inc.
    - c. Schier Products Company.
    - d. Sloane, George Fischer Inc.
    - e. Town & Country Plastics, Inc.
    - f. Watts Industries (Canada) Inc.
    - g. Spears Manufacturing Co.
  2. Body: With 7- to 9-inch top diameter, with flashing flange and weep holes; and with flashing clamp and trap-primer connection.
  3. Outlet: Bottom, to match connecting pipe, with NPS 2, NPS 3, NPS 4, or NPS 6 outlet as indicated.
- E. High-Silicon-Iron Cleanouts:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Flowserve Corporation; Foundry Operations.
  2. Standard: ASTM A 861, fitting with PTFE gasket and closure plug, of design appropriate for piping application.
- F. PP Sink Outlets:
1. Description: NPS 1-1/2, with clamping device, stopper, and 7-inch-high overflow fitting.

### PART 3 - EXECUTION

#### 3.1 EARTHWORK

- A. Comply with requirements in Section 312000 "Earth Moving" for excavating, trenching, and backfilling.

#### 3.2 PIPING INSTALLATION

- A. Chemical-Waste Sewerage Outside the Building:
  1. Locations and Arrangements: Drawing plans and details indicate general location and arrangement of underground chemical-waste sewerage piping. Location and arrangement of piping layout take design considerations into account. Install piping as indicated, to extent practical. Where specific installation is not indicated, follow piping manufacturer's written instructions.
  2. Install piping beginning at low point, true to grades and alignment indicated with unbroken continuity of invert. Place bell ends of piping facing upstream. Install gaskets, seals, sleeves, and couplings according to manufacturer's written instructions for using lubricants, cements, and other installation requirements.
  3. Install proper size increasers, reducers, and couplings where different sizes or materials of pipes and fittings are connected. Reducing size of piping in direction of flow is prohibited.
  4. Tunneling: Install pipe under streets or other obstructions that cannot be disturbed by tunneling, jacking, or combination of both.
  5. Install drainage piping pitched down in direction of flow, at minimum slope of 2 percent, unless otherwise indicated.
  6. Install drainage piping with 36-inch minimum cover.
  7. Clear interior of piping and structures of dirt and superfluous material as work progresses. Maintain swab or drag in piping, and pull past each joint as it is completed. Place plug in end of incomplete piping at end of day and when work stops.
- B. Chemical-Waste Piping Inside the Building:

1. Install piping next to equipment, accessories, and specialties to allow service and maintenance.
2. Transition and special fittings with pressure ratings at least equal to piping pressure rating may be used unless otherwise indicated.
3. Flanges may be used on aboveground piping unless otherwise indicated.
4. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
5. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
6. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
7. Install piping at indicated slopes.
8. Install piping free of sags and bends.
9. Install fittings for changes in direction and branch connections.
10. Verify final equipment locations for roughing-in.
11. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."
12. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Section 220517 "Sleeves and Sleeve Seals for Plumbing Piping."
13. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Section 220518 "Escutcheons for Plumbing Piping."

### 3.3 PIPING SPECIALTY INSTALLATION

- A. Embed floor drains in 4-inch minimum depth of concrete around bottom and sides. Comply with requirements in Section 033000 "Cast-in-Place Concrete" for concrete.
- B. Fasten grates to drains if indicated.
- C. Set floor drains with tops flush with pavement surface.
- D. Install cleanouts and riser extension from sewer pipe to cleanout at grade. Use fittings of same material as sewer pipe at branches for cleanouts and riser extensions to cleanouts. Install piping so cleanouts open in direction of flow in pipe.
  1. Set cleanout bodies in earth in cast-in-place concrete block, 18 by 18 by 12 inches deep. Set with tops 1 inch above surrounding grade. Set cleanout plugs in concrete pavement with tops flush with pavement surface. Comply with requirements in Section 033000 "Cast-in-Place Concrete" for formwork, reinforcement, and concrete requirements.

### 3.4 JOINT CONSTRUCTION

- A. Chemical-Waste Sewerage Outside the Building:

1. Plastic-Piping, Electrofusion Joints: Make polyolefin drainage-piping joints according to ASTM F 1290.
2. Join dissimilar pipe materials with adapters compatible with pipe materials being joined.
3. Join high-silicon-iron, hub-and-plain-end piping with calked joints using acid-resistant packing and lead.
4. Join high-silicon-iron, mechanical-joint piping with coupled joints using clamps and sleeves.

B. Chemical-Waste Piping Inside the Building:

1. Plastic-Piping Electrofusion Joints: Make polyolefin drainage-piping joints according to ASTM F 1290.
2. Dissimilar-Material Piping Joints: Make joints using adapters compatible with both system materials.
3. Join high-silicon-iron, hub-and-plain-end piping with calked joints using acid-resistant packing and lead.
4. Join high-silicon-iron, mechanical-joint piping with coupled joints using clamps and sleeves.

3.5 HANGER AND SUPPORT INSTALLATION

- A. Pipe sizes in this article refer to aboveground, single-wall piping .
- B. Comply with requirements in Section 220548 "Vibration and Seismic Controls for Plumbing Piping and Equipment" for seismic-restraint devices.
- C. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for pipe hanger and support devices. Install the following:
  1. Vertical Piping: MSS Type 8 or MSS Type 42, riser clamps.
  2. Individual, Straight, Horizontal Piping Runs:
    - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    - c. Longer Than 100 Feet, if Indicated: MSS Type 49, spring cushion rolls.
  3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
  4. Base of Vertical Piping: MSS Type 52, spring hangers.
- D. Comply with requirements in Section 220529 "Hangers and Supports for Plumbing Piping and Equipment" for installation of supports.
- E. Support horizontal piping and tubing within 12 inches of each fitting and coupling.
- F. Support vertical piping and tubing at base and at each floor.
- G. Rod diameter may be reduced 1 size for double-rod hangers, to minimum of 3/8 inch.



- H. Install vinyl-coated hangers for PP piping with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 2: 33 inches with 3/8-inch rod.
  - 2. NPS 2-1/2 and NPS 3: 42 inches with 1/2-inch rod.
  - 3. NPS 4 and NPS 5: 48 inches with 5/8-inch rod.
  - 4. NPS 6: 48 inches with 3/4-inch rod.
  - 5. NPS 8: 48 inches with 7/8-inch rod.
- I. Install supports for vertical PP piping every 72 inches.
- J. Install hangers for high-silicon-iron piping with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 1-1/2 and NPS 2: 60 inches with 3/8-inch rod.
  - 2. NPS 3: 60 inches with 1/2-inch rod.
  - 3. NPS 4 and NPS 5: 60 inches with 5/8-inch rod.
  - 4. NPS 6: 60 inches with 3/4-inch rod.
  - 5. NPS 8 to NPS 12: 60 inches with 7/8-inch rod.
  - 6. NPS 15: 60 inches with 1-inch rod.
  - 7. Spacing for horizontal pipe in 84-inch lengths may be increased to 84 inches. Spacing for fittings is limited to 60 inches.
- K. Install supports for vertical high-silicon-iron piping every 15 feet.
- L. Support piping and tubing not listed above according to MSS SP-69.

### 3.6 CONCRETE PLACEMENT

- A. Comply with requirements in Section 033000 "Cast-in-Place Concrete" for concrete supports.
- B. Place cast-in-place concrete according to ACI 318/318R.

### 3.7 CONNECTIONS

- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Make connections to existing piping so finished Work complies as nearly as practical with requirements specified for new Work.
- C. Use commercially manufactured wye fittings for sewerage piping branch connections. Remove section of existing pipe; install wye fitting into existing piping; and encase entire wye fitting plus 6-inch overlap, with not less than 6 inches of concrete with 28-day compressive strength of 3000 psi.
- D. Protect existing piping to prevent concrete or debris from entering while making connections. Remove debris or other extraneous material that may accumulate.

- E. Install piping adjacent to equipment to allow service and maintenance.

### 3.8 LABELING AND IDENTIFICATION

- A. Comply with requirements in Section 220553 "Identification for Plumbing Piping and Equipment" for labeling of equipment and piping.
  - 1. Use warning tape or detectable warning tape over ferrous piping.
  - 2. Use detectable warning tape over nonferrous piping and over edges of underground structures.

### 3.9 FIELD QUALITY CONTROL

- A. Inspect interior of sewerage piping to determine whether line displacement or other damage has occurred. Inspect after approximately 24 inches of backfill is in place and again at completion of Project.
  - 1. Defects requiring correction include the following:
    - a. Alignment: Less than full diameter of inside of pipe is visible between inspection points.
    - b. Deflection: Flexible piping with deflection that prevents passage of ball or cylinder of size not less than 92.5 percent of piping diameter.
    - c. Crushed, broken, cracked, or otherwise damaged piping.
    - d. Hydrostatic Tests for Drainage Piping:
      - 1) Allowable leakage is a maximum of 50 gal./inch of nominal pipe size per mile of pipe, during 24-hour period.
      - 2) Close openings in system and fill with water.
      - 3) Purge air and refill with water.
      - 4) Disconnect water supply.
      - 5) Test and inspect joints for leaks.
    - e. Air Tests for Drainage Piping: Comply with UNI-B-6.
  - 2. Leaks and loss in test pressure constitute defects that must be repaired.
  - 3. Submit separate reports for each test.
- B. Replace leaking sewerage piping using new materials, and repeat testing until leakage is within allowances specified.
- C. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.
- D. Perform tests and inspections.

1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

E. Chemical-waste piping will be considered defective if it does not pass tests and inspections.

F. Prepare test and inspection reports.

### 3.10 ADJUSTING

A. Adjust neutralization-system set points.

B. Adjust leak-detection-system control and device settings.

### 3.11 CLEANING

A. Use procedures prescribed by authorities having jurisdiction or, if not prescribed, use procedures described below:

1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
2. Clean piping by flushing with potable water.

### 3.12 PIPING SCHEDULE

A. Transition and special fittings with pressure ratings at least equal to piping pressure rating may be used in applications below unless otherwise indicated.

B. Single-Wall, Chemical-Waste Sewerage Piping: Use the following piping materials for each size range:

1. NPS 1-1/2 to NPS 4: PP drainage pipe and fittings and electrofusion joints.
2. NPS 6: PP drainage pipe and fittings and electrofusion joints.
3. NPS 8 to NPS 12: PP drainage pipe and fittings and electrofusion joints.
4. NPS 15: High-silicon-iron, hub-and-plain-end pipe and fittings and calked joints.

C. Aboveground Chemical-Waste Piping: Use the following piping materials for each size range:

1. NPS 1-1/2 to NPS 6: PP drainage piping and electrofusion joints.
2. NPS 8 to NPS 12: High-silicon-iron piping with hub-and-plain ends and calked joints.

D. Under Slab-on-Grade, Indoor, Chemical-Waste Piping: Use the following piping materials for each size range:

1. NPS 1-1/2 to NPS 6: PP drainage piping and electrofusion joints.

2. NPS 8: High-silicon-iron piping with hub-and-plain ends and calked joints.
3. NPS 10 to NPS 15: High-silicon-iron piping with hub-and-plain ends and calked joints.

END OF SECTION 22 6600

## SECTION 22 6710 - PURE WATER PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes pure water piping.

#### 1.3 DEFINITIONS

- A. PP: Polypropylene plastic.
- B. PVC: Polyvinyl chloride plastic.

#### 1.4 PERFORMANCE REQUIREMENTS

- A. Provide components and installation capable of producing piping with the following minimum working-pressure ratings, unless otherwise indicated:
  - 1. Deionized (Reagent grade) Water Piping: 150 psig unless otherwise indicated.

#### 1.5 SUBMITTALS

- A. Product Data: For each type of pipe and fitting indicated.
- B. Welding certificates.
- C. Samples of field quality-control test reports.

#### 1.6 QUALITY ASSURANCE

- A. Piping materials shall bear label, stamp, or other markings of specified testing laboratory.
- B. Welding: Qualify procedures and personnel according to ASME Boiler and Pressure Vessel Code: Section IX.

- C. ASME Compliance: Comply with ASME B31.3, "Process Piping."

#### 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Do not store plastic pipe and fittings in direct sunlight.
- B. Protect pipe and fittings from dirt and damage.

### PART 2 - PRODUCTS

#### 2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the manufacturers specified.

#### 2.2 PIPING MATERIALS

- A. Refer to Part 3 "Piping Applications" Article for applications of pipe, fitting, and joining materials.
- B. Transition Fittings: Couplings, flanges, or other manufactured fittings, same size as, with pressure rating at least equal to and ends compatible with piping to be joined.

#### 2.3 PLASTIC PIPE AND FITTINGS

- A. Schedule 80, CPVC Pipe and Fittings: Ultra-pure piping and fittings are to be low extractable CPVC with a Cell classification of 12343 per ASTM D1784, Schedule 80 with a type II pressure rating. .
  - 1. Manufacturers:
    - a. Spears LXT

#### 2.4 PLASTIC VALVES

- A. CPVC Valves: Made from ASTM D 1784, CPVC compounds.
  - 1. Ball Valves, NPS 2 and Smaller: MSS SP-122, union type with socket ends and pressure rating not less than 150 psig at 73 deg F.

2. Check Valves: Swing or ball type with pressure rating not less than 150 psig at 73 deg F.

### PART 3 - EXECUTION

#### 3.1 PIPING APPLICATIONS

- A. Transition and special fittings with pressure ratings at least equal to and of material same as, or compatible with, piping may be used in applications in this article, unless otherwise indicated.
- B. Pure -Water Piping: Use the following piping materials for each size range:
  1. Spears Schedule 80 LXT CPVC pipe and fittings and glued joints.
  2. Piping running in the plenum shall be wrapped with an approved fire wrap to meet the fire and smoke requirements of the plenum.

#### 3.2 VALVE APPLICATIONS

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirement apply:
  1. Shutoff Duty: Use ball valves.
  2. Throttling Duty: Use ball valves.
- B. General Locations and Arrangements: Drawing plans and details indicate general location and arrangement of deionized-water piping. Location and arrangement of piping layout take design considerations into account. Install piping as indicated, to extent practical. Where specific installation is not indicated, follow piping manufacturer's written instructions.
- C. Refer to Division 23 Section "Basic Mechanical Materials and Methods" for general piping installation requirements.

#### 3.3 JOINT CONSTRUCTION

- A. Refer to Division 23 Section "Basic Mechanical Materials and Methods" for basic piping joint construction. Where specific joint construction is not indicated, follow piping manufacturer's written instructions. Join in accordance with manufacturers recommendations.
- B. Joint dissimilar pipe materials with transition fittings compatible with pipe materials being joined.

#### 3.4 VALVE INSTALLATION

- A. Refer to Division 23 Section "Valves" for general valve installation requirements.

- B. Install sectional valves close to mains on each branch and riser serving equipment.
- C. Install shutoff valve on each supply to equipment.

### 3.5 HANGER AND SUPPORT INSTALLATION

- A. Seismic-restraint devices are specified in Division 23 Section "Mechanical Vibration and Seismic Controls."
- B. Pipe hanger and support devices and installation requirements are specified in Division 23 Section "Hangers and Supports." Install the following:
  - 1. Clamps for Vertical Piping: MSS Type 8 or Type 42.
  - 2. Individual, Straight, Horizontal Piping Runs:
    - a. 100 Feet and Less: MSS Type 1, adjustable, steel clevis hangers.
    - b. Longer Than 100 Feet: MSS Type 43, adjustable roller hangers.
    - c. Longer Than 100 Feet, if Indicated: MSS Type 49, spring cushion rolls.
  - 3. Multiple, Straight, Horizontal Piping Runs 100 Feet or Longer: MSS Type 44, pipe rolls. Support pipe rolls on trapeze.
  - 4. Base of Vertical Piping: MSS Type 52, spring hangers.
- C. Support horizontal piping and tubing within 12 inches of each fitting, valve, and coupling.
- D. Support vertical piping and tubing at base and at each floor.
- E. Rod diameter may be reduced 1 size for double-rod hangers, to minimum of 3/8 inch.
- F. Install padded hangers for CPVC piping with the following maximum horizontal spacing and minimum rod diameters:
  - 1. NPS 1-1/4 and Smaller: 36 inches with 3/8-inch rod.
  - 2. NPS 1-1/2 and NPS 2: 42 inches with 3/8-inch rod.
  - 3. NPS 2-1/2 to NPS 3-1/2: 48 inches mm with 1/2-inch rod.
  - 4. NPS 4 and NPS 5 and DN 125: 48 inches with 5/8-inch rod.
  - 5. NPS 6: 48 inches with 3/4-inch rod.
  - 6. NPS 8: 48 inches with 7/8-inch rod.
- G. Install padded supports for vertical PVC piping every 48 inches.
- H. Support piping and tubing not listed above according to MSS SP-69 and manufacturer's written instructions.

### 3.6 CONNECTIONS



- A. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to equipment and machines to allow service and maintenance.
- C. Connect deionized-water piping to equipment and service outlets with unions or flanges.

### 3.7 LABELING AND IDENTIFICATION

- A. Install pipe markers and valve tags on piping. Distinguish between different systems and include direction of flow indication on each pipe. Labeling and identification devices are specified in Division 23 Section "Mechanical Identification."

### 3.8 FIELD QUALITY CONTROL

- A. Test new piping and parts of existing piping that have been altered, extended, or repaired, for leaks and defects.
  - 1. Schedule tests and their inspections by authorities having jurisdiction, with at least 24 hours' advance notice.
  - 2. Do not cover or put into service before inspection and approval.
  - 3. Test completed piping according to authorities having jurisdiction. If authorities having jurisdiction do not have published procedures, perform tests as follows:
    - a. Hydrostatic Tests: Test piping at pressure not less than 1-1/2 times the maximum system operating pressure, but not less than 150 psig.
    - b. Exception: Do not subject glass piping to pressure above manufacturer's pressure rating for size.
  - 4. Replace leaking joints with new materials and retest until no leaks exist.
  - 5. Submit separate reports for each test.

### 3.9 CLEANING

- A. Use procedures prescribed by authorities having jurisdiction or, if not prescribed, use procedures described below:
  - 1. Purge new piping and parts of existing piping that have been altered, extended, or repaired before using.
  - 2. Clean piping by flushing with system deionized water.

END OF SECTION 22 6710

## SECTION 23 0100 - MECHANICAL REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 GENERAL CONDITIONS

- A. The General Conditions of the Contract, with the amendments, supplements, forms and requirements in Division 01, and herewith made a part of this Division.
- B. All sections of Division 21, 22, & 23 shall comply with the Mechanical General Requirements. The standards established in this section as to quality of materials and equipment, the type and quality of workmanship, mode of operations, safety rules, code requirements, etc., shall apply to all sections of this Division as though they were repeated in each Division.
- C. Mechanical equipment that is pre-purchased if any will be assigned to the Mechanical Contractor. By assignment to the Mechanical Contractor, the Mechanical Contractor shall accept and installed the equipment and provide all warranties and guarantees as if the Mechanical Contractor had purchased the equipment.
- D. Construction Indoor-Air Quality Management
  - 1. Comply with SMACNA's "SMACNA IAQ Guideline for Occupied Buildings under Construction."
    - a. If Owner authorizes use of permanent heating, cooling, and ventilating systems during construction period as specified in Division 01 Section "Temporary Facilities and Controls," install filter media having a MERV 8 according to ASHRAE 52.2 at each return-air inlet for the air-handling system used during construction.
    - b. Replace all air filters immediately prior to occupancy.

#### 1.2 SCOPE OF WORK

- A. The project described herein is the ACC 3rd Floor OR Expansion. This work shall include all labor, materials, equipment, fixtures, and devices for the entire mechanical work and a complete operating and tested installation as required for this project.

#### 1.3 CODES & ORDINANCES

- A. All work shall be executed in accordance with all underwriters, public utilities, local and state rules and regulations applicable to the trade affected. Should any change in the plans and Specifications be required to comply with these regulations, the Contractor shall notify the Architect before the time of submitting his bid. After entering into contract, the Contractor will be held to complete all work necessary to meet these requirements without extra expense to the Owner. Where work required by drawings or specifications is above the standard required, it shall be done as shown or specified.

B. Applicable codes:

1. International Building Code- 2018 Edition
2. International Mechanical Code- 2018 Edition
3. International Plumbing Code- 2018 Edition
4. International Fire Code- 2018 Edition
5. International Conservation Energy Code - 2018 Edition
6. National Electrical Code- 2016 Edition
7. ASHRAE Standard 62.1 – 2016 Edition
8. ASHRAE Standard 170 – 2010 Edition

1.4 INDUSTRY STANDARDS

A. All work shall comply with the following standards.

1. Associated Air Balance council (AABC)
2. Air Conditioning and Refrigeration Institute (ARI)
3. Air Diffusion council (ADC)
4. Air Movement and Control Association (AMCA)
5. American Gas Association (AGA)
6. American National Standards Institute (ANSI)
7. American Society of Heating, Refrigeration, and Air Conditioning Engineers (ASHRAE)
8. American Society of Mechanical Engineers (ASME)
9. American Society of Testing Materials (ASTM)
10. American Water Works Association (AWWA)
11. Cooling Tower Institute (CTI)
12. ETL Testing Laboratories (ETL)
13. Institute of Electrical and Electronic Engineers (IEEE)
14. Hydronics Institute (HI)
15. Manufacturers Standardization Society of the Valve and Fitting Industry (MSS)
16. National Fire Protection Association (NFPA)
17. National Electrical Code (NEC)
18. National Electrical Manufacturers Association (NEMA)
19. National Electrical Safety code (NESC)
20. Utah safety Standard (OSHA), Utah State Industrial Council.
21. Sheet Metal and Air Conditioning Contractor's National Association (SMACNA)
22. Underwriters Laboratories (UL)
23. Tubular Exchanger Manufacturers Association, Inc. (TEMA)
24. Heat Exchanger Institute (HEI)
25. Hydraulic Institute (HI)
26. Thermal Insulation Manufacturer=s Association (TIMA)
27. Scientific Apparatus Makers Association (SAMA)

B. Compliance Verification:

1. All items required by code or specified to conform to the ASME code shall be stamped with the ASME seal.
2. Form U-1, the manufacturer=s data report for pressure vessels, is to be included in the Operation and Maintenance Manuals. National Board Register (NBR) numbers shall be provided where required by code.
3. Manufactured equipment which is represented by a UL classification and/or listing, shall bear the UL or equivalent ETL label.

1.5 UTILITIES & FEES

- A. All fees for permits required by this work will be paid by this division with the understanding that any fees that are required to be paid will be reimbursed by the owner. The contractor shall obtain the necessary permits to perform this work. Unless noted otherwise, all systems furnished and or installed by this Contractor, shall be complete with all utilities, components, commodities and accessories required for a fully functioning system. This Contractor shall furnish smoke generators when required for testing, furnish glycol for glycol piping systems, full load of salt to fill brine tank for water softening system, furnish cleaners and water treatment additives.

1.6 SUBMITTALS AND SHOP DRAWINGS

- A. General: As soon as possible after the contract is awarded, but in no case more than 45 calendar days thereafter, the Contractor shall submit to the Architect manufacturer's data on products and materials to be used in the installation of mechanical systems for this project. The review of the submitted data will require a minimum of 14 days. The first day starts after the day they are received in the engineer's office to which the project is being constructed from. If the Contractors schedule requires return of submitted literature in less than the allotted time, the Contractor shall accelerate his submittal delivery date. The Contractor shall resubmit all items requiring re-review within 14 days of returned submittals. Refer to each specification section for items requiring submittal review. If the re-submittal is returned a 2<sup>nd</sup> time for correction the Contractor will provide the specific equipment that is specified on the drawings and/or the specifications. Written approval of the Owner's Representative shall be obtained before installing any such equipment or materials for the project.
- B. Review by the Owner's Representative is for general conformance of the submitted equipment to the project specification. In no way does such review relieve this Contractor of his obligation to furnish equipment and materials that comply in detail to the specification nor does it relieve the Contractor of his obligation to determine actual field dimensions and conditions that may affect his work. Regardless of any items overlooked by the submittal review, the requirements of the contract drawings and specifications must be followed and are not waived or superseded in any way by the review.
- C. By description, catalog number, and manufacturer's names, standards of quality have been established by the Architect and the Engineer for certain manufactured equipment items and specialties that are to be furnished by this Division. Alternate products and equipment may be proposed for use only if specifically named in the specifications or if given written prior approval in published addenda. Design equipment is the equipment listed on the drawings or if not listed on the drawings is the equipment first named in the specifications.
- D. Submittal Format: At the contractor's discretion, project submittals may be in either of the formats described in the following paragraphs, but mixing the two formats is not acceptable.
  - 1. Electronic Submittal Format: Identify and incorporate information in each electronic submittal file as follows:
    - a. All items shall be submitted at one time except automatic temperature control drawings and seismic restraint drawings which may be submitted separately within 120 days of the contract award date. Partial submittals will not be reviewed until the complete submittal is received.

- b. Submitted electronic file shall bear the Contractor's stamp, indicating that he has checked all equipment being submitted; that each item will fit into the available space with the accesses shown on the drawings; and, further, that each item conforms to the capacity and quality standards given in the contract documents.
- c. Submitted electronic file shall clearly indicate performance, quality, and utility requirements; shall show dimension and size of connection points; and shall include derating factors that were applied for each item of equipment to provide capacity at job site elevation. Temperature control submittals shall include piping and wiring diagrams, sequence of operation and equipment. Equipment must fit into the available space with allowance for operation, maintenance, etc. Factory piped and wired equipment shall include shop drawings for all internal wiring and piping furnished with the unit.
- d. Submitted electronic file shall clearly show all required field install wiring, piping, and accessory installations required by the Contractor to provide a complete operating system.
- e. Assemble complete submittal package into a single indexed file incorporating submittal requirements of a single Specification Section and transmittal form with links enabling navigation to each item.
- f. Name file with submittal number or other unique identifier, including revision identifier.
- g. Electronic file shall be completely electronically searchable or it will be rejected.
- h. Provide means for insertion to permanently record Contractor's review and approval markings and action taken by:
  - 1) Architect.
- i. Transmittal Form for Electronic Submittals:
  - 1) Use one of the following options acceptable to the Owner;
    - a) Software-generated form from electronic project management software.
    - b) Electronic form.
  - 2) The Electronic Submittal shall contain the following information:
    - a) Project name.
    - b) Date.
    - c) Name and address of Architect.
    - d) Name of Construction Manager.
    - e) Name of Contractor.
    - f) Name of firm or entity that prepared submittal.
    - g) Names of subcontractor, manufacturer, and supplier.
    - h) Category and type of submittal.
    - i) Submittal purpose and description.
    - j) Specification Section number and title.
    - k) Specification paragraph number or drawing designation and generic name for each of multiple items.
    - l) Drawing number and detail references, as appropriate.
    - m) Location(s) where product is to be installed, as appropriate.
    - n) Related physical samples submitted directly.
    - o) Indication of full or partial submittal.
    - p) Transmittal number[, numbered consecutively].

- q) Submittal and transmittal distribution record.
    - r) Other necessary identification.
    - s) Remarks.
  - j. Metadata: Include the following information as keywords in the electronic submittal file metadata:
    - 1) Project name.
    - 2) Number and title of appropriate Specification Section.
    - 3) Manufacturer name.
    - 4) Product name.
- E. Submittal Requirements - Submittals MUST be compiled in PDF format, organized, properly labeled with specification sections, and book marked.
- 1. Mail physical samples to the mechanical contractor's office.
  - 2. Submittal files larger than 25MB must be delivered to the mechanical contractor.
  - 3. Subcontractor/Vendor markups should be purple. GC markups will be blue, architect markups will be red, and consultant markups will be green. Any variations of sizing and/or performance shall be clearly indicated with an explanation of variation.
  - 4. Submittals must be submitted no later than two weeks from notice.
  - 5. Partial submittals will not be accepted. All required test data, certifications, qualification data, schedules, shop drawings, test reports, etc. must be included.
  - 6. Substitutions not previously accepted will not be allowed in submittals.
  - 7. All clarifications and questions about scope of work must be submitted in RFI(s) rather than in submittals
  - 8. Specific schedule of lead times for all items that are not 'off the shelf' must be submitted within 10 days of NTP. (See schedule requirements)

## 1.7 DRAWINGS AND MEASUREMENTS

- A. Construction Drawings: The contract document drawings show the general design, arrangements, and extent of the system. In certain cases, the drawings may include details that show more nearly exact locations and arrangements; however, the locations, as shown diagrammatically, are to be regarded as general.
- B. It shall be the work of this Section to make such slight alterations as may be necessary to make adjustable parts fit to fixed parts, leaving all complete and in proper shape when done. All dimensions given on the drawings shall be verified as related to this work and with the Architect's office before work is started.
- C. This Section shall carefully study building sections, space, clearances, etc., and then provide offsets in piping or ductwork as required to accommodate the building structure without additional cost to the Owner. In any case and at any time during the construction process, a change in location required by obstacles or the installation of other trades not shown on the mechanical plans shall be made without charge.
- D. The drawings shall not be scaled for roughing in measurements nor shall they be used as shop drawings. Where drawings are required for these purposes or where drawings must be made from field measurements, the Contractor shall take the necessary measurements and prepare the drawings. Shop drawings of the various subcontractors shall be coordinated to eliminate all

interferences and to provide sufficient space for the installation of all equipment, piping, ductwork, etc.

- E. The drawings and specifications have been prepared to supplement each other and they shall be interpreted as an integral unit with items shown on one and not the other being furnished and installed as though shown and called out on both.
- F. Coordination Drawings: The contractor shall provide coordination drawings for mechanical rooms, fan rooms, equipment rooms, and congested areas to eliminate conflicts with equipment, piping, or work of other trades. The drawings shall be a minimum scale of 1/4 inch= 1 foot and of such detail as may be required by the Engineer to fully illustrate the work. These drawings shall include all piping, conduit, valves, equipment, and ductwork.
- G. Sheet-metal shop drawings will be required for all ductwork in the entire building. These drawings will show all ductwork in the entire building and shall be coordinated with architectural, structural and electrical portions of the project. The contractor shall specifically obtain copies of the structural shop drawings and shall coordinate the ductwork shop drawings with approved structural members. These drawings shall be submitted to the engineer for review prior to any fabrication. The contractor is responsible for all modifications necessary to accommodate duct installation within the structural, architectural and electrical restrictions. These drawings, once reviewed by the engineer, will be made available to all mechanical, electrical, and fire sprinkler subcontractors to coordinate installation of their work.

#### 1.8 CONTRACTOR'S USE OF BUILDING EQUIPMENT

- A. The Contractor may use equipment such as electric motors, fans, heat exchangers, filters, etc., with the written permission of the Owner. As each piece of equipment is used (such as electric motors and fans), maintenance procedures approved by the manufacturer are to be followed. A careful record is to be kept of the length of the time the equipment is used, maintenance procedures followed, and any difficulty encountered. The record is to be submitted to the Owner upon acceptance. All fan belts and filter media (such as bearings) shall be carefully inspected just prior to acceptance. Any excessive wear noted shall require replacement. New filter media shall be installed in air handlers at the time systems are turned over to the owner.

#### 1.9 EXISTING CONDITIONS

- A. The Contractor shall carefully examine all existing conditions that might affect the mechanical system and shall compare these conditions with all drawings and specifications for work included under this contract. He shall, at such time, ascertain and check all conditions that may affect his work. No allowance shall subsequently be made in his behalf for an extra expense incurred as a result of his failure or neglect to make such examination. This Contractor shall include in his bid proposal all necessary allowances to repair or replace any item that will remain or will be removed, and any item that will be damaged or destroyed by new construction.
- B. The Contractor shall remove all abandoned piping, etc., required by new construction and cap or plug openings. No capping, etc., shall be exposed in occupied areas. All openings of items removed shall be sealed to match adjacent surfaces.

- C. The Contractor shall verify the exact location of all existing services, utilities, piping, etc., and make connections to existing systems as required or as shown on the drawings. The exact location of each utility line, together with size and elevation, shall be established before any on-site lines are installed. Should elevation or size of existing main utility lines make connections to them impossible as shown on drawings, then notification of such shall immediately be given to the Owners Representative for a decision.
- D. Any HVAC system that is modified shall be rebalanced and recommissioned additional requirements. If the unit modified serves more than the area under the current scope of work, the entire area served by that unit must be re-balanced and recommissioned.

#### 1.10 EQUIPMENT CAPACITIES

- A. Capacities shown for equipment in the specifications and on the drawings are the minimum acceptable. No equipment shall be considered as an alternate that has capacities or performance less than that of design equipment.
- B. All equipment shall give the specified capacity and performance at the job-site elevation. Manufacturers' standard ratings shall be adjusted accordingly. All capacities and performances listed on drawings or in specifications are for job-site conditions.

#### 1.11 SEISMIC REQUIREMENTS FOR EQUIPMENT

- A. All equipment shall be furnished structurally adequate to withstand seismic forces as outlined in the International Building Code. Refer to section Mechanical Vibration Controls and Seismic Restraints. Equipment bases shall be designed for direct attachment of seismic snubbers and/or seismic anchors.

#### 1.12 COOPERATION WITH OTHER TRADES

- A. The Contractor shall refer to other drawings and parts of this specification that cover work of other trades that is carried on in conjunction with the mechanical work such that all work can proceed without interference resulting from lack of coordination.
- B. The Contractor shall properly size and locate all openings, chases, sleeves, equipment bases, and accesses. He shall provide accurate wiring diagrams to the Electrical Contractor for all equipment furnished under this Division.
- C. The ceiling cavity must be carefully reviewed and coordinated with all trades. In the event of conflict, the installation of the mechanical equipment and piping shall be in the following order: plumbing, waste, and soil lines; supply, return, and exhaust ductwork; water piping; medical gases; fire protection piping; and pneumatic control piping.
- D. The mechanical Contractor shall insure that the installation of all piping, ducts and equipment is in compliance with Articles 110-16 and 384-4 of the National Electrical Code relative to proper clearances in front of and over all electrical panels and equipment. No piping or ductwork will be allowed to run over electrical panel.



1.13 RESPONSIBILITY OF CONTRACTOR

- A. The Contractor is responsible for the installation of a satisfactory piece of work in accordance with the true intent of the drawings and specifications. He shall provide, as a part of his work and without expense, all incidental items required even though these items are not particularly specified or indicated. The installation shall be made so that its several component parts will function together as a workable system and shall be left with all equipment properly adjusted and in working order. The Contractor shall familiarize the Owner's Representative with maintenance and lubrication instructions as prepared by the Contractor and shall explain and fully instruct him relative to operating, servicing, and maintenance of them.
- B. If a conflict arises between the drawings and the specifications the most stringent procedure/action shall be followed. A clarification to the engineer will help to determine the course of action to be taken. If a conflict arises between specification sections the engineer will determine which course of action is to be followed.

1.14 PIPE AND DUCT OPENINGS AND EQUIPMENT RECESSES

- A. Pipe and duct chases, openings, and equipment recesses shall be provided by others only if shown on architectural or structural drawings. All openings for the mechanical work, except where plans and specifications indicate otherwise, shall be provided as work of this Division. Include openings information with coordination drawings.
- B. Whether chases, recesses, and openings are provided as work of this Division or by others, this Contractor shall supervise their construction and be responsible for the correct size and location even though detailed and dimensioned on the drawings. This Contractor shall pay for all necessary cutting, repairing, and finishing if any are left out or incorrectly made. All necessary openings thru existing walls, ceilings, floors, roofs, etc. shall be provided by this Contractor unless indicated otherwise by the drawing and/or specifications.

1.15 UNFIT OR DAMAGED WORK

- A. Any part of this installation that fails, is unfit, or becomes damaged during construction, shall be replaced or otherwise made good. The cost of such remedy shall be the responsibility of this Division.

1.16 WORKMANSHIP

- A. Workmanship shall be the best quality of its kind for the respective industries, trades, crafts, and practices, and shall be acceptable in every respect to the Owner's representative. Nothing contained herein shall relieve the Contractor from making good and perfect work in all details in construction.

1.17 SAFETY REGULATION

- A. The Contractor shall comply with all local, Federal, and OSHA safety requirements in performance with this work. (See General Conditions). This Contractor shall be required to provide equipment,

supervision, construction, procedures, and all other necessary items to assure safety to life and property.

#### 1.18 ELECTRICAL SERVICES

- A. All equipment control wiring and all automatic temperature control wiring including all necessary contacts, relays, and interlocks, whether low or line voltage, except power wiring, shall be furnished and installed as work of this Division unless shown to be furnished by Division 26. All such wiring shall be in conduit as required by electrical codes. Wiring in the mechanical rooms, fans rooms and inaccessible ceilings and walls shall be installed in conduit as well. Installation of any and all wiring done under Division 21, 22 and 23 shall be in accordance with the requirements of Division 26, Electrical.
- B. All equipment that requires an electrical connection shall be furnished so that it will operate properly and deliver full capacity on the electrical service available.
- C. Refer to the electrical control equipment and wiring shown on the diagrams. Any changes or additions required by specific equipment furnished shall be the complete responsibility of the Contractor furnishing the equipment.
- D. The Mechanical Contractor must coordinate with the Electrical Contractor to insure that all required components of control work are included and fully understood. No additional cost shall accrue to the Owner as a result of lack of such coordination.

#### 1.19 WORK, MATERIALS, AND QUALITY OF EQUIPMENT

- A. Unless otherwise specified, all materials shall be new and of the best quality of their respective kinds and all labor shall be done in a most thorough and workmanlike manner.
- B. Products or equipment of any of the manufacturers cited herein or any of the products approved by the Addenda may be used. However, where lists of products are cited herein, the one first listed in the design equipment used in drawings and schedules to establish size, quality, function, and capacity standards. If other than design equipment is used, it shall be carefully checked for access to equipment, electrical and control requirements, valving, and piping. Should changes or additions occur in piping, valving, electrical work, etc., or if the work of other Contractors would be revised by the alternate equipment, the cost of all changes shall be borne as work of this Division.
- C. The Execution portions of the specifications specify what products and materials may be used. Any products listed in the Product section of the specification that are not listed in the Execution portion of the specification may not be used without written approval by the Engineer.
- D. The access to equipment shown on the drawings is the minimum acceptable space requirements. No equipment that reduces or restricts accessibility to this or any other equipment will be considered.
- E. All major items of equipment are specified in the equipment schedules on the drawings or in these specifications and shall be furnished complete with all accessories normally supplied with the catalog item listed and all other accessories necessary for a complete and satisfactory installation.

- F. All welders shall be certified in accordance with Section IX of the ASME Boiler and Pressure Vessel Code, latest Edition.

#### 1.20 PROTECTION AGAINST WEATHER AND STORING OF MATERIALS

- A. All equipment and materials shall be properly stored and protected against moisture, dust, and wind. Coverings or other protection shall be used on all items that may be damaged or rusted or may have performance impaired by adverse weather or moisture conditions. Damage or defect developing before acceptance of the work shall be made good at the Contractor's expense.
- B. All open duct and pipe openings shall be adequately covered at all times.

#### 1.21 INSTALLATION CHECK

- A. An experienced, competent, and authorized representative of the manufacturer or supplier of each item of equipment indicated in the equipment schedule and the seismic supplier shall visit the site of the work and inspect, check, adjust if necessary, and approve the equipment installation. In each case, the equipment supplier's representative shall be present when the equipment is placed in operation. The equipment supplier's representative shall revisit the job site as often as necessary until all trouble is corrected and the equipment installation and operation is satisfactory to the Engineer.
- B. Each equipment supplier's representative shall furnish to the Owner, through the Engineer, a written report certifying that the equipment (1) has been properly installed and lubricated; (2) is in accurate alignment; (3) is free from any undue stress imposed by connecting piping or anchor bolts; and, (4) has been operated under full load conditions and that it operated satisfactorily.
- C. All costs for this work shall be included in the prices quoted by equipment suppliers.

#### 1.22 EQUIPMENT LUBRICATION

- A. The Contractor shall properly lubricate all pieces of equipment before turning the building over to the Owner. A linen tag shall be attached to each piece of equipment, showing the date of lubrication and the lubricant used. No equipment shall be started until it is properly lubricated.
- B. Necessary time shall be spent with the Owner's Representative to thoroughly familiarize him with all necessary lubrications and maintenance that will be required of him.
- C. Detergent oil as used for automotive purposes shall not be used for this work.

#### 1.23 CUTTING AND PATCHING

- A. No cutting or drilling in structural members shall be done without written approval of the Architect. The work shall be carefully laid out in advance, and cutting, channeling, chasing, or drilling of floors, walls, partitions, ceilings, or other surfaces necessary for the mechanical work shall be carefully done. Any damage to building, piping, or equipment shall be repaired by professional

plasterers, masons, concrete workers, etc., and all such work shall be paid for as work of this Division.

- B. When concrete, grading, etc., is disturbed, it shall be restored to original condition as described in the applicable Division of this Specification.

#### 1.24 ACCESS

- A. Provide access doors in walls, ceilings and floors by this division unless otherwise noted. For access to mechanical equipment such as valves, dampers, VAV boxes, fans, controls, etc. Refer to Division 8 for door specifications. All access doors shall be 24" x 24" unless otherwise indicated or required. Coordinate location of doors with the Architect prior to installation. . If doors are not specified in Division 8, provide the following: Doors in ceilings and wall shall be equal to JR Smith No. 4760 bonderized and painted. Doors in tile walls shall be equal to JR Smith No. 4730 chrome plated. Doors in floors shall be equal to JR Smith No. 4910
- B. Valves: Valve must be installed in locations where access is readily available. If access is compromised, as judged by the Mechanical Engineer, these valves shall be relocated where directed at the Contractors expense.
- C. Equipment: Equipment must be installed in locations and orientations so that access to all components requiring service or maintenance will not be compromised. If access is compromised, as judged by the Mechanical Engineer, the contractor shall modify the installation as directed by the Engineer at the Contractors expense.
- D. It is the responsibility of this division to install terminal boxes, valves and all other equipment and devices so they can be accessed. If any equipment or devices are installed so they cannot be accessed on a ladder a catwalk and ladder system shall be installed above the ceiling to access and service this equipment.
- E. Fans with 3 HP and above, which are elevated such that the distance from floor to any maintenance point is 6-feet or higher, shall have an appropriate access platform with permanent ladders or steps designed and shown on the design drawings.
- F.

#### 1.25 CONCRETE BASES AND INSERTS

- A. Bases: The concrete bases shall be provided and installed as work by this division. This Division shall be responsible for the proper size and location of bases and shall furnish all required anchor bolts and sleeves with templates to be installed as work of Division 03, Concrete.
- B. All floor-mounted mechanical equipment shall be set on 6-inch high concrete bases, unless otherwise noted or shown on drawings. Such bases shall extend 6 inches beyond equipment or mounting rails on all sides or as shown on the drawings and shall have a 1-inch beveled edge all around.

- C. Inserts: Where slotted or other types of inserts required for this work are to be cast into concrete, they shall be furnished as work of this Division
- D. Concrete inserts and pipe support systems shall be equal to Unistrut P3200 series for all piping where more than one pipe is suspended at a common location. Spacing of the inserts shall match the size and type of pipe and of ductwork being supported. The Unistrut insert and pipe support system shall include all inserts, vertical supports, horizontal support members, clamps, hangers, rollers, bolts, nuts, and any other accessory items for a complete pipe-supporting system.

#### 1.26 CLEANING AND PAINTING

- A. Cleaning: After all tests and adjustments have been made and all systems pronounced satisfactory for permanent operation, this Contractor shall clean all exposed piping, ductwork, insulated members, fixture, and equipment installed under this Section and leave them ready for painting. He shall refinish any damaged finish and leave everything in proper working order. The Contractor shall remove all stains or grease marks on walls, floors, glass, hardware, fixtures, or elsewhere, caused by his workman or for which he is responsible. He shall remove all stickers on plumbing fixtures, do all required patching up and repair all work of others damaged by this division of the work, and leave the premises in a clean and orderly condition.
- B. Painting: Painting of exposed pipe, insulated pipe, ducts, or equipment is work of Division 09, Exterior and Interior Painting.
- C. Mechanical Contractor: All equipment which is to be furnished in factory prefinished conditions by the mechanical Contractor shall be left without mark, scratch, or impairment to finish upon completion of job. Any necessary refinishing to match original shall be done. Do not paint over nameplates, serial numbers, or other identifying marks.
- D. Removal of Debris, Etc: Upon completion of this division of the work, remove all surplus material and rubbish resulting from this work, and leave the premises in a clean and orderly condition.

#### 1.27 CONTRACT COMPLETION

- A. Incomplete and Unacceptable Work: If additional site visits or design work is required by the Engineer or Architect because of the use of incomplete or unacceptable work by the Contractor, then the Contractor shall reimburse the Engineer and Architect for all additional time and expenses involved.
- B. Maintenance Instructions: The Contractor shall furnish the Owner complete printed and illustrated operating and maintenance instructions covering all units of mechanical equipment, together with parts lists.
- C. Instructions To Owner's Representatives: In addition to any detailed instructions called for, the mechanical Contractor must provide, without expense to the Owner, competent instructors to train the Owner's representatives who will be in charge of the apparatus and equipment, in the care, adjustment, and operation of all parts on the heating, air conditioning, ventilating, plumbing, fire protection, and automatic temperature control equipment. Instruction dates shall be scheduled at time of final inspection. A written report specifying times, dates, and name of personnel instructed

shall be forwarded to the Architect. A minimum of four 8-hour instruction periods shall be provided. The instruction periods will be broken down to shorter periods when requested by the Owner. The total instruction hours shall not be reduced. The ATC Contractor shall provide 4 hours of instructions. The remaining hours shall be divided between the mechanical and sheet metal Contractor.

- D. Guarantee: By the acceptance of any contract award for the work herein described or shown on the drawings, the Contractor assumes the full responsibility imposed by the guarantee as set forth herein and in the General Conditions, and should protect himself through proper guarantees from equipment and special equipment Contractors and from subcontractors as their interests may appear.
- E. The guarantee so assumed by the Contractor and as work of this Section is as follows:
1. That the entire mechanical system, including plumbing, heating, and air-conditioning system shall be quiet in operation.
  2. That the circulation of water shall be complete and even.
  3. That all pipes, conduit, and connections shall be perfectly free from foreign matter and pockets and that all other obstructions to the free passage of air, water, liquid, sewage, and vent shall be removed.
  4. That he shall make promptly and free of charge, upon notice from the Owner, any necessary repairs due to defective workmanship or materials that may occur during a period of one year from date of Substantial Completion.
  5. That all specialties, mechanical, and patent devices incorporated in these systems shall be adjusted in a manner that each shall develop its maximum efficiency in the operation of the system; i.e., diffusers shall deliver the designed amount of air shown on drawings, thermostats shall operate to the specified limits, etc.
  6. All equipment and the complete mechanical, ductwork, piping and plumbing systems shall be guaranteed for a period of one year from the date of the Architect's Certificate of Substantial Completion, this includes all mechanical, ductwork, piping and plumbing equipment and products and is not limited to boiler, chillers, coils, fans, filters etc. Any equipment supplier not willing to comply with this guarantee period shall not submit a bid price for this project. The Contractor shall be responsible for a 100-percent guarantee for the system and all items of equipment for this period. If the contractor needs to provide temporary heating or cooling to the building and or needs to insure systems are installed properly and or to meet the project schedule the guaranteed of all systems and equipment shall be as indicated above, on year from the date of the Architect's Certificate of Substantial Completion.
  7. All filters used during construction shall be replaced just before equipment is turned over to the Owner, and all required equipment and parts shall be oiled. Any worn parts shall also be replaced.
  8. If any systems or equipment is used for temporary heating or cooling the systems shall be protected so they remain clean. I.e. if the ductwork systems are used temporary filters and a filter holder (not duct-taped to ducts or grilles) shall be installed to insure the systems and the equipment remain clean.

#### 1.28 CURBS

- A. Unless otherwise noted in these specifications or on the documents all roof curbs for all equipment are to be provided by Division 22 and 23.

1.29 TEST RUN

- A. The Mechanical Contractor shall operate the mechanical system for a minimum of 30 days to prove the operation of the system.

1.30 EQUIPMENT STARTUP AND CHECKOUT:

- A. Each major piece of equipment shall be started and checked out by an authorized representative of the equipment manufacturer. A certificate indicating the equipment is operating to the satisfaction of the manufacturer shall be provided and shall be included in the commissioning report.
- B. This contractor shall coordinate commissioning procedures and activities with the commissioning agent.

1.31 DEMOLITION

- A. General: Demolish and remove existing construction only to the extent required by new construction and as indicated. Use methods required to complete the Work within limitations of governing regulations and as follows:
- B. Proceed with demolition systematically, from higher to lower level. Complete selective demolition operations above each floor or tier before disturbing supporting members on the next lower level.
- C. Neatly cut openings and holes plumb, square, and true to dimensions required. Use cutting methods least likely to damage construction to remain or adjoining construction. Use hand tools or small power tools designed for sawing or grinding, not hammering and chopping, to minimize disturbance of adjacent surfaces. Temporarily cover openings to remain.
- D. Cut or drill from the exposed or finished side into concealed surfaces to avoid marring existing finished surfaces.
- E. Do not use cutting torches until work area is cleared of flammable materials. At concealed spaces, such as duct and pipe interiors, verify condition and contents of hidden space before starting flame-cutting operations. Maintain portable fire-suppression devices during flame-cutting operations.
- F. Maintain adequate ventilation when using cutting torches.
- G. Remove decayed, vermin-infested, or otherwise dangerous or unsuitable materials and promptly dispose of off-site.
- H. Remove structural framing members and lower to ground by method suitable to avoid free fall and to prevent ground impact or dust generation.
- I. Locate selective demolition equipment and remove debris and materials so as not to impose excessive loads on supporting walls, floors, or framing.
- J. Dispose of demolished items and materials promptly.

- K. Return elements of construction and surfaces that are to remain to condition existing before selective demolition operations began.
- L. Existing Facilities: Comply with building manager's requirements for using and protecting elevators, stairs, walkways, loading docks, building entries, and other building facilities during selective demolition operations.
- M. Concrete: Demolish in sections. Cut concrete full depth at junctures with construction to remain and at regular intervals, using power-driven saw, then remove concrete between saw cuts.
- N. Masonry: Demolish in small sections. Cut masonry at junctures with construction to remain, using power-driven saw, and then remove masonry between saw cuts.
- O. Concrete Slabs-on-Grade: Saw-cut perimeter of area to be demolished, then break up and remove.
- P. Air-Conditioning Equipment: Remove equipment without releasing refrigerants.

END OF SECTION 23 0100



## SECTION 23 0150 - TEMPORARY USE OF EQUIPMENT AND SYSTEMS

### PART 1 - GENERAL

#### 1.1 SUMMARY

- A. This section includes requirements for temporary use of equipment and systems and any other items that are used during the construction of the project.

#### 1.2 EQUIPMENT OR SYSTEMS NEEDED TO OPERATE BEFORE CONTRACT COMPLETION

- A. If the contractor needs to provide temporary heating or cooling to the building and or needs to insure systems are installed properly for start up and or to meet the project schedule the guaranteed of all systems and equipment shall be for one year from the date of the Architect's Certificate of Substantial Completion.

All equipment and the complete mechanical, ductwork, piping and plumbing systems shall be guaranteed for a period of one year from the date of the Architect's Certificate of Substantial Completion, this includes all mechanical, ductwork, piping and plumbing equipment and products and is not limited to boiler, chillers, coils, fans, filters etc. Any contractor or equipment supplier who is not willing to comply with this guarantee period shall not submit a bid price for this project. The Contractor shall be responsible for a 100-percent guarantee for the systems and all items of equipment for this period.

All filters used during construction shall be replaced just before equipment is turned over to the Owner, and all required equipment and parts shall be oiled. Any worn parts shall also be replaced.

If any systems or equipment is used for temporary heating or cooling the systems shall be protected so they remain clean. I.e. if the ductwork systems are used temporary filters and a filter holder (not duct-taped to ducts or grilles) shall be installed to insure the systems and the equipment remain clean. All return air openings shall be protected with a metal filter frame and filters.

#### 1.3 TEMPORARY EQUIPMENT OR SYSTEM SUBMITTALS

- A. If it is determined by the project or contractor that equipment or systems are needed to operate to provide heating, cooling or other needed services this division shall submit a document indicating what measures will be taken to insure the safe and proper operation of the equipment, systems and personal associated with the operation, this document shall be submitted to the engineer for approval. This plan shall show connections of equipment, utility hookups (if required) staging areas etc.

#### 1.4 QUALITY ASSURANCE

- A. Electric Service: Comply with NECA, NEMA, and UL standards and regulations for temporary electric service. Install service to comply with NFPA 70.
- B. Tests and Inspections: Arrange for authorities having jurisdiction to test and inspect each temporary utility before use. Obtain required certifications and permits.
- C. Accessible Temporary Egress: Comply with applicable provisions in the U.S. Architectural & Transportation Barriers Compliance Board's ADA-ABA Accessibility Guidelines.
- D. SMACNA: The latest standard from SSMACNA shall apply.

#### 1.5 PROJECT CONDITIONS

- A. Temporary Use of equipment or systems: Engage installer of each permanent service to assume responsibility for operation, maintenance, and protection of each permanent service during its use until the facility has been accepted by the owner regardless of previously assigned responsibilities.

### PART 2 - PRODUCTS

#### 2.1 EQUIPMENT

- A. Fire Extinguishers: Portable, UL rated; with class and extinguishing agent as required by locations and classes of fire exposures.
- B. HVAC Equipment: Unless Owner authorizes use of permanent HVAC system, provide vented, self-contained, liquid-propane-gas or fuel-oil heaters and cooling units if required with individual space thermostatic control.
  - 1. Use of gasoline-burning space heaters, open-flame heaters, or salamander-type heating units is prohibited.
  - 2. Heating Units: Listed and labeled for type of fuel being consumed, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
  - 3. Permanent HVAC System: If Owner authorizes use of permanent HVAC system for temporary use during construction, provide filters with MERV of 8 at each return air opening in system and remove at end of construction. These filters are to be installed in a filter housing frame and are not to be duct taped. Clean HVAC system as required in Division 01 Section "Closeout Procedures."

## PART 3 - EXECUTION

### 3.1 INSTALLATION, GENERAL

- A. Locate equipment where they will serve Project adequately and result in minimum interference with performance of the Work. Relocate and modify equipment and systems as required by progress of the Work.
  - 1. Locate equipment to limit site disturbance as specified in Division 01 Section "Summary."

### 3.2 TEMPORARY UTILITY INSTALLATION

- A. General: Install temporary service or connect to existing service.
  - 1. Arrange with utility company, Owner, and existing users for time when service can be interrupted, if necessary, to make connections for temporary services.
- B. Water Service: Install water service and distribution piping in sizes and pressures adequate for construction.
- C. Heating and Cooling: Provide temporary heating and cooling required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of low temperatures or high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed.
- D. Ventilation and Humidity Control: Provide temporary ventilation required by construction activities for curing or drying of completed installations or for protecting installed construction from adverse effects of high humidity. Select equipment that will not have a harmful effect on completed installations or elements being installed. Coordinate ventilation requirements to produce ambient condition required and minimize energy consumption.

### 3.3 OPERATION, TERMINATION, AND REMOVAL

- A. Maintenance: Maintain equipment and systems in good operating condition until removal.
  - 1. Maintain operation of temporary enclosures, heating, cooling, humidity control, ventilation, and similar equipment and systems on a 24-hour basis where required to achieve indicated results and to avoid possibility of damage.
- B. Termination and Removal: Remove each temporary facility or equipment when need for its service has ended, when it has been replaced by authorized use of a permanent facility, or no later than Substantial Completion. Complete or, if necessary, restore permanent construction that may have been delayed because of interference with temporary facility. Repair damaged Work, clean exposed surfaces, and replace construction that cannot be satisfactorily repaired.
  - 1. Materials equipment that constitute temporary equipment are property of Contractor.

2. At Substantial Completion, repair, renovate, and clean permanent equipment and systems used during construction period. Comply with final cleaning requirements specified in Division 01 Section "Closeout Procedures."

#### 3.4 EQUIPMENT STARTUP AND CHECKOUT:

- A. Each major piece of equipment shall be started and checked out by an authorized representative of the equipment manufacturer at substantial completion. A certificate indicating the equipment is operating to the satisfaction of the manufacturer shall be provided and shall be included in the commissioning report.

END OF SECTION 23 0150

## SECTION 23 0500 - COMMON WORK RESULTS FOR HVAC

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following: Piping materials and installation instructions common to most piping systems.
  - 1. Transition fittings.
  - 2. Dielectric fittings.
  - 3. Grout.
  - 4. Equipment installation requirements common to equipment sections.
  - 5. Painting and finishing.
  - 6. Concrete bases.
  - 7. Supports and anchorages.
  - 8. Link-Seal

#### 1.3 DEFINITIONS

- A. Finished Spaces: Spaces other than mechanical and electrical equipment rooms, furred spaces, pipe and duct chases, unheated spaces immediately below roof, spaces above ceilings, unexcavated spaces, and crawlspaces.
- B. Exposed, Interior Installations: Exposed to view indoors. Examples include finished occupied spaces, mechanical equipment rooms, accessible pipe shafts, accessible plumbing chases, and accessible tunnels.
- C. Exposed, Exterior Installations: Exposed to view outdoors or subject to outdoor ambient temperatures and weather conditions. Examples include rooftop locations.
- D. Concealed, Interior Installations: Concealed from view and protected from physical contact by building occupants. Examples include above ceilings and chases.
- E. Concealed, Exterior Installations: Concealed from view and protected from weather conditions and physical contact by building occupants but subject to outdoor ambient temperatures. Examples include installations within unheated shelters.
- F. The following are industry abbreviations for plastic materials:
  - 1. CPVC: Chlorinated polyvinyl chloride plastic.
  - 2. PVC: Polyvinyl chloride plastic.

G. The following are industry abbreviations for rubber materials:

1. EPDM: Ethylene-propylene-diene terpolymer rubber.
2. NBR: Acrylonitrile-butadiene rubber.

1.4 SUBMITTALS

A. Product Data: For the following:

1. Transition fittings.
2. Dielectric fittings.

B. Welding certificates.

1.5 QUALITY ASSURANCE

A. Steel Support Welding: Qualify processes and operators according to AWS D1.1, "Structural Welding Code--Steel."

B. Steel Pipe Welding: Qualify processes and operators according to ASME Boiler and Pressure Vessel Code: Section IX, "Welding and Brazing Qualifications."

1. Comply with provisions in ASME B31 Series, "Code for Pressure Piping."
2. Certify that each welder has passed AWS qualification tests for welding processes involved and that certification is current.

C. Electrical Characteristics for HVAC Equipment: Equipment of higher electrical characteristics may be furnished provided such proposed equipment is approved in writing and connecting electrical services, circuit breakers, and conduit sizes are appropriately modified. If minimum energy ratings or efficiencies are specified, equipment shall comply with requirements.

1.6 DELIVERY, STORAGE, AND HANDLING

A. Deliver pipes and tubes with factory-applied end caps. Maintain end caps through shipping, storage, and handling to prevent pipe end damage and to prevent entrance of dirt, debris, and moisture.

B. Store plastic pipes protected from direct sunlight. Support to prevent sagging and bending.

1.7 COORDINATION

A. Arrange for pipe spaces, chases, slots, and openings in building structure during progress of construction, to allow for HVAC installations.

B. Coordinate installation of required supporting devices and set sleeves in poured-in-place concrete and other structural components as they are constructed.

- C. Coordinate requirements for access panels and doors for HVAC items requiring access that are concealed behind finished surfaces. Access panels and doors are specified in Division 08 Section "Access Doors and Frames."

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. In other Part 2 articles where subparagraph titles below introduce lists, the following requirements apply for product selection:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by the manufacturers specified.

### 2.2 PIPE, TUBE, AND FITTINGS

- A. Refer to individual Division 23 piping Sections for pipe, tube, and fitting materials and joining methods.
- B. Pipe Threads: ASME B1.20.1 for factory-threaded pipe and pipe fittings.

### 2.3 JOINING MATERIALS

- A. Refer to individual Division 23 piping Sections for special joining materials not listed below.
- B. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
  - 1. ASME B16.21, nonmetallic, flat, asbestos-free, 1/8-inch maximum thickness unless thickness or specific material is indicated.
    - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
    - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
  - 2. AWWA C110, rubber, flat face, 1/8 inch thick, unless otherwise indicated; and full-face or ring type, unless otherwise indicated.
- C. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.
- D. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- E. Brazing Filler Metals: AWS A5.8, BCuP Series, copper-phosphorus alloys for general-duty brazing, unless otherwise indicated; and AWS A5.8, BAg1, silver alloy for refrigerant piping, unless otherwise indicated.

1. Use of flux is required in all brazing applications. The flux used is to be a black brazing flux that does not contain boric acid and conforms to AWS A5.31 class FB3-C.

- F. Welding Filler Metals: Comply with AWS D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

## 2.4 TRANSITION FITTINGS

- A. Plastic-to-Metal Transition Fittings: CPVC and PVC one-piece fitting with manufacturer's Schedule 80 equivalent dimensions; one end with threaded brass insert, and one solvent-cement-joint end.

1. Manufacturers:

- a. Eslon Thermoplastics.

- B. Plastic-to-Metal Transition Adaptors: One-piece fitting with manufacturer's SDR 11 equivalent dimensions; one end with threaded brass insert, and one solvent-cement-joint end.

1. Manufacturers:

- a. Thompson Plastics, Inc.

## 2.5 DIELECTRIC FITTINGS

- A. General: Assembly or fitting with insulating material isolating joined dissimilar metals, to prevent galvanic action and stop corrosion.

- B. Description: Combination of copper alloy and ferrous; threaded, solder, plain, and weld-neck end types and matching piping system materials.

- C. Insulating Material: Suitable for system fluid, pressure, and temperature.

- D. Dielectric Unions: Factory-fabricated, union assembly, for 250-psig minimum working pressure at 180 deg F.

- E. Dielectric Flanges: Factory-fabricated, companion-flange assembly, for 150- or 300-psig minimum working pressure as required to suit system pressures.

- F. Dielectric-Flange Insulation Kits: Field-assembled, companion-flange assembly, full-face or ring type. Components include neoprene or phenolic gasket, phenolic or polyethylene bolt sleeves, phenolic washers, and steel backing washers.

1. Provide separate companion flanges and steel bolts and nuts for 150- or 300-psig minimum working pressure as required to suit system pressures.

- G. Dielectric Couplings: Galvanized-steel coupling with inert and noncorrosive, thermoplastic lining; threaded ends; and 300-psig minimum working pressure at 225 deg F.



- H. Dielectric Nipples: Electroplated steel nipple with inert and noncorrosive, thermoplastic lining; plain, threaded, or grooved ends; and 300-psi minimum working pressure at 225 deg F.

1. Manufacturers:
  - a. Capitol Manufacturing Co.
  - b. Central Plastics Company.
  - c. Watts Industries, Inc.; Water Products Div

## 2.6 GROUT

- A. Description: ASTM C 1107, Grade B, non-shrink and nonmetallic, dry hydraulic-cement grout.
1. Characteristics: Post-hardening, volume-adjusting, non-staining, noncorrosive, nongaseous, and recommended for interior and exterior applications.
  2. Design Mix: 5000-psi, 28-day compressive strength.
  3. Packaging: Premixed and factory packaged.

## 2.7 LINK-SEAL MODULAR SEAL PRESSURE PLATES

- A. Link-Seal® modular seal pressure plates shall be molded of glass reinforced Nylon Polymer with the following properties:
1. Izod Impact - Notched = 2.05ft-lb/in. per ASTM D-256
  2. Flexural Strength @ Yield = 30,750 psi per ASTM D-790
  3. Flexural Modulus = 1,124,000 psi per ASTM D-790
  4. Elongation Break = 11.07% per ASTM D-638
  5. Specific Gravity = 1.38 per ASTM D-792
- B. Models LS200-275-300-315 shall incorporate the most current Link-Seal® Modular Seal design modifications and shall include an integrally molded compression assist boss on the top (bolt entry side) of the pressure plate, which permits increased compressive loading of the rubber sealing element. Models 315-325-340-360-400-410-425-475-500-525-575-600 shall incorporate an integral recess known as a "Hex Nut Interlock" designed to accommodate commercially available fasteners to insure proper thread engagement for the class and service of metal hardware. All pressure plates shall have a permanent identification of the manufacturer's name molded into it.
- C. For fire service, pressure plates shall be steel with 2-part Zinc Dichromate Coating.
- D. Link-Seal® Modular Seal Hardware: All fasteners shall be sized according to latest Link-Seal® modular seal technical data. Bolts, flange hex nuts shall be:
1. 316 Stainless Steel per ASTM F593-95, with a 85,000 psi average tensile strength.

## PART 3 - EXECUTION

### 3.1 PIPING SYSTEMS - COMMON REQUIREMENTS

- A. Install piping according to the following requirements and Division 23 Sections specifying piping systems.
- B. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Indicated locations and arrangements were used to size pipe and calculate friction loss, expansion, pump sizing, and other design considerations. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
- C. Install piping in concealed locations, unless otherwise indicated and except in equipment rooms and service areas.
- D. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls. Diagonal runs are prohibited unless specifically indicated otherwise.
- E. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal.
- F. Install piping to permit valve servicing.
- G. Install piping at indicated slopes.
- H. Install piping free of sags and bends.
- I. Install fittings for changes in direction and branch connections.
- J. Install piping to allow application of insulation.
- K. Select system components with pressure rating equal to or greater than system operating pressure.
- L. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Refer to Division 07 Section "Penetration Firestopping" for materials.
- M. Verify final equipment locations for roughing-in.
- N. Refer to equipment specifications in other Sections of these Specifications for roughing-in requirements.

### 3.2 PIPING JOINT CONSTRUCTION

- A. Join pipe and fittings according to the following requirements and Division 23 Sections specifying piping systems.
- B. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.

- C. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.
- D. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.
- E. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8 & a black brazing flux that does not contain boric acid complying with AWS A5.31 class FB3-C.
- F. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- G. Welded Joints: Construct joints according to AWS D10.12, using qualified processes and welding operators according to Part 1 "Quality Assurance" Article.
- H. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.

### 3.3 PIPING CONNECTIONS

- A. Make connections according to the following, unless otherwise indicated:
  - 1. Install unions, in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
  - 2. Install flanges, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.
  - 3. Dry Piping Systems: Install dielectric unions and flanges to connect piping materials of dissimilar metals.
  - 4. Wet Piping Systems: Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.

### 3.4 EQUIPMENT INSTALLATION - COMMON REQUIREMENTS

- A. Install equipment to allow maximum possible headroom unless specific mounting heights are not indicated.
- B. Install equipment level and plumb, parallel and perpendicular to other building systems and components in exposed interior spaces, unless otherwise indicated.

- C. Install HVAC equipment to facilitate service, maintenance, and repair or replacement of components. Connect equipment for ease of disconnecting, with minimum interference to other installations. Extend grease fittings to accessible locations.
- D. Install equipment to allow right of way for piping installed at required slope.

### 3.5 PAINTING

- A. Painting of HVAC systems, equipment, and components is specified in Division 09 Sections "Interior Painting" and "Exterior Painting."
- B. Damage and Touchup: Repair marred and damaged factory-painted finishes with materials and procedures to match original factory finish.

### 3.6 CONCRETE BASES

- A. Concrete Bases: Anchor equipment to concrete base according to equipment manufacturer's written instructions and according to seismic codes at Project.
  - 1. Construct concrete bases of dimensions indicated, but not less than 4 inches larger in both directions than supported unit.
  - 2. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch centers around the full perimeter of the base.
  - 3. Install epoxy-coated anchor bolts for supported equipment that extend through concrete base, and anchor into structural concrete floor.
  - 4. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
  - 5. Install anchor bolts to elevations required for proper attachment to supported equipment.
  - 6. Install anchor bolts according to anchor-bolt manufacturer's written instructions.
  - 7. Use 3000-psi, 28-day compressive-strength concrete and reinforcement as specified in Division 03 Section "Cast-in-Place Concrete."

### 3.7 ERECTION OF METAL SUPPORTS AND ANCHORAGES

- A. Refer to Division 05 Section "Metal Fabrications" for structural steel.
- B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor HVAC materials and equipment.
- C. Field Welding: Comply with AWS D1.1.

3.8 GROUTING

- A. Mix and install grout for HVAC equipment base bearing surfaces, pump and other equipment base plates, and anchors.
- B. Clean surfaces that will come into contact with grout.
- C. Provide forms as required for placement of grout.
- D. Avoid air entrapment during placement of grout.
- E. Place grout, completely filling equipment bases.
- F. Place grout on concrete bases and provide smooth bearing surface for equipment.
- G. Place grout around anchors.
- H. Cure placed grout.

3.9 LINK SEAL

- A. Provide Link Seal at all piping penetrations from the outside.

END OF SECTION 23 0500

## SECTION 23 0513 - COMMON MOTOR REQUIREMENTS FOR HVAC EQUIPMENT

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes general requirements for single-phase and polyphase, general-purpose, horizontal, small and medium, squirrel-cage induction motors for use on ac power systems up to 600 V and installed at equipment manufacturer's factory or shipped separately by equipment manufacturer for field installation.

#### 1.3 COORDINATION

- A. Coordinate features of motors, installed units, and accessory devices to be compatible with the following:
  - 1. Motor controllers.
  - 2. Torque, speed, and horsepower requirements of the load.
  - 3. Ratings and characteristics of supply circuit and required control sequence.
  - 4. Ambient and environmental conditions of installation location.

### PART 2 - PRODUCTS

#### 2.1 GENERAL MOTOR REQUIREMENTS

- A. Comply with requirements in this Section except when the requirements in equipment schedules, other specification sections, drawing notes or in other contract documents are more stringent.
- B. Comply with NEMA MG 1 unless otherwise indicated.
- C. All submitted motors are to be premium efficient motors.

#### 2.2 MOTOR CHARACTERISTICS

- A. Duty: Continuous duty at ambient temperature of 40 deg C and at altitude of 3300 feet above sea level.

- B. Capacity and Torque Characteristics: Sufficient to start, accelerate, and operate connected loads at designated speeds, at installed altitude and environment, with indicated operating sequence, and without exceeding nameplate ratings or considering service factor.
- C. Motors 3/4 HP and larger: Polyphase.
- D. Motors smaller than 3/4 HP: Single phase.
- E. All motors shall have ASTM Grade 5 hardware that is Yellow Zinc-dichromate plated.

## 2.3 POLYPHASE MOTORS

- A. Description: NEMA MG 1, Design B, medium induction motor.
- B. Efficiency: Premium energy efficient, as defined in NEMA MG 1.
- C. Service Factor: 1.15.
- D. Rotor: Random-wound, squirrel cage.
- E. Bearings: Regreasable, shielded, antifriction ball bearings suitable for radial and thrust loading.
- F. Temperature Rise: Match insulation rating.
- G. Insulation: Class F.
- H. Code Letter Designation:
  - 1. Motors 15 HP and Larger: NEMA starting Code F or Code G.
  - 2. Motors smaller than 15 HP: Manufacturer's standard starting characteristic.
- I. Enclosure Material: Cast iron for motor frame sizes 324T and larger; rolled steel for motor frame sizes smaller than 324T.

## 2.4 POLYPHASE MOTORS WITH ADDITIONAL REQUIREMENTS

- A. Motors Used with Reduced-Voltage and Multispeed Controllers: Match wiring connection requirements for controller with required motor leads. Provide terminals in motor terminal box, suited to control method.
- B. Motors Used with Variable Frequency Controllers: Ratings, characteristics, and features coordinated with and approved by controller manufacturer.
  - 1. Windings: Copper magnet wire with moisture-resistant insulation varnish, designed and tested to resist transient spikes, high frequencies, and short time rise pulses produced by pulse-width modulated inverters.
  - 2. Premium-Efficient Motors: Class B temperature rise; Class F insulation.
  - 3. Inverter-Duty Motors: Class F temperature rise; Class F insulation.

4. Thermal Protection: Comply with NEMA MG 1 requirements for thermally protected motors.
5. Shaft Grounding Ring: Microfiber type.
  - a. Provide grounded discharge path for VFD induced voltage in the shaft to prevent arching in the motor bearings.

C. Severe-Duty Motors: Comply with IEEE 841, with 1.15 minimum service factor.

## 2.5 ELECTRONICALLY COMMUTATED MOTOR (ECM)

- A. Motor enclosures: Open type
- B. Motor to be a DC electronic commutation type motor (ECM).
  1. AC induction type motors are not acceptable.
- C. Permanently lubricated motor with heavy duty ball bearing
- D. Internal motor circuitry to convert AC power supplied to the fan to DC power to operate the motor.
- E. Speed controllable to 20% of full speed (80% turndown).
  1. Potentiometer dial mounted at the motor speed controller
  2. 0-10 VDC signal.
- F. 85% efficient at all speeds minimum.
- G. Motors smaller than 2.0 hp.

## 2.6 SINGLE-PHASE MOTORS

- A. Motors larger than 1/20 hp shall be one of the following, to suit starting torque and requirements of specific motor application:
  1. Permanent-split capacitor.
  2. Split phase.
  3. Capacitor start, inductor run.
  4. Capacitor start, capacitor run.
- B. Bearings: Prelubricated, antifriction ball bearings or sleeve bearings suitable for radial and thrust loading.
- C. Motors 1/20 HP and Smaller: Shaded-pole type.
- D. Thermal Protection: Internal protection to automatically open power supply circuit to motor when winding temperature exceeds a safe value calibrated to temperature rating of motor insulation. Thermal-protection device shall automatically reset when motor temperature returns to normal range, unless otherwise indicated.



ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84104

Code Review

PART 3 - EXECUTION (Not Applicable)

END OF SECTION 23 0513

## SECTION 23 0517 - SLEEVES AND SLEEVE SEALS FOR HVAC PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Sleeves.
  - 2. Stack-sleeve fittings.
  - 3. Sleeve-seal systems.
  - 4. Sleeve-seal fittings.
  - 5. Grout.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

### PART 2 - PRODUCTS

#### 2.1 SLEEVES

- A. Cast-Iron Wall Pipes: Cast or fabricated of cast or ductile iron and equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.
- B. Galvanized-Steel Wall Pipes: ASTM A 53, Schedule 40, with plain ends and welded steel collar; zinc coated.
- C. Galvanized-Steel-Pipe Sleeves: ASTM A 53, Type E, Grade B, Schedule 40, zinc coated, with plain ends.
- D. PVC-Pipe Sleeves: ASTM D 1785, Schedule 40.
- E. Galvanized-Steel-Sheet Sleeves: 0.0239-inch minimum thickness; round tube closed with welded longitudinal joint.
- F. Molded-PE or -PP Sleeves: Removable, tapered-cup shaped, and smooth outer surface with nailing flange for attaching to wooden forms.
- G. Molded-PVC Sleeves: With nailing flange for attaching to wooden forms.

## 2.2 STACK-SLEEVE FITTINGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Smith, Jay R. Mfg. Co.
  - 2. Zurn Industries, LLC.
- C. Description: Manufactured, cast-iron sleeve with integral clamping flange. Include clamping ring, bolts, and nuts for membrane flashing.
  - 1. Underdeck Clamp: Clamping ring with setscrews.

## 2.3 SLEEVE-SEAL SYSTEMS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Advance Products & Systems, Inc.
  - 2. CALPICO, Inc.
  - 3. Metraflex Company (The).
  - 4. Pipeline Seal and Insulator, Inc.
  - 5. Proco Products, Inc.
  - 6. Hilti, cast in place system
- B. Description: Modular sealing-element unit, designed for field assembly, for filling annular space between piping and sleeve.
  - 1. Sealing Elements: EPDM-rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
  - 2. Pressure Plates: Stainless steel.
  - 3. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements.

## 2.4 SLEEVE-SEAL FITTINGS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
- B. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. HOLDRITE.
- C. Description: Manufactured plastic, sleeve-type, waterstop assembly made for imbedding in concrete slab or wall. Unit has plastic or rubber waterstop collar with center opening to match piping OD.

## 2.5 GROUT

- A. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- B. Characteristics: Nonshrink; recommended for interior and exterior applications.
- C. Design Mix: 5000-psi, 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

## PART 3 - EXECUTION

### 3.1 SLEEVE INSTALLATION

- A. Install sleeves for piping passing through penetrations in floors, partitions, roofs, and walls.
- B. For sleeves that will have sleeve-seal system installed, select sleeves of size large enough to provide Insert dimension annular clear space between piping and concrete slabs and walls.
  - 1. Sleeves are not required for core-drilled holes.
- C. Install sleeves in concrete floors, concrete roof slabs, and concrete walls as new slabs and walls are constructed.
  - 1. Permanent sleeves are not required for holes in slabs formed by molded-PE or -PP sleeves.
  - 2. Cut sleeves to length for mounting flush with both surfaces.
    - a. Exception: Extend sleeves installed in floors of mechanical equipment areas or other wet areas 2 inches above finished floor level.
  - 3. Using grout, seal the space outside of sleeves in slabs and walls without sleeve-seal system.
- D. Install sleeves for pipes passing through interior partitions.
  - 1. Cut sleeves to length for mounting flush with both surfaces.
  - 2. Install sleeves that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
  - 3. Seal annular space between sleeve and piping or piping insulation; use joint sealants appropriate for size, depth, and location of joint. Comply with requirements for sealants specified in Division 07 Section "Joint Sealants."
  - 4. For sound-rated partitions, fill the opening between sleeve and piping with insulation prior to sealing.
- E. Fire-Barrier Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements for firestopping specified in Division 07 Section "Penetration Firestopping."

### 3.2 STACK-SLEEVE-FITTING INSTALLATION

- A. Install stack-sleeve fittings in new slabs as slabs are constructed.
  - 1. Install fittings that are large enough to provide 1/4-inch annular clear space between sleeve and pipe or pipe insulation.
  - 2. Secure flashing between clamping flanges for pipes penetrating floors with membrane waterproofing. Comply with requirements for flashing specified in Division 07 Section "Sheet Metal Flashing and Trim."
  - 3. Install section of cast-iron soil pipe to extend sleeve to 2 inches above finished floor level.
  - 4. Extend cast-iron sleeve fittings below floor slab as required to secure clamping ring if ring is specified.
  - 5. Using grout, seal the space around outside of stack-sleeve fittings.
- B. Fire-Barrier Penetrations: Maintain indicated fire rating of floors at pipe penetrations. Seal pipe penetrations with firestop materials. Comply with requirements for firestopping specified in Division 07 Section "Penetration Firestopping."

### 3.3 SLEEVE-SEAL-SYSTEM INSTALLATION

- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at service piping entries into building.
- B. Select type, size, and number of sealing elements required for piping material and size and for sleeve ID or hole size. Position piping in center of sleeve. Center piping in penetration, assemble sleeve-seal system components, and install in annular space between piping and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make a watertight seal.

### 3.4 SLEEVE-SEAL-FITTING INSTALLATION

- A. Install sleeve-seal fittings in new walls and slabs as they are constructed.
- B. Assemble fitting components of length to be flush with both surfaces of concrete slabs and walls. Position waterstop flange to be centered in concrete slab or wall.
- C. Secure nailing flanges to concrete forms.
- D. Using grout, seal the space around outside of sleeve-seal fittings.

### 3.5 SLEEVE AND SLEEVE-SEAL SCHEDULE

- A. Use sleeves and sleeve seals for the following piping-penetration applications:
  - 1. Exterior Concrete Walls above Grade:
    - a. Piping Smaller Than NPS 6: Cast-iron wall sleeves.
    - b. Piping NPS 6 and Larger: Cast-iron wall sleeves.
  - 2. Exterior Concrete Walls below Grade:

- a. Piping Smaller Than NPS 6: Cast-iron wall sleeves with sleeve-seal system.
    - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
  - b. Piping NPS 6 and Larger: Cast-iron wall sleeves with sleeve-seal system.
    - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
- 3. Concrete Slabs-on-Grade:
  - a. Piping Smaller Than NPS 6: Cast-iron wall sleeves with sleeve-seal system.
    - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
  - b. Piping NPS 6 and Larger: Cast-iron wall sleeves with sleeve-seal system.
    - 1) Select sleeve size to allow for 1-inch annular clear space between piping and sleeve for installing sleeve-seal system.
- 4. Concrete Slabs above Grade:
  - a. Piping Smaller Than NPS 6: Galvanized-steel-pipe sleeves.
  - b. Piping NPS 6 and Larger: Galvanized-steel-pipe sleeves.
- 5. Interior Partitions:
  - a. Piping Smaller Than NPS 6: Galvanized-steel-pipe sleeves.
  - b. Piping NPS 6 and Larger: Galvanized-steel-sheet sleeves.

END OF SECTION 23 0517

## SECTION 23 0518 - ESCUTCHEONS FOR HVAC PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Escutcheons.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

### PART 2 - PRODUCTS

#### 2.1 ESCUTCHEONS

- A. One-Piece, Cast-Brass Type: With polished, chrome-plated or rough-brass finish and setscrew fastener.
- B. One-Piece, Deep-Pattern Type: Deep-drawn, box-shaped brass with chrome-plated finish and spring-clip fasteners.
- C. One-Piece, Stamped-Steel Type: With chrome-plated finish and spring-clip fasteners.

### PART 3 - EXECUTION

#### 3.1 INSTALLATION

- A. Install escutcheons for piping penetrations of walls, ceilings, and finished floors.
- B. Install escutcheons with ID to closely fit around pipe, tube, and insulation of insulated piping and with OD that completely covers opening.
  - 1. Escutcheons for New Piping:

- a. Piping with Fitting or Sleeve Protruding from Wall: One-piece, deep-pattern type with polished, chrome-plated finish.
- b. Chrome-Plated Piping: One-piece, cast-brass type with polished, chrome-plated finish.
- c. Insulated Piping: One-piece, stamped-steel type with chrome-plated finish.
- d. Bare Piping 2 inch and Smaller at Wall and Floor Penetrations in Finished Spaces: One-piece, cast-brass type with polished, chrome-plated finish.
- e. Bare Piping Larger than 2 inch at Wall and Floor Penetrations in Finished Spaces: One-piece, stamped-steel type with polished, chrome-plated finish.
- f. Bare Piping 2 inch and Smaller at Ceiling Penetrations in Finished Spaces: One-piece, cast-brass type with polished, chrome-plated finish.
- g. Bare Piping Larger than 2 inch at Ceiling Penetrations in Finished Spaces: One-piece, stamped-steel type with polished, chrome-plated finish.
- h. Bare Piping 2 inch and Smaller in Unfinished Service Spaces: One-piece, cast-brass type with polished, chrome-plated.
- i. Bare Piping Larger than 2 inch in Unfinished Service Spaces: One-piece, stamped-steel type with polished, chrome-plated finish.
- j. Bare Piping 2 inch and Smaller in Equipment Rooms: One-piece, cast-brass type with polished, chrome-plated finish.
- k. Bare Piping in Equipment Rooms Larger than 2 inch: One-piece, stamped-steel type with chrome- or cadmium-plated finish.

### 3.2 FIELD QUALITY CONTROL

- A. Replace broken and damaged escutcheons and floor plates using new materials.

END OF SECTION 23 0518



## SECTION 23 0523 - GENERAL-DUTY VALVES FOR HVAC PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. Bronze ball valves.
  - 2. Iron, single-flange butterfly valves.
  - 3. Bronze lift check valves.
  - 4. Bronze swing check valves.
  - 5. Iron swing check valves.
  - 8. Bronze globe valves.
  - 9. Iron globe valves.
  - 10. Lubricated plug valves.
  - 11. Chainwheels.
  - 12. High-performance butterfly valves.

- B. Related Sections:

- 1. Division 23 Section "Identification for HVAC Piping and Equipment" for valve tags and schedules.

#### 1.3 DEFINITIONS

- A. CWP: Cold working pressure.
- B. EPDM: Ethylene propylene copolymer rubber.
- C. NBR: Acrylonitrile-butadiene, Buna-N, or nitrile rubber.
- D. NRS: Nonrising stem.
- E. OS&Y: Outside screw and yoke.
- F. RS: Rising stem.
- G. SWP: Steam working pressure.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of valve indicated. Body material, valve design, pressure and temperature classification, end connection details, seating materials, trim material and arrangement, dimensions and required clearances, and installation instructions. Include list indicating valve and its application.
- B. Maintenance data for valves to be included in the operation and maintenance data specified in Division 1. Include detailed manufacturer's instructions on adjusting, servicing, disassembling, and repairing.

#### 1.5 QUALITY ASSURANCE

- A. Source Limitations for Valves: Obtain each type of valve as listed in SUMMARY from a single source and from a single manufacturer.
- B. Compliance:
  - 1. ASME B16.10 and ASME B16.34 for ferrous valve dimensions and design criteria.
  - 2. ASME B31.1 for power piping valves.
  - 3. ASME B31.9 for building services piping valves.
  - 4. MSS Compliance: Comply with the various MSS Standard Practice documents referenced.

#### 1.6 DELIVERY, STORAGE, AND HANDLING

- A. Prepare valves for shipping as follows:
  - 1. Protect internal parts against rust and corrosion.
  - 2. Protect threads, flange faces, and weld ends.
  - 3. Set angle, and globe valves closed to prevent rattling.
  - 4. Set ball and plug valves open to minimize exposure of functional surfaces.
  - 5. Set butterfly valves closed or slightly open.
  - 6. Block check valves in either closed or open position.
- B. Use the following precautions during storage:
  - 1. Maintain valve end protection.
  - 2. Store valves indoors and maintain at higher than ambient dew point temperature. If outdoor storage is necessary, store valves off the ground in watertight enclosures.
- C. Use sling to handle large valves; rig sling to avoid damage to exposed parts. Do not use handwheels or stems as lifting or rigging points.

## PART 2 - PRODUCTS

### 2.1 GENERAL REQUIREMENTS FOR VALVES

- A. Refer to HVAC valve schedule articles for applications of valves.
- B. Valve Pressure and Temperature Ratings: Not less than indicated and as required for system pressures and temperatures.
- C. Valve Sizes: Same as upstream piping unless otherwise indicated.
- D. Valve Actuator Types:
  - 1. Gear Actuator: For quarter-turn valves NPS 8 and larger.
  - 2. Handwheel: For valves other than quarter-turn types.
  - 3. Handlever: For quarter-turn valves NPS 6 and smaller[ except plug valves].
  - 4. Wrench: For plug valves with square heads. Furnish Owner with 1 wrench for every 10 plug valves, for each size square plug-valve head.
  - 5. Chainwheel: Device for attachment to valve handwheel, stem, or other actuator; of size and with chain for mounting height, as indicated in the "Valve Installation" Article.
- E. Valves in Insulated Piping: With 2-inch stem extensions and the following features:
  - 2. Ball Valves: With extended operating handle of non-thermal-conductive material, and protective sleeve that allows operation of valve without breaking the vapor seal or disturbing insulation.
  - 3. Butterfly Valves: With extended neck.
- F. Valve-End Connections:
  - 1. Flanged: With flanges according to ASME B16.1 for iron valves.
  - 2. Solder Joint: With sockets according to ASME B16.18.
    - a. Caution: Where soldered end connections are used, use solder having a melting point below 840 deg. For, globe, and check valves: below 421 deg. F for ball valves.
  - 3. Threaded: With threads according to ASME B1.20.1.
- G. Valve Bypass and Drain Connections: MSS SP-45.

### 2.2 MANUFACTURERS

- A. Subject to compliance with requirements, provide products by one of the following:
  - 1. APCO Willamette Valve and Primer Corp.
  - 2. Babbitt Steam Specialty Company.
  - 3. Bray Controls.
  - 4. Center Line.

5. Cla-Val Company.
6. Conbraco Industries Inc.
7. Crane Co.; Crane Valve Group.
8. Fisher Valve by Emerson.
9. Flo Fab Inc.
10. Flow-Tek Inc.
11. Grinnell Corporation.
12. Hammond Valve.
13. Jamesbury; a subsidiary of Metso Automation.
14. Jomar International LTD.
15. Keystone Valve USA, Inc.
16. Kitz Corp.
17. Metraflex Company.
18. Milwaukee Valve Company.
19. Mueller Steam Specialty.
20. NIBCO Inc.
21. Red-White Valve Corp.
22. Spence Strainers International.
23. Stockham Valves and Fittings, Inc.
24. Tyco Fire/Shurjoint Piping Products.
25. Tyco/Pentair LTD.
26. Val-Matic Valve & Mfg. Corp.
27. Victaulic Company.
28. Watts Regulator Company.

## 2.4 BRONZE BALL VALVES

### C. Two-Piece, Full-Port, Bronze Ball Valves with Bronze Trim:

1. Description:
  - a. Standard: MSS SP-110.
  - b. SWP Rating: 150 psig.
  - c. CWP Rating: 600 psig.
  - d. Body Design: Two piece.
  - e. Body Material: Bronze.
  - f. Ends: Threaded.
  - g. Seats: PTFE or TFE.
  - h. Stem: Bronze.
  - i. Ball: Chrome-plated brass.
  - j. Port: Full.

## 2.5 IRON, SINGLE-FLANGE BUTTERFLY VALVES

### A. 150 CWP, Iron, Single-Flange (Lug) Butterfly Valves:

1. Description:

- a. Standard: MSS SP-67, Type I.
  - b. CWP Rating: 150 psig.
  - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
  - d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
  - e. Seat: EPDM.
  - f. Stem: One- or two-piece stainless steel.
  - g. Disc: Nylon 11 coated ductile iron.
- B. 175 CWP, Iron, Single-Flange (Lug) Butterfly Valves:
  - 1. Description:
    - a. Standard: MSS SP-67, Type I.
    - b. CWP Rating: 175 psig.
    - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
    - d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
    - e. Seat: EPDM.
    - f. Stem: One- or two-piece stainless steel.
    - g. Disc: Nylon 11 coated ductile iron.
- C. 200 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Nylon 11 coated ductile Iron Disc:
  - 1. Description:
    - a. Standard: MSS SP-67, Type I.
    - b. CWP Rating: 200 psig.
    - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
    - d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
    - e. Seat: EPDM.
    - f. Stem: One- or two-piece stainless steel.
    - g. Disc: Nylon 11 coated ductile iron.
- D. 250 CWP, Iron, Single-Flange Butterfly Valves with EPDM Seat and Nylon 11 coated ductile Iron Disc:
  - 1. Description:
    - a. Standard: MSS SP-67, Type I.
    - b. CWP Rating: 250 psig.
    - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
    - d. Body Material: ASTM A 126, cast iron or ASTM A 536, ductile iron.
    - e. Seat: EPDM.
    - f. Stem: One- or two-piece stainless steel.
    - g. Disc: Nylon 11 coated ductile iron.

## 2.6 BRONZE LIFT CHECK VALVES

### A. Class 125, Lift Check Valve:

1. Description:
  - a. Standard: MSS SP-80.
  - b. CWP Rating: 200 psig.
  - c. Body Design: Vertical flow.
  - d. Body Material: ASTM B 61, ASTM B 62, bronze.
  - e. Ends: Threaded.
  - f. Disc: Bronze, Type 1.

## 2.7 BRONZE SWING CHECK VALVES

### A. Class 150, Bronze Swing Check Valves with Bronze Disc:

1. Description:
  - a. Standard: MSS SP-80, Type 3.
  - b. CWP Rating: 300 psig.
  - c. Body Design: Horizontal flow.
  - d. Body Material: ASTM B 62, bronze.
  - e. Ends: Threaded.
  - f. Disc: Bronze.

## 2.8 IRON SWING CHECK VALVES

### A. Class 125, Iron Swing Check Valves with Metal Seats:

1. Description:
  - a. Standard: MSS SP-71, Type I.
  - b. NPS 2-1/2 to NPS 12, CWP Rating: 200 psig.
  - c. Body Design: Clear or full waterway.
  - d. Body Material: ASTM A 126, gray iron with bolted bonnet.
  - e. Ends: Flanged.
  - f. Trim: Bronze.
  - g. Gasket: Asbestos free.

## 2.9 BRONZE GLOBE VALVES

### A. Class 150, Bronze Globe Valves with Nonmetallic Disc:

1. Description:
  - a. Standard: MSS SP-80, Type 2.

- b. CWP Rating: 300 psig.
- c. Body Material: ASTM B 62, bronze with integral seat and union-ring bonnet.
- d. Ends: Threaded.
- e. Stem: Bronze.
- f. Disc: PTFE or TFE.
- g. Packing: Teflon impregnated, asbestos free.
- h. Handwheel: Malleable iron.

## 2.10 IRON GLOBE VALVES

### A. Class 125, Iron Globe Valves:

#### 1. Description:

- a. Standard: MSS SP-85, Type I.
- b. CWP Rating: 200 psig.
- c. Body Material: ASTM A 126, gray iron with bolted bonnet.
- d. Ends: Flanged.
- e. Stem: Brass alloy. OS &Y.
- f. Disc: Renewable bronze seat.
- g. Trim: Bronze.
- h. Packing and Gasket: Teflon impregnated, asbestos free.
- i. Handwheel: Cast iron

## 2.11 LUBRICATED PLUG VALVES

### A. Class 125, Regular-Gland, Lubricated Plug Valves with Threaded Ends:

#### 1. Description:

- a. Standard: MSS SP-78, Type II.
- b. NPS 2-1/2 to NPS 12, CWP Rating: 200 psig.
- c. Pattern: Regular or short.
- d. Body Material: ASTM A 48 or ASTM A 126, cast iron with lubrication-sealing system.
- e. Plug: Cast iron or bronze with sealant groove.

## 2.12 CHAINWHEELS

### A. Description: Valve actuation assembly with sprocket rim, brackets, and chain.

- 1. Brackets: Type, number, size, and fasteners required to mount actuator on valve.
- 2. Attachment: For connection to [ball] [butterfly] [and] [plug] valve stems.
- 3. Sprocket Rim with Chain Guides: Ductile or cast iron, of type and size required for valve. Include zinc coating.
- 4. Chain: Hot-dip, galvanized steel, of size required to fit sprocket rim.

## 2.13 HIGH-PERFORMANCE BUTTERFLY VALVES

### A. Class 300, Single-Flange, High-Performance Butterfly Valves:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following
  - a. ABZ Valve and Controls; a division of ABZ Manufacturing, Inc.
  - b. Bray Controls; a division of Bray International.
  - c. Cooper Cameron Valves; a division of Cooper Cameron Corp.
  - d. Crane Co.; Crane Valve Group; Flowseal.
  - e. Crane Co.; Crane Valve Group; Stockham Division.
  - f. DeZurik Water Controls.
  - g. Hammond Valve.
  - h. Jamesbury; a subsidiary of Metso Automation.
  - i. Milwaukee Valve Company.
  - j. NIBCO INC.
  - k. Process Development & Control, Inc.
  - l. Tyco Valves & Controls; a unit of Tyco Flow Control.
  - m. Xomox Corporation.
2. Description:
  - a. Standard: MSS SP-68.
  - b. CWP Rating: 720 psig at 100 deg F.
  - c. Body Design: Lug type; suitable for bidirectional dead-end service at rated pressure without use of downstream flange.
  - d. Body Material: Carbon steel, cast iron, or ductile iron.
  - e. Seat: Reinforced PTFE or metal.
  - f. Stem: Stainless steel; offset from seat plane.
  - g. Disc: Carbon steel.
  - h. Service: Bidirectional.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine piping system for compliance<sup>3</sup> with requirements for installation tolerances and other conditions affecting performance of valves. Do not proceed with installation until unsatisfactory conditions have been corrected.
- B. Examine valve interior for cleanliness, freedom from foreign matter, and corrosion. Remove special packing materials, such as blocks, used to prevent disc movement during shipping and handling.
- C. Operate valves in positions from fully open to fully closed. Examine guides and seats made accessible by such operations.



- D. Examine threads on valve and mating pipe for form and cleanliness.
- E. Examine mating flange faces for conditions that might cause leakage. Check bolting for proper size, length, and material. Verify that gasket is of proper size, that its material composition is suitable for service, and that it is free from defects and damage.
- F. Do not attempt to repair defective valves; replace with new valves.

### 3.2 VALVE INSTALLATION

- A. Install valves as indicated, according to manufacturer's written instructions.
- B. Piping installation requirements are specified in other Division 23 Sections. Drawings indicate the general arrangement of piping, fittings, and specialties.
- C. Install valves with unions or flanges at each piece of equipment arranged to allow service, maintenance, and equipment removal without system shutdown.
- D. Locate valves for easy access and provide separate support where necessary.
- E. Install valves in horizontal piping with stem at or above center of pipe.
- F. Install valves in position to allow full stem movement.
- G. Install chainwheels on operators for ball, butterfly globe and plug valves NPS 4 and larger and more than 96 inches above floor.
- H. Extend the chainwheels for chains to 60 inches above finished floor.
- I. Install check valves for proper direction of flow and as follows:
  - 1. Swing Check Valves: In horizontal position with hinge pin level.
  - 2. Check Valves: In horizontal or vertical position, between flanges.
  - 3. Lift Check Valves: With stem upright and plumb.
  - 4. Install all check valves a minimum of five pipe diameters downstream of pump discharge or elbow to avoid flow turbulence. In extreme cases add flow straighteners as required to correct the turbulence.

### 3.3 ADJUSTING

- A. Adjust or replace valve packing after piping systems have been tested and put into service but before final adjusting and balancing. Replace valves if persistent leaking occurs.

### 3.4 GENERAL REQUIREMENTS FOR VALVE APPLICATIONS

- A. If valve applications are not indicated, use the following:
  - 1. Shutoff Service: Ball or butterfly valves.

2. Butterfly Valve Dead-End Service: Single-flange (lug) type.
  3. Throttling Service except Steam: Globe valves.
  4. Throttling Service, Steam: Globe valves.
  5. Pump-Discharge Check Valves:
    - a. NPS 2 and Smaller: Bronze swing check valves with bronze disc.
    - b. NPS 2-1/2 and Larger: Iron swing check valves with lever and weight or with spring or iron, metal-seat check valves.
  6. Drain Service (except Steam): Two-Piece, Full Port Bronze Ball Valves with Bronze Trim. To be installed with NPS 3/4 hose thread outlet and hose cap with chain.
- B. If valves with specified SWP classes or CWP ratings are not available, the same types of valves with higher SWP classes or CWP ratings may be substituted.
- C. Select valves, except wafer types, with the following end connections:
1. For Copper Tubing, NPS 2 and Smaller: Threaded ends except where solder-joint valve-end option is indicated in valve schedules below.
  2. For Copper Tubing, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
  3. For Copper Tubing, NPS 5 and Larger: Flanged ends.
  4. For Steel Piping, NPS 2 and Smaller: Threaded ends.
  5. For Steel Piping, NPS 2-1/2 to NPS 4: Flanged ends except where threaded valve-end option is indicated in valve schedules below.
  6. For Steel Piping, NPS 5 and Larger: Flanged ends.

### 3.5 CHILLED-WATER VALVE SCHEDULE

- A. Pipe NPS 2 and Smaller:
1. Bronze Valves: May be provided with solder-joint ends instead of threaded ends.
  3. Ball Valves:
    - a. Piece: Two
    - b. Port: Full.
    - c. Material/Trim: Bronze with:
      - 1) Bronze trim.
  4. Bronze Swing Check Valves:
    - a. Class 150
    - b. Bronze disc.
  6. Bronze Globe Valves:
    - a. Class 125
    - b. Bronze disc.
- B. Pipe NPS 2-1/2 and Larger:
1. Iron Valves, NPS 2-1/2 to NPS 4: May be provided with threaded ends instead of flanged ends.
  2. Iron, Single-Flange Butterfly Valves, NPS 2-1/2 to NPS 12:

- a. 200 CWP,
  - b. Seat: EPDM.
  - c. Disc: Ductile-iron.
3. Iron Swing Check Valves: Class 125, metal seats.
4. Iron Globe Valves: Class 125.
5. Lubricated Plug Valves: Class 125, regular gland, flanged.

### 3.6 HEATING-WATER VALVE SCHEDULE

#### A. Pipe NPS 2 and Smaller:

1. Bronze Valves: May be provided with solder-joint ends instead of threaded ends.
3. Ball Valves:
  - a. Piece: Two
  - b. Port: Full.
  - c. Material/Trim: Bronze with:
    - 1) Bronze trim.
4. Bronze Swing Check Valves:
  - a. Class 150
  - b. Bronze disc.
6. Bronze Globe Valves:
  - a. Class 125
  - b. Bronze disc.

#### B. Pipe NPS 2-1/2 and Larger:

1. Iron Valves, NPS 2-1/2 to NPS 4: May be provided with threaded ends instead of flanged ends.
2. Iron, Single-Flange Butterfly Valves, NPS 2-1/2 to NPS 12:
  - a. 200 CWP,
  - b. Seat: EPDM.
  - c. Disc: Ductile-iron.
3. Iron Swing Check Valves: Class 125, metal seats.
4. Iron Globe Valves: Class 125.

END OF SECTION 23 0523

## SECTION 23 0529 - HANGERS AND SUPPORTS FOR HVAC PIPING AND EQUIPMENT

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

- 1. Metal pipe hangers and supports.
  - 2. Trapeze pipe hangers.
  - 3. Metal framing systems.

- B. Related Sections:

- 1. Division 05 Section "Metal Fabrications" for structural-steel shapes and plates for trapeze hangers for pipe and equipment supports.
  - 2. Division 23 Section "Vibration and Seismic Controls for HVAC" for vibration isolation devices.
  - 3. Division 23 Section "Metal Ducts" for duct hangers and supports.

#### 1.3 DEFINITIONS

- A. MSS: Manufacturers Standardization Society of The Valve and Fittings Industry Inc.

#### 1.4 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Hangers and supports for HVAC piping and equipment shall withstand the effects of gravity loads and stresses within limits and under conditions indicated according to ASCE/SEI 7.
  - 1. Design supports for multiple pipes, including pipe stands, capable of supporting combined weight of supported systems, system contents, and test water.
  - 2. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
  - 3. Design seismic-restraint hangers and supports for piping and equipment.

#### 1.5 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.

- B. Shop Drawings: Signed and sealed by a qualified professional engineer. Show fabrication and installation details and include calculations for the following; include Product Data for components:

1. Trapeze pipe hangers.
2. Metal framing systems.

## 1.6 INFORMATIONAL SUBMITTALS

- A. Welding certificates.

## PART 2 - PRODUCTS

### 2.1 METAL PIPE HANGERS AND SUPPORTS

- A. Carbon-Steel Pipe Hangers and Supports:

1. Description: MSS SP-58, Types 1 through 58, factory-fabricated components.
2. Galvanized Metallic Coatings: Pre-galvanized or hot dipped.
3. Nonmetallic Coatings: Plastic coating, jacket, or liner.
4. Padded Hangers: Hanger with fiberglass or other pipe insulation pad or cushion to support bearing surface of piping.
5. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.

### 2.2 TRAPEZE PIPE HANGERS

- A. Description: MSS SP-69, Type 59, shop- or field-fabricated pipe-support assembly made from structural carbon-steel shapes with MSS SP-58 carbon-steel hanger rods, nuts, saddles, and U-bolts.

### 2.3 METAL FRAMING SYSTEMS

- A. MFMA Manufacturer Metal Framing Systems:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Anvil International.
  - b. Cooper B-Line, Inc.; a division of Cooper Industries.
  - c. ERICO/Michigan Hanger Co. ; ERISTRUT Div.
  - d. GS Metals Corp.
  - e. Hilti, Inc.
  - f. Power-Strut Div. Tyco International.
  - g. Thomas & Betts Corporation.
  - h. Tolco Inc.

- i. Unistrut; an Atkore International company.
  2. Description: Shop- or field-fabricated pipe-support assembly for supporting multiple parallel pipes.
  3. Standard: MFMA-4.
  4. Channels: Continuous slotted steel channel with inturned lips.
  5. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
  6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
  7. Metallic Coating:
    - a. Electroplated zinc.
- B. Non-MFMA Manufacturer Metal Framing Systems:
1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Anvil International; a subsidiary of Mueller Water Products, Inc.
    - b. Empire Industries, Inc.
    - c. ERICO International Corporation.
    - d. Haydon Corporation.
    - e. NIBCO INC.
    - f. PHD Manufacturing, Inc.
    - g. PHS Industries, Inc.
  2. Description: Shop- or field-fabricated pipe-support assembly made of steel channels, accessories, fittings, and other components for supporting multiple parallel pipes.
  3. Standard: Comply with MFMA-4.
  4. Channels: Continuous slotted steel channel with inturned lips.
  5. Channel Nuts: Formed or stamped steel nuts or other devices designed to fit into channel slot and, when tightened, prevent slipping along channel.
  6. Hanger Rods: Continuous-thread rod, nuts, and washer made of carbon steel.
  7. Coating:
    - a. Zinc.

## 2.4 THERMAL-HANGER SHIELD INSERTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Carpenter & Paterson, Inc.
  2. Clement Support Services.
  3. ERICO International Corporation.
  4. National Pipe Hanger Corporation.
  5. PHS Industries, Inc.
  6. Pipe Shields Inc.
  7. Piping Technology & Products, Inc.

- 8. Rilco Manufacturing Co., Inc.
- 9. Value Engineered Products, Inc.
- B. Insulation-Insert Material for Cold Piping:
  - 1. Water-repellent treated, ASTM C 533, Type I calcium silicate with 100-psig minimum compressive strength.
- C. Insulation-Insert Material for Hot Piping:
  - 1. Water-repellent treated, ASTM C 533, Type I calcium silicate with 100-psig minimum compressive strength.
- D. For Trapeze or Clamped Systems: Insert and shield shall cover entire circumference of pipe.
- E. For Clevis or Band Hangers: Insert and shield shall cover lower 180 degrees of pipe.
- F. Insert Length: Extend 2 inches beyond sheet metal shield for piping operating below ambient air temperature.

## 2.5 FASTENER SYSTEMS

- A. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.
- B. Mechanical-Expansion Anchors: Insert-wedge-type, [zinc-coated] [stainless-] steel anchors, for use in hardened portland cement concrete; with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

## 2.6 MISCELLANEOUS MATERIALS

- A. Structural Steel: ASTM A 36, carbon-steel plates, shapes, and bars; black and galvanized.
- B. Grout: ASTM C 1107, factory-mixed and -packaged, dry, hydraulic-cement, nonshrink and nonmetallic grout; suitable for interior and exterior applications.
  - 1. Properties: Nonstaining, noncorrosive, and nongaseous.
  - 2. Design Mix: 5000-psi, 28-day compressive strength.

## PART 3 - EXECUTION

### 3.1 HANGER AND SUPPORT INSTALLATION

- A. Comply with SEI/ASCE 7 and with requirements for seismic-restraint devices in Section 230548 "Vibration and Seismic Controls for HVAC."

- B. Metal Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Install hangers, supports, clamps, and attachments as required to properly support piping from the building structure.
- C. Metal Trapeze Pipe-Hanger Installation: Comply with MSS SP-69 and MSS SP-89. Arrange for grouping of parallel runs of horizontal piping, and support together on field-fabricated trapeze pipe hangers.
  - 1. Pipes of Various Sizes: Support together and space trapezes for smallest pipe size or install intermediate supports for smaller diameter pipes as specified for individual pipe hangers.
  - 2. Field fabricate from ASTM A 36, carbon-steel shapes selected for loads being supported. Weld steel according to AWS D1.1.
- D. Metal Framing System Installation: Arrange for grouping of parallel runs of piping, and support together on field-assembled metal framing systems.
- E. Install hangers and supports complete with necessary attachments, inserts, bolts, rods, nuts, washers, and other accessories.
- F. Install hangers and supports to allow controlled thermal and seismic movement of piping systems, to permit freedom of movement between pipe anchors, and to facilitate action of expansion joints, expansion loops, expansion bends, and similar units.
- G. Install lateral bracing with pipe hangers and supports to prevent swaying.
- H. Install building attachments within concrete slabs or attach to structural steel. Install additional attachments at concentrated loads, including valves, flanges, and strainers, NPS 2-1/2 and larger and at changes in direction of piping. Install concrete inserts before concrete is placed; fasten inserts to forms and install reinforcing bars through openings at top of inserts.
- I. Load Distribution: Install hangers and supports so that piping live and dead loads and stresses from movement will not be transmitted to connected equipment.
- J. Pipe Slopes: Install hangers and supports to provide indicated pipe slopes and to not exceed maximum pipe deflections allowed by ASME B31.9 for building services piping.
- K. Insulated Piping:
  - 1. Attach clamps and spacers to piping.
    - a. Piping Operating above Ambient Air Temperature: Clamp may project through insulation.
    - b. Piping Operating below Ambient Air Temperature: Use thermal-hanger shield insert with clamp sized to match OD of insert.
    - c. Do not exceed pipe stress limits allowed by ASME B31.9 for building services piping.
  - 2. Install MSS SP-58, Type 39, protection saddles if insulation without vapor barrier is indicated. Fill interior voids with insulation that matches adjoining insulation.



- a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
- 3. Install MSS SP-58, Type 40, protective shields on cold piping with vapor barrier. Shields shall span an arc of 180 degrees.
  - a. Option: Thermal-hanger shield inserts may be used. Include steel weight-distribution plate for pipe NPS 4 and larger if pipe is installed on rollers.
- 4. Shield Dimensions for Pipe: Not less than the following:
  - a. NPS 1/4 to NPS 3-1/2: 12 inches long and 0.048 inch thick.
  - b. NPS 4: 12 inches long and 0.06 inch thick.
  - c. NPS 5 and NPS 6: 18 inches long and 0.06 inch thick.
  - d. NPS 8 to NPS 14: 24 inches long and 0.075 inch thick.
  - e. NPS 16 to NPS 24: 24 inches long and 0.105 inch thick.
- 5. Pipes NPS 8 and Larger: Include wood or reinforced calcium-silicate-insulation inserts of length at least as long as protective shield.
- 6. Thermal-Hanger Shields: Install with insulation same thickness as piping insulation.

### 3.2 METAL FABRICATIONS

- A. Cut, drill, and fit miscellaneous metal fabrications for trapeze pipe hangers.
- B. Fit exposed connections together to form hairline joints. Field weld connections that cannot be shop welded because of shipping size limitations.
- C. Field Welding: Comply with AWS D1.1/D1.1M procedures for shielded, metal arc welding; appearance and quality of welds; and methods used in correcting welding work; and with the following:
  - 1. Use materials and methods that minimize distortion and develop strength and corrosion resistance of base metals.
  - 2. Obtain fusion without undercut or overlap.
  - 3. Remove welding flux immediately.
  - 4. Finish welds at exposed connections so no roughness shows after finishing and so contours of welded surfaces match adjacent contours.

### 3.3 ADJUSTING

- A. Hanger Adjustments: Adjust hangers to distribute loads equally on attachments and to achieve indicated slope of pipe.
- B. Trim excess length of continuous-thread hanger and support rods to 1-1/2 inches.

### 3.4 PAINTING

- A. Touchup: Cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal are specified in Division 09.
- B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

### 3.5 HANGER AND SUPPORT SCHEDULE

- A. Specific hanger and support requirements are in Sections specifying piping systems and equipment.
- B. Comply with MSS SP-69 for pipe-hanger selections and applications that are not specified in piping system Sections.
- C. Use hangers and supports with galvanized metallic coatings for piping and equipment that will not have field-applied finish.
- D. Use nonmetallic coatings on attachments for electrolytic protection where attachments are in direct contact with copper tubing.
- E. Use carbon-steel pipe hangers and supports and attachments for general service applications.
- F. Use padded hangers for piping that is subject to scratching.
- G. Use thermal-hanger shield inserts for insulated piping and tubing.
- H. Horizontal-Piping Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
  - 1. Adjustable, Steel Clevis Hangers (MSS Type 1): For suspension of noninsulated or insulated, stationary pipes NPS 1/2 to NPS 30.
  - 2. Yoke-Type Pipe Clamps (MSS Type 2): For suspension of up to 1050 deg F, pipes NPS 4 to NPS 24, requiring up to 4 inches of insulation.
  - 3. Carbon- or Alloy-Steel, Double-Bolt Pipe Clamps (MSS Type 3): For suspension of pipes NPS 3/4 to NPS 36, requiring clamp flexibility and up to 4 inches of insulation.
  - 4. Steel Pipe Clamps (MSS Type 4): For suspension of cold and hot pipes NPS 1/2 to NPS 24 if little or no insulation is required.
  - 5. Pipe Hangers (MSS Type 5): For suspension of pipes NPS 1/2 to NPS 4, to allow off-center closure for hanger installation before pipe erection.
  - 6. Adjustable, Swivel Split- or Solid-Ring Hangers (MSS Type 6): For suspension of noninsulated, stationary pipes NPS 3/4 to NPS 8.
  - 7. Adjustable, Steel Band Hangers (MSS Type 7): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
  - 8. Adjustable Band Hangers (MSS Type 9): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.
  - 9. Adjustable, Swivel-Ring Band Hangers (MSS Type 10): For suspension of noninsulated, stationary pipes NPS 1/2 to NPS 8.

10. Split Pipe Ring with or without Turnbuckle Hangers (MSS Type 11): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 8.
  11. Extension Hinged or Two-Bolt Split Pipe Clamps (MSS Type 12): For suspension of noninsulated, stationary pipes NPS 3/8 to NPS 3.
  12. U-Bolts (MSS Type 24): For support of heavy pipes NPS 1/2 to NPS 30.
  13. Clips (MSS Type 26): For support of insulated pipes not subject to expansion or contraction.
  14. Pipe Saddle Supports (MSS Type 36): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate.
  15. Pipe Stanchion Saddles (MSS Type 37): For support of pipes NPS 4 to NPS 36, with steel-pipe base stanchion support and cast-iron floor flange or carbon-steel plate, and with U-bolt to retain pipe.
  16. Adjustable Pipe Saddle Supports (MSS Type 38): For stanchion-type support for pipes NPS 2-1/2 to NPS 36 if vertical adjustment is required, with steel-pipe base stanchion support and cast-iron floor flange.
  17. Single-Pipe Rolls (MSS Type 41): For suspension of pipes NPS 1 to NPS 30, from two rods if longitudinal movement caused by expansion and contraction might occur.
  18. Adjustable Roller Hangers (MSS Type 43): For suspension of pipes NPS 2-1/2 to NPS 24, from single rod if horizontal movement caused by expansion and contraction might occur.
  19. Complete Pipe Rolls (MSS Type 44): For support of pipes NPS 2 to NPS 42 if longitudinal movement caused by expansion and contraction might occur but vertical adjustment is not necessary.
  20. Pipe Roll and Plate Units (MSS Type 45): For support of pipes NPS 2 to NPS 24 if small horizontal movement caused by expansion and contraction might occur and vertical adjustment is not necessary.
  21. Adjustable Pipe Roll and Base Units (MSS Type 46): For support of pipes NPS 2 to NPS 30 if vertical and lateral adjustment during installation might be required in addition to expansion and contraction.
- I. Vertical-Piping Clamps: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Extension Pipe or Riser Clamps (MSS Type 8): For support of pipe risers NPS 3/4 to NPS 24.
  2. Carbon- or Alloy-Steel Riser Clamps (MSS Type 42): For support of pipe risers NPS 3/4 to NPS 24 if longer ends are required for riser clamps.
- J. Hanger-Rod Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel Turnbuckles (MSS Type 13): For adjustment up to 6 inches for heavy loads.
  2. Steel Clevises (MSS Type 14): For 120 to 450 deg F piping installations.
  3. Swivel Turnbuckles (MSS Type 15): For use with MSS Type 11, split pipe rings.
  4. Malleable-Iron Sockets (MSS Type 16): For attaching hanger rods to various types of building attachments.
  5. Steel Weldless Eye Nuts (MSS Type 17): For 120 to 450 deg F piping installations.
- K. Building Attachments: Unless otherwise indicated and except as specified in piping system Sections, install the following types:

1. Steel or Malleable Concrete Inserts (MSS Type 18): For upper attachment to suspend pipe hangers from concrete ceiling.
  2. Top-Beam C-Clamps (MSS Type 19): For use under roof installations with bar-joist construction, to attach to top flange of structural shape.
  3. Side-Beam or Channel Clamps (MSS Type 20): For attaching to bottom flange of beams, channels, or angles.
  4. Center-Beam Clamps (MSS Type 21): For attaching to center of bottom flange of beams.
  5. Welded Beam Attachments (MSS Type 22): For attaching to bottom of beams if loads are considerable and rod sizes are large.
  6. C-Clamps (MSS Type 23): For structural shapes.
  7. Top-Beam Clamps (MSS Type 25): For top of beams if hanger rod is required tangent to flange edge.
  8. Side-Beam Clamps (MSS Type 27): For bottom of steel I-beams.
  9. Steel-Beam Clamps with Eye Nuts (MSS Type 28): For attaching to bottom of steel I-beams for heavy loads.
  10. Linked-Steel Clamps with Eye Nuts (MSS Type 29): For attaching to bottom of steel I-beams for heavy loads, with link extensions.
  11. Malleable-Beam Clamps with Extension Pieces (MSS Type 30): For attaching to structural steel.
  12. Welded-Steel Brackets: For support of pipes from below or for suspending from above by using clip and rod. Use one of the following for indicated loads:
    - a. Light (MSS Type 31): 750 lb.
    - b. Medium (MSS Type 32): 1500 lb.
    - c. Heavy (MSS Type 33): 3000 lb.
  13. Side-Beam Brackets (MSS Type 34): For sides of steel or wooden beams.
  14. Plate Lugs (MSS Type 57): For attaching to steel beams if flexibility at beam is required.
  15. Horizontal Travelers (MSS Type 58): For supporting piping systems subject to linear horizontal movement where headroom is limited.
- L. Saddles and Shields: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Steel-Pipe-Covering Protection Saddles (MSS Type 39): To fill interior voids with insulation that matches adjoining insulation.
  2. Protection Shields (MSS Type 40): Of length recommended in writing by manufacturer to prevent crushing insulation.
  3. Thermal-Hanger Shield Inserts: For supporting insulated pipe.
- M. Spring Hangers and Supports: Unless otherwise indicated and except as specified in piping system Sections, install the following types:
1. Restraint-Control Devices (MSS Type 47): Where indicated to control piping movement.
  2. Spring Cushions (MSS Type 48): For light loads if vertical movement does not exceed 1-1/4 inches.
  3. Spring-Cushion Roll Hangers (MSS Type 49): For equipping Type 41, roll hanger with springs.
  4. Spring Sway Braces (MSS Type 50): To retard sway, shock, vibration, or thermal expansion in piping systems.

5. Variable-Spring Hangers (MSS Type 51): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from hanger.
  6. Variable-Spring Base Supports (MSS Type 52): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from base support.
  7. Variable-Spring Trapeze Hangers (MSS Type 53): Preset to indicated load and limit variability factor to 25 percent to allow expansion and contraction of piping system from trapeze support.
  8. Constant Supports: For critical piping stress and if necessary to avoid transfer of stress from one support to another support, critical terminal, or connected equipment. Include auxiliary stops for erection, hydrostatic test, and load-adjustment capability. These supports include the following types:
    - a. Horizontal (MSS Type 54): Mounted horizontally.
    - b. Vertical (MSS Type 55): Mounted vertically.
    - c. Trapeze (MSS Type 56): Two vertical-type supports and one trapeze member.
- N. Comply with MSS SP-69 for trapeze pipe-hanger selections and applications that are not specified in piping system Sections.
- O. Comply with MFMA-103 for metal framing system selections and applications that are not specified in piping system Sections.
- P. Use powder-actuated fasteners or mechanical-expansion anchors instead of building attachments where required in concrete construction.

END OF SECTION 23 0529

## SECTION 23 0548 - VIBRATION AND SEISMIC CONTROLS FOR HVAC

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SCOPE

- A. Provide engineered vibration isolation and restraint systems in accordance with the requirements of this section including design, engineering, materials, testing, inspections and reports.
- B. Mechanical equipment with moving parts shall be mounted on or suspended from vibration isolators to reduce the transmission of vibration and mechanically transmitted sound to the building structure.
- C. All mechanical equipment, piping and ductwork shall be restrained as required by Federal, State and Local building codes to preserve the integrity of nonstructural building components during seismic events to minimize hazards to occupants and reduce property damage.

#### 1.3 SUMMARY

- A. This Section includes the following:
  - 1. Elastomeric isolation pads.
  - 2. Elastomeric isolation mounts.
  - 3. Restrained elastomeric isolation mounts.
  - 4. Open-spring isolators.
  - 5. Housed-spring isolators.
  - 6. Restrained-spring isolators.
  - 7. Housed-restrained-spring isolators.
  - 8. Elastomeric hangers.
  - 9. Spring hangers.
  - 10. Seismic-restraint accessories.
  - 11. Mechanical anchor bolts.
  - 12. Adhesive anchor bolts.
  - 13. Restrained isolation roof-curb rails.
  - 14. Certification of seismic restraint designs.
  - 15. Installation supervision.
  - 16. All components requiring IBC compliance and certification.
  - 17. All inspection and test procedures for components requiring IBC compliance.

18. Restraint of all mechanical equipment, pipe and ductwork, within, on, or outdoors of the building and entry of services to the building, up to but not including, the utility connection, is part of this Specification.
19. Seismic certification of equipment

B. Related Requirements:

1. Division 22 Section "Vibration and Seismic Controls for Plumbing Piping and Equipment" for devices for plumbing equipment and systems.
2. Division 03 Section "Cast-in-Place Concrete."
3. Division 07 Section "Roof Accessories"
4. Division 23 Section "Hydronic Piping"

1.4 DEFINITIONS

- A. IBC: International Building Code.
- B. ICC-ES: ICC-Evaluation Service.
- C. ASCE: American Society of Civil Engineers
- D. Ip: Importance Factor.
- E. ESSENTIAL FACILITIES, (Occupancy Category IV, IBC-2018)
  1. Buildings and other structures that are intended to remain operational in the event of extreme environmental loading from flood, wind, snow or earthquakes.

F. LIFE SAFETY

1. All systems involved with fire protection, including sprinkler piping, jockey pumps, fire pumps, control panels, service water supply piping, water tanks, fire dampers, smoke exhaust systems and fire alarm panels.
2. All mechanical, electrical, plumbing or fire protection systems that support the operation of, or are connected to, emergency power equipment, including all lighting, generators, transfer switches and transformers.
3. All medical and life support systems.
4. Hospital heating systems and air conditioning systems for maintaining normal ambient temperature.
5. Automated supply, exhaust, fresh air and relief air systems on emergency control sequence, including air handlers, duct, dampers, etc., or manually-operated systems used for smoke evacuation, purge or fresh air relief by the fire department.

6. Heating systems in any facility with Occupancy Category IV, IBC-2018 where the ambient temperature can fall below 32 degrees Fahrenheit.

G. HIGH HAZARD

1. All gases or fluids that must be contained in a closed system which are flammable or combustible. Any gas that poses a health hazard if released into the environment and vented Fuel Cells.

1.5 REFERENCE CODES AND STANDARDS

- A. Codes and Standards: The following shall apply and conform to good engineering practices unless otherwise directed by the Federal, State or Local authorities having jurisdiction.

1. IBC
2. ASCE 7
3. NFPA 13 (National Fire Protection Association)
4. IBC 2018

- B. The following guides may be used for supplemental information on typical seismic installation practices. Where a conflict exists between the guides and these construction documents, the construction documents will preside.

1. FEMA (Federal Emergency Management Agency) manuals 412, Installing Seismic Restraints for Mechanical Equipment and 414, Installing Seismic Restraints for Ductwork and Pipe.
2. SMACNA (Sheet Metal and Air-conditioning Contractors' National Association) Seismic Restraint Manual Guidelines for Mechanical Systems, 3rd ed.
3. ASHRAE (American Society for Heating, Refrigerating and Air-conditioning Engineers) A Practical Guide to Seismic Restraint
4. MSS (Manufacturers Standardization Society of the Valve and Fittings Industry) MSS SP-127, Bracing for Piping Systems, Seismic – Wind – Dynamic, Design, Selection, Application.

1.6 ISOLATOR AND RESTRAINT MANUFACTURER'S RESPONSIBILITIES:

- A. Provide project specific vibration isolation and seismic restraint design prepared by a registered design professional in the state where the project is being constructed, and manufacturer certifications that the components are seismically qualified.

1. Provide calculations to determine restraint loads resulting from seismic forces as required by IBC, Chapter 16 and ASCE 7, latest editions. Seismic calculations shall be certified by an engineer licensed in the state where the project is being constructed.

- B. Provide installation instructions and shop drawings for all materials supplied under this section of the specifications.



1. Provide seismic restraint details with specific information relating to the materials, type, size, and locations of anchorages; materials used for bracing; attachment requirements of bracing to structure and component; and locations of transverse and longitudinal sway bracing and rod stiffeners.
2. Provide seismic bracing layout drawings indicating the location of all seismic restraints.
  - a. Each piece of rotating isolated equipment shall be tagged to clearly identify quantity and size of vibration isolators and seismic restraints.
- C. Provide, in writing, the special inspection requirements for all Designated Seismic Systems as indicated in Chapter 17 of the IBC.
- D. Provide training for installation, operation and maintenance of isolation and restraint systems.

#### 1.7 PERFORMANCE REQUIREMENTS

- A. Wind-Restraint Loading: Per the structural drawings and specifications.
- B. Flood-Restraint Loading: Per the structural drawings and specifications.
- C. Seismic-Restraint Loading:
  1. Site Class as Defined in the IBC: Per the structural drawings and specifications. See structural general notes drawing S-001.
  2. Assigned Occupancy Category as Defined in the IBC: Per the structural drawings and specifications.
    - a. Component Importance Factor: 1.5.
      - 1) Life safety components required to function after an earthquake.
      - 2) Components containing hazardous or flammable materials in quantities that exceed the exempted amounts for an open system listed in Chapter 4.
      - 3) For structures with an Occupancy Category IV, components needed for continued operation of the facility or whose failure could impair the continued operation of the facility.
      - 4) Storage racks in occupancies open to the general public (e.g., warehouse retail stores).
    - b. Component Importance Factor: 1.0.
      - 1) All other components
    - c. Component Response Modification Factor: Per the structural drawings and specifications.
    - d. Component Amplification Factor: Per the structural drawings and specifications.
  3. Design Spectral Response Acceleration at Short Periods: Per the structural drawings and specifications.
  4. Design Spectral Response Acceleration at 1-Second Period: Per the structural drawings and specifications.

## 1.8 ACTION SUBMITTALS

### A. Product Data: For the following:

1. Submittals shall include catalog cut sheets and installation instructions for each type of anchor and seismic restraint used on equipment or components being isolated and/or restrained.
2. Submittals for mountings and hangers incorporating springs shall include spring diameter and free height, rated load, rated deflection, and overload capacity for each vibration isolation device.
3. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of seismic-restraint component used.
  - a. Tabulate types and sizes of seismic restraints, complete with report numbers and rated strength in tension and shear as evaluated by an evaluation service member of ICC-ES.
  - b. Annotate to indicate application of each product submitted and compliance with requirements.
4. Interlocking Snubbers: Include ratings for horizontal, vertical, and combined loads.

### B. Shop Drawings:

1. Detail fabrication and assembly of equipment bases. Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.

### C. Delegated-Design Submittal: For vibration isolation and seismic-restraint details indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.

1. “Basis for Design” report: Statement from the registered design professional that the design complies with the requirements of the ASCE 7-05 Chapter 13, IBC 2052 chapter 1912 and ACI 318. In addition, the basis for compliance must also be noted, as listed below:
  - a. Project specific design documentation prepared and submitted by a registered design professional (ASCE 7, 13.2.1.1)
  - b. Submittal of the manufacturer’s certification that the isolation equipment is seismically qualified by:
  - c. An engineered analysis conforming to the requirements of Chapter 13 of ASCE 7.
  - d. Testing by a nationally recognized testing standard procedure such as ICC-ES AC 156. The substantiated seismic design capacities shall exceed the seismic demands determined by Section 13.3 of ASCE 7.
  - e. Experience data conforming to a nationally recognized procedure. The substantiated seismic design capacities shall exceed the seismic demands determined by Section 13.3 of ASCE 7.

2. Seismic restraint load ratings must be certified and substantiated by testing or calculations under direct control of a registered professional engineer. Copies of testing and calculations must be submitted as part of submittal documents.
3. Include design calculations and details for selecting vibration isolators, seismic restraints, and vibration isolation bases complying with performance requirements, design criteria, and analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
4. Design Calculations: Calculate static and dynamic loading due to equipment weight and operation, seismic forces required to select vibration isolators, seismic restraints, and for designing vibration isolation bases.
  - a. Coordinate design calculations with wind load calculations required for equipment mounted outdoors. Comply with requirements in other Division 23 Sections for equipment mounted outdoors.
5. Vibration Isolation Base Details: Detail overall dimensions, including anchorages and attachments to structure and to supported equipment. Include auxiliary motor slides and rails, base weights, equipment static loads, power transmission, component misalignment, and cantilever loads.
6. Seismic-Restraint Details:
  - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads.
  - b. Details: Indicate fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events. Indicate association with vibration isolation devices.
  - c. Preapproval and Evaluation Documentation: By an evaluation service member of ICC-ES, showing maximum ratings of restraint items and the basis for approval (tests or calculations).

## 1.9 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show coordination of seismic bracing for HVAC piping and equipment with other systems and equipment in the vicinity, including other supports and seismic restraints.
  1. Submittal drawings and calculations must be stamped by a registered professional engineer in the State where the project is being constructed who is responsible for the seismic restraint design.
  2. Calculations and restraint device submittal drawings shall specify anchor bolt type, embedment, concrete compressive strength, minimum spacing between anchors, and minimum distances of anchors from concrete edges. Concrete anchor locations shall not be near edges, stress joints, or an existing fracture. All bolts shall be ASTM A307 or better.

- B. Qualification Data: For professional engineer and testing agency.
- C. Welding certificates.
- D. Field quality-control test reports.

#### 1.10 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
- B. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.
- C. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- D. Seismic-restraint devices shall have horizontal and vertical load testing and analysis and shall bear anchorage preapproval by ICC-ES, or preapproval by another agency acceptable to authorities having jurisdiction, showing maximum seismic-restraint ratings. Ratings based on independent testing are preferred to ratings based on calculations. If preapproved ratings are not available, submittals based on independent testing are preferred. Calculations (including combining shear and tensile loads) to support seismic-restraint designs must be signed and sealed by a qualified professional engineer.

#### 1.11 SEISMIC CERTIFICATION OF EQUIPMENT

- A. Component Importance Factor. All plumbing and mechanical components shall be assigned a component importance factor. The component importance factor,  $I_p$ , shall be taken as 1.5 if any of the following conditions apply:
  - 1. The component is required to function for life-safety purposes after an earthquake.
  - 2. The component contains hazardous materials.
  - 3. The component is in or attached to an Occupancy Category IV structure and it is needed for continued operation of the facility or its failure could impair the continued operation of the facility.
- B. All other components shall be assigned a component importance factor,  $I_p$ , equal to 1.0.
- C. For equipment or components where  $I_p = 1.0$ .
  - 1. Submit manufacturer's certification that the equipment is seismically qualified by:
    - a. An engineered analysis conforming to the requirements of Chapter 13 of ASCE 7.
    - b. Testing by a nationally recognized testing standard procedure such as ICC-ES AC 156. The substantiated seismic design capacities shall exceed the seismic demands determined by Section 13.3 of ASCE 7.

- c. Experience data conforming to a nationally recognized procedure. The substantiated seismic design capacities shall exceed the seismic demands determined by Section 13.3 of ASCE 7.
  2. The equipment and components listed below are considered rugged and shall not require Special Seismic Certification:
    - a. Valves (not in cast-iron housings, except for ductile cast iron).
    - b. Pneumatic operators.
    - c. Hydraulic operators.
    - d. Motors and motor operators.
    - e. Horizontal and vertical pumps (including vacuum pumps).
    - f. Air compressors
    - g. Refrigerators and freezers.
    - h. Elevator cabs.
    - i. Underground tanks.
    - j. Equipment and components weighing not more than 20 lbs. supported directly on structures (and not mounted on other equipment or components) with supports and attachments in accordance with Chapter 13, ASCE 7.
  3. Rugged equipment and components in this section are for factory assembled discrete equipment and components only and do not apply to site assembled or field assembled equipment or equipment anchorage.
- D. Special Certification requirements for Designated Seismic Systems (i.e.  $I_p = 1.5$ ): Seismic Certificates of Compliance supplied by manufacturers shall be submitted for all components that are part of Designated Seismic Systems. In accordance with the ASCE 7, certification shall be via one of the following methods:
  1. For active mechanical and electrical equipment that must remain operable following the design earthquake:
    - a. Testing as detailed by part C.1.b above.
    - b. Experience data as detailed by part C.1.c above.
    - c. Equipment that is considered “rugged” per part C.2 above.
  2. Components with hazardous contents shall be certified by the manufacturer as maintaining containment following the design earthquake by:
    - a. Testing as detailed by part C.1.b above.
    - b. Experience data as detailed by part C.1.c above.
    - c. Engineering analysis utilizing dynamic characteristics and forces. Tanks (without vibration isolators) designed by a registered design professional in accordance with ASME Boiler and Pressure Vessel Code, and satisfying the force and displacement requirements of Sections 13.3.1 and 13.3.2 of ASCE 7 having an importance factor,  $I_p = 1.0$  shall be considered to satisfy the Special Seismic Certification requirements on the basis of ASCE 7 Section 13.6.9.

## PART 2 - PRODUCTS

### 2.1 VIBRATION ISOLATORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Amber/Booth Company, Inc.
  - 2. CalDyn (California Dynamics Corporation).
  - 3. ISAT (International Seismic Application Technology).
  - 4. Kinetics Noise Control.
  - 5. Mason Industries.
  - 6. Vibro-Acoustics
  - 7. VMC (Vibration Mountings & Controls, Inc.)
- B. Elastomeric Isolation Pads P1:
  - 1. Fabrication: Single or multiple layers of sufficient durometer stiffness for uniform loading over pad area.
  - 2. Size: Factory or field cut to match requirements of supported equipment.
  - 3. Pad Material: Oil and water resistant with elastomeric properties.
  - 4. Surface Pattern: Ribbed pattern.
  - 5. Load-bearing metal plates adhered to pads.
- C. Double-Deflection, Elastomeric Isolation Mounts M1:
  - 1. Mounting Plates:
    - a. Top Plate: Encapsulated steel load transfer top plates, factory drilled and threaded, or with threaded studs or bolts.
    - b. Baseplate: Encapsulated steel bottom plates with holes provided for anchoring to support structure.
  - 2. Elastomeric Material: Molded, oil-resistant rubber, neoprene, or other elastomeric material.
- D. Restrained Elastomeric Isolation Mounts M2:
  - 1. Description: All-directional isolator with seismic restraints containing two separate and opposing elastomeric elements that prevent central threaded element and attachment hardware from contacting the housing during normal operation.
    - a. Housing: Cast-ductile iron or welded steel.
    - b. Elastomeric Material: Molded, oil-resistant rubber, neoprene, or other elastomeric material.
- E. Spring Isolators S1: Freestanding, laterally stable, open-spring isolators.

1. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
  2. Minimum Additional Travel: 50 percent of the required deflection at rated load.
  3. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
  4. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
  5. Baseplates: Factory drilled for bolting to structure and bonded to 1/4-inch-thick, rubber isolator pad attached to baseplate underside. Baseplates shall limit floor load to 500 psig.
  6. Top Plate and Adjustment Bolt: Threaded top plate with adjustment bolt and cap screw to fasten and level equipment.
- F. Restrained Spring Isolators S2: Freestanding, steel, open-spring isolators with seismic or limit-stop restraint.
1. Housing: Steel with resilient vertical-limit stops to prevent spring extension due to weight being removed; factory-drilled baseplate bonded to 1/4-inch-thick, neoprene or rubber isolator pad attached to baseplate underside; and adjustable equipment mounting and leveling bolt that acts as blocking during installation. Baseplates shall limit floor load to 500 psig.
  2. Restraint: Seismic or limit stop as required for equipment and authorities having jurisdiction.
  3. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
  4. Minimum Additional Travel: 50 percent of the required deflection at rated load.
  5. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
  6. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
- G. Housed Restrained Spring Isolators S3: Freestanding, Steel, Open-Spring Isolators with Vertical-Limit Stop Restraint in Two-Part Telescoping Housing:
1. Two-Part Telescoping Housing: A steel top and bottom frame separated by an elastomeric material and enclosing the spring isolators. Housings are equipped with adjustable snubbers to limit vertical movement.
    - a. Drilled base housing for bolting to structure with an elastomeric isolator pad attached to the underside. Bases shall limit floor load to 500 psig.
    - b. Threaded top housing with adjustment bolt and cap screw to fasten and level equipment.
  2. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
  3. Minimum Additional Travel: 50 percent of the required deflection at rated load.
  4. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
  5. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
  6. Elastomeric pad: For high frequency absorption at the base of the spring.
- H. Elastomeric Hangers H1:

1. Description: Elastomeric Mount in a Steel Frame with Upper and Lower Steel Hanger Rods
  - a. Frame: Steel, fabricated with a connection for an upper threaded hanger rod and an opening on the underside to allow for a maximum of 30 degrees of angular lower hanger-rod misalignment without binding or reducing isolation efficiency.
  - b. Dampening Element: Molded, oil-resistant rubber, neoprene, or other elastomeric material with a projecting bushing for the underside opening preventing steel to steel contact.
- I. Spring Hangers H2: Combination coil-spring and elastomeric-insert hanger with spring and insert in compression.
  1. Description: Combination Coil-Spring and Elastomeric-Insert Hanger with spring and Insert in Compression.
    - a. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
    - b. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
    - c. Minimum Additional Travel: 50 percent of the required deflection at rated load.
    - d. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
    - e. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
    - f. Elastomeric Element: Molded, oil-resistant rubber or neoprene. Steel-washer-reinforced cup to support spring and bushing projecting through bottom of frame.
    - g. Self-centering hanger rod cap to ensure concentricity between hanger rod and support spring coil.
- J. Spring Hangers with Vertical-Limit Stop H3: Combination coil-spring and elastomeric-insert hanger with spring and insert in compression.
  1. Description: Combination Coil-Spring and Elastomeric-Insert Hanger with spring and insert in Compression and vertical limit stop.
    - a. Frame: Steel, fabricated for connection to threaded hanger rods and to allow for a maximum of 30 degrees of angular hanger-rod misalignment without binding or reducing isolation efficiency.
    - b. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
    - c. Minimum Additional Travel: 50 percent of the required deflection at rated load.
    - d. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
    - e. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
    - f. Elastomeric Element: Molded, oil-resistant rubber or neoprene. Steel-washer-reinforced cup to support spring and bushing projecting through bottom of frame.
    - g. Adjustable Vertical Stop: Steel washer with neoprene washer "up-stop" on lower threaded rod.
    - h. Self-centering hanger rod cap to ensure concentricity between hanger rod and support spring coil.



K. Pipe Riser Resilient Support R1:

1. Description: All-directional, acoustical pipe anchor consisting of 2 steel tubes separated by a minimum of 1/2-inch-thick neoprene.
  - a. Vertical-Limit Stops: Steel and neoprene vertical-limit stops arranged to prevent vertical travel in both directions.
  - b. Maximum Load Per Support: 500 psig on isolation material providing equal isolation in all directions.

L. Resilient Pipe Guides R2:

1. Description: Telescopic arrangement of two steel tubes or post and sleeve arrangement separated by a minimum 1/2-inch-thick neoprene.
  - a. Factory-Set Height Guide with Shear Pin: Shear pin shall be removable and reinsertable to allow for selection of pipe movement. Guides shall be capable of motion to meet location requirements.

M. Horizontal Thrust Restraints T1: Modified specification S2 isolator.

1. Horizontal thrust restraints shall consist of a modified specification S2 spring mounting. Restraint springs shall have the same deflection as the isolator springs.
2. The assembly shall be preset at the factory and fine tuned in the field to allow for a maximum of 1/4" movement from stop to maximum thrust.
3. The assemblies shall be furnished with rod and angle brackets for attachment to both the equipment and duct work or the equipment and the structure.
4. Restraints shall be attached at the center line of thrust and symmetrically on both sides of the unit.

2.2 RESTRAINED VIBRATION ISOLATION ROOF-CURB RAILS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Amber/Booth Company, Inc.
2. CalDyn (California Dynamics Corporation).
3. ISAT (International Seismic Application Technology).
4. Kinetics Noise Control.
5. Mason Industries.
6. Vibro-Acoustics
7. VMC (Vibration Mountings & Controls, Inc.)

B. Restrained Vibration Isolation Roof-Curb Rails: RC1:

C. Description: Factory-assembled, fully enclosed, insulated, air- and watertight curb rail designed to resiliently support equipment and to withstand seismic and wind forces.

- D. Upper Frame: The upper frame shall provide continuous support for equipment and shall be captive to resiliently resist seismic forces.
- E. Lower Support Assembly: The lower support assembly shall be a formed sheet-metal section containing adjustable and removable steel springs that support upper frame. Lower support assembly shall have a means for attaching to building structure and a wood nailer for attaching roof materials, and shall be insulated with a minimum of 2 inches of rigid, glass-fiber insulation on inside of assembly.
- F. Spring Isolators: Adjustable, restrained spring isolators shall be mounted on 1/4-inch-thick, elastomeric vibration isolation pads and shall have access ports, for level adjustment, with removable waterproof covers at all isolator locations. Isolators shall be located so they are accessible for adjustment at any time during the life of the installation without interfering with the integrity of the roof.
  - 1. Restrained Spring Isolators: Freestanding, steel, open-spring isolators with seismic and wind restraint.
    - a. Housing: Steel with resilient vertical-limit stops and adjustable equipment mounting and leveling bolt.
    - b. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
    - c. Minimum Additional Travel: 50 percent of the required deflection at rated load.
    - d. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
    - e. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
- G. Snubber Bushings: All-directional, elastomeric snubber bushings at least 1/4 inch-thick.
- H. Water Seal: Galvanized sheet metal with EPDM seals at corners, attached to upper support frame, extending down past wood nailer of lower support assembly, and counter flashed over roof materials.

## 2.3 VIBRATION ISOLATION EQUIPMENT BASES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Amber/Booth Company, Inc.
  - 2. CalDyn (California Dynamics Corporation).
  - 3. ISAT (International Seismic Application Technology).
  - 4. Kinetics Noise Control.
  - 5. Mason Industries.
  - 6. Vibro-Acoustics
  - 7. VMC (Vibration Mountings & Controls, Inc.)
- B. Steel Bases and Rails SB1: Factory-fabricated, welded, structural-steel bases and rails.

1. Design Requirements: Lowest possible mounting height with not less than 1-inch clearance above the floor. Include equipment anchor bolts and auxiliary motor slide bases or rails.
    - a. Include supports for suction and discharge elbows for pumps.
  2. Structural Steel: Steel shapes, plates, and bars complying with ASTM A 36/A 36M. Bases shall have shape to accommodate supported equipment.
  3. Support Brackets: Factory-welded steel brackets on frame for outrigger isolation mountings and to provide for anchor bolts and equipment support.
- C. Inertia Base IB1: Factory-fabricated, welded, structural-steel bases and rails ready for placement of cast-in-place concrete.
1. Design Requirements: Lowest possible mounting height with not less than 2-inch clearance above the floor. Include equipment anchor bolts and auxiliary motor slide bases or rails.
    - a. Include supports for suction and discharge elbows for pumps.
  2. Structural Steel: Steel shapes, plates, and bars complying with ASTM A 36/A 36M. Bases shall have shape to accommodate supported equipment.
  3. Support Brackets: Factory-welded steel brackets on frame for outrigger isolation mountings and to provide for anchor bolts and equipment support.
  4. Fabrication: Fabricate steel templates to hold equipment anchor-bolt sleeves and anchors in place during placement of concrete. Obtain anchor-bolt templates from supported equipment manufacturer.

## 2.4 SEISMIC-RESTRAINT DEVICES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Amber/Booth Company, Inc.
  2. CalDyn (California Dynamics Corporation).
  3. ISAT (International Seismic Application Technology).
  4. Kinetics Noise Control.
  5. Mason Industries.
  6. Vibro-Acoustics
  7. VMC (Vibration Mountings & Controls, Inc.)
- B. General Requirements for Restraint Components: Rated strengths, features, and applications shall be as defined in reports by an evaluation service member of ICC-ES.
1. Structural Safety Factor: Allowable strength in tension, shear, and pullout force of components shall be at least four times the maximum seismic forces to which they will be subjected.

- C. Snubbers: Factory fabricated using welded structural-steel shapes and plates, anchor bolts, and replaceable resilient isolation washers and bushings.
  - 1. Anchor bolts for attaching to concrete shall be seismic-rated, drill-in, and stud-wedge or female-wedge type.
  - 2. Resilient Isolation Washers and Bushings: Oil- and water-resistant neoprene.
  - 3. Maximum 1/4-inch air gap, and minimum 1/4-inch-thick resilient cushion.
- D. Channel Support System: MFMA-4, shop- or field-fabricated support assembly made of slotted steel channels with accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; and rated in tension, compression, and torsion forces.
- E. Restraint Cables: ASTM A 603 galvanized or ASTM A 492 stainless-steel cables with end connections made of steel assemblies with thimbles, brackets, swivel, and bolts designed for restraining cable service; and with a minimum of two clamping bolts for cable engagement. Cables located in exterior or other wet locations such as wash-down areas shall be stainless steel.
- F. Hanger Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections or reinforcing steel angle clamped to hanger rod.
- G. Hinged and Swivel Brace Attachments: Multifunctional steel connectors for attaching hangers to rigid channel bracings and restraint cables.
- H. Bushings for Floor-Mounted Equipment Anchor Bolts: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchor bolts and studs.
- I. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices used.
- J. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.
- K. Mechanical Anchor Bolts: Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488. Minimum length of eight times diameter.
- L. Adhesive Anchor Bolts: Drilled-in and capsule anchor system containing polyvinyl or urethane methacrylate-based resin and accelerator, or injected polymer or hybrid mortar adhesive. Provide anchor bolts and hardware with zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488.
- M. All post installed anchors utilized in the seismic design must be qualified for use in cracked concrete and approved for use with seismic loads.

- N. Expansion anchors shall not be used for anchorage of equipment with motors rated over 10 HP with the exception of undercut expansion anchors. Spring or internally isolated equipment are exempt from this requirement.
- O. All beam clamps utilized for vertical support must also incorporate retention straps.
- P. All seismic brace arm anchorages to include concrete anchors, beam clamps, truss connections, etc., must be approved for use with seismic loads.

## 2.5 FACTORY FINISHES

- A. Finish: Manufacturer's standard paint applied to factory-assembled and tested equipment before shipping.
  - 1. Powder coating on springs and housings.
  - 2. All hardware shall be galvanized. Hot-dip galvanize metal components for exterior use.
  - 3. Baked enamel or powder coat for metal components on isolators for interior use.
  - 4. Color-code or otherwise mark vibration isolation and seismic control devices to indicate capacity range.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine areas and equipment to receive vibration isolation and seismic control devices for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 COORDINATION

- A. Coordinate the location of embedded connection hardware with supported equipment attachment and mounting points and with requirements for concrete reinforcement and formwork specified in Division 03 Section "Cast-in-Place Concrete."
- B. Coordinate size, shape, reinforcement and attachment of all housekeeping pads supporting vibration/seismically rated equipment. Concrete shall have a minimum compressive strength of 4,000 psi or as specified by the project engineer. Coordinate size, thickness, doweling, and reinforcing of concrete equipment housekeeping pads and piers with vibration isolation and seismic restraint device manufacturer to ensure adequate space, embedment and prevent edge breakout failures. Pads and piers must be adequately doweled in to structural slab.

- C. Housekeeping pads shall have adequate space to mount equipment and seismic restraint devices.
- D. Housekeeping Pads must be adequately reinforced and adequately sized for proper installation of equipment anchors and shall also be large enough and thick enough to ensure adequate edge distance and embedment depth for restraint anchor bolts to avoid housekeeping pad breakout failure. Refer seismic restraint manufacturer's written instructions.
- E. Coordinate with vibration/seismic restraint manufacturer and the structural engineer of record to locate and size structural supports underneath vibration/seismically restrained equipment (e.g. roof curbs, cooling towers and other similar equipment). Installation of all seismic restraint materials specified in this section shall be accomplished as per the manufacturer's written instructions. Adjust isolators and restraints after piping systems have been filled and equipment is at its operating weight, following the manufacturer's written instructions.

### 3.3 APPLICATIONS

- A. Multiple Pipe Supports: Secure pipes to trapeze member with clamps approved for application by an evaluation service member of ICC-ES and per the seismic restraint manufacturer's design.
- B. Hanger Rod Stiffeners: Install hanger rod stiffeners where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods due to seismic forces.
- C. Strength of Support and Seismic-Restraint Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static and seismic loads within specified loading limits.

### 3.4 VIBRATION-CONTROL DEVICE INSTALLATION

- A. Comply with requirements in Division 07 Section "Roof Accessories" for installation of roof curbs, equipment supports, and roof penetrations.
- B. Comply with requirements in Division 23 Section "Hydronic Piping" for piping flexible connections.
- C. Isolate all mechanical equipment 0.75 hp and over per the isolator and seismic restraint schedule and these specifications. Vibration isolators shall be selected in accordance with the equipment, pipe or duct weight distribution so as to produce reasonably uniform deflections
- D. All isolation materials and seismic restraints shall be of the same vendor and shall be selected and certified using published or factory certified data
- E. Installation of all vibration isolation materials, flexible connectors and supplemental equipment bases specified in this section shall be accomplished as per the manufacturer's written instructions with mountings adjusted to level equipment. Any variance or non-compliance with the manufacturer's instructions shall be reviewed and approved in writing by the manufacturer or corrected by the contractor in an approved manner.

- F. Installation of vibration isolators must not cause any change of position of equipment, piping or duct work resulting in stresses or misalignment.
- G. Locate isolation hangers as near to the overhead support structure as possible.
- H. No rigid connections between isolated components and the building structure shall be made that degrades the noise and vibration control system herein specified. "Building" includes, but is not limited to, slabs, beams, columns, studs and walls. "Components" includes, but is not limited to, mechanical equipment, piping and ducts.
- I. Coordinate work with other trades to avoid rigid contact with the building.
- J. Any conflicts with other trades which will result in rigid contact with equipment or piping due to inadequate space or other unforeseen conditions should be brought to the architects/engineers attention prior to installation. Corrective work necessitated by conflicts after installation shall be at the responsible contractor's expense.
- K. Bring to the architects/engineers attention any discrepancies between the specifications and the field conditions or changes required due to specific equipment selection, prior to installation. Corrective work necessitated by discrepancies after installation shall be at the responsible contractor's expense.
- L. Correct, at no additional cost, all installations which are deemed defective in workmanship and materials at the contractor's expense.
- M. Use horizontal thrust restraints T1 to protect Air handling equipment and centrifugal fans against excessive displacement which results from high air thrust when thrust forces exceed 10% of the equipment weight.
- N. Isolated equipment, duct and piping located on roofs must be attached to the structure. Supports (e.g., sleepers) that are not attached to the structure will not be acceptable.
- O. On completion of installation of all isolation materials and before startup of isolated equipment all debris shall be cleared from areas surrounding and from beneath all isolated equipment, leaving equipment free to move on the isolation supports.
- P. All floor mounted isolated equipment shall be protected with specification M1, M2, S1, S2 or S3 isolator.
- Q. Horizontal Pipe Isolation: All HVAC pumped water, pumped condensate, glycol, and refrigerant piping size 1-1/4" and larger within mechanical rooms shall be isolated. Outside equipment rooms this piping shall be isolated for the greater of 50' or 100 pipe diameters from rotating equipment. For the first three (3) support locations from externally isolated equipment provide specification H2 or H3 hangers or specification S1, S2 or S3 mounts with the same deflection as equipment isolators (max 2"). All other piping within the equipment rooms shall be isolated with the same specification isolators with a 3/4" minimum deflection. Steam piping size 1-1/4" and larger which is within an equipment room and connected to rotating equipment shall be isolated for three (3) support locations from the equipment. Provide specification H2 or H3 hangers, or specification S1 or S2 mounts with the same deflection as equipment isolators but a minimum of 3/4".

- R. Install full line size flexible pipe connectors at the inlet and outlet of each pump, cooling tower, condenser, chiller, coiling connections and where shown on the drawings. All connectors shall be suitable for use at the temperature, pressure, and service encountered at the point of installation and operation. End fitting connectors shall conform to the pipefitting schedule. Control rods or protective braid must be used to limit elongation to 3/8". Flexible connectors shall not be required for suspended in-line pumps.
- S. All plumbing pumped water, piping size 1-1/4" and larger within mechanical rooms shall be isolated the same as HVAC piping above. Isolators are not required for any plumbing pumped water, pumped condensate, and steam piping outside of mechanical rooms unless listed in the isolation schedule.
- T. Pipe Riser Isolation: The operating weight of all variable temperature vertical pipe risers 1-1/4" and larger, requiring isolation where specifically shown and detailed on riser drawings shall be fully supported by specification M1, M2 or R1 supports. S1, S2, S3, H2 or H3 steel spring deflection isolators with minimum 3/4-inch minimum shall be in those locations where added deflection is required due to pipe expansion and contraction. Spring deflection shall be a minimum of 4 times the anticipated deflection change. Springs shall be selected to keep the riser in tension. Height saving brackets used with isolators having 2.5" deflection or greater shall be of the precompression type to limit exposed bolt length. Specification R1 riser supports shall be installed near the center point of the riser to anchor the riser when spring isolation is used. Specification R2 riser guides may be used in conjunction with spring isolators per design calculations. Pipe risers up through 16" shall be supported at intervals of every third floor of the building. Pipe risers 18" and over, every second floor. Wall sleeves for take-offs from riser shall be sized for insulation O.D. plus two times the anticipated movement to prevent binding. Horizontal take-offs and at upper and lower elbows shall be supported with spring isolators as required to accommodate anticipated movement. In addition to submittal data requirements previously outlined, riser diagrams and calculations shall be submitted for approval. Calculations must show anticipated expansion and contraction at each support point, initial and final loads on the building structure, and spring deflection changes. Submittal data shall include certification that the riser system has been examined for excessive stresses and that none will exist if installed per design proposed.
- U. Where riser pipes pass through cored holes, core diameters shall be a maximum of 2" larger than pipe O.D. including insulation. Cored holes must be packed with resilient material or firestop as provided by other sections of this specification or local codes. Where seismic restraint is required specification isolator S3 shall support risers and provide longitudinal restraint at floors where thermal expansion is minimal and will not bind isolator restraints.
- V. Duct Isolation: Isolate all duct work with a static pressure 2" W.C. and over in equipment rooms and to minimum of 50 feet from the fan or air handler. Use specification type H2 or H3 hangers or type S1 or S2 floor mounts.

### 3.5 SEISMIC-RESTRAINT DEVICE INSTALLATION

#### A. Equipment Restraints:

1. On projects with Seismic Site Class A or B, seismic design or restraint is not required.



2. On projects with Seismic Design Category C: Components with an importance factor of 1.0 do not require seismic design or restraint.
3. Install seismic snubbers on HVAC equipment mounted on vibration isolators. Locate snubbers as close as possible to vibration isolators and bolt to equipment base and supporting structure.
4. Install resilient bolt isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
5. Install seismic-restraint devices using methods approved by an evaluation service member of ICC-ES providing required submittals for component.
6. Suspended Equipment: All suspended equipment that meets any of the following conditions requires seismic restraints as specified by the supplier:
  - a. Rigidly attached to pipe or duct that is 75 lbs. and greater,
  - b. Items greater than 20 lbs and distribution systems weighing more than 5 lbs/lineal foot, with an importance factor of 1.0 hung independently or with flexible connections.
  - c. Possibility of consequential damage.
  - d. For importance factors greater than 1.0 all suspended equipment requires seismic restraint regardless of the above notes.
  - e. Wall mounted equipment weighing more than 20 lbs.
  - f. Exemptions:
    - 1) Equipment weighing less than 20 lbs and distribution systems weighing less than 5 lbs/lineal foot, with an  $I_p = 1.0$  and where flexible connections exist between the component and associated ductwork, piping or conduit.
7. Base Mounted Equipment: All base mounted equipment that meets any of the following conditions requires attachments and seismic restraints as specified by the supplier:
  - a. Connections to or containing hazardous material,
  - b. With an overturning moment.
  - c. Weight greater than 400 lbs.
  - d. Mounted on a stand 4 ft. or more from the floor
  - e. Possibility of consequential damage.
  - f. For importance factors greater than 1.0 all base mounted items require seismic restraints regardless of the above notes.
  - g. For equipment with high center of gravity additional cable restraints shall be furnished, as required by isolation manufacturer, to limit forces and motion caused by rocking.
  - h. Exemptions:
    - 1) Floor or curb-mounted equipment weighing less than 400 lbs and not resiliently mounted, where the Importance Factor,  $I_p = 1.0$ , the components are mounted at 4 feet or less above a floor level, flexible connections between the components and associated duct work, piping and conduit are provided and there is no possibility of consequential damage.

8. Roof Mounted Equipment:
  - a. To be installed on a structural frame, seismically rated roof curb, or structural curb frame mechanically connected to the structure. Items shall not be mounted onto sleepers or pads that are not mechanically and rigidly attached to the structure. Restraint must be adequate to resist both seismic and wind forces.
  - b. Roof curbs shall be installed directly to building structural steel or concrete roof deck and not to top of steel deck or roofing material.
  - c. Exemptions:
    - 1) Curb-mounted mushroom, exhaust and vent fans with curb area less than nine square feet are excluded.
9. Rigid Mounted Equipment:
  - a. Anchor floor and wall mounted equipment to the structure as per the stamped seismic certifications / drawings.
  - b. For equipment with high center of gravity additional cable restraints shall be furnished, as required by isolation manufacturer, to limit forces and motion caused by rocking.
  - c. Suspended equipment shall be restrained using seismic cable restraints, or struts, and hanger rods as per the stamped seismic certifications / drawings.
10. Vibration Isolated Equipment:
  - a. Seismic control shall not compromise the performance of noise control, vibration isolation or fire stopping systems.
  - b. Equipment supported by vibration-isolation hangers shall be detailed and installed with approximately a 1/8" gap between the isolation hangers and the structure. Isolators at restraint locations must be fitted with uplift limit stops.
- B. Install seismic snubbers on HVAC equipment mounted on vibration isolators. Locate snubbers as close as possible to vibration isolators and bolt to equipment base and supporting structure.
- C. Install resilient bolt isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch.
- D. Install seismic-restraint devices using methods approved by an evaluation service member of ICC-ES providing required submittals for component.
- E. Installation and adjustment of all seismic restraints specified in this section shall be accomplished as per the manufacturer's written instructions. Any deviation from the manufacturer's instructions shall be reviewed and approved by the manufacturer.
- F. Piping Restraints:
  1. Comply with requirements in MSS SP-127.
  4. Seismically restrain piping, with an  $I_p = 1.0$ , located in boiler rooms, mechanical equipment rooms and refrigeration equipment rooms that is 1¼" I.D. and larger.
  5. Seismically restrain all other  $I_p = 1.0$  piping 2½" diameter and larger.
  6. Seismically restrain all  $I_p = 1.5$  piping larger than 1" diameter.
  7. Branch lines may not be used to brace main lines.

8. Exemptions:
- a. All high deformability pipe 3" or less in diameter suspended by individual hanger rods where  $I_p = 1.0$ .
  - b. High deformability pipe or conduit in Seismic Design Category C, 2" or less in diameter suspended by individual hanger rods where  $I_p = 1.5$ .
  - c. High deformability pipe in Seismic Design Category D, E or F, 1" or less in diameter suspended by individual hanger rods where  $I_p = 1.5$ .
  - d. All clevis supported pipe runs installed less than 12" from the top of the pipe to the underside of the support point and trapeze supported pipe suspended by hanger rods having a distance less than 12" in length from the underside of the pipe support to the support point of the structure.
  - e. Piping systems, including their supports, designed and constructed in accordance with ASME B31.
  - f. Piping systems, including their supports, designed and constructed in accordance with NFPA, provided they meet the force and displacement requirements of Section 13.3.1 and 13.3.2 (ASCE 7).
- G. Install flexible metal hose loops in piping which crosses building seismic joints, sized for the anticipated amount of movement.
- H. Install flexible piping connectors where adjacent sections or branches are supported by different structural elements, and where the connections terminate with connection to equipment that is anchored to a different structural element from the one supporting the connections as they approach equipment.
- I. Where pipe sizes reduce below dimensions required for seismic, the final restraint shall be installed at the transition location.
- J. Restraint Spacing For Piping: Sizes shown are maximum. Actual spacing determined by calculation.
- 1. For non-ductile piping (e.g., cast iron, PVC) space transverse supports a maximum of 20' o.c., and longitudinal supports a maximum of 40' o.c.
  - 2. For piping with hazardous material inside (e.g., natural gas, medical gas) space Transverse supports a maximum of 20' o.c., and longitudinal supports a maximum of 40' o.c.
  - 3. For pipe risers, restrain the piping at floor penetrations using the same spacing requirements as above.
  - 4. For all other ductile piping see Table "A" below
- K. Seismic Restraint of Ductwork: Seismically restrain per specific code requirements, all ductwork listed below (unless otherwise indicated on the drawings), using seismic cable restraints: (Ductwork not meeting criteria listed below is to be "Exempt")
- 1. Restrain rectangular ductwork with cross sectional area of 6 square feet or larger. Duct with and an importance factor of 1.5 must be braced with no exceptions regardless of size or distance requirements.
  - 2. Restrain round ducts with diameters of 28" or larger. Duct with an importance factor of 1.5 must be braced with no exceptions regardless of size or distance requirements.

3. Restrain flat oval ducts the same as rectangular ducts of the same nominal size.
4. Duct must be reinforced at the restraint locations. Reinforcement shall consist of an additional angle on top of the ductwork that is attached to the support hanger rods. Ductwork is to be attached to both upper angle and lower trapeze. Additional reinforcing is not required if duct sections are mechanically fastened together with frame bolts and positively fastened to the duct support suspension system.
5. A group of ducts may be combined in a larger frame so that the combined weights and dimensions of the ducts are less than or equal to the maximum weight and dimensions of the duct for which bracing details are selected.
6. Walls, including gypsum board non-bearing partitions, which have ducts running through them, may replace a typical transverse brace. Provide channel framing around ducts and solid blocking between the duct and frame.
7. If ducts are supported by angles, channels or struts, ducts shall be fastened to it at seismic brace locations in lieu of duct reinforcement.
8. All ductwork weighing more than 17 lb/ft.
9. Exemptions:
  - a. Duct runs supported at locations by two rods less than 12 inches in length from the structural support to the structural connection to the ductwork. This exemption does not apply to ducts with an importance factor of 1.5.
10. See Table "A" below for restraint spacing.

L. Exemptions do not apply for:

1. Life Safety or High Hazard Components
  - a. Including gas, fire protection, medical gas, fuel oil and compressed air needed for the continued operation of the facility or whose failure could impair the facility's continued operation, Occupancy Category IV, IBC-2018 as listed in Section 1.3 B regardless of governing code for HVAC, Plumbing, Electrical piping or equipment. (A partial list is illustrated.) High Hazard is additionally classified as any system handling flammable, combustible or toxic material. Typical systems not excluded are additionally listed below.
2. Piping
  - a. Fuel oil, gasoline, natural gas, medical gas, steam, compressed air or any piping containing hazardous, flammable, combustible, toxic or corrosive materials. Fire protection standpipe, risers and mains. Fire Sprinkler Branch Lines must be end tied.
3. Duct
  - a. Smoke evacuation duct or fresh air make up connected to emergency system, emergency generator exhaust, boiler breeching or as used by the fire department on manual override.
4. Equipment

- a. Previously excluded non life safety duct mounted systems such as fans, variable air volume boxes, heat exchangers and humidifiers having a weight greater than 75 lbs require independent seismic bracing.

M. Spacing Chart For Suspended Components:

| Table "A" Seismic Bracing<br>(Maximum Allowable Spacing Shown- Actual Spacing to Be Determined by Calculation) |                      |                        |                     |
|----------------------------------------------------------------------------------------------------------------|----------------------|------------------------|---------------------|
| Equipment                                                                                                      | On Center Transverse | On Center Longitudinal | Change Of Direction |
| Duct                                                                                                           |                      |                        |                     |
| All Sizes                                                                                                      | 30 Feet              | 60 Feet                | 4 Feet              |
| Pipe Threaded, Welded, Soldered Or Grooved                                                                     |                      |                        |                     |
| To 16"                                                                                                         | 40 Feet              | 80 Feet                | 4 Feet              |
| 18" – 28"                                                                                                      | 30 Feet              | 60 Feet                | 4 Feet              |
| 30" – 40"                                                                                                      | 20 Feet              | 60 Feet                | 4 Feet              |
| 42" & Larger                                                                                                   | 10 Feet              | 30 Feet                | 4 Feet              |

- N. Roof mounted duct is to be installed on sleepers or frames mechanically connected to the building structure. Roof anchors and seismic cables or frames shall be used to resist seismic and wind loading. Wind loading factors shall be determined by the registered design professional.
- O. Where duct sizes reduce below dimensions required for seismic restraint the final restraint shall be installed at the transition location.
- P. Install cables so they do not bend across edges of adjacent equipment or building structure.
- Q. Install bushing assemblies for anchor bolts for floor-mounted equipment, arranged to provide resilient media between anchor bolts and mounting hole in concrete base.
- R. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- S. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.
- T. Seismically Rated Beam Clamps are required where welding to or penetrations to steel beams are not approved.
- U. Drilled-in Anchors:
  1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify the structural engineer if reinforcing steel or other embedded items are encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
  2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.

3. Wedge Anchors: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
4. Adhesive Anchors: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
5. Set anchors to manufacturer's recommended torque, using a torque wrench.
6. Install zinc-coated steel anchors for interior and stainless-steel anchors for exterior applications.

### 3.6 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

- A. Install flexible connections in piping where they cross seismic joints, where adjacent sections or branches are supported by different structural elements, and where the connections terminate with connection to equipment that is anchored to a different structural element from the one supporting the connections as they approach equipment. Comply with requirements in Division 23 Section "Hydronic Piping" for piping flexible connections.

### 3.7 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Perform tests and inspections.
  1. A representative of the vibration isolation system manufacturer shall review the project installation and provide documentation indicating conformance to vibration isolation design intent
- C. Remove and replace malfunctioning units and retest as specified above.
- D. Prepare test and inspection reports.
  1. The installing contractor shall submit a report upon request to the building architect and/or engineer, including the manufacturer's representative's final report, indicating that all seismic restraint material has been properly installed, or steps that are to be taken by the contractor to properly complete the seismic restraint work as per the specifications.

### 3.8 IDENTIFICATION

- A. Install identification tags at all seismic brace locations. Tags to include the following information:
  1. Specific seismic forces (g-force) the location was designed to resist.
  2. Maximum brace reaction at connection to structure.
  3. For single hung items, the maximum pipe/conduit size the brace location was designed to accommodate.

4. For trapeze supported items, the maximum weight (lbs/lf) the brace location was designed to accommodate.
5. For suspended equipment, the maximum unit operating weight (lbs) the brace location was designed to accommodate.
6. Location identifier cross matched to that on plan set layout.
7. Company name of installing contractor.

### 3.9 ADJUSTING

- A. Adjust isolators after piping system is at operating weight.
- B. Adjust leveling devices as required to distribute loading uniformly on isolators. Shim units as required where leveling devices cannot be used to distribute loading properly.
  1. Adjust active height of spring isolators.
- C. Adjust limit stops on restrained spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.
- D. Adjust restraints to permit free movement of equipment within normal mode of operation.

| EQUIPMENT ISOLATION<br>SCHEDULE                   |                                        |                                       |              |                                        |                                       |              |                      |                                       |              |
|---------------------------------------------------|----------------------------------------|---------------------------------------|--------------|----------------------------------------|---------------------------------------|--------------|----------------------|---------------------------------------|--------------|
| LOCATION<br><br>EQUIPMENT (1)                     | A'<br>CRITICAL<br>AL<br>(35'-50' SPAN) |                                       |              | B'<br>UPPER<br>STORY<br>(20'-35' SPAN) |                                       |              | C'<br>GRADE          |                                       |              |
|                                                   | ISOL<br>ATOR<br>TYPE                   | MINIM<br>UM<br>DEFLE<br>CTION<br>(IN) | BASE<br>TYPE | ISOL<br>ATOR<br>TYPE                   | MINIM<br>UM<br>DEFLE<br>CTION<br>(IN) | BASE<br>TYPE | ISOLA<br>TOR<br>TYPE | MINIM<br>UM<br>DEFLE<br>CTION<br>(IN) | BASE<br>TYPE |
| AIR HANDLING UNITS<br>FLOOR MOUNTED               |                                        |                                       |              |                                        |                                       |              |                      |                                       |              |
| UP TO 15 HP                                       | S3                                     | 1.5                                   |              | S3                                     | 0.75                                  |              | S3                   | 0.75                                  |              |
| 20 HP & OVER                                      | S3                                     | 2.5                                   | SB1          | S3                                     | 1.5                                   |              | S3                   | 0.75                                  |              |
| SUSPENDED                                         |                                        |                                       |              |                                        |                                       |              |                      |                                       |              |
| UP TO 15 HP                                       | H3                                     | 1.75                                  |              | H3                                     | 1                                     |              | H3                   | 1                                     |              |
| 20 HP & OVER                                      | H3                                     | 2.5                                   | SB1          | H3                                     | 1.75                                  |              | H3                   | 1                                     |              |
| HIGH PRESSURE FAN<br>SECTIONS                     |                                        |                                       |              |                                        |                                       |              |                      |                                       |              |
| UP TO 30 HP                                       | S1                                     | 2.5                                   | IB1          | S3                                     | 1.5                                   | IB1          | S3                   | 0.75                                  | IB1          |
| 40 HP & OVER                                      | S1                                     | 3.5                                   | IB1          | S3                                     | 2.5                                   | IB1          | S3                   | 1.5                                   | IB1          |
| CENTRIFUGAL FANS<br>CL. I & II UP TO 54-112" W.D. |                                        |                                       |              |                                        |                                       |              |                      |                                       |              |
| UPT015HP                                          | S3                                     | 1.5                                   | SB1          | S3                                     | 0.75                                  | SB1          | S3                   | 0.75                                  | SB1          |
| 20-50 HP                                          | S1                                     | 2.5                                   | IB1          | S3                                     | 1.5                                   | IB1          | S3                   | 0.75                                  | SB1          |

|                                                                |    |      |     |    |      |     |      |      |     |
|----------------------------------------------------------------|----|------|-----|----|------|-----|------|------|-----|
| 60 HP & OVER<br>CL. I & II 60" W.D. & OVER<br>ALL CL. III FANS | S1 | 3.5  | IB1 | S1 | 2.5  | IB1 | S3   | 1.5  | SB1 |
| UPT015HP                                                       | S1 | 2.5  | IB1 | S3 | 1.5  | IB1 | S3   | 0.75 | IB1 |
| 20-50 H P                                                      | S1 | 2.5  | IB1 | S1 | 2.5  | IB1 | S3   | 1.5  | IB1 |
| 60 HP & OVER                                                   | S1 | 3.5  | IB1 | S1 | 2.5  | IB1 | S3   | 1.5  | IB1 |
| AXIAL FLOWFANS                                                 |    |      |     |    |      |     |      |      |     |
| FLOOR MTD.                                                     |    |      |     |    |      |     |      |      |     |
| UP TO 15 HP                                                    | S3 | 1.5  | SB1 | S3 | 0.75 |     | S3   | 0.75 |     |
| 20 HP & OVER                                                   | S1 | 3.5  | IB1 | S3 | 1.5  |     | S3   | 0.75 |     |
| SUSPENDED                                                      |    |      |     |    |      |     |      |      |     |
| UP TO 15 HP                                                    | H3 | 1.75 | SB1 | H3 | 1    |     | H3   | 1    |     |
| 20 HP & OVER                                                   | H3 | 2.5  | SB1 | H3 | 1.75 | SB1 | H3   | 1.5  |     |
| VENT (UTILITY SETS)                                            |    |      |     |    |      |     |      |      |     |
| FLOOR MTD                                                      | S3 | 1.5  | SB1 | S3 | 0.75 |     | S3   | 0.75 |     |
| SUSPENDED                                                      | H3 | 1.75 | SB1 | H3 | 1    |     | H3   | 0.75 |     |
| CABINET FANS, FANS<br>SECTIONS                                 |    |      |     |    |      |     |      |      |     |
| FLOOR MTD.                                                     |    |      |     |    |      |     |      |      |     |
| UP TO 15 HP                                                    | S3 | 1.5  |     | S3 | 0.75 |     | S3   | 0.75 |     |
| 20 HP & OVER                                                   | S1 | 2.5  | IB1 | S3 | 1.5  |     | S3   | 0.75 |     |
| SUSPENDED                                                      |    |      |     |    |      |     |      |      |     |
| UP TO 15 HP                                                    | H3 | 1.75 |     | H3 | 1    |     | H3   | 0.75 |     |
| 20 HP & OVER                                                   | H3 | 2.5  | SB1 | H3 | 1.75 |     | H3   | 1.75 |     |
| PUMPS                                                          |    |      |     |    |      |     |      |      |     |
| FLOOR MTD.                                                     |    |      |     |    |      |     |      |      |     |
| UP TO 15 HP                                                    | S3 | 0.75 | IB1 | S3 | 0.75 | IB1 | SRVD | 0.4  | IB1 |
| 7-112 HP & OVER                                                | S3 | 1.5  | IB1 | S3 | 1.5  | IB1 | S3   | 0.75 | IB1 |
| SUSPENDED INLINE                                               | H3 | 1.75 |     | H3 | 1.75 |     | H3   | 1    |     |
| REFRIGERATION UNITS                                            |    |      |     |    |      |     |      |      |     |
| RECIPROCATING<br>COMPRESSORS                                   | S1 | 2.5  | IB1 | S3 | 1.5  | IB1 | S3   | 0.75 | IB1 |
| RECIPROCATING COND.<br>UNITS & CHILLERS                        | S1 | 2.5  | IB1 | S3 | 1.5  |     | S3   | 0.75 |     |
| HERMETIC<br>CENTRIFUGALS                                       | S3 | 2.5  |     | S3 | 1.5  |     | P1   | 0.15 |     |
| OPEN CENTRIFUGALS                                              | S1 | 2.5  | IB1 | S3 | 1.5  | IB1 | P1   | 0.15 |     |
| ABSORPTION MACHINES                                            | S3 | 1.5  |     | S3 | 0.75 |     | P1   | 0.15 |     |
| AIR COMPRESSORS                                                |    |      |     |    |      |     |      |      |     |
| TANK TYPE<br>(HORIZONTAL TANK)                                 | S1 | 2.5  | IB1 | S3 | 1.5  |     | S3   | 0.75 |     |
| TANK TYPE (VERTICAL<br>TANK)                                   | S1 | 2.5  | IB1 | S3 | 1.5  | IB1 | S3   | 0.75 |     |
| COOLING TOWERS &<br>CLOSED CIRCUIT COOLERS                     |    |      |     |    |      |     |      |      |     |
| UP TO 500 TONS                                                 | S3 | 2.5  |     | S3 | 0.75 |     | P1   | 0.15 |     |
| OVER 500 TONS                                                  | S3 | 4.5  |     | S3 | 2.5  |     | P1   | 0.15 |     |
| AIR COOLED CONDENSERS                                          |    |      |     |    |      |     |      |      |     |
| UP TO 50 TONS                                                  | S3 | 1.5  |     | S3 | 0.75 |     | P1   | 0.15 |     |



|                                                                |    |     |     |    |      |     |    |      |  |
|----------------------------------------------------------------|----|-----|-----|----|------|-----|----|------|--|
| OVER 50 TONS                                                   | S3 | 2.5 |     | S3 | 1.5  |     | P1 | 0.15 |  |
| ROOFTOP AIR<br>CONDITIONING UNITS<br>REQUIRING WEATHER<br>SEAL |    |     |     |    |      |     |    |      |  |
| UP TO 5000 CFM (12 TON)                                        | S1 | 1.5 | RC1 | S1 | 0.75 | RC1 |    |      |  |
| OVER 5000 CFM (12 TON)                                         | S3 | 2.5 | RC1 | S3 | 1.5  | RC1 |    |      |  |
| OTHER TYPES                                                    |    |     |     |    |      |     |    |      |  |
| UP TO 25 TONS                                                  | S3 | 1.5 |     | S3 | 1.5  |     |    |      |  |
| OVER 25 TONS                                                   | S3 | 2.5 |     | S3 | 1.5  |     |    |      |  |
| BOILER (PACKAGE TYPE)                                          |    |     |     |    |      |     |    |      |  |
| ALL SIZES                                                      | S3 | 1.5 |     | S3 | 0.75 |     | P1 | 0.15 |  |
| ENGINE DRIVEN<br>GENERATORS                                    |    |     |     |    |      |     |    |      |  |
| UP TO 60 HP                                                    | S1 | 2.5 | IB1 | S3 | 1.5  | IB1 | S3 | 0.75 |  |
| 75 HP & OVER                                                   | S1 | 3.5 | IB1 | S3 | 2.5  | IB1 | S3 | 0.75 |  |

NOTES:

1) Thrust restraints required on all high-pressure fan section, suspended axial-flow fans and on floor-mounted axial fans operating at 3.0" S.P. or greater.

END OF SECTION 23 0548

## SECTION 23 0550 - OPERATION AND MAINTENANCE OF HVAC SYSTEMS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. All pertinent sections of Division 21, 22, & 23 Mechanical General Requirements, are part of the work of this Section. Division 01 is part of this and all other sections of these specifications.
  - 1. Division 23 Section "Testing, Adjusting, and Balancing for HVAC".
  - 2. Division 23 Section "Mechanical Requirements" for Training and Instructions to Owner's Representative.

#### 1.2 SCOPE OF WORK

- A. Submission of Operating and Maintenance Manuals complete with balancing reports. (Coordinate with Division 01).
- B. Coordination of work required for system commissioning.
- C. Provide a hard copy and an electronic copy on CD of the O and M manual fully searchable in PDF format.

#### 1.3 SUBMITTALS

- A. Submit product data in accordance with Division 01 and Division 23 Section "Mechanical Requirements". Submit the following:
  - 1. Sample of O and M manual outline.

### PART 2 - PRODUCTS

#### 2.1 O & M MANUALS

- A. The operating and maintenance manuals shall be as follows:
  - 1. Binders shall be red buckram with easy-view metal for size 8-1/2 x 11-inch sheets, with capacity expandable from 2 inches to 3-1/2 inches as required for the project. Construction shall be rivet-through with library corners. No. 12 backbone and lining shall be the same material as the cover. The front cover and backbone shall be foil-stamped in white as follows: (coordinate with Division 01 )

#### OPERATING AND MAINTENANCE MANUAL

FOR THE  
(INSERT PROJECT NAME)  
(INSERT PROJECT COMPLETION YEAR)  
VOLUME No. ( )

VAN BOERUM & FRANK ASSOCIATES, INC.  
MECHANICAL ENGINEER

(INSERT ARCHITECT)

Binders shall be a manufactured by:

We R Memory Makers  
631 North 400 West  
Salt Lake City, Utah 84103  
801-539-5000

### PART 3 - EXECUTION

#### 3.1 OPERATING AND MAINTENANCE MANUALS:

- A. Work under this section shall be performed in concert with the contractor performing the system testing and balancing. Six (6) copies of the manuals shall be furnished to the Architect for distribution to the owner.
- B. The "Start-Up and Operation" section is one of the most important in the manual. Information in this section shall be complete and accurately written and shall be verified with the actual equipment on the job, such as switches, starters, relays, automatic controls, etc. A step-by-step start-up procedure shall be described.
- C. The manuals shall include air and water-balancing reports, system commissioning procedures, start-up tests and reports, equipment and system performance test reports, warranties, and certificates of training given to the owner's representatives.
- D. American Society of Mechanical Engineers (ASME) Stamp shall be required on all items required by code or specified to conform to the ASME Code, and certificates will be included in the O&M manuals.
- E. Form U-1, the manufacturers' data report for pressure vessels, is to be included in the operation and maintenance manuals. National Board Register (NBR) numbers shall be provided where required by code, and included in the manuals.
- F. Underwriters Laboratories (UL) or equivalent ETL labels shall be applied to manufactured equipment represented by a UL classification and/or listing. Included certification in the O&M manuals.

An index sheet typed on AICO Gold-Line indexes shall be provided in the front of the binder.  
The manual shall include the following:

SYSTEM DESCRIPTIONS

START-UP PROCEDURE AND OPERATION OF SYSTEM

MAINTENANCE AND LUBRICATION TABLE

OPERATION AND MAINTENANCE BULLETINS

AUTOMATIC TEMPERATURE CONTROL DESCRIPTION OF OPERATION,  
INTERLOCK AND CONTROL DIAGRAMS, AND CONTROL PANELS.

AIR AND WATER SYSTEM BALANCING REPORTS

EQUIPMENT WARRANTIES AND TRAINING CERTIFICATES

SYSTEM COMMISSIONING REPORTS

EQUIPMENT START-UP CERTIFICATES

END OF SECTION 23 0550

## SECTION 23 0553 - IDENTIFICATION FOR HVAC PIPING AND EQUIPMENT

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Equipment labels.
  - 2. Danger, Warning and Caution signs and labels.
  - 3. Pipe labels.
  - 4. Duct labels.
  - 5. Stencils.
  - 6. Valve tags.
  - 7. Danger tags.
  - 8. Warning tags.
  - 9. Caution tags.
  - 10. Ceiling grid

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Equipment Label Schedule: Include a listing of all equipment to be labeled with the proposed content for each label.
- C. Valve numbering scheme.
- D. Valve Schedules: For each piping system to include in maintenance manuals.

#### 1.4 COORDINATION

- A. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- B. Coordinate installation of identifying devices with locations of access panels and doors.
- C. Install identifying devices before installing acoustical ceilings and similar concealment.

## PART 2 - PRODUCTS

### 2.1 EQUIPMENT LABELS

#### A. Metal Labels for Equipment:

1. Material and Minimum Thickness, predrilled or stamped holes for attachment hardware:
  - a. Brass, 0.032-inch .
2. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
3. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
4. Fasteners: Stainless-steel;
  - a. Rivets or self-tapping screws
5. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

#### B. Plastic Labels for Equipment:

1. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, and having predrilled holes for attachment hardware, 1/16 inch thick.
2. Letter Color:
  - a. Black.
3. Background Color:
  - a. White.
4. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
5. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
6. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
7. Fasteners: Stainless-steel;
  - a. Rivets or self-tapping screws
8. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.

#### C. Label Content: Include equipment's Drawing designation or unique equipment number, Drawing numbers where equipment is indicated (plans, details, and schedules), , plus the Specification Section number and title where equipment is specified. Label shall also include: capacity specified at designed operating conditions, actual capacity as balanced at site operating conditions, and area or zone served.

#### D. Equipment Label Schedule: For each item of equipment to be labeled, on 8-1/2-by-11-inch bond paper. Tabulate equipment identification number and identify Drawing numbers where equipment is indicated (plans, details, and schedules), plus the Specification Section number and title where equipment is specified. Equipment schedule shall be included in operation and maintenance data.

## 2.2 DANGER, WARNING AND CAUTION SIGNS AND LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, having predrilled holes for attachment hardware; 1/16 inch thick.
- B. Danger signs, colors:
  - 1. Letter Color:
    - a. White.
  - 2. Background Color:
    - a. Red.
- C. Warning signs, colors:
  - 1. Letter Color:
    - a. Black.
  - 2. Background Color:
    - a. Orange.
- D. Caution signs, colors:
  - 1. Letter Color:
    - a. Black.
  - 2. Background Color:
    - a. Yellow.
- E. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- F. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- G. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- H. Fasteners: Stainless-steel;
  - 1. Rivets or self-tapping screws
- I. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- J. Label Content: Include caution and warning information, plus emergency notification instructions.

## 2.3 PIPE LABELS

- A. General Requirements for Manufactured Pipe Labels: Preprinted, color-coded, with lettering indicating service, and showing flow direction.
- B. Pretensioned Pipe Labels: Precoiled, semirigid plastic formed to partially cover circumference of pipe and to attach to pipe without fasteners or adhesive.
- C. Self-Adhesive Pipe Labels: Printed plastic with contact-type, permanent-adhesive backing.

- D. Pipe Label Contents: Include identification of piping service using same designations or abbreviations as used on Drawings, pipe size, and an arrow indicating flow direction.
  - 1. Flow-Direction Arrows: Integral with piping system service lettering to accommodate both directions, or as separate unit on each pipe label to indicate flow direction.
  - 2. Lettering Size: At least 1-1/2 inches high.

## 2.4 DUCT LABELS

- A. Material and Thickness: Multilayer, multicolor, plastic labels for mechanical engraving, having predrilled holes for attachment hardware; 1/16 inch thick.
- B. Letter Color:
  - 1. As required per Duct Label Color Schedule
- C. Background Color:
  - 1. As required per Duct Label Color Schedule
- D. Maximum Temperature: Able to withstand temperatures up to 160 deg F.
- E. Minimum Label Size: Length and width vary for required label content, but not less than 2-1/2 by 3/4 inch.
- F. Minimum Letter Size: 1/4 inch for name of units if viewing distance is less than 24 inches, 1/2 inch for viewing distances up to 72 inches, and proportionately larger lettering for greater viewing distances. Include secondary lettering two-thirds to three-fourths the size of principal lettering.
- G. Fasteners: Stainless-steel;
  - 1. Rivets or self-tapping screws
- H. Adhesive: Contact-type permanent adhesive, compatible with label and with substrate.
- I. Duct Label Contents: Include identification of duct service using same designations or abbreviations as used on Drawings, duct size, and an arrow indicating flow direction.
  - 1. Flow-Direction Arrows: Integral with duct system service lettering to accommodate both directions, or as separate unit on each duct label to indicate flow direction.
  - 2. Lettering Size: At least 1-1/2 inches high.

## 2.5 STENCILS

- A. Stencils: Prepared with letter sizes according to ASME A13.1 for piping; minimum letter height of 1-1/4 inches for ducts; and minimum letter height of 3/4 inch for access panel and door labels, equipment labels, and similar operational instructions.
  - 1. Stencil Material:
    - a. Aluminum.
  - 2. Stencil Paint:



- a. Exterior, gloss, alkyd enamel black unless otherwise indicated.
  - b. Paint may be in pressurized spray-can form.
- 3. Identification Paint:
  - a. Exterior, alkyd enamel in colors according to ASME A13.1 unless otherwise indicated.

## 2.6 VALVE TAGS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
  - 1. Tag Material, predrilled or stamped holes for attachment hardware, minimum thickness:
    - a. Brass, 0.051-inch
    - b. At least 1 inch by 3 inch
  - 2. Fasteners: Steel;
    - a. Wire-link or beaded chain; or S-hook
  - 3. Label Content
    - a. Plan Identification
    - b. Normal Position
    - c. Duty
    - d. Areas Served
    - e. Valve Type
- B. Valve Schedules:
  - 1. For each piping system, on 8-1/2-by-11-inch bond paper, tabulate;
    - a. Valve number.
    - b. Piping system.
    - c. System abbreviation (as shown on valve tag).
    - d. Location of valve (room or space).
    - e. Normal-operating position (open, closed, or modulating).
    - f. Variations for identification.
    - g. Mark valves for emergency shutoff and similar special uses.
  - 2. Valve-tag schedule:
    - a. Shall be included in operation and maintenance data.

## 2.7 VALVE TAGS FOR HEATING VALVES, STEAM VALVES, AND LOW PRESSURE SIDE HTW HEAT EXCHANGERS

- A. Valve Tags: Stamped or engraved with 1/4-inch letters for piping system abbreviation and 1/2-inch numbers.
  - 1. Tag Material, predrilled or stamped holes for attachment hardware, minimum thickness:
    - a. Brass, 0.051-inch
    - b. At least 1 inch by 3 inch
  - 2. Fasteners: Steel;

- a. Wire-link or beaded chain; or S-hook
- 3. Label Content
  - a. Plan Identification
  - b. Normal Position
  - c. Duty
  - d. Areas Served
  - e. Valve Type
  - f. Manufacturer
  - g. Size
  - h. Grade
  - i. Pressure-Temperature service rating

## 2.8 DANGER TAGS

- A. Danger Tags: Preprinted or partially preprinted, accident-prevention tags, of plasticized card stock with matte finish suitable for writing.
  - 1. Size:
    - a. 3 by 5-1/4 inches minimum
  - 2. Fasteners:
    - a. Brass grommet and wire.
  - 3. Nomenclature: Large-size primary caption such as "DANGER," and "DO NOT OPERATE."
  - 4. Color: Red background with white lettering.

## 2.9 WARNING TAGS

- A. Warning Tags: Preprinted or partially preprinted, accident-prevention tags, of plasticized card stock with matte finish suitable for writing.
  - 1. Size:
    - a. 3 by 5-1/4 inches minimum
  - 2. Fasteners:
    - a. Brass grommet and wire.
  - 3. Nomenclature: Large-size primary caption such as "WARNING" and "DO NOT OPERATE."
  - 4. Color: Yellow background with black lettering.

## 2.10 CAUTION TAGS

- A. Caution Tags: Preprinted or partially preprinted, accident-prevention tags, of plasticized card stock with matte finish suitable for writing.
  - 1. Size:
    - a. 3 by 5-1/4 inches minimum
  - 2. Fasteners:
    - a. Brass grommet and wire.

3. Nomenclature: Large-size primary caption such as "CAUTION," and "DO NOT OPERATE."
4. Color: Orange background with black lettering.

## 2.11 CEILING GRID

- A. Provide red lettering on the ceiling tile grid of the locations of all fire dampers, smoke dampers and fire/smoke dampers. Size of lettering and verbiage is to conform to IBC and NFPA standards.
- B. Provide valve identification for all HVAC valves located above the ceiling on the ceiling grid below the valve.
- C. Provide VAV box identification for all VAV boxes located above the ceiling on the ceiling grid below the VAV box.

## PART 3 - EXECUTION

### 3.1 PREPARATION

- A. Clean piping and equipment surfaces of substances that could impair bond of identification devices, including dirt, oil, grease, release agents, and incompatible primers, paints, and encapsulants.

### 3.2 EQUIPMENT LABEL INSTALLATION

- A. Install or permanently fasten labels on each major item of mechanical equipment.
- B. Locate equipment labels where accessible and visible.

### 3.3 PIPE LABEL INSTALLATION

- A. Piping Color-Coding: Painting of piping as specified in Division 09 Section "Exterior Painting" & "Interior Painting".
- B. Stenciled Pipe Label Option:
  1. Stenciled labels may be provided instead of manufactured pipe labels, at Installer's option.
  2. Install stenciled pipe labels with painted, color-coded bands or rectangles on each piping system.
    - a. Identification Paint: Use for contrasting background.
    - b. Stencil Paint: Use for pipe marking.

C. Locate pipe labels where piping is exposed or above accessible ceilings in finished spaces; machine rooms; accessible maintenance spaces such as shafts, tunnels, and plenums; and exterior exposed locations as follows:

1. Near each valve and control device.
2. Near each branch connection, excluding short takeoffs for fixtures and terminal units. Where flow pattern is not obvious, mark each pipe at branch.
3. Near penetrations through walls, floors, ceilings, and inaccessible enclosures.
4. At access doors, manholes, and similar access points that permit view of concealed piping.
5. Near major equipment items and other points of origination and termination.
6. Spaced at maximum intervals of 50 feet along each run. Reduce intervals to 25 feet in areas of congested piping and equipment.
7. On piping above removable acoustical ceilings. Omit intermediately spaced labels.

D. Pipe Label Color Schedule:

| MEDIUM IN PIPE                                               | BACKGROUND COLOR | IDENTIFYING LETTERING     | LETTERING COLOR |
|--------------------------------------------------------------|------------------|---------------------------|-----------------|
| COMPRESSED GAS                                               |                  |                           |                 |
| Hydrogen                                                     | Brown            | Hydrogen                  | Black           |
| Natural Gas                                                  | Brown            | Natural Gas               | Yellow          |
| Oxygen                                                       | Brown            | Oxygen                    | Black           |
| VACUUM                                                       |                  |                           |                 |
| Vacuum                                                       | Silver           | Vacuum                    | Black           |
| WATER **NOTE: DIRECTIONAL ARROWS ARE REQUIRED ON HTW PIPING. |                  |                           |                 |
| Boiler Blow-Off                                              | Yellow           | Blow-Off Water            | Black           |
| Chilled Water Supply                                         | Blue             | Chilled Water Supply      | White           |
| Chilled Water Return                                         | Blue             | Chilled Water Return      | White           |
| Condenser Water Supply                                       | Blue             | Cooling Water Supply      | White           |
| Condenser Water Return                                       | Blue             | Cooling Water Return      | Black           |
| Condensate Return                                            | Orange           | Condensate Return         | Black           |
| Cold Water (Potable)                                         | Green            | Domestic Cold Water       | White           |
| Non Potable                                                  | Green            | Unsafe Water              | Black           |
| Domestic Hot Water (Potable)                                 | Green            | Domestic Hot Water        | White           |
| Domestic Hot Water Return                                    | Green            | Domestic Hot Water Return | White           |
| Fire Protection Water                                        | Red              | Fire Protection           | White           |
| Glycol Solution                                              | Purple           | Glycol Solution           | White           |
| Secondary Heating Water Supply                               | Brown            | Heating Water Supply      | White           |

|                                                   |                      |                      |       |
|---------------------------------------------------|----------------------|----------------------|-------|
| Secondary Heating Water Return                    | Brown                | Heating Water Return | White |
| Reverse Osmosis                                   | Green                | Rev. Osmosis Water   | White |
| Softened                                          | Green                | Softened Water       | Black |
| Roof Drain                                        | Green                | Roof Drain           | White |
| System Make-Up                                    | Green                | Make-Up Water        | White |
| Treated Water                                     | Green                | Treated Water        | Black |
| WASTE                                             |                      |                      |       |
| Building Waste                                    | (unpainted) or Black | Waste                | White |
| ALL EQUIPMENT OR PIPING LOCATED OUTSIDE BUILDINGS |                      |                      |       |
| All Equipment or Piping Located Outside Buildings | Brown                | ---                  | ---   |

### 3.4 DUCT LABEL INSTALLATION

- A. Install plastic-laminated duct labels with permanent adhesive on air ducts in the following color codes:
  1. Blue : For cold-air supply ducts.
  2. Yellow : For hot-air supply ducts.
  3. Green : For exhaust-, outside-, relief-, return-, and mixed-air ducts.
  4. ASME A13.1 Colors and Designs: For hazardous material exhaust.
- B. Locate labels near points where ducts enter into concealed spaces and at maximum intervals of 50 feet in each space where ducts are exposed or concealed by removable ceiling system.

### 3.5 VALVE-TAG INSTALLATION (See Drawing Schedules.)

- A. Install tags on valves and control devices in piping systems, except check valves; valves within factory-fabricated equipment units; shutoff valves; faucets; convenience and lawn-watering hose connections; and HVAC terminal devices and similar roughing-in connections of end-use fixtures and units. List tagged valves in a valve schedule.

### 3.6 WARNING-TAG INSTALLATION

- A. Write required message on, and attach warning tags to, equipment and other items where required.

### 3.7 ELECTRICAL SWITCHES AND STARTERS FOR MECHANICAL EQUIPMENT

- A. Label all electrical switches and starters identifying equipment served.

END OF SECTION 23 0553

## SECTION 23 0593 - TESTING, ADJUSTING, AND BALANCING FOR HVAC

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Balancing Air Systems:
    - a. Constant-volume air systems.
    - b. Variable-air-volume systems.
  - 2. Balancing Hydronic Piping Systems:
    - a. Constant-flow hydronic systems.
    - b. Variable-flow hydronic systems.
    - c. Primary-secondary hydronic systems.
  - 3. Balancing Steam Systems.
  - 4. Various HVAC Equipment.
    - a. Heat Exchangers.
    - b. Motors.
    - c. Chillers.
    - d. Cooling Towers.
    - e. Condensing Units.
    - f. Boilers.
    - g. Heat Transfer Coils.
  - 5. Domestic Heater Systems.

#### 1.3 DEFINITIONS

- A. AABC: Associated Air Balance Council.
- B. NEBB: National Environmental Balancing Bureau.
- C. TAB: Testing, adjusting, and balancing.

- D. TABB: Testing, Adjusting, and Balancing Bureau.
- E. TAB Specialist: An entity engaged to perform TAB Work.

#### 1.4 ACTION SUBMITTALS

- A. LEED Submittals:
  - 1. Air-Balance Report for Prerequisite IEQ 1: Documentation of work performed for ASHRAE 62.1, Section 7.2.2 - "Air Balancing."
  - 2. TAB Report for Prerequisite EA 2: Documentation of work performed for ASHRAE/IESNA 90.1, Section 6.7.2.3 - "System Balancing."

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: Within the following number of days of the Contractor's Notice to Proceed, submit documentation that the TAB contractor and this Project's TAB team members meet the qualifications specified in "Quality Assurance" Article;
  - 1. 30 days.
- B. Certified TAB reports.
- C. Instrument calibration reports, to include the following:
  - 1. Instrument type and make.
  - 2. Serial number.
  - 3. Application.
  - 4. Dates of use.
  - 5. Dates of calibration.

#### 1.6 QUALITY ASSURANCE

- A. TAB Contractor Qualifications: Engage a TAB entity certified by AABC or NEBB.
  - 1. TAB Field Supervisor: Employee of the TAB contractor and certified by AABC or NEBB and shall be the same as the TAB Contractor.
  - 2. TAB Technician: Employee of the TAB contractor and who is certified by AABC or NEBB as a TAB technician and shall be the same as the TAB Contractor.
- B. Certify TAB field data reports and perform the following:
  - 1. Review field data reports to validate accuracy of data and to prepare certified TAB reports.
  - 2. Certify that the TAB team complied with the approved TAB plan and the procedures specified and referenced in this Specification.
- C. TAB Report Forms: Use standard TAB contractor's forms approved by:
  - 1. Architect.

- D. Instrumentation Type, Quantity, Accuracy, and Calibration: As described in ASHRAE 111, Section 5, "Instrumentation."
- E. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 7.2.2 - "Air Balancing."
- F. ASHRAE/IESNA Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6.7.2.3 - "System Balancing."

#### 1.7 PROJECT CONDITIONS

- A. Full Owner Occupancy: Owner will occupy the site and existing building during entire TAB period. Cooperate with Owner during TAB operations to minimize conflicts with Owner's operations.

#### 1.8 COORDINATION

- A. Notice: Provide seven days' advance notice for each test. Include scheduled test dates and times.
- B. Perform TAB after leakage and pressure tests on the following distribution systems have been satisfactorily completed:
  - 1. Air and water.

#### PART 2 - PRODUCTS (Not Applicable)

#### PART 3 - EXECUTION

##### 3.1 TAB SPECIALISTS

- A. Subject to compliance with requirements, engage one of the following:
  - 1. BTC Service.
  - 2. Certified Test & Balance.
  - 3. RS Analysis.

##### 3.2 EXAMINATION

- A. Examine the Contract Documents to become familiar with Project requirements and to discover conditions in systems' designs that may preclude proper TAB of systems and equipment.
- B. Examine systems for installed balancing devices, such as test ports, gage cocks, thermometer wells, flow-control devices, balancing valves and fittings, and manual volume dampers. Verify that locations of these balancing devices are accessible.



- C. Examine the approved submittals for HVAC systems and equipment.
- D. Examine design data including HVAC system descriptions, statements of design assumptions for environmental conditions and systems' output, and statements of philosophies and assumptions about HVAC system and equipment controls.
- E. Examine:
  - 1. Ceiling plenums and underfloor air plenums used for supply, return, or relief air to verify that they meet the leakage class of connected ducts as specified in:
    - a. Division 23 Section "Metal Ducts"
  - 2. Verify ceiling plenums and underfloor air plenums used for supply, return or relief air are properly separated from adjacent areas.
  - 3. Verify that penetrations in plenum walls are sealed and fire-stopped if required.
- F. Examine equipment performance data including fan and pump curves.
  - 1. Relate performance data to Project conditions and requirements, including system effects that can create undesired or unpredicted conditions that cause reduced capacities in all or part of a system.
  - 2. Calculate system-effect factors to reduce performance ratings of HVAC equipment when installed under conditions different from the conditions used to rate equipment performance. To calculate system effects for air systems, use tables and charts found in AMCA 201, "Fans and Systems," or in SMACNA's "HVAC Systems - Duct Design." Compare results with the design data and installed conditions.
- G. Examine system and equipment installations and verify that field quality-control testing, cleaning, and adjusting specified in individual Sections have been performed.
- H. Examine test reports specified in individual system and equipment Sections.
- I. Examine HVAC equipment and filters and verify that bearings are greased, belts are aligned and tight, and equipment with functioning controls is ready for operation.
- J. Examine terminal units, such as variable-air-volume boxes, and verify that they are accessible and their controls are connected and functioning.
- K. Examine strainers. Verify that startup screens are replaced by permanent screens with indicated perforations.
- L. Examine three-way valves for proper installation for their intended function of diverting or mixing fluid flows.
- M. Examine heat-transfer coils for correct piping connections and for clean and straight fins.
- N. Examine system pumps to ensure absence of entrained air in the suction piping.
- O. Examine operating safety interlocks and controls on HVAC equipment.

- P. Report deficiencies discovered before and during performance of TAB procedures. Observe and record system reactions to changes in conditions. Record default set points if different from indicated values.

### 3.3 PREPARATION

- A. Prepare a TAB plan that includes strategies and step-by-step procedures.
- B. Complete system-readiness checks and prepare reports. Verify the following:
  - 1. Permanent electrical-power wiring is complete.
  - 2. Hydronic systems are filled, clean, and free of air.
  - 3. Automatic temperature-control systems are operational.
  - 4. Equipment and duct access doors are securely closed.
  - 5. Balance, smoke, and fire dampers are open.
  - 6. Isolating and balancing valves are open and control valves are operational.
  - 7. Ceilings are installed in critical areas where air-pattern adjustments are required and access to balancing devices is provided.
  - 8. Windows and doors can be closed so indicated conditions for system operations can be met.

### 3.4 GENERAL PROCEDURES FOR TESTING AND BALANCING

- A. Perform testing and balancing procedures on each system according to the procedures contained in this section and:
  - 1. AABC's "National Standards for Total System Balance"
  - 2. Comply with requirements in ASHRAE 62.1, Section 7.2.2 - "Air Balancing."
- B. Cut insulation, ducts, pipes, and equipment cabinets for installation of test probes to the minimum extent necessary for TAB procedures.
  - 1. After testing and balancing, patch probe holes in ducts with same material and thickness as used to construct ducts.
  - 2. Install and join new insulation that matches removed materials. Restore insulation, coverings, vapor barrier, and finish according to Division 23 Section "Duct Insulation," Division 23 Section "HVAC Equipment Insulation," and Division 23 Section "HVAC Piping Insulation."
- C. Mark equipment and balancing devices, including damper-control positions, valve position indicators, fan-speed-control levers, and similar controls and devices, with paint or other suitable, permanent identification material to show final settings.
- D. Take and report testing and balancing measurements in inch-pound (IP) .

### 3.5 GENERAL PROCEDURES FOR BALANCING AIR SYSTEMS

- A. Prepare test reports for both fans and outlets. Obtain manufacturer's outlet factors and recommended testing procedures. Crosscheck the summation of required outlet volumes with required fan volumes.
- B. Prepare schematic diagrams of systems' "as-built" duct layouts.
- C. For variable-air-volume systems, develop a plan to simulate diversity.
- D. Determine the best locations in main and branch ducts for accurate duct-airflow measurements.
- E. Check airflow patterns from the outdoor-air louvers and dampers and the return- and exhaust-air dampers through the supply-fan discharge and mixing dampers.
- F. Locate start-stop and disconnect switches, electrical interlocks, and motor starters.
- G. Verify that motor starters are equipped with properly sized thermal protection.
- H. Check dampers for proper position to achieve desired airflow path.
- I. Check for airflow blockages.
- J. Check condensate drains for proper connections and functioning.
- K. Check for proper sealing of air-handling-unit components.
- L. Verify that air duct system is sealed as specified in Division 23 Section "Metal Ducts."

### 3.6 PROCEDURES FOR CONSTANT-VOLUME AIR SYSTEMS

- A. Adjust fans to deliver total indicated airflows within the maximum allowable fan speed listed by fan manufacturer.
  - 1. Measure total airflow.
    - a. Where sufficient space in ducts is unavailable for Pitot-tube traverse measurements, measure airflow at terminal outlets and inlets and calculate the total airflow.
  - 2. Measure fan static pressures as follows to determine actual static pressure:
    - a. Measure outlet static pressure as far downstream from the fan as practical and upstream from restrictions in ducts such as elbows and transitions.
    - b. Measure static pressure directly at the fan outlet or through the flexible connection.
    - c. Measure inlet static pressure of single-inlet fans in the inlet duct as near the fan as possible, upstream from the flexible connection, and downstream from duct restrictions.
    - d. Measure inlet static pressure of double-inlet fans through the wall of the plenum that houses the fan.

3. Measure static pressure across each component that makes up an air-handling unit, rooftop unit, and other air-handling and -treating equipment.
    - a. Report the cleanliness status of filters and the time static pressures are measured.
  4. Measure static pressures entering and leaving other devices, such as sound traps, heat-recovery equipment, and air washers, under final balanced conditions.
  5. Review Record Documents to determine variations in design static pressures versus actual static pressures. Calculate actual system-effect factors. Recommend adjustments to accommodate actual conditions.
  6. Obtain approval from one of the following entities for adjustment of fan speed higher or lower than indicated speed. Comply with requirements in HVAC Sections for air-handling units for adjustment of fans, belts, and pulley sizes to achieve indicated air-handling-unit performance:
    - a. Architect.
  7. Do not make fan-speed adjustments that result in motor overload. Consult equipment manufacturers about fan-speed safety factors. Modulate dampers and measure fan-motor amperage to ensure that no overload will occur. Measure amperage in full-cooling, full-heating, economizer, and any other operating mode to determine the maximum required brake horsepower.
- B. Adjust volume dampers for main duct, submain ducts, and major branch ducts to indicated airflows within specified tolerances.
1. Measure airflow of submain and branch ducts.
    - a. Where sufficient space in submain and branch ducts is unavailable for Pitot-tube traverse measurements, measure airflow at terminal outlets and inlets and calculate the total airflow for that zone.
  2. Measure static pressure at a point downstream from the balancing damper, and adjust volume dampers until the proper static pressure is achieved.
  3. Remeasure each submain and branch duct after all have been adjusted. Continue to adjust submain and branch ducts to indicated airflows within specified tolerances.
- C. Measure air outlets and inlets without making adjustments.
1. Measure terminal outlets using a direct-reading hood or outlet manufacturer's written instructions and calculating factors.
- D. Adjust air outlets and inlets for each space to indicated airflows within specified tolerances of indicated values. Make adjustments using branch volume dampers rather than extractors and the dampers at air terminals.
1. Adjust each outlet in same room or space to within specified tolerances of indicated quantities without generating noise levels above the limitations prescribed by the Contract Documents.
  2. Adjust patterns of adjustable outlets for proper distribution without drafts.

### 3.7 PROCEDURES FOR VARIABLE-AIR-VOLUME SYSTEMS

- A. Compensating for Diversity: When the total airflow of all terminal units is more than the indicated airflow of the fan, place a selected number of terminal units at a minimum set-point airflow with the remainder at maximum-airflow condition until the total airflow of the terminal units equals the indicated airflow of the fan. Select the reduced-airflow terminal units so they are distributed evenly among the branch ducts.
- B. Pressure-Independent, Variable-Air-Volume Systems: After the fan systems have been adjusted, adjust the variable-air-volume systems as follows:
  - 1. Set outdoor-air dampers at minimum, and set return- and exhaust-air dampers at a position that simulates full-cooling load.
  - 2. Select the terminal unit that is most critical to the supply-fan airflow and static pressure. Measure static pressure. Adjust system static pressure so the entering static pressure for the critical terminal unit is not less than the sum of the terminal-unit manufacturer's recommended minimum inlet static pressure plus the static pressure needed to overcome terminal-unit discharge system losses.
  - 3. Measure total system airflow. Adjust to within indicated airflow.
  - 4. Set terminal units at maximum airflow and adjust controller or regulator to deliver the designed maximum airflow. Use terminal-unit manufacturer's written instructions to make this adjustment. When total airflow is correct, balance the air outlets downstream from terminal units the same as described for constant-volume air systems.
  - 5. Set terminal units at minimum airflow and adjust controller or regulator to deliver the designed minimum airflow. Check air outlets for a proportional reduction in airflow the same as described for constant-volume air systems.
    - a. If air outlets are out of balance at minimum airflow, report the condition but leave outlets balanced for maximum airflow.
  - 6. Remeasure the return airflow to the fan while operating at maximum return airflow and minimum outdoor airflow.
  - 7. Measure static pressure at the most critical terminal unit and adjust the static-pressure controller at the main supply-air sensing station to ensure that adequate static pressure is maintained at the most critical unit.
  - 8. Record final fan-performance data.
- C. Pressure-Dependent, Variable-Air-Volume Systems without Diversity: After the fan systems have been adjusted, adjust the variable-air-volume systems as follows:
  - 1. Balance variable-air-volume systems the same as described for constant-volume air systems.
  - 2. Set terminal units and supply fan at full-airflow condition.
  - 3. Adjust inlet dampers of each terminal unit to indicated airflow and verify operation of the static-pressure controller. When total airflow is correct, balance the air outlets downstream from terminal units the same as described for constant-volume air systems.
  - 4. Readjust fan airflow for final maximum readings.

5. Measure operating static pressure at the sensor that controls the supply fan if one is installed, and verify operation of the static-pressure controller.
  6. Set terminal units at minimum airflow and adjust controller or regulator to deliver the designed minimum airflow. Check air outlets for a proportional reduction in airflow the same as described for constant-volume air systems.
    - a. If air outlets are out of balance at minimum airflow, report the condition but leave the outlets balanced for maximum airflow.
  7. Measure the return airflow to the fan while operating at maximum return airflow and minimum outdoor airflow.
- D. Pressure-Dependent, Variable-Air-Volume Systems with Diversity: After the fan systems have been adjusted, adjust the variable-air-volume systems as follows:
1. Set system at maximum indicated airflow by setting the required number of terminal units at minimum airflow. Select the reduced-airflow terminal units so they are distributed evenly among the branch ducts.
  2. Adjust supply fan to maximum indicated airflow with the variable-airflow controller set at maximum airflow.
  3. Set terminal units at full-airflow condition.
  4. Adjust terminal units starting at the supply-fan end of the system and continuing progressively to the end of the system. Adjust inlet dampers of each terminal unit to indicated airflow. When total airflow is correct, balance the air outlets downstream from terminal units the same as described for constant-volume air systems.
  5. Adjust terminal units for minimum airflow.
  6. Measure the return airflow to the fan while operating at maximum return airflow and minimum outdoor airflow. Adjust the fan and balance the return-air ducts and inlets the same as described for constant-volume air systems.

### 3.8 GENERAL PROCEDURES FOR HYDRONIC SYSTEMS

- A. Prepare test reports with pertinent design data, and number in sequence starting at pump to end of system. Check the sum of branch-circuit flows against the approved pump flow rate. Correct variations that exceed plus or minus 5 percent.
- B. Prepare schematic diagrams of systems' "as-built" piping layouts.
- C. Prepare hydronic systems for testing and balancing according to the following, in addition to the general preparation procedures specified above:
  1. Open all manual valves for maximum flow.
  2. Check liquid level in expansion tank.
  3. Check makeup water-station pressure gage for adequate pressure for highest vent.
  4. Check flow-control valves for specified sequence of operation, and set at indicated flow.
  5. Set differential-pressure control valves at the specified differential pressure. Do not set at fully closed position when pump is positive-displacement type unless several terminal valves are kept open.

6. Set system controls so automatic valves are wide open to heat exchangers.
7. Check pump-motor load. If motor is overloaded, throttle main flow-balancing device so motor nameplate rating is not exceeded.
8. Check air vents for a forceful liquid flow exiting from vents when manually operated.

### 3.9 PROCEDURES FOR CONSTANT-FLOW HYDRONIC SYSTEMS

- A. Measure water flow at pumps. Use the following procedures except for positive-displacement pumps:
  1. Verify impeller size by operating the pump with the discharge valve closed. Read pressure differential across the pump. Convert pressure to head and correct for differences in gage heights. Note the point on manufacturer's pump curve at zero flow and verify that the pump has the intended impeller size.
    - a. If impeller sizes must be adjusted to achieve pump performance, obtain approval from the following entity and comply with requirements in Division 23 Section "Hydronic Pumps.":
      - 1) Architect.
  2. Check system resistance. With all valves open, read pressure differential across the pump and mark pump manufacturer's head-capacity curve. Adjust pump discharge valve until indicated water flow is achieved.
    - a. Monitor motor performance during procedures and do not operate motors in overload conditions.
  3. Verify pump-motor brake horsepower. Calculate the intended brake horsepower for the system based on pump manufacturer's performance data. Compare calculated brake horsepower with nameplate data on the pump motor. Report conditions where actual amperage exceeds motor nameplate amperage.
  4. Report flow rates that are not within plus or minus 10 percent of design.
- B. Measure flow at all automatic flow control valves to verify that valves are functioning as designed.
- C. Measure flow at all pressure-independent characterized control valves, with valves in fully open position, to verify that valves are functioning as designed.
- D. Set calibrated balancing valves, if installed, at calculated presettings.
- E. Measure flow at all stations and adjust, where necessary, to obtain first balance.
  1. System components that have Cv rating or an accurately cataloged flow-pressure-drop relationship may be used as a flow-indicating device.
- F. Measure flow at main balancing station and set main balancing device to achieve flow that is 5 percent greater than indicated flow.

- G. Adjust balancing stations to within specified tolerances of indicated flow rate as follows:
  - 1. Determine the balancing station with the highest percentage over indicated flow.
  - 2. Adjust each station in turn, beginning with the station with the highest percentage over indicated flow and proceeding to the station with the lowest percentage over indicated flow.
  - 3. Record settings and mark balancing devices.
- H. Measure pump flow rate and make final measurements of pump amperage, voltage, rpm, pump heads, and systems' pressures and temperatures including outdoor-air temperature.
- I. Measure the differential-pressure-control-valve settings existing at the conclusion of balancing.
- J. Check settings and operation of each safety valve. Record settings.

### 3.10 PROCEDURES FOR VARIABLE-FLOW HYDRONIC SYSTEMS

- A. Balance systems with automatic two- and three-way control valves by setting systems at maximum flow through heat-exchange terminals and proceed as specified above for hydronic systems.

### 3.11 PROCEDURES FOR PRIMARY-SECONDARY HYDRONIC SYSTEMS

- A. Balance the primary circuit flow first and then balance the secondary circuits.

### 3.12 PROCEDURES FOR MOTORS

- A. Motors, 1/2 HP and Larger: Test at final balanced conditions and record the following data:
  - 1. Manufacturer's name, model number, and serial number.
  - 2. Motor horsepower rating.
  - 3. Motor rpm.
  - 4. Efficiency rating.
  - 5. Motor balanced frequency and the date & time it was balanced.
  - 6. Drive kW.
  - 7. Drive torque.
  - 8. Nameplate and measured voltage, each phase.
  - 9. Nameplate and measured amperage, each phase.
  - 10. Starter thermal-protection-element rating.
- B. Motors Driven by Variable-Frequency Controllers: Test for proper operation at speeds varying from minimum to maximum. Test the manual bypass of the controller to prove proper operation. Record observations including name of controller manufacturer, model number, serial number, and nameplate data.



### 3.13 PROCEDURES FOR HEAT-TRANSFER COILS

- A. Measure, adjust, and record the following data for each water coil:
  - 1. Entering- and leaving-water temperature.
  - 2. Water flow rate.
  - 3. Water pressure drop.
  - 4. Dry-bulb temperature of entering and leaving air.
  - 5. Wet-bulb temperature of entering and leaving air for cooling coils.
  - 6. Airflow.
  - 7. Air pressure drop.
- B. Measure, adjust, and record the following data for each electric heating coil:
  - 1. Nameplate data.
  - 2. Airflow.
  - 3. Entering- and leaving-air temperature at full load.
  - 4. Voltage and amperage input of each phase at full load and at each incremental stage.
  - 5. Calculated kilowatt at full load.
  - 6. Fuse or circuit-breaker rating for overload protection.
- C. Measure, adjust, and record the following data for each steam coil:
  - 1. Dry-bulb temperature of entering and leaving air.
  - 2. Airflow.
  - 3. Air pressure drop.
  - 4. Inlet steam pressure.
- D. Measure, adjust, and record the following data for each refrigerant coil:
  - 1. Dry-bulb temperature of entering and leaving air.
  - 2. Wet-bulb temperature of entering and leaving air.
  - 3. Airflow.
  - 4. Air pressure drop.
  - 5. Refrigerant suction pressure and temperature.

### 3.14 DOMESTIC HEATER SYSTEMS

- A. Test domestic heater system per Engineer's instructions.

### 3.15 TOLERANCES

- A. Set HVAC system's air flow rates and water flow rates within the following tolerances:
  - 1. Supply, Return, and Exhaust Fans and Equipment with Fans: Plus or minus 10 percent.
  - 2. Air Outlets and Inlets: Plus or minus 10 percent.
  - 3. Heating-Water Flow Rate: Plus or minus 10 percent.

4. Cooling-Water Flow Rate: Plus or minus 10 percent.

### 3.16 REPORTING

- A. Initial Construction-Phase Report: Based on examination of the Contract Documents as specified in "Examination" Article, prepare a report on the adequacy of design for systems' balancing devices. Recommend changes and additions to systems' balancing devices to facilitate proper performance measuring and balancing. Recommend changes and additions to HVAC systems and general construction to allow access for performance measuring and balancing devices.
- B. Status Reports: Prepare progress reports on the following interval to describe completed procedures, procedures in progress, and scheduled procedures. Include a list of deficiencies and problems found in systems being tested and balanced. Prepare a separate report for each system and each building floor for systems serving multiple floors;
  1. Weekly.

### 3.17 FINAL REPORT

- A. General: Prepare a certified written report; tabulate and divide the report into separate sections for tested systems and balanced systems.
  1. Include a certification sheet at the front of the report's binder, signed and sealed by the certified testing and balancing engineer.
  2. Include a list of instruments used for procedures, along with proof of calibration.
- B. Final Report Contents: In addition to certified field-report data, include the following:
  1. Pump curves.
  2. Fan curves.
  3. Manufacturers' test data.
  4. Field test reports prepared by system and equipment installers.
  5. Other information relative to equipment performance; do not include Shop Drawings and product data.
- C. General Report Data: In addition to form titles and entries, include the following data:
  1. Title page.
  2. Name and address of the TAB contractor.
  3. Project name.
  4. Project location.
  5. Architect's name and address.
  6. Engineer's name and address.
  7. Contractor's name and address.
  8. Report date.
  9. Signature of TAB supervisor who certifies the report.
  10. Table of Contents with the total number of pages defined for each section of the report. Number each page in the report.

11. Summary of contents including the following:
    - a. Indicated versus final performance.
    - b. Notable characteristics of systems.
    - c. Description of system operation sequence if it varies from the Contract Documents.
  12. Nomenclature sheets for each item of equipment.
  13. Data for terminal units, including manufacturer's name, type, size, and fittings.
  14. Notes to explain why certain final data in the body of reports vary from indicated values.
  15. Test conditions for fans and pump performance forms including the following:
    - a. Settings for outdoor-, return-, and exhaust-air dampers.
    - b. Conditions of filters.
    - c. Cooling coil, wet- and dry-bulb conditions.
    - d. Face and bypass damper settings at coils.
    - e. Fan drive settings including settings and percentage of maximum pitch diameter.
    - f. Inlet vane settings for variable-air-volume systems.
    - g. Settings for supply-air, static-pressure controller.
    - h. Other system operating conditions that affect performance.
- D. System Diagrams: Include schematic layouts of air and hydronic distribution systems. Present each system with single-line diagram and include the following:
1. Quantities of outdoor, supply, return, and exhaust airflows.
  2. Water and steam flow rates.
  3. Duct, outlet, and inlet sizes.
  4. Pipe and valve sizes and locations.
  5. Terminal units.
  6. Balancing stations.
  7. Position of balancing devices.
- E. Air-Handling-Unit Test Reports: For air-handling units with coils, include the following:
1. Unit Data:
    - a. Unit identification.
    - b. Location.
    - c. Make and type.
    - d. Model number and unit size.
    - e. Manufacturer's serial number.
    - f. Unit arrangement and class.
    - g. Discharge arrangement.
    - h. Sheave make, size in inches, and bore.
    - i. Center-to-center dimensions of sheave, and amount of adjustments in inches.
    - j. Number, make, and size of belts.
    - k. Number, type, and size of filters.
  2. Motor Data:

- a. Motor make, and frame type and size.
- b. Horsepower and rpm.
- c. Volts, phase, and hertz.
- d. Full-load amperage and service factor.
- e. Sheave make, size in inches, and bore.
- f. Center-to-center dimensions of sheave, and amount of adjustments in inches.

3. Test Data (Indicated and Actual Values):

- a. Total air flow rate in cfm.
- b. Total system static pressure in inches wg.
- c. Fan rpm.
- d. Discharge static pressure in inches wg.
- e. Filter static-pressure differential in inches wg.
- f. Preheat-coil static-pressure differential in inches wg.
- g. Cooling-coil static-pressure differential in inches wg.
- h. Heating-coil static-pressure differential in inches wg.
- i. Outdoor airflow in cfm.
- j. Return airflow in cfm.
- k. Outdoor-air damper position.
- l. Return-air damper position.
- m. Vortex damper position.

F. Apparatus-Coil Test Reports:

1. Coil Data:

- a. System identification.
- b. Location.
- c. Coil type.
- d. Number of rows.
- e. Fin spacing in fins per inch o.c.
- f. Make and model number.
- g. Face area in sq. ft..
- h. Tube size in NPS.
- i. Tube and fin materials.
- j. Circuiting arrangement.

2. Test Data (Indicated and Actual Values):

- a. Air flow rate in cfm.
- b. Average face velocity in fpm.
- c. Air pressure drop in inches wg.
- d. Outdoor-air, wet- and dry-bulb temperatures in deg F.
- e. Return-air, wet- and dry-bulb temperatures in deg F.
- f. Entering-air, wet- and dry-bulb temperatures in deg F.
- g. Leaving-air, wet- and dry-bulb temperatures in deg F.
- h. Water flow rate in gpm.
- i. Water pressure differential in feet of head or psig.
- j. Entering-water temperature in deg F.

- k. Leaving-water temperature in deg F.
- l. Refrigerant expansion valve and refrigerant types.
- m. Refrigerant suction pressure in psig.
- n. Refrigerant suction temperature in deg F.
- o. Inlet steam pressure in psig.

3. Test Data (Indicated and Actual Values):

- a. Total air flow rate in cfm.
- b. Entering-air temperature in deg F.
- c. Leaving-air temperature in deg F.
- d. Air temperature differential in deg F.
- e. Entering-air static pressure in inches wg.
- f. Leaving-air static pressure in inches wg.
- g. Air static-pressure differential in inches wg.
- h. Low-fire fuel input in Btu/h.
- i. High-fire fuel input in Btu/h.
- j. Manifold pressure in psig.
- k. High-temperature-limit setting in deg F.
- l. Operating set point in Btu/h.
- m. Motor voltage at each connection.
- n. Motor amperage for each phase.
- o. Heating value of fuel in Btu/h.

G. Fan Test Reports: For supply, return, and exhaust fans, include the following:

1. Fan Data:

- a. System identification.
- b. Location.
- c. Make and type.
- d. Model number and size.
- e. Manufacturer's serial number.
- f. Arrangement and class.
- g. Sheave make, size in inches, and bore.
- h. Center-to-center dimensions of sheave, and amount of adjustments in inches.

2. Motor Data:

- a. Motor make, and frame type and size.
- b. Horsepower and rpm.
- c. Volts, phase, and hertz.
- d. Full-load amperage and service factor.
- e. Sheave make, size in inches, and bore.
- f. Center-to-center dimensions of sheave, and amount of adjustments in inches.
- g. Number, make, and size of belts.

3. Test Data (Indicated and Actual Values):

- a. Total airflow rate in cfm.

- b. Total system static pressure in inches wg.
  - c. Fan rpm.
  - d. Discharge static pressure in inches wg.
  - e. Suction static pressure in inches wg.
- H. Round, Flat-Oval, and Rectangular Duct Traverse Reports: Include a diagram with a grid representing the duct cross-section and record the following:
  - 1. Report Data:
    - a. System and air-handling-unit number.
    - b. Location and zone.
    - c. Traverse air temperature in deg F.
    - d. Duct static pressure in inches wg.
    - e. Duct size in inches.
    - f. Duct area in sq. ft..
    - g. Indicated air flow rate in cfm.
    - h. Indicated velocity in fpm.
    - i. Actual air flow rate in cfm.
    - j. Actual average velocity in fpm.
    - k. Barometric pressure in psig.
- I. Air-Terminal-Device Reports:
  - 1. Unit Data:
    - a. System and air-handling unit identification.
    - b. Location and zone.
    - c. Apparatus used for test.
    - d. Area served.
    - e. Make.
    - f. Number from system diagram.
    - g. Type and model number.
    - h. Size.
    - i. Effective area in sq. ft..
  - 2. Test Data (Indicated and Actual Values):
    - a. Air flow rate in cfm.
    - b. Air velocity in fpm.
    - c. Preliminary air flow rate as needed in cfm.
    - d. Preliminary velocity as needed in fpm.
    - e. Final air flow rate in cfm.
    - f. Final velocity in fpm.
    - g. Space temperature in deg F.
- J. System-Coil Reports: For reheat coils and water coils of terminal units, include the following:
  - 1. Unit Data:

- a. System and air-handling-unit identification.
- b. Location and zone.
- c. Room or riser served.
- d. Coil make and size.
- e. Flowmeter type.

2. Test Data (Indicated and Actual Values):

- a. Air flow rate in cfm.
- b. Entering-water temperature in deg F.
- c. Leaving-water temperature in deg F.
- d. Water pressure drop in feet of head or psig.
- e. Entering-air temperature in deg F.
- f. Leaving-air temperature in deg F.

K. Pump Test Reports: Calculate impeller size by plotting the shutoff head on pump curves and include the following:

1. Unit Data:

- a. Unit identification.
- b. Location.
- c. Service.
- d. Make and size.
- e. Model number and serial number.
- f. Water flow rate in gpm.
- g. Water pressure differential in feet of head or psig.
- h. Required net positive suction head in feet of head or psig.
- i. Pump rpm.
- j. Impeller diameter in inches.
- k. Motor make and frame size.
- l. Motor horsepower and rpm.
- m. Voltage at each connection.
- n. Amperage for each phase.
- o. Full-load amperage and service factor.
- p. Seal type.

2. Test Data (Indicated and Actual Values):

- a. Static head in feet of head or psig.
- b. Pump shutoff pressure in feet of head or psig.
- c. Actual impeller size in inches.
- d. Full-open flow rate in gpm.
- e. Full-open pressure in feet of head or psig.
- f. Final discharge pressure in feet of head or psig.
- g. Final suction pressure in feet of head or psig.
- h. Final total pressure in feet of head or psig.
- i. Final water flow rate in gpm.
- j. Voltage at each connection.
- k. Amperage for each phase.

L. Instrument Calibration Reports:

1. Report Data:
  - a. Instrument type and make.
  - b. Serial number.
  - c. Application.
  - d. Dates of use.
  - e. Dates of calibration.

3.18 INSPECTIONS

A. Initial Inspection:

1. After testing and balancing are complete, operate each system and randomly check measurements to verify that the system is operating according to the final test and balance readings documented in the final report.
2. Check the following for each system:
  - a. Measure airflow of at least 10 percent of air outlets.
  - b. Measure water flow of at least 5 percent of terminals.
  - c. Measure room temperature at each thermostat/temperature sensor. Compare the reading to the set point.
  - d. Verify that balancing devices are marked with final balance position.
  - e. Note deviations from the Contract Documents in the final report.

B. Final Inspection:

1. After initial inspection is complete and documentation by random checks verifies that testing and balancing are complete and accurately documented in the final report, request that a final inspection be made by:
  - a. Architect.
2. The TAB contractor's test and balance engineer shall conduct the inspection in the presence of:
  - a. Architect.
3. The following entity shall randomly select measurements, documented in the final report, to be rechecked. Rechecking shall be limited to either 10 percent of the total measurements recorded or the extent of measurements that can be accomplished in a normal 8-hour business day:
  - a. Architect.
4. If rechecks yield measurements that differ from the measurements documented in the final report by more than the tolerances allowed, the measurements shall be noted as "FAILED."
5. If the number of "FAILED" measurements is greater than 10 percent of the total measurements checked during the final inspection, the testing and balancing shall be considered incomplete and shall be rejected.

C. TAB Work will be considered defective if it does not pass final inspections. If TAB Work fails, proceed as follows:



1. Recheck all measurements and make adjustments. Revise the final report and balancing device settings to include all changes; resubmit the final report and request a second final inspection.
  2. If the second final inspection also fails, Owner may contract the services of another TAB contractor to complete TAB Work according to the Contract Documents and deduct the cost of the services from the original TAB contractor's final payment.
- D. Prepare test and inspection reports.

3.19 ADDITIONAL TESTS

- A. Within 90 days of completing TAB, perform additional TAB to verify that balanced conditions are being maintained throughout and to correct unusual conditions.
- B. Seasonal Periods: If initial TAB procedures were not performed during near-peak summer and winter conditions, perform additional TAB during near-peak summer and winter conditions.

END OF SECTION 23 0593

## SECTION 23 0713 - DUCT INSULATION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes insulating the following duct services:
  - 1. Indoor, concealed supply and outdoor air.
  - 2. Indoor, exposed supply and outdoor air.
  - 3. Indoor, concealed return located in unconditioned space.
  - 4. Indoor, exposed return located in unconditioned space.
  - 5. Outdoor, concealed supply and return.
  - 6. Outdoor, exposed supply and return.
- B. Related Sections:
  - 1. Division 23 Section "HVAC Equipment Insulation."
  - 2. Division 23 Section "HVAC Piping Insulation."
  - 3. Division 23 Section "Metal Ducts" for duct liners.
  - 4. Division 23 Section "Hangers and Supports for HVAC Piping and Equipment."

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory- and field-applied if any).
- B. LEED Submittals:
  - 1. Product Data for Credit IEQ 4.1: For adhesives and sealants, documentation including printed statement of VOC content.
  - 2. Laboratory Test Reports for Credit IEQ 4: For adhesives and sealants, documentation indicating that products comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- C. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.
  - 1. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.

2. Detail insulation application at elbows, fittings, dampers, specialties and flanges for each type of insulation.
3. Detail application of field-applied jackets.
4. Detail application at linkages of control devices.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.
- C. Field quality-control reports.

#### 1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
  1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
  2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

#### 1.6 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

#### 1.7 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Division 23 Section "Hangers and Supports for HVAC Piping and Equipment."
- B. Coordinate clearance requirements with duct Installer for duct insulation application. Before preparing ductwork Shop Drawings, establish and maintain clearance requirements for installation of insulation and field-applied jackets and finishes and for space required for maintenance.

- C. Coordinate installation and testing of heat tracing.

## 1.8 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

## PART 2 - PRODUCTS

### 2.1 INSULATION MATERIALS

- A. Comply with requirements in "Duct Insulation Schedule, General," "Indoor Duct and Plenum Insulation Schedule," and "Aboveground, Outdoor Duct and Plenum Insulation Schedule" articles for where insulating materials shall be applied.
- B. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- C. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- D. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- E. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- F. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type II for sheet materials.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Aeroflex USA, Inc.; Aerocel.
    - b. Armacell LLC; AP Armaflex.
    - c. K-Flex USA; Insul-Sheet, K-Flex Gray Duct Liner, and K-FLEX LS.
- G. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553, Type II and ASTM C 1290, Type III with factory-applied FSK jacket. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. CertainTeed Corp.; SoftTouch Duct Wrap.
    - b. Johns Manville; Microlite.
    - c. Knauf Insulation; Friendly Feel Duct Wrap.

- d. Manson Insulation Inc.; Alley Wrap.
  - e. Owens Corning; SOFTR All-Service Duct Wrap.
- H. Mineral-Fiber Board Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 612, Type IA or Type IB. For duct and plenum applications, provide insulation with factory-applied ASJ. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. CertainTeed Corp.; Commercial Board.
    - b. Fibrex Insulations Inc.; FBX.
    - c. Johns Manville; 800 Series Spin-Glas.
    - d. Knauf Insulation; Insulation Board.
    - e. Manson Insulation Inc.; AK Board.
    - f. Owens Corning; Fiberglas 700 Series.
- I. Polyolefin: Unicellular, polyethylene thermal plastic insulation. Comply with ASTM C 534 or ASTM C 1427, Type I, Grade 1 for tubular materials and Type II, Grade 1 for sheet materials.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Armacell LLC; Tubolit.
    - b. Nomaco Insulation; IMCOLOCK, IMCOSHEET, NOMALOCK, and NOMAPLY.

## 2.2 FIRE-RATED INSULATION SYSTEMS

- A. Fire-Rated Board: Structural-grade, press-molded, xonolite calcium silicate, fireproofing board suitable for operating temperatures up to 1700 deg F. Comply with ASTM C 656, Type II, Grade 6. Tested and certified to provide a:
  - a. 2-hour fire rating by an NRTL acceptable to authorities having jurisdiction
  - 1. Products: Subject to compliance with requirements, provide the following :
    - a. Johns Manville; Super Firetemp M.
- B. Fire-Rated Blanket: High-temperature, flexible, blanket insulation with FSK jacket that is tested and certified to provide a:
  - a. 2-hour fire rating by an NRTL acceptable to authorities
  - 1. Products: Subject to compliance with requirements, provide one of the following :
    - a. CertainTeed Corp.; FlameChek.
    - b. Johns Manville; Firetemp Wrap.
    - c. Nelson Fire Stop Products; Nelson FSB Flameshield Blanket.
    - d. Thermal Ceramics; FireMaster Duct Wrap.
    - e. 3M; Fire Barrier Wrap Products.

- f. Unifrax Corporation; FyreWrap.

## 2.3 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.
- B. Flexible Elastomeric and Polyolefin Adhesive: Comply with MIL-A-24179A, Type II, Class I.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Aeroflex USA, Inc.; AeroSeal.
    - b. Armacell LLC; Armaflex 520 Adhesive.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-75.
    - d. K-Flex USA; R-373 Contact Adhesive.
  - 2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- C. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-127.
    - b. Eagle Bridges - Marathon Industries; 225.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-60/85-70.
    - d. Mon-Eco Industries, Inc.; 22-25.
  - 2. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- D. FSK Jacket Adhesive, and ASJ Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-82.
    - b. Eagle Bridges - Marathon Industries; 225.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-50.
    - d. Mon-Eco Industries, Inc.; 22-25.
  - 2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

## 2.4 MASTICS

- A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.
  - 1. For indoor applications, use mastics that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below ambient services.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 30-80/30-90.
    - b. Vimasco Corporation; 749.
  - 2. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm at 43-mil dry film thickness.
  - 3. Service Temperature Range: Minus 20 to plus 180 deg F.
  - 4. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
  - 5. Color: White.
- C. Breather Mastic: Water based; suitable for indoor and outdoor use on above ambient services.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-10.
    - b. Eagle Bridges - Marathon Industries; 550.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 46-50.
    - d. Mon-Eco Industries, Inc.; 55-50.
    - e. Vimasco Corporation; WC-1/WC-5.
  - 2. Water-Vapor Permeance: ASTM F 1249, 1.8 perms at 0.0625-inch dry film thickness.
  - 3. Service Temperature Range: Minus 20 to plus 180 deg F.
  - 4. Solids Content: 60 percent by volume and 66 percent by weight.
  - 5. Color: White.

## 2.5 LAGGING ADHESIVES

- A. Description: Comply with MIL-A-3316C, Class I, Grade A and shall be compatible with insulation materials, jackets, and substrates.
  - 1. For indoor applications, use lagging adhesives that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 2. Products: Subject to compliance with requirements, provide one of the following:

- a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-50 AHV2.
  - b. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 30-36.
  - c. Vimasco Corporation; 713 and 714.
3. Fire-resistant, water-based lagging adhesive and coating for use indoors to adhere fire-resistant lagging cloths over duct insulation.
  4. Service Temperature Range: 0 to plus 180 deg F.
  5. Color: White.

## 2.6 SEALANTS

### A. FSK and Metal Jacket Flashing Sealants:

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-76.
  - b. Eagle Bridges - Marathon Industries; 405.
  - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 95-44.
  - d. Mon-Eco Industries, Inc.; 44-05.
2. Materials shall be compatible with insulation materials, jackets, and substrates.
3. Fire- and water-resistant, flexible, elastomeric sealant.
4. Service Temperature Range: Minus 40 to plus 250 deg F.
5. Color: Aluminum.
6. For indoor applications, sealants shall have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).

## 2.7 FACTORY-APPLIED JACKETS

- ### A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:
1. FSK Jacket: Aluminum-foil, fiberglass-reinforced scrim with kraft-paper backing; complying with ASTM C 1136, Type II.

## 2.8 FIELD-APPLIED JACKETS

- ### A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.
- ### B. FSK Jacket: Aluminum-foil-face, fiberglass-reinforced scrim with kraft-paper backing.
- ### C. Metal Jacket:



1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; Metal Jacketing Systems.
  - b. ITW Insulation Systems; Aluminum and Stainless Steel Jacketing.
  - c. RPR Products, Inc.; Insul-Mate.
2. Aluminum Jacket: Comply with ASTM B 209, Alloy 3003, 3005, 3105, or 5005, Temper H-14.
  - a. Sheet and roll stock ready for shop or field sizing
  - b. Finish and thickness are indicated in field-applied jacket schedules.
  - c. Moisture Barrier for Indoor Applications: 3-mil-thick, heat-bonded polyethylene and kraft paper.
  - d. Moisture Barrier for Outdoor Applications: 3-mil-thick, heat-bonded polyethylene and kraft.

## 2.9 TAPES

- A. FSK Tape: Foil-face, vapor-retarder tape matching factory-applied jacket with acrylic adhesive; complying with ASTM C 1136.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. ABI, Ideal Tape Division; 491 AWF FSK.
  - b. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0827.
  - c. Compac Corporation; 110 and 111.
  - d. Venture Tape; 1525 CW NT, 1528 CW, and 1528 CW/SQ.
2. Width: 3 inches.
3. Thickness: 6.5 mils.
4. Adhesion: 90 ounces force/inch in width.
5. Elongation: 2 percent.
6. Tensile Strength: 40 lbf/inch in width.
7. FSK Tape Disks and Squares: Precut disks or squares of FSK tape.

- B. Aluminum-Foil Tape: Vapor-retarder tape with acrylic adhesive.

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. ABI, Ideal Tape Division; 488 AWF.
  - b. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0800.
  - c. Compac Corporation; 120.
  - d. Venture Tape; 3520 CW.
2. Width: 2 inches.
3. Thickness: 3.7 mils.
4. Adhesion: 100 ounces force/inch in width.
5. Elongation: 5 percent.

6. Tensile Strength: 34 lbf/inch in width.

## 2.10 SECUREMENTS

### A. Bands:

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. ITW Insulation Systems; Gerrard Strapping and Seals.
  - b. RPR Products, Inc.; Insul-Mate Strapping, Seals, and Springs.
2. Aluminum: ASTM B 209, Alloy 3003, 3005, 3105, or 5005; Temper H-14, 0.020 inch thick, 3/4 inch wide with wing seal.
3. Springs: Twin spring set constructed of stainless steel with ends flat and slotted to accept metal bands. Spring size determined by manufacturer for application.

### B. Insulation Pins and Hangers:

1. Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.135-inch-diameter shank, length to suit depth of insulation indicated.
  - a. Products: Subject to compliance with requirements, provide one of the following:
    - 1) AGM Industries, Inc.; CWP-1.
    - 2) GEMCO; CD.
    - 3) Midwest Fasteners, Inc.; CD.
    - 4) Nelson Stud Welding; TPA, TPC, and TPS.
2. Cupped-Head, Capacitor-Discharge-Weld Pins: Copper- or zinc-coated steel pin, fully annealed for capacitor-discharge welding, 0.135-inch- diameter shank, length to suit depth of insulation indicated with integral 1 to 1-1/2-inch galvanized carbon-steel washer.
  - a. Products: Subject to compliance with requirements, provide one of the following:
    - 1) AGM Industries, Inc.; CHP-1.
    - 2) GEMCO; Cupped Head Weld Pin.
    - 3) Midwest Fasteners, Inc.; Cupped Head.
    - 4) Nelson Stud Welding; CHP.
3. Metal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
  - a. Products: Subject to compliance with requirements, provide one of the following:
    - 1) AGM Industries, Inc.; Tactoo Perforated Base Insul-Hangers.
    - 2) GEMCO; Perforated Base.
    - 3) Midwest Fasteners, Inc.; Spindle.

- b. Baseplate: Perforated, galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
  - c. Spindle: Copper- or zinc-coated, low-carbon steel fully annealed, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
  - d. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
- 4. Nonmetal, Adhesively Attached, Perforated-Base Insulation Hangers: Baseplate fastened to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
  - a. Products: Subject to compliance with requirements, provide one of the following:
    - 1) GEMCO; Nylon Hangers.
    - 2) Midwest Fasteners, Inc.; Nylon Insulation Hangers.
  - b. Baseplate: Perforated, nylon sheet, 0.030 inch thick by 1-1/2 inches in diameter.
  - c. Spindle: Nylon, 0.106-inch- diameter shank, length to suit depth of insulation indicated, up to 2-1/2 inches.
  - d. Adhesive: Recommended by hanger manufacturer. Product with demonstrated capability to bond insulation hanger securely to substrates indicated without damaging insulation, hangers, and substrates.
- 5. Self-Sticking-Base Insulation Hangers: Baseplate welded to projecting spindle that is capable of holding insulation, of thickness indicated, securely in position indicated when self-locking washer is in place. Comply with the following requirements:
  - a. Products: Subject to compliance with requirements, provide one of the following:
    - 1) AGM Industries, Inc.; Tactoo Self-Adhering Insul-Hangers.
    - 2) GEMCO; Peel & Press.
    - 3) Midwest Fasteners, Inc.; Self Stick.
  - b. Baseplate: Galvanized carbon-steel sheet, 0.030 inch thick by 2 inches square.
  - c. Spindle: Copper- or zinc-coated, low-carbon steel, fully annealed, 0.106-inch-diameter shank, length to suit depth of insulation indicated.
  - d. Adhesive-backed base with a peel-off protective cover.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
  - 1. Verify that systems to be insulated have been tested and are free of defects.

2. Verify that surfaces to be insulated are clean and dry.

- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.

### 3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of ducts and fittings.
- B. Install insulation materials, vapor barriers or retarders, jackets, and thicknesses required for each item of duct system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.
- F. Keep insulation materials dry during application and finishing.
- G. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- H. Install insulation with least number of joints practical.
- I. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  1. Install insulation continuously through hangers and around anchor attachments.
  2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
- J. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- K. Install insulation with factory-applied jackets as follows:
  1. Draw jacket tight and smooth.

2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
  3. Overlap jacket longitudinal seams at least 1-1/2 inches. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at:
    - a. 2 inche o.c.
    - b. For below ambient services, apply vapor-barrier mastic over staples.
  4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to duct flanges and fittings.
- L. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- M. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.
- N. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.

### 3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
1. Seal penetrations with flashing sealant.
  2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
  4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
1. Seal penetrations with flashing sealant.
  2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
  4. Seal jacket to wall flashing with flashing sealant.

- C. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated):  
Install insulation continuously through walls and partitions.
- D. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Terminate insulation at fire damper sleeves for fire-rated wall and partition penetrations. Externally insulate damper sleeves to match adjacent insulation and overlap duct insulation at least 2 inches.
  - 1. Comply with requirements in Section 078413 "Penetration Firestopping" firestopping and fire-resistive joint sealers.
- E. Insulation Installation at Floor Penetrations:
  - 1. Duct: For penetrations through fire-rated assemblies, terminate insulation at fire damper sleeves and externally insulate damper sleeve beyond floor to match adjacent duct insulation. Overlap damper sleeve and duct insulation at least 2 inches.
  - 2. Seal penetrations through fire-rated assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

### 3.5 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

- A. Seal longitudinal seams and end joints with manufacturers recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

### 3.6 INSTALLATION OF MINERAL-FIBER INSULATION

- A. Blanket Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
  - 1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for:
    - a. 100 percent coverage of duct and plenum surfaces.
  - 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
  - 3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
    - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    - b. On duct sides with dimensions larger than 18 inches, place pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    - d. Do not overcompress insulation during installation.
    - e. Impale insulation over pins and attach speed washers.

- f. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.
  - 4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
    - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
    - b. Install vapor stops for ductwork and plenums operating below 50 deg F at 18-foot intervals. Vapor stops shall consist of vapor-barrier mastic applied in a Z-shaped pattern over insulation face, along butt end of insulation, and over the surface. Cover insulation face and surface to be insulated a width equal to two times the insulation thickness, but not less than 3 inches.
  - 5. Overlap unfaced blankets a minimum of 2 inches on longitudinal seams and end joints. At end joints, secure with steel bands spaced a maximum of 18 inches o.c.
  - 6. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
  - 7. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch- wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.
- B. Board Insulation Installation on Ducts and Plenums: Secure with adhesive and insulation pins.
- 1. Apply adhesives according to manufacturer's recommended coverage rates per unit area, for:
    - a. 50 percent coverage of duct and plenum surfaces.
  - 2. Apply adhesive to entire circumference of ducts and to all surfaces of fittings and transitions.
  - 3. Install either capacitor-discharge-weld pins and speed washers or cupped-head, capacitor-discharge-weld pins on sides and bottom of horizontal ducts and sides of vertical ducts as follows:
    - a. On duct sides with dimensions 18 inches and smaller, place pins along longitudinal centerline of duct. Space 3 inches maximum from insulation end joints, and 16 inches o.c.
    - b. On duct sides with dimensions larger than 18 inches, space pins 16 inches o.c. each way, and 3 inches maximum from insulation joints. Install additional pins to hold insulation tightly against surface at cross bracing.
    - c. Pins may be omitted from top surface of horizontal, rectangular ducts and plenums.
    - d. Do not overcompress insulation during installation.
    - e. Cut excess portion of pins extending beyond speed washers or bend parallel with insulation surface. Cover exposed pins and washers with tape matching insulation facing.

4. For ducts and plenums with surface temperatures below ambient, install a continuous unbroken vapor barrier. Create a facing lap for longitudinal seams and end joints with insulation by removing 2 inches from one edge and one end of insulation segment. Secure laps to adjacent insulation section with 1/2-inch outward-clinching staples, 1 inch o.c. Install vapor barrier consisting of factory- or field-applied jacket, adhesive, vapor-barrier mastic, and sealant at joints, seams, and protrusions.
  - a. Repair punctures, tears, and penetrations with tape or mastic to maintain vapor-barrier seal.
5. Install insulation on rectangular duct elbows and transitions with a full insulation section for each surface. Groove and score insulation to fit as closely as possible to outside and inside radius of elbows. Install insulation on round and flat-oval duct elbows with individually mitered gores cut to fit the elbow.
6. Insulate duct stiffeners, hangers, and flanges that protrude beyond insulation surface with 6-inch- wide strips of same material used to insulate duct. Secure on alternating sides of stiffener, hanger, and flange with pins spaced 6 inches o.c.

### 3.7 FIELD-APPLIED JACKET INSTALLATION

- A. Where glass-cloth jackets are indicated, install directly over bare insulation or insulation with factory-applied jackets.
  1. Draw jacket smooth and tight to surface with 2-inch overlap at seams and joints.
  2. Embed glass cloth between two 0.062-inch- thick coats of lagging adhesive.
  3. Completely encapsulate insulation with coating, leaving no exposed insulation.
- B. Where FSK jackets are indicated, install as follows:
  1. Draw jacket material smooth and tight.
  2. Install lap or joint strips with same material as jacket.
  3. Secure jacket to insulation with manufacturer's recommended adhesive.
  4. Install jacket with 1-1/2-inch laps at longitudinal seams and 3-inch- wide joint strips at end joints.
  5. Seal openings, punctures, and breaks in vapor-retarder jackets and exposed insulation with vapor-barrier mastic.
- C. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints; for horizontal applications, install with longitudinal seams along top and bottom of tanks and vessels. Seal with manufacturers recommended adhesive.
  1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.
- D. Where metal jackets are indicated, install with 2-inch overlap at longitudinal seams and end joints. Overlap longitudinal seams arranged to shed water. Seal end joints with weatherproof sealant recommended by insulation manufacturer. Secure jacket with stainless-steel bands 12 inches o.c. and at end joints.



### 3.8 FIRE-RATED INSULATION SYSTEM INSTALLATION

- A. Where fire-rated insulation system is indicated, secure system to ducts and duct hangers and supports to maintain a continuous fire rating.
- B. Insulate duct access panels and doors to achieve same fire rating as duct.
- C. Install firestopping at penetrations through fire-rated assemblies. Fire-stop systems are specified in Division 07 Section "Penetration Firestopping."

### 3.9 FINISHES

- A. Insulation with ASJ, Glass-Cloth, or Other Paintable Jacket Material: Paint jacket with paint system identified below and as specified in Division 09 Section "Exterior Painting" and "Interior Painting."
  - 1. Flat Acrylic Finish: Two finish coats over a primer that is compatible with jacket material and finish coat paint. Add fungicidal agent to render fabric mildew proof.
    - a. Finish Coat Material: Interior, flat, latex-emulsion size.
- B. Flexible Elastomeric Thermal Insulation: After adhesive has fully cured, apply two coats of insulation manufacturer's recommended protective coating.
- C. Color: Final color as selected by Architect. Vary first and second coats to allow visual inspection of the completed Work.
- D. Do not field paint aluminum or stainless-steel jackets.

### 3.10 FIELD QUALITY CONTROL

- A. Testing Agency:
  - a. Engage a qualified testing agency to perform tests and inspections.
- B. Perform tests and inspections.
- C. Tests and Inspections:
  - 1. Inspect ductwork, randomly selected by Architect, by removing field-applied jacket and insulation in layers in reverse order of their installation. Extent of inspection shall be limited to one location (s) for each duct system defined in the "Duct Insulation Schedule, General" Article.
- D. All insulation applications will be considered defective Work if sample inspection reveals noncompliance with requirements.

### 3.11 DUCT INSULATION SCHEDULE, GENERAL

#### A. Plenums and Ducts Requiring Insulation:

1. Indoor, concealed supply and outdoor air.
2. Indoor, exposed supply and outdoor air.
3. Indoor, concealed return located in unconditioned space.
4. Indoor, exposed return located in unconditioned space.
5. Outdoor, concealed supply and return.
6. Outdoor, exposed supply and return.

#### B. Items Not Insulated:

1. Fibrous-glass ducts.
2. Metal ducts with duct liner of sufficient thickness to comply with energy code and ASHRAE/IESNA 90.1.
3. Factory-insulated flexible ducts.
4. Factory-insulated plenums and casings.
5. Flexible connectors.
6. Vibration-control devices.
7. Factory-insulated access panels and doors.

3.12 Insulation shall have an R value that meets the minimum requirements of the latest International Energy Conservation Code (IECC).

### 3.13 INDOOR DUCT AND PLENUM INSULATION SCHEDULE

#### A. Concealed, round and flat-oval, supply-air duct insulation shall be one of the following:

1. Flexible Elastomeric: 1 inch thick.
2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.

#### B. Concealed, round and flat-oval, return-air duct insulation shall be one of the following:

1. Flexible Elastomeric: 1 inch thick.
2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.

#### C. Concealed, round and flat-oval, outdoor-air and combustion-air duct insulation shall be one of the following:

1. Flexible Elastomeric: 1 inch thick.
2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.

#### D. Concealed, round and flat-oval, exhaust-air duct insulation shall be one of the following:

1. Flexible Elastomeric: 1 inch thick.
2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.

- E. Concealed, rectangular, supply-air duct insulation shall be one of the following:
  - 1. Flexible Elastomeric: 1 inch thick.
  - 2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.
- F. Concealed, rectangular, return-air duct insulation shall be one of the following:
  - 1. Flexible Elastomeric: 1 inch thick.
  - 2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.
- G. Concealed, rectangular, outdoor-air and combustion-air duct insulation shall be one of the following:
  - 1. Flexible Elastomeric: 1 inch thick.
  - 2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.
- H. Concealed, supply-air plenum insulation shall be one of the following:
  - 1. Flexible Elastomeric: 1 inch thick.
  - 2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.
- I. Concealed, return-air plenum insulation shall be one of the following:
  - 1. Flexible Elastomeric: 1 inch thick.
  - 2. Mineral-Fiber Blanket: 1 inch thick and 0.75-lb/cu. ft. nominal density.

END OF SECTION 23 0713

## SECTION 23 0719 - HVAC PIPING INSULATION

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes insulating the following HVAC piping systems:

1. Condensate drain piping.
2. Chilled-water piping.
3. Heating hot-water piping.

- B. Related Sections:

1. Division 23 Section "Duct Insulation."
2. Division 23 Section "HVAC Equipment Insulation."

#### 1.3 DEFINITIONS:

- A. Refer to Division 23 Section "Common Work Results for HVAC".

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include thermal conductivity, water-vapor permeance thickness, and jackets (both factory and field applied if any).

- B. LEED Submittals:

1. Product Data for Credit IEQ 4.1: For adhesives and sealants, documentation including printed statement of VOC content.
2. Laboratory Test Reports for Credit IEQ 4: For adhesives and sealants, documentation indicating that products comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

- C. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.

1. Detail application of protective shields, saddles, and inserts at hangers for each type of insulation and hanger.
2. Detail attachment and covering of heat tracing inside insulation.

3. Detail insulation application at pipe expansion joints for each type of insulation.
4. Detail insulation application at elbows, fittings, flanges, valves, and specialties for each type of insulation.
5. Detail removable insulation at piping specialties.
6. Detail application of field-applied jackets.
7. Detail application at linkages of control devices.

## 1.5 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified Installer.
- B. Material Test Reports: From a qualified testing agency acceptable to authorities having jurisdiction indicating, interpreting, and certifying test results for compliance of insulation materials, sealers, attachments, cements, and jackets, with requirements indicated. Include dates of tests and test methods employed.

## 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: Skilled mechanics who have successfully completed an apprenticeship program or another craft training program certified by the Department of Labor, Bureau of Apprenticeship and Training.
- B. Surface-Burning Characteristics: For insulation and related materials, as determined by testing identical products according to ASTM E 84, by a testing and inspecting agency acceptable to authorities having jurisdiction. Factory label insulation and jacket materials and adhesive, mastic, tapes, and cement material containers, with appropriate markings of applicable testing agency.
  1. Insulation Installed Indoors: Flame-spread index of 25 or less, and smoke-developed index of 50 or less.
  2. Insulation Installed Outdoors: Flame-spread index of 75 or less, and smoke-developed index of 150 or less.

## 1.7 DELIVERY, STORAGE, AND HANDLING

- A. Packaging: Insulation material containers shall be marked by manufacturer with appropriate ASTM standard designation, type and grade, and maximum use temperature.

## 1.8 COORDINATION

- A. Coordinate sizes and locations of supports, hangers, and insulation shields specified in Division 23 Section "Hangers and Supports for HVAC Piping and Equipment."
- B. Coordinate clearance requirements with piping Installer for piping insulation application. Before preparing piping Shop Drawings, establish and maintain clearance requirements for

installation of insulation and field-applied jackets and finishes and for space required for maintenance.

## 1.9 SCHEDULING

- A. Schedule insulation application after pressure testing systems and, where required, after installing and testing heat tracing. Insulation application may begin on segments that have satisfactory test results.
- B. Complete installation and concealment of plastic materials as rapidly as possible in each area of construction.

## PART 2 - PRODUCTS

### 2.1 INSULATION MATERIALS

- A. Comply with requirements in "Piping Insulation Schedule, General," "Indoor Piping Insulation Schedule," "Outdoor, Aboveground Piping Insulation Schedule," and "Outdoor, Underground Piping Insulation Schedule" articles for where insulating materials shall be applied.
- B. Insulation for below-ambient service requires a vapor-barrier.
- C. Products shall not contain asbestos, lead, mercury, or mercury compounds.
- D. Products that come in contact with stainless steel shall have a leachable chloride content of less than 50 ppm when tested according to ASTM C 871.
- E. Insulation materials for use on austenitic stainless steel shall be qualified as acceptable according to ASTM C 795.
- F. Foam insulation materials shall not use CFC or HCFC blowing agents in the manufacturing process.
- G. Calcium Silicate:
  - 1. Products: Subject to compliance with requirements, provide the following:
    - a. Industrial Insulation Group (IIG); Thermo-12 Gold.
  - 2. Preformed Pipe Sections: Flat-, curved-, and grooved-block sections of noncombustible, inorganic, hydrous calcium silicate with a non-asbestos fibrous reinforcement. Comply with ASTM C 533, Type I.
  - 3. Flat-, curved-, and grooved-block sections of noncombustible, inorganic, hydrous calcium silicate with a non-asbestos fibrous reinforcement. Comply with ASTM C 533, Type I.
  - 4. Prefabricated Fitting Covers: Comply with ASTM C 450 and ASTM C 585 for dimensions used in preforming insulation to cover valves, elbows, tees, and flanges.

- H. Flexible Elastomeric Insulation: Closed-cell, sponge- or expanded-rubber materials. Comply with ASTM C 534, Type I for tubular materials.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Aeroflex USA, Inc.; Aerocel.
    - b. Armacell LLC; AP Armaflex.
    - c. K-Flex USA; Insul-Lock, Insul-Tube, and K-FLEX LS.
- I. Mineral-Fiber Blanket Insulation: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 553,
  - 1. Type II and ASTM C 1290, Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 2. Products: Subject to compliance with requirements, provide one of the following:
    - a. CertainTeed Corp.; SoftTouch Duct Wrap.
    - b. Johns Manville; Microlite.
    - c. Knauf Insulation; Friendly Feel Duct Wrap.
    - d. Manson Insulation Inc.; Alley Wrap.
    - e. Owens Corning; SOFTR All-Service Duct Wrap.
- J. Mineral-Fiber, Preformed Pipe Insulation:
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Johns Manville; Micro-Lok.
    - b. Knauf Insulation; 1000-Degree Pipe Insulation.
    - c. Manson Insulation Inc.; Alley-K.
    - d. Owens Corning; Fiberglas Pipe Insulation.
    - e. Type I, 850 deg F Materials: Mineral or glass fibers bonded with a thermosetting resin. Comply with ASTM C 547, Type I, Grade A:
      - 1) with factory-applied ASJ-SSL. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
- K. Mineral-Fiber, Pipe and Tank Insulation: Mineral or glass fibers bonded with a thermosetting resin. Semirigid board material with factory-applied:
  - 1. ASJ complying with ASTM C 1393, Type II or Type IIIA Category 2, or with properties similar to ASTM C 612, Type IB. Nominal density is 2.5 lb/cu. ft. or more. Thermal conductivity (k-value) at 100 deg F is 0.29 Btu x in./h x sq. ft. x deg F or less. Factory-applied jacket requirements are specified in "Factory-Applied Jackets" Article.
  - 2. Products: Subject to compliance with requirements, provide one of the following:
    - a. CertainTeed Corp.; CrimpWrap.
    - b. Johns Manville; MicroFlex.
    - c. Knauf Insulation; Pipe and Tank Insulation.
    - d. Manson Insulation Inc.; AK Flex.
    - e. Owens Corning; Fiberglas Pipe and Tank Insulation.

- L. Prefabricated Thermal Insulating Fitting Covers: Comply with ASTM C 450 for dimensions used in preforming insulation to cover valves, elbows, tees, and flanges.

## 2.2 INSULATING CEMENTS

- A. Mineral-Fiber Insulating Cement: Comply with ASTM C 195.
  - 1. Products: Subject to compliance with requirements, provide the following:
    - a. Ramco Insulation, Inc.; Super-Stik.
- B. Mineral-Fiber, Hydraulic-Setting Insulating and Finishing Cement: Comply with ASTM C 449.
  - 1. Products: Subject to compliance with requirements, provide the following:
    - a. Ramco Insulation, Inc.; Ramcote 1200 and Quik-Cote.

## 2.3 ADHESIVES

- A. Materials shall be compatible with insulation materials, jackets, and substrates and for bonding insulation to itself and to surfaces to be insulated unless otherwise indicated.
- B. Calcium Silicate Adhesive: Fibrous, sodium-silicate-based adhesive with a service temperature range of 50 to 800 deg F.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-97.
    - b. Eagle Bridges - Marathon Industries; 290.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 81-27.
    - d. Mon-Eco Industries, Inc.; 22-30.
    - e. Vimasco Corporation; 760.
  - 2. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- C. Flexible Elastomeric Adhesive: Comply with MIL-A-24179A, Type II, Class I.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Aeroflex USA, Inc.; Aero seal.
    - b. Armacell LLC; Armaflex 520 Adhesive.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-75.



- d. K-Flex USA; R-373 Contact Adhesive.
  - 2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- D. Mineral-Fiber Adhesive: Comply with MIL-A-3316C, Class 2, Grade A.
- 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-127.
    - b. Eagle Bridges - Marathon Industries; 225.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-60/85-70.
    - d. Mon-Eco Industries, Inc.; 22-25.
  - 2. For indoor applications, adhesive shall have a VOC content of 80 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- E. ASJ Adhesive, and FSK Jacket Adhesive: Comply with MIL-A-3316C, Class 2, Grade A for bonding insulation jacket lap seams and joints.
- 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-82.
    - b. Eagle Bridges - Marathon Industries; 225.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 85-50.
    - d. Mon-Eco Industries, Inc.; 22-25.
  - 2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- F. PVC Jacket Adhesive: Compatible with PVC jacket.
- 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Dow Corning Corporation; 739, Dow Silicone.
    - b. Johns Manville; Zeston Perma-Weld, CEEL-TITE Solvent Welding Adhesive.
    - c. P.I.C. Plastics, Inc.; Welding Adhesive.
    - d. Speedline Corporation; Polyco VP Adhesive.

2. For indoor applications, adhesive shall have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
3. Adhesive shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.4 MASTICS

- A. Materials shall be compatible with insulation materials, jackets, and substrates; comply with MIL-PRF-19565C, Type II.
  1. For indoor applications, use mastics that have a VOC content of 50 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- B. Vapor-Barrier Mastic: Water based; suitable for indoor use on below-ambient services.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 30-80/30-90.
    - b. Vimasco Corporation; 749.
  2. Water-Vapor Permeance: ASTM E 96/E 96M, Procedure B, 0.013 perm at 43-mil dry film thickness.
  3. Service Temperature Range: Minus 20 to plus 180 deg F.
  4. Solids Content: ASTM D 1644, 58 percent by volume and 70 percent by weight.
  5. Color: White.
- C. Vapor-Barrier Mastic: Solvent based; suitable for outdoor use on below-ambient services.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; Encacel.
    - b. Eagle Bridges - Marathon Industries; 570.
    - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 60-95/60-96.
  2. Water-Vapor Permeance: ASTM F 1249, 0.05 perm at 30-mil dry film thickness.
  3. Service Temperature Range: Minus 50 to plus 220 deg F.
  4. Solids Content: ASTM D 1644, 33 percent by volume and 46 percent by weight.
  5. Color: White.
- D. Breather Mastic: Water based; suitable for indoor and outdoor use on above-ambient services.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-10.

- b. Eagle Bridges - Marathon Industries; 550.
  - c. Foster Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; 46-50.
  - d. Mon-Eco Industries, Inc.; 55-50.
  - e. Vimasco Corporation; WC-1/WC-5.
- 2. Water-Vapor Permeance: ASTM F 1249, 1.8 perms at 0.0625-inch dry film thickness.
  - 3. Service Temperature Range: Minus 20 to plus 180 deg F.
  - 4. Solids Content: 60 percent by volume and 66 percent by weight.
  - 5. Color: White.

## 2.5 SEALANTS

### A. ASJ Flashing Sealants and PVC Jacket Flashing Sealants:

- 1. Products: Subject to compliance with requirements, provide the following:
  - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; CP-76.
- 2. Materials shall be compatible with insulation materials, jackets, and substrates.
- 3. Fire- and water-resistant, flexible, elastomeric sealant.
- 4. Service Temperature Range: Minus 40 to plus 250 deg F.
- 5. Color: White.
- 6. For indoor applications, sealants shall have a VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- 7. Sealants shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.6 FACTORY-APPLIED JACKETS

### A. Insulation system schedules indicate factory-applied jackets on various applications. When factory-applied jackets are indicated, comply with the following:

- 1. ASJ-SSL: ASJ with self-sealing, pressure-sensitive, acrylic-based adhesive covered by a removable protective strip; complying with ASTM C 1136, Type I.

## 2.7 FIELD-APPLIED JACKETS

- A. Field-applied jackets shall comply with ASTM C 921, Type I, unless otherwise indicated.
- B. PVC Jacket: High-impact-resistant, UV-resistant PVC complying with ASTM D 1784, Class 16354-C; thickness as scheduled; roll stock ready for shop or field cutting and forming. Thickness is indicated in field-applied jacket schedules.
  - 1. Products: Subject to compliance with requirements, provide one of the following:

- a. Johns Manville; Zeston.
  - b. P.I.C. Plastics, Inc.; FG Series.
  - c. Proto Corporation; LoSmoke.
  - d. Speedline Corporation; SmokeSafe.
2. Adhesive: As recommended by jacket material manufacturer.
3. Color: PVC, white: 30 mils thick.
4. Factory-fabricated fitting covers to match jacket if available; otherwise, field fabricate.
  - a. Shapes: 45- and 90-degree, short- and long-radius elbows, tees, valves, flanges, unions, reducers, end caps, soil-pipe hubs, traps, mechanical joints, and P-trap and supply covers for lavatories.

C. Metal Jacket:

1. Products: Subject to compliance with requirements, provide one of the following:
  - a. Childers Brand, Specialty Construction Brands, Inc., a business of H. B. Fuller Company; Metal Jacketing Systems.
  - b. ITW Insulation Systems; Aluminum and Stainless Steel Jacketing.
  - c. RPR Products, Inc.; Insul-Mate.
2. Aluminum Jacket: Comply with ASTM B 209, Alloy 3003, 3005, 3105, or 5005, Temper H-14.
  - a. Sheet and roll stock ready for shop or field sizing or factory cut and rolled to size.
  - b. Finish and thickness are indicated in field-applied jacket schedules.
  - c. Moisture Barrier for Indoor Applications:
    - 1) 1-mil- thick, heat-bonded polyethylene and kraft paper.
  - d. Moisture Barrier for Outdoor Applications:
    - 1) 3-mil- thick, heat-bonded polyethylene and kraft paper.
  - e. Factory-Fabricated Fitting Covers:
    - 1) Same material, finish, and thickness as jacket.
    - 2) Preformed 2-piece or gore, 45- and 90-degree, short- and long-radius elbows.
    - 3) Tee covers.
    - 4) Flange and union covers.
    - 5) End caps.
    - 6) Beveled collars.
    - 7) Valve covers.
    - 8) Field fabricate fitting covers only if factory-fabricated fitting covers are not available.

2.8 TAPES

- A. ASJ Tape: White vapor-retarder tape matching factory-applied jacket with acrylic adhesive, complying with ASTM C 1136.

1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ABI, Ideal Tape Division; 428 AWF ASJ.
    - b. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0836.
    - c. Compac Corporation; 104 and 105.
    - d. Venture Tape; 1540 CW Plus, 1542 CW Plus, and 1542 CW Plus/SQ.
  2. Width: 3 inches.
  3. Thickness: 11.5 mils.
  4. Adhesion: 90 ounces force/inch in width.
  5. Elongation: 2 percent.
  6. Tensile Strength: 40 lbf/inch in width.
  7. ASJ Tape Disks and Squares: Precut disks or squares of ASJ tape.
- B. PVC Tape: White vapor-retarder tape matching field-applied PVC jacket with acrylic adhesive; suitable for indoor and outdoor applications.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ABI, Ideal Tape Division; 370 White PVC tape.
    - b. Compac Corporation; 130.
    - c. Venture Tape; 1506 CW NS.
  2. Width: 2 inches.
  3. Thickness: 6 mils.
  4. Adhesion: 64 ounces force/inch in width.
  5. Elongation: 500 percent.
  6. Tensile Strength: 18 lbf/inch in width.
- C. Aluminum-Foil Tape: Vapor-retarder tape with acrylic adhesive.
1. Products: Subject to compliance with requirements, provide one of the following:
    - a. ABI, Ideal Tape Division; 488 AWF.
    - b. Avery Dennison Corporation, Specialty Tapes Division; Fasson 0800.
    - c. Compac Corporation; 120.
    - d. Venture Tape; 3520 CW.
  2. Width: 2 inches.
  3. Thickness: 3.7 mils.
  4. Adhesion: 100 ounces force/inch in width.
  5. Elongation: 5 percent.
  6. Tensile Strength: 34 lbf/inch in width.

## 2.9 SECUREMENTS

- A. Staples: Outward-clinching insulation staples, nominal 3/4-inch- wide, stainless steel or Monel.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine substrates and conditions for compliance with requirements for installation tolerances and other conditions affecting performance of insulation application.
  - 1. Verify that systems to be insulated have been tested and are free of defects.
  - 2. Verify that surfaces to be insulated are clean and dry.
  - 3. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 PREPARATION

- A. Surface Preparation: Clean and dry surfaces to receive insulation. Remove materials that will adversely affect insulation application.
- B. Surface Preparation: Clean and prepare surfaces to be insulated. Before insulating, apply a corrosion coating to insulated surfaces as follows:
  - 1. Stainless Steel: Coat 300 series stainless steel with an epoxy primer 5 mils thick and an epoxy finish 5 mils thick if operating in a temperature range between 140 and 300 deg F. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
  - 2. Carbon Steel: Coat carbon steel operating at a service temperature between 32 and 300 deg F with an epoxy coating. Consult coating manufacturer for appropriate coating materials and application methods for operating temperature range.
- C. Coordinate insulation installation with the trade installing heat tracing. Comply with requirements for heat tracing that apply to insulation.
- D. Mix insulating cements with clean potable water; if insulating cements are to be in contact with stainless-steel surfaces, use demineralized water.

#### 3.3 GENERAL INSTALLATION REQUIREMENTS

- A. Install insulation materials, accessories, and finishes with smooth, straight, and even surfaces; free of voids throughout the length of piping including fittings, valves, and specialties.
- B. Install insulation materials, forms, vapor barriers or retarders, jackets, and thicknesses required for each item of pipe system as specified in insulation system schedules.
- C. Install accessories compatible with insulation materials and suitable for the service. Install accessories that do not corrode, soften, or otherwise attack insulation or jacket in either wet or dry state.
- D. Install insulation with longitudinal seams at top and bottom of horizontal runs.
- E. Install multiple layers of insulation with longitudinal and end seams staggered.

- F. Do not weld brackets, clips, or other attachment devices to piping, fittings, and specialties.
- G. Keep insulation materials dry during application and finishing.
- H. Install insulation with tight longitudinal seams and end joints. Bond seams and joints with adhesive recommended by insulation material manufacturer.
- I. Install insulation with least number of joints practical.
- J. Where vapor barrier is indicated, seal joints, seams, and penetrations in insulation at hangers, supports, anchors, and other projections with vapor-barrier mastic.
  - 1. Install insulation continuously through hangers and around anchor attachments.
  - 2. For insulation application where vapor barriers are indicated, extend insulation on anchor legs from point of attachment to supported item to point of attachment to structure. Taper and seal ends at attachment to structure with vapor-barrier mastic.
  - 3. Install insert materials and install insulation to tightly join the insert. Seal insulation to insulation inserts with adhesive or sealing compound recommended by insulation material manufacturer.
  - 4. Cover inserts with jacket material matching adjacent pipe insulation. Install shields over jacket, arranged to protect jacket from tear or puncture by hanger, support, and shield.
- K. Apply adhesives, mastics, and sealants at manufacturer's recommended coverage rate and wet and dry film thicknesses.
- L. Install insulation with factory-applied jackets as follows:
  - 1. Draw jacket tight and smooth.
  - 2. Cover circumferential joints with 3-inch- wide strips, of same material as insulation jacket. Secure strips with adhesive and outward clinching staples along both edges of strip, spaced 4 inches o.c.
  - 3. Overlap jacket longitudinal seams at least 1-1/2 inches. Install insulation with longitudinal seams at bottom of pipe. Clean and dry surface to receive self-sealing lap. Staple laps with outward clinching staples along edge at
    - a. 2 inches o.c.
    - b. For below-ambient services, apply vapor-barrier mastic over staples.
  - 4. Cover joints and seams with tape, according to insulation material manufacturer's written instructions, to maintain vapor seal.
  - 5. Where vapor barriers are indicated, apply vapor-barrier mastic on seams and joints and at ends adjacent to pipe flanges and fittings.
- M. Cut insulation in a manner to avoid compressing insulation more than 75 percent of its nominal thickness.
- N. Finish installation with systems at operating conditions. Repair joint separations and cracking due to thermal movement.

- O. Repair damaged insulation facings by applying same facing material over damaged areas. Extend patches at least 4 inches beyond damaged areas. Adhere, staple, and seal patches similar to butt joints.
- P. For above-ambient services, do not install insulation to the following:
  - 1. Vibration-control devices.
  - 2. Testing agency labels and stamps.
  - 3. Nameplates and data plates.
  - 4. Manholes.
  - 5. Handholes.
  - 6. Cleanouts.

### 3.4 PENETRATIONS

- A. Insulation Installation at Roof Penetrations: Install insulation continuously through roof penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation above roof surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside roof flashing at least 2 inches below top of roof flashing.
  - 4. Seal jacket to roof flashing with flashing sealant.
- B. Insulation Installation at Underground Exterior Wall Penetrations: Terminate insulation flush with sleeve seal. Seal terminations with flashing sealant.
- C. Insulation Installation at Aboveground Exterior Wall Penetrations: Install insulation continuously through wall penetrations.
  - 1. Seal penetrations with flashing sealant.
  - 2. For applications requiring only indoor insulation, terminate insulation inside wall surface and seal with joint sealant. For applications requiring indoor and outdoor insulation, install insulation for outdoor applications tightly joined to indoor insulation ends. Seal joint with joint sealant.
  - 3. Extend jacket of outdoor insulation outside wall flashing and overlap wall flashing at least 2 inches.
  - 4. Seal jacket to wall flashing with flashing sealant.
- D. Insulation Installation at Interior Wall and Partition Penetrations (That Are Not Fire Rated): Install insulation continuously through walls and partitions.
- E. Insulation Installation at Fire-Rated Wall and Partition Penetrations: Install insulation continuously through penetrations of fire-rated walls and partitions.



1. Comply with requirements in Section 078413 "Penetration Firestopping" for firestopping and fire-resistive joint sealers.

F. Insulation Installation at Floor Penetrations:

1. Pipe: Install insulation continuously through floor penetrations.
2. Seal penetrations through fire-rated assemblies. Comply with requirements in Division 07 section "Penetration Firestopping."

3.5 GENERAL PIPE INSULATION INSTALLATION

A. Requirements in this article generally apply to all insulation materials except where more specific requirements are specified in various pipe insulation material installation articles.

B. Insulation Installation on Fittings, Valves, Strainers, Flanges, and Unions:

1. Install insulation over fittings, valves, strainers, flanges, unions, and other specialties with continuous thermal and vapor-retarder integrity unless otherwise indicated.
2. Insulate pipe elbows using preformed fitting insulation or mitered fittings made from same material and density as adjacent pipe insulation. Each piece shall be butted tightly against adjoining piece and bonded with adhesive. Fill joints, seams, voids, and irregular surfaces with insulating cement finished to a smooth, hard, and uniform contour that is uniform with adjoining pipe insulation.
3. Insulate tee fittings with preformed fitting insulation or sectional pipe insulation of same material and thickness as used for adjacent pipe. Cut sectional pipe insulation to fit. Butt each section closely to the next and hold in place with tie wire. Bond pieces with adhesive.
4. Insulate valves using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. For valves, insulate up to and including the bonnets, valve stuffing-box studs, bolts, and nuts. Fill joints, seams, and irregular surfaces with insulating cement.
5. Insulate strainers using preformed fitting insulation or sectional pipe insulation of same material, density, and thickness as used for adjacent pipe. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker. Fill joints, seams, and irregular surfaces with insulating cement. Insulate strainers so strainer basket flange or plug can be easily removed and replaced without damaging the insulation and jacket. Provide a removable reusable insulation cover. For below-ambient services, provide a design that maintains vapor barrier.
6. Insulate flanges and unions using a section of oversized preformed pipe insulation. Overlap adjoining pipe insulation by not less than two times the thickness of pipe insulation, or one pipe diameter, whichever is thicker.
7. Cover segmented insulated surfaces with a layer of finishing cement and coat with a mastic. Install vapor-barrier mastic for below-ambient services and a breather mastic for above-ambient services. Reinforce the mastic with fabric-reinforcing mesh. Trowel the mastic to a smooth and well-shaped contour.

8. For services not specified to receive a field-applied jacket except for flexible elastomeric install fitted PVC cover over elbows, tees, strainers, valves, flanges, and unions. Terminate ends with PVC end caps. Tape PVC covers to adjoining insulation facing using PVC tape.
  9. Stencil or label the outside insulation jacket of each union with the word "union." Match size and color of pipe labels.
- C. Insulate instrument connections for thermometers, pressure gages, pressure temperature taps, test connections, flow meters, sensors, switches, and transmitters on insulated pipes. Shape insulation at these connections by tapering it to and around the connection with insulating cement and finish with finishing cement, mastic, and flashing sealant.
- D. Install removable insulation covers at locations indicated. Installation shall conform to the following:
1. Make removable flange and union insulation from sectional pipe insulation of same thickness as that on adjoining pipe. Install same insulation jacket as adjoining pipe insulation.
  2. When flange and union covers are made from sectional pipe insulation, extend insulation from flanges or union long at least two times the insulation thickness over adjacent pipe insulation on each side of flange or union. Secure flange cover in place with stainless-steel or aluminum bands. Select band material compatible with insulation and jacket.
  3. Construct removable valve insulation covers in same manner as for flanges, except divide the two-part section on the vertical center line of valve body.
  4. When covers are made from block insulation, make two halves, each consisting of mitered blocks wired to stainless-steel fabric. Secure this wire frame, with its attached insulation, to flanges with tie wire. Extend insulation at least 2 inches over adjacent pipe insulation on each side of valve. Fill space between flange or union cover and pipe insulation with insulating cement. Finish cover assembly with insulating cement applied in two coats. After first coat is dry, apply and trowel second coat to a smooth finish.
  5. Unless a PVC jacket is indicated in field-applied jacket schedules, finish exposed surfaces with a metal jacket.

### 3.6 INSTALLATION OF CALCIUM SILICATE INSULATION

A. Insulation Installation on Straight Pipes and Tubes:

1. Secure single-layer insulation with stainless-steel bands at 12-inch intervals and tighten bands without deforming insulation materials.
2. Install two-layer insulation with joints tightly butted and staggered at least 3 inches. Secure inner layer with wire spaced at 12-inch intervals. Secure outer layer with stainless-steel bands at 12-inch intervals.
3. Apply a skim coat of mineral-fiber, hydraulic-setting cement to insulation surface. When cement is dry, apply flood coat of lagging adhesive and press on one layer of glass cloth or tape. Overlap edges at least 1 inch. Apply finish coat of lagging adhesive over glass cloth or tape. Thin finish coat to achieve smooth, uniform finish.

B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of block insulation of same material and thickness as pipe insulation.
4. Finish flange insulation same as pipe insulation.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available. Secure according to manufacturer's written instructions.
2. When preformed insulation sections of insulation are not available, install mitered sections of calcium silicate insulation. Secure insulation materials with wire or bands.
3. Finish fittings insulation same as pipe insulation.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install mitered segments of calcium silicate insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
2. Install insulation to flanges as specified for flange insulation application.
3. Finish valve and specialty insulation same as pipe insulation.

### 3.7 INSTALLATION OF FLEXIBLE ELASTOMERIC INSULATION

A. Seal longitudinal seams and end joints with manufacturers recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

B. Insulation Installation on Pipe Flanges:

1. Install pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with cut sections of sheet insulation of same thickness as pipe insulation.
4. Secure insulation to flanges and seal seams with manufacturers recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

C. Insulation Installation on Pipe Fittings and Elbows:

1. Install mitered sections of pipe insulation.
2. Secure insulation materials and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed valve covers manufactured of same material as pipe insulation when available.

2. When preformed valve covers are not available, install cut sections of pipe and sheet insulation to valve body. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
3. Install insulation to flanges as specified for flange insulation application.
4. Secure insulation to valves and specialties and seal seams with manufacturer's recommended adhesive to eliminate openings in insulation that allow passage of air to surface being insulated.

### 3.8 INSTALLATION OF MINERAL-FIBER INSULATION

#### A. Insulation Installation on Straight Pipes and Tubes:

1. Secure each layer of preformed pipe insulation to pipe with wire or bands and tighten bands without deforming insulation materials.
2. Where vapor barriers are indicated, seal longitudinal seams, end joints, and protrusions with vapor-barrier mastic and joint sealant.
3. For insulation with factory-applied jackets on above-ambient surfaces, secure laps with outward-clinched staples at 6 inches o.c.
4. For insulation with factory-applied jackets on below-ambient surfaces, do not staple longitudinal tabs. Instead, secure tabs with additional adhesive as recommended by insulation material manufacturer and seal with vapor-barrier mastic and flashing sealant.

#### B. Insulation Installation on Pipe Flanges:

1. Install preformed pipe insulation to outer diameter of pipe flange.
2. Make width of insulation section same as overall width of flange and bolts, plus twice the thickness of pipe insulation.
3. Fill voids between inner circumference of flange insulation and outer circumference of adjacent straight pipe segments with mineral-fiber blanket insulation.
4. Install jacket material with manufacturer's recommended adhesive, overlap seams at least 1 inch, and seal joints with flashing sealant.

#### C. Insulation Installation on Pipe Fittings and Elbows:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed insulation elbows and fittings are not available, install mitered sections of pipe insulation, to a thickness equal to adjoining pipe insulation. Secure insulation materials with wire or bands.

#### D. Insulation Installation on Valves and Pipe Specialties:

1. Install preformed sections of same material as straight segments of pipe insulation when available.
2. When preformed sections are not available, install mitered sections of pipe insulation to valve body.
3. Arrange insulation to permit access to packing and to allow valve operation without disturbing insulation.
4. Install insulation to flanges as specified for flange insulation application.

### 3.9 FIELD-APPLIED JACKET INSTALLATION

- A. Where PVC jackets are indicated, install with 1-inch overlap at longitudinal seams and end joints; for horizontal applications. Seal with manufacturers recommended adhesive.
  - 1. Apply two continuous beads of adhesive to seams and joints, one bead under lap and the finish bead along seam and joint edge.

### 3.10 PIPING INSULATION SCHEDULE, GENERAL

- A. Acceptable preformed pipe and tubular insulation materials and thicknesses are identified for each piping system and pipe size range. If more than one material is listed for a piping system, selection from materials listed is Contractor's option.
- B. Items Not Insulated: Unless otherwise indicated, do not install insulation on the following:
  - 1. Drainage piping located in crawl spaces.
  - 2. Underground piping.
  - 3. Chrome-plated pipes and fittings unless there is a potential for personnel injury.

### 3.11 INDOOR PIPING INSULATION SCHEDULE

- A. Condensate and Equipment Drain Water below 60 Deg F:
  - 1. All Pipe Sizes: Insulation shall be one of the following:
    - a. Flexible Elastomeric:
      - 1) 1/2 inch thick
    - b. Mineral-Fiber, Preformed Pipe Insulation, Type I:
      - 1) 1/2 inch thick
- B. Chilled Water, 40 Deg F and below:
  - 1. NPS 1-1/2 inch and Smaller: Insulation shall be the following:
    - a. Flexible Elastomeric:
      - 1) 1-1/2 inch thick.
  - 2. NPS 2 inch and Larger: Insulation shall be the following:
    - a. Flexible Elastomeric:
      - 1) 2 inch thick
  - 3. Insulation for runouts not exceeding 48 inches in length for connection to equipment shall be the following:
    - a. Flexible Elastomeric: 1 inch thick.
- C. Chilled Water, above 40 Deg F:
  - 1. NPS 1-1/2 inch and Smaller: Insulation shall be the following:
    - a. Flexible Elastomeric:

- 1) 1-1/2 inch thick.
    - b. Mineral-Fiber, Preformed Pipe, Type I:
      - 1) 1-1/2 inches thick.
  - 2. NPS 2 inch and Larger: Insulation shall be the following:
    - a. Flexible Elastomeric:
      - 1) 2 inch thick.
    - b. Mineral-Fiber, Preformed Pipe, Type I:
      - 1) 2 inch thick.
  - 3. Insulation runouts not exceeding 48 inches in length for connection to equipment shall be one of the following:
    - a. Flexible Elastomeric: 1 inch thick.
    - b. Mineral-Fiber, Preformed Pipe, Type I: 1 inch thick
- D. Heating-Hot-Water Supply and Return, 200 Deg F and Below:
- 1. NPS 1 1/2 and Smaller: Insulation shall be the following:
    - a. Mineral-Fiber, Preformed Pipe, Type I:
      - 1) 1-1/2 inch thick
  - 2. Greater than NPS 1-1/2 inch : Insulation shall be the following:
    - a. Mineral-Fiber, Preformed Pipe, Type I or Pipe and Tank Insulation:
      - 1) 2 inches thick
  - 3. Insulation for runouts not exceeding 48 inches in length for connection to equipment shall be the following:
    - a. Mineral-Fiber, Preformed Pipe, Type I: 1 inch thick.
- E. Heating-Hot-Water Supply and Return, above 200 Deg F:
- 1. NPS 1 and Smaller: Insulation shall be one of the following:
    - a. Calcium Silicate:
      - 1) 2 inches thick
    - b. Mineral-Fiber, Preformed Pipe, Type I or II:
      - 1) 1-1/2 inches thick
  - 2. NPS 1-1/4 and Larger: Insulation shall be one of the following:
    - a. Calcium Silicate:
      - 1) 3 inches thick
    - b. Mineral-Fiber, Preformed Pipe, Type I or II:
      - 1) 2 inches thick
  - 3. Insulation runouts not exceeding 48 inches in length for connection to equipment shall be the following:

- a. Mineral-Fiber, Preformed Pipe, Type I: 1-1/2 inch thick.

3.12 INDOOR, FIELD-APPLIED JACKET SCHEDULE

- A. Install jacket over insulation material. For insulation with factory-applied jacket, install the field-applied jacket over the factory-applied jacket.
- B. If more than one material is listed, selection from materials listed is Contractor's option.
- C. Piping, Concealed:
  - 1. None.
- D. Piping, Exposed:
  - 1. PVC:
    - a. PVC, white: 30 mils thick.

END OF SECTION 23 0719

## SECTION 230900 - INSTRUMENTATION AND CONTROL FOR HVAC

### PART 1 - GENERAL

#### 1.1 SCOPE OF WORK

- A. The Facility Management and Control System (FMCS) Agency shall furnish and install a fully integrated building automation system, incorporating direct digital control (DDC) for energy management, equipment monitoring and control as herein specified. The system shall include all required computer software and hardware, controllers, sensors, transmission equipment, system workstations, local panels, conduit, wire, installation, engineering, database and setup, supervision, commissioning, acceptance test, training, warranty service and, at the owner's option, extended warranty service. The system shall be an extension of the existing ACC Talon Tridium FMCS by Atkinson Electronics, Inc.
- B. The system shall use BacNet as its floor level protocol. System components shall be certified and display the BTL logo where applicable.
- C. The FMCS shall demonstrate, with (3) proof sources, integration with HVAC industry open standard protocols, including LonMark, BACnet, ModBus, and Internet standard SQL database and HTTP / HTML / XML text formats.
- D. The FMCS shall communicate to third party systems such as boilers, air handling systems, energy metering systems, other energy management systems, fire-life safety systems and other building management related devices using any of the open, interoperable communication protocols referenced in Paragraph C.
- E. All materials and equipment used shall be standard components, regularly manufactured for this and/or other systems and not custom designed especially for this project
- F. Plenum rated cable is allowed for low voltage control wiring.
- G. Control voltage on each floor for VAV boxes, fan coil units, phoenix valves and other mechanical equipment is located in the electrical rooms. See electrical drawings for location.

#### 1.2 RELATED WORK SPECIFIED ELSEWHERE

- A. Drawings and general provisions of the Contract, including General and supplementary Conditions and Division-1 specification sections, apply to work of this section.
- B. Products furnished but not installed under this section:
  - 1. Valves, flow switches, flow sensors, thermowells and pressure taps to be installed under Division 22 & 23.
  - 2. Automatic dampers to be installed under Division 23.



C. Coordination with electrical:

1. Installation of all line voltage power wiring by Division 26 with the exception where line voltage power wiring is required by the FMCS and is not shown to be provided by Division 26, it shall be furnished as part of the work of the FMCS.
2. Each motor starter provided under Division 26, shall be furnished with individual control power transformer to supply 120 volt control power and auxiliary contacts (one N.O. and one N.C.) for use by this section.

1.3 QUALITY ASSURANCE

- A. The system shall be furnished, engineered, and installed by the manufacturers' locally authorized representative. The FMCS Agency shall have factory-trained technicians to provide instruction, routine maintenance, and emergency service within 24 hours upon receipt of request.
- B. At the time of bid, all FMCS Application Specific Controllers and Programmable Equipment Controllers shall be listed as follows:
  1. Underwriters Laboratory UL 916
  2. FCC Regulation, Part 15, Class B

1.4 SUBMITTALS

- A. Submit 10 complete sets of documentation in the following phased delivery schedule:
  1. Valve and damper schedules
  2. Equipment data cut sheets
  3. System schematics, including:
    - a. sequence of operations
    - b. point names
    - c. point addresses
    - d. point to point wiring
    - e. interface wiring diagrams
    - f. panel layouts
    - g. system riser diagrams
  4. AutoCAD® compatible as-built drawings
- B. Upon project completion, submit operation and maintenance manuals, consisting of the following:

1. Index sheet, listing contents in alphabetical order
2. Manufacturer's equipment parts list of all functional components of the system, disk of system schematics, including wiring diagrams
3. Description of sequence of operations
4. As-Built interconnection wiring diagrams
5. User's documentation containing product, system architectural and programming information.
6. Trunk cable schematic showing remote electronic panel locations, and all trunk data
7. List of connected data points, including panels to which they are connected and input device (ionization detector, sensors, etc.)
8. Conduit routing diagrams
9. Copy of the warranty/guarantee
10. Operating and maintenance cautions and instructions
11. Recommended spare parts list

#### 1.5 COMMISSIONING COORDINATION

- A. The FMCS Agency shall coordinate all work with the Commissioning Agent. Work will include but not be limited to control sequence review meetings, establish remote BMS access, functional testing and retesting.

## PART 2 - PRODUCTS

### 2.1 ACCEPTABLE MANUFACTURERS

- A. Talon Tridium N4 BacNet by Atkinson Electronics

### 2.2 The Facility Management Control System (FMCS) shall be comprised of a network of interoperable, stand-alone digital controllers. The FMCS shall incorporate BacNet technology. The system shall include:

- A. Programmable Equipment Controllers (PEC's) for control of primary mechanical systems and distributed system applications. Controllers shall be fully programmable to create custom control solutions.
- B. Network Area Controllers (NAC's) for distributed system applications, databases and networking functions.

- C. Application Specific Controllers (ASC's) for control of VAV terminal units, fan coil terminal units, unit vent terminal units, heat pump units and other terminal equipment.
- D. Graphical User Interface (GUI), which includes the hardware and software necessary for a user to interface with the control system and devices.
- E. The zone controller network shall use twisted pair wiring and 78Kbps RS485 BacNet MSTP wiring topologies. The GU, PEC and NAC shall reside on a 100 Mb Ethernet backbone.
- F. All components and controllers supplied under this contract shall be true "peer-to-peer" communicating devices. Components or controllers requiring "polling" by a host to pass data shall not be acceptable.
- G. Communication and integration of 3<sup>rd</sup> party BacNet products shall be accomplished without gateways or interface devices. The 3<sup>rd</sup> party product supplier shall provide BacNet PIC statements for each device.

## 2.3 NETWORK AREA CONTROLLER (NAC)

- A. The Network Area Controller (NAC) shall provide the interface between the field control devices, and provide global supervisory control functions over the control devices connected to the NAC. The NAC shall be JACE N4. It shall be capable of executing application control programs to provide:
  - 1. Calendar functions
  - 2. Scheduling
  - 3. Trending
  - 4. Alarm monitoring and routing
  - 5. Time synchronization
  - 6. Integration of BacNet controller data
  - 7. Integration of BacNet and MODBUS networks
  - 8. Lon Network
  - 9. Monitoring, control, and programming of all points.
  - 10. Network Management functions for all BacNet based devices
  - 11. Employ Niagara AX operating system.
- B. The NAC shall provide multiple, concurrent user access to the system and support for ODBC or SQL. A database resident on the NAC shall be an ODBC-compliant database or must provide an ODBC data access mechanism to read and write data stored within it.
- C. The NAC shall support standard Web browser access via the Intranet/Internet. It shall support a minimum of 16 simultaneous users.
- D. The NAC shall provide alarm recognition, storage; routing, management, and analysis to supplement distributed capabilities of equipment or application specific controllers.
  - 1. The NAC shall be able to route any alarm condition to any defined user location whether connected to a local network or remote via dial-up, telephone connection, or wide-area network.
  - 2. Alarm generation shall be selectable for annunciation type and acknowledgement requirements including, but not limited to:
    - a. To alarm
    - b. Return to normal
    - c. To fault
  - 3. Provide for the creation of an unlimited number of alarm classes for the purpose of routing types and or classes of alarms, i.e.: security, HVAC, Fire, etc.
  - 4. Provide timed (schedule) routing of alarms by class, object, group, or node.
  - 5. Provide alarm generation from binary object "runtime" and /or event counts for equipment maintenance. The user shall be able to reset runtime or event count values with appropriate password control.
- E. Alarms shall be annunciated in any of the following manners as user defined:
  - 1. Screen message text

2. Email of the complete alarm message to multiple recipients. Provide the ability to route and email alarms based on:
    - a. Day of week
    - b. Time of day
    - c. Recipient
  3. Pagers via paging services that initiate a page on receipt of email message
  4. Graphic with flashing alarm object(s)
  5. Printed message, routed directly to a dedicated alarm printer
- F. The following shall be recorded by the NAC for each alarm (at a minimum):
1. Time and date
  2. Location (building, floor, zone, office number, etc.)
  3. Equipment (air handler #, access way, etc.)
  4. Acknowledge time, date, and user who issued acknowledgement.
  5. Number of occurrences since last acknowledgement.
- G. Defined users shall be given proper access to acknowledge any alarm, or specific types or classes of alarms defined by the user.
- H. A log of all alarms shall be maintained by the NAC and/or a server (if configured in the system) and shall be available for review by the user.
- I. Provide a “query” feature to allow review of specific alarms by user defined parameters.
- J. A separate log for system alerts (controller failures, network failures, etc.) shall be provided and available for review by the user.
- K. An Error Log to record invalid property changes or commands shall be provided and available for review by the user.
- L. Data Collection and Storage
1. The NAC shall have the ability to collect data for any property of any object and store this data for future use.
  2. The data collection shall be performed by log objects, resident in the NAC that shall have, at a minimum, the following configurable properties:
    - a. Designating the log as interval or deviation.
    - b. For interval logs, the object shall be configured for time of day, day of week and the sample collection interval.
    - c. For deviation logs, the object shall be configured for the deviation of a variable to a fixed value. This value, when reached, will initiate logging of the object.
    - d. For all logs, provide the ability to set the maximum number of data stores for the log and to set whether the log will stop collecting when full, or rollover the data on a first-in, first-out basis.
    - e. Each log shall have the ability to have its data cleared on a time-based event or by a user-defined event or action.

3. All log data shall be stored in a relational database in the NAC and the data shall be accessed from a server (if the system is so configured) or a standard Web Browser.
4. All log data, when accessed from a server, shall be capable of being manipulated using standard SQL statements.
5. All log data shall be available to the user in the following data formats:
  - a. HTML
  - b. XML
  - c. Plain Text
  - d. Comma or tab separated values
6. Systems that do not provide log data in HTML and XML formats at a minimum shall not be acceptable.
7. The NAC shall have the ability to archive its log data either locally (to itself), or remotely to a server or other NAC on the network. Provide the ability to configure the following archiving properties, at a minimum:
  - a. Archive on time of day
  - b. Archive on user-defined number of data stores in the buffer (size)
  - c. Archive when buffer has reached its user-defined capacity
- M. Provide and maintain an Audit Log that tracks all activities performed on the NAC. Provide the ability to specify a buffer size for the log and the ability to archive log based on time or when the log has reached its user-defined buffer size. Provide the ability to archive the log locally (to the NAC), to another NAC on the network, or to a server. For each log entry, provide the following data:
  1. Time and date
  2. User ID
  3. Change or activity: i.e., Change set point, add or delete objects, commands, etc.
- N. The NAC shall have the ability to automatically backup its database. The database shall be backed up based on a user-defined time interval.
  1. Copies of the current database and, at the most recently saved database shall be stored in the NAC. The age of the most recently saved database is dependent on the user-defined database save interval.
  2. The NAC database shall be stored, at a minimum, in XML format to allow for user viewing and editing, if desired. Other formats are acceptable as well, as long as XML format is supported.
- O. Each Network Area Controller (NAC) that is part of the Ethernet backbone shall include local battery backed UPSs sized for 30 minutes backup.

## 2.4 PROGRAMMABLE EQUIPMENT CONTROLLERS (PEC)

- A. Programmable Equipment Controllers (PEC's) shall be stand-alone, multi-tasking, real-time digital control processors.

- B. The PEC's shall communicate via native BacNet MSTP protocol. Provide a minimum of 4MB Random Access Memory in each PEC.
- C. The PEC must communicate peer-to-peer with the all of the network application specific, programmable controllers and third party BacNet devices.
- D. Programming of the PEC shall be accomplished by using graphical software that incorporates drag and drop capabilities. The PEC software database must be able to execute all of the specified mechanical system controls functions. The programming software shall be able to bundle software logic to simplify control sequencing. All values, which make up the PID output value, shall be readable and modifiable at a workstation or portable service tool. Each input, output, or calculation result shall be capable of being shared/bound with any controller or interface device on the network.
- E. PEC's shall be able to execute custom, job specific processes defined by the user, to automatically perform calculations and special control routines.
- F. A single process shall be able to incorporate measured or calculated data from any and all other PEC's on the network. In addition, a single process shall be able to issue commands to points in any and all other PEC's on the network.
- G. Each PEC shall support firmware upgrades without the need to replace hardware.
- H. Each PEC shall continuously perform self-diagnostics, which include communication diagnosis and diagnosis of all components. The PEC shall provide both local and remote annunciation of any detected component failures, low battery conditions or repeated failure to establish communication.
- I. In the event of the loss of normal power, there shall be an orderly shutdown of all PEC's to prevent the loss of database or operating system software. Non-volatile memory shall be incorporated for all critical controller configuration data and battery backup shall be provided to support the real-time clock and all volatile memory for a minimum of 72 hours.
  - 1. Upon restoration of normal power, the PEC shall automatically resume full operation without manual intervention.
  - 2. All PEC's control programming and databases must be stored in Flash memory, therefore eliminating data loss, down time and re-load time.

## 2.5 APPLICATION SPECIFIC CONTROLLERS (ASC)

- A. Each Application Specific Controller (ASC) shall operate as a stand-alone BACnet MSTP compliant controller capable of performing its specified control responsibilities independent of other controllers in the network. Each ASC shall be a minimum 16-BIT microprocessor based, multi-tasking, multi-user, real time digital control processor.
- B. Service pin initiation shall be accomplished from the room sensor and/or the controller. ASC room sensors that do not provide service pin initiation must provide a wall jack by the room sensor to enable this feature.

- C. Controllers shall include all inputs and outputs necessary to perform the specified control sequences. Analog and digital outputs shall be industry standard signals such as 0-10V and 3-point floating control allowing for interface to a variety of industry standard modulating actuators. The ASC inputs and outputs shall consist of industry standards types. Inputs shall be electrically isolated from outputs, communications and power. All inputs shall be provided with an auto-calibrate function to eliminate sensing errors.
- D. All controller sequences and operation shall provide closed loop control of the intended application. Closing control loops over the network is not acceptable.
- E. The ASC must be mounted remotely from the room sensor. ASC's, that are wall mounted with integral room sensors, are not acceptable.
- F. The control program shall reside in the ASC. The application program and the configuration information shall be stored in non-volatile memory with no battery back-up required.
- G. After a power failure the ASC must run the control application using the current set points and configuration. Reverting to default or factory set points is not acceptable.



## 2.6 GRAPHICAL USER INTERFACE SOFTWARE (GUI)

- A. Operator workstations must be capable of supporting any LonMark or BacNet compliant product. The operator shall not be able to distinguish the DDC points from different manufacturers when commanding, monitoring points or acknowledging alarms.
- B. The software shall provide a multi-tasking type environment that allows the user to run several applications simultaneously. The GUI software shall run on a Windows 10 operating system. The operator shall be able to work in Microsoft Word, Excel, and other Windows10 based software packages, while concurrently annunciating on-line BMS alarms and monitoring information. If the software is unable to display several different types of displays at the same time, the as work of this section, provide at least two operator workstations at each location specified.
- C. Real-Time Displays. The GUI, shall at a minimum, support the following graphical features and functions:
  - 1. Graphic screens shall be developed using any drawing package capable of generating a GIF, BMP, or JPG file format. Use of proprietary graphic file formats shall not be acceptable. In addition to, or in lieu of a graphic background, the GUI shall support the use of scanned pictures.
  - 2. A gallery of HVAC and automation symbols shall be provided, including fans, valves, motors, chillers, AHU systems, standard ductwork diagrams and symbols. The user shall have the ability to add custom symbols to the gallery as required.
  - 3. Graphic screens shall have the capability to contain objects for text, real-time values, animation, color spectrum objects, logs, graphs, HTML or XML document links, schedule objects, hyperlinks to other URL's, and links to other graphic screens.
  - 4. Graphics shall support layering and each graphic object shall be configurable for assignment to a layer. A minimum of six layers shall be supported.
  - 5. Modifying common application objects, such as schedules, calendars, and setpoints shall be accomplished in a graphical manner.
    - a. Schedule times will be adjusted by mouse command using a graphical slider, without requiring any keyboard entry from the operator.
    - b. Holidays shall be set by mouse command using a graphical calendar, without requiring any keyboard entry from the operator.
  - 6. Commands to start and stop binary objects shall be done by mouse command from the pop-up menu. No entry of text shall be required.
  - 7. Adjustments to analog objects, such as set points, shall be done by mouse command using a graphical slider to adjust the value. No entry of text shall be required.
- D. System Configuration. At a minimum, the GUI shall permit the operator to perform the following tasks, with proper password access:

1. Create, delete or modify control strategies
  2. Add/delete objects to the system
  3. Tune control loops through the adjustment of control loop parameters
  4. Enable or disable control strategies
  5. Generate hard copy records or control strategies on a printer
  6. Select points to be alarmable and define the alarm state
  7. Select points to be trended over a period of time and initiate the recording of values automatically
- E. On-Line Help. Provide a context sensitive, on-line help system to assist the operator in operation and editing of the system. On-line help shall be available for all applications and shall provide the relevant data for that particular screen. Additional help information shall be available through the use of hypertext. All system documentation and help files shall be in HTML format.
- F. Each operator shall be required to log on to that system with a user name and password in order to view, edit, add, or delete data. System security shall be selectable for each operator. The system administrator shall have the ability to set passwords and security levels for all other operators. Each operator password shall be able to restrict the operators' access for viewing and/or changing each system application, full screen editor, and object. Each operator shall automatically be logged off of the system if no keyboard or mouse activity is detected. This auto log-off time shall be set per operator password. All system security data shall be stored in an encrypted format.
- G. System Diagnostics. The system shall automatically monitor the operation of all workstations, printers, modems, network connections, building management panels, and controllers. The failure of any device shall be annunciated to the operator.
- H. The system will be provided with a dedicated alarm window or console. This window will notify the operator of an alarm condition, and allow the operator to view details of the alarm and acknowledge the alarm. The use of the Alarm Console can be enabled or disabled by the system administrator.
- I. When the Alarm Console is enabled, a separate alarm notification window will supersede all other windows on the desktop and shall not be capable of being minimized or closed by the operator. This window will notify the operator of new alarms and un-acknowledged alarms. Alarm notification windows or banners that can be minimized or closed by the operator shall not be acceptable.

## 2.7 WEB BROWSER CLIENTS

- A. The system shall be capable of supporting an unlimited number of clients using a standard Web browser such as Internet Explorer® or Netscape Navigator®. Systems requiring

additional software (to enable a standard Web browser) to be resident on the client machine, or manufacture-specific browsers shall not be acceptable.

- B. The Web browser software shall run on any operating system and system configuration that is supported by the Web browser. Web page access and control shall be from system Network Area Controllers, or the Workstation.
- C. The Web browser shall provide the same system view, in terms of graphics, schedules, calendars, logs, etc., and provide the same interface methodology as is provided by the Graphical User Interface. Systems that require different views or that require different means of interacting with objects such as schedules, or logs, shall not be permitted.
- D. The Web browser client shall support at a minimum, the following functions:
  - 1. User log-on identification and password security shall be required and implemented using Java authentication and encryption techniques to prevent unauthorized access. If an unauthorized user attempts access, a blank web page shall be displayed.
  - 2. Graphical screens developed for the GUI shall be the same screens used for the Web browser client. Any animated graphical objects supported by the GUI shall be supported by the Web browser interface.
  - 3. HTML programming shall not be required to display system graphics or data on a Web page. HTML editing of the Web page shall be allowed if the user desires a specific look or format.
  - 4. Storage of the graphical screens shall be in the Network Area Controller (NAC), without requiring any graphics to be stored on the client machine. Systems that require graphics storage on each client machine are not acceptable.
  - 5. Real-time values displayed on a Web page shall update automatically without requiring a manual "refresh" of the Web page.
  - 6. Users shall have administrator-defined access privileges. Depending on the access privileges assigned, the user shall be able to perform the following:
    - a. Modify in a graphical manner, common application objects, such as schedules, calendars, and set points. Schedule times will be adjusted by mouse command using a graphical slider, without requiring any keyboard entry from the operator. Holidays shall be set by mouse command using a graphical calendar, without requiring any keyboard entry from the operator.
    - b. Commands to start and stop binary objects shall be done by mouse command right-click of the selected object and selecting the appropriate command from the pop-up menu. No entry of text shall be required.
    - c. View logs and charts
    - d. View and acknowledge alarms
  - 7. The system shall provide the capability to specify a user's home page (as determined by the log-on user identification). The system shall provide the ability to limit a specific

user to just their defined home page. From the home page, links to other views, or pages in the system shall be possible, if allowed by the system administrator.

8. Graphic screens on the Web Browser client shall support hypertext links to other locations on the Internet or on Intranet sites, by specifying the Uniform Resource Locator (URL) for the desired link.
- E. Trend logging and system monitoring requirements.
1. Trend data shall be stored for three years and be accessible through web-browser-based reporting tools.
  2. See Section 230800 for additional trending implementation requirements.

## 2.8 BACNET NETWORK MANAGEMENT

- A. Network management shall include the following services: device identification, device installation, device configuration, device diagnostics and device maintenance.
- B. The network management tool shall also provide diagnostics to identify devices on the network, to reset devices, and to view health and status counters within devices.
- C. These tools shall provide the ability to “learn” an existing BacNet network, regardless of what network management tool(s) were used to install the existing network, so that existing devices and newly added devices are part of a single network management database.
- D. The network management database shall be resident in the Network Area Controller (NAC), ensuring that users with proper authorization have access to the network management database at all times. Systems employing network management databases that are not resident at all times within the control system shall not be accepted.

## 2.9 PROJECT SPECIFIC WEB PAGES

- A. Home page shall include a campus layout of the individual buildings at the site. Once an individual building is selected the following minimum web-based tree structure shall be provided:
  - 1. Documents Page: The document page shall include the O&M Manuals for the control system in PDF format along with AutoCAD drawings for each drawing provided in the control system O&M Manual.
  - 2. Station Functions:
    - a. Logging separate sheet of station functions for a particular selected building shall be the viewing of one or more logs or the creation of logs in which any value at any point, or the mode of any point, shall be selected via the web to be trended against any other point with an adjustable frequency in seconds, minutes, hours or days.
    - b. The alarm acknowledgement via the web shall allow the viewing and acknowledgement of the alarms.
    - c. Audit log shall be provided via the web to show the operator actions as well as other audit logs as specified in section 2.5 Network Area Controller (NAC) paragraph “M” Data Collection and Storage.
  - 3. Floor Plans:
    - a. AutoCAD drawings of floor plans shall be provided in the control system such that via the web the user shall be able to turn layers on and off on the mechanical floor plans. These floor plans shall also include an overlay of the temperature control as-built wiring for the project showing thermostat locations, communication runs, transformer locations, controller locations, etc.
    - b. Floor Display Summaries. The operator shall be able to select floor plans displaying the following formats:

1. All zone temperatures
  2. All zone heating percentages
  3. All zone cooling percentages
  4. All zone room names and numbers
  5. All zones cfm delivered.
- c. Upon selecting a graphical floor plan layout the web page shall show all the zone temperature sensor locations on the floor. By clicking on the zone temperature location, an individual VAV box graphic shall be displayed with the following attributes:
  1. A manual menu that shall allow the operator to manually set the air flow set point, space temperature set point, damper position, cooling percentage, heating percentage, and zero the box.
  2. A 24 hour log chart that shows space temperature history, flow history, and allows the operator to build custom charts by comparing this log to other associated selectable logs.
  3. A display of the VAV box discharge temperature, air handler discharge temperature, space temperature, and space temperature set point.
  4. A bar graph that shows actual CFM, current air flow, and current air flow set point, percentage of heating and cooling in a thermometer-like fashion and changes color based on heating or cooling mode.
  5. The damper position, reheat valve position, occupancy status, room name and heating/cooling mode shall also be shown.
4. Systems:
  - a. On selecting the systems menu, a tree structure shall allow the operator to select the air handlers, boilers, chillers, control valves, pumps, heat exchangers, critical air flow valves, etc. systems associated with that building. The graphics shall also show the piping and ductwork associated with the air handler as well as the safeties, temperature sensors, humidity sensors, dampers, VFD's, associated with that fan system. See points lists for specifics.
  - b. All devices that provide dynamic function in the primary equipment, i.e., fans, pumps, coils, dampers shall be dynamic in nature showing their operating status/percentage of capacity by movement on the web page.
  - c. The set points for the various control loops shall be adjustable via the web page. Individual controlled devices, i.e. valves, dampers and fans shall be controlled via the web page and be stopped or started or placed in a command state or percentage of value output.

#### 5. Psychometric Graphic

The work station shall include a psychometric graphic that displays the actual job site outdoor weather conditions including grains per pound of moisture, dew point temperature, wet bulb temperature, relative humidity, and dry bulb temperature. The psychometric chart shall include the dynamic values and include switch over points for free cooling to mechanical cooling and back. It shall show the actual values which shall be adjustable from the graphic shown as vertical and horizontal lines and diagonal wet bulb lines on the psychometric chart.

## 2.10 BUILDING OPERATORS/MANAGERS WORK STATION

- A. Provide a work station to be located where directed by the owner/engineer. Minimum requirements are as follows:
  - 1. INTEL COE i7 COMET LAKE OR BETTER CPU
  - 2. 126GB of RAM
  - 3. Windows 10
  - 4. 750 GB Hard Drive
  - 5. Dual 30" Flat Screen Color Monitors and Optical Mouse
  - 6. USB Keyboard

## 2.11 FIELD DEVICES

- A. Provide automatic control valves, automatic control dampers, thermostats, clocks, sensors, controllers, and other components as required for complete installation. Except as otherwise indicated, provide manufacturer's standard control system components as indicated by published product information, designed and constructed as recommended by manufacturer.
- B. TEMPERATURE SENSORS
  - 1. Temperature Sensors: Temperature sensors shall be linear precision elements with ranges appropriate for each specific application. Where sensors are located in public areas they shall not employ set point adjustments or override capability. Set point adjustment shall be programmed for 2.5° maximum initially.
  - 2. Space (room) sensors shall be available with set point adjustment and override switch.
  - 3. Duct mounted averaging sensors shall utilize a sensing element incorporated in a copper capillary with a minimum length of 20 feet. The sensor shall be installed according to manufacture recommendation and looped and fastened at a minimum of every 36 inches.
  - 4. Sunshields shall be provided for outside air sensors.
  - 5. Thermo-wells for all immersion sensors shall be stainless steel or brass as required for the application.
- C. Humidity Sensors: Humidity sensors shall be of the solid-state type using a capacitance-sensing element. The sensor shall vary the output voltage with a change in relative humidity. Room humidity sensors shall have a minimum range of 10% to 90%  $\pm$  5%. Supply air humidity sensors shall have a normal range of 10% to 90%  $\pm$  5%.
- D. Air Velocity Sensors: The sensor shall use differential pressure to determine airflow rate and have repeatability within 1% of reading and an accuracy of  $\pm$  5% of range. The velocity range shall be from 0 to 3250 FPM.

- E. Pressure Sensors: The differential pressure sensor shall be temperature compensated and shall vary the output voltage with a change in differential pressure. Sensing range shall be suitable for the application with linearity of 1.5% of full scale and offset of less than 1% of full scale. Sensor shall be capable of withstanding up to 150% of rated pressure without damage. Sensor range shall not exceed 4 times the set point.
- F. Building Static Pressure Transmitters and Building Sensing Arrays: Building static pressure transmitter installations shall include four runs of equal length 3/8 pneumatic tubing to the four exposures of the building. The indoor transmitter reference point shall be the lobby if the air handler serves the lobby or a public outside entrance. For the upper floors of the building, the indoor reference point shall be the elevator lobby of the middle floor served by the air handler, with the outdoor references located on the same floor as the elevator lobby reference with equal length 3/8 tubing to each exposure of the building.

Outdoor pickups shall include a bug screen to prevent insects from plugging and shielded to prevent rain water or snow from entering the pickup sensor.

#### G. SWITCHES AND THERMOSTATS

- 1. As work of this section, furnish all electric relays and coordinate with the supplier of magnetic starters for auxiliary contact requirements. All electric control devices shall be of a type to meet current, voltage, and switching requirement of their particular application. Relays shall be provided with 24 VAC coils and contacts shall be rated at 10 amps minimum.
- 2. Differential Pressure Switches: Pressure differential switches shall have SPDT changeover contact, switching at an adjustable differential pressure set point.
- 3. Low Temperature Detection Thermostats: Shall be the manual reset type. The thermostat shall operate in response to the coldest one-foot length of the 20-foot sensing element, regardless of the temperatures at other parts of the element. The element shall be properly supported to cover the entire downstream side of the coil with a minimum of three loops. Separate thermostats shall be provided for each 25 square feet of coil face area or fraction thereof.
- 4. Current Sensing Relays: Motor status indications, where shown on the plans point list shall be provided via current sensing relays. The switch output contact shall be rated for 30 VDC, .15 amps.
- 5. Flow Switches: Motor status indications, where shown on the plans point list, shall be provided via flow switches. Flow switches shall be of the paddle type equipped with SPDT contacts to establish proof of flow.

#### H. CONTROL VALVES

- 1. General: Control Valves up to 4 inches shall be sized for a 3 to 5 psi pressure drop. Valves shall be pack-less, modulating, electrically or magnetically actuated, with a



control rangeability of 100 to 1. These valves shall have true equal percentage flow characteristics in relationship to valve opening.

2. ½ inch to 4 inch: Valves shall be equipped with handwheel, or manual position mounted dial adjacent to valve, to allow manual positioning of valve in absence of control power.
3. 4 inches to 6 inches: Valves shall be modulating electrically actuated, 2-way or 3-way as required, with a rangeability of 50 to 1. Valve body shall be flanged and shall be equipped with a handwheel, or manual position dial mounted adjacent to the valve, to allow manual positioning of the valve in the absence of control power.
4. Butterfly Valves: 2-way and 3-way butterfly valves shall be cast iron valve body, with stainless steel stem, and available with disc seal for bubble-tight shut off.
5. Pressure Independent Chilled Water Control Valves for Primary Equipment
  - a. The control valves shall be NPS 2 and smaller with a forged brass body rated at no less than 400 PSI, chrome plated brass ball and stem, female NPT union ends, dual EPDM lubricated O-rings and a brass or TEFZEL characterizing disc.
  - b. The control valves shall be NPS 2-1/2 through 6 with GG25 cast iron body according to ANSI Class 125, standard class B, stainless steel ball and blowout proof stem, flange to match ANSI 125 with a dual EPDM O-ring packing design, PTFE seals and a stainless steel flow characterizing disc.
  - c. The control valves shall accurately control the flow from 0 to 100% full rated flow with an operating pressure differential range of 5 to 50 PSI differential across the valve with a valve body accuracy of  $\pm 5\%$  variance due to differential pressure fluctuation or  $\pm 10\%$  total assembly error incorporating differential pressure fluctuation, manufacturing tolerances and valve hysteresis.
  - d. The control valves shall have equal percentage flow characteristics.
  - e. The control valves manufacturer shall provide a published commissioning procedure following the guidelines of the National Environmental Balancing Bureau (NEBB) and the Testing Adjusting Balancing Bureau (TABB).

I. BTU METERS – ONICON SYSTEM 10:

1. The BTU Meters shall have BACnet compatible serial communications. They shall provide complete energy, flow and temperature data to the control system through a single BACnet/IP network connection for measurement of chilled water, heating water and steam.
2. The BTU Meters shall be a single source responsibility with one manufacturer responsible for every aspect of the energy measurement process to ensure component compatibility and overall system accuracy.
3. The BTU Meters shall have N.I.S.T. traceable calibration with certification. Each BTU measurement system shall be individually calibrated using application specific flow and temperature data and shall provide calibration certificates.
4. The BTU Meters shall use precision solid state temperature sensors that shall be custom calibrated and matched to an accuracy better than  $\pm 0.15^\circ \text{F}$  over calibrated range.
5. The BTU Meters shall be highly accurate flow meters with a wide variety of insertion and inline type flow measurement technologies including turbine, electromagnetic and

vortex sensing. Each flow meter shall be individually wet calibrated and designed to operate over a wide flow velocity range with accuracies ranging from  $\pm 0.2\%$  to  $\pm 2.0\%$  of rate.

6. The BTU Meters shall be factory programmed for specific application and field programmable via the front panel interface.
7. The BTU Meters shall have non-volatile EEPROM memory which retains all program parameters and totalized values in the event of a power loss.
8. The BTU Meters shall have alphanumeric LCD which shall display total energy, total flow, energy rate, flow rate, supply temperature and return temperature.
9. The BTU Meters shall have a BACnet/IP output signal.

#### J. DAMPER ACTUATORS

1. Actuators shall be of the push-pull or rotary type of modulating, 3-point floating, or 2-position control as required by the application. The actuator shall use an overload-proof synchronous motor or an electric motor with end switches to de-energize the motor at the end of the stroke limits. Control voltage shall be 24 VAC, 0-20 VDC, or 4-20 ma as required. Actuators shall be available with spring return to the normal position when required. Actuators shall have a position indicator for external indication of damper position. Actuators shall have manual override capability without disconnecting damper linkage. Actuators for purge system shall meet failsafe and smoke control speed requirements.

#### K. CONTROL DAMPERS

1. Motorized dampers, unless otherwise specified elsewhere, shall have damper frames using 13 gauge galvanized steel channel or 1/8" extruded aluminum with reinforced corner bracing. Damper blades shall not exceed ten (10) inches in width or 48" in length. Blades are to be suitable for high velocity performance. Damper bearings shall be as recommended by manufacturer for application. Bushings that turn in the bearing are to be oil impregnated sintered metal. All blade edges and top and bottom of the frame shall be provided with replaceable, butyl rubber or neoprene seals. Side seals may be spring-loaded stainless steel. The seals shall provide a maximum of 1% leakage at a wide open face velocity of 1500 FPM and 4: W.C. close-off pressure. The damper linkage shall provide a linear flow or equal percentage characteristic as required. Provide Ruskin RCD46 model.
2. Control dampers shall be parallel or opposed blade type as scheduled on drawings or outdoor and return air mixing box dampers shall be parallel blade, arranged to direct air streams towards each other. All other dampers may be parallel or opposed blade types.

#### 2.12 AIRFLOW MEASURING STATION (These shall be provided for all air handling equipment and shall be provided by the FMCS Agency)

##### A. General:

1. Provide Ebtron Gold or Air Monitor Electraflo, VOLU-probe and VOLU-flo/OAM total supply air, and outside, and return air flow measurement stations (AFMS) for each new air handling unit and return fans.
2. AFMS shall consist of single or multiple probes as required to achieve an airflow measurement accuracy of  $\pm 3\%$  of reading.

3. AFMS probe assemblies must have multiple sensors that use instrument grade thermal dispersion, temperature compensated, thermistor sensing technology and digital electronics.
4. The AFMS manufacturer &/or their local representative shall recommend and approve the actual location for the AFMS and determine whether or not a honeycomb straightener is required.
5. Vortex shedding or pitot tube arrays and differential pressure sensing arrays with sensors that require auto-zeroing will not be accepted.
6. The basis of design for the AFMS is powered by the low voltage controls. If line voltage is required, it will be the responsibility of this section to coordinate and provide line voltage at no additional cost to the owner.
7. The flow monitor/controller shall be capable of direct measurement of airflow through an outside air inlet and produce dual outputs; one representing the measured airflow, and the other to control the inlet damper.

The monitor/controller shall contain an integral multi-line liquid crystal display for use during the configuration and calibration processes, and to display two measured processes (volume, velocity, temperature) during normal operation. All configuration, output scaling, calibration, and controller tuning will be performed digitally in the on-board microprocessor via input pushbuttons.

The monitor/controller shall measure inlet airflow with an accuracy of  $\pm 5\%$  of reading over range of 150-600 FPM, 2501,000 FPM, 500-2,000 FPM, and 150-2,000 FPM and not have its reading affected by the presence of directional or gusting wind. Measured airflow shall be density corrected for ambient temperature variances, and atmospheric pressure due to site altitude.

The monitor/controller shall interface with existing building automation systems (BAS), accepting inputs for fan system start, economizer mode operation, and an external controller setpoint, and provide flow deviation alarm outputs.

The sensors shall be constructed of materials that resist corrosion due to the presence of salt or chemicals in the air; all non-painted surfaces shall be constructed of stainless steel. The electronics enclosure shall be NEMA 1.

8. Provide where indicated, an array of airflow traverse probes capable of continuously monitoring the fan or duct capacities (air volumes) they serve.

Each airflow traverse probe shall contain multiple total and static pressure sensors located along the exterior surface of the cylindrical probe and internally connected to their respective averaging manifolds. The flow sensors shall not protrude beyond the surface of the probe(s), and shall be the offset (Fechheimer) type for static pressure and the chamfered impact type for total pressure measurement. The airflow sensing probe's measurement accuracy shall not be affected by directional flow having pitch and/or yaw angles up to 30°. Each airflow traverse probe shall be of extruded aluminum construction and furnished with mounting plate(s), gasket, and signal fittings suitable for HVAC duct installation.

Total and static pressure sensors shall be located at the centers of equal areas (for rectangular ducts) or at equal concentric area centers (for circular ducts) along the probe

length.

Probes shall be AMCA certified and be capable of measuring the airflow rates within an accuracy of  $\pm 2\%$  without the use of correction factors. The maximum allowable unrecovered pressure drop caused by the probes shall not exceed .025" w.c. at 2000 FPM, or .085" w.c. at 4000 FPM.

9. The transmitter shall be capable of receiving flow signals (total and static pressure) from an airflow station or probe array and produce an output linear and scaled for air volume, velocity, differential pressure, etc.

The transmitter shall contain an integral multi-line digital display for use during the configuration and calibration process, and to display one transmitter output during normal operating mode. All transmitter configuration, parameter setting, zero and span calibration, plus display formatting and scaling will be performed digitally in the on-board microprocessor via input pushbuttons.

The transmitter will be available in multiple spans covering the range of 0.05 IN w.c. to 25.0 IN w.c. with an accuracy of 0.25% of natural span. The transmitter shall be furnished with a transducer automatic zeroing circuit and be capable of maintaining linear output signals on applications requiring 10 to 1 velocity turndown.

B. Sensors:

1. Each sensing point shall consist of one glass encapsulated self-heated thermistor for velocity sensing and one glass encapsulated thermistor for temperature sensing.
2. Sensors must be hermetically sealed to be water resistant and capable of being frequently exposed to moisture without causing sensor failure.
3. Factory calibration: @ 0 fpm & @ 16 different airflow rates to NIST standards.
4. Velocity accuracy:  $\sim 2\%$  of reading.
5. Temperature accuracy:  $+ 0.180^\circ\text{F}$ .
6. Velocity output scaling: 0-500; 0-1000; 0-2500; 0-5000 or 0-10000 fpm (as required by the application).
7. Operating temp. Range:  $\sim 20^\circ\text{C}$  to  $1600^\circ\text{F}$ .
8. Operating RH Range: 0 to 99% (non-condensing).

C. Probes:

1. Aluminum, 316 stainless steel or gold anodized bodies with 2 to 8 sensors per probe.
2. Air pressure drop: 0.0005 in wg. @ 2000 fpm (maximum).

D. Electronics:

1. Microprocessor based, totally solid state, industrial grade integrated circuits that do not require periodic calibration.
2. Each sensor shall be independent from any other sensor.
3. An intelligent "sensor detection system" (SDS) shall put the transmitter into an alarm mode if any sensor or the transmitter is not operating properly.
4. The SDS shall ignore any sensor that is inoperable and utilize only the remaining operable sensors to determine airflow and assure an accurate and uninterrupted output

signal.

5. Transmitter outputs: 4-20 ma; 0-10 vdc; N2~ or Modbus~.
6. Operating temp. Range: -20~ to 1600F.
7. Operating RH range: 0 to 99% (non-condensing).
8. Multi-character based for transmitter visual interface (note: LCD available or Gold Series product line only).

E. Start-up:

1. Factory authorized start-up certification and owner-training services must be provided and conducted by the AFMS manufacturer's local representative.

F. Warranty:

1. 24 months from date of start-up certification.

2.13 VFDs

- A. The VFD shall be as specified in Division 26-0923. The VFD shall be installed by the Division 26 as to mounting and power conductors and disconnects.

2.14 SMOKE CONTROL PANEL

- A. Scope of work is to furnish and install a smoke control panel, smoke control subpanels, wiring, devices, actuators, and coordinate these new systems with the building management system and fire alarm system.
- B. General: Fire-fighter's control panel for fire department emergency response purposes only. Panel shall include manual control or override of automatic control for mechanical smoke control system. The panel shall be located as shown on drawings.
- C. Fans within the building shall be shown on the fire-fighter's control panel in a graphical representation. A clear indication of the direction of airflow and the relationship of components shall be displayed. Status indicators shall be provided for all smoke control equipment, annunciated by fan and zone, and by LED indicators as follows:
1. Fans, dampers and other operating equipment in their normal status –WHITE.
  2. Fans, dampers and other operating equipment in their off or closed status –RED.
  3. Fans, dampers and other operating equipment in their on or open status –GREEN.
  4. Fans, dampers and other operating equipment in a fault status –YELLOW/AMBER.
- D. The Fire-fighter's control panel shall provide control capability over the complete smoke-control system equipment within the building as follows:
1. ON-OFF-AUTO control over each individual piece of operating smoke control equipment that can also be controlled from other sources within the building. This

includes smoke exhaust fans and other operating equipment used or intended for smoke control purposes.

2. OPEN-AUTO-CLOSE control over individual dampers relating to smoke control and that are also controlled from other sources within the building.
3. ON-OFF or OPEN-CLOSE control over smoke control and other critical equipment associated with a fire or smoke emergency and that can only be controlled from the fire-fighter's control panel.

#### 2.15 SYSTEM COMPONENTS CRITICAL AIR FLOW.

- A. The Critical Airflow system for infectious isolation and BMT rooms shall include a five (5) year material and workmanship manufacturer's warranty.

#### 2.16 AIRFLOW CONTROL DEVICE – GENERAL

- A. The airflow control device shall be a Venturi valve by Phoenix Controls.
- B. The valve assembly manufacturer's Quality Management System shall be registered to ISO 9001:2000.
- C. The airflow control device shall be pressure independent over its specified differential static pressure operating range. An integral pressure independent assembly shall respond and maintain specific airflow within one second of a change in duct static pressure irrespective of the magnitude of pressure and/or flow change or quantity of airflow controllers on a manifold system.
- D. The airflow control device shall maintain accuracy within  $\pm 5\%$  of signal over an airflow turndown range of no less than:

| Pressure Drop Range | Airflow                             | Turndown | Valve Type |
|---------------------|-------------------------------------|----------|------------|
| 0.6- 3.0-inch WC    | Devices up to 1,000 CFM (472 l/s)   | 20 to 1  | Standard   |
|                     | Devices up to 1,500 CFM (708 l/s)   | 16 to 1  | Standard   |
|                     | Devices up to 2,500 CFM (1,180 l/s) | 12 to 1  | Standard   |
|                     | Devices up to 850 CFM (401 l/s)     | 17 to 1  | Shutoff    |
|                     | Devices up to 1,300 CFM (614 l/s)   | 14 to 1  | Shutoff    |
| 0.3- 3.0-inch WC    | Devices up to 550 CFM (260 l/s)     | 11 to 1  | Standard   |
|                     | Devices up to 1,050 CFM (496 l/s)   | 11 to 1  | Standard   |

- E. No minimum entrance or exit duct diameters shall be required to ensure accuracy and/or pressure independence.
- F. The airflow control device shall be constructed of the following:
  - 1. Class A: The airflow control device for non-corrosive airstreams, such as supply and general exhaust, shall be constructed of 16-gauge aluminum. The device's shaft and shaft support brackets shall be made of 316 stainless steel. The pivot arm and internal mounting link shall be made of aluminum. The pressure independent springs shall be a spring-grade stainless steel. All shaft bearing surfaces shall be made of a Teflon, polyester or PPS (polyphenylene sulfide) composite.
  - 2. Sound attenuating devices used in conjunction with general exhaust or supply airflow control devices shall be constructed using 24 gauge galvanized steel or other suitable material used in standard duct construction. No sound absorptive materials of any kind shall be used.

G. Actuation

- 1. For electrically actuated VAV operation, a UL 916 listed electronic actuator shall be factory mounted to the valve. Loss of main power shall cause the valve to position itself in an appropriate failsafe state. Options for these failsafe states include: normally open-maximum position, normally closed-minimum position and last position. This position shall be maintained constantly without external influence, regardless of external conditions on the valve (within product specifications).
- 2. The shutoff airflow control device shall have shutoff and casing leakage of no more than:

| Static Pressure Across<br>Valve in Shutoff | Airflow                                                  | Shutoff<br>Leakage | Casing<br>Leakage             |
|--------------------------------------------|----------------------------------------------------------|--------------------|-------------------------------|
| 5.0-inch WC                                | Shutoff devices up to 850 CFM (472 l/s)                  | 6 CFM              | 0.12<br>CFM/ ft <sup>2</sup>  |
|                                            | Shutoff devices up to 1,300 CFM (708 l/s)                | 6 CFM              | 0.12<br>CFM/ ft <sup>2</sup>  |
|                                            | Low leakage shutoff devices up to 850<br>CFM (472 l/s)   | 0.005 CFM          | 0.010<br>CFM/ ft <sup>2</sup> |
|                                            | Low leakage shutoff devices up to 1,300<br>CFM (708 l/s) | 0.010 CFM          | 0.010<br>CFM/ ft <sup>2</sup> |

- H. The controllers for the airflow control devices shall be microprocessor based furnished by

Phoenix with valves and operate using peer-to-peer control architecture. The room-level airflow control devices shall function as a standalone network.

- I. The room-level control network shall utilize a BacNet MSTP communications protocol.
- J. There shall be no reliance on external or building-level control devices to perform room-level control functions. Each critical airflow control system shall have the capability of performing fume hood control, pressurization control, temperature control, humidity control, and implement occupancy and emergency mode control schemes.
- K. The venturi valves shall come equipped with a differential pressure transducer that measures the pressure drop across the valve. This value shall be an input into the valve DDC controller. The value shall be linked to the BAS system. The FMCS Agency shall display the value on the system graphics for each valve.
- L. Start-up and Commissioning Tool (Separate from the BMS Interface): The critical airflow control manufacturer shall provide to the owner a start-up and commissioning tool separate from any tools provided by the FMCS Agency. The tool shall be a thin Client application that will allow access to the air flow control system through the customer's computer network. The access to the system must be web enabled and the interface shall be through the use of standard internet browsers.
- M. The tool shall be graphical based and allow for the adjustment of all set-up parameters.
  1. A floor plan shall be provided that allows the operator to see the location of each pressurization zone in the building. The area will display the space temperature and or supply/exhaust flows for each area. A Schematic shall be provided for each pressurization zone. The schematic shall show the following"
  2. All air flow devices i.e. hood valves, supply valves, general exhaust valves, etc. The flow and set-point valves for each device shall be displayed. The total supply, total exhaust, offset command, and offset value shall be shown as well
  3. All temperature and humidity information that is controlled by the system shall also be displayed including but not limited to, supply duct temperature, heating coil valve position, space temperature, space temperature set point, percent heating or cooling demand, occupied/unoccupied status
  4. A table of emergency modes shall be shown on the graphic at what the status of the mode is by selecting a valve on the schematic the operator will be taken to the parameter set-up pages for that valve.
- N. Interface to Building Management Systems:
  1. The critical airflow control system network shall be digitally integrated with the BAS.
  2. All room-level points shall be mapped to the BMS for monitoring or trending.
  3. Multiple BacNet IP gateways shall be provided in order to connect to the building-level network.



- O. Interface to Building Management System
  - 1. Native BACnet airflow controllers are also acceptable.
- P. See the points list for integration with the BAS at a minimum. Any other points used by the system in its control sequences, but not shown here shall also be made available
  - 1. The critical airflow control systems shall be integrated with the BMS, using BacNet IP.
- Q. Certification
  - 1. Each airflow control device shall be factory calibrated to the job specific airflows as detailed on the plans and specifications using NIST traceable air stations and instrumentation having a combined accuracy of no more than  $\pm 1\%$  of signal over the entire range of measurement. Electronic airflow control devices shall be further calibrated and their accuracy verified to  $\pm 5\%$  of signal at a minimum of 48 different airflows across the full operating range of the device.
  - 2. Each airflow control device shall be marked with device-specific factory calibration data. At a minimum, it should include the tag number, serial number, model number, eight-point characterization information (for electronic devices), and quality control inspection numbers. All information shall be stored by the manufacturer for use with as-built documentation.

## 2.17 EXHAUST AND SUPPLY TRACKING PAIR DEVICE CONTROLLER

- A. One controller shall be supplied for both the supply airflow control device and the corresponding exhaust air control device. The controller shall be a microprocessor-based design and use closed-loop control to linearly regulate airflow based on a digital control signal. The device shall generate a digital feedback signal that represents its airflow.
- B. In flow tracking applications, where an exhaust device is tracking a supply device, flow data for each device shall be downloaded to the controller in the factory.
- C. The airflow control device shall store its control algorithms in non-volatile, rewritable memory. The device shall be able to stand alone or to be networked with other room-level digital airflow control devices through an industry standard protocol.
- D. Room-level flow tracking control functions shall be embedded in and executed by one controller mounted on one of the airflow devices.
- E. The room-level control network shall communicate by using the BacNet MSTP protocol.
- F. The airflow control device shall use 24 Vac power  $\pm 15\%$ , the industry standard.
- G. The airflow control device shall be able to connect a notebook PC commissioning tool. Every node on the local network shall be accessible.
- H. The airflow control device shall have integral input/output for the following functions:

temperature control, humidity control, occupancy control, emergency control, shut-off control, and non-network sensor switches and control devices. At a minimum, the airflow controller shall have:

1. Base models shall have three universal inputs capable of accepting 0 to 10 Vdc, 4 to 20 mA, 0 to 65 K ohms, or Type 2 or Type 3, 10 K ohm @ 25 degree C; thermistor temperature sensors available for space temperature, set point lever adjust and discharge air temperature.
2. Expanded models shall have five universal inputs capable of accepting 0 to 10 Vdc, 4 to 20 mA, 0 to 65 K ohms, or Type 2 or Type 3, 10 K ohm @ 25 degree C, thermistor temperature sensors available for space temperature, set point lever adjust and discharge air temperature, humidity control (UI 4 and 5) and pressure monitoring (UI 4 and 5).
3. One digital input capable of accepting a dry contact or logic-level signal input, which may be used for occupancy override via a local room-level sensor.
4. All inputs shall have an accuracy of  $\pm 1\%$  F.S.
5. All models shall have two analog outputs capable of developing either a 0 to 10 Vdc or 4 to 20 mA linear control signal, to be available for duct reheat and ancillary room heat (i.e., fin tube radiation, radiant heat panels, each with its own independent PID control loops).
6. All models shall one floating point Triac® output available for proportional reheat coil valve operation. This output shall have a rating of 6 VA Max at 24 VAC.
7. All models shall have one Form C (SPDT) relay output capable of driving up to 1 A @ 24 Vac/Vdc to be available for local audio/visual alarms.
8. All outputs shall have the following accuracies:
  - a. 0 to 10 Vdc-  $\pm 1\%$  F.S. into 10 K ohms minimum
  - b. 4 to 20 mA-  $\pm 1\%$  F.S. into 500 ohms, +0 ohms/ -50 ohms
9. The airflow control device shall meet the following agency compliance requirements: FCC Part 15 Subpart J Class A, CE and CSA.

## 2.18 CRITICAL AIR FLOW INSTALLATION

- A. The FMCS Agency shall install all routers and repeaters in an accessible location in or around the designated OR room.
- B. The FMCS Agency shall install an appropriately sized and fused 24 Vac transformer suitable for NEC Class II wiring.
- C. All cable shall be furnished and installed by the FMCS Agency. The FMCS Agency shall terminate and connect all cables as required. The FMCS Agency shall utilize cables specifically recommended by the laboratory airflow controls supplier.

- D. Division 23 shall install all airflow control devices in the ductwork and shall connect all airflow control valve linkages.
- E. Division 23 shall provide and install all reheat coils and transitions.
- F. Division 23 shall provide and install insulation as required.
- G. Each pressurization zone shall have either a dedicated, single-phase primary circuit or a secondary circuit disconnect.

## 2.19 SYSTEM START-UP AND TRAINING

- A. System start-up shall be provided by a factory-authorized representative of the critical airflow control system manufacturer. Start-up shall include calibrating the fume hood monitor and any combination sash sensing equipment, as required. Start-up shall also provide electronic verification of airflow (fume hood exhaust, supply, make-up, general exhaust or return), system programming and integration to BAS system.
- B. The Division 23 shall be responsible for final verification and reporting of all airflows
- C. The critical airflow control system supplier shall furnish a minimum of eight hours of owner training by factory trained and certified personnel. The training will provide an overview of the job specific airflow control components, verification of initial fume hood monitor calibration, general procedures for verifying airflows of air valves and general troubleshooting procedures. The class will also show owner personnel step to replacing and reprogramming valves.
- D. Operation and maintenance manuals, including as-built wiring diagrams and component lists, shall be provided for each training attendee.

## 2.20 SYSTEM COMMISSIONING

- A. The FMCS Agency shall provide a trained system technician to assist in the commissioning of the critical air flow systems as described in sections 230800 and 019113.

## 2.21 PROJECT MANAGEMENT

- A. Provide a manager who shall, as part of his duties, be responsible for the following activities:
  - 1. Coordination between the FMCS Agency and all other trades, owner, local authorities and the design team.
  - 2. Scheduling of manpower, material delivery, equipment installation and checkout.
  - 3. Maintenance of construction records such as project scheduling and manpower planning and AutoCAD or Visio for project co-ordination and as-built drawings.
  - 4. Coordination/single point of contact.

## PART 3 - INSTALLATION

### 3.1 INSTALLATION METHODS

- A. Install systems and materials in accordance with manufacturer's instructions, rough-in drawings and equipment details. Install electrical components and use electrical products complying with requirements of applicable Division 26000 sections of these specifications.
  - 1. Division 23 is required to deliver a functionally complete operating building. Provide unconditional one-year parts and service warranty. Warranty period commences when architectural substantial completion has been achieved and all the BMS controls commissioning issues have been resolved. At that time, a completion certificate will be issued by the Cx agent.
- B. The term "control wiring" is defined to include providing of wire, conduit, and miscellaneous materials as required for mounting and connecting electric or electronic control devices.
- C. All exposed wiring, low and line voltage subject to mechanical damage, shall be run in conduit. Line and low voltage wiring shall be run in separate conduits. Concealed but accessible wiring, except in mechanical rooms and areas where other conduit and piping are exposed shall run in UL plenum rated cable as approved by local codes unless expressly restricted by requirements in Division 26000 specification. Control wiring below 8 feet in Mechanical Rooms and areas exposed to severe physical damage (i.e. loading dock, corridors subject to carts, forklifts, etc.) may be run in EMT conduit in lieu of rigid conduit as required in Section 260533.
- D. All controllers, relays, transducers, etc., required for stand-alone control shall be housed in a NEMA 1 enclosure with a lockable door.
- E. All field installed wiring for smoke control stairwell pressurization shall meet 2 hour NEC and IBC requirements

### 3.2 SYSTEM ACCEPTANCE

- A. General: The system installation shall be complete and tested for proper operation prior to acceptance testing for the Owner's authorized representative. A letter shall be submitted to the Architect requesting system acceptance. This letter shall certify all controls are installed and the software programs have been completely exercised for proper equipment operation. Acceptance testing will commence at a mutually agreeable time within ten (10) calendar days of request. When the field test procedures have been demonstrated to the Owner's representative, the system will be accepted. The warranty period will start at this time.
- B. Field Equipment Test Procedures: DDC control panels shall be demonstrated via a functional end-to-end test. Such that:
  - 1. All output channels shall be commanded (on/off, stop/start, adjust, etc.) and their operation verified.

2. All analog input channels shall be verified for proper operation.
  3. All digital input channels shall be verified by changing the state of the field device and observing the appropriate change of displayed value.
  4. If a point should fail testing, perform necessary repair action and retest failed point and all interlocked points.
  5. Automatic control operation shall be verified by introducing an error into the system and observing the proper corrective system response.
  6. Selected time and set point schedules shall be verified by changing the schedule and observing the correct response on the controlled outputs.
- C. As-Built Documentation: After a successful acceptance demonstration, Division 23 shall submit as-built drawings of the completed project for final approval. After receiving final approval, supply "6" complete 11x17 as-built drawing sets, together with AutoCAD or Visio diskettes to the owner.
- D. Operation and Maintenance Manuals: Submit four copies of operation and maintenance manuals. Include the following.
1. Manufacturer's catalog data and specifications on sensors, transmitters, controllers, control valves, damper actuators, gauges, indicators, terminals, and any miscellaneous components used in the system.
  2. An operator's manual that will include detailed instructions for all operations of the system.
  3. An operator's reference table listing the addresses of all connected input points and output points. Settings shall be shown where applicable.
  4. A copy of the warranty/guarantee.
  5. Operating and maintenance cautions and instructions.

### 3.3 TRAINING

- A. Division 23 shall provide to the engineer a training class outline prior to any scheduled training.
- B. Factory trained control engineers and technicians shall provide 10 training sessions (4 Hrs each) for the Owner's personnel.
- C. The course shall include instruction on specific systems and instructions for operating the installed system to include as a minimum:
  1. HVAC system overview

2. Operation of control system
3. Function of each component
4. System operating procedures
5. Programming procedures
6. Maintenance procedures

#### 3.4 WARRANTY/GUARANTEE

- A. The control system shall be warranted/guaranteed to be free from defects in both material and workmanship for a period of twelve (12) months of normal use and service. This warranty/guarantee shall become effective the date the owner accepts or receives beneficial use of the system as defined by Utah state law.

#### PART 4 SEQUENCE OF OPERATIONS

- 4.1 Refer to construction drawings for sequence of operations and points list.

END OF SECTION 23 0900

## SECTION 23 2113 - HYDRONIC PIPING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes pipe and fitting materials and joining methods for the following:

1. Hot-water heating piping.
2. Chilled-water piping.
3. Condensate-drain piping.
4. Air-vent piping.
5. Dielectric fittings.

#### 1.3 SEISMIC REQUIREMENTS

- A. All other components shall be assigned a component importance factor,  $I_p$ , equal to 1.0.
- B. Seismic Performance: Pipe hangers and supports shall withstand the effects of earthquake motions determined according to SEI/ASCE 7 and with the requirements specified in Division 23 Section "Vibration and Seismic Controls for HVAC."
  1. For piping with a seismic importance factor of 1.0 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified."
  2. For piping with a seismic importance factor of 1.5 the term "withstand" means "the system will remain in place without separation of any parts when subjected to the seismic forces specified and the system will be fully operational after the seismic event."

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of the following:
  1. Steel pipe and fittings.
  2. Copper pipe, tubing and fittings.
  3. Dielectric fittings.
- B. LEED Submittals:

1. Product Data for Credit IEQ 4.1: For solvent cements and adhesive primers, documentation including printed statement of VOC content.
2. Laboratory Test Reports for Credit IEQ 4.1: For solvent cements and adhesive primers, documentation indicating that products comply with the testing and product requirements of the California Department of Public Health's (formerly, the California Health Services') "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."

C. Delegated-Design Submittal:

1. Design calculations and detailed fabrication and assembly of pipe anchors and alignment guides, hangers and supports for multiple pipes, expansion joints and loops, and attachments of the same to the building structure.
2. Locations of pipe anchors and alignment guides and expansion joints and loops.
3. Locations of and details for penetrations, including sleeves and sleeve seals for exterior walls, floors, basement, and foundation walls.

1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Piping layout, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
1. Suspended ceiling components.
  2. Other building services.
  3. Structural members.
- B. Qualification Data: For Installer.
- C. Welding certificates.
- D. Field quality-control reports: Written reports as specified in Part 3 of this section including:
1. Test procedures used.
  2. Test results showing compliance with specified requirements.
  3. Failed test results with corrective action taken to achieve compliance with specified requirements.

1.6 QUALITY ASSURANCE

- A. Steel Support Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- B. Pipe Welding: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code: Section IX.
1. Comply with ASME B31.9, "Building Services Piping," for materials, products, and installation.



2. Certify that each welder has passed AWS qualification tests for welding processes involved and that certification is current.

#### 1.7 COORDINATION

- A. Coordinate layout and installation of hydronic piping and suspension system components with other construction, including light fixtures, HVAC equipment, fire-suppression-system components, and partition assemblies.
- B. Coordinate pipe sleeve installations for foundation wall penetrations.
- C. Coordinate piping installation with roof curbs, equipment supports, and roof penetrations. Roof specialties are specified in Division 07 Sections.
- D. Coordinate pipe fitting pressure classes with products specified in related sections.
- E. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into base. Concrete, reinforcement, and formwork requirements are specified in Division 03 Sections.
- F. Coordinate installation of pipe sleeves for penetrations through exterior walls and floor assemblies. Coordinate with requirements for firestopping specified in Division 07 Section "Penetration Firestopping" for fire and smoke wall and floor assemblies.

### PART 2 - PRODUCTS

#### 2.1 COPPER TUBE AND FITTINGS

- A. Drawn-Temper Copper Tubing: ASTM B 88, Type L.
- B. Grooved, Mechanical-Joint, Wrought-Copper Fittings: ASME B16.22.
  1. Grooved-End Copper Fittings: ASTM B 75, copper tube or ASTM B 584, bronze casting.
  2. Grooved-End-Tube Couplings: Coupling housings shall be cast with offsetting, angle-pattern bolt pads to provide joint rigidity and support and hanging in accordance with ANSI B31.1 and B31.9. Ductile-iron housing with keys matching pipe and fitting grooves, EPDM gasket rated for minimum 230 deg F without use of special lubricants. For use with housing, and ASTM A449 electroplated steel nuts and bolts.

#### 2.2 STEEL PIPE AND FITTINGS

- A. Steel Pipe: ASTM A 53, black steel with plain ends; welded and seamless, Grade B, and wall thickness as indicated in "Piping Applications" Article.
- B. Cast-Iron Threaded Fittings: ASME B16.4; Classes 125 and 250 as indicated in "Piping Applications" Article.

- C. Malleable-Iron Threaded Fittings: ASME B16.3, Classes 150 and 300 as indicated in "Piping Applications" Article.
- D. Malleable-Iron Unions: ASME B16.39; Classes 150, 250, and 300 as indicated in "Piping Applications" Article.
- E. Cast-Iron Pipe Flanges and Flanged Fittings: ASME B16.1, Classes 25, 125, and 250; raised ground face, and bolt holes spot faced as indicated in "Piping Applications" Article.
- F. Wrought-Steel Fittings: ASTM A 234, wall thickness to match adjoining pipe.
- G. Wrought Cast- and Forged-Steel Flanges and Flanged Fittings: ASME B16.5, including bolts, nuts, and gaskets of the following material group, end connections, and facings:
  - 1. Material Group: 1.1.
  - 2. End Connections: Butt welding.
  - 3. Facings: Raised face.
- H. Forged Steel "Olet" Type Fittings, Welding, Socket-Welding and Threaded: ASME B16.11 and ASTM A105.
  - 1. Welding Filler Metals: Comply with AWS D10.12M/D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.
- I. Steel Pipe Nipples: ASTM A 733, made of same materials and wall thicknesses as pipe in which they are installed.
- J. Grooved Mechanical-Joint Fittings and Couplings:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by the following provide products by one of the following:
    - a. Victaulic Company.
    - b. Anvil International, Inc.
    - c. Tyco-Grinnel
  - 2. Joint Fittings: ASTM A 536, Grade 65-45-12 ductile iron; ASTM A 53, Type F, E, or S, Grade B factory-fabricated steel; or ASTM A 234, Grade WPB steel fittings with grooves or shoulders designed and constructed to accept grooved-end couplings.
  - 3. Couplings: Two Ductile- housing and synthetic rubber gasket of central cavity pressure-responsive design; with ASTM A449 electroplated steel nuts and bolts to secure grooved pipe and fittings. Couplings shall comply with ASTM F1476 Standard Specification for the Performance of Gasketed Mechanical Couplings for Use in Piping Applications.
    - a. Rigid Type: Coupling housings shall be cast with offsetting, angle-pattern bolt pads to provide joint rigidity and support and hanging in accordance with ANSI B31.1 and B31.9.
    - b. Gasket: High temperature EPDM gasket, suitable for water service to +250 deg F, without use of special lubricants.

- c. Flexible Type: For use in locations where vibration attenuation and stress relief are required, and for the elimination of flexible connectors.
- d. 14" and Larger: Two –segment coupling, with lead-in chamfer on housing key and a wide-width gasket having a center-leg.
- 4. Combinations of grooved mechanical-joint couplings and short nipples may also be used.

## 2.3 JOINING MATERIALS

- A. Pipe-Flange Gasket Materials: Suitable for chemical and thermal conditions of piping system contents.
  - 1. ASME B16.21, nonmetallic, flat, asbestos free, 1/8-inch (3.2-mm) maximum thickness unless otherwise indicated.
    - a. Full-Face Type: For flat-face, Class 125, cast-iron and cast-bronze flanges.
    - b. Narrow-Face Type: For raised-face, Class 250, cast-iron and steel flanges.
- B. Flange Bolts and Nuts: ASME B18.2.1, carbon steel, unless otherwise indicated.
- C. Solder Filler Metals: ASTM B 32, lead-free alloys. Include water-flushable flux according to ASTM B 813.
- D. Brazing Filler Metals: AWS A5.8, BCuP Series, copper-phosphorus alloys for joining copper with copper; or BAg-1, silver alloy for joining copper with bronze or steel. Use of flux is required in all brazing applications. The flux used is to be a black brazing flux that does not contain boric acid and conforms to AWS A5.31 class FB3-C.
- E. Welding Filler Metals: Comply with AWS D10.12M/D10.12 for welding materials appropriate for wall thickness and chemical analysis of steel pipe being welded.

## 2.4 DIELECTRIC FITTINGS

- A. General: Assembly or fitting with insulating material isolating joined dissimilar metals, to prevent galvanic action and stop corrosion.
  - 1. Manufacturers:
    - a. Advance Products & Systems, Inc.
    - b. Calpico, Inc. Capitol Manufacturing Co.
    - c. Capitol Manufacturing Company.
    - d. Central Plastics Company.
    - e. Elster Perfection.
    - f. Grinnell Mechanical Products.
    - g. Matco-Norca.
    - h. Pipeline Seal and Insulator, Inc.
    - i. Precision Plumbing Products, Inc.
    - j. Victaulic Company.
    - k. Watts Regulator Co.
    - l. Zurn Industries, LLC.

- B. Description: Combination of copper alloy and ferrous; threaded, solder, plain, and weld-neck end types and matching piping system materials.
- C. Insulating Material: Suitable for system fluid, pressure, and temperature.
- D. End Connections: Threaded, or flanged.
- E. Dielectric Couplings: Galvanized-steel coupling with inert and noncorrosive, thermoplastic lining; threaded ends; and 300-psig minimum working pressure at 225 deg F.
- F. Dielectric Nipples or Waterways: Electroplated steel with inert and noncorrosive, thermoplastic lining; plain, threaded, or grooved ends; and 300-psig minimum working pressure at 225 deg F.

### PART 3 - EXECUTION

#### 3.1 PIPING APPLICATIONS

- A. Hot-water heating piping, aboveground, NPS 2 and smaller shall be any of the following:
  - 1. Type L drawn-temper copper tubing, wrought-copper fittings, and soldered joints.
  - 2. Schedule 40, Grade B, Type 96 steel pipe; Class 125, cast-iron fittings; cast-iron flanges and flange fittings; and threaded joints.
- B. Hot-water heating piping, aboveground, NPS 2-1/2 and larger, shall be any of the following:
  - 1. Type L, drawn-temper copper tubing, wrought-copper fittings, and soldered joints.
  - 2. Schedule 40 steel pipe, wrought-steel fittings and wrought-cast or forged-steel flanges and flange fittings, and welded and flanged joints.
  - 3. Schedule 40 steel pipe; grooved, mechanical joint coupling and fittings; and grooved, mechanical joints.
- C. Chilled-water piping, aboveground, NPS 2 and smaller, shall be any of the following:
  - 1. Type L, drawn-temper copper tubing, wrought-copper fittings, and soldered joints.
  - 2. Schedule 40, Grade B, Type 96 steel pipe; Class 125, cast-iron fittings; cast-iron flanges and flange fittings; and threaded joints.
- D. Chilled-water piping, aboveground, NPS 2-1/2 and larger, shall be any of the following:
  - 1. Type L, drawn-temper copper tubing, wrought-copper fittings, and soldered joints.
  - 2. Schedule 40 steel pipe, wrought-steel fittings and wrought-cast or forged-steel flanges and flange fittings, and welded and flanged joints.
  - 3. Schedule 40 steel pipe; grooved, mechanical joint coupling and fittings; and grooved, mechanical joints.
- E. Condensate-drain piping shall be the following:

1. Type M, drawn-temper copper tubing, wrought-copper fittings, and soldered joints.

F. Air-Vent Piping:

1. Inlet: Same as service where installed with metal-to-plastic transition fittings for plastic piping systems according to piping manufacturer's written instructions.
2. Outlet: Type K, annealed-temper copper tubing with soldered or flared joints.

- G. Safety-Valve-Inlet and -Outlet Piping for Hot-Water Piping: Same materials and joining methods as for piping specified for the service in which safety valve is installed with metal-to-plastic transition fittings for plastic piping systems according to piping manufacturer's written instructions.

### 3.2 PIPING INSTALLATIONS

A. PRE-WORK / PRE-REQUISITES

1. Drawing plans, schematics, and diagrams indicate general location and arrangement of piping systems. Install piping as indicated unless deviations to layout are approved on Coordination Drawings.
2. The Contractor shall study the architectural, structural, mechanical, electrical and other drawings to eliminate conflict of piping with other structure lighting or other services.

B. CONDITION

1. All installed pipe lines shall be free from dents, scars, and burrs, with ends reamed smooth.
2. All piping shall be clean and free from acids and loose dirt when installed and shall be kept clean during the completion of the installation.
3. Install piping free of sags and bends.
4. All installed pipe lines shall remain straight against strains tending to cause distortion during system operation. The contractor shall make proper allowance for pipe line expansion and contraction so that no unsightly distortion, noise, damage or improper operation results therefrom.

C. SELECTION

1. Select system components with pressure rating equal to or greater than system operating pressure.
2. No street type fittings shall be used.
3. No short nipples shall be used except at drain valves.
4. Plugs of rags, wools, cottons, waste, or similar materials may not be used for plugging.

D. ROUTING/ARRANGEMENT

1. Piping installations shall be neatly organized.
2. Install piping in concealed locations unless otherwise indicated and except in equipment rooms and service areas.
3. Install groups of pipes parallel to each other.
4. Install piping spaced to permit application of insulation.
5. Install piping parallel and spaced to permit the servicing of valves.
6. Install piping indicated to be exposed and piping in equipment rooms and service areas at right angles or parallel to building walls or axis of the building.
7. Diagonal runs are prohibited unless specifically indicated otherwise.
8. Install fittings for all changes in direction.
9. No piping shall be run above any electrical panels, electrical equipment or access clearances for electrical for electrical panels or equipment. No piping shall be allowed to run through any electrical rooms.
10. Piping shall be arranged, placed and installed to facilitate equipment maintenance and shall be so arranged to not interfere with the installation of the air-conditioning equipment, ducts, or the removal of other equipment or devices. All specialties shall be so placed to permit easy operation and access.
11. All piping shall be so installed to insure noiseless circulation.
12. Install fittings for all branch connections.
13. Unless otherwise indicated, install branch connections to mains using [mechanically formed] tee fittings or forged steel branch fittings in main pipe, with the branch connected to the bottom of the main pipe.
14. For up-feed risers, connect the branch to the top of the main pipe.
15. Forged branch fittings shall be installed per the manufacturer's recommendations.

E. ACCESS / ARRANGEMENT

1. Install piping above accessible ceilings to allow sufficient space for ceiling panel removal. All piping shall be so arranged to not block access to manholes, access openings, etc.
2. Install piping at indicated slopes. If not indicated, install piping at a uniform grade of 0.2 percent where possible, upward in direction of flow. Traps are to be avoided where-ever possible.

3. Reduce pipe sizes using eccentric reducer fitting installed with level side up.
4. When insulated pipes are supported by a roller hanger they shall be protected from damage by suitable pipe covering protection saddles. Saddles shall support pipe on roller and shall be packed with insulation.
5. Install valves according to Division 23 Section "General-Duty Valves for HVAC Piping."
6. Install unions in piping, NPS 2 and smaller, adjacent to valves, at final connections of equipment, at each coil on all sides of automatic valves where valves do not have union connections, elsewhere as indicated, and wherever necessary to prevent undue difficulty in making repairs or replacement. Unions are not required at flanged connections.
7. Install flanges in piping, NPS 2-1/2 and larger, at final connections of equipment and elsewhere as indicated. Install flanges on valves, apparatus, and equipment having 2 ½ inch NPS and larger connections. Flanges or unions as applicable for the type of piping specified, shall be provided in the piping at connections to all items of equipment.
8. Install shutoff valve immediately upstream of each dielectric fitting. Install dielectric coupling and nipple fittings to connect piping materials of dissimilar metals.
9. Comply with requirements in Division 23 Section "Expansion Fittings and Loops for HVAC Piping" for installation of expansion loops, expansion joints, anchors, and pipe alignment guides. Anchor piping for proper direction of expansion and contraction.
10. Install sleeves for piping penetrations of walls, ceilings, and floors. Comply with requirements for sleeves specified in Division 23 Section "Sleeves and Sleeve Seals for HVAC Piping."
11. Install sleeve seals for piping penetrations of concrete walls and slabs. Comply with requirements for sleeve seals specified in Division 23 Section "Sleeves and Sleeve Seals for HVAC Piping."
12. Install escutcheons for piping penetrations of walls, ceilings, and floors. Comply with requirements for escutcheons specified in Division 23 Section "Escutcheons for HVAC Piping."
13. Install strainers on supply side of each control valve, pressure-reducing valve, solenoid valve, in-line pump, and elsewhere as indicated. Install NPS ¾) nipple and ball valve in blow-down connection of strainers NPS 2) and larger. Match size of strainer blow-off connection for strainers smaller than NPS 2).
14. Install flexible connectors at inlet and discharge connections to pumps (except inline pumps) and other vibration-producing equipment.
15. Polypropylene pipe in or passing through plenums must be fire wrapped or installed in a metal conduit.

F. DRAINAGE

1. Drain valves shall be installed at all low points in all piping systems to allow for complete drainage of piping systems.
2. Install drains, consisting of a tee fitting, NPS 3/4 ball valve, and short NPS 3/4 threaded nipple with cap, at low points in piping system mains and elsewhere as required for system drainage.
3. All piping systems shall be installed so that they can be easily drained by means of drainage of low points of all piping without disconnecting pipe.
4. If not specifically indicated on the drawings, the frequency of draining shall determine whether drain caps, plugs, cocks, or valves are to be used.

G. IDENTIFICATION

1. Comply with requirements in Division 23 Section "Identification for HVAC Piping and Equipment" for identifying piping.

3.3 DIELECTRIC FITTING INSTALLATION

A. Make connections according to the following, unless otherwise indicated:

1. Install dielectric nipples or waterways in piping NPS 2 and smaller, adjacent to each valve and at final connection to each piece of equipment.
2. Install waterways, in piping NPS 2-1/2 and larger, adjacent to flanged valves and at final connection to each piece of equipment.
3. Install Dielectric Fittings into Hydronic Piping Systems: Install dielectric nipples, waterways or couplings to connect piping materials of dissimilar metals.
4. End Connections: Threaded, or flanged.

3.4 HANGERS AND SUPPORTS

- A. Comply with requirements in Division 23 Section "Hangers and Supports for HVAC Piping and Equipment" for hanger, support, and anchor devices. Comply with the following requirements for maximum spacing of supports.
- B. Comply with requirements in Division 23 Section "Vibration and Seismic Controls for HVAC" for seismic restraints.
- C. Steel roof deck shall not be used to support loads from piping, ductwork or equipment, unless noted otherwise. Hanger loads less than 50 lbs. may be hung from the steel roof deck in cases when hanging from the steel roof deck cannot be avoided; the attachment method must distribute the load across the deck as approved by the Structural Engineer.
- D. Install the following pipe attachments:



1. Adjustable steel clevis hangers for individual horizontal piping less than 20 feet long.
  2. Adjustable roller hangers and spring hangers for individual horizontal piping 20 feet or longer.
  3. Pipe Roller: MSS SP-58, Type 44 for multiple horizontal piping 20 feet or longer, supported on a trapeze.
  4. Spring hangers to support vertical runs.
  5. Provide copper-clad hangers and supports for hangers and supports in direct contact with copper pipe.
  6. On plastic pipe, install pads or cushions on bearing surfaces to prevent hanger from scratching pipe.
- E. Install hangers for steel piping with the following maximum spacing and minimum rod sizes:
1. NPS 3/4: Maximum span, 7 feet; minimum rod size, 3/8 inch.
  2. NPS 1: Maximum span, 7 feet; minimum rod size, 3/8 inch.
  3. NPS 1-1/2: Maximum span, 9 feet; minimum rod size, 3/8 inch.
  4. NPS 2: Maximum span, 10 feet; minimum rod size, 3/8 inch.
  5. NPS 2-1/2: Maximum span, 11 feet; minimum rod size, 1/2 inch.
  6. NPS 3 and Larger: Maximum span, 12 feet; minimum rod size, 1/2 inch.
- F. Install hangers for drawn-temper copper piping with the following maximum spacing and minimum rod sizes:
1. NPS 3/4: Maximum span, 5 feet; minimum rod size, 1/4 inch.
  2. NPS 1: Maximum span, 6 feet; minimum rod size, 1/4 inch.
  3. NPS 1-1/4: Maximum span, 7 feet; minimum rod size, 3/8 inch.
  4. NPS 1-1/2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
  5. NPS 2: Maximum span, 8 feet; minimum rod size, 3/8 inch.
  6. NPS 2-1/2: Maximum span, 9 feet; minimum rod size, 3/8 inch.
  7. NPS 3 and Larger: Maximum span, 10 feet; minimum rod size, 3/8 inch.
- G. Fiberglass Piping Hanger Spacing: Space hangers according to pipe manufacturer's written instructions for service conditions. Avoid point loading. Space and install hangers with the fewest practical rigid anchor points.
- H. Support vertical runs at roof, at each floor, and at 10-foot intervals between floors.
- I. Support piping and tubing not listed in this article according to MSS SP-69 and manufacturer's written instructions.
- 3.5 PIPE JOINT CONSTRUCTION
- A. Ream ends of pipes and tubes and remove burrs. Bevel plain ends of steel pipe.
- B. Remove scale, slag, dirt, and debris from inside and outside of pipe and fittings before assembly.

- C. Soldered Joints: Apply ASTM B 813, water-flushable flux, unless otherwise indicated, to tube end. Construct joints according to ASTM B 828 or CDA's "Copper Tube Handbook," using lead-free solder alloy complying with ASTM B 32.
- D. Brazed Joints: Construct joints according to AWS's "Brazing Handbook," "Pipe and Tube" Chapter, using copper-phosphorus brazing filler metal complying with AWS A5.8.
- E. Threaded Joints: Thread pipe with tapered pipe threads according to ASME B1.20.1. Cut threads full and clean using sharp dies. Ream threaded pipe ends to remove burrs and restore full ID. Join pipe fittings and valves as follows:
  - 1. Apply appropriate tape or thread compound to external pipe threads unless dry seal threading is specified.
  - 2. Damaged Threads: Do not use pipe or pipe fittings with threads that are corroded or damaged. Do not use pipe sections that have cracked or open welds.
- F. Welded Joints: Construct joints according to AWS D10.12M/D10.12, using qualified processes and welding operators according to "Quality Assurance" Article.
- G. Flanged Joints: Select appropriate gasket material, size, type, and thickness for service application. Install gasket concentrically positioned. Use suitable lubricants on bolt threads.
- H. Grooved Joints: Assemble joints with coupling and gasket, lubricant, and bolts.
  - 1. Cut or roll grooves in ends of pipe based on pipe and coupling manufacturer's written instructions for pipe wall thickness. Use grooved-end fittings and rigid, grooved-end-pipe couplings.
  - 2. Installed in accordance with the manufacturer's written recommendations.
  - 3. Ends shall be clean and free from indentations, projections or roll marks.
  - 4. The gasket shall be molded and produced by the coupling manufacturer of an elastomer suitable for the intended service.
  - 5. Unions and flanges for servicing and disconnect are not required in installations using grooved joint couplings.
  - 6. Training: The coupling manufacturer's factory-direct trained representative shall provide on-site training for the contractor's field personnel in the use of grooving tools and installation of product. The representative shall periodically visit the job site to ensure best practices in grooved product installation are being followed. The distributor's representative will not be acceptable.

### 3.6 TERMINAL EQUIPMENT CONNECTIONS

- A. Sizes for supply and return piping connections shall be the same as or larger than equipment connections.
- B. Install control valves in accessible locations close to connected equipment.

### 3.7 FIELD QUALITY CONTROL

- A. Prepare hydronic piping according to ASME B31.9 and as follows:

1. Leave joints, including welds, uninsulated and exposed for examination during test.
2. Provide temporary restraints for expansion joints that cannot sustain reactions due to test pressure. If temporary restraints are impractical, isolate expansion joints from testing.
3. Flush hydronic piping systems with clean water; then remove and clean or replace strainer screens.
4. Isolate equipment from piping. If a valve is used to isolate equipment, its closure shall be capable of sealing against test pressure without damage to valve. Install blinds in flanged joints to isolate equipment.
5. Install safety valve, set at a pressure no more than one-third higher than test pressure, to protect against damage by expanding liquid or other source of overpressure during test.

B. Perform the following tests on hydronic piping:

1. Use ambient temperature water as a testing medium unless there is risk of damage due to freezing. Another liquid that is safe for workers and compatible with piping may be used.
2. While filling system, use vents installed at high points of system to release air. Use drains installed at low points for complete draining of test liquid.
3. Isolate expansion tanks and determine that hydronic system is full of water.
4. Subject piping system to hydrostatic test pressure that is not less than 1.5 times the system's working pressure. Test pressure shall not exceed maximum pressure for any vessel, pump, valve, or other component in system under test. Verify that stress due to pressure at bottom of vertical runs does not exceed 90 percent of specified minimum yield strength or 1.7 times the "SE" value in Appendix A in ASME B31.9, "Building Services Piping."
5. After hydrostatic test pressure has been applied for at least 10 minutes, examine piping, joints, and connections for leakage. Eliminate leaks by tightening, repairing, or replacing components, and repeat hydrostatic test until there are no leaks.
6. Prepare written report of testing.

C. Perform the following before operating the system:

1. Open manual valves fully.
2. Inspect pumps for proper rotation.
3. Set makeup pressure-reducing valves for required system pressure.
4. Inspect air vents at high points of system and determine if all are installed and operating freely (automatic type), or bleed air completely (manual type).
5. Set temperature controls so all coils are calling for full flow.
6. Inspect and set operating temperatures of hydronic equipment, such as boilers, chillers, cooling towers, to specified values.
7. Verify lubrication of motors and bearings.

END OF SECTION 23 2113

## SECTION 23 2116 - HYDRONIC PIPING SPECIALTIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes special-duty valves and specialties for the following:
  - 1. Hot-water heating piping.
  - 2. Chilled-water piping.
  - 3. Condensate-drain piping.
  - 4. Air-vent piping.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of the following:
  - 1. Valves: Include flow and pressure drop curves based on manufacturer's testing for calibrated-orifice balancing valves and automatic flow-control valves.
  - 2. Air-control devices.
  - 3. Hydronic specialties.

#### 1.4 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For air-control devices, hydronic specialties, and special-duty valves to include in emergency, operation, and maintenance manuals.

#### 1.5 QUALITY ASSURANCE

- A. Pipe Welding: Qualify procedures and operators according to ASME Boiler and Pressure Vessel Code: Section IX.
  - 1. Safety valves and pressure vessels shall bear the appropriate ASME label. Fabricate and stamp air separators and expansion tanks to comply with ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.

## PART 2 - PRODUCTS

### 2.1 VALVES

- A. Globe, Check, Ball, and Butterfly Valves: Comply with requirements specified in Division 23 Section "General-Duty Valves for HVAC Piping." Gate valves are not allowed on this project.
- B. Automatic Temperature-Control Valves, Actuators, and Sensors: Comply with requirements specified in Division 23 Section "Instrumentation and Control for HVAC."
- C. Refer to Part 3 "Valve Applications" Article for applications of each valve.
- D. Bronze, Calibrated-Orifice or Venturi, Balancing Valves, NPS 2 and smaller:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Armstrong Pumps, Inc.
    - b. Bell & Gossett Domestic Pump.
    - c. Flow Design Inc.
    - d. Gerand Engineering Co.
    - e. Griswold Controls.
    - f. Taco.
    - g. Tour & Andersson; available through Victaulic Company.
    - h. Tyco-Grinnell
  - 2. Body: Bronze, ball or plug type with calibrated orifice or venturi.
  - 3. Ball: Brass or stainless steel.
  - 4. Plug: Resin.
  - 5. Seat: PTFE.
  - 6. End Connections: Threaded or socket.
  - 7. Pressure Gage Connections: Integral seals for portable differential pressure meter.
  - 8. Handle Style: Lever, with memory stop to retain set position.
  - 9. CWP Rating: Minimum 125 psig.
  - 10. Maximum Operating Temperature: 250 deg F.
- E. Cast-Iron or Steel, Calibrated-Orifice or Venturi, Balancing Valves, NPS 2 ½ and larger:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Amtrol, Inc.
    - b. Armstrong Pumps, Inc.
    - c. Bell & Gossett Domestic Pump.
    - d. Flow Design Inc.
    - e. Gerand Engineering Co.
    - f. Grinnell.

- g. Griswold Controls.
    - h. Taco.
    - i. Tour & Andersson; available through Victaulic Company.
    - j. Spence Engineering Company Inc.
    - k. Watts Regulator Co.
  - 2. Body: Cast-iron or steel body, ball, plug, or globe pattern with calibrated orifice or venturi.
  - 3. Ball: Brass or stainless steel.
  - 4. Stem Seals: EPDM O-rings.
  - 5. Disc: Glass and carbon-filled PTFE.
  - 6. Seat: PTFE.
  - 7. End Connections: Flanged or grooved.
  - 8. Pressure Gage Connections: Integral seals for portable differential pressure meter.
  - 9. Handle Style: Lever, with memory stop to retain set position.
  - 10. CWP Rating: Minimum 125 psig.
  - 11. Maximum Operating Temperature: 250 deg F.
- F. Diaphragm-Operated, Pressure-Reducing Valves: ASME labeled.
- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Amtrol, Inc.
    - b. Armstrong Pumps, Inc.
    - c. Bell & Gossett Domestic Pump.
    - d. Conbraco Industries, Inc.
    - e. Spence Engineering Company, Inc.
    - f. Watts Regulator Co.
  - 2. Body: Bronze or brass.
  - 3. Disc: Glass and carbon-filled PTFE.
  - 4. Seat: Brass.
  - 5. Stem Seals: EPDM O-rings.
  - 6. Diaphragm: EPT.
  - 7. Low inlet-pressure check valve.
  - 8. Inlet Strainer: Brass, removable without system shutdown.
  - 9. Valve Seat and Stem: Noncorrosive.
  - 10. Valve Size, Capacity, and Operating Pressure: Selected to suit system in which installed, with operating pressure and capacity factory set and field adjustable.
- G. Diaphragm-Operated Safety Valves: ASME labeled.
- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Amtrol, Inc.
    - b. Armstrong Pumps, Inc.
    - c. Bell & Gossett Domestic Pump.
    - d. Conbraco Industries, Inc.

- e. Kunkle.
- f. Spence Engineering Company, Inc.
- 2. Body: Bronze or brass.
- 3. Disc: Glass and carbon-filled PTFE.
- 4. Seat: Brass.
- 5. Stem Seals: EPDM O-rings.
- 6. Diaphragm: EPT.
- 7. Wetted, Internal Work Parts: Brass and rubber.
- 8. Inlet Strainer: Brass, removable without system shutdown.
- 9. Valve Seat and Stem: Noncorrosive.
- 10. Valve Size, Capacity, and Operating Pressure: Comply with ASME Boiler and Pressure Vessel Code: Section IV, and selected to suit system in which installed, with operating pressure and capacity factory set and field adjustable.

H. Automatic Flow-Control Valves:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Armstrong Pumps, Inc.
  - b. Bell & Gossett Domestic Pump.
  - c. Flow Design Inc.
  - d. Griswold Controls.
  - e. Taco.
  - f. Nexus.
- 2. Body: Brass or ferrous metal.
- 3. Piston and Spring Assembly: Tamper proof, self-cleaning, and removable, for inspections and replacement.
  - a. Corrosion resistant.
- 4. Combination Assemblies: Include bronze or brass-alloy ball valve.
- 5. Identification Tag: Attached by chain and marked with zone identification, valve number, and flow rate.
- 6. Size: Same as pipe in which installed.
- 7. Performance: Maintain constant flow, plus or minus 5 percent over system pressure fluctuations:
  - a. Minimum CWP Rating: 175 psig.
- 8. Maximum Operating Temperature: 200 deg F.
- 9. Fitted with pressure and temperature test valves.
- 10. Equipped with a readout kit including flow meter, probes, hoses, flow charts, and carrying case.

2.2 AIR-CONTROL DEVICES

A. Manual Air Vents:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Amtrol, Inc.
  - b. Armstrong Pumps, Inc.
  - c. Bell & Gossett Domestic Pump.
  - d. Taco, Inc.
2. Body: Bronze.
3. Internal Parts: Nonferrous.
4. Operator: Screwdriver or thumbscrew.
5. Manually operated with ball valve in the down position.
6. Inlet Connection: NPS 1/2.
7. Discharge Connection: NPS 1/8.
8. CWP Rating: 150 psig.
9. Maximum Operating Temperature: 225 deg F.

B. Automatic Air Vents:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Amtrol, Inc.
  - b. Bell & Gossett Domestic Pump.
  - c. Hoffman Specialty ITT; Fluid Handling Div.
  - d. Spirax-Sarco.
  - e. Spirovent.
  - f. Taco, Inc.
  - g. Honeywell-Baukman.
2. Body: Bronze or cast iron.
3. Internal Parts: Nonferrous.
4. Operator: Noncorrosive metal float.
5. Inlet Connection: NPS 1/2.
6. Discharge Connection: NPS 1/4.
7. CWP Rating: 150 psig.
8. Maximum Operating Temperature: 240 deg F.

C. Bladder -Type Expansion Tanks:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Amtrol, Inc.
  - b. Armstrong Pumps, Inc.
  - c. Bell & Gossett Domestic Pump.
  - d. Taco, Inc.
  - e. Zilmet



2. Tank: Welded steel, rated for 125-psig working pressure and 240 deg F maximum operating temperature. Factory test after taps are fabricated and supports installed and are labeled according to ASME Boiler and Pressure Vessel Code: Section VIII, Division 1.
3. Bladder : Securely sealed into tank to separate air charge from system water to maintain required expansion capacity.
4. Air-Charge Fittings: Schrader valve, stainless steel with EPDM seats.
5. Access: Drain fitting and taps for pressure gage.
6. Support:
  - a. Vertical tanks with steel legs or base.
  - b. Horizontal tanks with steel saddles.

D. Tangential-Type Air Separators:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Amtrol, Inc.
  - b. Armstrong Pumps, Inc.
  - c. Bell & Gossett Domestic Pump.
  - d. Taco, Inc.
2. Tank: Welded steel; ASME constructed and labeled for 125-psig minimum working pressure and 240 deg F maximum operating temperature.
3. Air Collector Tube: Perforated stainless steel, constructed to direct released air into expansion tank.
4. Tangential Inlet and Outlet Connections: Threaded for NPS 2 and smaller; flanged connections for NPS 2-1/2 and larger.
5. Blowdown Connection: Threaded.
6. Size: Match system flow capacity.

## 2.3 HYDRONIC PIPING SPECIALTIES

A. Y-Pattern Strainers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Armstrong Machine Works.
  - b. Hoffman Specialty ITT; Fluid Handling Div.
  - c. Metraflex Co.
  - d. Mueller
  - e. Spirax Sarco.
  - f. Trane Co.
  - g. Tyco-Grinnell.
  - h. Tour & Andersson; available through Victaulic Company.
  - i. Watts Regulator Co.

2. Body: ASTM A 126, Class B, cast iron with bolted cover and bottom drain connection.
3. End Connections: Threaded ends for NPS 2 and smaller; flanged ends for NPS 2-1/2 and larger.
4. Strainer Screen: Stainless-steel, or perforated stainless-steel basket:
  - a. 20-mesh strainer.
5. CWP Rating: 125 psig.

B. Basket Strainers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Crane Co.
  - b. Metraflex Co.
  - c. Mueller
  - d. Spirax Sarco.
  - e. Tyco-Grinnell.
  - f. Tour & Andersson; available through Victaulic Company.
2. Body: ASTM A 126, Class B, high-tensile cast iron with bolted cover and bottom drain connection.
3. End Connections: Threaded ends for NPS 2 and smaller; flanged ends for NPS 2-1/2 and larger.
4. Strainer Screen: Perforated stainless-steel basket with 50 percent free area:
  - a. 40-mesh startup strainer.
5. CWP Rating: 125 psig.

C. Stainless-Steel Braided-Corrugated, Flexible Connectors:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Amber-Booth.
  - b. Mason Industries.
  - c. Metraflex Co.
  - d. Flex-Weld.
  - e. Fugate.
  - f. Twin City Hose.
2. Body: 321 Stainless-steel close pitch corrugated hose with woven, flexible, 304 Stainless-steel, protective jacket.
3. End Connections: Flanged, ANSI Class 150 carbon steel
4. Performance: Permanent Offset; 3/8 inch, Intermittent Offset; 1/8 inch.
5. Safe Working Pressure: 175 psig. (For 8 inch diameter)
6. Maximum Operating Temperature: 200 deg F. (For 8 inch diameter)

D. Spherical, Rubber, Flexible Connectors:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Amber-Booth.
  - b. Mason Industries.
  - c. Metraflex Co.
  - d. Flex-Weld.
  - e. Proco.
  - f. Fugate.
  - g. Twin City Hose.
2. Body: Double-sphere fiber-reinforced EPDM rubber body.
3. End Connections: Steel flanges drilled to align with Classes 150 and 300 steel flanges.
4. Performance: Capable of misalignment.
5. CWP Rating: 150 psig.
6. Maximum Operating Temperature: 250 deg F.

E. Diverting Fittings:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. Amtrol, Inc.
  - b. Armstrong Pumps, Inc.
  - c. Bell & Gossett Domestic Pump.
  - d. Taco, Inc.
2. Body: Cast Iron or Wrought Copper
3. Ends: Threaded or Soldered
4. Flow Direction: Indicated on fitting.
5. CWP Rating: 125 psig.
6. Maximum Operating Temperature: 250 deg F.

### PART 3 - EXECUTION

#### 3.1 VALVE APPLICATIONS

- A. Install shut off-duty valves at each branch connection to supply mains and at supply connection to each piece of equipment.
- B. Install calibrated-orifice, balancing valves at each branch connection to return main.
- C. Install calibrated-orifice, balancing valves in the return pipe of each heating or cooling terminal.
- D. Install check valves at each pump discharge and elsewhere as required to control flow direction.
- E. Install safety valves at hot-water generators and elsewhere as required by ASME Boiler and Pressure Vessel Code. Install drip-pan elbow on safety-valve outlet and pipe without valves to the outdoors; pipe drain to nearest floor drain or as indicated on Drawings. Comply with

ASME Boiler and Pressure Vessel Code: Section VIII, Division 1, for installation requirements.

- F. Install pressure-reducing valves at makeup-water connection to regulate system fill pressure.

### 3.2 HYDRONIC SPECIALTIES INSTALLATION

- A. Install manual air vents at high points in piping, at heat-transfer coils, and elsewhere as required for system air venting.
- B. Automatic air vents may cause damage to ceilings and other finished surfaces. Air vents aid in system filling. Air removal after initial startup is accomplished by air separator or boiler dip tube. Manual air vents may be a better solution.
- C. Install automatic air vents at high points of system piping in mechanical equipment rooms only. Install manual vents at heat-transfer coils and elsewhere as required for air venting.

END OF SECTION 23 2116

## SECTION 23 3001 - COMMON DUCT REQUIREMENTS

### PART 1 - GENERAL

#### 1.1 SUMMARY

A. Includes But Not Limited To:

1. General procedures and requirements for ductwork.
2. Repair leaks in ductwork, as identified by smoke test, at no additional cost to Owner.
3. Soundproofing procedures for duct penetrations of walls, ceilings, and floors in mechanical equipment rooms.

B. Related Sections:

1. Division 07: Quality of Acoustic Sealant.
2. Section 23 0500: Common Work Results for HVAC
3. Section 23 0593: Testing Adjusting and Balancing for HVAC.

#### 1.2 SUBMITTALS

A. Samples: Sealer and gauze proposed for sealing ductwork.

B. Quality Assurance / Control:

1. Manufacturer's installation manuals providing detailed instructions on assembly, joint sealing, and system pressure testing for leaks.
2. Specification data on sealer and gauze proposed for sealing ductwork.

#### 1.3 QUALITY ASSURANCE

A. Requirements: Construction details not specifically called out in Contract Documents shall conform to applicable requirements of SMACNA HVAC Duct Construction Standards.

B. Pre-Installation Conference: Schedule conference immediately before installation of ductwork.

## PART 2 - PRODUCTS

- 2.1 Finishes, Where Applicable: Colors as selected by Architect.
- 2.2 Duct Hangers:
  - A. One inch by 18 ga galvanized steel straps or steel rods as shown on Drawings, and spaced not more than 96 inches apart. Do not use wire hangers.
    - 1. Attaching screws at trusses shall be 2 inch No. 10 round head wood screws. Nails not allowed.
    - 2. Attach threaded rod to steel joist with Grinnell Steel washer plate Fig. 60 - ph-1. Double nut connection.
- 2.3 Penetration Soundproofing Materials:
  - A. Insulation for Packing: Fiberglass.
  - B. Calking: Polysulphide.
  - C. Escutcheon Frame: 22 ga galvanized iron 2 inches wide.

## PART 3 - EXECUTION

- 3.1 INSTALLATION
  - A. During installation, protect open ends of ducts by covering with plastic sheet tied in place to prevent entrance of debris and dirt.
  - B. Make necessary allowances and provisions in installation of sheet metal ducts for structural conditions of building. Revisions in layout and configuration may be allowed, with prior written approval of Architect. Maintain required airflows in suggesting revisions.
  - C. Hangers And Supports:
    - 1. Install upper ends of hanger securely to floor or roof construction above by method shown on Drawings.
    - 2. Attach strap hangers to ducts with cadmium-plated screws. Use of pop rivets or other means will not be accepted.
    - 3. Where hangers are secured to forms before concrete slabs are poured, cut off flush all nails, strap ends, and other projections after forms are removed.
    - 4. Secure vertical ducts passing through floors by extending bracing angles to rest firmly on floors without loose blocking or shimming. Support vertical ducts, which do not pass through floors, by using bands bolted to walls, columns, etc. Size, spacing, and method of attachment to vertical ducts shall be same as specified for hanger bands on horizontal ducts.

D. Penetration Soundproofing

1. Pack space between ducts and structure full of fiberglass insulation of sufficient thickness to be wedged tight, allowing space for application of calking.
2. Provide calking at least 2 inches thick between duct and structure on both ends of opening through structure.
3. Provide metal escutcheon on Equipment Room side. Secure escutcheon to wall.

3.2 CLEANING

- A. Clean interior of duct systems before final completion.

3.3 CROSS OVER LADDER

- A. All ductwork and piping at walking level that must be crossed for equipment maintenance and service shall have a cross-over ladder.

END OF SECTION 23 3001

## SECTION 23 3113 - METAL DUCTS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

1. Single-wall rectangular ducts and fittings.
2. Double-wall rectangular ducts and fittings.
3. Single-wall round and flat-oval ducts and fittings.
4. Double-wall round and flat-oval ducts and fittings.
5. Exhaust Air Stacks
6. Guy wires and connectors.
7. Sheet metal materials.
8. Duct liner.
9. Sealants and gaskets.
10. Hangers and supports.

- B. Related Sections:

1. Section 230593 "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing requirements for metal ducts.
2. Section 233119 "HVAC Casings" for factory- and field-fabricated casings for mechanical equipment.
3. Section 233300 "Air Duct Accessories" for dampers, sound-control devices, duct-mounting access doors and panels, turning vanes, and flexible ducts.
4. Section 230713 "Duct Insulation" for duct insulation and fire wrap.

- C. Stacks from the exhaust systems are to be designed per SMACNA guidelines. Use the "Guide for steel stack design and Construction" the latest edition. The outside of the stacks are to be painted with Pota-Pox. 80 series 141 material. Color is to be selected by the architect. Provide guy wires and angle supports. Construction shall be a minimum of 10 gauge and shall be painted on the inside of the stack and on the exterior where the stack is exterior to the building.

#### 1.3 PERFORMANCE REQUIREMENTS

- A. Delegated Duct Design: Duct construction, including sheet metal thicknesses, seam and joint construction, reinforcements, and hangers and supports, shall comply with SMACNA's "HVAC



Duct Construction Standards - Metal and Flexible" and performance requirements and design criteria indicated in "Duct Schedule" Article.

- B. Seismic Performance: Duct hangers and supports shall withstand the effects of earthquake motions determined according to SEI/ASCE 7 and with the requirements specified in Section 230548 "Vibration and Seismic Controls for HVAC."
  - 1. For equipment with a seismic importance factor of 1.0 the term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."
  - 2. For equipment with a seismic importance factor of 1.5 the term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."
- C. Structural Performance: Duct hangers and supports shall withstand the effects of gravity loads and stresses within limits and under conditions described in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"
- D. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of the following products:
  - 1. Liners and adhesives.
  - 2. Sealants and gaskets.
  - 3. Seismic-restraint devices.
- B. LEED Submittals:
  - 1. Product Data for Prerequisite IEQ 1: Documentation indicating that duct systems comply with ASHRAE 62.1, Section 5 - "Systems and Equipment."
  - 2. Product Data for Prerequisite EA 2: Documentation indicating that duct systems comply with ASHRAE/IESNA 90.1, Section 6.4.4 - "HVAC System Construction and Insulation."
  - 3. Leakage Test Report for Prerequisite EA 2: Documentation of work performed for compliance with ASHRAE/IESNA 90.1, Section 6.4.4.2.2 - "Duct Leakage Tests."
  - 4. Duct-Cleaning Test Report for Prerequisite IEQ 1: Documentation of work performed for compliance with ASHRAE 62.1, Section 7.2.4 - "Ventilation System Start-up."
  - 5. Laboratory Test Reports for Credit IEQ 4: For adhesives and sealants, documentation indicating that products comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
  - 6. Product Data for Credit IEQ 4.1: For adhesives and sealants, documentation including printed statement of VOC content.

C. Shop Drawings:

1. Fabrication, assembly, and installation, including plans, elevations, sections, components, and attachments to other work.
2. Factory- and shop-fabricated ducts and fittings.
3. Duct layout indicating sizes, configuration, liner material, and static-pressure classes.
4. Elevation of top of ducts.
5. Dimensions of main duct runs from building grid lines.
6. Fittings.
7. Reinforcement and spacing.
8. Seam and joint construction.
9. Penetrations through fire-rated and other partitions.
10. Equipment installation based on equipment being used on Project.
11. Locations for duct accessories, including dampers, turning vanes, and access doors and panels.
12. Hangers and supports, including methods for duct and building attachment, seismic restraints, and vibration isolation.
13. Duct fabrication shall not begin until shop drawings have been submitted and reviewed by the mechanical engineer.

D. Delegated-Design Submittal:

1. Sheet metal thicknesses.
2. Joint and seam construction and sealing.
3. Reinforcement details and spacing.
4. Materials, fabrication, assembly, and spacing of hangers and supports.
5. Design Calculations: Calculations for selecting hangers and supports.

1.5 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:

1. Duct installation in congested spaces, indicating coordination with general construction, building components, and other building services. Indicate proposed changes to duct layout.
2. Suspended ceiling components.
3. Structural members to which duct will be attached.
4. Size and location of initial access modules for acoustical tile.
5. Penetrations of smoke barriers and fire-rated construction.
6. Items penetrating finished ceiling including, but not limited to the following:
  - a. Lighting fixtures.
  - b. Air outlets and inlets.
  - c. Speakers.
  - d. Sprinklers.
  - e. Access panels.
  - f. Perimeter moldings.

- B. Field quality-control reports.

## 1.6 QUALITY ASSURANCE

- A. Welding Qualifications: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel," for hangers and supports. AWS D9.1M/D9.1, "Sheet Metal Welding Code," for duct joint and seam welding.
- B. Welding Qualifications: Qualify procedures and personnel according to the following:
  - 1. AWS D1.1/D1.1M, "Structural Welding Code - Steel," for hangers and supports.
  - 2. AWS D1.2/D1.2M, "Structural Welding Code - Aluminum," for aluminum supports.
  - 3. AWS D9.1M/D9.1, "Sheet Metal Welding Code," for duct joint and seam welding.
- C. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and System Start-up."
- D. ASHRAE/IESNA Compliance: Applicable requirements in ASHRAE/IESNA 90.1, Section 6.4.4 - "HVAC System Construction and Insulation."

## PART 2 - PRODUCTS

### 2.1 SINGLE-WALL RECTANGULAR DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.
- B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- C. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- D. Duct dimensions shown on drawings are inside clear dimensions.
- E. Elbows, Transitions, Offsets, Branch Connections, and Other Duct Construction: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 4, "Fittings and Other Construction," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

## 2.2 DOUBLE-WALL RECTANGULAR DUCTS AND FITTINGS

- A. Rectangular Ducts: Fabricate ducts with indicated dimensions for the inner duct.
- B. Duct dimensions shown on drawings are inside clear dimensions.
- C. Outer Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" based on indicated static-pressure class unless otherwise indicated.
- D. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- E. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- F. Interstitial Insulation: Fibrous-glass liner complying with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."
  - 1. Maximum Thermal Conductivity: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
  - 2. Install spacers that position the inner duct at uniform distance from outer duct without compressing insulation.
  - 3. Coat insulation with antimicrobial coating.
  - 4. Cover insulation with polyester film complying with UL 181, Class 1.
- G. Interstitial Insulation: Flexible elastomeric duct liner complying with ASTM C 534, Type II for sheet materials, and with NFPA 90A or NFPA 90B.
  - 1. Maximum Thermal Conductivity: 0.25 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
- H. Inner Duct: Minimum 0.028-inch solid sheet steel.
- I. Formed-on Transverse Joints (Flanges): Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-1, "Rectangular Duct/Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- J. Longitudinal Seams: Select seam types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 2-2, "Rectangular Duct/Longitudinal Seams," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

## 2.3 SINGLE-WALL ROUND AND FLAT-OVAL DUCTS AND FITTINGS

- A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.
- B. Duct dimensions shown on drawings are inside clear dimensions.
- C. Flat-Oval Ducts: Indicated dimensions are the duct width (major dimension) and diameter of the round sides connecting the flat portions of the duct (minor dimension).
- D. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
  - 1. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.
- E. Longitudinal Seams: Not allowed.
- F. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

## 2.4 DOUBLE-WALL ROUND AND FLAT-OVAL DUCTS AND FITTINGS

- A. Flat-Oval Ducts: Indicated dimensions are the duct width (major dimension) and diameter of the round sides connecting the flat portions of the duct (minor dimension) of the inner duct.
- B. Duct dimensions shown on drawings are inside clear dimensions.
- C. Outer Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on static-pressure class unless otherwise indicated.
  - 1. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
    - a. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.
  - 2. Longitudinal Seams: Not allowed.

3. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

D. Inner Duct: Minimum 0.028-inch solid sheet steel.

1. Perforated inner ducts exposed to air movement shall not be used in supply air ducts upstream of the following rooms: Operating rooms, trauma rooms, LDR rooms, NICU nurseries, ICU nurseries, positive pressure isolation rooms, cath labs, bone marrow, triage rooms, angiogram rooms, fluoroscopy rooms, linear accelerators, decontamination areas and any invasive procedure rooms where the duct insulation could be a source of contamination.
2. Inner duct shall be solid sheet steel a minimum of 10 feet downstream of humidifiers and/or air washers.

E. Interstitial Insulation: Fibrous-glass liner complying with ASTM C 1071, NFPA 90A, or NFPA 90B; and with NAIMA AH124, "Fibrous Glass Duct Liner Standard."

1. Maximum Thermal Conductivity: 0.27 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.
2. Install spacers that position the inner duct at uniform distance from outer duct without compressing insulation.
3. Coat insulation with antimicrobial coating.
4. Cover insulation with polyester film complying with UL 181, Class 1.

F. Interstitial Insulation: Flexible elastomeric duct liner complying with ASTM C 534, Type II for sheet materials, and with NFPA 90A or NFPA 90B.

1. Maximum Thermal Conductivity: 0.25 Btu x in./h x sq. ft. x deg F at 75 deg F mean temperature.

## 2.5 EXHAUST AIR STACKS

A. General Fabrication Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 3, "Round, Oval, and Flexible Duct," based on indicated static-pressure class unless otherwise indicated.

B. Transverse Joints: Select joint types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-1, "Round Duct Transverse Joints," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."

1. Transverse Joints in Ducts Larger Than 60 Inches in Diameter: Flanged.

C. Longitudinal Seams: Not allowed.

- D. Tees and Laterals: Select types and fabricate according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees," for static-pressure class, applicable sealing requirements, materials involved, duct-support intervals, and other provisions in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- E. Design Wind Loads: 150 mph.
- F. Design for seismic conditions at Project site.
- G. Accessories: Terminations, adjustable roof flashings, storm collars, support assemblies, thimbles, firestop spacers, and fasteners; fabricated from similar materials and designs as duct straight sections.
  - 1. Termination: Antibackdraft damper.
- H. Drain: Provide drain section incorporated into base of stack with trap. Seal depth design to prevent seal blowout at highest estimated static pressure.
- I. Guying and Bracing Materials
  - 1. Cable: Three minimum galvanized or stainless steel, stranded wires of the following thickness: [Four] <Insert number> [stainless steel]
    - a. Minimum Size: 1/4 inch in diameter.
    - b. For ID Sizes 4 to 15 Inches: 5/16 inch.
    - c. For ID Sizes 18 to 24 Inches: 3/8 inch.
    - d. For ID Sizes 27 to 30 Inches: 7/16 inch.
    - e. For ID Sizes 33 to 36 Inches: 1/2 inch.
    - f. For ID Sizes 39 to 48 Inches: 9/16 inch.
    - g. For ID Sizes 51 to 60 Inches: 5/8 inch.
  - 2. Cable Hardware: Provide duct angle ring, turnbuckles, cable loop thimbles, cable clamps and all hardware necessary to brace stack.
  - 3. Pipe: Two galvanized steel, NPS 1-1/4. [Three].
  - 4. Angle Iron: Two galvanized steel, 2 by 2 by 0.25 inch. [Three].

## 2.6 SHEET METAL MATERIALS

- A. General Material Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.
- B. Galvanized Sheet Steel: Comply with ASTM A 653.
  - 1. Galvanized Coating Designation: G90.
  - 2. Finishes for Surfaces Exposed to View: Mill phosphatized.

- C. Carbon-Steel Sheets: Comply with ASTM A 1008, with oiled, matte finish for exposed ducts.
- D. Reinforcement Shapes and Plates: ASTM A 36, steel plates, shapes, and bars; black and galvanized.
  - 1. Where black- and galvanized-steel shapes and plates are used to reinforce aluminum ducts, isolate the different metals with butyl rubber, neoprene, or EPDM gasket materials.
- E. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

## 2.7 DUCT LINER

- A. Reference section 3.12.I.

## 2.8 SEALANT AND GASKETS

- A. General Sealant and Gasket Requirements: Surface-burning characteristics for sealants and gaskets shall be a maximum flame-spread index of 25 and a maximum smoke-developed index of 50 when tested according to UL 723; certified by an NRTL.
- B. Two-Part Tape Sealing System:
  - 1. Tape: Woven cotton fiber impregnated with mineral gypsum and modified acrylic/silicone activator to react exothermically with tape to form hard, durable, airtight seal.
  - 2. Tape Width: 4 inches.
  - 3. Sealant: Modified styrene acrylic.
  - 4. Water resistant.
  - 5. Mold and mildew resistant.
  - 6. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
  - 7. Service: Indoor and outdoor.
  - 8. Service Temperature: Minus 40 to plus 200 deg F.
  - 9. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum.
  - 10. For indoor applications, sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 11. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- C. Water-Based Joint and Seam Sealant:
  - 1. Application Method: Brush on.
  - 2. Solids Content: Minimum 65 percent.



3. Shore A Hardness: Minimum 20.
4. Water resistant.
5. Mold and mildew resistant.
6. VOC: Maximum 75 g/L (less water).
7. Maximum Static-Pressure Class: 10-inch wg, positive and negative.
8. Service: Indoor or outdoor.
9. Substrate: Compatible with galvanized sheet steel, stainless steel, or aluminum sheets.

D. Solvent-Based Joint and Seam Sealant:

1. Application Method: Brush on.
2. Base: Synthetic rubber resin.
3. Solvent: Toluene and heptane.
4. Solids Content: Minimum 60 percent.
5. Shore A Hardness: Minimum 60.
6. Water resistant.
7. Mold and mildew resistant.
8. For indoor applications, sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
9. VOC: Maximum 395 g/L.
10. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
11. Maximum Static-Pressure Class: 10-inch wg, positive or negative.
12. Service: Indoor or outdoor.
13. Substrate: Compatible with galvanized sheet steel (both PVC coated and bare), stainless steel, or aluminum sheets.

E. Flanged Joint Sealant: Comply with ASTM C 920.

1. General: Single-component, acid-curing, silicone, elastomeric.
2. Type: S.
3. Grade: NS.
4. Class: 25.
5. Use: O.
6. For indoor applications, sealant shall have a VOC content of 250 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
7. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

F. Flange Gaskets: Butyl rubber, neoprene, or EPDM polymer with polyisobutylene plasticizer.

G. Round Duct Joint O-Ring Seals:

1. Seal shall provide maximum leakage class of 3 cfm/100 sq. ft. at 1-inch wg and shall be rated for 10-inch wg static-pressure class, positive or negative.
2. EPDM O-ring to seal in concave bead in coupling or fitting spigot.
3. Double-lipped, EPDM O-ring seal, mechanically fastened to factory-fabricated couplings and fitting spigots.

## 2.9 HANGERS AND SUPPORTS

- A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.
- B. Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.
- C. Strap and Rod Sizes: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct."
- D. Steel Cables for Galvanized-Steel Ducts: Galvanized steel complying with ASTM A 603.
- E. Steel Cables for Stainless-Steel Ducts: Stainless steel complying with ASTM A 492.
- F. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.
- G. Duct Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.
- H. Trapeze and Riser Supports:
  - 1. Supports for Galvanized-Steel Ducts: Galvanized-steel shapes and plates.
  - 2. Supports for Stainless-Steel Ducts: Stainless-steel shapes and plates.
  - 3. Supports for Aluminum Ducts: Aluminum or galvanized steel coated with zinc chromate.

## PART 3 - EXECUTION

### 3.1 DUCT INSTALLATION

- A. Drawing plans, schematics, and diagrams indicate general location and arrangement of duct system. Indicated duct locations, configurations, and arrangements were used to size ducts and calculate friction loss for air-handling equipment sizing and for other design considerations. Install duct systems as indicated unless deviations to layout are approved on Shop Drawings and Coordination Drawings.
- B. Install ducts according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" unless otherwise indicated.
- C. Install round and flat-oval ducts in maximum practical lengths.
- D. Install ducts with fewest possible joints.
- E. Install factory- or shop-fabricated fittings for changes in direction, size, and shape and for branch connections.

- F. Unless otherwise indicated, install ducts vertically and horizontally, and parallel and perpendicular to building lines.
- G. Install ducts close to walls, overhead construction, columns, and other structural and permanent enclosure elements of building.
- H. Install ducts with a clearance of 2 inch, plus allowance for insulation thickness.
- I. Route ducts to avoid passing through transformer vaults and electrical equipment rooms and enclosures.
- J. Where ducts pass through non-fire-rated interior partitions and exterior walls and are exposed to view, cover the opening between the partition and duct or duct insulation with sheet metal flanges of same metal thickness as the duct. Overlap openings on four sides by at least 1-1/2 inches.
- K. Where ducts pass through fire-rated interior partitions and exterior walls, install fire dampers. Comply with requirements in Section 233300 "Air Duct Accessories" for fire and smoke dampers.
- L. Protect duct interiors from moisture, construction debris and dust, and other foreign materials. Comply with SMACNA's "IAQ Guidelines for Occupied Buildings Under Construction," Appendix G, "Duct Cleanliness for New Construction Guidelines".
- M. Where ducts pass through sound-rated walls, fill the opening between the partition and duct with insulation and seal the opening.

### 3.2 INSTALLATION OF EXPOSED DUCTWORK

- A. Protect ducts exposed in finished spaces from being dented, scratched, or damaged.
- B. Trim duct sealants flush with metal. Create a smooth and uniform exposed bead. Do not use two-part tape sealing system.
- C. Grind welds to provide smooth surface free of burrs, sharp edges, and weld splatter. When welding stainless steel with a No. 3 or 4 finish, grind the welds flush, polish the exposed welds, and treat the welds to remove discoloration caused by welding.
- D. Maintain consistency, symmetry, and uniformity in the arrangement and fabrication of fittings, hangers and supports, duct accessories, and air outlets.
- E. Repair or replace damaged sections and finished work that does not comply with these requirements.

### 3.3 ADDITIONAL INSTALLATION REQUIREMENTS FOR COMMERCIAL KITCHEN HOOD EXHAUST DUCT

- A. Install commercial kitchen hood exhaust ducts without dips and traps that may hold grease, and sloped a minimum of 2 percent to drain grease back to the hood.
- B. Install fire-rated access panel assemblies at each change in direction and at maximum intervals of 12 feet in horizontal ducts, and at every floor for vertical ducts, or as indicated on Drawings. Locate access panel on top or sides of duct a minimum of 1-1/2 inches from bottom of duct. [20 feet]
- C. Do not penetrate fire-rated assemblies except as allowed by applicable building codes and authorities having jurisdiction.
- D. Perform a light test of grease ductwork per 2018 International Mechanical Code prior to concealment by insulation or covered by shaft.
  - 1. Perform light test in the presence of local Inspector/Engineer.
  - 2. Document whether test passed or failed.
  - 3. Repair any joints or duct welds that fail light test to the point the ductwork passes the light test.
- E. Install grease duct with minimum clearance to combustibles as required by IBC and local codes. Installations that do not meet the minimum required clearances shall be fire wrapped as specified in Section 230713 "Duct Insulation".
- F. Provide approved fire-wrap insulation that meets ASTM C 656.

### 3.4 DUCT SEALING

- A. Seal ducts for duct static-pressure, seal classes, and leakage classes specified in "Duct Schedule" Article according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
- B. Seal ducts to the following seal classes according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible":
  - 1. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible."
  - 2. Outdoor, Supply-Air Ducts: Seal Class A.
  - 3. Outdoor, Exhaust Ducts: Seal Class A.
  - 4. Outdoor, Return-Air Ducts: Seal Class A.
  - 5. Unconditioned Space, Supply-Air Ducts in Pressure Classes 2-Inch wg and Lower: Seal Class A.
  - 6. Unconditioned Space, Supply-Air Ducts in Pressure Classes Higher Than 2-Inch wg: Seal Class A.
  - 7. Unconditioned Space, Exhaust Ducts: Seal Class A.

8. Unconditioned Space, Return-Air Ducts: Seal Class A.
9. Conditioned Space, Supply-Air Ducts in Pressure Classes 2-Inch wg and Lower: Seal Class A.
10. Conditioned Space, Supply-Air Ducts in Pressure Classes Higher Than 2-Inch wg: Seal Class A.
11. Conditioned Space, Exhaust Ducts: Seal Class A.
12. Conditioned Space, Return-Air Ducts: Seal Class A.

### 3.5 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 5, "Hangers and Supports."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
  1. Where practical, install concrete inserts before placing concrete.
  2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
  3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes or for slabs more than 4 inches thick.
  4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes or for slabs less than 4 inches thick.
  5. Do not use powder-actuated concrete fasteners for seismic restraints.
- C. Hanger Spacing: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 5-1, "Rectangular Duct Hangers Minimum Size," and Table 5-2, "Minimum Hanger Sizes for Round Duct," for maximum hanger spacing; install hangers and supports within 24 inches of each elbow and within 48 inches of each branch intersection.
- D. Hangers Exposed to View: Threaded rod and angle or channel supports.
- E. Support vertical ducts with steel angles or channel secured to the sides of the duct with welds, bolts, sheet metal screws, or blind rivets; support at each floor and at a maximum intervals of 16 feet.
- F. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

### 3.6 SEISMIC-RESTRAINT-DEVICE INSTALLATION

- A. Install ducts with hangers and braces designed to support the duct and to restrain against seismic forces required by applicable building codes. Comply with the requirements specified in Section 230548 "Vibration and Seismic Controls for HVAC."
  1. Comply with ASCE/SEI 7.

### 3.7 CONNECTIONS

- A. Make connections to equipment with flexible connectors complying with Section 233300 "Air Duct Accessories."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for branch, outlet and inlet, and terminal unit connections.

### 3.8 PAINTING

- A. Paint interior of metal ducts that are visible through registers and grilles and that do not have duct liner. Apply one coat of flat, black, latex paint over a compatible galvanized-steel primer. Paint materials and application requirements are specified in Section 099113 "Exterior Painting" and Section 099123 "Interior Painting."

### 3.9 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Leakage Tests:
  - 1. Comply with SMACNA's "HVAC Air Duct Leakage Test Manual." Submit a test report for each test.
  - 2. Test the following systems:
    - a. Ducts with a Pressure Class Higher Than 3-Inch wg: Test representative duct sections, selected by Architect from sections installed, totaling no less than 25 percent of total installed duct area for each designated pressure class.
    - b. Supply Ducts with a Pressure Class of 2-Inch wg or Higher: Test representative duct sections, selected by Architect from sections installed, totaling no less than 50 percent of total installed duct area for each designated pressure class.
    - c. Return Ducts with a Pressure Class of 2-Inch wg or Higher: Test representative duct sections, selected by Architect from sections installed, totaling no less than 50 percent of total installed duct area for each designated pressure class.
    - d. Exhaust Ducts with a Pressure Class of 2-Inch wg or Higher: Test representative duct sections, selected by Architect from sections installed, totaling no less than 50 percent of total installed duct area for each designated pressure class.
    - e. Outdoor Air Ducts with a Pressure Class of 2-Inch wg or Higher: Test representative duct sections, selected by Architect from sections installed, totaling no less than 50 percent of total installed duct area for each designated pressure class.
  - 3. Disassemble, reassemble, and seal segments of systems to accommodate leakage testing and for compliance with test requirements.
  - 4. Test for leaks before applying external insulation.
  - 5. Conduct tests at static pressures equal to maximum design pressure of system or section being tested. If static-pressure classes are not indicated, test system at maximum system design pressure. Do not pressurize systems above maximum design operating pressure.

6. Give seven days' advance notice for testing.

C. Duct System Cleanliness Tests:

1. Visually inspect duct system to ensure that no visible contaminants are present.
2. Test sections of metal duct system, chosen randomly by Owner, for cleanliness according to "Vacuum Test" in NADCA ACR, "Assessment, Cleaning and Restoration of HVAC Systems."
  - a. Acceptable Cleanliness Level: Net weight of debris collected on the filter media shall not exceed 0.75 mg/100 sq. cm.
3. Any liner showing evidence that it has wet at any time shall be removed and replaced with new liner.
  - a. Disinfect affected sheet metal, and pins.
  - b. Install new liner per specifications
  - c. Seal friable edges and seams of repaired liner.

- D. Duct system will be considered defective if it does not pass tests and inspections.

- E. Prepare test and inspection reports.

3.10 DUCT CLEANING

- A. Clean new duct system before testing, adjusting, and balancing.

- B. Use service openings for entry and inspection.

1. Create new openings and install access panels appropriate for duct static-pressure class if required for cleaning access. Provide insulated panels for insulated or lined duct. Patch insulation and liner as recommended by duct liner manufacturer. Comply with Section 233300 "Air Duct Accessories" for access panels and doors.
2. Disconnect and reconnect flexible ducts as needed for cleaning and inspection.
3. Remove and reinstall ceiling to gain access during the cleaning process.

C. Particulate Collection and Odor Control:

1. When venting vacuuming system inside the building, use HEPA filtration with 99.97 percent collection efficiency for 0.3-micron-size (or larger) particles.
2. When venting vacuuming system to outdoors, use filter to collect debris removed from HVAC system, and locate exhaust downwind and away from air intakes and other points of entry into building.

- D. Clean the following components by removing surface contaminants and deposits:

1. Air outlets and inlets (registers, grilles, and diffusers).
2. Supply, return, and exhaust fans including fan housings, plenums (except ceiling supply and return plenums), scrolls, blades or vanes, shafts, baffles, dampers, and drive assemblies.

3. Air-handling unit internal surfaces and components including mixing box, coil section, air wash systems, spray eliminators, condensate drain pans, humidifiers and dehumidifiers, filters and filter sections, and condensate collectors and drains.
4. Coils and related components.
5. Return-air ducts, dampers, actuators, and turning vanes except in ceiling plenums and mechanical equipment rooms.
6. Supply-air ducts, dampers, actuators, and turning vanes.
7. Dedicated exhaust and ventilation components and makeup air systems.

E. Mechanical Cleaning Methodology:

1. Clean metal duct systems using mechanical cleaning methods that extract contaminants from within duct systems and remove contaminants from building.
2. Use vacuum-collection devices that are operated continuously during cleaning. Connect vacuum device to downstream end of duct sections so areas being cleaned are under negative pressure.
3. Use mechanical agitation to dislodge debris adhered to interior duct surfaces without damaging integrity of metal ducts, duct liner, or duct accessories.
4. Clean fibrous-glass duct liner with HEPA vacuuming equipment; do not permit duct liner to get wet. Replace fibrous-glass duct liner that is damaged, deteriorated, or delaminated or that has friable material, mold, or fungus growth.
5. Clean coils and coil drain pans according to NADCA 1992. Keep drain pan operational. Rinse coils with clean water to remove latent residues and cleaning materials; comb and straighten fins.
6. Provide drainage and cleanup for wash-down procedures.
7. Antimicrobial Agents and Coatings: Apply EPA-registered antimicrobial agents if fungus is present. Apply antimicrobial agents according to manufacturer's written instructions after removal of surface deposits and debris.

3.11 START UP

- A. Air Balance: Comply with requirements in Section 230593 "Testing, Adjusting, and Balancing for HVAC."

3.12 DUCT SCHEDULE

- A. Fabricate ducts with galvanized sheet steel.
- B. Ductwork running in areas where there are no ceilings or when noted on the drawings shall be doubled wall duct and shall meet the requirements indicated below.
- C. MRI Ducts:
  1. All ducts Connected to and serving MRI Areas:
    - a. All ductwork shall be aluminum with non-ferrous hardware and accessories.



- b. Pressure Class: Positive or negative 6-inch wg.
- c. Minimum SMACNA Seal Class: Welded seams, joints, and penetrations.
- d. SMACNA Leakage Class: 2.

D. Supply Ducts:

1. Ducts Connected to Fan Coil Units, Furnaces, Heat Pumps, and Terminal Units:
  - a. Pressure Class: Positive 2-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 16.
  - d. SMACNA Leakage Class for Round and Flat Oval: 8.
2. Ducts Connected to Constant-Volume Air-Handling Units:
  - a. Pressure Class: Positive 3-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 8.
  - d. SMACNA Leakage Class for Round and Flat Oval: 4.
3. Ducts Connected to Variable-Air-Volume Air-Handling Units:
  - a. Pressure Class: Positive 6-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 4.
  - d. SMACNA Leakage Class for Round and Flat Oval: 2.
4. Ducts Connected to Equipment Not Listed Above:
  - a. Pressure Class: Positive 4-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 4.
  - d. SMACNA Leakage Class for Round and Flat Oval: 2.

E. Return Ducts:

1. Ducts Connected to Fan Coil Units, Furnaces, Heat Pumps, and Terminal Units:
  - a. Pressure Class: Positive or negative 2-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 16.
  - d. SMACNA Leakage Class for Round and Flat Oval: 8 .
2. Ducts Connected to Air-Handling Units:
  - a. Pressure Class: Positive or negative 2-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 16.
  - d. SMACNA Leakage Class for Round and Flat Oval: 8.

3. Ducts Connected to Equipment Not Listed Above:
  - a. Pressure Class: Positive or negative 3-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 8.
  - d. SMACNA Leakage Class for Round and Flat Oval: 4.

F. Exhaust Ducts:

1. Ducts Connected to Fans Exhausting (ASHRAE 62.1, Class 1 and 2) Air:
  - a. Pressure Class: Negative 2-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 16.
  - d. SMACNA Leakage Class for Round and Flat Oval: 4.
2. Ducts Connected to Air-Handling Units:
  - a. Pressure Class: Positive or negative 3-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 8.
  - d. SMACNA Leakage Class for Round and Flat Oval: 4.
3. Ducts Connected to Variable-Air-Volume Air-Handling Units:
  - a. Pressure Class: Positive 6-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 4.
  - d. SMACNA Leakage Class for Round and Flat Oval: 2.
4. Ducts Connected to Type I (Grease) Commercial Kitchen Hoods: Comply with NFPA 96.
  - a. Exposed to View: 18 gauge Type 304, stainless-steel sheet, No. 4 finish.
  - b. Concealed: 16 gauge black steel.
  - c. Pressure Class: Positive or negative 3-inch wg.
  - d. Welded seams and joints.
  - e. Minimum SMACNA Seal Class: Welded seams, joints, and penetrations.
  - f. SMACNA Leakage Class: 2.
  - g. A light test shall be performed for grease duct prior to concealing the duct.
5. Ducts Connected to Type II (Heat) Commercial Kitchen Hoods:
  - a. Type 304, stainless-steel sheet.
  - b. Exposed to View: No. 4 finish.
  - c. Pressure Class: Positive or negative 3-inch wg.
  - d. Concealed: No. 2D finish.
  - e. Welded seams and joints.

- f. Minimum SMACNA Seal Class: Welded seams, joints, and penetrations.
    - g. SMACNA Leakage Class: 2.
- 6. Ducts Connected to Dishwasher and Low Temperature Vapor and Odor Hoods:
  - a. Type 304, stainless-steel sheet.
  - b. Exposed to View: No. 4 finish. Pressure Class: Positive or negative 3-inch wg.
  - c. Concealed: No. 2D finish.
  - d. Welded seams and flanged joints with watertight EPDM gaskets.
  - e. Minimum SMACNA Seal Class: Welded seams, joints, and penetrations, flanged joints class A.
  - f. SMACNA Leakage Class: 2.
- 7. Ducts Connected to Fans Exhausting Laboratory and Process (ASHRAE 62.1, Class 3 and 4) Air:
  - a. Type 304, stainless-steel sheet.
    - 1) 0.05-inch thick.
    - 2) Exposed to View: No. 4 finish.
    - 3) Concealed: No. 2B finish.
  - b. Pressure Class: Positive or negative 6-inch wg.
  - c. Minimum SMACNA Seal Class: Welded seams, joints, and penetrations.
  - d. SMACNA Leakage Class: 2.
  - e. Main laboratory exhaust trunks to be galvanized steel with same pressure, seal and leakage class.
- 8. Ducts Connected to Cage Wash Areas:
  - a. Type 316 .05-inch thick stainless-steel sheet.
    - 1) Exposed to View: No. 4 finish.
    - 2) Concealed: No. 2B finish.
  - b. Pressure Class: Positive or negative 6-inch wg.
  - c. Minimum SMACNA Seal Class: Welded seams, joints, and penetrations.
  - d. SMACNA Leakage Class: 2.
- 9. Ducts Connected to radioactive fume hoods:
  - a. Type 316 .05-inch thick stainless-steel sheet.
    - 1) Exposed to View: No. 4 finish.
    - 2) Concealed: No. 2B finish.
  - b. Pressure Class: Positive or negative 6-inch wg.
  - c. Minimum SMACNA Seal Class: A. Flanged and gasketed joints for future disassembly for decontamination.
  - d. SMACNA Leakage Class: 2.

10. Ducts Connected to Equipment Not Listed Above:
  - a. Pressure Class: Positive or negative 4-inch wg.
  - b. Minimum SMACNA Seal Class: A.
  - c. SMACNA Leakage Class for Rectangular: 4.
  - d. SMACNA Leakage Class for Round and Flat Oval: 2
- G. Outdoor-Air (Not Filtered, Heated, or Cooled) Ducts:
  1. Ducts Connected to Fan Coil Units, Furnaces, Heat Pumps, and Terminal Units:
    - a. Pressure Class: Positive or negative 2-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 16.
    - d. SMACNA Leakage Class for Round and Flat Oval: 4.
  2. Ducts Connected to Air-Handling Units:
    - a. Pressure Class: Positive or negative 3-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 8.
    - d. SMACNA Leakage Class for Round and Flat Oval: 4.
  3. Ducts Connected to Equipment Not Listed Above:
    - a. Pressure Class: Positive or negative 3-inch wg.
    - b. Minimum SMACNA Seal Class: A.
    - c. SMACNA Leakage Class for Rectangular: 8.
    - d. SMACNA Leakage Class for Round and Flat Oval: 4.
- H. Intermediate Reinforcement:
  1. Galvanized-Steel Ducts: Galvanized steel.
  2. Stainless-Steel Ducts:
    - a. Exposed to Airstream: Match duct material.
    - b. Not Exposed to Airstream: Match duct material.
  3. Aluminum Ducts: Aluminum.
- I. Duct Liner Restrictions:
  1. Duct liner is not allowed in any ductwork except return air systems. Reference ASHRAE Standard 170 section 6.9.
  2. Duct liner with an impervious cover is allowed in terminal units, sound attenuators, and air distribution devices downstream of air handler final filter.

3. Existing duct insulation and liner accessible during a renovation shall be inspected, repaired, and replaced as appropriate.
- J. Double-Wall Duct Interstitial Insulation:
1. Supply Air Ducts: 1 inch thick.
  2. Return Air Ducts: 1 inch thick.
  3. Exhaust Air Ducts: 1 inch thick.
- K. Exterior Ductwork Liner Insulation:
1. Supply Air Ducts: 2 inch thick with a minimum R value of 8.0.
  2. Return Air Ducts: 2 inch thick with a minimum R value of 8.0.
  3. Exhaust Air Ducts: 2 inch thick with a minimum R value of 8.0.
- L. Elbow Configuration:
1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-2, "Rectangular Elbows."
    - a. Radius Type RE 1 with minimum 1.5 radius-to-diameter ratio.
    - b. Radius Type RE 3 with minimum 1.0 radius-to-diameter ratio and two vanes.
    - c. Mitered Type RE 2 with vanes complying with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-3, "Vanes and Vane Runners," and Figure 4-4, "Vane Support in Elbows."
  2. Round Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-4, "Round Duct Elbows."
    - a. Minimum Radius-to-Diameter Ratio and Elbow Segments: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Table 3-1, "Mitered Elbows." Elbows with less than 90-degree change of direction have proportionately fewer segments.
      - 1) Velocity 1000 fpm or Lower: 1.0 radius-to-diameter ratio and three segments for 90-degree elbow.
      - 2) Velocity 1000 to 1500 fpm: 1.5 radius-to-diameter ratio and four segments for 90-degree elbow.
      - 3) Velocity 1500 fpm or Higher: 1.5 radius-to-diameter ratio and five segments for 90-degree elbow.
      - 4) Radius-to Diameter Ratio: 1.5.
    - b. Round Elbows, 12 Inches and Smaller in Diameter: Stamped or pleated.
    - c. Round Elbows, 14 Inches and Larger in Diameter: Welded.
- M. Branch Configuration:

1. Rectangular Duct: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 4-6, "Branch Connection."
  - a. Rectangular Main to Rectangular Branch: 45-degree entry high efficiency take-off.
  - b. Rectangular Main to Round Branch: 45-degree entry high efficiency take-off.
2. Round and Flat Oval:
  - a. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Figure 3-5, "90 Degree Tees and Laterals," and Figure 3-6, "Conical Tees." Saddle taps are permitted in existing duct.
  - b. Velocity 1000 to 1500 fpm: 45-degree entry high efficiency tap.
  - c. Velocity 1500 fpm or Higher: 45-degree lateral.

END OF SECTION 23 3113

## SECTION 23 3300 - AIR DUCT ACCESSORIES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:

1. Backdraft dampers.
2. Manual volume dampers.
3. Control dampers.
4. Fire dampers.
5. Smoke dampers.
6. Combination fire and smoke dampers.
7. Duct silencers.
8. Turning vanes.
9. Remote damper operators.
10. Duct-mounted access doors.
11. Flexible connectors.
12. Flexible ducts.
13. Duct accessory hardware.
14. High efficiency take-offs.

- B. Related Requirements:

1. Division 23 "HVAC Gravity Ventilators" for roof-mounted ventilator caps.
2. Division 23 "Diffusers, Registers and Grilles".
3. Division 28 "Digital, Addressable Fire-Alarm System" for duct-mounted fire and smoke detectors.
4. Division 28 "Zoned (DC-Loop) Fire-Alarm System" for duct-mounted fire and smoke detectors.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

1. For duct silencers, include pressure drop and dynamic insertion loss data. Include breakout noise calculations for high transmission loss casings.

B. LEED Submittals:

1. Product Data for Prerequisite IEQ 1: Documentation indicating that units comply with ASHRAE 62.1, Section 5 - "Systems and Equipment."
2. Product Data for Prerequisite EA 2: Documentation indicating that duct insulation R-values comply with tables in ASHRAE/IESNA 90.1, Section 6 - "Heating, Ventilating, and Air Conditioning."

C. Shop Drawings: For duct accessories. Include plans, elevations, sections, details and attachments to other work.

1. Detail duct accessories fabrication and installation in ducts and other construction. Include dimensions, weights, loads, and required clearances; and method of field assembly into duct systems and other construction. Include the following:
  - a. Special fittings.
  - b. Manual volume damper installations.
  - c. Control-damper installations.
  - d. Fire-damper, smoke-damper, combination fire- and smoke-damper, pressure relief-damper, ceiling, and corridor damper installations, including sleeves; and duct-mounted access doors and remote damper operators.
  - e. Wiring Diagrams: For power, signal, and control wiring.

1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which ceiling-mounted access panels and access doors required for access to duct accessories are shown and coordinated with each other, using input from Installers of the items involved.
- B. Source quality-control reports.

1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For air duct accessories to include in operation and maintenance manuals.

1.6 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  1. Fusible Links: Furnish quantity equal to 10 percent of amount installed.



## PART 2 - PRODUCTS

### 2.1 ASSEMBLY DESCRIPTION

- A. Comply with NFPA 90A, "Installation of Air Conditioning and Ventilating Systems," and with NFPA 90B, "Installation of Warm Air Heating and Air Conditioning Systems."
- B. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for acceptable materials, material thicknesses, and duct construction methods unless otherwise indicated. Sheet metal materials shall be free of pitting, seam marks, roller marks, stains, discolorations, and other imperfections.

### 2.2 MATERIALS

- A. Galvanized Sheet Steel: Comply with ASTM A 653.
  - 1. Galvanized Coating Designation: G60.
  - 2. Exposed-Surface Finish: Mill phosphatized.
- B. Aluminum Sheets: Comply with ASTM B 209, Alloy 3003, Temper H14; with mill finish for concealed ducts and standard, 1-side bright finish for exposed ducts.
- C. Extruded Aluminum: Comply with ASTM B 221, Alloy 6063, Temper T6.
- D. Reinforcement Shapes and Plates: Galvanized-steel reinforcement where installed on galvanized sheet metal ducts; compatible materials for aluminum and stainless-steel ducts.
- E. Tie Rods: Galvanized steel, 1/4-inch minimum diameter for lengths 36 inches or less; 3/8-inch minimum diameter for lengths longer than 36 inches.

### 2.3 BACKDRAFT DAMPERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. American Warming and Ventilating; a division of Mestek, Inc.
  - 2. Greenheck Fan Corporation.
  - 3. Nailor Industries Inc.
  - 4. Pottorff.
  - 5. Ruskin Company.
  - 6. United Enertech
- B. Function:
  - 1. Designed to allow airflow in one direction and prevent reverse airflow.
  - 2. Keeps outside air out of the space by sensing and closing against mass flow.
- C. Description:

1. Gravity balanced.
- D. Maximum Air Velocity:
  1. 1000 fpm
- E. Maximum System Pressure:
  1. 3-inch wg.
- F. Frame: Hat-shaped, with welded corners or mechanically attached and mounting flange:
  1. 16GA 0.063-inch- thick extruded aluminum.
- G. Blades: Multiple single-piece blades, maximum 6-inch width noncombustible, tear-resistant, neoprene-coated fiberglass with sealed edges:
  1. Center pivoted: 16GA 0.050-inch- thick aluminum sheet.
- H. Blade Action: Parallel.
- I. Blade Seals: Mechanically locked.
  1. Neoprene.
- J. Blade Axles: 0.20 inch diameter:
  1. Material: Nonferrous metal.
- K. Tie Bars and Brackets:
  1. Aluminum.
- L. Return Spring: Adjustable tension.
- M. Bearings:
  1. Synthetic pivot bushings.
- N. Accessories.
  1. Adjustment device to permit setting for varying differential static pressure.
  2. Counterweights and spring-assist kits for vertical airflow installations.
  3. Screen Mounting: Front mounted in sleeve.
    - a. Sleeve Thickness: 20 gage minimum.
    - b. Sleeve Length: 6 inches minimum.
  4. Screen Mounting: Rear mounted.
  5. Screen Material:
    - a. Aluminum.
  6. Screen Type:
    - a. Bird
  7. 90-degree stops.

## 2.4 MANUAL VOLUME DAMPERS

### A. Standard, Steel, Manual Volume Dampers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Warming and Ventilating; a division of Mestek, Inc.
  - b. McGill AirFlow LLC.
  - c. Nailor Industries Inc.
  - d. Pottorff.
  - e. Ruskin Company.
  - f. United Enertech
2. Standard leakage rating , with linkage outside airstream .
3. Suitable for horizontal or vertical applications.
4. Frames: Hat-shaped, Mitered and welded corners. Flanges for attaching to walls and flangeless frames for installing in ducts.
  - a. 16GA 0.064-inch thick, galvanized sheet steel.
5. Blades:
  - a. Multiple or single blade. Parallel- or opposed-blade design. Stiffened damper blades for stability.
  - b. Material:
    - 1) Galvanized -steel, 16GA 0.064 inch thick.
6. Blade Axles:
  - a. Nonferrous metal
  - b. Shall extend full length of damper blades in ducts with pressure classes of 3-inch wg or more.
7. Bearings:
  - a. Material:
    - 1) Molded synthetic.
  - b. Bearings at both ends of damper operating shafts in ducts with pressure classes of 3-inch wg or more.
8. Tie Bars and Brackets: Galvanized steel.

### B. Standard, Aluminum, Manual Volume Dampers:

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Warming and Ventilating; a division of Mestek, Inc.
  - b. McGill AirFlow LLC.
  - c. Nailor Industries Inc.
  - d. Pottorff.
  - e. Ruskin Company.

- f. United Enertech
  - 2. Standard leakage rating, with linkage outside airstream.
  - 3. Suitable for horizontal or vertical applications.
  - 4. Frames: Hat-shaped, 0.10-inch- thick, aluminum sheet channels; frames with flanges for attaching to walls and flangeless frames for installing in ducts.
  - 5. Blades:
    - a. Multiple or single blade.
    - b. Parallel- or opposed-blade design.
    - c. Stiffen damper blades for stability.
    - d. Roll-Formed Aluminum Blades: 0.10-inch- thick aluminum sheet.
    - e. Extruded-Aluminum Blades: 0.050-inch- thick extruded aluminum.
  - 6. Blade Axles: Nonferrous metal.
  - 7. Bearings:
    - a. Molded synthetic.
    - b. Dampers in ducts with pressure classes of 3-inch wg or more shall have axles full length of damper blades and bearings at both ends of operating shaft.
  - 8. Tie Bars and Brackets: Aluminum.
- C. Low-Leakage, Steel, Manual Volume Dampers:
- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. American Warming and Ventilating; a division of Mestek, Inc.
    - b. McGill AirFlow LLC.
    - c. Nailor Industries Inc.
    - d. Pottorff.
    - e. Ruskin Company.
    - f. United Enertech
  - 2. Comply with AMCA 500-D testing for damper rating.
  - 3. Low-leakage rating , with linkage outside airstream, and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.
  - 4. Suitable for horizontal or vertical applications.
  - 5. Frames:
    - a. Frame: Hat-shaped,
      - 1) 16GA 0.064-inch thick, galvanized sheet steel.
    - b. Mitered and welded corners.
    - c. Flanges for attaching to walls and flangeless frames for installing in ducts.
  - 6. Blades:
    - a. Multiple or single blade.
    - b. Parallel- or opposed-blade design.
    - c. Stiffen damper blades for stability.

- d. Material:
  - 1) Galvanized, roll-formed steel, 16GA 0.064 inch thick.
- 7. Blade Axles:
  - a. Nonferrous metal.
- 8. Bearings:
  - a. Molded synthetic.
  - b. Dampers in ducts with pressure classes of 3-inch wg or more shall have axles full length of damper blades and bearings at both ends of operating shaft.
- 9. Blade Seals:
  - a. Neoprene.
- 10. Jamb Seals: Cambered Stainless steel or aluminum.
- 11. Tie Bars and Brackets: Galvanized steel or aluminum.
- 12. Accessories:
  - a. Include locking device to hold single-blade dampers in a fixed position without vibration.

D. Low-Leakage, Aluminum, Manual Volume Dampers:

- 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - a. American Warming and Ventilating; a division of Mestek, Inc.
  - b. Nailor Industries Inc.
  - c. McGill AirFlow LLC.
  - d. Pottorff.
  - e. Ruskin Company.
  - f. United Enertech
- 2. Comply with AMCA 500-D testing for damper rating.
- 3. Low-leakage rating, with linkage outside airstream, and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.
- 4. Suitable for horizontal or vertical applications.
- 5. Frames: Hat-shaped, 0.10-inch- thick, aluminum sheet channels; frames with flanges for attaching to walls and flangeless frames for installing in ducts.
- 6. Blades:
  - a. Multiple or single blade.
  - b. Parallel- or opposed-blade design.
  - c. Roll-Formed Aluminum Blades: 0.10-inch- thick aluminum sheet.
  - d. Extruded-Aluminum Blades: 0.050-inch- thick extruded aluminum.
- 7. Blade Axles: Nonferrous metal.
- 8. Bearings:
  - a. Molded synthetic.

- b. Dampers in ducts with pressure classes of 3-inch wg or more shall have axles full length of damper blades and bearings at both ends of operating shaft.
  - 9. Blade Seals: Neoprene.
  - 10. Jamb Seals: Cambered aluminum.
  - 11. Tie Bars and Brackets: Aluminum.
  - 12. Accessories:
    - a. Include locking device to hold single-blade dampers in a fixed position without vibration.
- E. Jackshaft:
  - 1. Size:
    - a. 1-inch diameter.
  - 2. Material: Galvanized-steel pipe rotating within pipe-bearing assembly mounted on supports at each mullion and at each end of multiple-damper assemblies.
  - 3. Length and Number of Mountings: As required to connect linkage of each damper in multiple-damper assembly.
- F. Damper Hardware:
  - 1. Zinc-plated, die-cast core with dial and handle made of 3/32-inch- thick zinc-plated steel, and a 3/4-inch hexagon locking nut.
  - 2. Include center hole to suit damper operating-rod size.
  - 3. Include elevated platform for insulated duct mounting.

## 2.5 CONTROL DAMPERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Greenheck Fan Corporation.
  - 2. Pottorff.
  - 3. Ruskin Company.
  - 4. Young Regulator Company.
  - 5. United Enertech
- B. Low-leakage rating, with linkage outside airstream, and bearing AMCA's Certified Ratings Seal for both air performance and air leakage.
- C. Frames:
  - 1. Section:
    - a. Hat shaped.
  - 2. Material:
    - a. 20 GA 0.40-inch- thick galvanized steel .
  - 3. Corners:
    - a. Mitered-and-welded.

D. Blades: Multiple.

1. Maximum blade width:
  - a. 6 inches.
2. Opposed -blade design.
3. Material:
  - a. Galvanized-steel.
4. Thickness:
  - a. 20 GA 0.40-inch- thick galvanized steel
5. Blade Edging: Inflatable seal blade edging, or replaceable rubber seals.
  - a. Closed-cell neoprene

E. Blade Axles:

1. Section:
  - a. 3/8-inch-square
2. Material:
  - a. Galvanized steel.
3. Blade-linkage hardware:
  - a. Zinc-plated steel and brass.
  - b. Ends sealed against blade bearings:
4. Operating Temperature Range: From minus 40 to plus 200 deg F.

F. Bearings:

1. Type:
  - a. Molded synthetic.
2. Axles: Dampers in ducts with pressure classes of 3-inch wg or more shall have axles full length of damper blades.
3. Bearings: Thrust bearings at each end of every blade. Bearings at both ends of each operating shaft.

## 2.6 FIRE DAMPERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Arrow United Industries; a division of Mestek, Inc.
2. Greenheck Fan Corporation.
3. Nailor Industries Inc.
4. Pottorff.
5. Ruskin Company.
6. United Enertech

B. Type:

1. Dynamic.

C. Standard: Rated and labeled according to UL 555 by an NRTL.

- D. Closing rating in ducts up to 4-inch wg static pressure class and minimum 2000-fpm velocity.
  - E. Fire Rating:
    - 1. 1-1/2 hours.
  - F. Frame:
    - 1. Curtain type with blades outside airstream.
    - 2. Material:
      - a. Fabricated with roll-formed galvanized steel; with mitered and interlocking corners.
      - b. Thickness:
        - 1) 20GA-0.040-inch-.
  - G. Mounting Sleeve: Factory- or field-installed, galvanized sheet steel. Length to suit application.
    - 1. Minimum Thickness:
      - a. 18GA-0.05 inch, as indicated.
    - 2. Exception: Omit sleeve where damper-frame width permits direct attachment of perimeter mounting angles on each side of wall or floor; thickness of damper frame must comply with sleeve requirements.
  - H. Mounting Orientation: Vertical or horizontal as indicated.
  - I. Blades: Roll-formed, interlocking, galvanized sheet steel.
    - 1. Thickness:
      - a. 24GA-0.024-inch-
    - 2. In place of interlocking blades, use full-length, 0.034-inch- thick, galvanized-steel blade connectors.
  - J. Horizontal Dampers: Include blade lock and Type 301 constant force stainless-steel closure spring.
  - K. Heat-Responsive Device: Replaceable, 212 deg F rated, fusible links.
  - L. Accessories:
    - 1. Auxiliary switches for signaling:
      - a. Position indication.
- 2.7 SMOKE DAMPERS
- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - 1. Greenheck Fan Corporation.
    - 2. Nailor Industries Inc.
    - 3. Pottorff.
    - 4. Ruskin Company.



- 5. United Enertech
- B. General Requirements: Label according to UL 555S by an NRTL.
- C. Smoke Detector: See electrical for smoke detector requirements.
- C. Frame: Galvanized sheet steel. With or without mounting flange as required.
  - 1. Thickness:
    - a. Hat-shaped, 16GA-0.064-inch.
  - 2. Corners:
    - a. Welded.
- D. Blades: Horizontal, galvanized sheet steel.
  - 1. Section:
    - a. Roll-formed.
  - 2. Fit:
    - a. Interlocking.
  - 3. Thickness:
    - a. 14GA-0.079-inch.
- E. Leakage:
  - 1. Class II.
- F. Seals:
  - 1. Blade: Inflatable silicone fiberglass material to maintain smoke leakage rating to a minimum of 450 deg F.
- G. Rated pressure and velocity to exceed design airflow conditions.
- H. Mounting Sleeve: Factory-installed, galvanized sheet steel; length to suit wall or floor application with factory-furnished silicone calking.
  - 1. Minimum 17-inches long.
  - 2. Thickness:
    - a. 0.05-inch-.
- I. Damper Motors: Damper motors to be Belimo or approved equal. Honeywell motors are not allowed.
  - 1. Action:
    - a. Two-position
  - 2. Mode: Fail close.
  - 3. Mounting: External.
- J. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
  - 1. Electrical Connection: 115 V, single phase, 60 Hz .
- K. Accessories:
  - 1. Auxiliary switches for signaling:

- a. Position indication.
- 2. Test Switch type:
  - a. Momentary test switch.
- 3. Test Switch Mounting:
  - a. Damper.

## 2.8 COMBINATION FIRE AND SMOKE DAMPERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Greenheck Fan Corporation.
  - 2. Nailor Industries Inc.
  - 3. Pottorff.
  - 4. Ruskin Company.
  - 5. United Enertech
- B. Type: Dynamic; rated and labeled according to UL 555 and UL 555S by an NRTL.
- C. Closing rating in ducts up to 4-inch wg static pressure class and minimum velocity of:
  - 1. 4000-fpm
- D. Fire Rating:
  - 1. 1-1/2 hours.
- E. Frame: Hat shaped, galvanized sheet steel. With or without mounting flange as required.
  - 1. Thickness:
    - a. 16GA-0.064-inch
  - 2. Corners:
    - a. Welded.
- F. Heat-Responsive Device: Replaceable, 212 deg F rated, fusible links.
- G. Blades: Horizontal, galvanized sheet steel.
  - 1. Type:
    - a. Air-foil.
  - 2. Fit:
    - a. Interlocking.
  - 3. Thickness:
    - a. 0.063-inch-.
- H. Leakage:
  - 1. Class I.
- I. Rated pressure and velocity to exceed design airflow conditions.
- J. Mounting Sleeve: Factory-installed, galvanized sheet steel; length to suit wall or floor application with factory-furnished silicone caulking.
  - 1. Thickness:

- a. 18GA 0.05-inch-.
- K. Master control panel for use in dynamic smoke-management systems.
- L. Damper Motors: Damper Motors to be Belimo or approved equal. Honeywell motors are not allowed.
  - 1. Locate outside air stream unless otherwise indicated.
  - 2. Action: Two-position.
  - 3. Voltage: to match fire alarm system (coordinate).
  - 4. Listed: UL, as part of damper assembly.
  - 5. Outdoor Motors and Motors in Outside-Air Intakes:
    - a. Gaskets: O-ring gaskets designed to make motors weatherproof.
    - b. Internal Heaters: Equip to permit normal operation at minus 40 deg F.
- M. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 230513 "common Motor Requirements for HVAC Equipment."
  - 1. Electrical Connection: 115 V, single phase, 60 Hz.
- N. Monitoring: All combination fire & smoke dampers are to have the following parameters monitored as part of the fire alarm system:
  - 1. Damper status.
  - 2. Damper Position.
- O. Accessories:
  - 1. Auxiliary switches:
    - a. Signaling.
    - b. Position Indication.
  - 2. Test Switch Type:
    - a. Momentary test switch.
  - 3. Test Switch Mounting:
    - a. Damper.

## 2.9 DUCT SILENCERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Industrial Acoustics Company.
  - 2. Ruskin Company.
  - 3. SEMCO Incorporated.
  - 4. Vibro-Acoustics.
- B. General Requirements:
  - 1. Factory fabricated.
  - 2. Fire-Performance Characteristics: Adhesives, sealants, packing materials, and accessory materials shall have flame-spread index not exceeding 25 and smoke-developed index not exceeding 50 when tested according to ASTM E 84.

3. Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
- C. Shape:
1. Rectangular straight with splitters or baffles.
  2. Round straight with center bodies or pods.
  3. Rectangular elbow with splitters or baffles.
  4. Round elbow with center bodies or pods.
  5. Rectangular transitional with splitters or baffles.
- D. Rectangular Silencer Outer Casing: Galvanized sheet steel.
1. ASTM A 653:
    - a. G60.
  2. Thickness:
    - a. 22GA-0.034 inch.
- E. Round Silencer Outer Casing: Galvanized sheet steel.
1. ASTM A 653:
    - a. G60.
  2. Sheet Metal Thickness for Units up to 24 Inches in Diameter: 22GA-0.034 inch thick.
  3. Sheet Metal Thickness for Units 26 through 40 Inches in Diameter: 20GA-0.040 inch thick.
  4. Sheet Metal Thickness for Units 42 through 52 Inches in Diameter: 18GA-0.05 inch thick.
  5. Sheet Metal Thickness for Units 54 through 60 Inches in Diameter: 16GA-0.064 inch thick.
- F. Inner Casing and Baffles: Galvanized sheet metal with 1/8-inch- diameter perforations.
1. ASTM A 653:
    - a. G60.
  2. Thickness:
    - a. 22GA-0.034 inch.
- G. Special Construction:
1. Suitable for outdoor use.
  2. High transmission loss to achieve STC 45.
- H. Connection Sizes: Match connecting ductwork unless otherwise indicated.
- I. Principal Sound-Absorbing Mechanism:
1. Controlled impedance membranes and broadly tuned resonators without absorptive media.
  2. Dissipative or Film-lined type with fill material:

- a. Fill Material: Inert and vermin-proof fibrous material, packed under not less than 15 percent compression
  - b. Erosion Barrier: Polymer bag enclosing fill, and heat sealed before assembly.
  - c. Prohibited: Mineral wool will not be permitted as a substitute for glass fiber.
- 3. Lining:
  - a. Material:
    - 1) Tedlar
  - b. Prohibited: Mesh, screen or corrugated perforated liner will not be acceptable as a substitute for the specified spacer.
- J. Fabricate silencers to form rigid units that will not pulsate, vibrate, rattle, or otherwise react to system pressure variations. Do not use mechanical fasteners for unit assemblies.
  - 1. Joints:
    - a. Lock formed and sealed.
  - 2. Suspended Units: Factory-installed suspension hooks or lugs attached to frame in quantities and spaced to prevent deflection or distortion.
  - 3. Reinforcement: Cross or trapeze angles for rigid suspension.
  - 4. Structural Criteria: The silencers shall not fail structurally when subjected to a differential air pressure of 8 inches water gage.
  - 5. Spot Welds: All spot welds shall be painted.
- K. Accessories:
  - 1. Integral 1-1/2-hour fire damper with access door. Access door to be high transmission loss to match silencer.
  - 2. Factory-installed end caps to prevent contamination during shipping.
  - 3. Removable splitters.
  - 4. Airflow measuring devices.

## 2.10 TURNING VANES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. METALAIRE, Inc.
  - 2. SEMCO Incorporated.
  - 3. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
- B. Manufactured Turning Vanes for Metal Ducts: Curved blades of galvanized sheet steel; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
  - 1. Fabricate single blade vanes to comply with SMACNA's "HVAC Duct Construction Standards-Metal and Flexible."
  - 2. Acoustic Turning Vanes: Fabricate airfoil-shaped aluminum extrusions with perforated faces and fibrous-glass fill.

- C. Manufactured Turning Vanes for Nonmetal Ducts: Fabricate curved blades of resin-bonded fiberglass with acrylic polymer coating; support with bars perpendicular to blades set; set into vane runners suitable for duct mounting.
- D. General Requirements: Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 4-3, "Vanes and Vane Runners," and 4-4, "Vane Support in Elbows."
- E. Vane Construction:
  - 1. Single wall
- F. Vane Spacing:
  - 1. 1-1/2" spacing between turning vanes
  - 2. 3-1/4" spacing not allowed.
- G. Vane Construction: Single wall for ducts up to 36 inches wide and additional bracing for larger dimensions.

#### 2.11 REMOTE DAMPER OPERATORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Pottorff.
  - 2. Ruskin Company; Tomkins PLC.
- B. Cable Type:
  - 1. Description: Cable system designed for remote manual damper adjustment.
  - 2. Tubing/Sheathing: Galvinsed, Brass, Copper or Aluminum.
  - 3. Cable: Stainless steel or Steel.
  - 4. Wall-Box Mounting: Coordinate with Architect.
  - 5. Wall-Box Cover-Plate Material: Coordinate with Architect.
- C. Activated Electric Type:
  - 1. Description: Electrically activated zone control damper for remote adjustment. When an adjustment is needed the system is powered up.
  - 2. Means: Factory mounted actuator factory wired to damper.
  - 3. Portable 9 volt system. No field power requirement.
  - 4. Mounting: Recessed Wall Box or Diffuser or Hand Held.
  - 5. Wall-Box Cover Finish: Coordinate with Architect.
  - 6. Wall-Box Porting: 1 to 6 ports or more.

#### 2.12 DUCT-MOUNTED ACCESS DOORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Greenheck Fan Corporation.
  - 2. McGill AirFlow LLC.

3. Pottorff.
  4. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
  5. Ruskin Company
- B. Duct-Mounted Access Doors: Fabricate access panels according to SMACNA's "HVAC Duct Construction Standards - Metal and Flexible"; Figures 7-2, "Duct Access Doors and Panels," and 7-3, "Access Doors - Round Duct."
1. Door:
    - a. Double wall, rectangular.
    - b. Galvanized sheet metal with insulation fill and thickness as indicated for duct pressure class.
    - c. Hinges and Latches: 1-by-1-inch butt or piano hinge and cam latches.
    - d. Fabricate doors airtight and suitable for duct pressure class.
  2. Frame: Galvanized sheet steel, with bend-over tabs and foam gaskets.
  3. Number of Hinges and Locks:
    - a. Access Doors Less Than 12 Inches Square: No hinges and two sash locks.
    - b. Access Doors up to 18 Inches Square:
      - 1) Hinges:
        - a) Two hinges and two sash locks.
    - c. Access Doors up to 24 by 48 Inches, provide outside and inside handles:
      - 1) Hinges:
        - a) Three hinges and two compression latches.
    - d. Access Doors Larger Than 24 by 48 Inches, provide outside and inside handles:
      - 1) Hinges:
        - a) Continuous and two compression latches with outside and inside handles.

## 2.13 FLEXIBLE CONNECTORS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
1. Ductmate Industries, Inc.
  2. Ventfabrics, Inc.
  3. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
- B. Materials: Flame-retardant or noncombustible fabrics.
- C. Coatings and Adhesives: Comply with UL 181, Class 1.
- D. Metal-Edged Connectors: Factory fabricated with a wide fabric strip attached to two narrower metal strips. Provide strips of metal compatible with connected ducts.
1. Wide Strip:
    - a. 3-1/2 inches.
  2. Narrow Strips:

- a. 0.028-inch- thick, galvanized sheet steel.
- E. Indoor System, Flexible Connector Fabric: Glass fabric double coated with neoprene.
  - 1. Minimum Weight: 26 oz./sq. yd..
  - 2. Tensile Strength: 530 lbf/inch in the warp and 440 lbf/inch in the filling.
  - 3. Service Temperature: Minus 40 to plus 200 deg F.
- F. Outdoor System, Flexible Connector Fabric: Glass fabric double coated with weatherproof, synthetic rubber resistant to UV rays and ozone.
  - 1. Minimum Weight: 24 oz./sq. yd..
  - 2. Tensile Strength: 530 lbf/inch in the warp and 440 lbf/inch in the filling.
  - 3. Service Temperature: Minus 50 to plus 250 deg F.

## 2.14 DUCT SECURITY BARS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Carnes.
  - 2. KEES, Inc.
  - 3. Lloyd Industries, Inc.
  - 4. Metal Form Manufacturing, Inc.
  - 5. Price Industries.
  - 6. Titus
  - 7. Krueger
- B. Description: Factory-fabricated and field-installed duct security bars.
- C. Configuration:
  - 1. Frame: 1-1/2 by 1-1/2 by 3/16 inch angle.
  - 2. Sleeve: 3/16-inch, continuously welded steel frames with 1-1/2-by-1-1/2-by-1/8- angle frame furnished loose for field welding on other end. To be poured in place or set with concrete block or welded or bolted to wall, one side only. Duct connections on both sides.
  - 3. Horizontal Bars: 3/4 inch steel.
  - 4. Vertical Bars: 3/4 inch steel
  - 5. Bar Spacing: 6 inches.
  - 6. Mounting: Ductwork or other framing.
- D. Finish:
  - 1. White



## 2.15 FLEXIBLE DUCTS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Flexmaster U.S.A., Inc.
  - 2. McGill AirFlow LLC.
  - 3. Themaflex
  - 4. Ward Industries, Inc.; a division of Hart & Cooley, Inc.
- B. Ducts shall conform to the requirements for Class I connectors when tested in accordance with "Standard for Factory Made Air Ducts Materials and Air Duct Connectors" (UL 181).
- C. Ducts shall also pass the 15 minute U.L. flame penetration test as specified in the UL 181 Standard.
- D. Insulated, Flexible Duct: Two-ply vinyl film supported by helically wound, spring-steel wire; fibrous-glass insulation; polyethylene or aluminized vapor-barrier film.
  - 1. Pressure Rating: 10-inch wg positive and 1.0-inch wg negative.
  - 2. Maximum Air Velocity: 4000 fpm.
  - 3. Temperature Range: Minus 10 to plus 160 deg F.
  - 4. Insulation R-value: Comply with ASHRAE/IESNA 90.1.
- E. Flexible Duct Connectors:
  - 1. Clamps: in sizes 3 through 18 inches, to suit duct size.
    - a. Material: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action.
    - b. Clamps must be approved and listed with a UL181B-C listing.
  - 2. Nylon Duct Cable Tie: In sizes 3 through 18 inches, to suit duct size.
    - a. Material: Nylon
    - b. Fastener must be approved and listed with a UL181B-C listing.
  - 3. Adhesive Tape:
    - a. Material: Metalized polypropylene.
    - b. Tape must be approved and listed with a UL181B-FX listing.

## 2.16 DUCT ACCESSORY HARDWARE

- A. Instrument Test Holes: Cast iron or cast aluminum to suit duct material, including screw cap and gasket. Size to allow insertion of pitot tube and other testing instruments and of length to suit duct-insulation thickness.
- B. Adhesives: High strength, quick setting, neoprene based, waterproof, and resistant to gasoline and grease.
- C. Splitter Damper Accessories: Zinc-plated damper blade bracket; 1/4-inch, zinc-plated operating rod; and a duct-mounted, ball-joint bracket with flat rubber gasket and square-head set screw.

- D. Flexible Duct Clamps: Stainless-steel band with cadmium-plated hex screw to tighten band with a worm-gear action, in sizes 3 to 18 inches to suit duct size.

## 2.17 HIGH EFFICIENCY TAKE-OFFS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following.
  - 1. Air-Rite
  - 2. Hercules Industries
  - 3. Sheet Metal Connectors, Inc.
  - 4. Spiral Manufacturing Co. Inc.
  - 5. Ferguson
- B. Materials:
  - 1. 24 or 26 gauge galvanized sheet metal meeting ASTM A653 and A924
- C. Take-off shall meet SMACNA third edition Section 4.8 figure 4.6 - 45 degree entry.
- D. Rectangular opening with flanged sides on all sides. Complete with closed cell neoprene gasket to provide a tight seal.
- E. Zeros VOC's

## PART 3 - EXECUTION

### 3.1 INSTALLATION

#### General

- A. Install duct accessories according to applicable details in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible" for metal ducts and in NAIMA AH116, "Fibrous Glass Duct Construction Standards," for fibrous-glass ducts.
- B. Install duct accessories of materials suited to duct materials; use galvanized-steel accessories in galvanized-steel and fibrous-glass ducts, stainless-steel accessories in stainless-steel ducts, and aluminum accessories in aluminum ducts.
- C. Use the Remote Damper Operator when they are called out on the drawings or when the damper cannot be easily accessed.
- D. Install duct security bars. Construct duct security bars from 3/16-inch steel sleeve, continuously welded at all joints and 3/4-inch- diameter steel bars, 6 inches o.c. in each direction in center of sleeve. Weld each bar to steel sleeve and each crossing bar. Weld 1-1/2-by-1-1/2-by-1/8- steel angle to 4 sides and both ends of sleeve. Connect duct security bars to ducts with flexible

connections. Provide 12-by-12-inch hinged access panel with cam lock in duct in each side of sleeve.

- E. Install high efficiency take-off on all branch duct take-offs. Provide take-off with balancing damper as shown on drawings. Spin-in fittings are not allowed.

Flexible Ducts / Flexible Duct Connectors

- F. Install flexible connectors to connect ducts to equipment.
- G. Flexible duct connections from the main trunk ducts to diffuser boots shall be furnished and installed as shown on the drawings. Flexible ductwork shall only be used as indicated on the drawings.
- H. Where flexible duct is indicated, use insulated flexible duct for supply air return and exhaust air.
- I. Flexible ductwork shall be run in straight lengths.
- J. Provide support in flexible duct every three feet.
- K. Flexible ducts shall have compression fittings on both ends.
- L. Flexible ductwork is not allowed to bend 90 degrees. If a bend is needed use sheet-metal hard elbows. Hard turns, offsets, or kinks will not be allowed.
- M. Flexible ducts shall connect to trunk duct with high efficiency takeoffs.
- N. Connect flexible ducts to metal ducts with draw bands.
- O. Connect ducts to duct silencers:
  - 1. With flexible duct connectors.
- P. Connect terminal units to supply ducts:
  - 1. With maximum 12-inch lengths of flexible duct.
- Q. Do not use flexible ducts to change directions.
- R. Connect diffusers or light troffer boots to ducts:
  - 1. With maximum 60-inch lengths of flexible duct clamped or strapped in place.

Backdraft/Control/Pressure Relief Dampers

- S. Install backdraft dampers at inlet of exhaust fans or exhaust ducts as close as possible to exhaust fan unless otherwise indicated.
- T. Install pressure relief damper immediately upstream of main fire damper.

Volume Damper

- U. Install volume dampers at points on supply, return, and exhaust systems where branches extend from larger ducts. Where dampers are installed in ducts having duct liner, install dampers with hat channels of same depth as liner, and terminate liner with nosing at hat channel.
  - 1. Install steel volume dampers in steel ducts.
  - 2. Install aluminum volume dampers in aluminum ducts.
- V. Set dampers to fully open position before testing, adjusting, and balancing. Exception: Pressure relief damper.
- W. A balance damper with locking quadrant will be provided downstream of take-off from trunk duct.

#### Fans And Test Holes

- X. For fans developing static pressures of 5-inch wg and more, cover flexible connectors with loaded vinyl sheet held in place with metal straps.
- Y. Install thrust limits at centerline of thrust, symmetrical on both sides of equipment. Attach thrust limits at centerline of thrust and adjust to a maximum of 1/4-inch movement during start and stop of fans.
- Z. Install duct test holes where required for testing and balancing purposes.
- AA. Install test holes at fan inlets and outlets and elsewhere as indicated.

#### FIRE, SMOKE AND FIRE-SMOKE DAMPERS

- BB. Install fire and smoke dampers according to UL listing.
  - 1. Install fusible links in fire dampers.
- CC. For round ductwork 24-inch and smaller a true round fire damper with the same rating may be used.

#### Access Doors

- DD. Install duct access doors on sides of ducts to allow for inspecting, adjusting, and maintaining accessories and equipment at the following locations:
  - 1. On upstream side of duct coils.
  - 2. Upstream from duct filters.
  - 3. At outdoor-air intakes and mixed-air plenums.
  - 4. At drain pans and seals.
  - 5. Downstream from manual volume dampers, control dampers, backdraft dampers, and equipment.
  - 6. Adjacent to and close enough to fire or smoke dampers, to reset or reinstall fusible links. Access doors for access to fire or smoke dampers having fusible links shall be standard access doors and shall be outward operation for access doors installed upstream from dampers and inward operation for access doors installed downstream from dampers.
  - 7. At each change in direction and at maximum 50-foot spacing.

8. Upstream from turning vanes.
9. Upstream or downstream from duct silencers.
10. Control devices requiring inspection.
11. Elsewhere as indicated.
12. On upstream side of duct reheat coils. (between Phoenix valve and reheat coil)

EE. Install access doors with swing against duct static pressure.

FF. Access Door Sizes:

1. One-Hand or Inspection Access: 8 by 5 inches.
2. Two-Hand Access: 12 by 6 inches.
3. Head and Hand Access: 18 by 10 inches.
4. Head and Shoulders Access: 21 by 14 inches.
5. Body Access: 25 by 14 inches.
6. Body plus Ladder Access: 25 by 17 inches.

GG. Label access doors according to Section 230553 "Identification for HVAC Piping and Equipment" to indicate the purpose of access door.

### 3.2 FIELD QUALITY CONTROL

A. Tests and Inspections:

1. Operate dampers to verify full range of movement.
2. Inspect locations of access doors and verify that purpose of access door can be performed.
3. Operate fire, smoke, and combination fire and smoke dampers to verify full range of movement and verify that proper heat-response device is installed.
4. Inspect turning vanes for proper and secure installation.
5. Operate remote damper operators to verify full range of movement of operator and damper.

### 3.3 ADJUSTING

- A. Adjust duct accessories for proper settings.
- B. Adjust fire and smoke dampers for proper action.
- C. Final positioning of manual-volume dampers is specified in Division 23 Section "Testing, Adjusting, and Balancing for HVAC."

END OF SECTION 23 3300

## SECTION 23 3423 - HVAC POWER VENTILATORS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Utility Set Fans

#### 1.3 PERFORMANCE REQUIREMENTS

- A. Project Altitude: Base fan-performance ratings on:
  - 1. Actual Project site elevations.
- B. Operating Limits: Classify according to AMCA 99.
- C. Fan Schedule: Fan characteristics and performance data are described in an equipment schedule on the drawings including:
  - 1. Fan arrangement with wheel configuration, inlet and discharge configurations, and required accessories.
  - 2. Capacities, outlet velocities, static pressures, sound power characteristics, motor requirements, and electrical characteristics.

#### 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated. Include rated capacities, shipping weights, operating weights, operating characteristics, and furnished specialties and accessories. Also include the following:
  - 1. Certified fan performance curves with system operating conditions indicated.
  - 2. Certified fan sound-power ratings.
  - 3. Motor ratings and electrical characteristics, plus motor and electrical accessories.
  - 4. Material thickness and finishes, including color charts.
  - 5. Dampers, including housings, linkages, and operators.
  - 6. Roof curbs.
  - 7. Fan speed controllers.
- B. Shop Drawings: Include plans, elevations, sections, details, and attachments to other work.

1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  2. Wiring Diagrams: For power, signal, and control wiring.
    - a. Detail all wiring systems and differentiate clearly between manufacturer-installed and field-installed wiring.
- C. Delegated-Design Submittal: For unit hangars and supports indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
1. Vibration Isolation Base Details: Detail fabrication including anchorages and attachments to structure and to supported equipment. Include adjustable motor bases, rails, and frames for equipment mounting.
  2. Design Calculations: Calculate requirements for selecting vibration isolators and seismic restraints and for designing vibration isolation bases.

#### 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from Installers of the items involved:
1. Roof framing and support members relative to duct penetrations.
  2. Ceiling suspension assembly members.
  3. Size and location of initial access modules for acoustical tile.
  4. Ceiling-mounted items including light fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
- B. Field quality-control Reports

#### 1.6 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For power ventilators to include in emergency, operation, and maintenance manuals.

#### 1.7 MATERIALS MAINTENANCE SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
1. Belts: One set for each belt-driven unit.

#### 1.8 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. AMCA Compliance: Fans shall have AMCA-Certified performance ratings and shall bear the AMCA-Certified Ratings Seal.
- C. NEMA Compliance: Power ventilator electrical components shall comply with applicable NEMA standards.
- D. UL Standards: Power ventilators shall comply with UL 705. Power ventilators for use for restaurant kitchen exhaust shall also comply with UL 762.

## 1.9 COORDINATION

- A. Coordinate size and location of structural-steel support members.
- B. Coordinate sizes and locations of concrete bases with actual equipment provided.
- C. Coordinate sizes and locations of roof curbs, equipment supports, and roof penetrations with actual equipment provided.

## PART 2 - PRODUCTS

### 2.1 PRODUCTS FURNISHED BUT NOT INSTALLED

- A. Products furnished, but not installed, under this Section include roof curbs for roof-mounted exhaust fans. Roof curbs to be installed by Division 07, section "Roof Accessories".

### 2.2 UTILITY SET FANS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Greenheck Fan Corp.
  - 2. Loren Cook Company.
  - 3. Twin City
- B. Housing: Fabricated of steel with side sheets fastened with a deep lock seam or welded to scroll sheets.
  - 1. Housing Discharge Arrangement: Up blast.
- C. Fan Wheels: Single-width, single inlet; welded to cast-iron or cast-steel hub and spun-steel inlet cone, with hub keyed to shaft.
  - 1. Blade Materials:
    - a. Steel
  - 2. Blade Type:



a. Airfoil

- D. Integral stack (if applicable): Stack material to be a minimum of 18 gauge. Stack to match outlet dimensions of the fan and shall not add additional static pressure drop to the exhaust fan. [Stack discharge shall have tapered design increasing exit velocity and not adding additional static pressure drop to the exhaust fan.]
- E. Drain Connection: Threaded drain connection with plug shall be located at lowest part of scroll housing to prevent moisture build-up in the interior of fan.
- F. Accessories:
  - 1. Inlet Screens: Removable wire mesh.
  - 2. Disconnect Switch: Nonfusible type:
    - a. Thermal-overload protection; factory wired through an internal aluminum conduit.
      - 1) Mounted inside fan housing.

2.3 MOTORS

- A. Comply with NEMA designation, temperature rating, service factor, enclosure type, and efficiency requirements for motors specified in Section 230513 "Common Motor Requirements for HVAC Equipment."
  - 1. Motor Sizes: Minimum size as indicated. If not indicated, large enough so driven load will not require motor to operate in service factor range above 1.0.
  - 2. Controllers, Electrical Devices, and Wiring: Comply with requirements for electrical devices and connections specified in Division 26 Sections.
- B. Enclosure Type: Totally enclosed;
  - 1. Fan cooled

2.4 FACTORY FINISH

- A. Metal Parts: All assembly parts shall be protected from rust and corrosion.
  - 1. Stainless steel, aluminum, and other non-corroding materials require no protective finish.
  - 2. Non-galvanized sheet metal parts shall be prime coated or powder coated before final assembly.
  - 3. Prime coated parts shall receive baked enamel finish coat after assembly.

2.5 SOURCE QUALITY CONTROL

- A. Certify sound-power level ratings according to AMCA 301, "Methods for Calculating Fan Sound Ratings from Laboratory Test Data." Factory test fans according to AMCA 300, "Reverberant Room Method for Sound Testing of Fans." Label fans with the AMCA-Certified Ratings Seal.
- B. Certify fan performance ratings, including flow rate, pressure, power, air density, speed of rotation, and efficiency by factory tests according to AMCA 210, "Laboratory Methods of

Testing Fans for Aerodynamic Performance Rating." Label fans with the AMCA-Certified Ratings Seal.

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine areas and conditions for compliance with requirements of installation tolerances and other conditions affecting performance of the power ventilators. Do not proceed with installation until unsatisfactory conditions have been corrected.

#### 3.2 PROJECT CONDITIONS

- A. Field Measurements: Verify dimensions by field measurements. Verify clearances.
- B. Do not operate fans until ductwork is clean, filters are in place, bearings are lubricated, and fans have been commissioned.

#### 3.3 INSTALLATION

- A. Install power ventilators level and plumb according to manufacturer's written instructions.
- B. Base Mounted Equipment:
  - 1. Install power ventilators on cast-in-place concrete equipment base(s). Comply with requirements for equipment bases and foundations specified in:
    - a. Division 33 "Cast-in-Place Concrete."
- C. Secure roof-mounted fans to roof curbs with cadmium-plated hardware. See Section 077200 "Roof Accessories" for installation of roof curbs.
- D. Label units according to requirements specified in Division 23 "Identification for HVAC Piping and Equipment."
- E. Install power ventilators with factory recommended and code required clearances for service and maintenance.

#### 3.4 CONNECTIONS

- A. Duct installation and connection requirements are specified in other Division 23 Sections. Drawings indicate general arrangement of ducts and duct accessories. Make final duct connections with flexible connectors. Flexible connectors are specified in Section 233300 "Air Duct Accessories."
- B. Install ducts adjacent to power ventilators to allow service and maintenance.

- C. Ground equipment according to Division 26 "Grounding and Bonding for Electrical Systems."
  - 1. Tighten electrical connectors and terminals, including grounding connections, according to manufacturer's published torque-tightening values. Where manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
- D. Connect wiring according to Division 26 "Low-Voltage Electrical Power Conductors and Cables."
  - 1. Tighten electrical connectors and terminals, including grounding connections, according to manufacturer's published torque-tightening values. Where manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

### 3.5 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
  - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.

### 3.6 ADJUSTING

- A. Adjust damper linkages for proper damper operation.
- B. Adjust belt tension.
- C. Comply with requirements in Division 23 "Testing, Adjusting, and Balancing for HVAC" for testing, adjusting, and balancing procedures.
- D. Replace fan and motor pulleys as required to achieve design airflow.
- E. Lubricate bearings.

### 3.7 CLEANING

- A. After completing installation, inspect exposed finish. Remove burrs, dirt, and construction debris, and repair damaged finishes including chips, scratches, and abrasions.
- B. Clean fan interiors to remove foreign material and construction debris. Vacuum clean fan wheel and cabinet.

### 3.8 DEMONSTRATION

- A. Train Owner's maintenance personnel on procedures and schedules related to startup and shutdown, troubleshooting, servicing, and preventive maintenance.
- B. Review data in the operation and maintenance manuals. Refer to Division 1 Section "Contract Closeout."

- C. Schedule training with Owner, through Architect, with at least 7 days' advance notice.
- D. Demonstrate operation of power ventilators. Conduct walking tour of the Project. Briefly identify location and describe function, operation, and maintenance of each power ventilator.

END OF SECTION 23 3423

## SECTION 23 3600 - AIR TERMINAL UNITS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Shutoff, single-duct air terminal units.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of the following products, including rated capacities, furnished specialties, sound-power ratings, and accessories.
  - 1. Air terminal units.
  - 2. Liners and adhesives.
  - 3. Sealants and gaskets.
  - 4. Seismic-restraint devices.
- B. LEED Submittals:
  - 1. Product Data for Prerequisite IEQ 1: Documentation indicating that units comply with ASHRAE 62.1, Section 5 - "Systems and Equipment."
- C. Shop Drawings: For air terminal units. Include plans, elevations, sections, details, and attachments to other work.
  - 1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  - 2. Wiring Diagrams:
    - a. For power, signal, and control wiring.
    - b. Differentiate between manufacturer-installed and field-installed wiring.
  - 3. Hangers and supports, including methods for duct and building attachment, seismic restraints, and vibration isolation.
- D. Delegated-Design Submittal:
  - 1. Materials, fabrication, assembly, and spacing of hangers and supports.

2. Design Calculations: Calculations, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation for selecting hangers and supports.

E. Airborne noise data for terminal units serving Patient Rooms:

1. Declared discharge and radiated sound power levels by octave band covering a minimum range of 63 to 4000 hertz
2. Method of determining declared sound power levels.

#### 1.4 INFORMATIONAL SUBMITTALS

A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from Installers of the items involved:

1. Ceiling suspension assembly members.
2. Size and location of initial access modules for acoustic tile.
3. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.

B. Field quality-control reports.

#### 1.5 PERFORMANCE REQUIREMENTS

A. Seismic Performance: Air terminal units shall withstand the effects of earthquake motions determined according to SEI/ASCE 7.

1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."

#### 1.6 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For air terminal units to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:

1. Instructions for resetting minimum and maximum air volumes.
2. Instructions for adjusting software set points.

#### 1.7 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.

1. Fan-Powered-Unit Filters: Furnish one spare filter for each filter installed.

## 1.8 QUALITY ASSURANCE

- A. ASHRAE Compliance: Applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and System Start-Up."
- B. Product Options: Drawings and schedules indicate requirements of air terminals and are based on specific systems indicated. Other manufacturers' systems with equal performance characteristics may be considered. Refer to Division 1 Section "Substitutions."
- C. Listing and Labeling: Provide electrically operated air terminals specified in this Section that are listed and labeled.
  - 1. The Terms "Listed" and "Labeled": As defined in NFPA 70, Article 100.
- D. NFPA Compliance: Install air terminals according to NFPA 90A, "Standard for the Installation of Air Conditioning and Ventilating Systems."
- E. Comply with NFPA 70 for electrical components and installation.
- F. Airborne Noise:
  - 1. Comply with ANSI / AHRI 880 - Performance Rating of Air Terminals

## PART 2 - PRODUCTS

### 2.1 PERFORMANCE REQUIREMENTS

- A. Structural Performance: Hangers and supports shall withstand the effects of gravity loads and stresses within limits and under conditions described in SMACNA's "HVAC Duct Construction Standards - Metal and Flexible".
- B. Airborne Noise:
  - 1. Maximum sound power levels by octave band in decibels referenced to on picowatt:

| AHU                           | Source    | Sound Power Level by Octave Band (Hz), dBL (re 10 <sup>-12</sup> W) |     |     |     |      |      |      |
|-------------------------------|-----------|---------------------------------------------------------------------|-----|-----|-----|------|------|------|
|                               |           | 63                                                                  | 125 | 250 | 500 | 1000 | 2000 | 4000 |
| VAV Box serving Patient Rooms | Discharge | 71                                                                  | 69  | 69  | 62  | 54   | 50   | 47   |
|                               | Radiated  | 60                                                                  | 60  | 58  | 50  | 40   | 36   | 33   |

### 2.2 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

## 2.3 SHUTOFF, SINGLE-DUCT AIR TERMINAL UNITS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Anemostat Products; a Mestek Company.
  - 2. Carnes.
  - 3. Environmental Technologies, Inc.
  - 4. Krueger.
  - 5. METALAIRE, Inc.
  - 6. Nailor Industries Inc.
  - 7. Price Industries.
  - 8. Titus.
  - 9. Trox USA Inc.; a subsidiary of the TROX GROUP.
  - 10. Tuttle & Bailey.
  - 11. Warren Technology.
- B. Configuration: Volume-damper assembly inside unit casing with control components inside a protective metal shroud.
- C. Casing: 0.034-inch steel, single wall.
  - 1. Casing Lining: Adhesive attached, coated, fibrous-glass duct liner complying with ASTM C 1071, and having a maximum flame-spread index of 25 and a maximum smoke-developed index of 50, for both insulation and adhesive, when tested according to ASTM E 84.
    - a. Lining thickness:
      - 1) 1/2-inch-
    - b. Cover liner with nonporous foil.
  - 2. Air Inlet: Round stub connection or S-slip and drive connections for duct attachment.
  - 3. Air Outlet: S-slip and drive connections.
  - 4. Air Outlet: S-slip and drive connections size matching inlet size.
  - 5. Access: Removable panels for access to parts requiring service, adjustment, or maintenance; with airtight gasket.
  - 6. (LEED) Airstream Surfaces: Surfaces in contact with the airstream shall comply with requirements in ASHRAE 62.1.
  - 7. Access Door: Access door upstream of the reheat coil.
- D. Volume Damper: Galvanized steel with peripheral gasket and self-lubricating bearings.
  - 1. Maximum Damper Leakage:
    - a. ARI 880 rated, 3 percent of nominal airflow at 3-inch wg inlet static pressure.
  - 2. Damper Position:
    - a. Normally open.
- E. Hydronic Coils: Copper tube, with mechanically bonded aluminum fins spaced no closer than 0.1 inch, and rated for a minimum working pressure of 200 psig and a maximum entering-water temperature of 220 deg F. Include manual air vent and drain valve.
- F. Direct Digital Controls: See Section 230900 "Instrumentation and Controls for HVAC".



## 2.4 HANGERS AND SUPPORTS

- A. Hanger Rods for Noncorrosive Environments: Cadmium-plated steel rods and nuts.
- B. Hanger Rods for Corrosive Environments: Electrogalvanized, all-thread rods or galvanized rods with threads painted with zinc-chromate primer after installation.
- C. Steel Cables: Galvanized steel complying with ASTM A 603.
- D. Steel Cable End Connections: Cadmium-plated steel assemblies with brackets, swivel, and bolts designed for duct hanger service; with an automatic-locking and clamping device.
- E. Air Terminal Unit Attachments: Sheet metal screws, blind rivets, or self-tapping metal screws; compatible with duct materials.
- F. Trapeze and Riser Supports: Steel shapes and plates for units with steel casings; aluminum for units with aluminum casings.

## 2.5 SOURCE QUALITY CONTROL

- A. Factory Tests: Test assembled air terminal units according to ARI 880.
  - 1. Label each air terminal unit with plan number, nominal airflow, maximum and minimum factory-set airflows, and ARI certification seal.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Install air terminal units according to NFPA 90A, "Standard for the Installation of Air Conditioning and Ventilating Systems."
- B. Install air terminal units level and plumb. Maintain sufficient clearance for normal service and maintenance.
- C. Install wall-mounted thermostats.
- D. Install discharge air temperature sensors at the outlet of each Air Terminal Unit.
- E. Connect ductwork to air terminals according to Division 23 ductwork Sections.
- F. Comply with SEI/ASCE 7 and with requirements for seismic-restraint devices in Section 230548 "Vibration and Seismic Controls for HVAC."
- G. For Diffuser Type Air Terminal Units, provide and install all necessary control wiring and control voltage transformer. See drawings AND schedules for additional information.

### 3.2 HANGER AND SUPPORT INSTALLATION

- A. Comply with SMACNA's "HVAC Duct Construction Standards - Metal and Flexible," Chapter 5, "Hangers and Supports."
- B. Building Attachments: Concrete inserts, powder-actuated fasteners, or structural-steel fasteners appropriate for construction materials to which hangers are being attached.
  - 1. Where practical, install concrete inserts before placing concrete.
  - 2. Install powder-actuated concrete fasteners after concrete is placed and completely cured.
  - 3. Use powder-actuated concrete fasteners for standard-weight aggregate concretes and for slabs more than 4 inches thick.
  - 4. Do not use powder-actuated concrete fasteners for lightweight-aggregate concretes and for slabs less than 4 inches thick.
  - 5. Do not use powder-actuated concrete fasteners for seismic restraints.
- C. Hangers Exposed to View: Threaded rod and angle or channel supports.
- D. Install upper attachments to structures. Select and size upper attachments with pull-out, tension, and shear capacities appropriate for supported loads and building materials where used.

### 3.3 CONNECTIONS

- A. Install piping adjacent to air terminal unit to allow service and maintenance.
- B. Hot-Water Piping: In addition to requirements in Section 232113 "Hydronic Piping" and Section 232116 Hydronic Piping Specialties," connect heating coils to supply with shutoff valve, strainer, control valve, and union or flange; and to return with balancing valve and union or flange.
- C. Connect ducts to air terminal units according to Section 233113 "Metal Ducts."
- D. Make connections to air terminal units with flexible connectors complying with requirements in Section 233300 "Air Duct Accessories."
- E. Electrically ground all equipment:
  - 1. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. Where manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

### 3.4 IDENTIFICATION

- A. Label each air terminal unit with plan number, nominal airflow, and maximum and minimum factory-set airflows. Comply with requirements in Section 230553 "Identification for HVAC Piping and Equipment" for equipment labels and warning signs and labels.

### 3.5 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust components, assemblies, and equipment installations, including connections.
- B. Perform tests and inspections.
  - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- C. Tests and Inspections:
  - 1. After installing air terminal units and after electrical circuitry has been energized, test for compliance with requirements.
  - 2. Leak Test: After installation, fill water coils and test for leaks. Repair leaks and retest until no leaks exist.
  - 3. Operational Test: After electrical circuitry has been energized, start units to confirm proper motor rotation and unit operation.
  - 4. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- D. Air terminal unit will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.
- F. Cleaning:
  - 1. After completing system installation, including outlet fittings and devices, inspect exposed finish. Remove burrs, dirt, and construction debris, and repair damaged finishes.

### 3.6 STARTUP SERVICE

- A. Engage a factory-authorized service representative to perform startup service.
  - 1. Complete installation and startup checks according to:
    - a. Manufacturer's written instructions.
    - b. Construction documents.
  - 2. Verify that inlet duct connections are as recommended by air terminal unit manufacturer to achieve proper performance.
  - 3. Verify that controls and control enclosure are accessible.
  - 4. Verify that control connections are complete.
  - 5. Verify that nameplate and identification tag are visible.
  - 6. Verify that controls respond to inputs as specified.

### 3.7 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain air terminal units:

University of Utah

Salt Lake City, Utah 84104

1. Train Owner's maintenance personnel on procedures and schedules related to startup and shutdown, troubleshooting, servicing, and preventive maintenance.
2. Review data in the maintenance manuals. Refer to Division 1 Section "Contract Closeout."
3. Review data in the maintenance manuals. Refer to Division 1 Section "Operation and Maintenance Data."
4. Schedule training with Owner, through Architect, with at least 7 days' advance notice.

END OF SECTION 23 3600

## SECTION 23 3713 - DIFFUSERS, REGISTERS, AND GRILLES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This section includes ceiling- and wall-mounted diffusers, registers, and grilles.
- B. Related Sections:
  - 1. Section 233714 "Fixed Louvers" for fixed and louvers and wall vents, whether or not they are connected to ducts.
  - 2. Section 233300 "Air Duct Accessories" for fire and smoke dampers and volume-control dampers not integral to diffusers, registers, and grilles.
  - 3. Section 230594 "General Testing, Adjusting and Balancing" for balancing diffusers, registers, and grilles.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product indicated, include the following:
  - 1. Data Sheet: Indicate materials of construction, finish, and mounting details; and performance data including throw and drop, static-pressure drop, and noise ratings.
  - 2. Diffuser, Register, and Grille Schedule: Indicate drawing designation, room location, quantity, model number, size, and accessories furnished.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from Installers of the items involved:
  - 1. Ceiling suspension assembly members.
  - 2. Method of attaching hangers to building structure.
  - 3. Size and location of initial access modules for acoustical tile.
  - 4. Ceiling-mounted items including lighting fixtures, diffusers, grilles, speakers, sprinklers, access panels, and special moldings.
  - 5. Duct access panels.
- B. Source quality-control reports.

## 1.5 QUALITY ASSURANCE

- A. Product Options: Drawings and schedules indicate specific requirements of diffusers, registers, and grilles and are based on the specific requirements of the systems indicated.
- B. NFPA Compliance: Install diffusers, registers, and grilles according to NFPA 90A, "Standard for the Installation of Air-Conditioning and Ventilating Systems."
- C. Airborne Noise:
  - 1. Comply with ANSI / AHRI 880 - Performance Rating of Air Terminals

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Air Factors
  - 2. Carnes.
  - 3. Kruegar.
  - 4. METALAIRE, Inc.
  - 5. Nailor Industries Inc.
  - 6. Price Industries.
  - 7. Titus.
  - 8. Tuttle & Bailey.
  - 9. AJ Manufacturing

### 2.2 REGISTERS, GRILLES, & DIFFUSERS

- A. General: The frames for all registers, grilles, and diffusers shall match type of ceiling where they are to be installed. Special frames shall be provided for narrow T-bar ceilings. Refer to reflected ceiling plan and other specification divisions for ceiling type. See drawings AND schedules for additional information.

### 2.3 SOURCE QUALITY CONTROL

- A. Verification of Performance: Rate diffusers, registers, and grilles according to ASHRAE 70, "Method of Testing for Rating the Performance of Air Outlets and Inlets."

### PART 3 - EXECUTION

#### 3.1 EXAMINATION

- A. Examine areas where diffusers, registers, and grilles are to be installed for compliance with requirements for installation tolerances and other conditions affecting performance of equipment.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

#### 3.2 INSTALLATION

- A. Install diffusers, registers, and grilles level and plumb, according to manufacturer's written instructions, coordination drawings, original design, and referenced standards.
- B. Ceiling-Mounted Outlets and Inlets: Drawings indicate general arrangement of ducts, fittings, and accessories. Air outlet and inlet locations have been indicated to achieve design requirements for air volume, noise criteria, airflow pattern, throw, and pressure drop. Make final locations where indicated, as much as practical. For units installed in lay-in ceiling panels, locate units in the center of panel. Where architectural features or other items conflict with installation, notify Architect for a determination of final location.
- C. Install diffusers, registers, and grilles with airtight connections to ducts and to allow service and maintenance of dampers, air extractors, and fire dampers.

#### 3.3 ADJUSTING

- A. After installation, adjust diffusers, registers, and grilles to air patterns indicated, or as directed, before starting air balancing.

#### 3.4 CLEANING

- A. After installation of diffusers, registers, and grilles, inspect exposed finish. Clean exposed surfaces to remove burrs, dirt, and smudges. Replace diffusers, registers, and grilles that have damaged finishes.

END OF SECTION 23 3713

## SECTION 237313 - CUSTOM FANWALL RETRO FIT UNITS

### PART 1 – GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.
- B. See the project drawings for layout and arrangement of the refurbished air handler.

#### 1.2 SUMMARY

- A. This Section includes custom air-handling units for indoor installations.
  - 1. Shop Drawings for each air handler refurbish are required.
  - 2. The multiple fans must comply with the manufactures recommendations distances for space before, after and to the sides of each fan.
  - 3. The fans shall be field wired through factory provided raceway to single point disconnect. Two fused disconnects per section. Provide unit with factory wired motors, field mounting of VFD's to each fancell by electrical contractor.
  - 4. See drawings for exact configurations.
  - 5. Provide back-draft dampers on the inlet of each fan in the air handler.
  - 6. Coordinate with electrical contractor and manufacture of fans on connection points.
  - 7. Ensure fan wall components are properly caulked to prevent air from leaking back through the seams.

#### 1.3 SUBMITTALS

- A. General: Submit each item in this Article according to the Conditions of the Contract and Division 1 Specification Sections.
- B. Product Data for each central-station air-handling unit specified, including the following:
  - 1. Certified fan-performance curves with system operating conditions indicated.
  - 2. Certified fan-sound power ratings.
  - 3. Motor ratings and electrical characteristics plus motor and fan accessories.
  - 4. Material gages and finishes.
- C. Shop Drawings from manufacturer detailing equipment assemblies and indicating dimensions, weights, loadings, required clearances, method of field assembly, components, and location and size of each field connection.
- D. Coordination Drawings, including floor plans and sections drawn to scale. Submit with Shop Drawings. Show mechanical-room layout and relationships between components and adjacent structural and mechanical elements. Show support locations, type of support, and weight on each support. Indicate and certify field measurements.



- E. Field test reports indicating and interpreting test results relative to compliance with specified requirements. If required
- F. Maintenance data for fanwall to include in the operation and maintenance manual.

#### 1.4 QUALITY ASSURANCE

- A. UL and NEMA Compliance: Provide motors required as part of air-handling units that are listed and labeled by UL and comply with applicable NEMA standards.
- B. Comply with NFPA 70 for components.
- C. Listing and Labeling: Provide electrically operated components specified in this Section that are listed and labeled.
  - 1. The Terms "Listed" and "Labeled": As defined in the National Electrical Code, Article 100.
  - 2. Listing and Labeling Agency Qualifications: A "Nationally Recognized Testing Laboratory" (NRTL) as defined in OSHA Regulation 1910.7.
- D. Coordination: Coordinate layout and installation of air-handling units with piping and ductwork and with other installations.
- E. Major components shall be products of Manufacturing firms regularly engaged in manufacture of this equipment with characteristics and capacities required and whose products have been in satisfactory use in similar service for not less than 10 years.

#### 1.5 DELIVERY, STORAGE, AND HANDLING

- A. Deliver air-handling unit as a factory-assembled module with protective crating and covering.
- B. Lift and support units with manufacturer's designated lifting or supporting points.
- C. Field assembled units per manufacturer's instructions.

#### 1.6 SEQUENCING AND SCHEDULING

- A. Coordinate size and location of structural-steel support members if required.

#### 1.7 EXTRA MATERIALS

- A. Furnish extra materials described below that match products installed, are packaged with protective covering for storage, and are identified with labels describing contents.

#### 1.8 WARRANTY

- A. The special warranty specified in this Article shall not deprive Owner of other rights Owner may have under other provisions of Contract Documents and shall be in addition to, and run concurrent with, other warranties made by Contractor under requirements of Contract Documents.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- 1. Basis of design: Huntair
- 2. Temtrol
- 3. Governair
- 4. ClimateCraft

### 2.2 MANUFACTURED UNITS

- A. General Description: Factory assembled components only, consisting of fans, motor and drive assembly.

### 2.3 RETURN FANS

- A. The FANWALL Array, shall consist of multiple, direct driven, arrangement plenum fans constructed per AMCA requirements for the duty Class III. All fans shall be selected to deliver design air flow at the specified operating TSP at the specified motor speed and as scheduled. The FANWALL Array shall be selected to operate at a system Total Static Pressure that does not exceed 90% of the specified fan's peak static pressure producing capability at the specified fan speed. All fans shall be coated with a phenolic coating.
- B. Each fan/motor "cube" cell shall consist of a powder coated 11 gauge, A60 galvanized steel intake wall, 14 gauge spun steel inlet funnel, and an 11 gauge, A60 galvanized steel motor support plate and structure. The fan cartridge intake wall, inlet funnel, and motor support structure shall have a Powder Coated Finish Color to be ~~Gray~~ or Sky White for superior corrosion resistance and easy cleaning.
- C. When using FANWALL Array Control with Variable Frequency Drive(s), all motors shall be IEEE inverter duty, premium efficiency, TEAO, T-frame motors selected at the specified or scheduled operating voltage and RPM(s). No ODP Motors allowed. Each motor shall be provided with ceramic bearings to prevent Electrical Discharge Machining (EDM) damage to the motor bearings and extend motor life by safely channeling harmful shaft currents to ground-
- D. Each fan/motor assembly shall be dynamically balanced to meet AMCA standard 204-96, category BV-5, Grade 1.0 with peak to peak deflection equal to or less than 0.5 mil at the design operating speed for the fan/motor cartridge.

- E. Scheduled motor HP for each air handler is maximum HP allowed.
- F. FANWALL Arrays do NOT require spring isolators, seismic isolation, or inertia bases. Other manufacturers must provide spring isolators, if required for vibration and sound isolation.
- G. The Discharge and Inlet bare fan Sound Power Levels for each individual octave band shall NOT exceed the values specified or scheduled for each individual Supply / Return FANWALL Array.
- H. The FANWALL Array(s) shall be provided with Coplanar Silencer package(s) with (fiberglass or Melamine foam insulation) sound absorption, acoustical media as noted below and or scheduled. The Coplanar Silencers shall NOT increase the fan total static pressure, nor shall they increase the airway tunnel length of the FWT Air Handling Unit when compared to the same FWT Air Handling Unit without a Coplanar Silencer array. The Coplanar Silencers (SOUND ATTENUATORS) will reduce the bare fan discharge sound power levels as noted below and/or scheduled. If NOT otherwise specified, the acoustical silencers shall reduce the bare fan discharge sound power levels by a minimum of 15 db, re 10<sup>-12</sup> watts with center frequencies of 125, 250, 500, 1000, 2000, 4000, and 8000 HZ when compared to the same Air Handling Unit without the silencers.
- I. The FANWALL Array shall consist of multiple fan and motor “cells”, spaced in the air way tunnel cross-section to provide a uniform air flow and velocity profile across the entire air way tunnel cross-section and components contained therein. Each fan motor shall be individually wired to an electrical control panel containing a Motor Starter Protector (MSP) for each motor. The Motor Starter Protectors will be wired to Variable Frequency Drive(s) (VFD) as specified elsewhere. Wire sizing shall be determined, and installed, in accordance with applicable NEC standards.
- J. One VFD per motor with the fan quantities as shown on the schedule shall be considered as redundancy.
- K. The FANWALL Array shall produce a uniform air flow profile and velocity profile within the airway tunnel of the air handling unit not to exceed the specified cooling coil and/or filter bank face velocity when measured at a point 12” from the intake side of the FANWALL Array septum wall, and at a distance of 42” from the discharge side of the FANWALL Array septum wall.
- L. Each fan/motor assembly shall be removable through a 24” wide, free area, access door located on the (discharge and / or inlet) side of the FANWALL Array.) NOTE: Narrower width access doors may require the break-down of the fan/motor assemblies into separate fan and motor components. Refer to plans for locations and sizes of the Access Doors.
- M. All Fans equipped with Back Draft Dampers. Any pressure drop associated with Back Draft Dampers to be added to associated total static pressures listed on motor schedule and included with the associated fan selections.
- N. Each fan will need to have an individual proof of start-up, run, shutdown and alarm capabilities.

- O. Each fan will need to be completely sealed to each individual unit.
- P. Each fan will need to be completely sealed to the exterior of the unit.
- Q. Each fan wall motor will ceramic bearings.

## 2.4 FANWALL TECHNOLOGY™ (FWT) ELECTRICAL

- A. Provide complete electrical and control system(s) required to run the FANWALL system(s) including all equipment, material, electrical enclosure, electrical components and electrical labor.
- B. FANWALL Array designs shall be in accordance with specific system requirements. Please see system requirements before electrical design of FANWALL system is to commence.
- C. FANWALL Array electrical designs shall be in accordance with the NEC, UL 508A, and Local Codes.
- D. Motor Circuit Protection:
  - 1. All motors in the FANWALL Array shall be provided with an individual Motor Protection for thermal overload protection. All motor starter (circuit) protectors shall be located in main enclosure(s) rated NEMA 1 Indoor or NEMA 3R Outdoor depending upon location. Electrical Enclosure(s) include Control Transformer, Lighting Transformer and will be Externally Mounted, Recess Mounted or Located Inside the Cabinet (where allowed) as required or as detailed on the plans.
  - 2. Electrical enclosures single or multipoint connection.
- E. Input Line Filters:
  - 1. As required by electrical design, when using variable frequency drives provide Input Line reactors with three percent (3%) impedance mounted externally if not already internal to variable frequency drive.
- F. Output Filters:
  - 1. As required by electrical design, when using variable frequency drives where distance and filtering is an issue, provide output line reactors as required. Size the output filter(s) accordingly to manufacturer's recommendations.
- G. Redundant Variable Frequency Drive Control:
  - 1. As required by system design, provide one Variable Frequency Drive per motor for normal operation. The Variable Frequency Drives shall be sized accordingly to start and hold respective motors in the Fanwall. Provide short circuit protection for each drive through means of using fuses with fuse blocks or circuit breakers. **If less than the design # of fans are provided then redundancy shall be by a primary and a redundant VFD per motor.**

2. The Variable Frequency Drives shall be mounted in a dedicated enclosure for connection to single point power. Variable Frequency Drive enclosure shall be provided with a main disconnecting means. Provide appropriate cooling of enclosure or if smart cube then no enclosure for the vfd... they are mounted on the fan cube.
3. Motor circuit protectors shall be used for each motor in the Fanwall array. Motor circuit protectors shall be housed and mounted in the VFD enclosure as required coordinate with electrical contractor. Motor circuit protectors may be mounted in a remote enclosure that is separate from VFD enclosure if design requires. Variable frequency drive enclosure and remote Motor circuit protector enclosure must be mounted at a minimal distance from fan array motors and each other.
4. Provide three phase power distribution wiring and control wiring as required coordinate with electrical contractor. All three phase power components shall have a rating listed for Short Circuit Current Rating. Provide control wiring and components required for complete operation of fan wall system. System controls, controls components and control wiring shall include but is not limited to Auto mode or manual mode, CFM control mode, or BMS control mode. Controls and control wiring shall include auto start/stop, manual start stop, life safety shutdown, smoke shutdown, system alarms and VFD alarms. All control wiring shall be included in VFD enclosure provided with system.

## 2.5 VIBRATION TESTING

- A. A Factory Balance test shall be performed on the fan assembly to certify that the fan meets the following vibration values:
  1. Direct Drive - Spring Isolation Assembly
  2. Rotational: Vibration Amplitude
  3. Speed: Peak to Peak
  4. Up to and including 2000 rpm 0.50 mils
  5. 2000 + rpm 0.25 mils
- B. Vibration measurements shall be taken in three orthogonal directions: One taken parallel to shaft in the horizontal plane and two taken perpendicular to the shaft in the horizontal and vertical planes. The values will be checked with the levels being measured in mils peak to peak.
- C. During balancing, the fan shall be imposed with an operating resistance equal to the design external static pressure.
- D. A certificate of compliance signed by the manufacturers Quality Control Inspector shall be attached to each fan assembly at the factory and incorporated into the operating and maintenance manuals.

## 2.6 VARIABLE FREQUENCY DRIVES

- A. The manufacturer shall provide, mount and wire a Primary Variable Frequency Drive "VFD" to each fan motor. VFDs or electrical panels mounted outside the air handler shall have a minimum NEMA 3R enclosure with a fused disconnect device. A keypad and LED/LCD

display shall be integral to each VFD for programming and troubleshooting. Each VFD shall be certified and rated for operation in a temperature range of -10°C to 50°C and a RH range of 5% to 95% non-condensing. Each VFD shall be certified for operation at the jobsite altitude (show de-rating value in submittal). The VFD shall be capable of starting into a rotating load (forward or reverse) and shall smoothly accelerate or decelerate to the set point without experiencing component damage or causing a fault. Each VFD shall be provided with a DC link choke, a 5% line reactor and a harmonic filter if necessary to guarantee a total harmonic distortion of less than 5% per IEEE 519. The VFD manufacturer shall provide certified calculations to prove the 5% or less distortion, upon request by the engineer.

- B. For applications where the VFD is to be operating at various, but constant speeds, the RTU supplier must coordinate with the VFD manufacturer and motor manufacturer to determine if there is a need for the motor to be provided with either insulating bearings or a shaft grounding system to prevent pitting of the bearings due to electrical discharge.
- C. Each VFD must be started and set-up by a factory authorized service technician employed by a factory certified organization. A start-up report, complete with all initial program parameter, must be included in the O&M manuals that are provided by the contractor.
- D. Provide on the fly starting capability for each VFD.

## 2.7 SOUND POWERS LEVELS

- A. It shall be the option of the contractor to provide a quieter fan, acoustical lining, sound traps or other sound attenuating devices within the air handling unit(s) to supplement the alternate design in order to meet the specified levels above. Contractor is responsible for all costs associated with the supply and installation of larger fan(s), motor(s) or electrical service(s) to overcome increased component and/or system effect static pressures. The use of external sound treatment is not acceptable.
- B. The fans sound power data shall be submitted for approval. The submittal shall include a complete description of the methods and procedures used to develop the sound power levels being submitted.

## 2.8 CLEANING AND WRAPPING FOR SHIPMENT

- A. Unit shall be cleaned swept & vacuumed clean.
- B. Cleaned unit shall be shipped on an open flat bed truck and covered by a tarp to protect from road contamination prior to shipment.

## 2.9 DELIVERY, STORAGE & HANDLING

- A. Unit shall ship with all openings securely covered with wood and / or nylon reinforced plastic wrap and to be watertight. Each unit (will be covered by a tarp) and securely strapped down on an open flatbed truck.
- B. Units must be stored in a clean dry area and protected from the weather and construction traffic. Carefully follow manufacturers' storage instructions if installation does not immediately follow arrival at the job site.

- C. Follow manufacturers rigging guidelines for movement and installation of equipment.

## 2.10 WARRANTY

- A. Unit manufacturer to warrant it's product to be free of defects in materials and workmanship under normal use when installed and operated in accordance with factory recommendations for a period of 18 months from date of shipment or 12 months after initial equipment start-up, which ever occurs first. Equipment found to be defective should be replaced or repaired to include all parts and labor. Component parts that require periodic replacement due to normal wear such as filters, fan belts, etc. are not covered by the warranty.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine areas and conditions to receive equipment, for compliance with installation tolerances and other conditions affecting performance of central-station air-handling units.
- B. Examine roughing-in of steam, hydronic, condensate drainage piping, and electrical to verify actual locations of connections before installation.
- C. Do not proceed with installation until unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install custom air-handling units level and plumb, according to manufacturer's written instructions.
  - 1. Floor-Mounted Units: Support on concrete housekeeping curbs using neoprene pads. Secure units to anchor bolts.
- B. Arrange installation of units to provide access space around air-handling units for service and maintenance.

### 3.3 CONNECTIONS

- A. Electrical: Conform to applicable requirements of Division 23 Sections.
  - 1. Connect fan motors to wiring systems and to ground. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. Where manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.
  - 2. Temperature control wiring and interlock wiring is specified in Division 23.

### 3.4 ADJUSTING

- A. Adjust damper linkages for proper damper operation.

### 3.5 CLEANING

- A. After completing installation, inspect exposed finish. Remove burrs, dirt, and construction debris, and repair damaged finishes including chips, scratches, and abrasions.



- B. Clean fan interiors to remove foreign material and construction dirt and dust. Vacuum clean fan wheels, cabinets, and coils entering air face.

### 3.6 COMMISSIONING

- A. Manufacturer's Field Inspection: Engage a factory-authorized service representative to perform the following:
  - 1. Inspect field assembly of components and installation of central-station air-handling units including piping, ductwork, and electrical connections.
  - 2. Prepare a written report on findings and recommended corrective actions.
- B. Final Checks before Startup: Perform the following before startup:
  - 1. Verify that shipping, blocking, and bracing are removed.
  - 2. Verify that unit is secure on mountings and supporting devices and that connections for piping, ductwork, and electrical are complete. Verify that proper thermal overload protection is installed in motors, starters, and disconnects.
  - 3. Perform cleaning and adjusting specified in this Section.
  - 4. Disconnect fan drive from motor, verify proper motor rotation direction, and verify free fan wheel rotation and smooth bearings operations. Reconnect fan drive system, align belts, and install belt guards.
  - 5. Lubricate bearings, pulleys, belts, and other moving parts with factory-recommended lubricants.
  - 6. Verify that manual and automatic volume control, and fire and smoke dampers in connected ductwork systems are in fully open position.
- C. Starting procedures for central-station air-handling units include the following:
  - 1. Energize motor; verify proper operation of motor, drive system, and fan wheel. Adjust fan to indicated rpm. Replace fan and motor pulleys as required to achieve design conditions.
  - 2. Measure and record motor electrical values for voltage and amperage.
  - 3. Manually operate dampers from fully closed to fully open position and record fan performance.
- D. Refer to Division 23 Section "Testing, Adjusting, and Balancing" for air-handling system testing, adjusting, and balancing.

3.7 DEMONSTRATION

- A. Engage the services of a factory-authorized service representative to train Owner's maintenance personnel on procedures and schedules related to startup and shutdown, troubleshooting, servicing, and preventive maintenance.
  - 1. Review data in the operation and maintenance manuals. Refer to Division 1 Section "Contract Closeout."
  - 2. Schedule training with Owner, through Architect, with at least 7 days' advance notice.

END OF SECTION

BLANK PAGE

## SECTION 23 7600 - HOSPITAL OPERATING ROOM MODULAR DIFFUSER SYSTEM

### PART 1 - GENERAL

#### 1.1. WORK INCLUDED

- A. The purpose of this specification is to provide a modular diffuser system with integrated LED flush lighting, and integrated structural support that has the capability of accepting operating room equipment boom, surgical light/monitor and imaging equipment loads directly. Internal framing shall be capable of handling the lateral forces of all equipment supports. The system will be installed by the contractor in accordance with the manufacturer's instructions as outlined in the manufacturer's installation manual. Supplier of this modular diffuser system shall be responsible for all costs associated with the engineering, manufacturing, and project coordination of lights, structural boom and equipment supports included within the boundary of this modular system. These costs shall include the fully integrated (factory assembled) supply of the air delivery system, lighting system, and structural support system as identified above along with the layout and engineering for all electrical wiring, piping, mechanical and support structures within the system. Non-structural diffuser modules are not allowed. These costs also include a set of fully executed and stamped structural engineering calculations on the entire modular system, including all components mentioned above, for the state in which this project will be installed. The structural calculation package shall be delivered to the project team after a "For Record" approval of submittal documents has been signed and returned by an authorized administrator of the project team.

#### 1.2. SYSTEM DESCRIPTION

- A. The operating room air supply array shall be a single large diffuser (SLD) system of modular construction consisting of a continuous ceiling grid with an aluminum air frame, HEPA filter grid channel (filters optional), integrated LED lighting system (capable of integrating Indigo-Clean® disinfecting technology), integrated boom mounts, guillotine style (room side adjustable) dampers and laminar air diffuser openings. The ceiling grid is required to be able to completely seal off the interstitial space from the room. The diffuser system shall also include a structural steel air delivery duct (SLD) that is an integrated part of the ceiling grid. The structural steel duct is required to pressurize the system for distribution through each individual supply air opening in the ceiling while providing integrated mounting plates for all ceiling hung equipment. The steel duct shall have a powder coating to ensure all exterior and interior surfaces are protected. The system shall also be capable of accepting operating room boom loads directly as part of an engineered and structurally stamped architectural system.
- B.

#### 1.3. QUALITY ASSURANCE

- A. Owner's Factory Inspection:
  1. The owner or owner's representative shall maintain the right to tour the operating room diffuser system at manufacturer's plants any time that fabrication is being performed on components intended for this project.

2. The owner may exercise the option, giving 24-hour advance notice minimum, to tour the plant and inspect for component assembly, painting, cleaning, or packaging to ensure that quality control is being maintained.

#### 1.4. SUBMITTAL

- A. Submittal shall be by the manufacturer.
- B. Required with the Bid: Detailed information on structural, mechanical, electrical, and other services necessary to evaluate installation requirements.
- C. Required after execution of Contract: Shop drawings shall be submitted within two weeks of purchase order acceptance, and they shall include: complete specifications, descriptive drawings, catalog cuts, and descriptive literature on all components used in the diffuser system, with make, model, dimensions, capacity, weight, and electrical schematics.

#### 1.5. MANUFACTURER CONTACTS

- A. Contact manufacturer directly if additional information is required, such as product or material descriptions, layouts, or installation requirements. Manufacturer is required to have a full-scale Surgical Suite mock-up showing the Modular Diffuser system similar to the product available for demonstration.

### PART 2 - PRODUCTS

#### 2.1. ACCEPTABLE MANUFACTURERS

- A. SLD AirFrame

#### 2.2. DIFFUSER GRID SYSTEM

- A. The grid system shall utilize an LED lighted grid and bottom-load flush powder-coated steel HEPA filtered air frame. HEPA filters, diffusers, guillotine style balancing dampers and blank pans shall be capable of being loaded from the bottom of the system directly into the grid opening. All lighting components shall be accessible from the room side. The system shall incorporate a hinged damper/diffuser assembly capable of being independently opened for cleaning as well as access for (optional) HEPA filter installation. The damper/diffuser shall be room side adjustable. The damper/diffuser assembly shall be located downstream of the (optional) HEPA filter and flush with the ceiling to ensure easy balancing of the system with all components installed. The damper/diffuser assembly shall incorporate an Allen Key guide for easy access to the guillotine style damper adjustment mechanism. Systems that utilize balancing dampers located upstream of the HEPA are not permitted. Systems that utilize balancing dampers that are not room side adjustable are not permitted.
- B. Grid members shall be formed together into modules. Grid shall be caulked with an appropriate sealant as necessary. The ceiling support grid shall be structurally constructed to remain dimensionally stable.

- C. The lighted grid system shall have integrated LED lighting within the grid channel. The interior space within the Lighted Grid channel is not required to be powder coated. The lighted grid shall be integrated into the diffuser system such that the finished elevation of the lighted grid lines up within 1/8" in elevation to the bottom of the HEPA filtered air frame. Light fixtures, such as teardrop lights, are not permitted. Light fixtures that block the airflow within the supply air, such as recessed light troffers, are not permitted. All lighting components shall be pre-installed at the factory. Systems that require field installation of lighting components are not permitted. Lighting circuits shall utilize quick connect fittings for module-to-module connection.
1. The complete lighting system consisting of LED assemblies, drivers, wireway, lenses, and wiring shall be an integral part of the lighted grid. The LED lighted grid shall be UL listed and so marked.
  2. The drivers shall be housed in external electrical enclosures factory mounted on sidewall and accessible from the room side via access panel (by others). Drivers shall be UL listed and so marked. Drivers can also be remote mounted in an electrical closet or mechanical space with proper gage wiring selections.
  3. Wiring within the grid for the lighting circuit shall be contained within and protected by the grid system. The system shall have the ability to handle normal and emergency wiring circuits. The system shall have the ability to handle high and low voltage wiring circuits. The light lens shall sit flush with the bottom of the air frame grid channel. Light lens covers shall be clear acrylic or polycarbonate ribbed diffusers that snap flush to the grid channel without external fasteners.
  4. LED lighting components shall be able to easily snap into the grid without the use of rivets, nuts, bolts, or other hardware fasteners.
  5. LED lighting system shall be bi-directional in grid array and capable of dimming to 1%.
  6. Indigo-Clean™ LED technology with two operational modes: White Disinfection Mode is a white LED array for ambient lighting plus simultaneous low power 405nm indigo array for low-level continuous environmental disinfection. Indigo Disinfection Mode is a high power 405nm Indigo LED array for continuous environmental disinfection. Operational mode determined via internal low-voltage device based upon input provided by external IC100 room control system. Room controls and control wiring shall be installed in the field by electrical contractor to meet all local codes.
    - a. Serviceable composite-bodied mid-power white LED array and high-power 405 nm indigo LED array.
    - b. Available 3700K and 4300K color temperatures with maximum 3-step MacAdam variation allowance.
    - c. Minimum 80 CRI standard with optional minimum 90 CRI available.
    - d. 120/277VAC, 50/60Hz electrical input with serviceable high-power factor electronic, constant-current drivers (<10% THD, >0.90 PF). Minimum 85% driver efficiency.
    - e. Standard 0-10V dimming with 1-100% range with dim-to-dark capabilities in White Disinfection Mode. 700 µA maximum source current.
- D. The HEPA filtered air frame system shall incorporate air passages on all sides to jet air underneath the lighted grid to wash the area below the lights of particles. The top duct, steel structures and air frame channels shall be protected with a powder-coat finish. All hardware shall be stainless steel.
- E. The installing contractor shall furnish and install the all thread rod (ATR) up to and including the connection components at the building structure.

- F. The lighted grid system shall be capable of attaching clips for hanging patient lifts, equipment supports, and other components.
- G. All surfaces that are scratched shall be painted and touched up by the contractor after installation. Paint color to match all surfaces or as approved by the engineer or owner.
- H. Filler Blank Panels: Solid filler panels (if required) shall be constructed of powder coated steel or aluminum with welded corners, an upward facing trough and designed to affect an airtight seal in the channel grid. The finish of the panel shall match the ceiling grid finish.
- I. Care should be used in selection of materials that are resistant to cleaning agents used by the owner.

### 2.3. AIR SUPPLY INTEGRATED TO CEILING GRID

- A. Provide an air delivery duct attached to the ceiling grid as an integral part of the ceiling grid diffuser system. Modules shall be supplied completely pre-assembled with the lighting grid, HEPA filtered air frame and duct as one piece.
- B. The ceiling grid module shall be capable of being suspended from the building structure based on the coordination between the structural engineer of record and the modular diffuser system manufacturer's structural stamped package. The structural engineer of record (SEOR) shall be responsible for designing the structural connections and related steel infrastructure (if required) to support the ceiling system from the building.
- C. Modules will be welded or rivet style construction using steel roof panels and side panels welded to internal HSS framing (type of HSS framing is determined by ceiling loads). System shall be sized to meet structural load requirements. Minimum four pre-drilled holes per module will be provided at the perimeter of the module roof for suspension using 5/8" hardware (ATR typical). The entire ceiling grid module shall be coated with a baked-on powder coating.
- D. Units shall be manufactured to dimensional tolerance of +/- 1/8" on width and length and diagonal dimensions or squareness of +/- 1/8".
- E. Provide pre-drilled bolt holes in the sides of modules for field connection of one module to another (splits) where applicable. In most cases, each module is sized to fit through a standard doorway and freight elevator.
- F. The HSS framed modules shall be capable of accepting operating room boom loads directly as part of an engineered and structurally stamped system.

## PART 3 - EXECUTION

### 3.1. INSTALLATION - GENERAL

- A. Install in accordance with the manufacturer's installation manual. The installing contractor shall be responsible for the complete installation of the operating room ceiling system. All repairs and re-testing cost of the repairs and other related tests that would have to be repeated as a result of repairs done to the system shall be the installing contractor's responsibility.

### 3.2. MODULE INSTALLATION

- A. It is the intent that the modules be installed to line and true level, symmetrical to rooms and spaces, and with due regard to appearance and structural stability. The ceiling shall be level throughout within 1/8 inch.

- B. All suspended ceiling system work shall be done in accordance with the procedures endorsed by the Ceiling and Interior Systems Contractor's Association (CISCA), except where specified otherwise.
- C. Lay out modules as shown on shop drawings. Coordinate with mechanical and electrical equipment in framing and cutting around ceiling penetrations.
- D. Hang level as shown on the drawings in accordance with ASTM C636 and the manufacturer's current printed instructions for the type of installation used.
- E. Modules shall be supported per structural specifications. Modules are butted side to side and end to end and bolted together. A sealant is required at all joints. All field assembly, installation equipment and materials are by contractor unless noted.
- F. Install hanging hardware at specified locations and per manufacturer's instructions.
- G. Install seals per manufacturer's instructions.
- H. Blank pans (if required) and associated hold-down clips are to be installed per manufacturer's instructions.
- I. Damper-Diffuser (DD) assemblies riveted in each grid opening per layout drawings.
- J. Perimeter lighting fixtures in hard ceiling to be installed per the ceiling plans (including optional UltraLED® linear lighting fixtures).
- K. Wiring shall be installed by electrical contractor to meet all local codes. House power and room control wiring from modular system electrical enclosures is completed in the field by others.

### 3.3. MODULE INSTALLATION

- A. The general cleanliness requirements shall be that all hardware exposed to the operating room interior or in the airstream, regardless of size or complexity, must be visibly free of oil, grease, particles, chips, fibers, dirt, etc., prior to installation in the operating room area.
- B. The general cleaning sequence for the units shall be as follows: Visual inspection per above; vacuum removal of particles; solvent wipe cleaning; drying; visual inspection per above.

### 3.4. CEILING CERTIFICATION

- A. At the completion of the ceiling installation, with all components installed and wall system in place, an independent certifier under a separate contract shall conduct a series of tests to ensure that the operating room complies with owner's specifications.

END OF SECTION 23 7600



## SECTION 23 8216 - HYDRONIC AIR COILS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section includes hydronic heating and cooling air coils.
- B. VAV box and Phoenix valve reheat coils.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for each air coil.
  - 2. Include rated capacities, operating characteristics, and pressure drops for each air coil.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Reflected ceiling plans, drawn to scale, on which coil location and ceiling-mounted access panels are shown and coordinated with each other.

#### 1.5 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For air coils to include in operation and maintenance manuals.

### PART 2 - PRODUCTS

#### 2.1 DESCRIPTION

- A. ASHRAE Compliance: Comply with applicable requirements in ASHRAE 62.1, Section 5 - "Systems and Equipment" and Section 7 - "Construction and Startup."

## 2.2 COILS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Aerofin.
  - 2. Carrier Corporation; a UTC company.
  - 3. Coil Company, LLC.
  - 4. Colmac Coil Manufacturing, Inc.
  - 5. Dunham-Bush USA.
  - 6. Heatcraft Worldwide Refrigeration.
  - 7. Greenheck Fan Corporation.
  - 8. Trane.
  - 9. USA Coil & Air.
  - 10. York
  - 11. Konvekta
  - 12. Precision Coil
- B. Performance Ratings: Tested and rated according to AHRI 410 and ASHRAE 33.
- C. Minimum Working-Pressure/Temperature Ratings: 200 psig, 325 deg F.
- D. Source Quality Control: Factory tested to 300 psig.
- E. Tubes: ASTM B 743 copper, minimum 0.035 inch thick.
- F. Fins: Aluminum or Copper, minimum 0.006 inch thick.
- G. Headers: Seamless copper tube with brazed joints, prime coated.
- H. Reference specification 233600 "Air Terminal Units" for reheat coils for both VAV Boxes and Phoenix valves.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine ducts, plenums, and casings to receive air coils for compliance with requirements for installation tolerances and other conditions affecting coil performance.
- B. Examine roughing-in for piping systems to verify actual locations of piping connections before coil installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install coils level and plumb.
- B. Install coils in metal ducts and casings constructed according to SMACNA's "HVAC Duct Construction Standards, Metal and Flexible."
- C. Straighten bent fins on air coils.
- D. Clean coils using materials and methods recommended in writing by manufacturers, and clean inside of casings and enclosures to remove dust and debris.

### 3.3 CONNECTIONS

- A. Piping installation requirements are specified in other Sections. Drawings indicate general arrangement of piping, fittings, and specialties.
- B. Install piping adjacent to coils to allow service and maintenance.
- C. Connect water piping with unions and shutoff valves to allow coils to be disconnected without draining piping. Control valves are specified in Section 230900 "Instrumentation and Control for HVAC," and other piping specialties are specified in Section 232116 "Hydronic Piping Specialties."

END OF SECTION 23 8216

## SECTION 260519 - LOW-VOLTAGE ELECTRICAL POWER CONDUCTORS AND CABLES

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Building wires and cables rated 600 V and less.
  - 2. Connectors, splices, and terminations rated 600 V and less.
- B. Related Requirements:
  - 1. Section 271500 "Communications Horizontal Cabling" for cabling used for voice and data circuits.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each type of product.

#### 1.4 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For testing agency.
- B. Field quality-control reports.

#### 1.5 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Member Company of NETA or an NRTL.
  - 1. Testing Agency's Field Supervisor: Certified by NETA to supervise on-site testing.

### PART 2 - PRODUCTS

#### 2.1 CONDUCTORS AND CABLES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Alcan Products Corporation; Alcan Cable Division.
  - 2. Alpha Wire.
  - 3. Belden Inc.
  - 4. Encore Wire Corporation.
  - 5. General Cable Technologies Corporation.
  - 6. Southwire Incorporated.
- B. Copper Conductors: Comply with NEMA WC 70/ICEA S-95-658.
- C. Conductor Insulation: Comply with NEMA WC 70/ICEA S-95-658 for Type THHN-2-THWN-2.

## 2.2 CONNECTORS AND SPLICES

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. AFC Cable Systems, Inc.
  - 2. Gardner Bender.
  - 3. Hubbell Power Systems, Inc.
  - 4. Ideal Industries, Inc.
  - 5. IlSCO; a branch of Bardes Corporation.
  - 6. NSI Industries LLC.
  - 7. O-Z/Gedney; a brand of the EGS Electrical Group.
  - 8. 3M; Electrical Markets Division.
  - 9. Tyco Electronics.
  - 10.
- B. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

## 2.3 SYSTEM DESCRIPTION

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.

## PART 3 - EXECUTION

- A. Feeders:
  - 1. Copper Stranded
- B. Branch Circuits: Copper. Solid or stranded for No. 10 AWG and smaller; stranded for No. 8 AWG and larger, except VFC cable, which shall be extra flexible stranded.
- C. Fire Alarm Circuits:
  - 1. THWN-2 conductors in raceway for fire alarm power and horn/strobe indicating circuits.
  - 2. Power limited signaling circuit cable in raceway for initiating loops
- D. Class 1 Control Circuits: Type THWN-2, in raceway.
- E. Class 2 Control Circuits: Type THWN-2, in raceway.
- F.

## 3.2 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

- A. Branch Circuits Concealed in Wall and Partitions: Type THHN/THWN-2, single conductors in raceway.
  - 1. Patient Care Area branch circuits: Branch circuit wiring in all patient care areas shall comply with NEC 517.13 (a). Do not use non-metallic conduits or raceways for branch circuits serving areas other than mechanical and electrical rooms.
- B. Branch Circuits Concealed in Concrete, below Slabs-on-Grade, and Underground: Type THHN-2-THWN-2, single conductors in raceway.
- C. Every Branch circuit must have a dedicated neutral.

- D. Cord Drops and Portable Appliance Connections: Type SO, hard service cord with stainless-steel, wire-mesh, strain relief device at terminations to suit application.

### 3.3 INSTALLATION OF CONDUCTORS AND CABLES

- A. Conceal cables in finished walls, ceilings, and floors unless otherwise indicated.
- B. Complete raceway installation between conductor and cable termination points according to Section 260533 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.
- C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.
- D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.
- E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.
- F. Support cables according to Section 260529 "Hangers and Supports for Electrical Systems."
- G. Complete cable tray systems installation according to Section 260536 "Cable Trays for Electrical Systems" prior to installing conductors and cables.
- H. Fire alarm cables to be installed in EMT raceway

### 3.4 CONNECTIONS

- A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.
- B. Make splices, terminations, and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than unspliced conductors.
  - 1. Use oxide inhibitor in each splice, termination, and tap for aluminum conductors.
- C. Wiring at Outlets: Install conductor at each outlet, with at least 6 inches (150 mm) of slack.

### 3.5 IDENTIFICATION

- A. Identify and color-code conductors and cables according to Section 260553 "Identification for Electrical Systems."
- B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

### 3.6 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

3.7 FIRESTOPPING

- A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Section 078413 "Penetration Firestopping."

3.8 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
  - 1. After installing conductors and cables and before electrical circuitry has been energized, test service entrance and feeder conductors and conductors feeding all imaging equipment for compliance with requirements.
  - 2. Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each splice in conductors No. 3 AWG and larger. Remove box and equipment covers so splices are accessible to portable scanner. Correct deficiencies determined during the scan.
    - a. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each splice 11 months after date of Substantial Completion.
    - b. Instrument: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
    - c. Record of Infrared Scanning: Prepare a certified report that identifies splices checked and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
- B. Test and Inspection Reports: Prepare a written report to record the following:
  - 1. Procedures used.
  - 2. Results that comply with requirements.
  - 3. Results that do not comply with requirements and corrective action taken to achieve compliance with requirements.
- C. Cables will be considered defective if they do not pass tests and inspections.

**END OF SECTION 260519**

## **SECTION 260529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. This Section includes the following:
  - 1. Hangers and supports for electrical equipment and systems.
  - 2. Construction requirements for concrete bases.
- B. Related Sections include the following:
  - 1. Section 260548 "Vibration and Seismic Controls for Electrical Systems" for products and installation requirements necessary for compliance with seismic criteria.

#### **1.3 DEFINITIONS**

- A. EMT: Electrical metallic tubing.
- B. IMC: Intermediate metal conduit.
- C. RMC: Rigid metal conduit.

#### **1.4 PERFORMANCE REQUIREMENTS**

- A. Delegated Design: Design supports for multiple raceways, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.
- B. Design supports for multiple raceways capable of supporting combined weight of supported systems and its contents.
- C. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.
- D. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed for this Project, with a minimum structural safety factor of five times the applied force.

#### **1.5 ACTION SUBMITTALS**

- A. Product Data: For the following:
  - 1. Steel slotted support systems.
  - 2. Nonmetallic slotted support systems.
- B. Shop Drawings: Signed and sealed by a qualified professional engineer. Show fabrication and installation details and include calculations for the following:
  - 1. Trapeze hangers. Include Product Data for components.
  - 2. Steel slotted channel systems. Include Product Data for components.
  - 3. Nonmetallic slotted channel systems. Include Product Data for components.
  - 4. Equipment supports.

#### **1.6 INFORMATIONAL SUBMITTALS**

- A. Welding certificates.

#### **1.7 QUALITY ASSURANCE**

- A. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."



University of Utah

Salt Lake City, Utah 84104

- B. Comply with NFPA 70.

## 1.8 COORDINATION

- A. Coordinate size and location of concrete bases. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified together with concrete Specifications.
- B. Coordinate installation of roof curbs, equipment supports, and roof penetrations. These items are specified in Section 077200 "Roof Accessories."

## PART 2 - PRODUCTS

### 2.1 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

- A. Steel Slotted Support Systems: Comply with MFMA-4, factory-fabricated components for field assembly.
  - 1. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Allied Tube & Conduit.
    - b. Cooper B-Line, Inc.; a division of Cooper Industries.
    - c. ERICO International Corporation.
    - d. GS Metals Corp.
    - e. Thomas & Betts Corporation.
    - f. Unistrut; Tyco International, Ltd.
    - g. Wesanco, Inc.
  - 2. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
  - 3. Nonmetallic Coatings: Manufacturer's standard PVC, polyurethane, or polyester coating applied according to MFMA-4.
  - 4. Painted Coatings: Manufacturer's standard painted coating applied according to MFMA-4.
  - 5. Channel Dimensions: Selected for applicable load criteria.
- B. Raceway and Cable Supports: As described in NECA 1 and NECA 101.
- C. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.
- D. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for non-armored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be malleable iron.
- E. Structural Steel for Fabricated Supports and Restraints: ASTM A 36/A 36M, steel plates, shapes, and bars; black and galvanized.
- F. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:
  - 1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
    - a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
      - 1) Hilti Inc.
      - 2) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
      - 3) MKT Fastening, LLC.
      - 4) Simpson Strong-Tie Co., Inc.; Masterset Fastening Systems Unit.
  - 2. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.

- a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1) Cooper B-Line, Inc.; a division of Cooper Industries.
  - 2) Empire Tool and Manufacturing Co., Inc.
  - 3) Hilti Inc.
  - 4) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
  - 5) MKT Fastening, LLC.
3. Concrete Inserts: Steel or malleable-iron, slotted support system units similar to MSS Type 18; complying with MFMA-4 or MSS SP-58.
4. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.
5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.
6. Toggle Bolts: All-steel springhead type.
7. Hanger Rods: Threaded steel.

## 2.2 FABRICATED METAL EQUIPMENT SUPPORT ASSEMBLIES

- A. Description: Welded or bolted, structural-steel shapes, shop or field fabricated to fit dimensions of supported equipment.
- B. Materials: Comply with requirements in Section 055000 "Metal Fabrications" for steel shapes and plates.

## PART 3 - EXECUTION

### 3.1 APPLICATION

- A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems except if requirements in this Section are stricter.
- B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMT, IMC, and RMC as required by NFPA 70. Minimum rod size shall be 1/4 inch (6 mm) in diameter.
- C. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted or other support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.
  1. Secure raceways and cables to these supports with single-bolt conduit clamps using spring friction action for retention in support channel.
- D. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch (38-mm) and smaller raceways serving branch circuits and communication systems above suspended ceilings and for fastening raceways to trapeze supports.

### 3.2 SUPPORT INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this Article.
- B. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb (90 kg).
- C. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:
  1. To New Concrete: Bolt to concrete inserts.
  2. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
  3. To Steel: Beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69.
  4. To Light Steel: Sheet metal screws.

University of Utah

Salt Lake City, Utah 84104

5. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel racks attached to substrate by means that meet seismic-restraint strength and anchorage requirements.
  - D. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.
- 3.3 INSTALLATION OF FABRICATED METAL SUPPORTS
- A. Comply with installation requirements in Section 055000 "Metal Fabrications" for site-fabricated metal supports.
  - B. Cut, fit, and place miscellaneous metal supports accurately in location, alignment, and elevation to support and anchor electrical materials and equipment.
  - C. Field Welding: Comply with AWS D1.1/D1.1M.
- 3.4 CONCRETE BASES
- A. Construct concrete bases of dimensions indicated but not less than 4 inches (100 mm) larger in both directions than supported unit, and so anchors will be a minimum of 10 bolt diameters from edge of the base.
  - B. Use 3000-psi (20.7-MPa), 28-day compressive-strength concrete. Concrete materials, reinforcement, and placement requirements are specified in Section 033000 "Cast-in-Place Concrete" or Section 033053 "Miscellaneous Cast-in-Place Concrete."
  - C. Anchor equipment to concrete base.
    1. Place and secure anchorage devices. Use supported equipment manufacturer's setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
    2. Install anchor bolts to elevations required for proper attachment to supported equipment.
    3. Install anchor bolts according to anchor-bolt manufacturer's written instructions.
- 3.5 PAINTING
- A. Touchup: Clean field welds and abraded areas of shop paint. Paint exposed areas immediately after erecting hangers and supports. Use same materials as used for shop painting. Comply with SSPC-PA 1 requirements for touching up field-painted surfaces.
    1. Apply paint by brush or spray to provide minimum dry film thickness of 2.0 mils (0.05 mm).
  - B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

**END OF SECTION 260529**

## **SECTION 260533 - RACEWAYS AND BOXES FOR ELECTRICAL SYSTEMS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Metal conduits, tubing, and fittings.
  - 2. Nonmetal conduits, tubing, and fittings.
  - 3. Metal wireways and auxiliary gutters.
  - 4. Nonmetal wireways and auxiliary gutters.
  - 5. Surface raceways.
  - 6. Boxes, enclosures, and cabinets.
  - 7. Handholes and boxes for exterior underground cabling.
- B. Related Requirements:
  - 1. Section 260543 "Underground Ducts and Raceways for Electrical Systems" for exterior ductbanks, manholes, and underground utility construction.
  - 2. Section 270528 "Pathways for Communications Systems" for conduits, wireways, surface pathways, innerduct, boxes, faceplate adapters, enclosures, cabinets, and handholes serving communications systems.
  - 3. Section 280528 "Pathways for Electronic Safety and Security" for conduits, surface pathways, innerduct, boxes, and faceplate adapters serving electronic safety and security.

#### **1.3 DEFINITIONS**

- A. ARC: Aluminum rigid conduit.
- B. GRC: Galvanized rigid steel conduit.
- C. IMC: Intermediate metal conduit.

#### **1.4 ACTION SUBMITTALS**

- A. Product Data: For surface raceways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.
- B. LEED Submittals:
  - 1. Product Data for Credit IEQ 4.1: For solvent cements and adhesive primers, documentation including printed statement of VOC content.
  - 2. Laboratory Test Reports for Credit IEQ 4: For solvent cements and adhesive primers, documentation indicating that products comply with the testing and product requirements of the California Department of Health Services' "Standard

Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

- C. Shop Drawings: For custom enclosures and cabinets. Include plans, elevations, sections, and attachment details.

## 1.5 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Conduit routing plans, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of items involved:
  - 1. Structural members in paths of conduit groups with common supports.
  - 2. HVAC and plumbing items and architectural features in paths of conduit groups with common supports.
- B. Qualification Data: For professional engineer.
- C. Seismic Qualification Certificates: For enclosures, cabinets, and conduit racks and their mounting provisions, including those for internal components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
  - 4. Detailed description of conduit support devices and interconnections on which the certification is based and their installation requirements.
- D. Source quality-control reports.

## PART 2 - PRODUCTS

### 2.1 METAL CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. AFC Cable Systems, Inc.
  - 2. Allied Tube & Conduit; a Tyco International Ltd. Co.
  - 3. Anamet Electrical, Inc.
  - 4. Electri-Flex Company.
  - 5. O-Z/Gedney; a brand of EGS Electrical Group.
  - 6. Picoma Industries, a subsidiary of Mueller Water Products, Inc.
  - 7. Republic Conduit.
  - 8. Robroy Industries.
  - 9. Southwire Company.
  - 10. Thomas & Betts Corporation.
  - 11. Western Tube and Conduit Corporation.
  - 12. Wheatland Tube Company; a division of John Maneely Company.

- B. Listing and Labeling: Metal conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. GRC: Comply with ANSI C80.1 and UL 6.
- D. ARC: Comply with ANSI C80.5 and UL 6A.
- E. IMC: Comply with ANSI C80.6 and UL 1242.
- F. PVC-Coated Steel Conduit: PVC-coated IMC.
  - 1. Comply with NEMA RN 1.
  - 2. Coating Thickness: 0.040 inch (1 mm), minimum.
- G. EMT: Comply with ANSI C80.3 and UL 797.
  - 1. Factory applied color coded organic polymer coating.
- H. FMC: Comply with UL 1; zinc-coated steel.
- I. LFMC: Flexible steel conduit with PVC jacket and complying with UL 360.
- J. Fittings for Metal Conduit: Comply with NEMA FB 1 and UL 514B.
  - 1. Fittings for EMT:
    - a. Material: Steel.
    - b. Type: Setscrew or compression.
  - 2. Expansion Fittings: PVC or steel to match conduit type, complying with UL 651, rated for environmental conditions where installed, and including flexible external bonding jumper.
  - 3. Coating for Fittings for PVC-Coated Conduit: Minimum thickness of 0.040 inch (1 mm), with overlapping sleeves protecting threaded joints. Minimum 4" in length
- K. Joint Compound for IMC, GRC, or ARC: Approved, as defined in NFPA 70, by authorities having jurisdiction for use in conduit assemblies, and compounded for use to lubricate and protect threaded conduit joints from corrosion and to enhance their conductivity.

## 2.2 NONMETALLIC CONDUITS, TUBING, AND FITTINGS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. AFC Cable Systems, Inc.
  - 2. Anamet Electrical, Inc.
  - 3. Arnco Corporation.
  - 4. CANTEX Inc.
  - 5. CertainTeed Corp.
  - 6. Condux International, Inc.
  - 7. Electri-Flex Company.
  - 8. Kraloy.
  - 9. Lamson & Sessions; Carlon Electrical Products.
  - 10. Niedax-Kleinhuis USA, Inc.

11. RACO; a Hubbell company.
  12. Thomas & Betts Corporation.
- B. Listing and Labeling: Nonmetallic conduits, tubing, and fittings shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. ENT: Comply with NEMA TC 13 and UL 1653.
- D. RNC: Type EPC-40-PVC, complying with NEMA TC 2 and UL 651 unless otherwise indicated.
- E. LFNC: Comply with UL 1660.
- F. Rigid HDPE: Comply with UL 651A.
- G. Continuous HDPE: Comply with UL 651B.
- H. Coilable HDPE: Preassembled with conductors or cables, and complying with ASTM D 3485.
- I. RTRC: Comply with UL 1684A and NEMA TC 14.
- J. Fittings for ENT and RNC: Comply with NEMA TC 3; match to conduit or tubing type and material.
- K. Fittings for LFNC: Comply with UL 514B.
- L. Solvent cements and adhesive primers shall have a VOC content of 510 and 550 g/L or less, respectively, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- M. Solvent cements and adhesive primers shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.3 METAL WIREWAYS AND AUXILIARY GUTTERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
1. Cooper B-Line, Inc.
  2. Hoffman; a Pentair company.
  3. Mono-Systems, Inc.
  4. Square D; a brand of Schneider Electric.
- B. Description: Sheet metal, complying with UL 870 and NEMA 250, Type 1 unless otherwise indicated, and sized according to NFPA 70.
1. Metal wireways installed outdoors shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

- C. Fittings and Accessories: Include covers, couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings to match and mate with wireways as required for complete system.
- D. Wireway Covers: Screw-cover type unless otherwise indicated.
- E. Finish: Manufacturer's standard enamel finish.

## 2.4 NONMETALLIC WIREWAYS AND AUXILIARY GUTTERS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - 1. Allied Moulded Products, Inc.
  - 2. Hoffman; a Pentair company.
  - 3. Lamson & Sessions; Carlon Electrical Products.
  - 4. Niedax-Kleinhuis USA, Inc.
- B. Listing and Labeling: Nonmetallic wireways and auxiliary gutters shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. Description: Fiberglass polyester, extruded and fabricated to required size and shape, without holes or knockouts. Cover shall be gasketed with oil-resistant gasket material and fastened with captive screws treated for corrosion resistance. Connections shall be flanged and have stainless-steel screws and oil-resistant gaskets.
- D. Description: PVC, extruded and fabricated to required size and shape, and having snap-on cover, mechanically coupled connections, and plastic fasteners.
- E. Fittings and Accessories: Couplings, offsets, elbows, expansion joints, adapters, hold-down straps, end caps, and other fittings shall match and mate with wireways as required for complete system.
- F. Solvent cements and adhesive primers shall have a VOC content of 510 and 550 g/L or less, respectively, when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
- G. Solvent cements and adhesive primers shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

## 2.5 SURFACE RACEWAYS

- A. Listing and Labeling: Surface raceways and tele-power poles shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Surface Metal Raceways: Extruded Aluminum with snap-on covers complying with UL 5.



University of Utah

Salt Lake City, Utah 84104

1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  - a. Mono-Systems, Inc.
  - b. Panduit Corp.
  - c. Wiremold / Legrand.

## 2.6 BOXES, ENCLOSURES, AND CABINETS

- A. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  1. Adalet.
  2. Cooper Technologies Company; Cooper Crouse-Hinds.
  3. EGS/Appleton Electric.
  4. Erickson Electrical Equipment Company.
  5. FSR Inc.
  6. Hoffman; a Pentair company.
  7. Hubbell Incorporated; Killark Division.
  8. Kraloy.
  9. Milbank Manufacturing Co.
  10. Mono-Systems, Inc.
  11. O-Z/Gedney; a brand of EGS Electrical Group.
  12. RACO; a Hubbell Company.
  13. Robroy Industries.
  14. Spring City Electrical Manufacturing Company.
  15. Stahlin Non-Metallic Enclosures; a division of Robroy Industries.
  16. Thomas & Betts Corporation.
  17. Wiremold / Legrand.
- B. General Requirements for Boxes, Enclosures, and Cabinets: Boxes, enclosures, and cabinets installed in wet locations shall be listed for use in wet locations.
- C. Sheet Metal Outlet and Device Boxes: Comply with NEMA OS 1 and UL 514A.
- D. Cast-Metal Outlet and Device Boxes: Comply with NEMA FB 1, aluminum, Type FD, with gasketed cover.
- E. Nonmetallic Outlet and Device Boxes: Comply with NEMA OS 2 and UL 514C.
- F. Metal Floor Boxes:
  1. Material: Cast metal or sheet metal.
  2. Type: Fully adjustable.
  3. Shape: Rectangular.
  4. Listing and Labeling: Metal floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- G. Nonmetallic Floor Boxes: Nonadjustable, rectangular.

1. Listing and Labeling: Nonmetallic floor boxes shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- H. Luminaire Outlet Boxes: Nonadjustable, designed for attachment of luminaire weighing 50 lb (23 kg). Outlet boxes designed for attachment of luminaires weighing more than 50 lb (23 kg) shall be listed and marked for the maximum allowable weight.
- I. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.
- J. Cast-Metal Access, Pull, and Junction Boxes: Comply with NEMA FB 1 and UL 1773, cast aluminum with gasketed cover.
- K. Box extensions used to accommodate new building finishes shall be of same material as recessed box.
- L. Device Box Dimensions: 4 inches square by 2-1/8 inches deep (100 mm square by 60 mm deep).
- M. Gangable boxes are prohibited.
- N. Hinged-Cover Enclosures: Comply with UL 50 and NEMA 250, Type 1 with continuous-hinge cover with flush latch unless otherwise indicated.
  1. Metal Enclosures: Steel, finished inside and out with manufacturer's standard enamel.
  2. Interior Panels: Steel; all sides finished with manufacturer's standard enamel.
- O. Cabinets:
  1. NEMA 250, Type 1 galvanized-steel box with removable interior panel and removable front, finished inside and out with manufacturer's standard enamel.
  2. Hinged door in front cover with flush latch and concealed hinge.
  3. Key latch to match panelboards.
  4. Metal barriers to separate wiring of different systems and voltage.
  5. Accessory feet where required for freestanding equipment.
  6. Nonmetallic cabinets shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

## 2.7 HANDHOLES AND BOXES FOR EXTERIOR UNDERGROUND WIRING

- A. General Requirements for Handholes and Boxes:
  1. Boxes and handholes for use in underground systems shall be designed and identified as defined in NFPA 70, for intended location and application.
  2. Boxes installed in wet areas shall be listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Polymer-Concrete Handholes and Boxes with Polymer-Concrete Cover: Molded of sand and aggregate, bound together with polymer resin, and reinforced with steel, fiberglass, or a combination of the two.
  1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:

University of Utah

Salt Lake City, Utah 84104

- a. Armorcast Products Company.
    - b. Carson Industries LLC.
    - c. CDR Systems Corporation; Hubbell Power Systems.
    - d. NewBasis.
    - e. Oldcastle Precast, Inc.; Christy Concrete Products.
    - f. Synertech Moulded Products; a division of Oldcastle Precast, Inc.
  2. Standard: Comply with SCTE 77.
  3. Configuration: Designed for flush burial with open bottom unless otherwise indicated.
  4. Cover: Weatherproof, secured by tamper-resistant locking devices and having structural load rating consistent with enclosure and handhole location.
  5. Cover Finish: Nonskid finish shall have a minimum coefficient of friction of 0.50.
  6. Cover Legend: Molded lettering, "ELECTRIC."
  7. Conduit Entrance Provisions: Conduit-terminating fittings shall mate with entering ducts for secure, fixed installation in enclosure wall.
  8. Handholes 12 Inches Wide by 24 Inches Long (300 mm Wide by 600 mm Long) and Larger: Have inserts for cable racks and pulling-in irons installed before concrete is poured.
- C. Fiberglass Handholes and Boxes: Molded of fiberglass-reinforced polyester resin, with frame and covers of fiberglass.
1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following: Retain "Basis-of-Design Product" Subparagraph and list of manufacturers below to identify a specific product or a comparable product from manufacturers listed. Retain option and delete insert note if manufacturer's name and model number are indicated on Drawings.
    - a. Armorcast Products Company.
    - b. Carson Industries LLC.
    - c. CDR Systems Corporation; Hubbell Power Systems.
    - d. NewBasis.
    - e. Nordic Fiberglass, Inc.
    - f. Oldcastle Precast, Inc.; Christy Concrete Products.
    - g. Synertech Moulded Products; a division of Oldcastle Precast, Inc.
  2. Standard: Comply with SCTE 77.
  3. Color of Frame and Cover: Gray.
  4. Configuration: Designed for flush burial with open bottom unless otherwise indicated.
  5. Cover: Weatherproof, secured by tamper-resistant locking devices and having structural load rating consistent with enclosure and handhole location.
  6. Cover Finish: Nonskid finish shall have a minimum coefficient of friction of 0.50.
  7. Cover Legend: Molded lettering, "ELECTRIC."
  8. Conduit Entrance Provisions: Conduit-terminating fittings shall mate with entering ducts for secure, fixed installation in enclosure wall.
  9. Handholes 12 Inches Wide by 24 Inches Long (300 mm Wide by 600 mm Long) and Larger: Have inserts for cable racks and pulling-in irons installed before concrete is poured.

## 2.8 SOURCE QUALITY CONTROL FOR UNDERGROUND ENCLOSURES

- A. Handhole and Pull-Box Prototype Test: Test prototypes of handholes and boxes for compliance with SCTE 77. Strength tests shall be for specified tier ratings of products supplied.
  - 1. Tests of materials shall be performed by an independent testing agency.
  - 2. Strength tests of complete boxes and covers shall be by either an independent testing agency or manufacturer. A qualified registered professional engineer shall certify tests by manufacturer.
  - 3. Testing machine pressure gages shall have current calibration certification complying with ISO 9000 and ISO 10012 and traceable to NIST standards.

## PART 3 - EXECUTION

### 3.1 RACEWAY APPLICATION

- A. Outdoors: Apply raceway products as specified below unless otherwise indicated:
  - 1. Exposed Conduit: GRC or IMC.
  - 2. Concealed Conduit, Aboveground: GRC or IMC.
  - 3. Underground Conduit: RNC, Type EPC-40-PVC. Conduits for feeders and services concrete encased. Branch circuits direct buried.
  - 4. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): LFMC.
  - 5. Boxes and Enclosures, Aboveground: NEMA 250, Type 3R.
- B. Indoors: Apply raceway products as specified below unless otherwise indicated:
  - 1. Exposed, Not Subject to Physical Damage: EMT.
  - 2. Exposed, Not Subject to Severe Physical Damage: EMT.
  - 3. Exposed and Subject to Severe Physical Damage: GRC or IMC. Raceway locations include the following:
    - a. Loading dock.
    - b. Corridors used for traffic of mechanized carts, forklifts, and pallet-handling units.
    - c. Mechanical rooms.
  - 4. Concealed in Ceilings and Interior Walls and Partitions: EMT.
  - 5. Connection to Vibrating Equipment (Including Transformers and Hydraulic, Pneumatic, Electric Solenoid, or Motor-Driven Equipment): FMC, except use LFMC in damp or wet locations.
  - 6. Damp or Wet Locations: GRC or IMC.
  - 7. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4 stainless steel in damp or wet locations.
- C. Minimum Raceway Size: 3/4-inch (21-mm) trade size for circuit homeruns. 1/2" is acceptable for fire alarm cabling and for all raceway with a single branch circuit size #10 or smaller.
- D. Minimum Raceway Size for Structural Cabling: 1-inch
- E. Minimum Raceway Size for A/V cabling 1.25-inch
- F. Raceway Fittings: Compatible with raceways and suitable for use and location.

1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings unless otherwise indicated. Comply with NEMA FB 2.10.
2. PVC Externally Coated, Rigid Steel Conduits: Use only fittings listed for use with this type of conduit. Patch and seal all joints, nicks, and scrapes in PVC coating after installing conduits and fittings. Use sealant recommended by fitting manufacturer and apply in thickness and number of coats recommended by manufacturer.
3. EMT: Use setscrew or compression, steel fittings. Comply with NEMA FB 2.10.
4. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.

G. Install surface raceways only where indicated on Drawings.

### 3.2 INSTALLATION

- A. Comply with NECA 1 and NECA 101 for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum conduits. Comply with NFPA 70 limitations for types of raceways allowed in specific occupancies and number of floors.
- B. Keep raceways at least 6 inches (150 mm) away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.
- C. Complete raceway installation before starting conductor installation.
- D. Comply with requirements in Section 260529 "Hangers and Supports for Electrical Systems" for hangers and supports.
- E. Arrange stub-ups so curved portions of bends are not visible above finished slab.
- F. Install no more than the equivalent of three 90-degree bends in any conduit run except for control wiring conduits, for which fewer bends are allowed. Support within 12 inches (300 mm) of changes in direction.
- G. Conceal conduit and EMT within finished walls, ceilings, and floors unless otherwise indicated. Install conduits parallel or perpendicular to building lines.
- H. Support conduit within 12 inches (300 mm) of enclosures to which attached.
- I. Do not install raceways embedded in slabs.
- J. Stub-ups to Above Recessed Ceilings:
  1. Use EMT, IMC, or RMC for raceways.
  2. Use a conduit bushing or insulated fitting to terminate stub-ups not terminated in hubs or in an enclosure.
- K. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.

- L. Coat field-cut threads on PVC-coated raceway with a corrosion-preventing conductive compound prior to assembly.
- M. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors including conductors smaller than No. 4 AWG.
- N. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to 1-1/4-inch (35mm) trade size and insulated throat metal bushings on 1-1/2-inch (41-mm) trade size and larger conduits terminated with locknuts. Install insulated throat metal grounding bushings on service conduits.
- O. Install raceways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.
- P. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to assure a continuous ground path.
- Q. Cut conduit perpendicular to the length. For conduits 2-inch (53-mm) trade size and larger, use roll cutter or a guide to make cut straight and perpendicular to the length.
- R. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb (90-kg) tensile strength. Leave at least 12 inches (300 mm) of slack at each end of pull wire. Cap underground raceways designated as spare above grade alongside raceways in use.
- S. Surface Raceways:
  - 1. Install surface raceway with a minimum 2-inch (50-mm) radius control at bend points.
  - 2. Secure surface raceway with screws or other anchor-type devices at intervals not exceeding 48 inches (1200 mm) and with no less than two supports per straight raceway section. Support surface raceway according to manufacturer's written instructions. Tape and glue are not acceptable support methods.
- T. Install raceway sealing fittings at accessible locations according to NFPA 70 and fill them with listed sealing compound. For concealed raceways, install each fitting in a flush steel box with a blank cover plate having a finish similar to that of adjacent plates or surfaces. Install raceway sealing fittings according to NFPA 70.
- U. Install devices to seal raceway interiors at accessible locations. Locate seals so no fittings or boxes are between the seal and the following changes of environments. Seal the interior of all raceways at the following points:
  - 1. Where conduits pass from warm to cold locations, such as boundaries of refrigerated spaces.
  - 2. Where an underground service raceway enters a building or structure.
  - 3. Where otherwise required by NFPA 70.
- V. Comply with manufacturer's written instructions for solvent welding RNC and fittings.
- W. Expansion-Joint Fittings:

1. Install in each run of aboveground RNC that is located where environmental temperature change may exceed 30 deg F (17 deg C) and that has straight-run length that exceeds 25 feet (7.6 m). Install in each run of aboveground RMC and EMT conduit that is located where environmental temperature change may exceed 100 deg F (55 deg C) and that has straight-run length that exceeds 100 feet (30 m).
  2. Install type and quantity of fittings that accommodate temperature change listed for each of the following locations:
    - a. Outdoor Locations Not Exposed to Direct Sunlight: 125 deg F (70 deg C) temperature change.
    - b. Outdoor Locations Exposed to Direct Sunlight: 155 deg F (86 deg C) temperature change.
    - c. Indoor Spaces Connected with Outdoors without Physical Separation: 125 deg F (70 deg C) temperature change.
  3. Install expansion fittings at all locations where conduits cross building or structure expansion joints.
  4. Install each expansion-joint fitting with position, mounting, and piston setting selected according to manufacturer's written instructions for conditions at specific location at time of installation. Install conduit supports to allow for expansion movement.
- X. Flexible Conduit Connections: Comply with NEMA RV 3. Use a maximum of 72 inches (1830 mm) of flexible conduit for recessed and semirecessed luminaires, equipment subject to vibration, noise transmission, or movement (including raceways that cross seismic joints); and for transformers and motors.
1. Use LFMC in damp or wet locations subject to severe physical damage.
  2. Use LFMC or LFNC in damp or wet locations not subject to severe physical damage.
- Y. Mount boxes at heights indicated on Drawings. If mounting heights of boxes are not individually indicated, give priority to ADA requirements. Install boxes with height measured to bottom of box unless otherwise indicated.
- Z. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall. Prepare block surfaces to provide a flat surface for a raintight connection between box and cover plate or supported equipment and box.
- AA. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.
- BB. Locate boxes so that cover or plate will not span different building finishes.
- CC. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.
- DD. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.
- EE. Set metal floor boxes level and flush with finished floor surface.

- FF. Set nonmetallic floor boxes level. Trim after installation to fit flush with finished floor surface.

### 3.3 INSTALLATION OF UNDERGROUND CONDUIT

#### A. Direct-Buried Conduit:

1. Excavate trench bottom to provide firm and uniform support for conduit. Prepare trench bottom as specified in Section 312000 "Earth Moving" for pipe less than 6 inches (150 mm) in nominal diameter.
2. Install backfill as specified in Section 312000 "Earth Moving."
3. After installing conduit, backfill and compact. Start at tie-in point, and work toward end of conduit run, leaving conduit at end of run free to move with expansion and contraction as temperature changes during this process. Firmly hand tamp backfill around conduit to provide maximum supporting strength. After placing controlled backfill to within 12 inches (300 mm) of finished grade, make final conduit connection at end of run and complete backfilling with normal compaction as specified in Section 312000 "Earth Moving."
4. Install manufactured duct elbows for stub-ups at poles and equipment and at building entrances through floor unless otherwise indicated. Encase elbows for stub-up ducts throughout length of elbow.
5. Install manufactured rigid steel conduit elbows for stub-ups at poles and equipment and at building entrances through floor.
  - a. Couple steel conduits to ducts with adapters designed for this purpose, and encase coupling with 3 inches (75 mm) of concrete for a minimum of 12 inches (300 mm) on each side of the coupling.
  - b. For stub-ups at equipment mounted on outdoor concrete bases and where conduits penetrate building foundations, extend steel conduit horizontally a minimum of 60 inches (1500 mm) from edge of foundation or equipment base. Install insulated grounding bushings on terminations at equipment.
6. Warning Planks: Bury warning planks approximately 12 inches (300 mm) above direct-buried conduits but a minimum of 6 inches (150 mm) below grade. Align planks along centerline of conduit.
7. Underground Warning Tape: Comply with requirements in Section 260553 "Identification for Electrical Systems."

### 3.4 INSTALLATION OF UNDERGROUND HANDHOLES AND BOXES

- A. Install handholes and boxes level and plumb and with orientation and depth coordinated with connecting conduits to minimize bends and deflections required for proper entrances.
- B. Unless otherwise indicated, support units on a level bed of crushed stone or gravel, graded from 1/2-inch (12.5-mm) sieve to No. 4 (4.75-mm) sieve and compacted to same density as adjacent undisturbed earth.
- C. Elevation: In paved areas, set so cover surface will be flush with finished grade. Set covers of other enclosures 1 inch (25 mm) above finished grade.
- D. Install handholes with bottom below frost line, below grade.



- E. Install removable hardware, including pulling eyes, cable stanchions, cable arms, and insulators, as required for installation and support of cables and conductors and as indicated. Select arm lengths to be long enough to provide spare space for future cables but short enough to preserve adequate working clearances in enclosure.
- F. Field-cut openings for conduits according to enclosure manufacturer's written instructions. Cut wall of enclosure with a tool designed for material to be cut. Size holes for terminating fittings to be used, and seal around penetrations after fittings are installed.

### 3.5 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

- A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 260544 "Sleeves and Sleeve Seals for Electrical Raceways and Cabling."

### 3.6 FIRESTOPPING

- A. Install firestopping at penetrations of fire-rated floor and wall assemblies. Comply with requirements in Section 078413 "Penetration Firestopping."

### 3.7 PROTECTION

- A. Protect coatings, finishes, and cabinets from damage and deterioration.
  - 1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.
  - 2. Repair damage to PVC coatings or paint finishes with matching touchup coating recommended by manufacturer.

## **END OF SECTION 260533**

## SECTION 260537 - CABLE HOOK SUPPORT SYSTEMS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes steel cable hook (J-Hook) support systems and accessories.
- B. The work covered under this section consists of the furnishing of all necessary labor, supervision, materials, equipment, and services to completely execute the cable hook system as described in this specification.
- C. Related Sections include the following:
  - 1. Division 7 Section "Through-Penetration Firestop Systems" for firestopping materials and installation at penetrations through walls, ceilings, and other fire-rated elements.
  - 2. Division 16 Section "Basic Electrical Materials and Methods" for supports not specified in this Section.
  - 3. Division 16 Section "Seismic Controls for Electrical Work" for mounting and anchoring wire basket support systems.

#### 1.3 SUBMITTALS

- A. Submit product data on cable hook devices, including attachment methods. Product data to include, but not limited to materials, finishes, approvals, load ratings, and dimensional information.

#### 1.4 QUALITY ASSURANCE

- A. Cable hooks shall be listed and labeled by Underwriters Laboratories (UL) and by UL to Canadian standards (cUL) as required.
- B. Cable hooks shall have the manufacturers name and part number stamped in the part itself for identification.

#### 1.5 COORDINATION

- A. Coordinate layout and installation of cable hook support systems and suspension system with other construction elements. Coordinate items that penetrate ceilings or are supported by them, including light fixtures, HVAC equipment, fire-suppression system, and partition assemblies.
- B. The drawings indicate the general route of the cable hook support systems. Data presented on these drawings is as accurate as preliminary surveys and planning can determine until final equipment selection is made. Accuracy is not guaranteed and field verification of all dimensions, routing, etc., is required.
- C. Specifications and drawings are for assistance and guidance, but exact routing, locations, distances and levels will be governed by actual field conditions. Contractor is directed to make field surveys as part of his work prior to submitting system layout drawings.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. B-Line Systems, Inc..
  - 2. GS Metals Corp.
  - 3. MPHusky.
  - 4. P-W Industries, Inc.
  - 5. Thomas & Betts Corporation.

### 2.2 CABLE HOOK SYSTEMS

- A. Cable hooks shall have a flat bottom and provide a minimum of 1-5/8 inch cable bearing surface.
- B. Cable hooks shall have 90-degree radiused edges to prevent damage while installing cables.
- C. Cable hooks shall be designed so the mounting hardware is recessed to prevent cable damage.
- D. Cable hooks shall have a stainless steel cable latch retainer to provide containment of cables within the hook. The retainer shall be removable and reusable.
- E. Cable hooks shall be factory assembled for direct attachment to walls, hanger rods, beam flanges, purlins, strut, floor posts, etc. to meet job conditions.
- F. Factory assembled multi-tiered cable hooks shall be used where required to provide separate cabling compartments, or where additional capacity is needed.
- G. Cable hooks shall be Single sided, 3-tiered. Minimum hook size shall be 2".

### 2.3 FINISHES

- A. Cable hooks for non-corrosive areas shall be pre-galvanized steel, ASTM A653. Where additional strength is required, cable hooks shall be spring steel with a zinc-plated finish, ASTM B633, SC3.
- B. Cable hooks for corrosive areas shall be stainless steel, AISI Type 304.

### 2.4 CABLE HOOK CAPACITY AND LOAD RATING

- A. Cable hooks shall be capable of supporting a minimum of 30 pounds with a safety factor of 3.
- B. Spring steel cable hooks shall be capable of supporting a minimum of 100 pounds with a safety factor of 3 where extra strength is required.
- C. Follow manufacturer's recommendations for allowable fill capacity for each size of cable hook.

### 2.5 FIRESTOPPING

- A. Materials: UL listed and labeled and FM approved for fire ratings consistent with penetrated barriers.
- B. Sleeves: Schedule 40, welded black steel pipe sleeves. Sizes as indicated or inside pipe area to match cross-sectional area of wire basket support system.

## 2.6 SOURCE QUALITY CONTROL

- A. Perform design and production tests according to NEMA VE 1.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine substrates, areas, and conditions for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 CABLE HOOK SUPPORT SYSTEM INSTALLATION

- A. Installation and configuration shall conform to the requirements of the ANSI/ EIA/TIA Standards 568A & 569, NFPA 70 (National Electrical Code), and applicable local codes.
- B. Install three-tier, 4 inch diameter, cable hooks fastened to walls above accessible ceilings on both walls in every corridor and hallway at maximum 4'-0" center to center.
- C. Install 2-inch diameter cable hooks at 4'-0" center to center on all walls in all rooms that have cabled electronic systems such as voice/data, medical LAN, Nurse Call, CCTV, Access Control, Intercoms, Building Management, or Intrusion Detection
- D. Cable hooks are to be utilized for installation of cables for all low voltage systems. These systems include, but are not limited to, Backbone and Horizontal Communications Wiring, Nurse Call, CCTV, Access Control, Intercoms, Building Management, Intrusion Detection and Lighting Control. It is not intended to imply that the supports indicated herein will provide all necessary support. Additional hooks will be required and must be installed to provide support as required by other specification sections.
- E. Install additional hooks as required by other specification sections and to support all cables at not more than 4'-0" intervals.
- F. Locate cable hook support system above piping unless accessibility to cable hook support system is restricted less than minimum specified.
- G. Fasten cables hooks to walls at stud locations or provide suitable backing.
- H. In areas without walls support cable hooks with 1/4" allthread rod that is anchored to the structure. Provide a ceiling wire between the bottom of the hook and the ceiling grid to hold the hook in position.
- I. Seal penetrations through fire and smoke barriers according to Division 7 Section "Through-Penetration Firestop Systems."

- J. Sleeves for Future Cables: Install capped sleeves for future cables through firestop-sealed penetrations of fire and smoke barriers. Refer to Section 260509 for sleeve construction requirements. As a minimum, for each J-Hook, install one sleeve that is equal in size to the J-Hook in each corridor wall of the Communications Rooms and through walls that form a barrier above the ceiling in corridors.
- K. Workspace: Install cable hook support systems with sufficient space (minimum 6") to permit access for installing cables.

END OF SECTION 260537

## **SECTION 260544 - SLEEVES AND SLEEVE SEALS FOR ELECTRICAL RACEWAYS AND CABLING**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Sleeves for raceway and cable penetration of non-fire-rated construction walls and floors.
  - 2. Sleeve-seal systems.
  - 3. Grout.
  - 4. Silicone sealants.
- B. Related Requirements:
  - 1. Section 078413 "Penetration Firestopping" for penetration firestopping installed in fire-resistance-rated walls, horizontal assemblies, and smoke barriers, with and without penetrating items.

#### **1.3 ACTION SUBMITTALS**

- A. Product Data: For each type of product.
- B. LEED Submittals:
  - 1. Product Data for Credit EQ 4.1: For sealants, documentation including printed statement of VOC content.
  - 2. Laboratory Test Reports for Credit EQ 4: For sealants, documentation indicating that products comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."

### **PART 2 - PRODUCTS**

#### **2.1 SLEEVES**

- A. Wall Sleeves:
  - 1. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, zinc coated, plain ends.
  - 2. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop unless otherwise indicated.
- B. Sleeves for Conduits Penetrating Non-Fire-Rated Gypsum Board Assemblies: Galvanized-steel sheet; 0.0239-inch (0.6-mm) minimum thickness; round tube closed with welded longitudinal joint, with tabs for screw-fastening the sleeve to the board.
- C. PVC-Pipe Sleeves: ASTM D 1785, Schedule 40.
- D. Molded-PVC Sleeves: With nailing flange for attaching to wooden forms.
- E. Molded-PE or -PP Sleeves: Removable, tapered-cup shaped, and smooth outer surface with nailing flange for attaching to wooden forms.
- F. Sleeves for Rectangular Openings:
  - 1. Material: Galvanized sheet steel.
  - 2. Minimum Metal Thickness:
    - a. For sleeve cross-section rectangle perimeter less than 50 inches (1270 mm) and with no side larger than 16 inches (400 mm), thickness shall be 0.052 inch (1.3 mm).

- b. For sleeve cross-section rectangle perimeter 50 inches (1270 mm) or more and one or more sides larger than 16 inches (400 mm), thickness shall be 0.138 inch (3.5 mm).

## 2.2 SLEEVE-SEAL SYSTEMS

- A. Description: Modular sealing device, designed for field assembly, to fill annular space between sleeve and raceway or cable.
  - 1. Manufacturers: Subject to compliance with requirements, available manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
    - a. Advance Products & Systems, Inc.
    - b. CALPICO, Inc.
    - c. Metraflex Company (The).
    - d. Pipeline Seal and Insulator, Inc.
    - e. Proco Products, Inc.
  - 2. Sealing Elements: EPDM rubber interlocking links shaped to fit surface of pipe. Include type and number required for pipe material and size of pipe.
  - 3. Pressure Plates: Composite.
  - 4. Connecting Bolts and Nuts: Stainless steel of length required to secure pressure plates to sealing elements.

## 2.3 GROUT

- A. Description: Nonshrink; recommended for interior and exterior sealing openings in non-fire-rated walls or floors.
- B. Standard: ASTM C 1107/C 1107M, Grade B, post-hardening and volume-adjusting, dry, hydraulic-cement grout.
- C. Design Mix: 5000-psi (34.5-MPa), 28-day compressive strength.
- D. Packaging: Premixed and factory packaged.

## 2.4 SILICONE SEALANTS

- A. Silicone Sealants: Single-component, silicone-based, neutral-curing elastomeric sealants of grade indicated below.
  - 1. Grade: Pourable (self-leveling) formulation for openings in floors and other horizontal surfaces that are not fire rated.
  - 2. Sealant shall have VOC content of 420 g/L or less when calculated according to 40 CFR 59, Subpart D (EPA Method 24).
  - 3. Sealant shall comply with the testing and product requirements of the California Department of Health Services' "Standard Practice for the Testing of Volatile Organic Emissions from Various Sources Using Small-Scale Environmental Chambers."
- B. Silicone Foams: Multicomponent, silicone-based liquid elastomers that, when mixed, expand and cure in place to produce a flexible, nonshrinking foam.

## PART 3 - EXECUTION

### 3.1 SLEEVE INSTALLATION FOR NON-FIRE-RATED ELECTRICAL PENETRATIONS

- A. Comply with NECA 1.
- B. Comply with NEMA VE 2 for cable tray and cable penetrations.
- C. Sleeves for Conduits Penetrating Above-Grade Non-Fire-Rated Concrete and Masonry-Unit Floors and Walls:
  - 1. Interior Penetrations of Non-Fire-Rated Walls and Floors:

- a. Seal annular space between sleeve and raceway or cable, using joint sealant appropriate for size, depth, and location of joint. Comply with requirements in Section 079200 "Joint Sealants."
      - b. Seal space outside of sleeves with mortar or grout. Pack sealing material solidly between sleeve and wall so no voids remain. Tool exposed surfaces smooth; protect material while curing.
    2. Use pipe sleeves unless penetration arrangement requires rectangular sleeved opening.
    3. Size pipe sleeves to provide 1/4-inch (6.4-mm) annular clear space between sleeve and raceway or cable unless sleeve seal is to be installed or unless seismic criteria require different clearance.
    4. Install sleeves for wall penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of walls. Cut sleeves to length for mounting flush with both surfaces of walls. Deburr after cutting.
    5. Install sleeves for floor penetrations. Extend sleeves installed in floors 2 inches (50 mm) above finished floor level. Install sleeves during erection of floors.
  - D. Sleeves for Conduits Penetrating Non-Fire-Rated Gypsum Board Assemblies:
    1. Use circular metal sleeves unless penetration arrangement requires rectangular sleeved opening.
    2. Seal space outside of sleeves with approved joint compound for gypsum board assemblies.
  - E. Roof-Penetration Sleeves: Seal penetration of individual raceways and cables with flexible boot-type flashing units applied in coordination with roofing work.
  - F. Aboveground, Exterior-Wall Penetrations: Seal penetrations using [steel] [cast-iron] pipe sleeves and mechanical sleeve seals. Select sleeve size to allow for 1-inch (25-mm) annular clear space between pipe and sleeve for installing mechanical sleeve seals.
  - G. Underground, Exterior-Wall and Floor Penetrations: Install cast-iron pipe sleeves. Size sleeves to allow for 1-inch (25-mm) annular clear space between raceway or cable and sleeve for installing sleeve-seal system.
- 3.2 SLEEVE-SEAL-SYSTEM INSTALLATION
- A. Install sleeve-seal systems in sleeves in exterior concrete walls and slabs-on-grade at raceway entries into building.
  - B. Install type and number of sealing elements recommended by manufacturer for raceway or cable material and size. Position raceway or cable in center of sleeve. Assemble mechanical sleeve seals and install in annular space between raceway or cable and sleeve. Tighten bolts against pressure plates that cause sealing elements to expand and make watertight seal.
- 3.3 SLEEVE-SEAL-FITTING INSTALLATION
- A. Install sleeve-seal fittings in new walls and slabs as they are constructed.
  - B. Assemble fitting components of length to be flush with both surfaces of concrete slabs and walls. Position waterstop flange to be centered in concrete slab or wall.
  - C. Secure nailing flanges to concrete forms.
  - D. Using grout, seal the space around outside of sleeve-seal fittings.

**END OF SECTION 260544**



## **SECTION 260548 - VIBRATION AND SEISMIC CONTROLS FOR ELECTRICAL SYSTEMS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. This Section includes the following:
  - 1. Isolation pads.
  - 2. Spring isolators.
  - 3. Restrained spring isolators.
  - 4. Channel support systems.
  - 5. Restraint cables.
  - 6. Hanger rod stiffeners.
  - 7. Anchorage bushings and washers.
- B. Related Sections include the following:
  - 1. Section 260529 "Hangers and Supports for Electrical Systems" for commonly used electrical supports and installation requirements.

#### **1.3 DEFINITIONS**

- A. The IBC: International Building Code.
- B. ICC-ES: ICC-Evaluation Service.
- C. OSHPD: Office of Statewide Health Planning and Development for the State of California.

#### **1.4 PERFORMANCE REQUIREMENTS**

- A. Seismic-Restraint Loading: Refer to structural specifications.

#### **1.5 ACTION SUBMITTALS**

- A. Product Data: For the following:
  - 1. Include rated load, rated deflection, and overload capacity for each vibration isolation device.
  - 2. Illustrate and indicate style, material, strength, fastening provision, and finish for each type and size of seismic-restraint component used.
    - a. Tabulate types and sizes of seismic restraints, complete with report numbers and rated strength in tension and shear as evaluated by an evaluation service member of ICC-ES.
    - b. Annotate to indicate application of each product submitted and compliance with requirements.
  - 3. Restrained-Isolation Devices: Include ratings for horizontal, vertical, and combined loads.
- B. Delegated-Design Submittal: For seismic-restraint details indicated to comply with performance requirements and design criteria, including analysis data signed and sealed by the qualified professional engineer responsible for their preparation.
  - 1. Design Calculations: Calculate static and dynamic loading due to equipment weight and operation, seismic forces required to select vibration isolators and seismic restraints.
    - a. Coordinate design calculations with wind-load calculations required for equipment mounted outdoors. Comply with requirements in other electrical Sections for equipment mounted outdoors.
  - 2. Indicate materials and dimensions and identify hardware, including attachment and anchorage devices.

University of Utah

Salt Lake City, Utah 84104

3. Field-fabricated supports.
4. Seismic-Restraint Details:
  - a. Design Analysis: To support selection and arrangement of seismic restraints. Include calculations of combined tensile and shear loads.
  - b. Details: Indicate fabrication and arrangement. Detail attachments of restraints to the restrained items and to the structure. Show attachment locations, methods, and spacings. Identify components, list their strengths, and indicate directions and values of forces transmitted to the structure during seismic events.
  - c. Preapproval and Evaluation Documentation: By an evaluation service member of ICC-ES, showing maximum ratings of restraint items and the basis for approval (tests or calculations).

## 1.6 INFORMATIONAL SUBMITTALS

- A. Coordination Drawings: Show coordination of seismic bracing for electrical components with other systems and equipment in the vicinity, including other supports and seismic restraints.
- B. Qualification Data: For professional engineer.
- C. Welding certificates.
- D. Field quality-control test reports.

## 1.7 QUALITY ASSURANCE

- A. Testing Agency Qualifications: An independent agency, with the experience and capability to conduct the testing indicated, that is a nationally recognized testing laboratory (NRTL) as defined by OSHA in 29 CFR 1910.7, and that is acceptable to authorities having jurisdiction.
- B. Comply with seismic-restraint requirements in the IBC unless requirements in this Section are more stringent.
- C. Welding: Qualify procedures and personnel according to AWS D1.1/D1.1M, "Structural Welding Code - Steel."
- D. Comply with NFPA 70.

## PART 2 - PRODUCTS

### 2.1 VIBRATION ISOLATORS

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  1. Ace Mountings Co., Inc.
  2. Amber/Booth Company, Inc.
  3. California Dynamics Corporation.
  4. Isolation Technology, Inc.
  5. Kinetics Noise Control.
  6. Mason Industries.
  7. Vibration Eliminator Co., Inc.
  8. Vibration Isolation.
  9. Vibration Mountings & Controls, Inc.
- B. Spring Isolators: Freestanding, laterally stable, open-spring isolators.
  1. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
  2. Minimum Additional Travel: 50 percent of the required deflection at rated load.
  3. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
  4. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.
  5. Baseplates: Factory drilled for bolting to structure and bonded to 1/4-inch- (6-mm-) thick, rubber isolator pad attached to baseplate underside. Baseplates shall limit floor load to 500 psig (3447 kPa).

University of Utah

Salt Lake City, Utah 84104

6. Top Plate and Adjustment Bolt: Threaded top plate with adjustment bolt and cap screw to fasten and level equipment.
- C. Restrained Spring Isolators: Freestanding, steel, open-spring isolators with seismic or limit-stop restraint.
  1. Housing: Steel with resilient vertical-limit stops to prevent spring extension due to weight being removed; factory-drilled baseplate bonded to 1/4-inch- (6-mm-) thick, neoprene or rubber isolator pad attached to baseplate underside; and adjustable equipment mounting and leveling bolt that acts as blocking during installation.
  2. Restraint: Seismic or limit-stop as required for equipment and authorities having jurisdiction.
  3. Outside Spring Diameter: Not less than 80 percent of the compressed height of the spring at rated load.
  4. Minimum Additional Travel: 50 percent of the required deflection at rated load.
  5. Lateral Stiffness: More than 80 percent of rated vertical stiffness.
  6. Overload Capacity: Support 200 percent of rated load, fully compressed, without deformation or failure.

## 2.2 SEISMIC-RESTRAINT DEVICES

- A. Available Manufacturers: Subject to compliance with requirements, manufacturers offering products that may be incorporated into the Work include, but are not limited to, the following:
  1. Amber/Booth Company, Inc.
  2. California Dynamics Corporation.
  3. Cooper B-Line, Inc.; a division of Cooper Industries.
  4. Hilti Inc.
  5. Loos & Co.; Seismic Earthquake Division.
  6. Mason Industries.
  7. TOLCO Incorporated; a brand of NIBCO INC.
  8. Unistrut; Tyco International, Ltd.
- B. General Requirements for Restraint Components: Rated strengths, features, and application requirements shall be as defined in reports by an evaluation service member of ICC-ES.
  1. Structural Safety Factor: Allowable strength in tension, shear, and pullout force of components shall be at least four times the maximum seismic forces to which they will be subjected.
- C. Channel Support System: MFMA-3, shop- or field-fabricated support assembly made of slotted steel channels with accessories for attachment to braced component at one end and to building structure at the other end and other matching components and with corrosion-resistant coating; and rated in tension, compression, and torsion forces.
- D. Restraint Cables: ASTM A 492 stainless-steel cables with end connections made of steel assemblies with thimbles, brackets, swivels, and bolts designed for restraining cable service; and with a minimum of two clamping bolts for cable engagement.
- E. Hanger Rod Stiffener: Steel tube or steel slotted-support-system sleeve with internally bolted connections to hanger rod. Do not weld stiffeners to rods.
- F. Bushings for Floor-Mounted Equipment Anchor: Neoprene bushings designed for rigid equipment mountings, and matched to type and size of anchors and studs.
- G. Bushing Assemblies for Wall-Mounted Equipment Anchorage: Assemblies of neoprene elements and steel sleeves designed for rigid equipment mountings, and matched to type and size of attachment devices.
- H. Resilient Isolation Washers and Bushings: One-piece, molded, oil- and water-resistant neoprene, with a flat washer face.
- I. Mechanical Anchor: Drilled-in and stud-wedge or female-wedge type in zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchors with strength

required for anchor and as tested according to ASTM E 488. Minimum length of eight times diameter.

- J. Adhesive Anchor: Drilled-in and capsule anchor system containing polyvinyl or urethane methacrylate-based resin and accelerator, or injected polymer or hybrid mortar adhesive. Provide anchor bolts and hardware with zinc-coated steel for interior applications and stainless steel for exterior applications. Select anchor bolts with strength required for anchor and as tested according to ASTM E 488.

### 2.3 FACTORY FINISHES

- A. Finish: Manufacturer's standard prime-coat finish ready for field painting.
- B. Finish: Manufacturer's standard paint applied to factory-assembled and -tested equipment before shipping.
  - 1. Powder coating on springs and housings.
  - 2. All hardware shall be galvanized. Hot-dip galvanize metal components for exterior use.
  - 3. Baked enamel or powder coat for metal components on isolators for interior use.
  - 4. Color-code or otherwise mark vibration isolation and seismic-control devices to indicate capacity range.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine areas and equipment to receive vibration isolation and seismic-control devices for compliance with requirements for installation tolerances and other conditions affecting performance.
- B. Examine roughing-in of reinforcement and cast-in-place anchors to verify actual locations before installation.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 APPLICATIONS

- A. Multiple Raceways or Cables: Secure raceways and cables to trapeze member with clamps approved for application by an evaluation service member of ICC-ES.
- B. Hanger Rod Stiffeners: Install hanger rod stiffeners where indicated or scheduled on Drawings to receive them and where required to prevent buckling of hanger rods due to seismic forces.
- C. Strength of Support and Seismic-Restraint Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static and seismic loads within specified loading limits.

### 3.3 SEISMIC-RESTRAINT DEVICE INSTALLATION

- A. Equipment and Hanger Restraints:
  - 1. Install restrained isolators on electrical equipment.
  - 2. Install resilient, bolt-isolation washers on equipment anchor bolts where clearance between anchor and adjacent surface exceeds 0.125 inch (3.2 mm).
  - 3. Install seismic-restraint devices using methods approved by an evaluation service member of ICC-ES providing required submittals for component.
- B. Install bushing assemblies for mounting bolts for wall-mounted equipment, arranged to provide resilient media where equipment or equipment-mounting channels are attached to wall.
- C. Attachment to Structure: If specific attachment is not indicated, anchor bracing to structure at flanges of beams, at upper truss chords of bar joists, or at concrete members.
- D. Drilled-in Anchors:
  - 1. Identify position of reinforcing steel and other embedded items prior to drilling holes for anchors. Do not damage existing reinforcing or embedded items during coring or drilling. Notify the structural engineer if reinforcing steel or other embedded items are

- encountered during drilling. Locate and avoid prestressed tendons, electrical and telecommunications conduit, and gas lines.
2. Do not drill holes in concrete or masonry until concrete, mortar, or grout has achieved full design strength.
  3. Wedge Anchors: Protect threads from damage during anchor installation. Heavy-duty sleeve anchors shall be installed with sleeve fully engaged in the structural element to which anchor is to be fastened.
  4. Adhesive Anchors: Clean holes to remove loose material and drilling dust prior to installation of adhesive. Place adhesive in holes proceeding from the bottom of the hole and progressing toward the surface in such a manner as to avoid introduction of air pockets in the adhesive.
  5. Set anchors to manufacturer's recommended torque, using a torque wrench.
  6. Install zinc-coated steel anchors for interior and stainless-steel anchors for exterior applications.

### 3.4 ACCOMMODATION OF DIFFERENTIAL SEISMIC MOTION

- A. Install flexible connections in runs of raceways, cables, wireways, cable trays, and busways where they cross seismic joints, where adjacent sections or branches are supported by different structural elements, and where they terminate with connection to equipment that is anchored to a different structural element from the one supporting them as they approach equipment.

### 3.5 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
- B. Tests and Inspections:
  1. Provide evidence of recent calibration of test equipment by a testing agency acceptable to authorities having jurisdiction.
  2. Schedule test with Owner, through Architect, before connecting anchorage device to restrained component (unless postconnection testing has been approved), and with at least seven days' advance notice.
  3. Obtain Architect's approval before transmitting test loads to structure. Provide temporary load-spreading members.
  4. Test at least four of each type and size of installed anchors and fasteners selected by Architect.
  5. Test to 90 percent of rated proof load of device.
  6. Measure isolator restraint clearance.
  7. Measure isolator deflection.
  8. Verify snubber minimum clearances.
  9. If a device fails test, modify all installations of same type and retest until satisfactory results are achieved.
- C. Remove and replace malfunctioning units and retest as specified above.
- D. Prepare test and inspection reports.

### 3.6 ADJUSTING

- A. Adjust isolators after isolated equipment is at operating weight.
- B. Adjust limit stops on restrained spring isolators to mount equipment at normal operating height. After equipment installation is complete, adjust limit stops so they are out of contact during normal operation.
- C. Adjust active height of spring isolators.
- D. Adjust restraints to permit free movement of equipment within normal mode of operation.

## END OF SECTION 260548

## SECTION 260553 - IDENTIFICATION FOR ELECTRICAL SYSTEMS

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Identification for raceways.
  - 2. Identification of power and control cables.
  - 3. Identification for conductors.
  - 4. Underground-line warning tape.
  - 5. Warning labels and signs.
  - 6. Instruction signs.
  - 7. Equipment identification labels.
  - 8. Miscellaneous identification products.

#### 1.3 ACTION SUBMITTALS

- A. Product Data: For each electrical identification product indicated.
- B. Samples: For each type of label and sign to illustrate size, colors, lettering style, mounting provisions, and graphic features of identification products.
- C. Identification Schedule: An index of nomenclature of electrical equipment and system components used in identification signs and labels.

#### 1.4 QUALITY ASSURANCE

- A. Comply with ANSI A13.1 and IEEE C2.
- B. Comply with NFPA 70.
- C. Comply with 29 CFR 1910.144 and 29 CFR 1910.145.
- D. Comply with ANSI Z535.4 for safety signs and labels.
- E. Adhesive-attached labeling materials, including label stocks, laminating adhesives, and inks used by label printers, shall comply with UL 969.

#### 1.5 COORDINATION

- A. Coordinate identification names, abbreviations, colors, and other features with requirements in other Sections requiring identification applications, Drawings, Shop Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance

Manual; and with those required by codes, standards, and 29 CFR 1910.145. Use consistent designations throughout Project.

- B. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.
- C. Coordinate installation of identifying devices with location of access panels and doors.
- D. Install identifying devices before installing acoustical ceilings and similar concealment.

## PART 2 - PRODUCTS

### 2.1 POWER AND CONTROL RACEWAY IDENTIFICATION MATERIALS

- A. Color coded raceways with factory applied color coating.
- B. Colors for Raceways:
  - 1. Normal power circuits: no added color.
  - 2. Emergency power circuits: blue
  - 3. Optional Standby and UPS power circuits: green
  - 4. Fire Alarm wiring: red
  - 5. Access control and CCTV systems wiring: white
  - 6. All other systems: black

### 2.2 ARMORED AND METAL-CLAD CABLE IDENTIFICATION MATERIALS

- A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each cable size.
- B. Colors for Cables Carrying Circuits at 600 V and Less:
  - 1. Black letters on an orange field.
  - 2. Legend: Indicate voltage and system or service type.
- C. Heat-Shrink Preprinted Tubes: Flame-retardant polyolefin tube with machine-printed identification label. Sized to suit diameter of and shrinks to fit firmly around cable it identifies. Full shrink recovery at a maximum of 200 deg F (93 deg C). Comply with UL 224.

### 2.3 POWER AND CONTROL CABLE IDENTIFICATION MATERIALS

- A. Comply with ANSI A13.1 for minimum size of letters for legend and for minimum length of color field for each cable size.
- B. Snap-Around Labels: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeve, with diameter sized to suit diameter of cable it identifies and to stay in place by gripping action.

### 2.4 CONDUCTOR IDENTIFICATION MATERIALS

- A. Color-Coding Conductor Tape: Colored, self-adhesive vinyl tape not less than 3 mils (0.08 mm) thick by 1 to 2 inches (25 to 50 mm) wide.

- B. Snap-Around Labels: Slit, pretensioned, flexible, preprinted, color-coded acrylic sleeve, with diameter sized to suit diameter of conductor it identifies and to stay in place by gripping action.

## 2.5 FLOOR MARKING TAPE

- A. **2-inch- (50-mm-)** wide, **5-mil (0.125-mm)** pressure-sensitive vinyl tape, with yellow and black stripes and clear vinyl overlay.

## 2.6 UNDERGROUND-LINE WARNING TAPE

- A. Tape:
  - 1. Recommended by manufacturer for the method of installation and suitable to identify and locate underground electrical and communications utility lines.
  - 2. Printing on tape shall be permanent and shall not be damaged by burial operations.
  - 3. Tape material and ink shall be chemically inert, and not subject to degrading when exposed to acids, alkalis, and other destructive substances commonly found in soils.
- B. Color and Printing:
  - 1. Comply with ANSI Z535.1 through ANSI Z535.5.
  - 2. Inscriptions for Red-Colored Tapes: ELECTRIC LINE, HIGH VOLTAGE,.
  - 3. Inscriptions for Orange-Colored Tapes: TELEPHONE CABLE, CATV CABLE, COMMUNICATIONS CABLE, OPTICAL FIBER CABLE,.

## 2.7 WARNING LABELS AND SIGNS

- A. Comply with NFPA 70 and 29 CFR 1910.145.
- B. Metal-Backed, Butyrate Warning Signs:
  - 1. Weather-resistant, nonfading, preprinted, cellulose-acetate butyrate signs with **0.0396-inch (1-mm)** galvanized-steel backing; and with colors, legend, and size required for application.
  - 2. **1/4-inch (6.4-mm)** grommets in corners for mounting.
  - 3. Nominal size, **10 by 14 inches (250 by 360 mm)**.
- C. Warning label and sign shall include, but are not limited to, the following legends:
  - 1. Multiple Power Source Warning: "DANGER - ELECTRICAL SHOCK HAZARD - EQUIPMENT HAS MULTIPLE POWER SOURCES."
  - 2. Workspace Clearance Warning: "WARNING - OSHA REGULATION - AREA IN FRONT OF ELECTRICAL EQUIPMENT MUST BE KEPT CLEAR FOR **36 INCHES (915 MM)**."

## 2.8 INSTRUCTION SIGNS

- A. Engraved, laminated acrylic or melamine plastic, minimum **1/16 inch (1.6 mm)** thick for signs up to **20 sq. inches (129 sq. cm)** and **1/8 inch (3.2 mm)** thick for larger sizes.
  - 1. Engraved legend with black letters on white face.
  - 2. Punched or drilled for mechanical fasteners.



3. Framed with mitered acrylic molding and arranged for attachment at applicable equipment.

## 2.9 EQUIPMENT IDENTIFICATION LABELS

- A. Engraved, Laminated Acrylic or Melamine Label: Punched or drilled for screw mounting. White letters on a dark-gray background. Minimum letter height shall be **3/8 inch (10 mm)**.

## 2.10 MISCELLANEOUS IDENTIFICATION PRODUCTS

- A. Paint: Comply with requirements in painting Sections for paint materials and application requirements. Select paint system applicable for surface material and location (exterior or interior).
- B. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Verify identity of each item before installing identification products.
- B. Location: Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.
- C. Apply identification devices to surfaces that require finish after completing finish work.
- D. Self-Adhesive Identification Products: Clean surfaces before application, using materials and methods recommended by manufacturer of identification device.
- E. Attach signs and plastic labels that are not self-adhesive type with mechanical fasteners appropriate to the location and substrate.
- F. Attach plastic raceway and cable labels that are not self-adhesive type with clear vinyl tape with adhesive appropriate to the location and substrate.
- G. System Identification Color-Coding Bands for Raceways and Cables: Each color-coding band shall completely encircle cable or conduit. Place adjacent bands of two-color markings in contact, side by side. Locate bands at changes in direction, at penetrations of walls and floors, at **50-foot (15-m)** maximum intervals in straight runs, and at **25-foot (7.6-m)** maximum intervals in congested areas.
- H. Aluminum Wraparound Marker Labels and Metal Tags: Secure tight to surface of conductor or cable at a location with high visibility and accessibility.
- I. Cable Ties: For attaching tags. Use general-purpose type, except as listed below:
  1. Outdoors: UV-stabilized nylon.
  2. In Spaces Handling Environmental Air: Plenum rated.

- J. Underground-Line Warning Tape: During backfilling of trenches install continuous underground-line warning tape directly above line at 6 to 8 inches (150 to 200 mm) below finished grade. Use multiple tapes where width of multiple lines installed in a common trench or concrete envelope exceeds 16 inches (400 mm) overall.
- K. Painted Identification: Comply with requirements in painting Sections for surface preparation and paint application.

### 3.2 IDENTIFICATION SCHEDULE

- A. Accessible Raceways and Cables within Buildings: Identify the covers of each junction and pull box of the following systems with color coding that matches raceways and self-adhesive vinyl labels with the wiring system legend. For power circuits include the panel and circuit numbers of all conductors contained in the box and the voltage. For fire alarm circuits include the circuit numbering to match shop drawings. For other systems include the system type such as Access Control, CCTV, Overhead Paging, etc. System color coding shall be as follows:
  - 1. Normal power circuits: no added color.
  - 2. Emergency power circuits: blue
  - 3. Optional Standby and UPS power circuits: green
  - 4. Fire Alarm wiring: red
  - 5. Access control and CCTV systems wiring: white
  - 6. All other systems: black
- B. Power-Circuit Conductor Identification, 600 V or Less: For conductors in vaults, pull and junction boxes, manholes, and handholes, use color-coding conductor tape to identify the phase.
  - 1. Color-Coding for Phase and Voltage Level Identification, 600 V or Less: Use colors listed below for ungrounded service, feeder, and branch-circuit conductors.
    - a. Color shall be factory applied.
    - b. Colors for 208/120-V Circuits:
      - 1) Phase A: Black.
      - 2) Phase B: Red.
      - 3) Phase C: Blue.
    - c. Colors for 480/277-V Circuits:
      - 1) Phase A: Orange
      - 2) Phase B: Brown
      - 3) Phase C: Yellow.
- C. Install instructional sign including the color-code for grounded and ungrounded conductors using adhesive- vinyl-film-type labels.
- D. Control-Circuit Conductor Identification: For conductors and cables in pull and junction boxes, manholes, and handholes, use self-adhesive vinyl labels with the conductor or cable designation, origin, and destination.
- E. Conductors to Be Extended in the Future: Attach marker tape to conductors and list source.

- F. Auxiliary Electrical Systems Conductor Identification: Identify field-installed alarm, control, and signal connections.
  - 1. Identify conductors, cables, and terminals in enclosures and at junctions, terminals, and pull points. Identify by system and circuit designation.
  - 2. Use system of marker tape designations that is uniform and consistent with system used by manufacturer for factory-installed connections.
  - 3. Coordinate identification with Project Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual.
- G. Locations of Underground Lines: Identify with underground-line warning tape for power, lighting, communication, and control wiring and optical fiber cable.
  - 1. Limit use of underground-line warning tape to direct-buried cables.
  - 2. Install underground-line warning tape for both direct-buried cables and cables in raceway.
- H. Workspace Indication: Install floor marking tape to show working clearances in the direction of access to live parts. Workspace shall be as required by NFPA 70 and 29 CFR 1926.403 unless otherwise indicated. Do not install at flush-mounted panelboards and similar equipment in finished spaces.
- I. Warning Labels for Indoor Cabinets, Boxes, and Enclosures for Power and Lighting: Self-adhesive warning labels.
  - 1. Comply with 29 CFR 1910.145.
  - 2. Identify system voltage with black letters on an orange background.
  - 3. Apply to exterior of door, cover, or other access.
  - 4. For equipment with multiple power or control sources, apply to door or cover of equipment including, but not limited to, the following:
    - a. Power transfer switches.
    - b. Controls with external control power connections.
- J. Operating Instruction Signs: Install instruction signs to facilitate proper operation and maintenance of electrical systems and items to which they connect. Install instruction signs with approved legend where instructions are needed for system or equipment operation.
- K. Emergency Operating Instruction Signs: Install instruction signs with white legend on a red background with minimum **3/8-inch- (10-mm-)** high letters for emergency instructions at equipment used for power transfer.
- L. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and the Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification.
  - 1. Labeling Instructions:
    - a. Indoor Equipment: Engraved, laminated acrylic or melamine label. Unless otherwise indicated, provide a single line of text with **1/2-inch- (13-mm-)** high letters on **1-1/2-inch- (38-mm-)** high label; where two lines of text are required, use labels **2 inches (50 mm)** high.

- b. Outdoor Equipment: Engraved, laminated acrylic or melamine label.
  - c. Elevated Components: Increase sizes of labels and letters to those appropriate for viewing from the floor.
  - d. Fasten labels with appropriate mechanical fasteners that do not change the NEMA or NRTL rating of the enclosure.
2. Equipment to Be Labeled:
- a. Panelboards: Typewritten directory of circuits in the location provided by panelboard manufacturer. Panelboard identification shall be engraved, laminated acrylic or melamine label.
  - b. All receptacles and switches
  - c. Fire alarm devices
  - d. Circuit #'s on j-boxes
  - e. Enclosures and electrical cabinets.
  - f. Access doors and panels for concealed electrical items.
  - g. Switchboards.
  - h. Transformers: Label that includes tag designation shown on Drawings for the transformer, feeder, and panelboards or equipment supplied by the secondary.
  - i. Emergency system boxes and enclosures.
  - j. Enclosed switches.
  - k. Enclosed circuit breakers.
  - l. Enclosed controllers.
  - m. Variable-speed controllers.
  - n. Push-button stations.
  - o. Power transfer equipment.
  - p. Contactors.
  - q. Remote-controlled switches, dimmer modules, and control devices.
  - r. Battery racks.
  - s. Monitoring and control equipment.
  - t. UPS equipment.

**END OF SECTION 260553**

## **SECTION 260923 - LIGHTING CONTROL DEVICES**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Indoor occupancy sensors.
  - 2. Indoor vacancy sensors.
- B. Related Requirements:
  - 1. Section 262726 "Wiring Devices" for wall-box dimmers, wall-switch occupancy sensors, and manual light switches.

#### **1.3 ACTION SUBMITTALS**

- A. Product Data: For each type of product.

#### **1.4 INFORMATIONAL SUBMITTALS**

- A. Field quality-control reports.

#### **1.5 CLOSEOUT SUBMITTALS**

- A. Operation and Maintenance Data: For each type of lighting control device to include in emergency, operation, and maintenance manuals.

### **PART 2 - PRODUCTS**

#### **2.1 INDOOR CEILING MOUNTED OCCUPANCY SENSORS**

- A. Match existing Watt-Stopper manufacturer
- B. General Requirements for Sensors: Ceiling-mounted, solid-state indoor occupancy sensors with a separate power pack.
  - 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

2. Operation: Unless otherwise indicated, turn lights on when coverage area is occupied, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
  3. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A. Sensor is powered from the power pack.
  4. Power Pack: Dry contacts rated for 20-A ballast load at 120- and 277-V ac, for 13-A tungsten at 120-V ac, and for 1 hp at 120-V ac. Sensor has 24-V dc, 150-mA, Class 2 power source, as defined by NFPA 70.
  5. Mounting:
    - a. Sensor: Suitable for mounting in any position on a standard outlet box.
    - b. Relay: Externally mounted through a 1/2-inch (13-mm) knockout in a standard electrical enclosure.
    - c. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.
  6. Indicator: Digital display, to show when motion is detected during testing and normal operation of sensor.
  7. Bypass Switch: Override the "on" function in case of sensor failure.
  8. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc (21.5 to 2152 lux); turn lights off when selected lighting level is present.
- C. Dual-Technology Type: Ceiling mounted; detect occupants in coverage area using PIR and ultrasonic detection methods. The particular technology or combination of technologies that control on-off functions is selectable in the field by operating controls on unit.
1. Sensitivity Adjustment: Separate for each sensing technology.
  2. Detector Sensitivity: Detect occurrences of 6-inch- (150-mm-) minimum movement of any portion of a human body that presents a target of not less than 36 sq. in. (232 sq. cm), and detect a person of average size and weight moving not less than 12 inches (305 mm) in either a horizontal or a vertical manner at an approximate speed of 12 inches/s (305 mm/s).
  3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. (93 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.

## 2.2 INDOOR CEILING MOUNTED VACANCY SENSORS

- A. General Requirements for Sensors: Ceiling-mounted, solid-state indoor occupancy sensors with a separate power pack.
1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
  2. Receives input from momentary contact wall switch to turn on lights.
  3. Operation: Turn lights on when momentary contact switch is closed, and turn them off when unoccupied; with a time delay for turning lights off, adjustable over a minimum range of 1 to 15 minutes.
  4. Sensor Output: Contacts rated to operate the connected relay, complying with UL 773A. Sensor is powered from the power pack.
  5. Power Pack: Dry contacts rated for 20-A ballast load at 120- and 277-V ac, for 13-A tungsten at 120-V ac, and for 1 hp at 120-V ac. Sensor has 24-V dc, 150-mA, Class 2 power source, as defined by NFPA 70.
  6. Mounting:
    - a. Sensor: Suitable for mounting in any position on a standard outlet box.
    - b. Relay: Externally mounted through a 1/2-inch (13-mm) knockout in a standard electrical enclosure.

- c. Time-Delay and Sensitivity Adjustments: Recessed and concealed behind hinged door.
  - 7. Indicator: Digital display, to show when motion is detected during testing and normal operation of sensor.
  - 8. Bypass Switch: Override the "on" function in case of sensor failure.
  - 9. Automatic Light-Level Sensor: Adjustable from 2 to 200 fc (21.5 to 2152 lux); turn lights off when selected lighting level is present.
- B. Dual-Technology Type: Ceiling mounted; detect occupants in coverage area using PIR and ultrasonic detection methods. The particular technology or combination of technologies that control on-off functions is selectable in the field by operating controls on unit.
- 1. Sensitivity Adjustment: Separate for each sensing technology.
  - 2. Detector Sensitivity: Detect occurrences of 6-inch- (150-mm-) minimum movement of any portion of a human body that presents a target of not less than 36 sq. in. (232 sq. cm), and detect a person of average size and weight moving not less than 12 inches (305 mm) in either a horizontal or a vertical manner at an approximate speed of 12 inches/s (305 mm/s).
  - 3. Detection Coverage (Standard Room): Detect occupancy anywhere within a circular area of 1000 sq. ft. (93 sq. m) when mounted on a 96-inch- (2440-mm-) high ceiling.

## 2.3 SWITCHBOX-MOUNTED OCCUPANCY SENSORS

- A. General Requirements for Sensors: Automatic-wall-switch occupancy sensor, suitable for mounting in a single gang switchbox.
- 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
  - 2. Operating Ambient Conditions: Dry interior conditions, 32 to 120 deg F (0 to 49 deg C).
  - 3. Switch Rating: Not less than 800-VA fluorescent at 120 V, 1200-VA fluorescent at 277 V, and 800-W incandescent.
- B. Wall-Switch Sensor:
- 1. Standard Range: 210-degree field of view, with a minimum coverage area of 900 sq. ft. (84 sq. m).
  - 2. Sensing Technology: PIR.
  - 3. Switch Type: SP. SP, field selectable automatic "on," or manual "on" automatic "off."
  - 4. Voltage: Match the circuit voltage; dual-technology type.
  - 5. Ambient-Light Override: Concealed, field-adjustable, light-level sensor from 10 to 150 fc (108 to 1600 lux). The switch prevents the lights from turning on when the light level is higher than the set point of the sensor.
  - 6. Concealed, field-adjustable, "off" time-delay selector at up to 30 minutes.
  - 7. Concealed "off" time-delay selector at 30 seconds, and 5, 10, and 20 minutes.
  - 8. Adaptive Technology: Self-adjusting circuitry detects and memorizes usage patterns of the space and helps eliminate false "off" switching.

## 2.4 SWITCHBOX-MOUNTED VACANCY SENSORS

- A. General Requirements for Sensors: Automatic-wall-switch occupancy sensor, suitable for mounting in a single gang switchbox.
- 1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
  - 2. Operating Ambient Conditions: Dry interior conditions, 32 to 120 deg F (0 to 49 deg C).

3. Switch Rating: Not less than 800-VA fluorescent at 120 V, 1200-VA fluorescent at 277 V, and 800-W incandescent.
- B. Wall-Switch Sensor:
  1. Standard Range: 210-degree field of view, with a minimum coverage area of 900 sq. ft. (84 sq. m).
  2. Sensing Technology: PIR.
  3. Switch Type: SP, manual "on," automatic "off."
  4. Voltage: Match the circuit voltage; dual-technology type.
  5. Ambient-Light Override: Concealed, field-adjustable, light-level sensor from 10 to 150 fc (108 to 1600 lux). The switch prevents the lights from turning on when the light level is higher than the set point of the sensor.
  6. Concealed, field-adjustable, "off" time-delay selector at up to 30 minutes.
  7. Concealed "off" time-delay selector at 30 seconds, and 5, 10, and 20 minutes.Adaptive Technology: Self-adjusting circuitry detects and memorizes usage patterns of the space and helps eliminate false "off" switching

### PART 3 - EXECUTION

#### 3.1 SENSOR INSTALLATION

- A. Coordinate layout and installation of ceiling-mounted devices with other construction that penetrates ceilings or is supported by them, including light fixtures, HVAC equipment, smoke detectors, fire-suppression systems, and partition assemblies.
- B. Install and aim sensors in locations to achieve not less than 90 percent coverage of areas indicated. Do not exceed coverage limits specified in manufacturer's written instructions.

#### 3.2 CONTACTOR INSTALLATION

- A. Mount electrically held lighting contactors with elastomeric isolator pads to eliminate structure-borne vibration, unless contactors are installed in an enclosure with factory-installed vibration isolators.

#### 3.3 WIRING INSTALLATION

- A. Wiring Method: Comply with Section 260519 "Low-Voltage Electrical Power Conductors and Cables." Minimum conduit size is 1/2 inch (13 mm).
- B. Wiring within Enclosures: Comply with NECA 1. Separate power-limited and nonpower-limited conductors according to conductor manufacturer's written instructions.
- C. Size conductors according to lighting control device manufacturer's written instructions unless otherwise indicated.
- D. Splices, Taps, and Terminations: Make connections only on numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures.



### 3.4 IDENTIFICATION

- A. Identify components and power and control wiring according to Section 260553 "Identification for Electrical Systems."
  - 1. Identify controlled circuits in lighting contactors.
  - 2. Identify circuits or luminaires controlled by photoelectric and occupancy sensors at each sensor.
- B. Label time switches and contactors with a unique designation.

### 3.5 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections[ with the assistance of a factory-authorized service representative]:
  - 1. Operational Test: After installing time switches and sensors, and after electrical circuitry has been energized, start units to confirm proper unit operation.
  - 2. Test and adjust controls and safeties. Replace damaged and malfunctioning controls and equipment.
- B. Lighting control devices will be considered defective if they do not pass tests and inspections.
- C. Prepare test and inspection reports.

### 3.6 ADJUSTING

- A. Occupancy Adjustments: When requested within 2 months from date of Substantial Completion, provide on-site assistance in adjusting sensors to suit actual occupied conditions. Provide up to two visits to Project during other-than-normal occupancy hours for this purpose.
  - 1. For occupancy and motion sensors, verify operation at outer limits of detector range. Set time delay to suit Owner's operations.
  - 2. For daylighting controls, adjust set points and deadband controls to suit Owner's operations.

## END OF SECTION 260923

## **SECTION 262416 – PANELBOARDS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Distribution panelboards.
  - 2. Lighting and appliance branch-circuit panelboards.
  - 3. Isolation panel boards
  - 4. Electronic-grade panelboards.

#### **1.3 DEFINITIONS**

- A. SVR: Suppressed voltage rating.
- B. TVSS: Transient voltage surge suppressor.

#### **1.4 PERFORMANCE REQUIREMENTS**

- A. Seismic Performance: Panelboards shall withstand the effects of earthquake motions determined according to SEI/ASCE 7.
  - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."

#### **1.5 ACTION SUBMITTALS**

- A. Product Data: For each type of panelboard, switching and overcurrent protective device, transient voltage suppression device, accessory, and component indicated. Include dimensions and manufacturers' technical data on features, performance, electrical characteristics, ratings, and finishes.
- B. Shop Drawings: For each panelboard and related equipment.
  - 1. Include dimensioned plans, elevations, sections, and details. Show tabulations of installed devices, equipment features, and ratings.
  - 2. Detail enclosure types and details for types other than NEMA 250, Type 1.
  - 3. Detail bus configuration, current, and voltage ratings.
  - 4. Short-circuit current rating of panelboards and overcurrent protective devices.
  - 5. Include evidence of NRTL listing for series rating of installed devices.
  - 6. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices and auxiliary components.
  - 7. Include wiring diagrams for power, signal, and control wiring.
  - 8. Include time-current coordination curves for each type and rating of overcurrent protective device included in panelboards. Submit on translucent log-log graft paper; include selectable ranges for each type of overcurrent protective device.

## 1.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified testing agency.
- B. Seismic Qualification Certificates: Submit certification that panelboards, overcurrent protective devices, accessories, and components will withstand seismic forces defined in Section 260548 "Vibration and Seismic Controls for Electrical Systems." Include the following:
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- C. Field Quality-Control Reports:
  - 1. Test procedures used.
  - 2. Test results that comply with requirements.
  - 3. Results of failed tests and corrective action taken to achieve test results that comply with requirements.
- D. Panelboard Schedules: For installation in panelboards.

## 1.7 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For panelboards and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
  - 1. Manufacturer's written instructions for testing and adjusting overcurrent protective devices.
  - 2. Time-current curves, including selectable ranges for each type of overcurrent protective device that allows adjustments.

## 1.8 MAINTENANCE MATERIAL SUBMITTALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Keys: Two spares for each type of panelboard cabinet lock.
  - 2. Circuit Breakers Including GFCI and Ground Fault Equipment Protection (GFEP) Types: Two spares for each panelboard.

## 1.9 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Member company of NETA or an NRTL.
  - 1. Testing Agency's Field Supervisor: Currently certified by NETA to supervise on-site testing.
- B. Source Limitations: Obtain panelboards, overcurrent protective devices, components, and accessories from single source from single manufacturer.

- C. Product Selection for Restricted Space: Drawings indicate maximum dimensions for panelboards including clearances between panelboards and adjacent surfaces and other items. Comply with indicated maximum dimensions.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- E. Comply with NEMA PB 1.
- F. Comply with NFPA 70.

#### 1.10 DELIVERY, STORAGE, AND HANDLING

- A. Remove loose packing and flammable materials from inside panelboards; install temporary electric heating (250 W per panelboard) to prevent condensation.
- B. Handle and prepare panelboards for installation according to NEMA PB 1.

#### 1.11 PROJECT CONDITIONS

- A. Environmental Limitations:
  - 1. Do not deliver or install panelboards until spaces are enclosed and weathertight, wet work in spaces is complete and dry, work above panelboards is complete, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.
  - 2. Rate equipment for continuous operation under the following conditions unless otherwise indicated:
    - a. Ambient Temperature: Not exceeding [minus 22 deg F (minus 30 deg C)] [23 deg F (minus 5 deg C)] to plus 104 deg F (plus 40 deg C).
    - b. Altitude: Not exceeding 6600 feet (2000 m).
- B. Service Conditions: NEMA PB 1, usual service conditions, as follows:
  - 1. Ambient temperatures within limits specified.
  - 2. Altitude not exceeding 6600 feet (2000 m).
- C. Interruption of Existing Electric Service: Do not interrupt electric service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary electric service according to requirements indicated:
  - 1. Notify Architect no fewer than 7 days in advance of proposed interruption of electric service.
  - 2. Do not proceed with interruption of electric service without Construction Manager's Owner's written permission.
  - 3. Comply with NFPA 70E.

#### 1.12 COORDINATION

- A. Coordinate layout and installation of panelboards and components with other construction that penetrates walls or is supported by them, including electrical and

other types of equipment, raceways, piping, encumbrances to workspace clearance requirements, and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

- B. Coordinate sizes and locations of concrete bases with actual equipment provided. Cast anchor-bolt inserts into bases. Concrete, reinforcement, and formwork requirements are specified with concrete.

#### 1.13 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace transient voltage suppression devices that fail in materials or workmanship within specified warranty period.
  - 1. Warranty Period: Five years from date of Substantial Completion.

### PART 2 - PRODUCTS

#### 2.1 GENERAL REQUIREMENTS FOR PANELBOARDS

- A. Fabricate and test panelboards according to IEEE 344 to withstand seismic forces defined in Section 260548 "Vibration and Seismic Controls for Electrical Systems."
- B. Enclosures: Surface-mounted cabinets.
  - 1. Rated for environmental conditions at installed location.
    - a. Indoor Dry and Clean Locations: NEMA 250, Type 1.
  - 2. Hinged Front Cover: Entire front trim hinged to box and with standard door within hinged trim cover.
  - 3. Finishes:
    - a. Panels and Trim: Steel and galvanized steel, factory finished immediately after cleaning and pretreating with manufacturer's standard two-coat, baked-on finish consisting of prime coat and thermosetting topcoat.
    - b. Back Boxes: Galvanized steel.
    - c. Fungus Proofing: Permanent fungicidal treatment for overcurrent protective devices and other components.
  - 4. Directory Card: Inside panelboard door, metal frame with transparent protective cover.
- C. Incoming Mains Location: Top and bottom.
- D. Phase, Neutral, and Ground Buses:
  - 1. Material: Tin-plated aluminum.
  - 2. Equipment Ground Bus: Adequate for feeder and branch-circuit equipment grounding conductors; bonded to box.
  - 3. Isolated Ground Bus: Adequate for branch-circuit isolated ground conductors; insulated from box.
  - 4. Extra-Capacity Neutral Bus: Neutral bus rated 200 percent of phase bus and UL listed as suitable for nonlinear loads.
  - 5. Split Bus: Vertical buses divided into individual vertical sections.
  - 6.
- E. Conductor Connectors: Suitable for use with conductor material and sizes.

1. Material: Tin-plated aluminum.
  2. Main and Neutral Lugs: Mechanical type.
  3. Ground Lugs and Bus-Configured Terminators: Mechanical type.
  4. Feed-Through Lugs: Mechanical type, suitable for use with conductor material. Locate at opposite end of bus from incoming lugs or main device.
  5. Subfeed (Double) Lugs: Mechanical type suitable for use with conductor material. Locate at same end of bus as incoming lugs or main device.
  6. Extra-Capacity Neutral Lugs: Rated 200 percent of phase lugs mounted on extra-capacity neutral bus.
- F. Service Equipment Label: NRTL labeled for use as service equipment for panelboards or load centers with one or more main service disconnecting and overcurrent protective devices.
- G. Future Devices: Mounting brackets, bus connections, filler plates, and necessary appurtenances required for future installation of devices.
- H. Panelboard Short-Circuit Current Rating: Fully rated to interrupt symmetrical short-circuit current available at terminals.
- I. Surge Protective Device (SPD): Provide in all panelboards even if not specifically indicated on the drawings.
- J. Surge Protection Device: IEEE C62.41-compliant, integrally mounted,, solid-state, parallel-connected, modular (with field-replaceable modules) type, with sine-wave tracking suppression and filtering modules, short-circuit current rating complying with UL 1449, second edition, and matching or exceeding the panelboard short-circuit rating, redundant suppression circuits, with individually fused metal-oxide varistors.
1. Accessories:
    - a. Fuses rated at 200-kA interrupting capacity.
    - b. Fabrication using bolted compression lugs for internal wiring.
    - c. Integral disconnect switch.
    - d. Redundant suppression circuits.
    - e. Redundant replaceable modules.
    - f. Arrangement with wire connections to phase buses, neutral bus, and ground bus.
    - g. LED indicator lights for power and protection status.
    - h. Audible alarm, with silencing switch, to indicate when protection has failed.
    - i. Form-C contacts rated at 5 A and 250-V ac, one normally open and one normally closed, for remote monitoring of system operation. Contacts shall reverse position on failure of any surge diversion module or on opening of any current-limiting device. Coordinate with building power monitoring and control system.
    - j. Four-digit, transient-event counter set to totalize transient surges.
  2. Peak Single-Impulse Surge Current Rating: 160 kA per mode/160 kA per phase.
  3. Minimum single-impulse current ratings, using 8-by-20-mic.sec. waveform described in IEEE C62.41.2.
    - a. Line to Neutral: 70,000 A.
    - b. Line to Ground: 70,000 A.
    - c. Neutral to Ground: 50,000 A.

4. Withstand Capabilities: 12,000 IEEE C62.41, Category C3 (10 kA), 8-by-20-mic.sec. surges with less than 5 percent change in clamping voltage.
5. Protection modes and UL 1449 SVR for grounded wye circuits with 480Y/277 and 208Y/120-V, three-phase, four-wire circuits shall be as follows:
  - a. Line to Neutral: 800 V for 480Y/277, 400 V for 208Y/120.
  - b. Line to Ground: 800 V for 480Y/277, 400 V for 208Y/120.
  - c. Neutral to Ground: 800 V for 480Y/277, 400 V for 208Y/120.
6. Protection modes and UL 1449 SVR for 240/120-V, single-phase, three-wire circuits shall be as follows:
  - a. Line to Neutral: 400 V.
  - b. Line to Ground: 400 V.
  - c. Neutral to Ground: 400 V.
7. Protection modes and UL 1449 SVR for 240/120-V, three-phase, four-wire circuits with high leg shall be as follows:
  - a. Line to Neutral: 400 V, 800 V from high leg.
  - b. Line to Ground: 400 V.
  - c. Neutral to Ground: 400 V.

## 2.2 DISTRIBUTION PANELBOARDS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  1. Square D; a brand of Schneider Electric.
  2. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
  3. General Electric Company; GE Consumer & Industrial - Electrical Distribution.
  4. Siemens Energy & Automation, Inc.
  - 5.
- B. Panelboards: NEMA PB 1, power and feeder distribution type.
- C. Doors: Secured with vault-type latch with tumbler lock; keyed alike.
  1. For doors more than 36 inches (914 mm) high, provide two latches, keyed alike.
- D. Branch Overcurrent Protective Devices : Bolt-on circuit breakers; plug-in circuit breakers where individual positive-locking device requires mechanical release for removal.

## 2.3 LIGHTING AND APPLIANCE BRANCH-CIRCUIT PANELBOARDS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  1. Square D; a brand of Schneider Electric.
  2. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
  3. General Electric Company; GE Consumer & Industrial - Electrical Distribution.
  4. Siemens Energy & Automation, Inc.
- B. Panelboards: NEMA PB 1, lighting and appliance branch-circuit type.
- C. Branch Overcurrent Protective Devices: Bolt-on circuit breakers, replaceable without disturbing adjacent units.

- D. Doors: Concealed hinges; secured with flush latch with tumbler lock; keyed alike.

## 2.4 DISCONNECTING AND OVERCURRENT PROTECTIVE DEVICES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Square D; a brand of Schneider Electric.
  - 2. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
  - 3. General Electric Company; GE Consumer & Industrial - Electrical Distribution.
  - 4. Siemens Energy & Automation, Inc.
  - 5.
- B. Molded-Case Circuit Breaker (MCCB): Comply with UL 489, with interrupting capacity to meet available fault currents.
  - 1. Thermal-Magnetic Circuit Breakers: Inverse time-current element for low-level overloads, and instantaneous magnetic trip element for short circuits. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
  - 2. Adjustable Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
  - 3. Electronic trip circuit breakers with rms sensing; field-replaceable rating plug or field-replicable electronic trip; and the following field-adjustable settings:
    - a. Instantaneous trip.
    - b. Long- and short-time pickup levels.
    - c. Long- and short-time time adjustments.
    - d. Ground-fault pickup level, time delay, and I<sup>2</sup>t response.
  - 4. Current-Limiting Circuit Breakers: Frame sizes 400 A and smaller; let-through ratings less than NEMA FU 1, RK-5.
  - 5. GFCI Circuit Breakers: Single- and two-pole configurations with Class A ground-fault protection (6-mA trip).
  - 6. Ground-Fault Equipment Protection (GFEP) Circuit Breakers: Class B ground-fault protection (30-mA trip).
  - 7. Molded-Case Circuit-Breaker (MCCB) Features and Accessories:
    - a. Standard frame sizes, trip ratings, and number of poles.
    - b. Lugs: Mechanical style, suitable for number, size, trip ratings, and conductor materials.
    - c. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and high-intensity discharge (HID) lighting circuits.
    - d. Handle Padlocking Device: Fixed attachment, for locking circuit-breaker handle in on or off position.

## 2.5 ISOLATED POWER SYSTEM PANELBOARDS

- A. The following components shall be provided by the manufacturer of the Operating Room Hospital Isolated Power System Panelboards as one integral unit.
- B. Transformers:
  - 1. The transformer shall be wound with an electrostatic shield between the primary and secondary windings. The shield shall be grounded to the enclosure. The



electrostatic shield will be designed to prevent direct shorting of the primary winding to the secondary winding, and to reduce the coupling of harmonic distortions between the primary and secondary circuits.

2. The total leakage current to ground from the transformer shall not exceed the values shown in Table 29.2 of UL 1047.
3. Regulation to be certified not to exceed 2.5% at 0.8 power factor (PF) at 20° C above the full load continuous operating temperature in accordance with NEMA-ANSI standards.
4. The transformer is to be single-phase, 60 Hz with primary and secondary voltages as listed in the drawings and/or schedule.
5. Class H rated insulation shall be used in the manufacture of the transformer and the temperature rise will be limited to 55° C above ambient under full load conditions, when tested in accordance with NEMA-ANSI standards. Transformers must have a 220° C, UL recognized insulation system.
6. The core shall be of stacked design and securely clamped and bolted. The core and coils shall be internally isolated from the enclosure by means of a suitable vibration dampening system; varnish impregnated, and shall have a final wrap of insulating material to prevent exposure of bare conductors.
7. The design sound level of the completed units shall not exceed 35 dB. Certified sound level reports shall be furnished for each individual unit upon the request of the consulting engineer.

C. Circuit Breakers

1. All circuit breakers must be 2-pole with a minimum interrupting capacity of 10,000 amperes. Panels shall have a minimum capacity of 16 secondary circuit breakers. Refer to the panelboard schedule for quantity and sizes of breakers. All circuit breakers shall be thermal-magnetic type. Thermal-only type circuit breakers will not be considered as equal.

D. Line Isolation Monitor (LIM)

1. The LIM shall use microprocessor-based digital signal processing to continually monitor the impedance from all secondary conductors of the isolated power systems to ground. The LIM shall be capable of measuring all combinations of capacitive and resistive faults including balanced, unbalanced and hybrid faults. LIMs which internally switch between either line and ground will not be accepted. The LIM shall not contribute more than 15mA to the total hazard current of the system being monitored.
2. The LIM shall have the following specifications:
  - a. Operating voltage 85 to 265 VAC
  - b. Accuracy 5% or better
  - c. Alarm level 2 or 5 mA (selectable)
  - d. Alarm bandwidth Zero (0)
  - e. Alarm hysteresis (on/off) 50 mA
  - f. Mode Single- or three-phase
  - g. Monitor hazard current 50 A
  - h. Operating frequency 50 or 60 Hz
3. All of the listed specifications shall be contained within one unit and be user selectable thus allowing the LIM to be interchanged from system to system.

4. The LIM shall incorporate a momentary test switch. When pressed, it shall check and recalibrate the unit. Additionally, the test switch shall perform a complete test of all indicating lamps and meters on the face of the LIM and at any remote indicating stations.
5. The LIM shall use digital signal processing to determine the hazard current of the system being monitored. The algorithms used to determine the system hazard current shall be preprogrammed into the LIMs microprocessor. At least every 65 minutes, the unit shall recheck its calibration and recalibrate the system to original performance specifications. Additionally, by pressing the LIMs momentary test switch, an immediate check and recalibration of the LIM shall be performed.
6. If internal components are more than 30% out of original specifications because of aging or failure, the LIM shall notify the user by displaying a unique error code thus eliminating the need for periodic manual testing to determine the units integrity. LIMs which use analog signal processing technology and/or require manual testing or recalibration will not be accepted.
7. The LIM shall have an optical infrared LED type serial port on the face of the unit for transmitting pertinent LIM and isolated power system data directly to a personal computer and PDA. The transmission of data shall not require any mechanical or direct electrical connection to the LIM. The LIM shall provide both analog and digital indication of the isolated power systems hazard current. Digital indication shall be provided by a digital meter and analog indication shall be provided by an LED bar graph type meter calibrated from 0 (zero) to 160% of the alarm setting of the LIM. LIMs with only analog or only digital indicating will not be accepted.
8. The LIM shall have a green safe light and red hazard light on the front panel. The red hazard light shall remain illuminated for the duration when the isolated power system hazard current is above the selected alarm level of the LIM. An audible alarm shall be incorporated into the unit and shall activate in conjunction with the red hazard light. The audible alarm shall have high, low, and off settings. A silence button shall be provided on the face of the unit to silence the audible alarm during fault conditions. Upon silencing the audible alarm, a yellow indicating light shall illuminate to indicate the audible alarm has been silenced. The red hazard light and yellow silence light shall automatically reset when the fault condition is eliminated. During fault conditions, the red hazard light and all red segments to the LED bar graph shall blink at a constant rate. All lamps are to be long life LED type.
9. A set of normally open and normally closed contacts, rated 3 amperes at 120 VAC shall be provided on the LIM for use with external alarm systems. The LIM shall also provide a 12 VAC output signal rated at 10 VA to power remote indicator alarm units. This 12 VAC output signal shall not increase the hazard current of the system being monitored. Provisions for connection of the remote metering shall also be provided as part of the LIM. These connections shall have the ability to operate either an analog or digital type remote meter.
10. The LIM shall incorporate a loss-of-ground feature which will activate the audible and visual alarms when connection is lost with the reference ground of the isolated power system being monitored. In addition to activating the alarm, the unit shall display an error code in the digital display of the LIM.
11. All switches, meters, and indicating lamps shall be flush with the face of the LIM to provide a neat and clean appearance. The entire front face of the unit shall

- have a polymer overlay that protects the unit from the intrusion of housekeeping cleaning agents. LIMs with exposed fuses, meters, switches, or circuit breakers will not be accepted.
12. The design of the LIM shall consist of two circuit boards interconnected by a ribbon connector. The two boards shall contain all of the units electrical components and be mounted in the rear housing of the LIM. A phenolic cover shall complete the assembly. The unit shall not contain any components, such as circuit breakers, meter, switches or indicating lamps, which are mounted on or attached to the front cover of the LIM. Access to the inside of the LIM shall be through the front of the unit thus eliminating the need to remove the unit from its mounting position to change any of the settings. Unique fasteners shall attach to the front cover of the unit to prevent unauthorized access to the interior of the LIM.
  13. The LIM shall be UL component recognized under UL1022 Standard for Line Isolation Monitors, and UL recognized as meeting CSA 22.2 the Canadian Standard for Line Isolation Monitors.
- E. Remote Indicator Alarm
1. The remote indicator alarm shall be flush mounted and have a brushed stainless steel front trim. When the hazard current is within the predetermined limit for the circuits being monitored, a constant green light will remain illuminated. When the limit is exceeded, the green light will extinguish, a red indicator will illuminate, and an audible signal will sound.
  2. A silencing switch for the audible signal shall be provided. When pressed, it will cause a yellow warning light to illuminate, indicating that the audible signal has been silenced. When the current flow to ground returns to an acceptable level, the unit will automatically reset. The wiring from the LIM to the indicator alarm shall not contribute any leakage current to the isolated system.
- F. Enclosures
1. The enclosure shall be 14-gauge steel which is degreased, phosphatized, primed, and finish baked enamel paint. The front trim shall be type 304 stainless steel with a #4 brushed finish. The enclosure will be flush mounted unless otherwise stated on the plans; maximum depth of twelve inches. The flush trim panels shall have a hinged door, with keyed lock, to give access to the circuit breakers and LIM, and to provide for testing.
  2. The front panel shall not contain any type of grille or louver for ventilation. The panel and transformer shall be so designed that heat generated by the transformer under full load conditions shall not affect the normal operation of the circuit breakers and LIM. The maximum front panel temperature shall not exceed 30°C rise under full load continuous operation. Certification of this temperature test shall be provided to the consulting engineer upon request. The entire section behind the hinged door shall be of a dead front design. All hinges will be concealed.
- G. Wiring
1. Wiring within all panels shall meet all applicable NEC standards. Low leakage insulation shall be used on all secondary wiring. The total leakage for all panel types shall not exceed the values shown in table 29.1 of UL 1047.

2. The panel manufacturer shall provide certified test data on each individual panel as to maximum leakage of each complete assembly.
3. Wire all external receptacles to the panels using copper stranded conductor having a cross-linked polyethylene insulation or equivalent with a dielectric constant of 3.5 or less. Under no circumstances shall wire pulling compound be used when pulling the wire for isolated circuits. All wiring shall be color-coded in accordance with NEC and appropriate NFPA standards.
- 4.

## 2.6 ACCESSORY COMPONENTS AND FEATURES

- A. Accessory Set: Include tools and miscellaneous items required for overcurrent protective device test, inspection, maintenance, and operation.
- B. Portable Test Set: For testing functions of solid-state trip devices without removing from panelboard. Include relay and meter test plugs suitable for testing panelboard meters and switchboard class relays.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Receive, inspect, handle, and store panelboards according to NEMA PB 1.1.
- B. Examine panelboards before installation. Reject panelboards that are damaged or rusted or have been subjected to water saturation.
- C. Examine elements and surfaces to receive panelboards for compliance with installation tolerances and other conditions affecting performance of the Work.
- D. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Install panelboards and accessories according to NEMA PB 1.1.
- B. Equipment Mounting: Install panelboards on concrete bases, 4-inch (100-mm) nominal thickness. Comply with requirements for concrete base specified in Section 033053 "Miscellaneous Cast-in-Place Concrete."
  1. Install dowel rods to connect concrete base to concrete floor. Unless otherwise indicated, install dowel rods on 18-inch (450-mm) centers around full perimeter of base.
  2. For panelboards, install epoxy-coated anchor bolts that extend through concrete base and anchor into structural concrete floor.
  3. Place and secure anchorage devices. Use setting drawings, templates, diagrams, instructions, and directions furnished with items to be embedded.
  4. Install anchor bolts to elevations required for proper attachment to panelboards.
  5. Attach panelboard to the vertical finished or structural surface behind the panelboard.

- C. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from panelboards.
- D. Comply with mounting and anchoring requirements specified in Section 260548 "Vibration and Seismic Controls for Electrical Systems."
- E. Mount top of trim **90 inches (2286 mm)** above finished floor unless otherwise indicated.
- F. Mount panelboard cabinet plumb and rigid without distortion of box. Mount recessed panelboards with fronts uniformly flush with wall finish and mating with back box.
- G. Install overcurrent protective devices and controllers not already factory installed.
  - 1. Set field-adjustable, circuit-breaker trip ranges.
- H. Install filler plates in unused spaces.
- I. Stub four **1-inch (27-GRC)** empty conduits from panelboard into accessible ceiling space or space designated to be ceiling space in the future. Stub four **1-inch (27-GRC)** empty conduits into raised floor space or below slab not on grade.
- J. Arrange conductors in gutters into groups and bundle and wrap with wire ties after completing load balancing.
- K. Comply with NECA 1.

### 3.3 IDENTIFICATION

- A. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs complying with Section 260553 "Identification for Electrical Systems."
- B. Create a directory to indicate installed circuit loads after balancing panelboard loads; incorporate Owner's final room designations. Obtain approval before installing. Use a computer or typewriter to create directory; handwritten directories are not acceptable.
- C. Panelboard Nameplates: Label each panelboard with a nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."
- D. Device Nameplates: Label each branch circuit device in distribution panelboards with a nameplate complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems."

### 3.4 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
  - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- B. Acceptance Testing Preparation:

1. Test insulation resistance for each panelboard bus, component, connecting supply, feeder, and control circuit.
2. Test continuity of each circuit.

C. Tests and Inspections:

1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
3. Perform the following infrared scan tests and inspections and prepare reports:
  - a. Initial Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each panelboard. Remove front panels so joints and connections are accessible to portable scanner.
  - b. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each panelboard 11 months after date of Substantial Completion.
  - c. Instruments and Equipment:
    - 1) Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.

D. Panelboards will be considered defective if they do not pass tests and inspections.

E. Prepare test and inspection reports, including a certified report that identifies panelboards included and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.

### 3.5 ADJUSTING

- A. Adjust moving parts and operable component to function smoothly, and lubricate as recommended by manufacturer.
- B. Set field-adjustable circuit-breaker trip ranges as specified in Section 260573 "Overcurrent Protective Device Coordination Study."
- C. Load Balancing: After Substantial Completion, but not more than 60 days after Final Acceptance, measure load balancing and make circuit changes.
  1. Measure as directed during period of normal system loading.
  2. Perform load-balancing circuit changes outside normal occupancy/working schedule of the facility and at time directed. Avoid disrupting critical 24-hour services such as fax machines and on-line data processing, computing, transmitting, and receiving equipment.
  3. After circuit changes, recheck loads during normal load period. Record all load readings before and after changes and submit test records.
  4. Tolerance: Difference exceeding 20 percent between phase loads, within a panelboard, is not acceptable. Rebalance and recheck as necessary to meet this minimum requirement.

**END OF SECTION 262416**



## **SECTION 262726 - WIRING DEVICES**

### **PART 1 -**

### **PART 2 - GENERAL**

#### **2.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **2.2 SUMMARY**

- A. Section Includes:
  - 1. Receptacles, receptacles with integral GFCI, and associated device plates.
  - 2. Snap switches and wall-box dimmers.
  - 3. Wall-switch and exterior occupancy sensors.
  - 4. Floor service outlets, poke-through assemblies, service poles, and multioutlet assemblies.

#### **2.3 DEFINITIONS**

- A. EMI: Electromagnetic interference.
- B. GFCI: Ground-fault circuit interrupter.
- C. Pigtail: Short lead used to connect a device to a branch-circuit conductor.
- D. RFI: Radio-frequency interference.
- E. TVSS: Transient voltage surge suppressor.
- F. UTP: Unshielded twisted pair.

#### **2.4 ADMINISTRATIVE REQUIREMENTS**

- A. Coordination:
  - 1. Receptacles for Owner-Furnished Equipment: Match plug configurations.
  - 2. Cord and Plug Sets: Match equipment requirements.

#### **2.5 ACTION SUBMITTALS**

- A. Product Data: For each type of product.
- B. Shop Drawings: List of legends and description of materials and process used for premarking wall plates.
- C. Samples: One for each type of device and wall plate specified, in each color specified.



## 2.6 INFORMATIONAL SUBMITTALS

- A. Field quality-control reports.

## 2.7 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For wiring devices to include in all manufacturers' packing-label warnings and instruction manuals that include labeling conditions.

## PART 3 - PRODUCTS

### 3.1 MANUFACTURERS

- A. Manufacturers' Names: Shortened versions (shown in parentheses) of the following manufacturers' names are used in other Part 2 articles:
  - 1. Pass & Seymour/Legrand (Pass & Seymour).
- B. Source Limitations: Obtain each type of wiring device and associated wall plate from single source from single manufacturer.

### 3.2 GENERAL WIRING-DEVICE REQUIREMENTS

- A. Wiring Devices, Components, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NFPA 70.
- C. Use electrical devices with modular plug-in connectors which meet the following requirements:
  - 1. Connectors shall comply with UL 2459 and shall be made with stranding building wire.
  - 2. Devices shall comply with the requirements in this Section.

### 3.3 STRAIGHT-BLADE RECEPTACLES

- A. Convenience Receptacles, 125 V, 20 A: Comply with NEMA WD 1, NEMA WD 6 Configuration 5-20R, UL 498, and FS W-C-596.
  - a.
- B. Hospital grade Convenience Receptacles, 125 V, 20 A: Comply with NEMA WD 1, NEMA WD 6 Configuration 5-20R, UL 498 Supplement sd, and FS W-C-596.
  - 1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Pass & Seymour; TR63H (Plugtail).
    - b.
  - 2. Description: Labeled shall comply with NFPA 70, "Health Care Facilities" Article, "Pediatric Locations" Section.

### 3.4 GFCI RECEPTACLES

- A. General Description:

1. Straight blade, non-feed-through type hospital grade.
2. Comply with NEMA WD 1, NEMA WD 6, UL 498, UL 943 Class A, and FS W-C-596.
3. Include indicator light that shows when the GFCI has malfunctioned and no longer provides proper GFCI protection.

### 3.5 TWIST-LOCKING RECEPTACLES

- A. Single Convenience Receptacles, 125 V, 20 A: Comply with NEMA WD 1, NEMA WD 6 Configuration L5-20R, and UL 498.
  1. Products: Subject to compliance with requirements, provide one of the following:
    - a. Cooper; CWL520R.
    - b. Hubbell; HBL2310.
    - c. Leviton; 2310.
    - d. Pass & Seymour; L520-R.

### 3.6 TOGGLE SWITCHES

- A. Comply with NEMA WD 1, UL 20, and FS W-S-896.
- B. Switches, 120/277 V, 20 A:
  1. Products: Subject to compliance with requirements, provide one of the following:
    - 1) Single Pole:
    - 2) Pass & Seymour(Plugtail); CSB20AC1.
    - 3) Three Way:
    - 4) Pass & Seymour(Plugtail); CSB20AC3.
    - 5) Four Way:
    - 6) Pass & Seymour(Plugtail); CSB20AC4.
    - 7)

### 3.7 WALL-BOX DIMMERS

- A. Dimmer Switches: Modular, full-wave, solid-state units with integral, quiet on-off switches, with audible frequency and EMI/RFI suppression filters.
- B. Control: Continuously adjustable slider; with single-pole or three-way switching. Comply with UL 1472.
- C. Fluorescent Lamp Dimmer Switches: Modular; compatible with dimmer ballasts; trim potentiometer to adjust low-end dimming; dimmer-ballast combination capable of consistent dimming with low end not greater than 20 percent of full brightness.

### 3.8 WALL PLATES

- A. Single and combination types shall match corresponding wiring devices.
  1. Plate-Securing Screws: Metal with head color to match plate finish.
  2. Material for Finished Spaces: Smooth, high-impact thermoplastic.
  3. Material for Unfinished Spaces: Smooth, high-impact thermoplastic.
  4. Material for Damp Locations: Cast aluminum with spring-loaded lift cover, and listed and labeled for use in wet and damp locations.

- B. Wet-Location, Weatherproof Cover Plates: NEMA 250, complying with Type 3R, weather-resistant, die-cast aluminum with lockable cover.

### 3.9 FLOOR SERVICE FITTINGS

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:
1. Wiremold / Legrand.
  2. Hubbell
- B. Type: Modular, flush-type, dual- or multi- service units suitable for wiring method used.
- C. Compartments: Barrier separates power from voice and data communication cabling.
- D. Service Plate: Round, die-cast aluminum with satin finish.
- E. Power Receptacle: NEMA WD 6 Configuration 5-20R, gray finish, unless otherwise indicated.
- F. Voice and Data Communication Outlet: Two modular, keyed, color-coded, RJ-45 jacks for UTP cable complying with requirements in owner's Section 27 00 00 requirements.
- G. Description by Device Type:

H.

|      |                                                                                                                                                                                                                                                              |                                                          |
|------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------------------|
| FB1  | Flush, Dual Service, Furniture Feed. One .75" conduit for power and One 2" conduit for data cabling. See plans for circuits and data drops. Finish selected by architect.                                                                                    | Legrand EFBFF<br>Hubbell<br>CFB2G30/2GCFFCVR             |
| FB4  | Flush, Dual Service, one piece finish flange. Four gang capacity. One .75" conduit for power and one 2" conduit for data cabling. See plans for circuits and data drops. Finish selected by architect.                                                       | Legrand EFG45S<br>Hubbell<br>CFB2G30/24GCCVR             |
| FB6  | Flush, Dual Service, one piece finish flange. Six gang capacity. One .75" conduit for power and one 2" conduit for data cabling. See plans for circuits and data drops. Finish selected by architect.                                                        | Legrand EFB6S Evolution<br>Hubbell<br>CFB6G30/610GCCVR   |
| FB8  | Flush, Dual Service, one piece finish flange. Eight gang capacity. One .75" conduit for power and one 2" conduit for data cabling. See plans for circuits and data drops. Finish selected by architect.                                                      | Legrand EFB8S Evolution                                  |
| FB10 | Flush, Dual Service, one piece finish flange. Ten gang capacity. One .75" conduit for power and one 2" conduit for data cabling. See plans for circuits and data drops. Finish selected by architect.                                                        | Legrand EFB10S Evolution<br>Hubbell<br>CFB10G30/610GCCVR |
| FB11 | Flush single service floor box suitable for the wiring method used. NEMA 5-20R duplex receptacle with brushed aluminum flange and cover plate. Hinged receptacle covers. Housing material shall be stamped steel above grade and cast iron at grade. Provide | Legrand<br>880MS(CS)/817/828<br>Hubbell B2431/S3825      |

|  |                                      |  |
|--|--------------------------------------|--|
|  | appropriate carpet and tile flanges. |  |
|--|--------------------------------------|--|

### 3.10 POKE-THROUGH ASSEMBLIES

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:

1. Wiremold / Legrand.

- B. Description:

1. Factory-fabricated and -wired assembly of below-floor junction box with multichanneled, through-floor raceway/firestop unit and detachable matching floor service-outlet assembly.
2. Comply with UL 514 scrub water exclusion requirements.
3. Size: Selected to fit cored holes in floor and matched to floor thickness.
4. Fire Rating: Unit is listed and labeled for fire rating of floor-ceiling assembly.
5. Closure Plug: Arranged to close unused cored openings and reestablish fire rating of floor.

- C. Description by Device Type:

- D.

|      |                                                                                                                                                                                                                                              |                                              |
|------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|----------------------------------------------|
| PT1  | Flush, Dual Service, 4" Diameter Furniture Feed Poke-Thru. One piece finish flange. One .75" conduit for power, One 1.5" conduit for data cabling. See plans for circuits and data drops. Finish selected by architect.                      | Legrand 4FFATC<br>Hubbell<br>PT73FFS/FRF3    |
| PT2  | Flush, Dual Service Capable, 4"Diameter Poke-Thru. One .75" conduit for power, one 1.5" conduit for data cabling. Two Gang Capacity. See plans for circuits and data drops. Receptacles shall be NEMA 5-20R, Finish selected by architect.   | Legrand 4AT<br>Evolution<br>Hubbell S1R4PT   |
| PT3  | Flush, Dual Service Capable, 6"Diameter Poke-Thru. One .75" conduit for power, one 1.5" conduit for data cabling. Three Gang Capacity. See plans for circuits and data drops. Receptacles shall be NEMA 5-20R, Finish selected by architect. | Legrand 6AT<br>Evolution<br>Hubbell S1R6PT   |
| PT8  | Flush, Dual Service Capable, 8"Diameter Poke-Thru. One .75" conduit for power, one 2" conduit for data cabling. Five Gang Capacity. See plans for circuits and data drops. Receptacles shall be NEMA 5-20R, Finish selected by architect.    | Legrand 8AT<br>Evolution<br>Hubbell S1R8PT   |
| PT10 | Flush, Dual Service Capable, 10"Diameter Poke-Thru. One .75" conduit for power, one 2" conduit for data cabling. Eight Gang Capacity. See plans for circuits and data drops. Receptacles shall be NEMA 5-20R, Finish selected by architect.  | Legrand 10AT<br>Evolution<br>Hubbell S1R10PT |
| PT11 | Flush single service floor box suitable for the wiring method used. NEMA 5-20R duplex receptacle with brushed aluminum flange and cover plate. Hinged receptacle covers.                                                                     | Legrand RC7CTC<br>Hubbell<br>PT7FS/FRF       |

### 3.11 FINISHES

- A. Device Color:
  - 1. Wiring Devices Connected to Normal Power System: White unless otherwise indicated or required by NFPA 70 or device listing.
  - 2. Wiring Devices Connected to Emergency Power System: Red.
  - 3. TVSS Devices: Blue.
- B. Wall Plate Color: For plastic covers, match device color.

## PART 4 - EXECUTION

### 4.1 INSTALLATION

- A. Comply with NECA 1, including mounting heights listed in that standard, unless otherwise indicated.
- B. Coordination with Other Trades:
  - 1. Protect installed devices and their boxes. Do not place wall finish materials over device boxes and do not cut holes for boxes with routers that are guided by riding against outside of boxes.
  - 2. Keep outlet boxes free of plaster, drywall joint compound, mortar, cement, concrete, dust, paint, and other material that may contaminate the raceway system, conductors, and cables.
  - 3. Install device boxes in brick or block walls so that the cover plate does not cross a joint unless the joint is troweled flush with the face of the wall.
  - 4. Install wiring devices after all wall preparation, including painting, is complete.
- C. Conductors:
  - 1. Do not strip insulation from conductors until right before they are spliced or terminated on devices.
  - 2. Strip insulation evenly around the conductor using tools designed for the purpose. Avoid scoring or nicking of solid wire or cutting strands from stranded wire.
  - 3. The length of free conductors at outlets for devices shall meet provisions of NFPA 70, Article 300, without pigtails.
  - 4. Existing Conductors:
    - a. Cut back and pigtail, or replace all damaged conductors.
    - b. Straighten conductors that remain and remove corrosion and foreign matter.
    - c. Pigtail existing conductors is permitted, provided the outlet box is large enough.
- D. Device Installation:
  - 1. Replace devices that have been in temporary use during construction and that were installed before building finishing operations were complete.
  - 2. Keep each wiring device in its package or otherwise protected until it is time to connect conductors.
  - 3. All receptacles must be hospital grade.

4. Do not remove surface protection, such as plastic film and smudge covers, until the last possible moment.
  5. Connect devices to branch circuits using pigtails that are not less than 6 inches (152 mm) in length.
  6. When there is a choice, use side wiring with binding-head screw terminals. Wrap solid conductor tightly clockwise, two-thirds to three-fourths of the way around terminal screw.
  7. Use a torque screwdriver when a torque is recommended or required by manufacturer.
  8. When conductors larger than No. 12 AWG are installed on 15- or 20-A circuits, splice No. 12 AWG pigtails for device connections.
  9. Tighten unused terminal screws on the device.
  10. When mounting into metal boxes, remove the fiber or plastic washers used to hold device-mounting screws in yokes, allowing metal-to-metal contact.
- E. Receptacle Orientation:
1. Install ground pin of vertically mounted receptacles down, and on horizontally mounted receptacles to the right.
  2. Install hospital-grade receptacles in patient-care areas with the ground pin or neutral blade at the top.
- F. Device Plates: Do not use oversized or extra-deep plates. Repair wall finishes and remount outlet boxes when standard device plates do not fit flush or do not cover rough wall opening.
- G. Dimmers:
1. Install dimmers within terms of their listing.
  2. Verify that dimmers used for fan speed control are listed for that application.
  3. Install unshared neutral conductors on line and load side of dimmers according to manufacturers' device listing conditions in the written instructions.
- H. Arrangement of Devices: Unless otherwise indicated, mount flush, with long dimension vertical and with grounding terminal of receptacles on top. Group adjacent switches under single, multigang wall plates.
- I. Adjust locations of floor service outlets and service poles to suit arrangement of partitions and furnishings.
- #### 4.2 GFCI RECEPTACLES
- A. Install non-feed-through-type GFCI receptacles where protection of downstream receptacles is not required.
- #### 4.3 IDENTIFICATION
- A. Comply with Section 260553 "Identification for Electrical Systems."
- B. Identify each receptacle with panelboard identification and circuit number. Use hot, stamped, or engraved machine printing with black-filled lettering on face of plate, and durable wire markers or tags inside outlet boxes.

#### 4.4 FIELD QUALITY CONTROL

- A. Perform the following tests and inspections:
  - 1. In healthcare facilities, prepare reports that comply with recommendations in NFPA 99.
  - 2. Test Instruments: Use instruments that comply with UL 1436.
  - 3. Test Instrument for Convenience Receptacles: Digital wiring analyzer with digital readout or illuminated digital-display indicators of measurement.
- B. Tests for Convenience Receptacles:
  - 1. Line Voltage: Acceptable range is 105 to 132 V.
  - 2. Percent Voltage Drop under 15-A Load: A value of 6 percent or higher is unacceptable.
  - 3. Ground Impedance: Values of up to 2 ohms are acceptable.
  - 4. GFCI Trip: Test for tripping values specified in UL 1436 and UL 943.
  - 5. Using the test plug, verify that the device and its outlet box are securely mounted.
  - 6. Tests shall be diagnostic, indicating damaged conductors, high resistance at the circuit breaker, poor connections, inadequate fault current path, defective devices, or similar problems. Correct circuit conditions, remove malfunctioning units and replace with new ones, and retest as specified above.
- C. Test straight-blade convenience outlets in patient-care areas for the retention force of the grounding blade according to NFPA 99. Retention force shall be not less than 4 oz. (115 g).
- D. Wiring device will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

**END OF SECTION 262726**

## **SECTION 262813 – FUSES**

### **PART 1 -**

### **PART 2 - GENERAL**

#### **2.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **2.2 SUMMARY**

- A. Section Includes:
  - 1. Cartridge fuses rated 600-V ac and less for use in enclosed switches, panelboards and enclosed controllers.,
  - 2. Spare-fuse cabinets.

#### **2.3 ACTION SUBMITTALS**

- A. Product Data: For each type of product indicated. Include construction details, material, dimensions, descriptions of individual components, and finishes for spare-fuse cabinets. Include the following for each fuse type indicated:
  - 1. Ambient Temperature Adjustment Information: If ratings of fuses have been adjusted to accommodate ambient temperatures, provide list of fuses with adjusted ratings.
    - a. For each fuse having adjusted ratings, include location of fuse, original fuse rating, local ambient temperature, and adjusted fuse rating.
    - b. Provide manufacturer's technical data on which ambient temperature adjustment calculations are based.
  - 2. Dimensions and manufacturer's technical data on features, performance, electrical characteristics, and ratings.
  - 3. Fuse sizes for elevator feeders and elevator disconnect switches.

#### **2.4 CLOSEOUT SUBMITTALS**

- A. Operation and Maintenance Data: For fuses to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
  - 1. Ambient temperature adjustment information.
  - 2. Coordination charts and tables and related data.

#### **2.5 MAINTENANCE MATERIAL SUBMITTALS**

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Fuses: Equal to 10 percent of quantity installed for each size and type, but no fewer than three of each size and type.



## 2.6 QUALITY ASSURANCE

- A. Source Limitations: Obtain fuses, for use within a specific product or circuit, from single source from single manufacturer.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. Comply with NEMA FU 1 for cartridge fuses.
- D. Comply with NFPA 70.
- E. Comply with UL 248-11 for plug fuses.

## 2.7 PROJECT CONDITIONS

- A. Where ambient temperature to which fuses are directly exposed is less than 40 deg F (5 deg C) or more than 100 deg F (38 deg C), apply manufacturer's ambient temperature adjustment factors to fuse ratings.

## 2.8 COORDINATION

- A. Coordinate fuse ratings with utilization equipment nameplate limitations of maximum fuse size and with system short-circuit current levels.

# PART 3 - PRODUCTS

## 3.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Cooper Bussmann, Inc.
  - 2. Edison Fuse, Inc.
  - 3. Ferraz Shawmut, Inc.
  - 4. Littelfuse, Inc.
  - 5.

## 3.2 CARTRIDGE FUSES

- A. Characteristics: NEMA FU 1, nonrenewable cartridge fuses with voltage ratings consistent with circuit voltages.

## 3.3 PLUG FUSES

- A. Characteristics: UL 248-11, nonrenewable plug fuses; 125-V ac.

## 3.4 PLUG-FUSE ADAPTERS

- A. Characteristics: Adapters for using Type S, rejection-base plug fuses in Edison-base fuseholders or sockets; ampere ratings matching fuse ratings; irremovable once installed.

### 3.5 SPARE-FUSE CABINET

- A. Characteristics: Wall-mounted steel unit with full-length, recessed piano-hinged door and key-coded cam lock and pull.
  - 1. Size: Adequate for storage of spare fuses specified with 15 percent spare capacity minimum.
  - 2. Finish: Gray, baked enamel.
  - 3. Identification: "SPARE FUSES" in 1-1/2-inch- (38-mm-) high letters on exterior of door.
  - 4. Fuse Pullers: For each size of fuse, where applicable and available, from fuse manufacturer.

## PART 4 - EXECUTION

### 4.1 EXAMINATION

- A. Examine fuses before installation. Reject fuses that are moisture damaged or physically damaged.
- B. Examine holders to receive fuses for compliance with installation tolerances and other conditions affecting performance, such as rejection features.
- C. Examine utilization equipment nameplates and installation instructions. Install fuses of sizes and with characteristics appropriate for each piece of equipment.
- D. Evaluate ambient temperatures to determine if fuse rating adjustment factors must be applied to fuse ratings.
- E. Proceed with installation only after unsatisfactory conditions have been corrected.

### 4.2 FUSE APPLICATIONS

- A. Cartridge Fuses:
  - 1. Feeders: Class J, time delay.

### 4.3 INSTALLATION

- A. Install fuses in fusible devices. Arrange fuses so rating information is readable without removing fuse.
- B. Install spare-fuse cabinet(s).

### 4.4 IDENTIFICATION

- A. Install labels complying with requirements for identification specified in Section 260553 "Identification for Electrical Systems" and indicating fuse replacement information on inside door of each fused switch and adjacent to each fuse block, socket, and holder.

## END OF SECTION 262813

ACC LEVEL 3 OR EXPANSION REMODEL  
University of Utah  
Salt Lake City, Utah 84104

Code Review

## **SECTION 262816 - ENCLOSED SWITCHES AND CIRCUIT BREAKERS**

### **PART 1 -**

### **PART 2 - GENERAL**

#### **2.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 01 Specification Sections, apply to this Section.

#### **2.2 SUMMARY**

- A. Section Includes:
  - 1. Fusible switches.
  - 2. Nonfusible switches.
  - 3. Receptacle switches.
  - 4. Shunt trip switches.
  - 5. Molded-case circuit breakers (MCCBs).
  - 6. Molded-case switches.
  - 7. Enclosures.

#### **2.3 DEFINITIONS**

- A. NC: Normally closed.
- B. NO: Normally open.
- C. SPDT: Single pole, double throw.

#### **2.4 PERFORMANCE REQUIREMENTS**

- A. Seismic Performance: Enclosed switches and circuit breakers shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
  - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified."

#### **2.5 ACTION SUBMITTALS**

- A. Product Data: For each type of enclosed switch, circuit breaker, accessory, and component indicated. Include dimensioned elevations, sections, weights, and manufacturers' technical data on features, performance, electrical characteristics, ratings, accessories, and finishes.
  - 1. Enclosure types and details for types other than NEMA 250, Type 1.
  - 2. Current and voltage ratings.
  - 3. Short-circuit current ratings (interrupting and withstand, as appropriate).
  - 4. Include evidence of NRTL listing for series rating of installed devices.
  - 5. Detail features, characteristics, ratings, and factory settings of individual overcurrent protective devices, accessories, and auxiliary components.

6. Include time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device.

- B. Shop Drawings: For enclosed switches and circuit breakers. Include plans, elevations, sections, details, and attachments to other work.
  1. Wiring Diagrams: For power, signal, and control wiring.

## 2.6 INFORMATIONAL SUBMITTALS

- A. Qualification Data: For qualified testing agency.
- B. Seismic Qualification Certificates: For enclosed switches and circuit breakers, accessories, and components, from manufacturer.
  1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- C. Field quality-control reports.
  1. Test procedures used.
  2. Test results that comply with requirements.
  3. Results of failed tests and corrective action taken to achieve test results that comply with requirements.
- D. Manufacturer's field service report.

## 2.7 CLOSEOUT SUBMITTALS

- A. Operation and Maintenance Data: For enclosed switches and circuit breakers to include in emergency, operation, and maintenance manuals. In addition to items specified in Section 017823 "Operation and Maintenance Data," include the following:
  1. Manufacturer's written instructions for testing and adjusting enclosed switches and circuit breakers.
  2. Time-current coordination curves (average melt) for each type and rating of overcurrent protective device; include selectable ranges for each type of overcurrent protective device.

## 2.8 QUALITY ASSURANCE

- A. Testing Agency Qualifications: Member company of NETA or an NRTL.
  1. Testing Agency's Field Supervisor: Currently certified by NETA to supervise on-site testing.
- B. Source Limitations: Obtain enclosed switches and circuit breakers, overcurrent protective devices, components, and accessories, within same product category, from single source from single manufacturer.

- C. Product Selection for Restricted Space: Drawings indicate maximum dimensions for enclosed switches and circuit breakers, including clearances between enclosures, and adjacent surfaces and other items. Comply with indicated maximum dimensions.
- D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- E. Comply with NFPA 70.

## 2.9 PROJECT CONDITIONS

- A. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:
  - 1. Ambient Temperature: Not less than **minus 22 deg F (minus 30 deg C)** and not exceeding **104 deg F (40 deg C)**.
  - 2. Altitude: Not exceeding **6600 feet (2010 m)**.

## 2.10 COORDINATION

- A. Coordinate layout and installation of switches, circuit breakers, and components with equipment served and adjacent surfaces. Maintain required workspace clearances and required clearances for equipment access doors and panels.

## PART 3 - PRODUCTS

### 3.1 FUSIBLE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. **Eaton Electrical Inc.; Cutler-Hammer Business Unit.**
  - 2. **General Electric Company; GE Consumer & Industrial - Electrical Distribution.**
  - 3. **Siemens Energy & Automation, Inc.**
  - 4. **Square D; a brand of Schneider Electric.**
- B.
- C. Type HD, Heavy Duty, Single Throw, 240 and 600-V ac, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, with clips or bolt pads to accommodate indicated fuses, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.
- D. Accessories:
  - 1. Equipment Ground Kit: Internally mounted and labeled for copper and aluminum ground conductors.
  - 2. Neutral Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.
  - 3. Isolated Ground Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.
  - 4. Class R Fuse Kit: Provides rejection of other fuse types when Class R fuses are specified.

### 3.2 NONFUSIBLE SWITCHES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
  - 2. General Electric Company; GE Consumer & Industrial - Electrical Distribution.
  - 3. Siemens Energy & Automation, Inc.
  - 4. Square D; a brand of Schneider Electric.
- B. Type HD, Heavy Duty, Single Throw, 240 and 600-V ac, 1200 A and Smaller: UL 98 and NEMA KS 1, horsepower rated, lockable handle with capability to accept three padlocks, and interlocked with cover in closed position.
- C. Accessories:
  - 1. Equipment Ground Kit: Internally mounted and labeled for copper and aluminum ground conductors.
  - 2. Neutral Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.
  - 3. Isolated Ground Kit: Internally mounted; insulated, capable of being grounded and bonded; labeled for copper and aluminum neutral conductors.

### 3.3 MOLDED-CASE CIRCUIT BREAKERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Eaton Electrical Inc.; Cutler-Hammer Business Unit.
  - 2. General Electric Company; GE Consumer & Industrial - Electrical Distribution.
  - 3. Siemens Energy & Automation, Inc.
  - 4. Square D; a brand of Schneider Electric.
- B. General Requirements: Comply with UL 489, NEMA AB 1, and NEMA AB 3, with interrupting capacity to comply with available fault currents.
- C. Thermal-Magnetic Circuit Breakers: Inverse time-current element for low-level overloads and instantaneous magnetic trip element for short circuits. Adjustable magnetic trip setting for circuit-breaker frame sizes 250 A and larger.
- D. Adjustable, Instantaneous-Trip Circuit Breakers: Magnetic trip element with front-mounted, field-adjustable trip setting.
- E. Electronic Trip Circuit Breakers: Field-replaceable rating plug, rms sensing, with the following field-adjustable settings:
  - 1. Instantaneous trip.
  - 2. Long- and short-time pickup levels.
  - 3. Long- and short-time time adjustments.
  - 4. Ground-fault pickup level, time delay, and  $I^2t$  response.
- F. Features and Accessories:
  - 1. Standard frame sizes, trip ratings, and number of poles.

2. Lugs: Mechanical type, suitable for number, size, trip ratings, and conductor material.
3. Application Listing: Appropriate for application; Type SWD for switching fluorescent lighting loads; Type HID for feeding fluorescent and high-intensity discharge lighting circuits.

### 3.4 ENCLOSURES

- A. Enclosed Switches and Circuit Breakers: NEMA AB 1, NEMA KS 1, NEMA 250, and UL 50, to comply with environmental conditions at installed location.
  1. Indoor, Dry and Clean Locations: NEMA 250, Type 1.
    - a. Flush mount in radiology imaging rooms.
  2. Outdoor Locations: NEMA 250, Type 3R.

## PART 4 - EXECUTION

### 4.1 EXAMINATION

- A. Examine elements and surfaces to receive enclosed switches and circuit breakers for compliance with installation tolerances and other conditions affecting performance of the Work.
- B. Proceed with installation only after unsatisfactory conditions have been corrected.

### 4.2 INSTALLATION

- A. Install individual wall-mounted switches and circuit breakers with tops at uniform height unless otherwise indicated.
- B. Comply with mounting and anchoring requirements specified in Section 260548 "Vibration and Seismic Controls for Electrical Systems."
- C. Temporary Lifting Provisions: Remove temporary lifting eyes, channels, and brackets and temporary blocking of moving parts from enclosures and components.
- D. Install fuses in fusible devices.
- E. Comply with NECA 1.

### 4.3 IDENTIFICATION

- A. Comply with requirements in Section 260553 "Identification for Electrical Systems."
  1. Identify field-installed conductors, interconnecting wiring, and components; provide warning signs.
  2. Label each enclosure with engraved metal or laminated-plastic nameplate.

### 4.4 FIELD QUALITY CONTROL

- A. Perform tests and inspections.



1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
  - B. Acceptance Testing Preparation:
    1. Test insulation resistance for each enclosed switch and circuit breaker, component, connecting supply, feeder, and control circuit.
    2. Test continuity of each circuit.
  - C. Tests and Inspections:
    1. Perform each visual and mechanical inspection and electrical test stated in NETA Acceptance Testing Specification. Certify compliance with test parameters.
    2. Correct malfunctioning units on-site, where possible, and retest to demonstrate compliance; otherwise, replace with new units and retest.
    3. Perform the following infrared scan tests and inspections and prepare reports:
      - a. Initial Infrared Scanning: After Substantial Completion, but not more than 60 days after Final Acceptance, perform an infrared scan of each enclosed switch and circuit breaker. Remove front panels so joints and connections are accessible to portable scanner.
      - b. Follow-up Infrared Scanning: Perform an additional follow-up infrared scan of each enclosed switch and circuit breaker 11 months after date of Substantial Completion.
      - c. Instruments and Equipment: Use an infrared scanning device designed to measure temperature or to detect significant deviations from normal values. Provide calibration record for device.
    4. Test and adjust controls, remote monitoring, and safeties. Replace damaged and malfunctioning controls and equipment.
  - D. Enclosed switches and circuit breakers will be considered defective if they do not pass tests and inspections.
  - E. Prepare test and inspection reports, including a certified report that identifies enclosed switches and circuit breakers and that describes scanning results. Include notation of deficiencies detected, remedial action taken, and observations after remedial action.
- 4.5 ADJUSTING
- A. Adjust moving parts and operable components to function smoothly, and lubricate as recommended by manufacturer.
  - B. Set field-adjustable circuit-breaker trip ranges as specified in Section 260573 "Overcurrent Protective Device Coordination Study."

**END OF SECTION 262816**

## **SECTION 265119 - LED INTERIOR LIGHTING**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. Section Includes:
  - 1. Interior solid-state luminaires that use LED technology.
  - 2. Lighting fixture supports.
  - 3. Standby Emergency Power supplies for individual luminaires
- B. Related Requirements:
  - 1. Section 26 09 23 "Lighting Control Devices" for automatic control of lighting, including time switches, photoelectric relays, occupancy sensors, and multipole lighting relays and contactors.
  - 2. Section 26 09 36 "Standalone Multipreset Modular Dimming Controls" for architectural dimming systems and for fluorescent dimming controls with dimming ballasts specified in interior lighting Sections.
  - 3. Section 26 09 43 "Relay-Based Lighting Controls" for manual or programmable control systems with low-voltage control wiring or data communication circuits.

#### **1.3 DEFINITIONS**

- A. CCT: Correlated color temperature.
- B. CRI: Color Rendering Index.
- C. Fixture: See "Luminaire."
- D. IP: International Protection or Ingress Protection Rating.
- E. LED: Light-emitting diode.
- F. Lumen: Measured output of lamp and luminaire, or both.
- G. Luminaire: Complete lighting unit, including lamp, reflector, and housing.

## 1.4 ACTION SUBMITTALS

- A. Product Data: For each type of product.
  - 1. Arrange in order of luminaire designation.
  - 2. Include data on features, accessories, and finishes.
  - 3. Include physical description and dimensions of luminaires.
  - 4. Include emergency lighting units, including batteries and chargers.
  - 5. Include life, output (lumens, CCT, and CRI), and energy efficiency data.
  - 6. Photometric data and adjustment factors based on laboratory tests, complying with IESNA Lighting Measurements Testing and Calculation Guides, of each lighting fixture type. The adjustment factors shall be for lamps and accessories identical to those indicated for the lighting fixture as applied in this Project. Report data compliant with IES LM-79 and IES LM-80. Only Absolute Photometry is acceptable.
    - a. Manufacturers' Certified Data: Photometric data certified by manufacturer's laboratory with a current accreditation under the National Voluntary Laboratory Accreditation Program for Energy Efficient Lighting Products (NVLAP).
- B. Shop Drawings: For nonstandard or custom luminaires.
  - 1. Include plans, elevations, sections, and mounting and attachment details.
  - 2. Include details of luminaire assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  - 3. Include diagrams for power, signal, and control wiring.
- C. LEED Submittals:
  - 1. Product Data for Credit IEQ 4.2: For paints and coatings, documentation including printed statement of VOC content.
  - 2. Laboratory Test Reports for Credit IEQ 4.2: For paints and coatings, documentation indicating that products comply with the testing and product requirements of the California Department of Public Health's "Standard Method for the Testing and Evaluation of Volatile Organic Chemical Emissions from Indoor Sources Using Environmental Chambers."
- D. Samples: For each luminaire and for each color and texture with standard factory-applied finish.
- E. Samples for Initial Selection: For each type of luminaire with custom factory-applied finishes.
  - 1. Include Samples of luminaires and accessories involving color and finish selection.
- F. Samples for Verification: For each type of luminaire.
  - 1. Include Samples of luminaires and accessories to verify finish selection.
- G. Product Schedule: For luminaires and lamps. Use same designations indicated on Drawings.

## **1.5 INFORMATIONAL SUBMITTALS**

- A. Coordination Drawings: Reflected ceiling plan(s) and other details, drawn to scale, on which the following items are shown and coordinated with each other, using input from installers of the items involved:
  - 1. Lighting luminaires.
  - 2. Suspended ceiling components.
  - 3. Partitions and millwork that penetrate the ceiling or extend to within 12 inches (300 mm) of the plane of the luminaires.
  - 4. Structural members to which equipment and or luminaires will be attached.
  - 5. Initial access modules for acoustical tile, including size and locations.
  - 6. Items penetrating finished ceiling, including the following:
    - a. Other luminaires.
    - b. Air outlets and inlets.
    - c. Speakers.
    - d. Sprinklers.
    - e. Access panels.
    - f. Ceiling-mounted projectors.
    - g.
  - 7. Moldings.
- B. Qualification Data: For testing laboratory providing photometric data for luminaires.
- C. Seismic Qualification Certificates: For luminaires, accessories, and components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
- D. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- E. Product Certificates: For each type of luminaire.
- F. Product Test Reports: For each luminaire, for tests performed by manufacturer or a qualified testing agency holding NVLAP accreditation.
- G. Sample warranty.

## **1.6 CLOSEOUT SUBMITTALS**

- A. Operation and Maintenance Data: For luminaires and lighting systems to include in operation and maintenance manuals.
  - 1. Provide a list of all lamp types LED Modules and LED Drivers used on Project; use ANSI and manufacturers' codes.

## **1.7 MAINTENANCE MATERIAL SUBMITTALS**

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents citing lighting fixture types.
  - 1. Lamps: 2 for every 100 of each type and rating installed. Furnish at least one of each type.
  - 2. Diffusers and Lenses: One for every 100 of each type and rating installed. Furnish at least one of each type.
  - 3. Globes and Guards: One for every 20 of each type and rating installed. Furnish at least one of each type.

## **1.8 QUALITY ASSURANCE**

- A. Luminaire Photometric Data Testing Laboratory Qualifications: Luminaire manufacturer's laboratory that is accredited under the NVLAP for Energy Efficient Lighting Products.
- B. Luminaire Photometric Data Testing Laboratory Qualifications: Provided by an independent agency, with the experience and capability to conduct the testing indicated, that is an NRTL as defined by OSHA in 29 CFR 1910.7, accredited under the NVLAP for Energy Efficient Lighting Products, and complying with the applicable IES testing standards.
- C. Provide luminaires from a single manufacturer for each luminaire type.
- D. Each luminaire type shall be binned within a three-step MacAdam Ellipse to ensure color consistency among luminaires.
- E. Mockups: For interior lighting luminaires in room or module mockups, complete with power and control connections.
  - 1. Obtain Architect's approval of luminaires in mockups before starting installations.
  - 2. Maintain mockups during construction in an undisturbed condition as a standard for judging the completed Work.
  - 3. Approval of mockups does not constitute approval of deviations from the Contract Documents contained in mockups unless Architect specifically approves such deviations in writing.
  - 4. Subject to compliance with requirements, approved mockups may become part of the completed Work if undisturbed at time of Substantial Completion.

## **1.9 DELIVERY, STORAGE, AND HANDLING**

- A. Protect finishes of exposed surfaces by applying a strippable, temporary protective covering before shipping.

## **1.10 WARRANTY**

- A. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within specified warranty period.
- B. Warranty Period: Five year(s) from date of Substantial Completion.

## **PART 2 - PRODUCTS**

### **2.1 PERFORMANCE REQUIREMENTS**

- A. Seismic Performance: Luminaires shall withstand the effects of earthquake motions determined according to ASCE/SEI 7.
- B. Seismic Performance: Luminaires and lamps shall be labeled vibration and shock resistant.
  - 1. The term "withstand" means "the luminaire will remain in place without separation of any parts when subjected to the seismic forces specified and the luminaire will be fully operational during and after the seismic event."

### **2.2 LUMINAIRE REQUIREMENTS**

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. NRTL Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by an NRTL.
- C. FM Global Compliance: Luminaires for hazardous locations shall be listed and labeled for indicated class and division of hazard by FM Global.
- D. Recessed Fixtures: Comply with NEMA LE 4.
- E. Bulb shape complying with ANSI C79.1.
- F. Lamp base complying with ANSI C81.61 or IEC 60061-1, where employing universal base or mount.
- G. CRI of minimum 80. CCT of 3500 K.
- H. L70 rated lamp life of 50,000 hours.
- I. Lamps dimmable as indicated or 0.5 to 100 percent of maximum light output, via 0-10 VDC control signal or, where indicated, Digital Dimming Control Signal.
- J. Field Replaceable driver.

- K. Nominal Operating Voltage: Universal voltage 120 V ac or 277 V ac unless scheduled differently.
  - 1. Lens Thickness: At least 0.125 inch (3.175 mm) minimum unless otherwise indicated.
- L. Housings:
  - 1. Hydroformed, cast or extruded-aluminum housing and heat sink suitable for the environment.
  - 2. Anodized or powder-coat finish.

### **2.3 LED LAMPS AND DRIVERS:**

- A. Minimum CRI Ra- 82 or as specified.
- B. Lumen output shall be Luminaire Lumens or Delivered Lumens. Source lumens shall not be used.
- C. Each luminaire type shall be binned within a three-step MacAdam Ellipse to ensure color consistency among luminaires.
- D. LED Rated life L70 of 50,000 hours per (IES LM-80). Luminaire shall maintain LED operating temperature to achieve this rating per TM-21.
- E. Flicker: No visible or detectable flicker, operating on all dimmed intensities.
- F. Dimming drivers shall be compatible with the control method shown on the drawings. All dimmed drivers shall use 0-10vdc control unless specified differently. Minimum level as scheduled.
- G. Inrush current shall be reported and the lighting controls adjusted for inrush of LED product supplied.
- H. THD: THD shall not exceed 80%.
- I. Minimum driver efficiency shall be 83%.
- J. LED module shall be replaceable in the field using modules with digitally traceable matching modules.
- K. Luminaire shall be NRTL Listed at intended operating temperature.
- L. Photometry shall be measured or absolute photometry. Derived or calculated photometry shall not be provided for consideration.
- M. Approved Manufacturers- Drivers
  - 1. General Electric.
  - 2. Philips.
  - 3. Osram / Sylvania.
  - 4. Lutron

- 5. EldoLED
- 6. Thomas Research
- N. Approved Manufacturers- LEDs
  - 1. General Electric
  - 2. Philips
  - 3. Osram
  - 4. Cree
  - 5. Xicato
  - 6. Nichia
- O. Approved Manufacturers for Luminaires shall be as scheduled.

## 2.4 MATERIALS

- A. Metal Parts:
  - 1. Free of burrs and sharp corners and edges.
  - 2. Sheet metal components shall be steel unless otherwise indicated.
  - 3. Form and support to prevent warping and sagging.
- B. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.
- C. Diffusers and Globes:
  - 1. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
  - 2. Glass: Annealed crystal glass unless otherwise indicated.
  - 3. Lens Thickness: At least 0.125 inch (3.175 mm) minimum unless otherwise indicated.
- D. Housings:
  - 1. Hydroformed, cast or extruded-aluminum housing and heat sink suitable for the environment.
  - 2. Anodized or powder-coat finish.
- E. Factory-Applied Labels: Comply with UL 1598. Include recommended lamps and line wattage. Locate labels where they will be readily visible to service personnel, but not seen from normal viewing angles when lamps are in place.
  - 1. Label shall include the following lamp characteristics:
    - a. "USE ONLY" and include specific lamp type.
    - b. Lamp diameter, shape, size, wattage, and coating.
    - c. CCT and CRI for all luminaires.



## **2.5 METAL FINISHES**

- A. Variations in finishes are unacceptable in the same piece. Variations in finishes of adjoining components are acceptable if they are within the range of approved Samples and if they can be and are assembled or installed to minimize contrast.

## **2.6 LUMINAIRE FIXTURE SUPPORT COMPONENTS**

- A. Comply with requirements in Section 26 05 29 "Hangers and Supports for Electrical Systems" for channel and angle iron supports and nonmetallic channel and angle supports.
- B. Single-Stem Hangers: 1/2-inch (13-mm) steel tubing with swivel ball fittings and ceiling canopy. Finish same as luminaire.
- C. Wires: ASTM A 641/A 641 M, Class 3, soft temper, zinc-coated steel, 12 gauge (2.68 mm).
- D. Rod Hangers: 3/16-inch (5-mm) minimum diameter, cadmium-plated, threaded steel rod.
- E. Hook Hangers: Integrated assembly matched to luminaire, line voltage, and equipment with threaded attachment, cord, and locking-type plug.

## **2.7 GENERAL REQUIREMENTS FOR EMERGENCY LIGHTING**

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. NRTL Compliance: Fabricate and label emergency lighting units, exit signs, and batteries to comply with UL 924.
- C. Comply with NFPA 70 and NFPA 101.
- D. Comply with NEMA LE 4 for recessed luminaires.
- E. Internal Type Emergency Power Unit: Self-contained, modular, battery-inverter unit, factory mounted within luminaire body and compatible with LED light source and driver, including dimming driver.
  - 1. Emergency Connection: Operate luminaire continuously at an output of 5 watts upon loss of normal power. Connect unswitched circuit to battery-inverter unit and switched circuit to luminaire ballast.
  - 2. Operation: Relay automatically turns driver/led module on when power-supply circuit voltage drops to 80 percent of nominal voltage or below. Lamp automatically disconnects from battery when voltage approaches deep-discharge level. When normal voltage is restored, relay disconnects lamps from battery, and battery is automatically recharged and floated on charger.

3. Environmental Limitations: Rate equipment for continuous operation under the following conditions unless otherwise indicated:
  - a. Ambient Temperature: Less than 0 deg F or exceeding 104 deg F with an average value exceeding 95 deg over a 24-hour period.
  - b. Ambient Storage Temperature: Not less than minus 4 deg F and not exceeding 140 deg F
  - c. Humidity: More than 95 percent (condensing).
  - d. Altitude: Exceeding 3300 feet
4. Battery: Sealed, maintenance-free, lead-acid type.
5. Charger: Fully automatic, solid-state, constant-current type with sealed power transfer relay.
6. Integral Self-Test: Factory-installed electronic device automatically initiates code-required test of unit emergency operation at required intervals. Test failure is annunciated by an integral audible alarm and a flashing red LED.

## **PART 3 - EXECUTION**

### **3.1 EXAMINATION**

- A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.
- B. Examine roughing-in for luminaire to verify actual locations of luminaire and electrical connections before fixture installation. Proceed with installation only after unsatisfactory conditions have been corrected.

### **3.2 TEMPORARY LIGHTING**

- A. If approved by the Architect, use selected permanent luminaires for temporary lighting. When construction is sufficiently complete, clean luminaires used for temporary lighting and install new lamps.

### **3.3 INSTALLATION**

- A. Comply with NECA 1.
- B. Install luminaires level, plumb, and square with ceilings and walls unless otherwise indicated.
- C. Supports:
  1. Sized and rated for luminaire weight.
  2. Able to maintain luminaire position after cleaning and repair.
  3. Provide support for luminaire without causing deflection of ceiling or wall.

4. Luminaire mounting devices shall be capable of supporting a horizontal force of 100 percent of luminaire weight and vertical force of 400 percent of luminaire weight.
- D. Flush-Mounted Luminaire Support:
  1. Secured to outlet box.
  2. Attached to ceiling structural members at four points equally spaced around circumference of luminaire.
  3. Trim ring flush with finished surface.
- E. Wall-Mounted Luminaire Support:
  1. Attached to structural members or approved backer plate in walls
  2. Do not attach luminaires directly to gypsum board.
- F. Ceiling-Mounted Luminaire Support:
  1. Ceiling mount with four 5/32-inch- (4-mm) diameter steel wire or aircraft cable supports.
  2. Ceiling mount with hook mount.
- G. Suspended Luminaire Support:
  1. Pendants and Rods: Where longer than 48 inches (1200 mm), brace to limit swinging.
  2. Stem-Mounted, Single-Unit Luminaires: Suspend with twin-stem hangers. Support with approved outlet box and accessories that hold stem and provide damping of luminaire oscillations. Support outlet box vertically to building structure using approved devices.
  3. Continuous Rows of Luminaires: Use tubing or stem for wiring at one point and wire support for suspension for each unit length of luminaire chassis, including one at each end.
  4. Do not use ceiling grid as support for pendant luminaires. Connect support wires or rods to building structure.
- H. Ceiling-Grid-Mounted Luminaires:
  1. Secure to any required outlet box.
  2. Secure luminaire to the luminaire opening using approved fasteners in a minimum of four locations, spaced near corners of luminaire.
  3. Use approved devices and support components to connect luminaire to ceiling grid and building structure in a minimum of four locations, spaced near corners of luminaire.
- I. Comply with requirements in Section 26 05 19 "Low-Voltage Electrical Power Conductors and Cables" for wiring connections.

### **3.4 IDENTIFICATION**

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 26 05 53 "Identification for Electrical Systems."

### **3.5 FIELD QUALITY CONTROL**

- A. Perform the following tests and inspections:
  - 1. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
  - 2. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery power and retransfer to normal.
- B. Luminaire will be considered defective if it does not pass operation tests and inspections.
- C. Prepare test and inspection reports.

### **3.6 STARTUP SERVICE**

- A. Comply with requirements for startup specified in Section 26 09 43 "Relay-Based Lighting Controls."

### **3.7 ADJUSTING**

- A. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting the direction of aim of luminaires to suit occupied conditions. Make up to two visits to Project during other-than-normal hours for this purpose. Some of this work may be required during hours of darkness.
  - 1. During adjustment visits, inspect all luminaires. Replace luminaires that are defective.
  - 2. Parts and supplies shall be manufacturer's authorized replacement parts and supplies.
  - 3. Adjust the aim of luminaires in the presence of the Architect.

END OF SECTION 265119

SECTION 271100 - TELECOMMUNICATIONS PATHWAYS AND SPACES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. Section Includes:
  - 1. Telecommunications vertical and horizontal pathways.
  - 2. Backboards and mounting elements.
  - 3. Telecommunications equipment racks and cabinets.
  - 4. Telecommunications service entrance pathways.
  - 5. Grounding.
- B. Related Sections:
  - 1. Division 27 Section "Communications Backbone Cabling" for voice and data cabling associated with system panels and devices.
  - 2. Division 27 Section "Communications Horizontal Cabling" for voice and data cabling associated with system panels and devices.

1.3 DEFINITIONS

- A. Basket Cable Tray: A fabricated structure consisting of wire mesh bottom and side rails.
- B. BICSI: Building Industry Consulting Service International.
- C. LAN: Local area network.
- D. RCDD: Registered Communications Distribution Designer.

1.4 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Floor-mounted cabinets and cable pathways shall withstand the effects of earthquake motions determined according to SEI/ASCE 7, (Zone 4).
  - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."

1.5 SUBMITTALS

- A. Product Data: For each type of product indicated. Include construction details, material descriptions, dimensions of individual components and profiles, and finishes for equipment racks and cabinets. Include rated capacities, operating characteristics, electrical characteristics, and furnished specialties and accessories.

- B. Shop Drawings: For communications equipment room fittings. Include plans, elevations, sections, details, and attachments to other work.
  - 1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  - 2. Equipment Racks and Cabinets: Include workspace requirements and access for cable connections.
  - 3. Grounding: Indicate location of grounding bus bar and its mounting detail showing standoff insulators and wall mounting brackets.
- C. Qualification Data: For each qualified layout technician, installation supervisor, and field inspector.
- D. Seismic Qualification Certificates: For floor-mounted cabinets, accessories, and components, from manufacturer.
  - 1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  - 2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions. Base certification on the maximum number of components capable of being mounted in each rack type. Identify components on which certification is based.
  - 3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.

#### 1.6 QUALITY ASSURANCE

- A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.
  - 1. Layout Responsibility: Preparation of Shop Drawings shall be under the direct supervision of an RCDD.
  - 2. Installation Supervision: Installation shall be under the direct supervision of a Registered Technician (BICSI), who shall be present at all times when Work of this Section is performed at Project site.
  - 3. Field Inspector: Currently registered by BICSI as an RCDD to perform the on-site inspection.
  - 4. Contractor must be Commscope Systimax certified prior to the time of bid and must provide a 25 year Systimax system warranty to the owner at the conclusion of the project.
  - 5. Contractor must be a Corning certified contractor prior to time of bid and able to provide the Corning system warranty on all Corning fiber products installed.
- B. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- C. Telecommunications Pathways and Spaces: Comply with ANSI/TIA/EIA-569-B.
- D. Grounding: Comply with ANSI-J-STD-607-A.

#### 1.7 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install equipment frames and cable trays until spaces are enclosed and weathertight, wet work in spaces is complete and dry, and associated construction work on the subfloor and raised floor supports is substantially complete.

## PART 2 - PRODUCTS

### 2.1 PATHWAYS

- A. General Requirements: Comply with ANSI/TIA/EIA-569-B.
- B. Cable Support (Free Space): Cable installation of less than 5 cables shall not require basket cable tray management, but shall require bundling of cables with approved Velcro fasteners for orderly layout.
- C. Cable Trays:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Cablofil Inc.
    - b. Cooper B-Line, Inc.
    - c. WBT Wire Basket Tray
  - 2. Cable Tray Materials: Metal, suitable for indoors and protected against corrosion by electroplated zinc galvanizing, complying with ASTM B 633, Type 1, not less than 0.000472 inch (0.012 mm) thick.
    - a. Basket Cable Trays: Provide tray widths as noted – 4 – 24 inches - wide and minimum 2 inch deep. Wire mesh spacing shall not exceed 2 by 4 inches.
- D. Conduit and Boxes: Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems".
- E. Conduit Sleeves: Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems".
- F. Conduit and Boxes (Wireless Access Points): Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems". Provide a 1" conduit and two gang box, coordinated with the finished height of a hard lid ceiling for outlet mounting, and extend the conduit to the nearest cable tray.

### 2.2 BACKBOARDS

- A. Backboards: Provide plywood, fire-retardant treated, 3/4 by 48 by 96 inches, on at least two of the full non-door walls of each telecommunications room, or as noted. Comply with requirements for plywood backing panels specified in Division 06 Section "Rough Carpentry."

### 2.3 EQUIPMENT FRAMES

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Chatsworth
- B. General Frame Requirements:
  - 1. Distribution Frames: Freestanding, modular-metal units designed for telecommunications terminal support and coordinated with dimensions of units to be supported.
  - 2. Module Dimension: Width compatible with EIA 310 standard, 19-inch panel mounting.
  - 3. Finish: Manufacturer's standard, baked-polyester powder coat.
- C. Floor-Mounted Racks (Horizontal Termination): Modular-type, steel or aluminum construction.

1. Vertical and horizontal cable management channels, top and bottom cable troughs, grounding lug, and a power strip.
2. Baked-polyester powder coat finish.

D. Cable Management for Equipment Frames:

1. Chatsworth

2.4 POWER STRIPS

A. Power Strips: Comply with UL 1363.

1. Rack mounting.
2. Ten, 20-A, 120-V ac, NEMA WD 6, Configuration 5-20R receptacles.
3. LED indicator lights for power and protection status.
4. LED indicator lights for reverse polarity and open outlet ground.
5. Circuit Breaker and Thermal Fusing: When protection is lost, circuit opens and cannot be reset.
6. Circuit Breaker and Thermal Fusing: Unit continues to supply power if protection is lost.
7. Cord connected with 6-foot line cord.
8. Protection modes shall be line to neutral, line to ground, and neutral to ground. UL 1449 clamping voltage for all 3 modes shall be not more than 330 V.

2.5 GROUNDING

A. Comply with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems." for grounding conductors and connectors.

B. Telecommunications Main Ground Bus Bar:

1. Connectors: Mechanical type, cast silicon bronze, solderless exothermic-type wire terminals, and long-barrel, two-bolt connection to ground bus bar.
2. Ground Bus Bar: Copper, minimum 1/4 inch thick by 4 inches wide with 9/32-inch holes spaced 1-1/8 inches apart.
3. Stand-Off Insulators: Comply with UL 891 for use in switchboards, 600 V. Lexan or PVC, impulse tested at 5000 V.

C. Comply with ANSI-J-STD-607-A.

2.6 LABELING

A. Comply with TIA/EIA-606-A and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.

PART 3 - EXECUTION

3.1 ENTRANCE FACILITIES

A. Install underground pathways complying with recommendations in TIA/EIA-569-B, "Entrance Facilities" Article.



### 3.2 INSTALLATION

- A. Install underground entrance pathway complying with Division 26 Section "Raceway and Boxes for Electrical Systems." Comply with NECA 1.
- B. Comply with BICSI TDMM for layout and installation of communications equipment rooms.
- C. Cable Trays: Provide overhead cable runway (ladder rack) as noted. Comply with NEMA VE 2 and TIA/EIA-569-B.
- D. Bundle, wrap, and train conductors and cables to terminal points without exceeding manufacturer's limitations on bending radii. Install management bars and distribution spools.

### 3.3 FIRESTOPPING

- A. Comply with requirements in Division 07 Section "Penetration Firestopping." Comply with TIA/EIA-569-B, "Firestopping."
- B. Comply with BICSI TDMM, "Firestopping Systems" Article.

### 3.4 GROUNDING

- A. Install grounding according to BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. Comply with ANSI-J-STD-607-A.
- C. Locate grounding bus bar to minimize the length of bonding conductors. Fasten to wall allowing at least 2-inch (50-mm) clearance behind the grounding bus bar. Connect grounding bus bar with a minimum No. 4 AWG grounding electrode conductor from grounding bus bar to suitable electrical building ground.
- D. Bond metallic equipment to the grounding bus bar, using not smaller than No. 6 AWG equipment grounding conductor.
  - 1. Bond the shield of shielded cable to the grounding bus bar in communications rooms and spaces.

### 3.5 IDENTIFICATION

- A. Identify system components, wiring, and cabling complying with TIA/EIA-606-A. Comply with requirements in Division 26 Section "Identification for Electrical Systems."
- B. Comply with requirements in Division 09 Section "Interior Painting" for painting backboards. For fire-resistant plywood, do not paint over manufacturer's label.
- C. See Section 271300 "Communications Horizontal Cabling" for additional identification requirements. See Evaluations for discussion of TIA/EIA standard as it applies to this Section.
- D. Paint and label colors for equipment identification shall comply with TIA/EIA-606-A for Class 4 level of administration, including optional identification requirements of this standard.
- E. Labels shall be preprinted or computer-printed type.

END OF SECTION 271100

## SECTION 271300 - COMMUNICATIONS BACKBONE CABLING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Pathways.
  - 2. UTP cable.
  - 3. Optical fiber cabling.
  - 4. Cable connecting hardware, termination panels, and cross-connects.
  - 5. Cabling identification products.
- B. Related Sections:
  - 1. Division 27 Section "Communications Horizontal Cabling" for voice and data cabling associated with system panels and devices.

#### 1.3 DEFINITIONS

- A. BICSI: Building Industry Consulting Service International.
- B. Cross-Connect: A facility enabling the termination of cable elements and their interconnection or cross-connection.
- C. EMI: Electromagnetic interference.
- D. IDC: Insulation displacement connector.
- E. LAN: Local area network.
- F. RCDD: Registered Communications Distribution Designer.
- G. UTP: Unshielded twisted pair.

#### 1.4 BACKBONE CABLING DESCRIPTION

- A. Backbone cabling system shall provide interconnections between communications equipment rooms, main terminal space, and entrance facilities in the telecommunications cabling system structure. Cabling system consists of backbone cables, intermediate and main cross-connects, mechanical terminations, and patch cords or jumpers used for backbone-to-backbone cross-connection.

- B. Backbone cabling cross-connects shall be located in termination rooms (telecom) and at entrance facilities. Bridged taps and splitters shall not be used as part of backbone cabling.

#### 1.5 PERFORMANCE REQUIREMENTS

- A. General Performance: Backbone cabling system shall comply with transmission standards in TIA/EIA-568-C.1, when tested according to test procedures of this standard.

#### 1.6 SUBMITTALS

- A. Product Data: For each type of product indicated.
  - 1. For all cable, include the following installation data for each type used:
    - a. Nominal OD.
    - b. Minimum bending radius.
    - c. Maximum pulling tension.
- B. Shop Drawings:
  - 1. System Labeling Schedules: Electronic copy of labeling schedules, in software and format selected by Owner.
  - 2. System Labeling Schedules: Electronic copy of labeling schedules that are part of the cabling and asset identification system of the software.
  - 3. Cabling administration drawings and printouts.
  - 4. Wiring diagrams to show typical wiring schematics including the following:
    - a. Cross-connects.
    - b. Patch panels.
    - c. Patch cords.
  - 5. Cross-connects and patch panels. Detail mounting assemblies, and show elevations and physical relationship between the installed components.
  - 6. Cable tray layout, showing cable tray route to scale, with relationship between the tray and adjacent structural, electrical, and mechanical elements. Include the following:
    - a. Vertical and horizontal offsets and transitions.
    - b. Clearances for access above and to side of cable trays.
    - c. Vertical elevation of cable trays above the floor or bottom of ceiling structure.
    - d. Load calculations to show dead and live loads as not exceeding manufacturer's rating for tray and its support elements.
- C. Qualification Data: For all qualified layout technicians, installation supervisors, and field inspectors.
- D. Source quality-control reports.
- E. Field quality-control reports.
- F. Maintenance Data: For splices and connectors to include in maintenance manuals.
- G. Software and Firmware Operational Documentation:

1. Software operating and upgrade manuals.
2. Program Software Backup: On magnetic media or compact disk, complete with data files.
3. Device address list.
4. Printout of software application and graphic screens.

## 1.7 QUALITY ASSURANCE

- A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.
1. Layout Responsibility: Preparation of Shop Drawings, Cabling Administration Drawings, and field testing program development by an RCDD.
  2. Installation Supervision: Installation shall be under the direct supervision of a Registered Technician (BICSI), who shall be present at all times when Work of this Section is performed at Project site.
  3. Testing Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.
  4. Contractor must be Commscope Systimax certified prior to the time of bid and must provide a 25 year Systimax system warranty to the owner at the conclusion of the project.
  5. Contractor must be a Corning certified contractor prior to time of bid and able to provide the Corning system warranty on all Corning fiber products installed.
- B. Testing Agency Qualifications: An NRTL.
1. Testing Agency's Field Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- D. Telecommunications Pathways and Spaces: Comply with TIA/EIA-569-B.
- E. Grounding: Comply with ANSI-J-STD-607-A.

## 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Test cables upon receipt at Project site.
1. Test optical fiber cable to determine the continuity of the strand end to end. Use optical loss test set.
  2. Test optical fiber cable while on reels. Use an optical time domain reflectometer to verify the cable length and locate cable defects, splices, and connector, including the loss value of each. Retain test data and include the record in maintenance data.
  3. Test each pair of UTP cable for open and short circuits.

## 1.9 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.10 COORDINATION

- A. Coordinate layout and installation of telecommunications pathways and cabling with Owner's telecommunications and LAN equipment and service suppliers..

1.11 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents. Furnish five percent of total quantity provided for each component, minimum of one, if less than one.

PART 2 - PRODUCTS

2.1 PATHWAYS

- A. General Requirements: Comply with TIA/EIA-569-B.
- B. Cable Support: NRTL labeled for support of Category 6A cabling, designed to prevent degradation of cable performance and pinch points that could damage cable.
  - 1. Support brackets with cable tie slots for fastening cable ties to brackets.
  - 2. Lacing bars, spools, J-hooks, and D-rings.
  - 3. Straps and other devices.
- C. Overhead Cable Runway :
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. Chatsworth
  - 2. Cable Tray Material: Metal, suitable for indoors, and protected against corrosion by electroplated zinc galvanizing, complying with ASTM B 633, Type 1, not less than 0.000472 inches thick.
    - a. Ladder Cable Trays: Nominally 12 inches wide, and a rung spacing of 12 inches.
- D. Conduit and Boxes: Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems." Flexible metal conduit shall not be used. Minimum 1 inch conduit shall be provided from box to cable tray.
  - 1. Outlet boxes shall two gang with a single gang mud ring.

2.2 BACKBOARDS

- A. Backboards: Plywood, fire-retardant treated, 3/4 by 48 by 96 inches. Comply with requirements in Division 06 Section "Rough Carpentry" for plywood backing panels.

## 2.3 UTP CABLE

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following :
  - 1. CommScope Systimax, Inc.
- B. Description: 100-ohm, multipair UTP (quantity as noted), formed into 25-pair binder groups covered with a thermoplastic jacket.
  - 1. Comply with ICEA S-90-661 for mechanical properties.
  - 2. Comply with TIA/EIA-568-C.1 for performance specifications.
  - 3. Comply with TIA/EIA-568-C.2, Category 3.
  - 4. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444 and NFPA 70 for the following types:
    - a. Communications, Plenum Rated: Type CMP, complying with NFPA 262.

## 2.4 UTP CABLE HARDWARE

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. CommScope Systimax
- B. General Requirements for Cable Connecting Hardware: Comply with TIA/EIA-568-C.2, IDC type, with modules designed for punch-down caps or tools. Cables shall be terminated with connecting hardware of same category or higher.
- C. Riser Patch Panel: 110-style IDC for Category 5e. Provide 24 port patch panels for each 25 pair cable.
  - 1. Number of Terminals per Field: One for each conductor in assigned cables.
- D. Jacks and Jack Assemblies: Modular, color-coded, eight-position modular receptacle units with integral IDC-type terminals.
- E. Patch Cords: Factory-made, 4-pair cables.

## 2.5 OPTICAL FIBER CABLE

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Corning
  - 2. Sumitomo
- B. Description: 7 Tube Microduct System
  - 1. Provide (1) 7 tube microduct per location.

OPTICAL FIBER CABLE HARDWARE
- C. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Corning
  - D. Cross-Connects and Termination Panels: Modular panels housing multiple-numbered, duplex cable connectors.
    1. Number of Connectors per Field: One for each fiber of cable or cables assigned to field, plus spares and blank positions adequate to suit specified expansion criteria.
  - E. Jumper Cords: Factory-made, dual-fiber cables.
  - F. Cable Connecting Hardware:
    1. Comply with Optical Fiber Connector Intermateability Standards (FOCIS) specifications of TIA/EIA-604-2, TIA/EIA-604-3-A, and TIA/EIA-604-12. Comply with TIA/EIA-568-C.3.
    2. Quick-connect, simplex and duplex, Type SC/APC connectors. Insertion loss not more than 0.75 dB.
- 2.6 GROUNDING
- A. Comply with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems." for grounding conductors and connectors.
  - B. Comply with ANSI-J-STD-607-A.
- 2.7 IDENTIFICATION PRODUCTS
- A. Comply with TIA/EIA-606-A and UL 969 for a system of labeling materials, including label stocks, laminating adhesives, and inks used by label printers.
- 2.8 SOURCE QUALITY CONTROL
- A. Testing Agency: Engage a qualified testing agency to evaluate cables.
  - B. Factory test cables on reels according to TIA/EIA-568-C.1.
  - C. Factory test UTP cables according to TIA/EIA-568-C.2.
  - D. Factory test multimode optical fiber cables according to TIA/EIA-526-14-A and TIA/EIA-568-C.3.
  - E. Cable will be considered defective if it does not pass tests and inspections.
  - F. Prepare test and inspection reports.

## PART 3 - EXECUTION

### 3.1 ENTRANCE FACILITIES

- A. Coordinate backbone cabling with the protectors and demarcation point provided by communications service provider.

### 3.2 WIRING METHODS

- A. Wiring Method: Install cables in raceways and cable trays except within cabinets. Conceal raceway and cables except in unfinished spaces.
  - 1. Install plenum cable in all spaces.
  - 2. Comply with requirements for raceways and boxes specified in Division 26 Section "Raceway and Boxes for Electrical Systems."
- B. Wiring within Enclosures: Bundle, lace, and train cables within enclosures. Connect to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools.

### 3.3 INSTALLATION OF PATHWAYS

- A. Cable Trays: Comply with NEMA VE 2 and TIA/EIA-569-B.
- B. Comply with requirements for demarcation point, pathways, cabinets, and racks specified in Section 271100 "Telecommunications Pathways and Spaces." Drawings indicate general arrangement of pathways and fittings.
- C. Comply with TIA/EIA-569-B for pull-box sizing and length of conduit and number of bends between pull points.
- D. Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems" for installation of conduits and wireways.
- E. Install manufactured conduit sweeps and long-radius elbows whenever possible.
- F. Pathway Installation in Termination Rooms (Telecom):
  - 1. Position vertical conduit ends adjacent to a corner where plywood backboard is installed, or in the corner of room where multiple sheets of plywood are installed around perimeter walls of room.
  - 2. Secure conduits to backboard when entering room from overhead.
  - 3. Install metal conduits with grounding bushings and connect with grounding conductor to grounding system.
- G. Backboards: Install backboards with 96-inch dimension vertical. Butt adjacent sheets tightly, and form smooth gap-free corners and joints.



### 3.4 INSTALLATION OF CABLES

- A. Comply with NECA 1.
- B. General Requirements for Cabling:
  - 1. Comply with TIA/EIA-568-C.1.
  - 2. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."
  - 3. For UTP cable, install 110-style IDC termination hardware unless otherwise indicated.
  - 4. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.
  - 5. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
  - 6. Install lacing bars to restrain cables, to prevent straining connections, and to prevent bending cables to smaller radii than minimums recommended by manufacturer.
  - 7. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIM, "Cabling Termination Practices" Chapter. Use lacing bars and distribution spools.
  - 8. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
  - 9. Cold-Weather Installation: Bring cable to room temperature before de-reeling. Heat lamps shall not be used for heating.
  - 10. In the communications equipment room, install a 15-foot long service loop on the station end of cable.
  - 11. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
- C. UTP Cable Installation:
  - 1. Comply with TIA/EIA-568-C.2.
- D. Optical Fiber Cable Installation:
  - 1. Comply with TIA/EIA-568-C.3.
  - 2. Cable shall be terminated on connecting hardware that is rack or cabinet mounted.
- E. Open-Cable Installation:
  - 1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
  - 2. Suspend UTP cable not in a wireway or pathway, a minimum of 8 inches above ceilings by cable supports not more than 60" apart.
  - 3. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.
- F. Group connecting hardware for cables into separate logical fields.
- G. Separation from EMI Sources:
  - 1. Comply with BICSI TDMM and TIA/EIA-569-B recommendations for separating unshielded copper voice and data communication cable from potential EMI sources, including electrical power lines and equipment.

2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment shall be as follows:
  - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches.
  - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches.
  - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches.
3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
  - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
  - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
  - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.
4. Separation between communications cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
  - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
  - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
  - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.
5. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches.

### 3.5 FIRESTOPPING

- A. Comply with requirements in Division 07 Section "Penetration Firestopping. "Comply with TIA/EIA-569-B, "Firestopping."
- B. Comply with BICSI TDMM, "Firestopping Systems" Article.

### 3.6 GROUNDING

- A. Install grounding according to BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. Comply with ANSI-J-STD-607-A.
- C. Locate grounding bus bar to minimize the length of bonding conductors. Fasten to wall allowing at least 2-inch clearance behind the grounding bus bar. Connect grounding bus bar with a minimum No. 4 AWG grounding electrode conductor from grounding bus bar to suitable electrical building ground.
- D. Bond metallic equipment to the grounding bus bar, using not smaller than No. 6 AWG equipment grounding conductor.

### 3.7 IDENTIFICATION

- A. Identify system components, wiring, and cabling complying with TIA/EIA-606-A. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
  - 1. Administration Class: 4.
  - 2. Color-code cross-connect fields and apply colors to voice and data service backboards, connections, covers, and labels.
- B. Comply with requirements in Division 09 Section "Interior Painting" for painting backboards. For fire-resistant plywood, do not paint over manufacturer's label.
- C. See Division 27 Section "Communications Horizontal Cabling" for additional identification requirements. See Evaluations for discussion about TIA/EIA standard as it applies to this Section. Paint and label colors for equipment identification shall comply with TIA/EIA-606-A for Class 2 level of administration.
- D. Comply with requirements in Section 271500 "Communications Horizontal Cabling" for cable and asset management software.
- E. Cable Schedule: Install in a prominent location in each equipment room and wiring closet. List incoming and outgoing cables and their designations, origins, and destinations. Protect with rigid frame and clear plastic cover. Furnish an electronic copy of final comprehensive schedules for Project.
- F. Cabling Administration Drawings: Show building floor plans with cabling administration-point labeling. Identify labeling convention and show labels for telecommunications closets, backbone pathways and cables, entrance pathways and cables, terminal hardware and positions, horizontal cables, work areas and workstation terminal positions, grounding buses and pathways, and equipment grounding conductors.
- G. Cable and Wire Identification:
  - 1. Label each cable within 4 inches of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
  - 2. Label each terminal strip and screw terminal in each cabinet, rack, or panel.
    - a. Individually number wiring conductors connected to terminal strips and identify each cable or wiring group being extended from a panel or cabinet to a building-mounted device with name and number of particular device as shown.
    - b. Label each unit and field within distribution racks and frames.
- H. Labels shall be preprinted or computer-printed type with printing area and font color that contrasts with cable jacket color but still complies with requirements in TIA/EIA 606-A, for the following:
  - 1. Cables use flexible vinyl or polyester that flexes as cables are bent.

### 3.8 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.

- B. Perform tests and inspections.
- C. Tests and Inspections:
  - 1. Visually inspect UTP and optical fiber jacket materials for NRTL certification markings. Inspect cabling terminations in communications equipment rooms for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA/EIA-568-C.1.
  - 2. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
  - 3. Test UTP copper cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross-connection.
    - a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-C.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
  - 4. Optical Fiber Cable Tests:
    - a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-C.1. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
    - b. Link End-to-End Attenuation Tests:
      - 1) Horizontal and multimode backbone link measurements: Test at 1310 and 1550 nm in both directions according to ANSI/TIA/EIA 568-C standards
      - 2) Attenuation test results for backbone links shall be less than 2.0 dB.
- D. Data for each measurement shall be documented. Data for submittals shall be printed in a summary report that is formatted similar to Table 10.1 in BICSI TDMM, or transferred from the instrument to the computer, saved as text files, and printed and submitted.
- E. Remove and replace cabling where test results indicate that they do not comply with specified requirements.
- F. End-to-end cabling will be considered defective if it does not pass tests and inspections.
- G. Prepare test and inspection reports.

END OF SECTION 271300

## SECTION 271500 - COMMUNICATIONS HORIZONTAL CABLING

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Pathways.
  - 2. UTP cabling.
  - 3. Cable connecting hardware, patch panels, and cross-connects.
  - 4. Telecommunications outlet/connectors.
  - 5. Cabling system identification products.
  - 6. Cable management system.
- B. Related Sections:
  - 1. Section 271100 "Telecommunications Pathways and Spaces" for voice and data cabling associated with system panels and devices.
  - 2. Section 271300 "Communications Backbone Cabling" for voice and data cabling associated with system panels and devices.

#### 1.3 DEFINITIONS

- A. Basket Cable Tray: A fabricated structure consisting of wire mesh bottom and side rails.
- B. BICSI: Building Industry Consulting Service International.
- C. EMI: Electromagnetic interference.
- D. LAN: Local area network.
- E. Outlet/Connectors: A connecting device in the work area on which horizontal cable or outlet cable terminates.
- F. RCDD: Registered Communications Distribution Designer.
- G. UTP: Unshielded twisted pair.

#### 1.4 HORIZONTAL CABLING DESCRIPTION

- A. Horizontal cable and its connecting hardware provide the means of transporting signals between the telecommunications outlet/connector and the horizontal cross-connect located in the communications termination room (Telecom). This cabling and its connecting hardware are called "permanent link," a term that is used in the testing protocols.

1. TIA/EIA-568-C.2 requires that a minimum of two telecommunications outlet/connectors be installed for each work area, however, some locations designated by the owner shall have a single data outlet/connector.
  2. Horizontal cabling shall contain no more than one transition point or consolidation point between the horizontal cross-connect and the telecommunications outlet/connector.
  3. Bridged taps and splices shall not be installed in the horizontal cabling.
  4. Splitters shall not be installed as part of the optical fiber cabling.
- B. A work area is approximately 100 sq. ft., and includes the components that extend from the telecommunications outlet/connectors to the station equipment.
- C. The maximum allowable horizontal cable length is 295 feet. This maximum allowable length does not include an allowance for the length of 16 feet to the workstation equipment. The maximum allowable length does not include an allowance for the length of 16 feet in the horizontal cross-connect.

#### 1.5 PERFORMANCE REQUIREMENTS

- A. General Performance: Horizontal cabling system shall comply with transmission standards in TIA/EIA-568-C.1, when tested according to test procedures of this standard.

#### 1.6 SUBMITTALS

- A. Product Data: For each type of product indicated.
1. For all cable, include the following installation data for each type used:
    - a. Nominal OD.
    - b. Minimum bending radius.
    - c. Maximum pulling tension.
- B. Shop Drawings:
1. System Labeling Schedules: Electronic copy of labeling schedules, in software and format selected by Owner.
  2. System Labeling Schedules: Electronic copy of labeling schedules that are part of the cabling and asset identification system of the software.
  3. Cabling administration drawings and printouts.
  4. Wiring diagrams to show typical wiring schematics, including the following:
    - a. Cross-connects.
    - b. Patch panels.
    - c. Patch cords.
  5. Cross-connects and patch panels. Detail mounting assemblies, and show elevations and physical relationship between the installed components.
  6. Cable tray layout, showing cable tray route to scale, with relationship between the tray and adjacent structural, electrical, and mechanical elements. Include the following:
    - a. Vertical and horizontal offsets and transitions.
    - b. Clearances for access above and to side of cable trays.
    - c. Vertical elevation of cable trays above the subfloor.
- C. Samples: For workstation outlets, jacks, jack assemblies, in specified finish, one for each size and outlet configuration.
- D. Qualification Data: For all qualified layout technicians, installation supervisors, and field inspector.

- E. Source quality-control reports.
- F. Field quality-control reports.
- G. Maintenance Data: For splices and connectors to include in maintenance manuals.
- H. Software and Firmware Operational Documentation:
  - 1. Software operating and upgrade manuals.
  - 2. Program Software Backup: On magnetic media or compact disk, complete with data files.
  - 3. Device address list.
  - 4. Printout of software application and graphic screens.

#### 1.7 QUALITY ASSURANCE

- A. Installer Qualifications: Cabling Installer must have personnel certified by BICSI on staff.
  - 1. Layout Responsibility: Preparation of Shop Drawings, Cabling Administration Drawings, and field testing program development by an RCDD.
  - 2. Installation Supervision: Installation shall be under the direct supervision of a Registered Technician (BICSI), who shall be present at all times when Work of this Section is performed at Project site.
  - 3. Testing Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.
  - 4. Contractor must be Commscope Systimax certified prior to the time of bid and must provide a 25 year Systimax system warranty to the owner at the conclusion of the project.
  - 5. Contractor must be a Corning certified contractor prior to time of bid and able to provide the Corning system warranty on all Corning fiber products installed.
- B. Testing Agency Qualifications: An NRTL.
  - 1. Testing Agency's Field Supervisor: Currently certified by BICSI as an RCDD to supervise on-site testing.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- D. Telecommunications Pathways and Spaces: Comply with TIA/EIA-569-B.
- E. Grounding: Comply with ANSI-J-STD-607-A.

#### 1.8 DELIVERY, STORAGE, AND HANDLING

- A. Test cables upon receipt at Project site.
  - 1. Test each pair of UTP cable for open and short circuits.

#### 1.9 PROJECT CONDITIONS

- A. Environmental Limitations: Do not deliver or install cables and connecting materials until wet work in spaces is complete and dry, and temporary HVAC system is operating and maintaining ambient temperature and humidity conditions at occupancy levels during the remainder of the construction period.

1.10 COORDINATION

- A. Coordinate layout and installation of telecommunications pathways and cabling with Owner's telecommunications and LAN equipment and service suppliers.
- B. Coordinate telecommunications outlet/connector locations with location of power receptacles at each work area. This coordination will generally involve the placement of the raised floor floorboxes and the outlet arrangements therein.

1.11 EXTRA MATERIALS

- A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
  - 1. Patch-Panel Units: Two of each type.
  - 2. Device Plates: Three of each type.

PART 2 - PRODUCTS

2.1 PATHWAYS

- A. General Requirements: Comply with TIA/EIA-569-B.
- B. Cable Support: NRTL labeled for support of Category 6A cabling, designed to prevent degradation of cable performance and pinch points that could damage cable.
  - 1. Underfloor basket cable tray with floor support brackets for fastening to the subfloor.
  - 2. Lacing bars, spools, J-hooks, and D-rings.
  - 3. Straps and other devices.
- C. Basket Cable Trays:
  - 1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    - a. WBT
    - b. Cablofil Inc.
    - c. Cooper B-Line, Inc.
    - d. GS Metals Corp.
  - 2. Cable Tray Materials: Metal, suitable for indoors, and protected against corrosion by electroplated zinc galvanizing, complying with ASTM B 633, Type 1, not less than 0.000472 inch thick.
    - a. Basket Cable Trays: Width as noted – 2 - 24 inches - and 4 inch deep. Wire mesh spacing shall not exceed 2 by 4 inches.
- D. Conduit and Boxes: Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems." Minimum size of conduit shall be 1 inch.
  - 1. Wall outlet boxes shall be 2 gang, with a single gang trim ring..



## 2.2 BACKBOARDS

- A. Backboards: Plywood, fire-retardant treated, 3/4 by 48 by 96 inches. Comply with requirements in Division 06 Section "Rough Carpentry" for plywood backing panels.

## 2.3 UTP CABLE

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. CommScope Systimax.
- B. Description: 100-ohm, 4-pair UTP.
  - 1. Comply with ICEA S-90-661 for mechanical properties.
  - 2. Comply with TIA/EIA-568-C.1 for performance specifications.
  - 3. Comply with TIA/EIA-568-C.2, Category 6.
  - 4. Comply with TIA/EIA-568-C.2, Category 6A.
  - 5. Listed and labeled by an NRTL acceptable to authorities having jurisdiction as complying with UL 444 and NFPA 70 for the following types:
    - a. Communications, Plenum Rated: Type CMP, complying with NFPA 262.

## 2.4 UTP CABLE HARDWARE

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Commscope Systimax
- B. General Requirements for Cable Connecting Hardware: Comply with TIA/EIA-568-C.2, IDC type, with modules designed for punch-down caps or tools. Cables shall be terminated with connecting hardware of same category or higher.
- C. Patch Panel: Modular panels housing multiple-numbered jack units with IDC-type connectors at each jack for permanent termination of pair groups of installed cables.
  - 1. Number of Jacks per Field: One for each four-pair UTP cable indicated.
- D. Jacks and Jack Assemblies: Modular, color-coded, eight-position modular receptacle units with integral IDC-type terminals.
- E. Patch Cords: Factory-made, four-pair cables in lengths determined by shop drawings of rack elevations (minimum length of 6 feet); terminated with eight-position modular plug at each end.
  - 1. Patch cords shall have bend-relief-compliant boots and color-coded icons to ensure Category 6 performance. Patch cords shall have latch guards to protect against snagging.

## 2.5 TELECOMMUNICATIONS OUTLET/CONNECTORS

- A. Jacks: 100-ohm, balanced, twisted-pair connector; four-pair, eight-position modular. Comply with TIA/EIA-568-C.1.
- B. Workstation Outlets: Provide with the number of ports as noted – 1, 2, or 4, ports - connector assemblies mounted in single faceplate.

1. Floorbox Faceplate: Provide adapter plates to mount in the provided floorboxes for the appropriate cable solution being provided, ie. Commscope adapter plate for Commscope outlet connectors.
2. Legend: Machine printed, in the field, using adhesive-tape label or snap-in, clear-label covers and machine-printed paper inserts.

## 2.6 GROUNDING

- A. Comply with requirements in Division 26 Section "Grounding and Bonding for Electrical Systems" for grounding conductors and connectors.
- B. Comply with ANSI-J-STD-607-A.

## 2.7 IDENTIFICATION PRODUCTS

- A. Comply with TIA/EIA-606-A and UL 969 for labeling materials, including label stocks, laminating adhesives, and inks used by label printers.
- B. Comply with requirements in Division 26 Section "Identification for Electrical Systems."

## 2.8 SOURCE QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to evaluate cables.
- B. Factory test UTP cables on reels according to TIA/EIA-568-C.1.
- C. Factory test UTP cables according to TIA/EIA-568-C.2.
- D. Cable will be considered defective if it does not pass tests and inspections.
- E. Prepare test and inspection reports.

## PART 3 - EXECUTION

### 3.1 ENTRANCE FACILITIES

- A. Coordinate backbone cabling with the protectors and demarcation point provided by communications service provider.

### 3.2 WIRING METHODS

- A. Wiring Method: Install cables in raceways and cable trays except within cabinets. Conceal raceway and cables except in unfinished spaces.
  1. Install plenum cable in all spaces.
  2. Comply with requirements for raceways and boxes specified in Division 26 Section "Raceway and Boxes for Electrical Systems."
- B. Wiring within Enclosures: Bundle, lace, and train cables to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools.

### 3.3 INSTALLATION OF PATHWAYS

- A. Cable Trays: Comply with NEMA VE 2 and TIA/EIA-569-B.
- B. Comply with requirements for demarcation point, pathways, cabinets, and racks specified in Section 271100 "Telecommunications Pathways and Spaces." Drawings indicate general arrangement of pathways and fittings.
- C. Comply with TIA/EIA-569-B for pull-box sizing and length of conduit and number of bends between pull points.
- D. Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems" for installation of conduits and wireways.
- E. Install manufactured conduit sweeps and long-radius elbows whenever possible.
- F. Pathway Installation in Termination Rooms (Telecom):
  - 1. Position conduit ends adjacent to a corner on backboard where a single piece of plywood is installed, or in the corner of room where multiple sheets of plywood are installed around perimeter walls of room.
  - 2. Install basket cable trays to route cables from underfloor up into the floor mounted racks.
  - 3. Secure conduits to backboard when entering room from overhead.
  - 4. Extend conduits 3 inches above finished floor.
  - 5. Install metal conduits with grounding bushings and connect with grounding conductor to grounding system.
- G. Backboards: Install backboards with 96-inch dimension vertical. Butt adjacent sheets tightly, and form smooth gap-free corners and joints.

### 3.4 INSTALLATION OF CABLES

- A. Comply with NECA 1.
- B. General Requirements for Cabling:
  - 1. Comply with TIA/EIA-568-C.1.
  - 2. Comply with BICSI ITSIM, Ch. 6, "Cable Termination Practices."
  - 3. Terminate all conductors; no cable shall contain unterminated elements. Make terminations only at indicated outlets, terminals, cross-connects, and patch panels.
  - 4. Cables may not be spliced. Secure and support cables at intervals not exceeding 30 inches, not more than 6 inches from cabinets, boxes, fittings, outlets, racks, frames, and terminals.
  - 5. Install lacing bars to restrain cables, to prevent straining connections, and to prevent bending cables to smaller radii than minimums recommended by manufacturer.
  - 6. Bundle, lace, and train conductors to terminal points without exceeding manufacturer's limitations on bending radii, but not less than radii specified in BICSI ITSIM, "Cabling Termination Practices" Chapter. Install lacing bars and distribution spools.
  - 7. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
  - 8. Cold-Weather Installation: Bring cable to room temperature before de-reeling. Heat lamps shall not be used for heating.
  - 9. In the termination room (Telecom), install a 6-foot long service loop on each end of cable.
  - 10. Pulling Cable: Comply with BICSI ITSIM, Ch. 4, "Pulling Cable." Monitor cable pull tensions.
- C. UTP Cable Installation:

1. Comply with TIA/EIA-568-C.2.
2. Do not untwist UTP cables more than 1/2 inch from the point of termination to maintain cable geometry.

D. Open-Cable Installation:

1. Install cabling with horizontal and vertical cable guides in telecommunications spaces with terminating hardware and interconnection equipment.
2. Suspend UTP cable not in a wireway or pathway a minimum of 8 inches above ceilings by cable supports not more than 48 inches apart.
3. Cable shall not be run through structural members or in contact with pipes, ducts, or other potentially damaging items.

E. Installation of Cable Routed Exposed under Raised Floors:

1. Install plenum-rated cable only.
2. Install cabling after the flooring system has been installed in raised floor areas.
3. Coil cable 15 feet long not less than 12 inches in diameter at each feed point.

F. Group connecting hardware for cables into separate logical fields.

G. Separation from EMI Sources:

1. Comply with BICSI TDMM and TIA/EIA-569-B for separating unshielded copper voice and data communication cable from potential EMI sources, including electrical power lines and equipment.
2. Separation between open communications cables or cables in nonmetallic raceways and unshielded power conductors and electrical equipment shall be as follows:
  - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 5 inches.
  - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 12 inches.
  - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 24 inches.
3. Separation between communications cables in grounded metallic raceways and unshielded power lines or electrical equipment shall be as follows:
  - a. Electrical Equipment Rating Less Than 2 kVA: A minimum of 2-1/2 inches.
  - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 6 inches.
  - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 12 inches.
4. Separation between communications cables in grounded metallic raceways and power lines and electrical equipment located in grounded metallic conduits or enclosures shall be as follows:
  - a. Electrical Equipment Rating Less Than 2 kVA: No requirement.
  - b. Electrical Equipment Rating between 2 and 5 kVA: A minimum of 3 inches.
  - c. Electrical Equipment Rating More Than 5 kVA: A minimum of 6 inches.
5. Separation between Communications Cables and Electrical Motors and Transformers, 5 kVA or HP and Larger: A minimum of 48 inches.
6. Separation between Communications Cables and Fluorescent Fixtures: A minimum of 5 inches.

3.5 FIRESTOPPING

- A. Comply with requirements in Division 07 Section "Penetration Firestopping."
- B. Comply with TIA/EIA-569-B, "Firestopping."
- C. Comply with BICSI TDMM, "Firestopping Systems" Article.

3.6 GROUNDING

- A. Install grounding according to BICSI TDMM, "Grounding, Bonding, and Electrical Protection" Chapter.
- B. Comply with ANSI-J-STD-607-A.
- C. Locate grounding bus bar to minimize the length of bonding conductors. Fasten to wall allowing at least 2-inch clearance behind the grounding bus bar. Connect grounding bus bar with a minimum No. 4 AWG grounding electrode conductor from grounding bus bar to suitable electrical building ground.
- D. Bond metallic equipment to the grounding bus bar, using not smaller than No. 6 AWG equipment grounding conductor.

3.7 IDENTIFICATION

- A. Identify system components, wiring, and cabling complying with TIA/EIA-606-A. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
  - 1. Administration Class: 4.
  - 2. Color-code cross-connect fields. Apply colors to voice and data service backboards, connections, covers, and labels.
- B. Using cable management system software specified in Part 2, develop Cabling Administration Drawings for system identification, testing, and management. Use unique, alphanumeric designation for each cable and label cable, jacks, connectors, and terminals to which it connects with same designation. At completion, cable and asset management software shall reflect as-built conditions.
- C. Comply with requirements in Division 09 Section "Interior Painting" for painting backboards. For fire-resistant plywood, do not paint over manufacturer's label.
- D. Paint and label colors for equipment identification shall comply with TIA/EIA-606-A for Class 2 level of administration.
- E. Cable Schedule: Post in prominent location in each equipment room and wiring closet. List incoming and outgoing cables and their designations, origins, and destinations. Protect with rigid frame and clear plastic cover. Furnish an electronic copy of final comprehensive schedules for Project.
- F. Cabling Administration Drawings: Show building floor plans with cabling administration-point labeling. Identify labeling convention and show labels for telecommunications rooms, backbone pathways and cables, entrance pathways and cables, terminal hardware and positions, horizontal cables, work areas and workstation terminal positions, grounding buses and pathways, and equipment grounding conductors. Follow convention of TIA/EIA-606-A. Furnish electronic record of all drawings, in software and format selected by Owner.
- G. Cable and Wire Identification:
  - 1. Label each cable within 4 inches of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
  - 2. Each wire connected to building-mounted devices is not required to be numbered at device if color of wire is consistent with associated wire connected and numbered within panel or cabinet.
  - 3. Label each terminal strip and screw terminal in each cabinet, rack, or panel.
    - a. Individually number wiring conductors connected to terminal strips, and identify each cable or wiring group being extended from a panel or cabinet to a building-mounted device shall be identified with name and number of particular device as shown.
    - b. Label each unit and field within distribution racks and frames.

4. Identification within Connector Fields in Equipment Rooms and Wiring Closets: Label each connector and each discrete unit of cable-terminating and connecting hardware. Where similar jacks and plugs are used for both voice and data communication cabling, use a different color for jacks and plugs of each service.
- H. Labels shall be preprinted or computer-printed type with printing area and font color that contrasts with cable jacket color but still complies with requirements in TIA/EIA-606-A.
  1. Cables use flexible vinyl or polyester that flex as cables are bent.

### 3.8 FIELD QUALITY CONTROL

- A. Testing Agency: Engage a qualified testing agency to perform tests and inspections.
- B. Perform tests and inspections.
- C. Tests and Inspections:
  1. Visually inspect UTP and optical fiber cable jacket materials for NRTL certification markings. Inspect cabling terminations in communications equipment rooms for compliance with color-coding for pin assignments, and inspect cabling connections for compliance with TIA/EIA-568-C.1.
  2. Visually confirm Category 6 marking of outlets, cover plates, outlet/connectors, and patch panels.
  3. Visually inspect cable placement, cable termination, grounding and bonding, equipment and patch cords, and labeling of all components.
  4. Test UTP backbone copper cabling for DC loop resistance, shorts, opens, intermittent faults, and polarity between conductors. Test operation of shorting bars in connection blocks. Test cables after termination but not cross-connection.
    - a. Test instruments shall meet or exceed applicable requirements in TIA/EIA-568-C.2. Perform tests with a tester that complies with performance requirements in "Test Instruments (Normative)" Annex, complying with measurement accuracy specified in "Measurement Accuracy (Informative)" Annex. Use only test cords and adapters that are qualified by test equipment manufacturer for channel or link test configuration.
  5. UTP Performance Tests:
    - a. Test for each outlet. Perform the following tests according to TIA/EIA-568-C.1 and TIA/EIA-568-C.2:
      - 1) Wire map.
      - 2) Length (physical vs. electrical, and length requirements).
      - 3) Insertion loss.
      - 4) Near-end crosstalk (NEXT) loss.
      - 5) Power sum near-end crosstalk (PSNEXT) loss.
      - 6) Equal-level far-end crosstalk (ELFEXT).
      - 7) Power sum equal-level far-end crosstalk (PSELFEXT).
      - 8) Return loss.
      - 9) Propagation delay.
      - 10) Delay skew.
  6. Final Verification Tests: Perform verification tests for UTP systems after the complete communications cabling and workstation outlet/connectors are installed.
    - a. Voice Tests: These tests assume that dial tone service has been installed. Connect to the network interface device at the demarcation point. Go off-hook and listen and receive a dial tone. If a test number is available, make and receive a local, long distance, and digital subscription line telephone call.

- b. Data Tests: These tests assume the Information Technology Staff has a network installed and is available to assist with testing. Connect to the network interface device at the demarcation point. Log onto the network to ensure proper connection to the network.
- D. Document data for each measurement. Data for submittals shall be printed in a summary report that is formatted similar to Table 10.1 in BICSI TDMM, or transferred from the instrument to the computer, saved as text files, and printed and submitted.
- E. End-to-end cabling will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.

### 3.9 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel in cable-plant management operations, including changing signal pathways for different workstations, rerouting signals in failed cables, and keeping records of cabling assignments and revisions when extending wiring to establish new workstation outlets. Include training in cabling administration software.

END OF SECTION 271500

## SECTION 274133 - MASTER ANTENNA TELEVISION SYSTEM

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. This Section includes the following:
  - 1. Master antenna television systems using cable television service or direct broadcast satellite service as the signal source. Provide broadband coaxial cabling for distributing television signal to interface points.

#### 1.3 DEFINITIONS

- A. Agile Receiver: A broadband receiver that can be tuned to any desired channel.
- B. Broadband: For the purposes of this Section, wide bandwidth equipment or systems that can carry signals occupying in the frequency range of 54 to 1002 MHz. A broadband communication system can simultaneously accommodate television, voice, data, and many other services.
- C. Carrier: A pure-frequency signal that is modulated to carry information. In the process of modulation, it is spread out over a wider band. The carrier frequency is the center frequency on any television channel.
- D. CATV: Community antenna television; a communication system that simultaneously distributes several different channels of broadcast programs and other information to customers via a coaxial cable.
- E. dBmV: Decibels relative to 1 mV across 75 ohms. Zero dBmV is defined as 1 mV across 75 ohms.  $\text{dBmV} = 20 \log_{10}(V_1/V_2)$  where  $V_1$  is the measurement of voltage at a point having identical impedance to  $V_2$  (0.001 V across 75 ohms).
- F. Headend: The control center of the master antenna television system, where incoming signals are amplified, converted, processed, and combined into a common cable along with any locally originated television signals, for transmission to user-interface points. It is also called the "Central Retransmission Facility."
- G. RF: Radio frequency.
- H. TV Outlet: End point of Contractor's responsibility for Work of this Section. TV outlets are the 75-ohm terminals on device plates.



#### 1.4 SYSTEM DESCRIPTION

- A. Cable distribution system consisting of coaxial cables, user interfaces, signal taps and splitters. A new distribution power amplifier and splitters with new coaxial cabling to the new TV outlets shown in the drawings shall be provided. Input signal for the distribution amplifier will come from the existing TV signal in the hospital.
- B. Provide a RF CATV AM laser optical transmitter in existing hospital's 6<sup>th</sup> floor TDR to convert coax signal to fiber. Run fiber phase 5 TSR where the signal will be converted back from fiber to coax.

#### 1.5 PERFORMANCE REQUIREMENTS

- A. Minimum acceptable distribution system performance at all user-interface points for the entire specified spectrum, shall be as follows:
  - 1. RF Video Carrier Level: Between 2 and 10 dBmV.
  - 2. Relative Video Carrier Level: Within 3 dB to adjacent channel.
  - 3. Channel Frequency Response: Across any 6-MHz channel in 54- to 220-MHz frequency range, referenced to video, signal amplitude shall be plus or minus 1 dB, maximum.
  - 4. Carrier-to-Noise Ratio: 45 dB or more.
  - 5. RF Visual Signal-to-Noise Ratio: 43 dB or more.
  - 6. Cross Modulation: Less than minus 50 dB.
  - 7. Terminal Isolation from Television to Television: 25 dB, minimum.
  - 8. Hum Modulation: 2 percent, maximum.

#### 1.6 SUBMITTALS

- A. Product Data: For each type of product indicated.
- B. Shop Drawings: Show fabrication and installation details for television equipment.
  - 1. Include plans, elevations, sections, details, and attachments to other work.
  - 2. For coaxial cable, include the following installation data for each type used:
    - a. Nominal OD.
    - b. Minimum bending radius.
    - c. Maximum pulling tension.
  - 3. Wiring Diagrams: Power, signal, and control wiring; and grounding.
  - 4. Design Calculations: Calculate signal attenuation budget and show calculated line and equipment losses for the system, to show that proposed system layout can be expected to perform up to specification.
- C. Equipment List: Include every piece of equipment by model number, manufacturer, location, and date of original installation.
- D. Source quality-control test reports on coaxial cable sweep tests.
- E. Field quality-control test reports.

- F. Operation and Maintenance Data: For distribution system to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
  - 1. Lists of spare parts and replacement components recommended to be stored at the site for ready access.
  - 2. Include dimensioned plan and elevation views of components and enclosures. Show access and workspace requirements.

## 1.7 QUALITY ASSURANCE

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.
- B. Comply with NECA 1.
- C. Comply with NFPA 70.

## 1.8 PROJECT CONDITIONS

- A. Environmental Limitations: System components shall be equipped and rated for the environments where installed.

## 1.9 COORDINATION

- A. Coordinate size and location of raceway system, and provisions for electrical power to equipment of this Section.

# PART 2 - PRODUCTS

## 2.1 MANUFACTURERS

- A. In other Part 2 articles where titles below introduce lists, the following requirements apply to product selection:
  - 1. Manufacturers: Subject to compliance with requirements established by the equipment listed in the drawings, provide products by one of the manufacturers specified.

## 2.2 SYSTEMS REQUIREMENTS

- A. Components: Modular plug-in, heavy-duty, industrial- or commercial-grade units.
- B. Equipment: Silicon-based, solid-state, integrated circuit devices.
- C. RF and Video Impedance Matching: Signal-handling components, including connecting cable, shall have end-to-end impedance-matched signal paths. Match and balance devices used at

connections where it is impossible to avoid impedance mismatch or mismatch of balanced circuits to unbalanced circuits.

## 2.3 MATV EQUIPMENT

- A. Description: Signal-source components, distribution components, and interconnecting wiring. System shall receive signals from sources, amplify and process them, and distribute them to outlets for receiving sets.
- B. MATV System Quantitative Performance Requirements: Level and quality of signal at each outlet from each designated channel and source shall comply with Specifications below when tested according to 47 CFR 76.

## 2.4 DISTRIBUTION COMPONENTS

- A. Manufacturers:
  - 1. Blonder Tongue
  - 2. Channel Master
  - 3. Motorola Broadband Communications Sector.
  - 4. Pico Macom
- B. Distribution components shall be for signal processing and distribution downstream from headend equipment.
- C. Broadband Amplifier:
  - 1. Frequency Range: 54 to 750 MHz.
  - 2. Frequency Response: Plus or minus 1.0 dB across passband.
  - 3. Maximum Noise: 10 dB.
  - 4. Minimum Return Loss: 16 dB.
  - 5. I/O Impedance: 75 ohms
  - 6.
- D. Signal Splitters and Isolation Taps: Metal-enclosed directional couplers with brass connector parts.
  - 1. Return Loss: 17 dB.
  - 2. RFI Shielding: 100 dB.
  - 3. Isolation: 25 dB.
  - 4. Impedance: 75 ohms for input and output terminals.
  - 5. Electrically powered components shall be UL labeled.
- E. Attenuators: Passive, of fixed value, used to balance signal levels.
- F. Terminating Resistors: Enclosed units rated 0.5 W and matched for coaxial impedance.
- G. User-Interface Device (TV Outlets): Flush, female-type outlets for mounting in standard outlet box, with metallic parts of anodized brass, beryllium copper, or phosphor bronze. Cable connector mounting shall be semi-recessed so its protrusion is flush with the plane of device plate.

1. Cable Connector: Female, Type F.
2. Wall Plates: Match materials and finish of power outlets in same space.
3. Attenuation: Less than 0.1 dB.
4. Voltage Standing-Wave Ratio: Less than 1.15 to 1.

## 2.5 CABLES

- A. Manufacturers:
  1. Alpha Wire Company.
  2. Belden Inc.; Electronics Division.
  3. Coleman Cable.
  4. CommScope Properties, LLC.
  5. West Penn Wire/CDT.
- B. Cable Characteristics: Broadband type, recommended by cable manufacturer specifically for broadband MATV applications. Coaxial cable and accessories shall have 75-ohm nominal impedance with a return loss of 20 dB minimum from 7 to 806 MHz, and shall be listed to comply with NFPA 70, Articles 810 and 820.
- C. RG-6/U, Plenum-Rated Indoor Distribution Cable (Horizontal Drop): No. 16 AWG, solid bare copper conductor; gas-injected foam-PE insulation. Double shielded with 100 percent aluminum-foil shield, 60 percent aluminum braid. Copolymer jacket. NFPA 70, Type CATV and UL 910.
- D. RG-11/U, Plenum-Rated Indoor Distribution Cable (Trunk): No. 14 AWG, solid bare copper conductor, gas-injected foam-PE insulation. Double shielded with 100 percent aluminum foil shield, 60 percent aluminum braid. Copolymer jacket. NFPA 70, Type CATV and UL 910.

## 2.6 CABLE CONNECTORS

- A. Manufacturers:
  1. Amphenol Corporation.
  2. B&L Coaxial Connections, Ltd.
  3. Connect-Tech Products.
  4. Leviton Voice & Data Division.
- B. MATV Coaxial Cable Connectors: Type F, 75 ohms.

## 2.7 SOURCE QUALITY CONTROL

- A. Cable products shall be sweep tested at the factory before shipping at frequencies from 5 MHz to 1 GHz. Sweep test shall test the frequency response, or attenuation over frequency, of a cable by generating a voltage whose frequency is varied through the specified frequency range and graphing the results.
- B.

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine pathway elements intended for coaxial cable installation. Check raceways, cables, trays, and other elements for compliance with accessibility for installation and maintenance, and other conditions affecting installation.
- B. Examine walls, floors, roofs, equipment bases, and roof supports for suitable conditions where television equipment is to be installed.
- C. Proceed with installation only after unsatisfactory conditions have been corrected.

### 3.2 INSTALLATION

- A. Wiring Method: Install cables in raceways except in accessible indoor ceiling spaces, attics and as otherwise indicated. Conceal raceways and wiring except in unfinished spaces.
- B. Grounding: According to recommendations in IE EE 142 and IEEE 1100.

### 3.3 COAXIAL CABLE INSTALLATION

- A. Cold-Weather Installation: Bring cable to room temperature before dereeling. Heat lamps may not be used for heating.
- B. Cable may not be installed in same raceway with power cable.
- C. Coaxial cable shall not be spliced except on plywood backboards in termination rooms, or in cabinets designated for the purpose.
- D. Do not use water-based cable pulling lubricants with PVC-jacketed cable.
- E. Do not exceed manufacturer's recommended minimum bending radiuses
- F. Pulling Cable: Do not exceed manufacturer's recommended pulling tensions. Do not install bruised, kinked, scored, deformed, or abraded cable. Do not splice cable between termination, tap, or junction points. Remove and discard cable if damaged during installation and replace it with new cable.
- G. Exposed Cable: Install parallel to building lines, follow surface contours, and support cable according to manufacturer's written instructions. Do not run adjacent and parallel to power or data cables.
- H. Cable Support: Install supports at intervals recommended in writing by cable manufacturer. Install supports within 6 inches of connector so no weight of cable is carried by connector. Use no staples or wire ties, pull nylon tie-wraps snug, and do not over tighten.

- I. Signal Equalization: Where system performance may be degraded in certain operating modes, revise component connections and install distribution amplifiers and attenuators as required, providing a balanced signal across the system.

### 3.4 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals according to Division 26 Section "Identification for Electrical Systems."

### 3.5 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connections. Report results in writing.
- B. Inspection: Verify that units and controls are properly installed, connected, and labeled, and that interconnecting wires and terminals are identified.
- C. Pretesting: Align and adjust system and pretest components, wiring, and functions to verify that they comply with specified requirements. Replace malfunctioning or damaged items. Retest until satisfactory performance and conditions are achieved. Prepare television equipment for acceptance and operational testing as follows:
  - 1. Use an agile receiver and signal strength meter or spectrum analyzer for testing.
  - 2. CATV Sources: Connect receiver to an agile demodulator or CATV set-top converter at CATV service entrance to the facility.
  - 3. Satellite Earth-Station System Sources: Adapt receiver to the output of satellite-TV receiver.
- D. Test Schedule: Schedule tests after pretesting has successfully been completed and system has been in normal functional operation for at least 14 days. Provide a minimum of 10 days' notice of test schedule.
- E. Operational Tests: Perform operational system tests to verify that system complies with Specifications. Include all modes of system operation. Test equipment for proper operation in all functional modes.
- F. Distribution System Acceptance Tests:
  - 1. Field-Strength Instrument: Rated for minus 40-dBmV measuring sensitivity and a frequency range of 54 to 812 MHz, minimum. Provide documentation of recent calibration against recognized standards.
  - 2. Signal Level and Picture Quality: Use a field-strength meter or spectrum analyzer, and a standard TV receiver to measure signal levels and check picture quality at all TV outlets.
    - a. Test the signal strength in dBmV at 55 and 750 MHz.
    - b. Minimum acceptable signal level is 0 dBmV (1000 mV).
    - c. Maximum acceptable signal level over the entire bandwidth is 12 dBmV.
    - d. Television receiver shall show no evidence of cross-channel intermodulation, ghost images, or beat interference..

- G. Qualitative and Quantitative Performance Tests: Demonstrate reception quality of color-television program transmissions at each user interface from each designated channel and source. Quality shall be equal to or superior than that obtained with performance checks specified below, using a standard, commercial, cable-ready, color-television receiver. Level and quality of signal at each outlet and from each designated channel and source shall comply with the following Specifications when tested according to 47 CFR 76:
  - 1. RF video-carrier level.
  - 2. Relative video-carrier level.
  - 3. Broadband frequency response.
  - 4. Channel frequency response.
  - 5. Carrier-to-noise ratio.
  - 6. RF visual signal-to-noise ratio.
  - 7. Cross modulation.
  - 8. Terminal isolation.
  - 9. Hum modulation.
- H. Record test results.
- I. Retest: Correct deficiencies identified by tests and observations and retest until requirements specified in Part 1 are met.

### 3.6 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain MATV equipment.
  - 1. Train Owner's maintenance personnel on procedures and schedules for troubleshooting, servicing, and maintaining equipment.
  - 2. Demonstrate methods of determining optimum alignment and adjustment of components and settings for system controls.
  - 3. Refer to Division 01 Section "Demonstration and Training."
- B. Conduct a minimum of two hours' training as specified in instructions to Owner's employees in Division 01 Section "Demonstration and Training."

END OF SECTION 271433

## **SECTION 275117 - NETWORKED PUBLIC ADDRESS AND PAGING SYSTEM**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. This Section includes the installation of a new networked public address and overhead paging system components. It includes requirements for Biamp VOCIA Networked PA system components including, but not limited to, the following:
  - 1. Amplifier modules
  - 2. Speakers
  - 3. Wiring System
  - 4. Programming
- B. Related Requirements:
  - 1. "Raceways", for raceways used for overhead paging system cables.
  - 2. "Electrical Boxes and Fittings", for boxes, cabinets, and fittings used with overhead paging systems.

#### **1.3 SYSTEM DESCRIPTION**

- A. General: The networked public address paging system work shall be an addition to the existing VOCIA system for delivering audio signals to distributed programmable amplifier modules via the facility's Ethernet network.
- B. Functional Performance: Components and system features and functions shall include, but are not limited to, the following:
  - 1. Meet the following performance parameters as measured in 1/3 octave bands:
    - a. From 100 Hz to 2kHz, flat within plus or minus 2dB.
    - b. Above 2kHz, slope down along an approximate 3dB octave slope to 8kHz.
  - 2. When driven to maximum output, clipping shall first occur in power amplifiers.
  - 3. No noise, hum, RFI pickup or distortion shall be audible under normal operating conditions.
  - 4. The overhead paging system shall reproduce program material at a level of 85 dBA without audible distortion.

#### **1.4 ACTION SUBMITTALS**

- A. Product data for each type of product specified.
- B. Shop drawings detailing equipment layout elevations and specific installation requirements.
- C. Wiring Diagrams detailing wiring for power, signal, and control, differentiating clearly between manufacturer installed wiring and field installed wiring. Identify terminal numbers and wiring color codes to facilitate installation, operation, and maintenance.
- D. System operation description of the telephone audio/zone selection communication to the paging system.



1.5 QUALITY ASSURANCE

- A. Installer Qualifications: Engage an experienced Installer who is a factory authorized sales and service representative of those manufacturers specified to perform the work of this Section. Refer to Division 1 Section "Definitions and Standards" for definition of experienced Installer. Upon request, submit evidence of such qualifications to the specifying authority.
- B. Electrical Component Standard: Provide work complying with applicable requirements of NFPA 70 "National Electrical Code."
- C. EIA Compliance: Comply with the following Electronics Industries Association Standards:
  - 1. Sound Systems, EIA 160.2.
  - 2. Loudspeaker, Dynamic Magnetic Structures, and Impedance, EIA 299 A.
  - 3. Racks, Panels, and Associated Equipment, EIA 310 A.
  - 4. Amplifiers for Sound Equipment, SE 101 A.
  - 5. Speakers for Sound Equipment, SE 103.
  - 6. Microphones for Sound Equipment, SE 105.
  - 7. UL Compliance: Comply with requirements of UL 50.
- D. Coordination of Work: Coordinate the Work of this Section with the requirements of the Owner's paging system technicians and perform the following:
  - 1. Pre-Installation Meeting: Meet jointly with the representatives of the Owner, to exchange information and agree on details of installation interfaces, current system operations including zone identification and classification, and any other circumstances that impact on the completion of the work of this Section.
  - 2. Record agreements reached in the meeting and distribute the record to the other participants.

1.6 WARRANTY REQUIREMENTS

- A. In addition to the requirements of Division 1 and other sections of this specification, provide complete warranty repair or replacement for a minimum of one year after date of substantial completion at no cost to owner, except in the case of obvious abuse
- B. Disclaimers and Limitations: Manufacturer's disclaimers and limitations on product warranties do not relieve the Contractor of the warranty on the Work that incorporates the products, nor does it relieve suppliers, manufacturers, and subcontractors required to countersign special warranties with the Contractor.
- C. Reinstatement of Warranty: When Work covered by a warranty has failed and been corrected by replacement or rebuilding, reinstate the warranty by written endorsement. The reinstated warranty shall be equal to the original warranty.
- D. Related Damages and Losses: When correcting warranted Work that has failed, remove and replace other Work that has been damaged as a result of such failure or that must be removed and replaced to provide access for correction of warranted Work.
- E. Replacement Cost: Upon determination that Work covered by a warranty has failed, replace or rebuild the Work to an acceptable condition complying with requirements of Contract Documents. The Contractor is responsible for the cost of replacing or rebuilding defective Work regardless of whether the Owner has benefited from use of the Work through a portion of its anticipated useful service life.
- F. Owner's Recourse: Written warranties made to the Owner are in addition to implied warranties, and shall not limit the duties, obligations, rights and remedies otherwise available under the law, nor shall warranty periods be interpreted as limitations on time in which the Owner can enforce such other duties, obligations, rights, or remedies.

1. Rejection of Warranties: The Owner reserves the right to reject warranties and to limit selections to products with warranties not in conflict with requirements of the Contract Documents.
- G. The Owner reserves the right to refuse to accept Work for the Project where a special warranty, certification, or similar commitment is required on such Work or part of the Work, until evidence is presented that entities required to countersign such commitments are willing to do so.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following (for each type of product) as listed in the drawings and these specifications:
  1. Biamp VOCIA (Amplifiers).
  2. Atlas Sound (Speakers only)
  3. Bogen (Speakers only)
  4. Lowell (Speakers only)

### 2.2 SYSTEM REQUIREMENTS

- A. General: Provide complete and fully functional networked public address and paging systems using materials and equipment of types, sizes, ratings, and performances as indicated. Use materials and equipment that comply with referenced standards and manufacturers' standard design and construction in accordance with published product information. Coordinate the features of materials and equipment so they form an integrated system with components and interconnections matched for optimum performance of specified functions.

### 2.3 EQUIPMENT AND MATERIALS

- A. General: Provide all solid state components fully rated for continuous duty at the ratings indicated or specified. Select equipment for normal operation on input power supplied at 105 130 V, 60 Hz.
- B. Programmable Amplifier Modules: Provide the Biamp VOCIA amplifier as indicated in the drawings.
- C. Loudspeakers shall be a 8" dual cone type with a 10 ounce, ceramic magnet. Power handling rating shall be 5 watts continuous with a sensitivity of 94 dB at 1 meter/1 watt and frequency response of +/- 5 dB from 80 to 15,000 Hz. The speaker shall have an impedance of 8 ohms with no 70V transformer required. Recessed ceiling mounted speaker assemblies shall mount on an Atlas Sound 51-8 or similar baffle on an EZ-95-8 series or similar enclosure. Provide the Atlas Sound C10A speaker (or equivalent) for general purpose locations.
- D. 4-line VOIP-1-4
- E. One DS-10 station

## PART 3 - EXECUTION

### 3.1 EXAMINATION

- A. Examine conditions for compliance with requirements and other conditions affecting the performance of the Networked Public Address and Paging System work.
- B. Do not proceed until unsatisfactory conditions have been corrected.
- C. Verify compliance of the following items before beginning sound equipment installation.
- D. No cables spliced except at standard barrier terminal blocks inside equipment cabinet.
- E. Cables marked at each end with permanent wire labels such as Brady or equal.
- F. Isolated ground run back to main electrical panel from paging equipment cabinet.
- G. Specified conduit, cables, speaker enclosures and equipment cabinets are properly installed.

### 3.2 INSTALLATION

- A. General: Install system in accordance with NFPA 70 and other applicable codes. Install equipment in accordance with manufacturer's written instructions.
- B. Speakers:
  - 1. Confirm polarity of speaker before installation and wire to maintain uniform polarity.
  - 2. Neatly mount speaker grilles, panels, connector plates, etc., tight, plumb, and square unless indicated otherwise on drawings.
  - 3. Provide brackets, screws, adapters, springs, rack mounting kits, etc., recommended by manufacturer for correct assembly and installation of speaker assemblies and electronics components.
  - 4. Speakers shall be connected in a series-parallel methodology as indicated in the drawings. An impedance bridge will be required to read all speaker loops as they are terminated to the amplifier modules. Amplifier loss due to incorrect impedances shall be the responsibility of the Installer.
- C. Amplifier Modules:
  - 1. Assure sufficient ventilation for adequate cooling of equipment.
  - 2. Securely fasten equipment plumb and square in place according to manufacturer recommendations.
  - 3. Connect powered components to 120 VAC outlets on transient voltage surge suppressor.
  - 4. Cables:
    - a. Leave sufficient service loops of uniform length.
    - b. Do not parallel or branch cables and lines except at standard barrier terminal blocks using the provided phoenix connectors. Label all branch wiring.
    - c. Secure cables to equipment cabinet with wire ties to ensure neat installation. Do not use double-stick tape or sticky-back cable anchors.
- D. Repairs: Wherever walls, ceilings, floors, or other building finishes are cut for installation, repair, restore, and refinish to original appearance.

### 3.3 FIELD QUALITY CONTROL

- A. Manufacturer's Field Services: Provide services of a factory authorized service representative to supervise the field assembly and connection of components and the pre-testing, testing, and adjustment of the system.
- B. Pre-testing: Upon completing installation of the system, align, adjust, and balance the system and perform complete testing. Determine the conformance of the system to the requirements of the Drawings and Specifications. Correct deficiencies observed in pre-testing. Replace

malfunctioning or damaged items with new, and retest until materials satisfactory performance and conditions are achieved.

3.4 COMMISSIONING

- A. Occupancy Adjustments: When requested by the Architect or the Engineer within one year of date of substantial completion, provide onsite assistance in adjusting sound levels, zone assignments, and adjusting controls to suit actual occupied conditions. Provide one trip for this purpose.

3.5 CLEANING AND PROTECTION

- A. Prior to final acceptance, clean system components and protect from damage and deterioration.

END OF SECTION 275117

## **SECTION 275223 - NURSE CALL SYSTEM**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

- A. This Section includes system hardware and software that shall consist of nurse/patient communication systems comprised of nurse consoles, control stations, dome lights, entertainment call cords, call cords, pull cord stations, emergency push button stations, and wiring.
- B. All necessary equipment required to meet the intent of these specifications, whether or not enumerated within these specifications, shall be supplied and installed to provide a complete and operating nurse/patient communications network in the indicated areas.
- C. This section requires that rough-in materials for this section be provided by the Division 26 installer for installation under Division 26. Rough-in materials include but are not limited to conduit, junction boxes, alternative raceway, and device enclosures. Cable for this section is to be provided by the installer for this section.

#### **1.3 SUBMITTALS**

- A. Any supplying contractor proposing a system or equipment which does not meet the basic functional specifications as stated herein must provide full statement of exceptions 10 days prior to the time of bid. This option shall be exercised at the discretion of the owner/specifying authority.
- B. Prior to commencement of work, the supplying contractor shall submit a complete submittal set which shall include the following:
  - 1. Cabling Diagrams: Single-line block diagrams showing cabling interconnection of all components for this specific equipment. Include cable type for each interconnection.
  - 2. Wiring Diagrams: Power, signal, and control wiring.
  - 3. Station Installation Details: For built-in equipment; dimensioned and to scale.
  - 4. Equipment Cabinet Drawings: Dimensioned and to scale.
- C. Coordination Drawings: Detail system components that fit, match, and line up with provisions made in equipment specified in other Sections or in separate contracts:
  - 1. Patient head-wall units or wall elevations.
  - 2. Nurse Call Master consoles.
  - 3.

- D. Manufacturer Certificates: Signed by manufacturers certifying that nurse call equipment complies with requirements.
- E. Field Tests Reports and Observations: Include record of final adjustments certified by Installer.
- F. Operation and Maintenance Data: For nurse call equipment to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 1 "Closeout Procedures " and "Operation and Maintenance Data," include the following:
  - 1. Operating instructions.
  - 2. Troubleshooting guide.
  - 3. Wiring diagrams and terminal identification.
  - 4. Equipment parts list.
  - 5. Product data for types and sizes of wires and cables used.
- G. Warranty Statement: Special warranty requirements as specified in this Section.

#### 1.4 QUALITY ASSURANCE

- A. Installer Qualifications: Manufacturer's authorized representative who is trained and approved for installation of units required for this Project. The Installer shall be able to fully support the listed service and warranty requirements as specified herein.
- B. Manufacturer Qualifications: A firm experienced in manufacturing equipment similar to that indicated for this Project and that maintains technical support services capable of providing user with training, parts, and emergency maintenance and repair with a 24-hour-maximum response time.
- C. Source Limitations: Obtain nurse call equipment components through one source from a single manufacturer.
- D. Electrical Components, Devices, and Accessories: Listed and labeled according to UL 1069 as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

#### 1.5 COORDINATION

- A. Coordinate patient control units with items controlled that are not part of nurse call equipment.
  - 1. TV: Channel selection and volume.
- B. Coordinate wiring paths and maintenance access at locations listed below. Coordinate trim features and finishes at these locations to present a unified design appearance.
  - 1. Patient head-wall installations.
  - 2. Patient consoles.
  - 3. Nurse station.

## 1.6 WARRANTY

- A. The installing contractor shall provide a warranty on the system which shall include all necessary labor and equipment to maintain the system(s) in full operation for a period of one year from the date of acceptance.
- B. Manufacturer shall provide, free of charge, product firmware/software upgrades throughout the warranty period for any product feature enhancements.
  - 1.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1.
  - 2. ASCOM (IDEACOM)

### 2.2 SYSTEM REQUIREMENTS

- A. Coordinate the features of materials and equipment to form an integrated system. Match components and interconnections for optimum performance of specified functions. System shall be microprocessor based, but independent of the facility local area network, with a segmented platform configuration providing that system or equipment failures are locally mitigated without global system shutdowns or resets.
- B. Expansion Capability: Equipment ratings, housing volume, spare keys, switches, relays, annunciator modules, terminals, and cable conductor quantities adequate to increase the number of stations in the future by 20 percent above those indicated without adding internal or external components or main trunk cable conductors.
- C. Resistance to Electrostatic Discharge: System, components, and cabling, and the selection, arrangement, and connection of materials and circuits, shall be protected against damage or diminished performance when subjected to electrostatic discharges of up to 25,000 V in an environment with a relative humidity of 20 percent or less.
- D. Equipment: Solid state, modular.
- E. Wall-Mounted Component Connection Method: Components connect to system wiring in back boxes with factory-wired plug connectors.

### 2.3 FUNCTIONAL PERFORMANCE

- A. Station Selection: Master station is capable of selectively communicating with other stations or groups of stations on its system by operating selector switches.

- B. Master Station Privacy: Capable of conversing with individual stations in complete privacy.
- C. Hands Free: Called station is capable of conversing hands free.
- D. Annunciation: At the master station, a tone announces an incoming call and a visual indication is displayed on the console and identifies the calling station and indicates the priority of the call. LED/LCD lighted displays or touchscreens identify stations selected for outgoing calls.
- E. System Reset at Master Station: When a normal incoming call is canceled, associated lights and audible tones are extinguished, and the system is reset when the station switch is returned to the normal position after responding to a call.
- F. Patient Station Call: Activates the call-placed lamp at patient station, zone, and corridor dome lights. It sounds a tone and lights the call lights at staff/duty stations and actuates annunciation at the master station. When the calling station is selected at the master station, the patient can converse with the master station without moving and without raising or directing the voice. During voice communications, entertainment audio at the calling station is automatically muted.
- G. Pull-Cord Call Station and Emergency-Call Station Call: Activates call-placed lamp and corridor dome light, and flashes zone light. Master station tone pulses with visual display for that room flashes. When master station acknowledges the call, the tone stops but the display and lights continue to function until the call is canceled at the point of origin.
- H. Handset Operation: Lifting handset on master station disconnects speaker microphone and transfers conversation to the handset.
- I. Station Privacy: No patient, staff, or duty station can be remotely monitored without the lighting of a warning lamp at the monitored station.
- J. Patient Station Cord Set: When a patient station cord-set plug is removed from the jack in the station faceplate, a patient station call is initiated as described above. When the master station call button for the station is pressed, the tone stops but lights continue to flash until the call is canceled at the point of origin or the plug is reinserted or replaced with a dummy plug.
- K. Patient Station/Pillow Speaker: Controls entertainment volume and channel selection. Speaker is used for both nurse communication and entertainment sound. Entertainment sound is automatically muted when station is communicating with master station.

## 2.4 EQUIPMENT DESCRIPTIONS

- A. Master Station: Speaker-microphone unit with operating controls.
  - 1. LED/LCD displays with "button" controls or touchscreen technology to designate location and priority of calling stations and called stations.



- a. Pulse rate of incoming-call lights denotes priority of calls awaiting response.
  2. Station Selection Controls: Touchscreen controls or console "button" controls select stations for two-way voice communications.
  3. Signal Tones: Announce incoming calls.
  4. Volume Control: Regulates incoming-call volume.
  5. Privacy Handset with Hook Switch: Of the type that does not require push-to-talk switch, attached to each station, unless otherwise indicated.
- B. Central Equipment Cabinet: Lockable metal. Houses amplifiers, tone generators, power supplies, controls, terminal strips, and other components.
  1. Amplifier: With fidelity and overall gain necessary to achieve the sound transmission and reproduction characteristics specified, considering interoperability with the installed speakers/microphones and wiring.
    - a. Power Output: Not less than 3 W at a total harmonic distortion not exceeding 5 percent.
    - b. Hum and Noise: 60 dB below full output with normal input open.
    - c. Volume Control: Concealed within the amplifier unit to control the volume of sound reproduced at all stations.
    - d. Protection: Circuit to prevent damage to the amplifier in case shorted or open output.
    - e.
  2. System Power Supply: For low-voltage operation of the call system.
    - a. Equipment Rating: Suitable for continuous operation between 32 and 120 deg F (0 and 49 deg C), from a primary line voltage between 105- to 125-V ac, 60 Hz.
    - b. Output: Regulated low voltages with protection against overloads. Line-to-load regulation shall not exceed 2-1/2 percent with ripple and noise remaining below the 10 mV, RMS level.
    - c. Overload Protection: Electronic fold-back circuit set to limit the volt-ampere output to less than 100 VA during overloaded or shorted output. Restore power output automatically on removal of overload without resetting circuit breakers or replacing fuses.
  3. Power-on indicator lamp.
  4. Surge Protective Device: Comply with Division 26 Section "Transient Voltage Suppression" for auxiliary panel suppressors, with LED indicator lights for power and protection status.
  5. Battery Backup Unit: Sealed nickel-cadmium, wet-cell battery supplies power through an automatic switch when normal power fails, for a period of not less than six minutes at rated output.
    - a. Automatic retransfer to normal power, after a 15-minute time delay.
    - b. Two-rate battery charger with an automatic trickle rate and a recharge rate.
- C. Speaker/Microphones:
  1. Type: Permanent-magnet, dynamic or ceramic, protected against dust and humidity.
  2. Sound Reproduction: Sound level of 90 dB plus or minus 3 dB at a distance of 48 inches on the axis without overdriving or distorting any frequencies between 300 and 3000 Hz when installed in an enclosure or in the pillow speaker.

3. Power Handling Capacity: Not susceptible to damage from overdriving within the range of power available from the amplifier.
  4. Impedance Matching: Coordinated and matched to the input and output circuits of the amplifier, both for single connection and for group monitoring, to provide the sound reproduction specified. Subsystems or components shall not be combined, which could cause unacceptable distortion such as feedback between pillow speakers and unmuted room speaker/microphone combinations. This protection shall extend throughout the entire range of operation (volume control) of all components.
- D. Single-Patient Station: Each bedside control station shall be capable of the following functions:
1. At least 6 programmable call levels (including associated sub-stations).
  2. Sound Reproduction: Sound level of 90 dB plus or minus 3 dB at a distance of 48 inches on the axis without overdriving or distorting any frequencies between 300 and 3000 Hz when installed in an enclosure or in the pillow speaker.
  3. Entertainment/pillow speaker intercom.
  4. Entertainment muting shall occur when nurse call audio is established.
  5. Support and supervise up to 5 sub-stations including pull-cord, push-button, code blue, staff register, and fire/auxiliary modules.
  6. Provide interface to local equipment alarm contacts (i.e. ventilator, IV drip, fire detector, etc.) to notify console of local alarm condition in patient room.
- E. Staff and Duty Stations: Audible call-tone signal device, speaker microphone with dynamic cone, monitor lamp, reset switch, routine-call lamp, emergency-call lamp, and call push button; assembled under a single faceplate.

## 2.5 MISCELLANEOUS EQUIPMENT COMPONENT DESCRIPTIONS

- A. Emergency-Call Station: Locking-type push button, labeled "Push to Call Help"; reset trigger to release push button and cancel call; and call-placed lamp; mounted in a single faceplate.
- B. Pull-Cord Call Station (Bath): Water-resistant construction. Includes the following, mounted under a single faceplate:
1. Pull-Down Switch: Lever-locking type, labeled "Pull Down to Call Help."
  2. Reset trigger.
  3. Call-placed lamp.
- C. Call-Button Cord Set: Plug and 72-inch white cord; equipped with momentary-action, call-button switch.
1. Ethylene oxide, sterilizable.
  2. Washable cord.
  3. Palladium switch contacts in high-impact white housing with cord-set strain relief.
  4. Attachment: Stainless-steel bed clamp with permanently attached Mylar strap.
  5. Quantity: 3 cord sets for every 10 patient beds.
- D. Indicator Lamps: Light-emitting-diode type with 20-year rated life, unless otherwise indicated.

- E. Station Faceplates: High-impact plastic, color by architect. Molded or machine-engraved labeling identifies indicator lamps and controls.
- F. Corridor Dome Lights and Zone Lights: Four-lamp signal lights (minimum).
  - 1. Lamps: Front replaceable without tools, low voltage with rated life of 7500 hours. Barriers are such that only one color is displayed at a time.
  - 2. Lenses: Heat-resistant, shatterproof, translucent polymer that will not deform, discolor, or craze when exposed to hospital cleaning agents.
  - 3. Filters: Two per unit, amber and red.
- G. Cable: Features include the following, unless otherwise indicated:
  - 1. Conductors: Jacketed single and multiple twisted-pair, copper cables. Sizes and types as recommended by equipment manufacturer. All cable shall be plenum rated.
- H. Grounding Components: As specified in Division 26 Section "Grounding."

## PART 3 - EXECUTION

### 3.1 INSTALLATION

- A. Wiring Method: Install wiring in raceway except within consoles, desks, counters; and in accessible ceiling spaces, where loose air cable wiring methods may be used. Use UL-listed plenum cable in environmental air spaces including plenum ceilings. Conceal cable and raceway wiring except in unfinished spaces.
- B. Install cables without damaging conductors, shield, or jacket.
- C. Do not bend cables, in handling or in installing, to smaller radii than minimums recommended by manufacturer.
- D. Pull cables without exceeding cable manufacturer's recommended pulling tensions.
  - 1. Pull cables simultaneously if more than one is being installed in same raceway.
  - 2. Use pulling compound or lubricant if necessary. Use compounds that will not damage conductor or insulation.
  - 3. Use pulling means, including fish tape, cable, rope, and basket-weave wire or cable grips, that will not damage media or raceway.
- E. Install exposed raceways and cables parallel and perpendicular to surfaces or exposed structural members, and follow surface contours. Secure and support cables by straps, staples, or similar fittings designed and installed so as not to damage cables. Secure cable at intervals not exceeding 30 inches and not more than 6 inches from cabinets, boxes, or fittings.
- F. Wiring within Enclosures: Provide adequate length of conductors. Bundle, lace, and train conductors to terminal points with no excess. Provide and use lacing bars in cabinets.

- G. Separation of Wires: Separate speaker-microphone, line-level, speaker-level, and power-wiring runs. Run in separate raceways or, if exposed or in same enclosure, provide 12-inch minimum separation between conductors to speaker microphones and adjacent parallel power and telephone wiring. Provide separation as recommended by equipment manufacturer for other conductors.
- H. Splices, Taps, and Terminations: Make splices, taps, and terminations on numbered terminal strips in junction, pull, and outlet boxes, terminal cabinets, and equipment enclosures. Install terminal cabinets where there are splices, taps, or terminations for eight or more conductors.
- I. Impedance and Level Matching: Carefully match input and output impedances and signal levels at signal interfaces. Provide matching networks if required.
- J. Identification of Conductors and Cables: Retain color-coding of conductors and apply wire and cable marking tape to designate wires and cables so all media are identified in coordination with system wiring diagrams. Label stations, controls, and indications using approved consistent nomenclature.
  - 1. Label each cable within 4 inches of each termination and tap, where it is accessible in a cabinet or junction or outlet box, and elsewhere as indicated.
  - 2. Prepare cable administration drawings to show building floor plans with cable administration point labeling. Identify labeling convention and show labels for terminal hardware and positions, cables, stations and devices and equipment grounding conductors.

### 3.2 GROUNDING

- A. Ground cable shields and equipment to eliminate shock hazard and to minimize ground loops, common-mode returns, noise pickup, cross talk, and other signal impairments.
- B. Signal Ground Terminal: Locate at main equipment cabinet. Isolate from power system and equipment grounding except at connection to main building ground bus.
- C. Grounding Provisions: Comply with requirements in Division 26 Section "Grounding."

### 3.3 FIELD QUALITY CONTROL

- A. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect, test, and adjust field-assembled components and equipment installation, including connections, and to assist in field testing. Report results in writing.
- B. Test Procedure: Comply with the following:
  - 1. Schedule tests a minimum of seven days in advance of performance of tests.
  - 2. Report: Submit a written record of test results.
  - 3. Operational Test: Perform an operational system test, and demonstrate proper operations, adjustment, and sensitivity of each station. Perform tests that include originating station-to-station and all-call messages and pages at each nurse call station. Verify proper routing, volume levels, and freedom from noise and

distortion. Test each available message path from each station on the system. Meet the following criteria:

- a. Speaker Output: 90 dB plus or minus 3 dB, 300 to 3000 Hz.
  - b. Gain from patient's bedside station to nurse station, with distortion less than 65 dB (plus or minus 3 dB, 300 to 3000 Hz).
  - c. Signal-to-Noise Ratio: Hum and noise level at least 45 dB below full output.
4. Test Procedure:
- a. Frequency Response: Determine frequency response of two transmission paths by transmitting and recording audio tones.
  - b. Signal-to-Noise Ratio: Measure the ratio of signal to noise of the complete system at normal gain settings, using the following procedure: Disconnect a speaker microphone and replace it in the circuit with a signal generator using a 1000-Hz signal. Measure the ratio of signal to noise and repeat the test for four speaker microphones.
  - c. Distortion Test: Measure distortion at normal gain settings and rated power. Feed signals at frequencies of 300, 400, 1000, and 3000 Hz into each nurse call equipment amplifier, and measure the distortion in the amplifier output.
- C. Retesting: Rectify deficiencies indicated by tests and completely retest work affected by such deficiencies at Contractor's expense. Verify by the system test that the total system meets these Specifications and complies with applicable standards. Report results in writing.
- D. Inspection: Verify that units and controls are properly labeled and interconnecting wires and terminals are identified.

### 3.4 ADJUSTING

- A. Occupancy Adjustments: When requested within 12 months of date of Substantial Completion, provide on-site assistance in adjusting sound levels and controls to suit actual occupied conditions. Provide up to three visits to Project during other-than-normal operating hours for this purpose.

### 3.5 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel and caregiver staff to adjust, operate, and maintain nurse call equipment. Refer to Division 1 Section "Closeout Procedures" and "Demonstration and Training."

### 3.6 TRAINING

- A. Both manufacturer/factory supported and local installer training shall be provided to all nursing staff. Floor nurses/staff shall receive training appropriate to their needs, and likewise, unit secretaries (or any person whose specific responsibilities include answering patient calls and dispatching staff) shall receive operational training appropriate to their needs and charge nurses (or any person whose specific

responsibilities include scheduling staff to patient assignments) shall receive operational training appropriate to their needs.

- B. The training shall be comprehensive enough to allow the local in-house technical staff the ability to maintain and service the system themselves, including the making of internal programming alterations and to the extent of programming their own "canned" text messages. Include in the contract any factory training sessions required, trips, expenses, etc. at local or factory locations to provide this level of training.

**END OF SECTION 275223**

## **SECTION 281300 - ACCESS CONTROL AND SECURITY SYSTEMS**

### **PART 1 - GENERAL**

#### **1.1 RELATED DOCUMENTS**

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

#### **1.2 SUMMARY**

A. This section includes a microprocessor based and managed access control and security system and specifies sensors, signal equipment, system controls, and displays. System controllers and card readers will match the current University standard of existing campus Software House C\*Cure Security Management Control System. Coordination through the General Contractor with the University Project Manager and the UCard Office is required.

B. The C\*Cure system panel shall be interfaced with an alarm communicator provided by Peak Alarm for central station monitoring.

#### **1.3 DEFINITIONS**

A. Hard-Wired System: Alarm, supervisory, and detection devices are directly connected, through individual dedicated conductors, to central control panels.

#### **1.4 SYSTEM DESCRIPTION**

A. The system shall tie into the existing access control system currently installed on the University Campus. Provide any programming necessary to configure the system with the additional controllers on the system.

B. The system shall have access controlled doors as well as perimeter doors monitored with door position switches.

C. The system shall support automatic responses to alarms entering the system. Each alarm condition shall be capable of initiating numerous events including but not limited to: Activation of remote devices, door control, remote annunciation LED's, and card validation.

D. Access control functions shall include but not be limited to: Validation based on time of day and day of week, holiday scheduling with card validation override, and access validation based on positive verification of card.

E. The system shall interface with the fire alarm system and in the event of an alarm, shall release all controlled doors designated for emergency egress, and put them in fail-safe mode allowing free egress.

#### **1.5 FUNCTIONAL PERFORMANCE**

A. The system shall consist of intelligent controllers used in a distributed processing configuration. Each controller shall retain all data necessary for system operation in it's own RAM. Each controller will contain

an integrated real time clock that continues to govern events even if communication with the host computer is interrupted.

B. Card access system basic requirements:

1. Provide a system that is an extension of the existing access control system utilized by the University of Utah for all their facilities, with all existing functions available.

## 1.6 SUBMITTALS

A. General: Submit the following according to Conditions of Contract and Division 1 Specification Sections.

B. Product data for system components, including "Nationally Recognized Testing Laboratory" (NRTL) listing data and list of materials, dimensioned plans, sections, and elevations showing minimum clearances, mounting arrangements, and installed features and devices.

C. Wiring diagrams shall be provided for the system, including all devices, components, and auxiliary equipment. System diagram is unique to the Project system; a manufacturer's generic system diagram is not acceptable. Diagrams differentiate between manufacturer-installed and field-installed wiring. Include diagrams for equipment and for system with all terminals and interconnections identified.

D. System operation description, including method of operation and supervision of each component and each type of circuit, and sequence of operations for all manually and automatically initiated system inputs. Description must cover this specific Project; manufacturer's standard descriptions for generic systems are not acceptable.

E. Operation and maintenance data for inclusion in "Operating and Maintenance Manual" specified in Division 1. Include data for each type product, including all features and operating sequences, both automatic and manual. Include user's software data and recommendations for spare parts to be stocked at the site. Provide names, addresses, and telephone numbers of service organizations that stock repair parts for the system.

F. Product certifications signed by the manufacturers of system components certifying that their products comply with the referenced standards.

G. Separate Qualification Data for Manufacturers and Installers: Demonstrate their capabilities and experience as specified in Quality Assurance Article. Include lists of completed projects with project names and addresses, names of Contracting Officer and Government representatives, plus other information specified.

H. Record of field tests of system.

## 1.7 QUALITY ASSURANCE

A. Installer Qualifications: The system shall be installed by a contractor currently listed with the UCard Office and who has been regularly engaged in the installation of access control and security equipment for at least 5 years. The installer shall be a factory authorized sales and services representative and certified by Software House. Provide, in writing, proof of compliance with system manufacturers service and installation certification programs. Installer must be capable of providing emergency maintenance and repairs for the ove



rall system at the project site with 24 hours maximum response time. The installer shall have a local office staffed with factory trained technicians, fully capable of supervising installation, system start-up, providing training and servicing of both hardware and software for systems of similar complexity and function as the system described in this specification.

- B. Approved Installers: Structure Works, Yamas Controls, Ideacom and Convergent
- C. Comply with NFPA 70, "National Electrical Code."
- D. Listing and Labeling: Provide system and components that are listed and labeled for their indicated use and location on the Project.
  - 1. The Terms "Listed" and "Labeled": As defined in the "National Electrical Code," Article 100.
  - 2. Listing and Labeling Agency Qualifications: A "Nationally Recognized Testing Laboratory" (NRTL) as defined in OSHA Regulation 1910.7.
- E. FM Compliance: Provide FM-approved card access system and components.
- F. Single-Source Responsibility: Obtain system components from a single source (the prime system manufacturer) that assumes responsibility for system components and for their compatibility.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Software House C\*Cure – Door controllers and interfaces  
HID – Card readers

### 2.2 ACCESS CONTROL SYSTEM EQUIPMENT, GENERAL

- A. Surge Protection: Comply with minimum requirements of UL Standard 1449, "Transient Voltage Surge Suppressors," for each component using solid-state devices and having a line voltage power source connection or an exterior underground signal connection.
- B. Provide at the locations identified, a complete and operational Access Control and Security System including but not limited to the following equipment:
  - 1. Card Readers
  - 2. Door Logic Panels
  - 3. Relay output contacts
  - 4. All power supplies and/or transformers
  - 5. All equipment, security devices, components, wire, cable, and mounting hardware as required to meet specification requirements and manufacturers documented installation procedures.

C. Basic Central System Components:

1. Communications Hub and door logic controller panels to meet the system functional specifications listed above and for the number of readers as indicated in the drawings.

2.3 ELECTRICAL POWER

A. Normal System Power Supply: 120 V 60 Hz from locked disconnect device. System components are supplied with power through separate power supplies. Provide all required power supplies and associated transformers as specified by the manufacturer.

B. Power Source Transfer: When normal power is interrupted, system is automatically switched to backup supply without degradation of critical system function or loss of signals or status data.

1. Backup Source: Batteries in power supplies of individual system components. Such batteries are an integral part of power supplies of the components.
2. Annunciation: Switching of the system or any system component to backup power is indicated as a change in system condition.

2.4 CARD ACCESS SYSTEM HARDWARE, GENERAL

A. Types, features, accessories, and mounting conditions of individual devices are as indicated.

B. Battery Back-up: The access control panel shall be provided with back-up battery power for up to eight hours operation upon loss of AC power.

C. Suppression: The access control panel shall have provisions for relay suppressor kits for each relay used, to protect the access control panel from collapsing electrical fields.

D. Card Readers: Card readers shall be HID R-40 proximity readers matching the readers currently installed on campus for door control. The access control panel shall support card readers using Magstripe, Barcode, Wiegand, Proximity and Biometrics technologies.

2.5 INTRUSION DETECTION DEVICES, GENERAL

A. Types, features, accessories, and mounting conditions of individual devices are as indicated.

B. System Contact Arrangement: Contact-making intrusion detection devices are single-pole, double-throw type.

2.6 DOOR SWITCH CONTACT INDICATORS

A. Comply with UL Standard 634, "Connectors and Switches For Use With Burglar-Alarm Systems."

B. Description: Magnet part is designed for installation on the door; the magnetically operated switch is installed in the doorframe. Unit employs a magnet and a sensitive reed switch to resist compromise by introduction of foreign magnetic fields.

1. Flush-Mounted Units: Unobtrusive, flush with surface of doorframe and door.

## 2.7 MOTION DETECTION DEVICES

A. Comply with UL Standard 639, "Intrusion Detection Units," and the following general requirements:

1. Provide detectors using dual technology (PIR/Microwave) with a minimum of 40 feet by 40 feet coverage for wall mount and minimum 60 feet diameter X 360 degrees for ceiling mount. Provide with required wall mounting brackets that allow swivel adjustment.

## 2.8 EXIT REQUEST DEVICES

A. Provided by Hardware Contractor. See Division 8

B. On door types (see drawing schedules) that do not show motion detectors being used, the request to exit function will be handled by the switched exit hardware devices. It shall be the responsibility of the security contractor to coordinate with the hardware contractor in wiring of power transfer hinges and switched exit devices.

## 2.9 POWER SUPPLIES.

A. Provide power supplies as indicated in the drawings and per manufacturers written recommendations with total number of powered devices for each power supply restricted to only consuming 75 percent of the power supplies rated amperage. Provide separate power supplies for system controllers (As per manufacturer), card readers (12VDC, 5 A), and locks as indicated in the Card Access Door Schedule.

## 2.10 WIRE AND CABLE

A. General: Provide both TPS (Twisted pair Shielded) and TP (Twisted Pair) as indicated in the drawings, with the appropriate number of pairs.

B. Comply with Division 26 Section "Wires and Cables" except as indicated.

C. Cable for Low-Voltage Control and Signal Circuits: Shielded twisted-pair cable with drain. Comply with Division 26 Section "Wires and Cables."

## 2.11 RACEWAY

A. Comply with Division 26 Section "Raceways."

## PART 3 - EXECUTION

### 3.1 INSTALLATION

A. General: Install system according to NFPA 70, applicable codes, and manufacturer's printed instructions.

B. Wiring Method: Install all wiring in raceways, 3/4 inch minimum. Multiple home runs may be contained in a single conduit of appropriate size. Conceal raceways except in unfinished indoor spaces. Conduit fill shall not exceed 40%.

## SUGAR HOUSE DEVELOPMENT – BUILDING A

### INTERIORS PACKAGE

- B. Wiring Within Panels And Enclosures: Bundle, wrap, and train the conductors to terminal points with 6-inches of slack minimum, 12-inches of slack maximum. Provide and use cable management hardware and distribution spools.
- C. Number of Conductors: As recommended by system manufacturer for functions indicated.
- D. Splices, Taps, and Terminations: Make splices, taps, and terminations on numbered terminal strips in junction, pull and outlet boxes, terminal cabinets, and equipment enclosures.
- E. Tighten connections to comply with tightening torques specified in UL Standard 486A.
- F. Identification of Conductors and Cables: Color-code conductors and apply wire and cable marking tape to designate wires and cables so media are identified and coordinated with system wiring diagrams.
- G. Install power supplies and other auxiliary components for detection devices at the door controller panel or at a data-gathering panel except as otherwise indicated. Generally do not install such items in the vicinity of the devices they serve.
- J. Install fire interface relay such that in the event of a fire annunciation, designated locking devices will be put into access (FAIL SAFE) condition. Provide one input of the door logic controller for the fire alarm system.
- K. Coordinate door operation with hardware group descriptions in Division 8.

### 3.2 GROUNDING

- A. Ground system components and conductor and cable shields to eliminate shock hazard and to minimize ground loops, common mode returns, noise pickup, cross talk, and other impairments.

### 3.3 FIELD QUALITY CONTROL

- A. Manufacturer's Field Services: Provide services of a factory-authorized service representative to supervise the field assembly and connection of components and system pre-testing, testing, adjustment, and programming.
- B. Inspection: Verify that units and controls are properly labeled and interconnecting wires and terminals are identified.
- C. Pre-testing: Align and adjust the system and perform pre-testing of all components, wiring, and functions to verify conformance with specified requirements. Correct deficiencies by replacing malfunctioning or damaged items with new items. Retest until satisfactory performance and conditions are achieved.
- D. Testing: Provide at least 10 days' notice of acceptance test performance schedule.

SUGAR HOUSE DEVELOPMENT – BUILDING A  
INTERIORS PACKAGE

E. Operational Tests: Perform operational system tests to verify conformance with specifications. Test all modes of system operation and intrusion detection. Methodically test for false alarms in each zone of space intrusion detection devices by simulating activities outside indicated detection patterns.

F. Installer Start-up Responsibility: The Installer shall initiate system operation. The Installer shall provide competent start-up personnel on each consecutive working day until the system is fully functional. Upon reoccurring technical problems, the Installer shall supply factory direct Manufacturer's support in the form of factory technical representation and/or diagnostic equipment until the resolution of those defined problems.

### 3.4 ADJUSTMENT

A. Occupancy Adjustments: When requested within 1 year of date of substantial completion, provide on-site assistance in adjusting and reprogramming to suit actual occupied conditions. Provide up to 3 visits to the site for this purpose without additional cost.

### 3.5 DEMONSTRATION

A. Train Owner's operating personnel in the programming and operation of the system. Train Owner's maintenance personnel in the procedures and schedules involved in preventive maintenance and in programming, operating, adjusting, troubleshooting, and servicing of the system. Provide a minimum of 4 hours training.

B. Schedule training with advance notice of at least 7 days.

END OF SECTION 281300

## **SECTION 282300 - VIDEO SURVEILLANCE**

### **PART 1 - GENERAL**

#### **1.1 SUMMARY**

- A. Section includes a video surveillance system consisting of cameras, POE network switches, network video recorder/servers, and IP data transmission wiring.

#### **1.2 SUBMITTALS**

- A. Product Data: For each type of product indicated. Include dimensions and data on features, performance, electrical characteristics, ratings, and finishes.
- B. Shop Drawings: For video surveillance. Include plans, elevations, sections, details, and attachments to other work.
  - 1. Detail equipment assemblies and indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
  - 2. Functional Block Diagram: Show single-line interconnections between components for signal transmission and control. Show cable types and sizes.
  - 3. Dimensioned plan and elevations of equipment racks, control panels, and consoles. Show access and workspace requirements.
  - 4. Wiring Diagrams: For power, signal, and control wiring.
- C. Equipment List: Include every piece of equipment by model number, manufacturer, location, and date of original installation.
- D. Field quality-control reports.
- E. Operation and maintenance data.

#### **1.3 QUALITY ASSURANCE**

- A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- B. Comply with NECA 1.
- C. Comply with NFPA 70.
- D. Electronic data exchange between video surveillance system with an access-control system shall comply with SIA TVAC.
  - 1.

## 1.4 WARRANTY

- A. Special Warranty: Manufacturer's standard form in which manufacturer agrees to repair or replace components of cameras, equipment related to camera operation, and control-station equipment that fail in materials or workmanship within specified warranty period.
  - 1. Warranty Period: One year from date of Substantial Completion.

## PART 2 - PRODUCTS

### 2.1 SYSTEM REQUIREMENTS

- A. Video-signal format shall comply with IP based digital transmission.
- B. Surge Protection: Protect components from voltage surges entering through power, communication, signal, control, or sensing leads. Include surge protection for external wiring of each conductor's entry connection to components.
  - 1. Minimum Protection for Power Connections 120 V and More: Auxiliary panel suppressors complying with requirements in Division 26 Section "Transient-Voltage Suppression for Low-Voltage Electrical Power Circuits."
  - 2. Minimum Protection for Communication, Signal, Control, and Low-Voltage Power Connections: Comply with requirements in Division 26 Section "Transient-Voltage Suppression for Low-Voltage Electrical Power Circuits." as recommended by manufacturer for type of line being protected.
- C. Tamper Protection: Tamper protection capability shall be provided as part of the camera manufacture and design.

### 2.2 CAMERAS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  - 1. Avigilon
  - 2.
- B. Description: Camera shall be an all-in-one solution with integrated megapixel camera, varifocal lens, and vandal resistant dome enclosure.
  - 1. Camera shall be minimum 1 megapixel utilizing a 1/3" CMOS sensor, 720p resolution, and day/night iris management. Camera assembly shall be ONVIF compliant.
  - 2. Camera shall have a dome enclosure complying with IP66 weatherproofing standards.
  - 3. Camera shall have a 3 axis gimbal with 360 degree pan, 90 degree tilt, and 180 degree Z-rotation for accurate positioning.
  - 4. Camera shall be ceiling flush mounted or surface mounted with optional pendant or wall mount.
  - 5. Camera shall be H.264 (MPEG4, Part 10) compliant.

6. Camera's H.264 implementation shall maintain full real time video frame rates.
7. Camera shall have megapixel IR corrected varifocal lens, F1.8. Select best varifocal range for application.
8. Camera shall have auto backfocus.

## 2.3 POWER SUPPLIES

- A. Low-voltage power supplies matched for voltage and current requirements of cameras and accessories, and of type as recommended by manufacturer of camera and lens.
  1. Enclosure: NEMA 250, Type 3.

## 2.4 CAMERA-SUPPORTING EQUIPMENT

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  1. Avigilon
- B. Minimum Load Rating: Rated for load in excess of the total weight supported times a minimum safety factor of two.
- C. Mounting Brackets for Fixed Cameras: Type matched to items supported and mounting conditions. Include manual pan-and-tilt adjustment.
- D. Protective Housings for Fixed Cameras: Dome type enclosures with internal camera mounting and connecting provisions that are matched to camera/lens combination and mounting and installing arrangement of camera to be housed. Dome enclosures mounted outside, (Type 3), shall be manufactured with environmental features for sustained function in all expected temperatures.
  1. Camera Viewing Window: Polycarbonate dome window, smoked tint.
  2. Built-in environmental controls for operation in temperatures as specified.
  3. Mounting bracket and hardware for pole mounting of the housing, as indicated. Bracket shall be of same material as the housing.
  4. Finish: Housing and mounting bracket shall be factory finished using manufacturer's standard finishing process suitable for the environment.

## 2.5 NETWORK VIDEO RECORDER/SERVERS – Existing as part of the network provided for the Parking Terrace on P2.

## 2.6 IP VIDEO MANAGEMENT SYSTEMS - Existing

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
  1. Avigilon



## 2.7 SIGNAL AND POWER TRANSMISSION COMPONENTS – Provided by Div 27

### PART 3 - EXECUTION

#### 3.1 WIRING

- A. Comply with requirements in Division 26 Section "Raceway and Boxes for Electrical Systems."
- B. Wiring Method: Install cables in metal conduit raceways only in concealed spaces. Provide loose air cable management in accessible spaces. Installation shall be compliant with ANSI/TIA/EIA 569 D.
- C. Wiring within Enclosures: Bundle, lace, and train conductors to terminal points with no excess and without exceeding manufacturer's limitations on bending radii. Provide and use lacing bars and distribution spools.
- D. Splices, Taps, and Terminations: For power and control wiring, use numbered terminal strips in junction, pull, and outlet boxes; terminal cabinets; and equipment enclosures. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A-486B.
- E. For LAN complaint wiring, cables shall be installed and terminated per ANSI/TIA/EIA 568B standards.
- F. Grounding: Provide independent-signal circuit grounding recommended in writing by manufacturer.

#### 3.2 VIDEO SURVEILLANCE SYSTEM INSTALLATION

- A. Install cameras at heights noted in drawings.
- B. Set pan-and-tilt unit stops to suit final camera position and to obtain the field of view required for camera. Connect all controls and alarms, and adjust.
- C. Identify system components, wiring, cabling, and terminals according to Division 26 Section "Identification for Electrical Systems."

#### 3.3 FIELD QUALITY CONTROL

- A. Perform tests and inspections.
  - 1. Manufacturer's Field Service: Engage a factory-authorized service representative to inspect components, assemblies, and equipment installations, including connections, and to assist in testing.
- B. Tests and Inspections:

1. Inspection: Verify that units and controls are properly installed, connected, and labeled, and that interconnecting wires and terminals are identified.
2. Pretesting: Align and adjust system and pretest components, wiring, and functions to verify that they comply with specified requirements. Conduct tests at varying lighting levels, including day and night scenes as applicable. Prepare video-surveillance equipment for acceptance and operational testing as follows:
  - a. Verify operation of auto-iris lenses.
  - b. Set back-focus of fixed focal length lenses. At focus set to infinity, simulate nighttime lighting conditions by using a dark glass filter of a density that produces a clear image. Adjust until image is in focus with and without the filter.
  - c. Set back-focus of zoom lenses. At focus set to infinity, simulate nighttime lighting conditions by using a dark glass filter of a density that produces a clear image. Additionally, set zoom to full wide angle and aim camera at an object 50 to 75 feet away. Adjust until image is in focus from full wide angle to full telephoto, with the filter in place.
  - d. Set sensitivity of motion detection.
  - e. Connect and verify responses to alarms.
  - f. Verify operation of control-station equipment.
3. Test Schedule: Schedule tests after pretesting has been successfully completed and system has been in normal functional operation for at least 14 days. Provide a minimum of 10 days' notice of test schedule.
4. Operational Tests: Perform operational system tests to verify that system complies with Specifications. Include all modes of system operation.

C. Video surveillance system will be considered defective if it does not pass tests and inspections.

D. Prepare test and inspection reports.

### 3.4 DEMONSTRATION

- A. Train Owner's maintenance personnel to adjust, operate, and maintain video-surveillance equipment.

**END OF SECTION 282303**

## SECTION 283111 - DIGITAL, ADDRESSABLE FIRE-ALARM SYSTEM

### PART 1 - GENERAL

#### 1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

#### 1.2 SUMMARY

- A. Section Includes:
  - 1. Fire-alarm control unit.
  - 2. Manual fire-alarm boxes.
  - 3. System smoke detectors.
  - 4. Notification appliances.
  - 5. Magnetic door holders.

#### 1.3 DEFINITIONS

- A. LED: Light-emitting diode.
- B. NICET: National Institute for Certification in Engineering Technologies.

#### 1.4 SYSTEM DESCRIPTION

- A. The fire alarm system is an existing Johnson Controls system which has been modified at the head end to expand compatibility with Notifier devices. The contractor shall retain a fire alarm contractor authorized by the manufacturer to incorporate new compatible devices with the existing open source system.
- B. Noncoded, UL-certified addressable analog system, with multiplexed signal transmission, dedicated to fire-alarm service only.

#### 1.5 PERFORMANCE REQUIREMENTS

- A. Seismic Performance: Fire-alarm control unit and raceways shall withstand the effects of earthquake motions determined according to SEI/ASCE 7.
  - 1. The term "withstand" means "the unit will remain in place without separation of any parts from the device when subjected to the seismic forces specified and the unit will be fully operational after the seismic event."

#### 1.6 SUBMITTALS

- A. General Submittal Requirements:
  - 1. Submittals shall be approved by authorities having jurisdiction prior to submitting them to Architect.
  - 2. Shop Drawings shall be prepared by persons with the following qualifications:
    - a. Trained and certified by manufacturer in fire-alarm system design.
    - b. NICET-certified fire-alarm technician, Level III minimum.
    - c. Licensed or certified by authorities having jurisdiction.
- B. Product Data: For each type of product indicated.

- C. Shop Drawings: For fire-alarm system. Include plans, elevations, sections, details, and attachments to other work.
1. Comply with recommendations in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter in NFPA 72.
  2. Include voltage drop calculations for notification appliance circuits.
  3. Include battery-size calculations.
  4. Include performance parameters and installation details for each detector, verifying that each detector is listed for complete range of air velocity, temperature, and humidity possible when air-handling system is operating.
  5. Include plans, sections, and elevations of heating, ventilating, and air-conditioning ducts, drawn to scale and coordinating installation of duct smoke detectors and access to them. Show critical dimensions that relate to placement and support of sampling tubes, detector housing, and remote status and alarm indicators. Locate detectors according to manufacturer's written recommendations.
  6. Include voice/alarm signaling-service equipment rack or console layout, grounding schematic, amplifier power calculation, and single-line connection diagram.
  7. Include floor plans to indicate final outlet locations showing address of each addressable device. Show size and route of cable and conduits.
- D. Qualification Data: For qualified Installer.
- E. Seismic Qualification Certificates: For fire-alarm control unit, accessories, and components, from manufacturer.
1. Basis for Certification: Indicate whether withstand certification is based on actual test of assembled components or on calculation.
  2. Dimensioned Outline Drawings of Equipment Unit: Identify center of gravity and locate and describe mounting and anchorage provisions.
  3. Detailed description of equipment anchorage devices on which the certification is based and their installation requirements.
- F. Field quality-control reports.
- G. Operation and Maintenance Data: For fire-alarm systems and components to include in emergency, operation, and maintenance manuals. In addition to items specified in Division 01 Section "Operation and Maintenance Data," include the following:
1. Comply with the "Records" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
  2. Provide "Record of Completion Documents" according to NFPA 72 article "Permanent Records" in the "Records" Section of the "Inspection, Testing and Maintenance" Chapter.
  3. Record copy of site-specific software.
  4. Provide "Maintenance, Inspection and Testing Records" according to NFPA 72 article of the same name and include the following:
    - a. Frequency of testing of installed components.
    - b. Frequency of inspection of installed components.
    - c. Requirements and recommendations related to results of maintenance.
    - d. Manufacturer's user training manuals.
  5. Manufacturer's required maintenance related to system warranty requirements.
  6. Abbreviated operating instructions for mounting at fire-alarm control unit.
  7. Copy of NFPA 25.
- H. Software and Firmware Operational Documentation:
1. Software operating and upgrade manuals.
  2. Program Software Backup: On compact disk, complete with data files.
  3. Device address list.

4. Printout of software application and graphic screens.

## 1.7 QUALITY ASSURANCE

- A. Installer Qualifications: Installation shall be by personnel certified by NICET as fire-alarm Level IV technician, UL UUJS.5250 listed for fire alarm installation.
- B. Source Limitations for Fire-Alarm System and Components: Obtain fire-alarm system from single source from single manufacturer. Components shall be compatible with, and operate as, an extension of existing system.
- C. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.
- D. NFPA Certification: Obtain certification according to NFPA 72 by a UL-listed alarm company.
- E. Warranty: Provide a minimum three year warranty for all equipment, materials, and installation.

## 1.8 PROJECT CONDITIONS

- A. Interruption of Existing Fire-Alarm Service: Do not interrupt fire-alarm service to facilities occupied by Owner or others unless permitted under the following conditions and then only after arranging to provide temporary guard service according to requirements indicated:
  1. Notify Architect and Owner no fewer than five days in advance of proposed interruption of fire-alarm service.
  2. Do not proceed with interruption of fire-alarm service without Architect's and Owner's written permission.

## PART 2 - PRODUCTS

### 2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by the following:
  1. Notifier.

### 2.2 SYSTEMS OPERATIONAL DESCRIPTION

- A. Fire-alarm signal initiation shall conform to the existing system configuration.
- B. Fire-alarm signal shall conform to the existing system configuration.

### 2.3 FIRE-ALARM CONTROL UNIT

- A. General Requirements for Fire-Alarm Control Unit:
  1. Field-programmable, microprocessor-based, modular, power-limited design with electronic modules, complying with UL 864 and listed and labeled by an NRTL.
    - a. System software and programs shall be held in flash electrically erasable programmable read-only memory (EEPROM), retaining the information through failure of primary and secondary power supplies.
    - b. Include a real-time clock for time annotation of events on the event recorder.
  2. Addressable initiation devices that communicate device identity and status.
    - a. Smoke sensors shall additionally communicate sensitivity setting and allow for adjustment of sensitivity at fire-alarm control unit.

- b. Temperature sensors shall additionally test for and communicate the sensitivity range of the device.
  3. Addressable control circuits for operation of mechanical equipment.
- B. Alphanumeric Display and System Controls: Arranged for interface between human operator at fire-alarm control unit and addressable system components including annunciation and supervision. Display alarm, supervisory, and component status messages and the programming and control menu.
  1. Annunciator and Display: Liquid-crystal type, 3 line(s) of 40 characters, minimum.
  2. Keypad: Arranged to permit entry and execution of programming, display, and control commands and to indicate control commands to be entered into the system for control of smoke-detector sensitivity and other parameters.
- C. Circuits:
  1. Initiating Device, Notification Appliance, and Signaling Line Circuits: NFPA 72, Class A.
    - a. Initiating Device Circuits: Style D.
    - b. Notification Appliance Circuits: Style Z.
    - c. Signaling Line Circuits: Style 7.
    - d. Install no more than 50 addressable devices on each signaling line circuit.
- D. Smoke-Alarm Verification:
  1. Initiate audible and visible indication of an "alarm-verification" signal at fire-alarm control unit.
  2. Activate an NRTL-listed and -approved "alarm-verification" sequence at fire-alarm control unit and detector.
  3. Sound general alarm if the alarm is verified.
  4. Cancel fire-alarm control unit indication and system reset if the alarm is not verified.
- E. Controls: Door hold-open devices that are controlled by smoke detectors at doors in smoke barrier walls shall be connected to fire-alarm system.
- F. Remote Smoke-Detector Sensitivity Adjustment: Controls shall select specific addressable smoke detectors for adjustment, display their current status and sensitivity settings, and change those settings. Allow controls to be used to program repetitive, time-scheduled, and automated changes in sensitivity of specific detector groups. Record sensitivity adjustments and sensitivity-adjustment schedule changes in system memory, and print out the final adjusted values on system printer.
- G. Transmission to Remote Alarm Receiving Station: Automatically transmit alarm, supervisory, and trouble signals to a remote alarm station.
- H. Primary Power: 24-V dc obtained from 120-V ac service and a power-supply module. Initiating devices, notification appliances, signaling lines, trouble signals, supervisory signals, and supervisory and digital alarm communicator transmitters shall be powered by 24-V dc source.
  1. Alarm current draw of entire fire-alarm system shall not exceed 80 percent of the power-supply module rating.
  2. Mark the circuit breaker from which power is derived with the notation "Fire Alarm System - Do Not Turn Off."
- I. Secondary Power: 24-V dc supply system with batteries, automatic battery charger, and automatic transfer switch.
  1. Batteries: Sealed lead calcium.

- J. Instructions: Computer printout or typewritten instruction card mounted behind a plastic or glass cover in a stainless-steel or aluminum frame. Include interpretation and describe appropriate response for displays and signals. Briefly describe the functional operation of the system under normal, alarm, and trouble conditions.

## 2.4 MANUAL FIRE-ALARM BOXES

- A. General Requirements for Manual Fire-Alarm Boxes: Comply with UL 38. Boxes shall be finished in red with molded, raised-letter operating instructions in contrasting color; shall show visible indication of operation; and shall be mounted on recessed outlet box. If indicated as surface mounted, provide manufacturer's surface back box.
1. Single-action mechanism, pull-lever type; with integral addressable module arranged to communicate manual-station status (normal, alarm, or trouble) to fire-alarm control unit.
  2. Station Reset: Key- or wrench-operated switch.
  3. Indoor Protective Shield: Factory-fabricated clear plastic enclosure hinged at the top to permit lifting for access to initiate an alarm. Lifting the cover actuates an integral battery-powered audible horn intended to discourage false-alarm operation.
  4. Weatherproof Protective Shield: Factory-fabricated clear plastic enclosure hinged at the top to permit lifting for access to initiate an alarm.

## 2.5 SYSTEM SMOKE DETECTORS

- A. General Requirements for System Smoke Detectors:
1. Comply with UL 268; operating at 24-V dc, nominal.
  2. Detectors shall be four-wire type.
  3. Compatible with Johnson Controls and Notifier systems.
  4. Integral Addressable Module: Arranged to communicate detector status (normal, alarm, or trouble) to fire-alarm control unit.
  5. Base Mounting: Detector and associated electronic components shall be mounted in a twist-lock module that connects to a fixed base. Provide terminals in the fixed base for connection to building wiring.
  6. Self-Restoring: Detectors do not require resetting or readjustment after actuation to restore them to normal operation.
  7. Integral Visual-Indicating Light: LED type indicating detector has operated and power-on status.
  8. Remote Control: Unless otherwise indicated, detectors shall be analog-addressable type, individually monitored at fire-alarm control unit for calibration, sensitivity, and alarm condition and individually adjustable for sensitivity by fire-alarm control unit.
    - a. Rate-of-rise temperature characteristic shall be selectable at fire-alarm control unit for 15 or 20 deg F (8 or 11 deg C) per minute.
    - b. Fixed-temperature sensing shall be independent of rate-of-rise sensing and shall be settable at fire-alarm control unit to operate at 135 or 155 deg F (57 or 68 deg C).
    - c. Provide multiple levels of detection sensitivity for each sensor.
- B. Photoelectric Smoke Detectors:
1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
  2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
    - a. Primary status.
    - b. Device type.
    - c. Present average value.
    - d. Present sensitivity selected.

- e. Sensor range (normal, dirty, etc.).

C. Ionization Smoke Detector:

1. Detector address shall be accessible from fire-alarm control unit and shall be able to identify the detector's location within the system and its sensitivity setting.
2. An operator at fire-alarm control unit, having the designated access level, shall be able to manually access the following for each detector:
  - a. Primary status.
  - b. Device type.
  - c. Present average value.
  - d. Present sensitivity selected.
  - e. Sensor range (normal, dirty, etc.).

## 2.6 NOTIFICATION APPLIANCES

- A. General Requirements for Notification Appliances: Connected to notification appliance signal circuits, zoned as indicated, equipped for mounting as indicated and with screw terminals for system connections.
1. Combination Devices: Factory-integrated audible and visible devices in a single-mounting assembly, equipped for mounting as indicated and with screw terminals for system connections. Provide all devices selectable between horn/chime/silent function.
- B. Speakers: Match existing standard speaker type with ¼ watt, ½ watt, and 1 watt taps compatible with and suitable for exiting voice based evacuation system.
- C. Chimes, Low-Level Output: Vibrating type, 75-dBA minimum rated output.
- D. Visible Notification Appliances: Xenon strobe lights comply with UL 1971, with clear or nominal white polycarbonate lens mounted on an aluminum faceplate. The word "FIRE" is engraved in minimum 1-inch- (25-mm-) high letters on the lens.
1. Rated Light Output:
    - a. 15/30/75/110 cd, selectable in the field.
  2. Mounting: Wall mounted unless otherwise indicated.
  3. For units with guards to prevent physical damage, light output ratings shall be determined with guards in place.
  4. Flashing shall be in a temporal pattern, synchronized with other units.
  5. Strobe Leads: Factory connected to screw terminals.
  6. Mounting Faceplate: Factory finished, red.

## 2.7 MAGNETIC DOOR HOLDERS

- A. Description: Units are equipped for wall or floor mounting as indicated and are complete with matching doorplate.
1. Electromagnet: Requires no more than 3 W to develop 25-lbf (111-N) holding force.
  2. Wall-Mounted Units: Flush mounted unless otherwise indicated.
  3. Rating: 120-V ac.
- B. Material and Finish: Match door hardware.

## PART 3 - EXECUTION

### 3.1 EQUIPMENT INSTALLATION

- A. Comply with NFPA 72 for installation of fire-alarm equipment.



- B. Install all fire alarm cabling in steel conduit.
- C. Equipment Mounting: Install fire-alarm control unit on wall with tops of cabinets not more than 72 inches (1830 mm) above the finished floor.
  - 1. Comply with requirements for seismic-restraint devices specified in Division 26 Section "Vibration and Seismic Controls for Electrical Systems."
  - 2. Connect new system to existing building fire alarm monitoring system.
- D. Smoke-Detector Spacing:
  - 1. Comply with NFPA 72, "Smoke-Sensing Fire Detectors" Section in the "Initiating Devices" Chapter, for smoke-detector spacing.
  - 2. Smooth ceiling spacing shall not exceed 30 feet (9 m).
  - 3. Spacing of detectors for irregular areas, for irregular ceiling construction, and for high ceiling areas shall be determined according to Appendix A in NFPA 72.
  - 4. HVAC: Locate detectors not closer than 3 feet (1 m) from air-supply diffuser or return-air opening.
  - 5. Lighting Fixtures: Locate detectors not closer than 12 inches (300 mm) from any part of a lighting fixture.
- E. Visible Alarm-Indicating Devices: Install at least 6 inches (150 mm) below the ceiling.
- F. Device Location-Indicating Lights: Locate in public space near the device they monitor.

### 3.2 CONNECTIONS

- A. For fire-protection systems related to doors in fire-rated walls and partitions and to doors in smoke partitions, comply with requirements in Division 08 Section "Door Hardware." Connect hardware and devices to fire-alarm system.
  - 1. Verify that hardware and devices are NRTL listed for use with fire-alarm system in this Section before making connections.
- B. Make addressable connections with a supervised interface device to the following devices and systems. Install the interface device less than 3 feet (1 m) from the device controlled. Make an addressable confirmation connection when such feedback is available at the device or system being controlled.
  - 1. Smoke dampers in air ducts of designated air-conditioning duct systems.
  - 2. Alarm-initiating connection to activate emergency shutoffs for gas and fuel supplies.
  - 3. Supervisory connections at valve supervisory switches.

### 3.3 IDENTIFICATION

- A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Division 26 Section "Identification for Electrical Systems."
- B. Install framed instructions in a location visible from fire-alarm control unit.
- C. Label each initiation device with its appropriate address.

### 3.4 GROUNDING

- A. Ground fire-alarm control unit and associated circuits; comply with IEEE 1100. Install a ground wire from main service ground to fire-alarm control unit.

### 3.5 FIELD QUALITY CONTROL

- A. Field tests shall be witnessed by authorities having jurisdiction and owner.
- B. Manufacturer's Field Service: Test and adjust components, assemblies, and equipment installations, including connections.
- C. Tests and Inspections:
  - 1. Visual Inspection: Conduct visual inspection prior to testing.
    - a. Inspection shall be based on completed Record Drawings and system documentation that is required by NFPA 72 in its "Completion Documents, Preparation" Table in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter.
    - b. Comply with "Visual Inspection Frequencies" Table in the "Inspection" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72; retain the "Initial/Reacceptance" column and list only the installed components.
  - 2. System Testing: Comply with "Test Methods" Table in the "Testing" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
  - 3. Test audible appliances for the public operating mode according to manufacturer's written instructions. Perform the test using a portable sound-level meter complying with Type 2 requirements in ANSI S1.4.
  - 4. Test audible appliances for the private operating mode according to manufacturer's written instructions.
  - 5. Test visible appliances for the public operating mode according to manufacturer's written instructions.
  - 6. Factory-authorized service representative shall prepare the "Fire Alarm System Record of Completion" in the "Documentation" Section of the "Fundamentals of Fire Alarm Systems" Chapter in NFPA 72 and the "Inspection and Testing Form" in the "Records" Section of the "Inspection, Testing and Maintenance" Chapter in NFPA 72.
- D. Reacceptance Testing: Perform reacceptance testing in presence of University Fire Marshall to verify the proper operation of added or replaced devices and appliances.
- E. Fire-alarm system will be considered defective if it does not pass tests and inspections.
- F. Prepare test and inspection reports.
- G. Maintenance Test and Inspection: Perform tests and inspections listed for weekly, monthly, quarterly, and semiannual periods. Use forms developed for initial tests and inspections.
- H. Annual Test and Inspection: One year after date of Substantial Completion, test fire-alarm system complying with visual and testing inspection requirements in NFPA 72. Use forms developed for initial tests and inspections.

### 3.6 DEMONSTRATION

- A. Engage a factory-authorized service representative to train Owner's maintenance personnel to adjust, operate, and maintain fire-alarm system.

END OF SECTION 283111